


HANDBOOK FOR
ARCHITECTS AND BUILDERS

PUBLISHED
UNDER THE AUSPICES
OF THE

Illinois Society of Architects

VOL. XXIV. 1921




STANDARDIZATION

BET

“B₁

OF O

M



TER SERVICE
ME


ok

surance”

RANGE
SIREN POSSIBLE

ORK

oor Co.




HYGIENIC



FLOORING

Asbestone Flooring

The recognized standing of ASBESTONE Composition Flooring as the world's best interior flooring has been achieved through appreciation of the fact that ASBESTONE quality and service are beyond question.



School Installation. Floors. Wainscote & Stair Treads
36,000 feet

FLOORS ARE THE MOST USED AND
ABUSED PORTION *of* ANY BUILDING

therefore, specify ASBESTONE and secure best results.

We *Guarantee* all installations.

Prices, samples and full particulars free on application.

FRANKLYN R. MULLER & CO.

Composition Flooring and Stucco Manufacturers

22 Madison Street, Waukegan, Ill.

ESTABLISHED 1906

McCRAY FOR ALL REFRIGERATORS PURPOSES

OUR many friends among the Architects know that there is a McCRAY for every refrigerator need. The high quality of product and the length of satisfactory service—demanded by Architects—is found in McCRAY Refrigerators.

The particular point of excellence, which distinguishes all McCRAY Refrigerators is the McCRAY System of Refrigeration, perfected through Thirty-Five Years of Experience. The convenient arrangement of the food compartments and their commodious storage capacity are McCRAY features.

We manufacture a complete line of refrigerators and cooling rooms in stock sizes to meet the requirements of Residences, Hotels, Hospitals, Clubs and Institutions, Grocery Stores, Meat Markets, etc. These are arranged for either Ice or Mechanical Refrigeration.

PLANS FOR ASKING—Our Free Plan Service is open to all Architects. The ideas and suggestions of our Draftsmen are at your service. Send us a rough sketch—showing the general outline of your client's refrigerator requirements—and we will gladly make up blue prints and draw up specifications.



SEND FOR CATALOG—Our catalogs will assist you when you are confronted with refrigerator problems. No. 95 for Residences. No. 52 for Hotels, Restaurants and Clubs. No. 63 for Meat Markets. No. 71 for Grocery Stores. No. 74 for Florists.

McCRAY REFRIGERATOR CO.

2157 Lake St. Kendallville, Ind.

Salesrooms in All Principal Cities


Chicago Salesrooms, 1000 South Michigan Avenue



HANDBOOK


FOR

ARCHITECTS AND BUILDERS




PUBLISHED
UNDER THE AUSPICES
OF THE

ILLINOIS SOCIETY OF ARCHITECTS



TWENTY-FOURTH YEAR

1921



Emery Stanford Hall, Editor
Copyright 1921 by H. L. Palmer

FRED KLEIN CO., CHICAGO



The *Shurlox* Awning

PATENTED

The *only inside operated* awning with a *positive locking device*.

COMFORT, ECONOMY

ATTRACTIVENESS

DURABILITY

EASE OF OPERATION

THE ORIGINAL

WALGER
AWNING COMPANY

ESTABLISHED 1905


GENERAL OFFICES AND FACTORY:
561 W. MONROE STREET, CHICAGO
TELEPHONE MAIN 4347 AND 4348

Shade Equipments for Industrial Buildings

for Windows of any type made of our

TRANSLUCENT EVERLASTING SHADE MATERIAL

A TYPICAL INSTALLATION OF OUR STEEL SASH SHADES



ILLINOIS SOCIETY OF ARCHITECTS

Officers

F. E. DAVIDSON	President
HERBERT E. HEWITT	First Vice-President
JOHN A. NYDEN	Second Vice-President
JOHN A. ARMSTRONG	Treasurer
RALPH C. HARRIS	Secretary
H. L. PALMER	Financial Secretary

Directors

GEORGE BEAUMONT
EMERY STANFORD HALL
CHARLES HERRICK HAMMOND
BYRON H. JILLSON
ROBERT C. OSTERGREN
HARRY B. WHELOCK

Board of Arbitration

ALFRED S. ALSCHULER
ELMER C. JENSEN
JOSEPH C. LLEWELLYN
GEORGE C. NIMMONS
DWIGHT H. PERKINS
IRVING K. POND
RICHARD E. SCHMIDT

Committee on Public Action

JOHN A. NYDEN, *Chairman*
FRANK A. CARPENTER
WARREN W. DAY
ROBERT S. DeCOLYER
RALPH C. HARRIS

GEORGE B. HELMLE
ARTHUR L. PILLSBURY
HOWARD PUTNAM STURGES
JOHN W. WEISS
H. W. WHITSITT

Legislative Committee

HARRY B. WHELOCK, *Chairman*
JOHN REED FUGARD

JOSEPH C. LLEWELLYN
DAVIS D. MEREDITH
ROBERT C. OSTERGREN

Membership Committee

BYRON H. JILLSON, *Chairman*
ARCHIE H. HUBBARD

BERT C. HUBBARD
WILLIAM C. JONES
H. L. PALMER

Entertainment Committee

ROBERT C. OSTERGREN, *Chairman*
CHARLES D. FAULKNER

WILLIAM H. LAUTZ
H. L. PALMER
WILLIAM ROHM

Publication Committee

CHAS. H. HAMMOND, *Chairman*

N. MAX DUNNING
F. E. DAVIDSON

Committee on Education

HERBERT E. HEWITT, *Chairman*
SIDNEY LOVELL
ARTHUR L. PILLSBURY

FRANCIS W. PUCKEY
PERRY W. SWERN
JAMES M. WHITE

Committee on Materials and Specifications

E. S. HALL, *Chairman*
MELVILLE C. CHATTEN

L. H. PLEINS
L. W. RIDDLE
N. S. SPENCER

Committee on Publicity and Promotion

KARL M. VITZTHUM, *Chairman*
LEO H. PLENIS

E. E. ROBERTS
PERRY W. SWERN
MARK H. WHITMEYER

Committee on Pageants and Architectural Exhibits

GEORGE W. MAHER, *Chairman*
HUBERT BURNHAM

ARCHIE H. HUBBARD
CLARE C. HOSMER
CHARLES L. MORGAN



Important Facts About Kragstone Stucco

A Standard Building Material

Kragstone Stucco is a recognized standard building material of which magnesite is the bonding ingredient. It is a purely mineral product which, when mixed and applied with Kragstone Mixing Compound, acts chemically in setting up to a hard, solid mass.

Kragstone can be used on all forms of construction and all surfaces over which any plastering material can be applied successfully. Because of its strength and elasticity it will withstand the ordinary expansion and contraction without checking or cracking.

When properly applied, the bonding qualities of Kragstone are so great that it will not draw away from casings or corner boards. It is fireproof and weather resisting.

Stucco is cheaper than other types of construction except frame, and when the cost of upkeep is considered, it is cheaper than frame. Kragstone, in spite of its high quality, costs no more than other magnesite stuccoes.

We will gladly send you descriptive and specification literature on request.

American Magnesia Products Company

5746 Roosevelt Road

CHICAGO, ILL.

KRAGSTONE

The STUCCO BEAUTIFUL

PREFACE

IN PRESENTING the Twenty-fourth Edition of the "Handbook for Architects and Builders," we do so with considerable pride. Notwithstanding the disturbed conditions in the Building Trades Industries and the uncertainty of its future, long before the trouble May first and the Landis decision and wage award, Manufacturers, Contractors and Material Dealers showed their confidence in the Publication by liberally patronizing its pages.

Many changes have been made to increase the value of the Publication.

Our attention has been called by Architects, Engineers, Contractors and Draftsmen who use the Handbook by artificial light that the gloss on the enameled paper is reflected and is a strain on the eyes. To correct this feature we have used a dull finish Library Text paper in certain parts of the Publication.

We publish this year a list of Secretaries of the Chapters of the American Institute of Architects, the States requiring Architectural Registration, Rules and Regulations for Registration of Architects in Illinois and also Requirements of the National Council of Architectural Registration Boards as well as many new articles by men who stand high in the various lines on the subjects treated by them, also many new specifications and much technical data.

We welcome as contributors Mr. Stanley Macomber, A. S. C. E., who has contributed an article on Steel Lumber Construction; Mr. Frank Chambers of the Smoke Prevention Association of America, on Furnace Designs with Special Reference to Hand Fired Boilers and Limitations of Each Design; Mr. Homer Linn, Mechanical Engineer, on Hot Water Heating, Two Pipe Non-Short Circuit System; Mr. C. G. Everson, President, Lighting Fixture Council, on Lighting and its Relations to the House Beautiful; Dr. E. Vernon Hill, Aerologist, Division of Ventilation, Department of Health, City of Chicago, on Measuring Ventilation; Mr. R. W. Lindsay, Chemist; Mr. Leo H. Pleins, Architect and Sanitary Engineer; Mr. Fred J. Postel, Mechanical Engineer; Mr. Frank J. Llewellyn, A. S. C. E., and the balance of the staff of our contributors continue in the various departments.

We have exercised diligent care and caution in the editing and preparing the matter published in the Handbook for Architects and Builders, but realize that notwithstanding this, inaccuracies in judgment as to the selection of matter and mistakes in statement of facts may have crept into this work, and for such faults we ask the indulgence of our readers and that they forward to us their friendly criticism and suggestions to the end that succeeding Editions may be improved thereby.


The Handbook for Architects and Builders covers a peculiarly exclusive field and is a recognized reference work for everyone interested in Architecture and Building. The demand for this publication is constantly increasing and it has become almost indispensable to Architects, Engineers, Contractors, Builders and those connected with the Building Trades.

Our Classified Index furnishes the Architect with a list of those engaged in the manufacture and sale of material and the contracting business. We have exercised our best judgment in the selection of those represented in our book and we urge Architects desiring the names of contractors and material firms to use this list.

Publication Committee:

C. H. HAMMOND, Chairman,
N. MAX DUNNING,
F. E. DAVIDSON.

Johns-Manville Service to the Architect



Johns-Manville Service concerns itself primarily with the question of what will fulfill your requirements and thus best serve the needs of your clients. When a Johns-Manville Product is found to answer your requirements you may specify it in absolute assurance that its fullest service is guaranteed by Johns-Manville Responsibility.

Local Supervision of distant building operations is not the least important phase of Johns-Manville Service to the architect. It is a real satisfaction to know that your distant building is protected by the watchfulness and care of an adjacent Johns-Manville Branch. Johns-Manville Service offers this precaution with every product it installs.

Leading Johns-Manville Roofings and Building Materials

Johns-Manville Asbestos Roofings: All mineral composition. Made of Asbestos felts impregnated with asphalt. Durable and fire-resistant. In built-up form for flat surfaces; ready-to-lay form for sloping roofs and with corrugated steel reinforcement for skeleton construction. Approved by Underwriters and protected by Johns-Manville plan of roof registration.

Johns-Manville Standard and Colorblende Asbestos Shingles: Fire-proof and attractive. Made with asbestos fibres and Portland cement in different colors, shapes, sizes and two thicknesses, affording an opportunity to secure varied and distinctive roofing effects.

Johns-Manville Keystone Hair Insulator: Highly desirable in buildings where the localizing of noise is paramount, as in apartments, hotels, clubs, residences and office buildings. Also an effective insulator against heat and cold, not only in floors, walls and ceilings, but also under roofings.

Johns-Manville System of Refrigeration: A compact, efficient, mechanical means of producing refrigeration in hotels, clubs, apartment houses, residences, soda fountains, cafes, etc., or for ice making or cooling drinking water systems.

Johns-Manville Industrial Flooring: A tough, elastic monolithic flooring, without construction joints or cracks, which can be laid in any degree of hardness from "rubber" to "rock." Unaffected by ordinary commercial acids, alkalies or brine. Noiseless, dustless and easy under foot. Fire retardant and slip-proof.

Johns-Manville Pipe and Boiler Insulation: In various forms for superheat, high, medium and low pressures, cold water, hot water, brine, ammonia or any other service.

Johns-Manville Acoustical Correction: Sound control is as effective a contribution to comfort and efficiency as is heat or light. Johns-Manville Acoustical Service specializes in sound control. It can help you in your building problems.

Johns-Manville Underground System of Insulation: A complete installation, including conduit, fittings, supports, drains, and insulation for underground pipes carrying steam, water, etc. Installed under guarantee of a minimum of 90 per cent efficiency on approved test.

Johns-Manville Steam and Radiator Traps: An efficient, simple device, one moving part operated directly by the condensate and not by temperature. Delivers all water and gases to return line without steam loss.

All these and other Johns-Manville materials, backed by Johns-Manville Service and Responsibility, are at your command. Please address

Johns-Manville, Inc.

Michigan Ave. and Eighteenth St.

CHICAGO

Executive Offices, New York

Branches in 66 Large Cities

We call especial attention to the business announcements on these pages. We have accepted only such houses as are absolutely first-class and reliable. In the light of knowledge which we have upon the subject, acquired by experience, we feel that we have used every discretion in the matter of those represented herein





NORTHWESTERN

is a short form of specification for architectural Terra Cotta of superior quality.

The Wrigley Building, at Michigan Avenue Bridge, Chicago—Graham, Anderson, Probst & White, Architects—Lanquist & Illsley, General Contractors. Faced on all sides, from sidewalk to searchlight, with Northwestern Enamel Terra Cotta.

THE NORTHWESTERN TERRA COTTA CO.

GENERAL OFFICES AND WORKS
2525 CLYBOURN AVENUE
CHICAGO



HERBERT HEWITT

1ST VICE PRES.



JOHN A. NYDEN

2ND VICE PRES.



F. E. DAVIDSON
PRESIDENT



J. A. ARMSTRONG TREAS.




RALPH C. HARRIS SECY.

OFFICERS

RAYMOND

THE RAYMOND METHOD

A collapsible core or mandrel is encased in a spirally reinforced steel shell. Shell and core are driven to resistance — the core withdrawn—the shell *left in the ground*. Then, the shell interior is *inspected* and, finally, concrete poured into it. Simple—and *certain*—surely !



*A form for every pile
A pile for every purpose*

Study this Drawing Carefully

You have read the Raymond method.
Now study its illustration.

You see a method whereby excavation, pumping, shoring and sheeting expenses are reduced to the *minimum*.

Except when certain conditions prevent it, the excavation necessary for a pier of Raymond Concrete Piles is an extremely shallow one. In most cases, just enough to leave the tops exposed.

There's no digging down to reach below water level.

And note that the continuity of pile driving is unbroken. No waiting for the preceding concrete pile to set before driving alongside it—no danger of disturbing freshly poured concrete. The spirally reinforced steel shell protects it.

For economy, speed and safety —
Raymond Concrete Piles.

RAYMOND CONCRETE PILE COMPANY

New York: 140 Cedar Street

Chicago: 111 West Monroe Street

Raymond Concrete Pile Co., Montreal, Canada




CHAS. H. HAMMOND



BYRON H. JILLSON



EMERY S. HALL



R. C. OSTERGREN



H. B. WHEELOCK



GEO. BEAUMONT



CONVEYING EQUIPMENT

FOR ALL PURPOSES



Belt Conveyors
Gravity Conveyors
Apron Conveyors
Spiral Chutes
Automatic Elevators

Matter of fact we manufacture
equipment to handle any
type of commodity.



SAMUEL OLSON & COMPANY

Engineers, Manufacturers and Contractors

2418-2426 Bloomingdale Ave.
CHICAGO, ILL.


5th Avenue Building
NEW YORK, N. Y.



J.C. LLEWELLYN



IRVING K. POND



GEO. C. NIMMONS



DWIGHT H. PERKINS



RICHARD E. SCHMIDT



A. S. ALSCHULER



ELMER C. JENSEN

BOARD OF ARBITRATION

Federal Cement Tile Company

CHICAGO



Ford Motor Company, J. J. Storage Building, Detroit, Michigan

Covered with 213,000 square feet of Federal Cement Tile and flooded with daylight through the use of over 4,000 Glass Tile

"The Indestructible Roof"

FOR FLAT and PITCHED SURFACES

Made, Laid and Guaranteed by

FEDERAL CEMENT TILE COMPANY
110 S. DEARBORN ST
CHICAGO

HAMMOND, INDIANA. — Works — DETROIT, MICHIGAN



COMMITTEE
ON
PUBLIC ACTION



DURAND STEEL LOCKERS

are made in many types and sizes for schools, colleges, factories, clubs, stores and offices. They are built of steel specially rolled for the purpose; made to stand long and hard use; they are fire-proof, handsome, sanitary and indestructible. All moving parts are smooth-fitting and easy-working; nothing can rust or warp.

Durand Steel Lockers are the result of years of experience and specialization, careful thought and scientific skill applied to the making of every part.

Send for Catalog M of all types of
Durand Steel Lockers



DURAND STEEL RACKS



are scientifically designed, easily adjustable, and capable of an infinite number of variations by movable shelving, dividers, bin fronts, etc. They are fire-proof, and will stand up under heavy loads and rough usage. They are easily knocked down and re-erected; will increase storage capacity as much as 60%, making stock more accessible, reducing the help needed and making the stock room more efficient.

Send for Catalogue O of steel racks,
bins and shelving

Our Engineering Department will gladly prepare plans, specifications and estimates on steel locker or steel rack requirements. Write us of your special needs.

DURAND STEEL LOCKER COMPANY

1515 Ft. Dearborn Bank Building
Chicago

915 Park Row Building
New York City



HERBERT HEWETT



JAMES M. WHITE



HENRY R. HELMLE
SECRETARY

EXAMINING COMMITTEE
OF ARCHITECTS
• STATE OF ILLINOIS •



W. H. H. MILLER
DIRECTOR of
REGISTRATION and EDUCATION




EMERY S. HALL



F. A. CARPENTER





American Plaster Board
Eagle Gypsum Board
American Gypsum Blocks
Neat Wall Plasters
Sanded Wall Plasters
Wood Fiber Plasters
Gypsite Cement Plasters
Satin Spar Finish Plaster
Prepared Finishing Plasters
Sunflower Molding Plaster
Best Bros. Keene's Cement

Architects will find our line of products full and complete. We own and operate six of the best and largest gypsum deposits in the United States, located at the principal gypsum producing centers, thus enabling this company at all times to advantageously serve its trade in all principal markets on short hauls and low freight at the most economical costs. Mills are modern and unexcelled in equipment; the quality of these products is established in their use.

THE AMERICAN CEMENT PLASTER COMPANY

CHICAGO

ST. LOUIS, MO.

BUFFALO, N. Y.

Location of Mines and Mills:

Fort Dodge, Iowa
Gypsum, Ohio

Blue Rapids, Kans.
Agatite, Texas

Grand Rapids, Mich.
Akron, New York

GYP-SUM for PROTECTION

EDITORIAL.

THE SOCIETY.

The Illinois Society of Architects has been an effective working organization during the past year. Through its numerous committees it has prosecuted many and diversified activities. Always having in mind its first obligation to the public, it has sought and found many avenues of service to the profession which it represents. Indeed, while it has always been an organization of efficient service, it would be difficult to find a year in its history, or for that matter in the history of any similar society, when so much has been accomplished for the good of the community, as well as for the interests of its constituency. Space fails utterly to provide room to even enumerate its various accomplishments. Architects of Illinois may be justly proud of the great work being prosecuted by their state organization.

Get Busy.

Pride in another man's work, while it may be encouraging to the other man, is not constructive. Froth may be decorative, but real cream is nourishing. Every man ought to appreciate the fact that he himself has something to do for the common good. A mere cheer leader on the side lines has not much of which to be proud. Unfortunately, some rectly before them. There are many such tasks in connection with the work of the men are blind when a vicarious task lies di- Illinois Society of Architects. Far too few men are willing to give without promise of personal return. Therefore, the burden falls heavily upon the bent shoulders of the faithful ones. All honor to them! Let the slackers hang their heads with shame!

Legislation.

Constantly and in various ways the Society has kept the ends and aims of the best in the architectural profession before the public. Commendable legislation, both city and state, has been promulgated and carefully fostered. Perhaps those in charge of the amendment to the Illinois Architectural Act were slightly guilty of over-confidence in assuming that a bill unanimously passed by both houses of the legislature would not be vetoed by the Governor. Who knows? At least, the bill was vetoed and the committee worked hard up until the bill reached the Governor. It may have been the fault of the committee in not properly presenting the case. It might have been cheap politics. The enigma is unsolved. Let us hope that next time the mature judgment of the profession shall be given some small consideration.

Exhibitions.

Exhibitions are strange and difficult functions to handle. "Why did the committee do thus and so?" "Oh, well, they must have had their personal ends to accomplish!" The exhibition has been held and it pleased a lot of people. Why say "It might have been"? Our committee bore its share of the burden and accepts its portion of the anathemas of those whose offerings were not hung. It was ever thus; it ever will be so. Romanesque, renaissance, classic, colonial, Chicagoesque, prairie-esque, Sullivanesque, Wrighto, wrongo, all-the-samee-o exhibittee-o.

Public Action.

Our Public Action Committee has carefully scanned sky and sea and land. Dark specks on the horizon of clean professional practice have been quickly detected and as quickly annihilated by the charges of this efficient committee. Their scouting trips have accomplished much good, new companies have been organized and new out-works erected.

Education.

Education, professional,—what is it? Why have it? Shall we separate the material from the spiritual,—the architectural sheep from the engineering goats? The committee has wrestled with this problem; how hard, they know.

Membership.

Membership makes the machinery move. A purposeful migrating membership committee means more and more members. We have had such a committee and it has labored and brought forth forty-three new members during the past year. It reports that in the course of its travels it has found some dead self-centers which despite all efforts it has been unable to get out of self-lock.

Cooperation.


Democratic appreciation and brotherly cooperation between those that are and those that are to be is the key to real greatness. Architectural draftsmen and other assistants are embryo architects. Without their valuable aid no architect can hope to succeed in a large way. If they collectively, as well as individually, are not helped in the right direction, ill is promised for the future of the profession. The Committee on Co-operation with the Architectural Club has accomplished commendable results along these lines.

Publication.

A society without a seeing eye and an insistent voice is like a house without a foundation. The voice of the Society's Bulletin has been heard in many places; its eagle eye has peered into every corner and cranny. Evil has been torn from its hiding and held up to view, naked and ashamed. Wisdom has sprung forth as from a fountain. At the sound of that voice filthy combinations have slunk away and died in sadness and bitter dismay. Carefully groomed and held in leash by the Committee on Publications, the Illinois Society Bulletin has accomplished a unique work in the way of a professional publication and constitutes one of the largest services that the Society has been able to render to its members.

Entertainment.

Shallow entertainment for entertainment's sake accomplishes neither pleasure nor profit. A story without a purpose is not even an interesting story. The Entertainment Committee has seen to it that the programs of the Society have been both entertaining and instructive.



BIRD'S BUILT-UP ROOF

FOR FLAT ROOFS OR SAW-TOOTH CONSTRUCTION
OVER SHEATHING OR CONCRETE

Above cut shows method of application over sheathing. Completed roof over Sheathing weighs approximately 146 pounds. Mopped solid with hot Asphalt. In no place does felt touch felt.

THE CAP SHEET ON THIS ROOF IS PAROID ROOFING

Bird's Paroid Roofing was applied in 1903 on roof of the Dearborn Street Station, Chicago. Copper flashings of this roof were destroyed by gases. In 1912 the roof was reroiled, reflashed and painted, and examination in 1921 shows that now, after 18 years, it is still in good condition.

Bird's Paroid Roofing Cap Sheet takes the wear. It is used instead of slag or gravel. It seals and protects the Asphalt Compound and Felt of Neponset Built-Up Roof not only from sun and air but from Water, Acids and Gases.

Bird's Built-Up Roof is particularly adapted to Mill Roofs of saw tooth construction because it has no surface that will slide or slip; no slag or gravel to roll off. It will not slide or run in summer or harden and crack in winter. No nails exposed. Detailed specifications on request.

FOR STEEP PITCH ROOFS—BIRD'S PAROID ROOFING

BIRD'S NEPONSET BLACK WATERPROOF BUILDING PAPER
FOR INSULATION

EAST WALPOLE
MASS.

BIRD & SON

1472 W. 76th St.
CHICAGO

MATERIAL VS. ETHEREAL.

Continuous systematic study of the material problems of life is essential to the highest attainment. Vision is that intangible something that charms and soothes the jaded sense of man, gives repose to the weary heart, and blends the family into one common unit of purpose. It is a strong compelling agency in that power which drives man forth to work and fight for the protection of the home; the inspiration which enables woman to endure the dull monotony of endless household cares; a shrine toward which the lonely youth turns in the hour of discouragement and girds himself to carry on in life's battle. Dreams may be swallowed up in themselves and end only in disappointment and sorrow; or, dreams may be made facts by man's persistent effort. Beautiful drawings, charming only as drawings, are dreams not come true. Drawings are not designs, but only the medium for presenting the designs. Real design in architecture is the building complete in every detail, and the man who cannot dream material as well as lines has no right to call himself an architect. His vision is incomplete. If he cannot close his eyes and feel the texture of the stone, the colorful note in the brick and tile, and see his building functioning with human beings moving in and out performing their daily tasks with less fatigue and more pleasure because of beautiful environment perfectly adjusted to practical need, he has missed his calling. Good design is appropriate material rightly placed and molded in pleasing proportion. To design without the material sense is not to design at all, but is to be merely confused with fine draftsmanship. Architecture is not fine drawings, but beautiful buildings, beautiful in grouping of mass, proportion of openings, and well-balanced assignment of space to serve the functions involved. The Committee on Materials and Methods has devoted much time to an attempt to eliminate waste in the practice of building and to bring building laws in accord with economic principles of modern practice.

To sum up, the Society team has pulled together and pulled well. Probably the most successful year in the Society's history has been accomplished.

LABOR.

Economic necessity requires that all men shall work. Work with hand or brain is the price of everything that is worth having. Every bit of joy, every bit of knowledge, every bit of comfort is the product of work. The Scripture says that if any will not work, neither should he eat. But the law of economics says that if all men do not work their full share, by that measure shall all men suffer. Society has no place for either drones or wasters.

Artificial jurisdictional division of labor is wasteful of effort and a destroyer of industry. It implants a spirit of jealousy and distrust in the breast of every workman. It curtails per capita production. It acts like a wet blanket on the spirit of ambition. While the ambitious man would best his brother in the battle of life, he would not tear him down to his level, but, rather, while his brother climbs he would climb still higher.

Adequate remuneration, decent working conditions, reasonable hours of competent, efficient service, these are within the province of the labor union. To see that these are facts, the latter as well as the former and the former as well as the latter, is the proper function of the labor union. When the labor union sets up such conditions that two men must do the work that one could do as well and with no more effort, it commits an economic offence that cannot be forgiven.

Entangling alliances between labor unions and contractors are like entangling alliances between nations — dangerous precedents—precedents which are sure to open a broad road to trouble for all, the contractor as well as the laboring man. The extraction of chestnuts from collusive fire has caused many a clever cat to travel through its declining years of life with a bifurcated caudal appendage. Let labor, professional skill, and business each perform its separate duty to society and see that their several tasks are well done and all will be well. Let any of these combine against society and they combine against themselves. As "chickens come home to roost," so are economic sins set on our own doorsteps, no matter how hard we try to leave them on the doorsteps of our neighbors. The pitiful condition which has been revealed in the City of Chicago as a result of the investigations of the Daly Commission only serves to illustrate the accuracy of the foregoing observations. The condition, in which the building industry of this locality finds itself, cannot be wholly charged to labor unions. They are the result of cupidity on the part of owners, contractors, and so-called representatives of organized labor. Some rich owner says to himself, "My business requires thus and such a building. If I can secure this building by thus and such a time, I can add to my material wealth thus and such an amount of money. Now a proper and legitimate cost of this building is so much, and, yet, I know that by sharp practice and peculiar operation of that building, I can make it pay a handsome interest on a sum more than twice the proper cost of such building." Mr. Owner then hires himself to an architect and has his building designed, plans and specifications prepared, and instructs his architect to have the building completed by thus and such a time. The architect informs him that this is impractical and extravagantly expensive. He states, "Never mind about that, I must have the building." The architect then seeks out some contractor, not too scrupulous as to public interests, and submits the proposition to him. He in turn seeks out the representatives of union labor and by dark and devious arrangements persuades them to facilitate the project beyond reasonable speed. The building is erected at extravagant cost, the labor delegate, the contractor, and the architect have each received remuneration disproportionate to the actual service rendered, have each indulged in immoral practice, and have each had his standards of probity and justice lowered, never again to be the same as before. The owner has his building, is enabled to make a profit on the project, and is satisfied. What cares he if he has lowered the moral tone of the community? He has accomplished his purpose. He is on the road to greater affluence. Who pays the bill for the dangerous precedent established, for the excessive cost of the building erected, for the moral breakdown that has affected every department of building construction? The answer is simple—the Public. Every building that is erected at a cost which is greater than a legitimate cost is a charge on the community and comes out of the pockets, not only of the other fellow, but actually of those individuals who originally profited by its construction.

The conditions already depicted do not stop with the project in hand. Nervous haste, recklessness of cost, disregard of moral obligation, all put the directors of building projects in a position where they are easy victims of arbitrary rules and impossible working conditions. Such conditions have enabled the representatives of various natural groups of the craftsmanship entering into building construction to set up arbitrary and unscientific divisions of such groups; thereby making more jobs for walking delegates and more possibilities for discord among craftsmen on account of artificial



WATERPROOFING PRODUCTS *and* BUILDING SPECIALTIES

Crescent Waterproofing Products are dependable. Our salesmen are practical men. This combination insures satisfaction when our materials are specified and used.

We Manufacture

CRESCENT WATERPROOFING
INDURITE LIQUID HARDENER
METALLIC FLOOR HARDENER
BRICK AND CEMENT COATING
TRANSPARENT WATERPROOFING
DAMPPROOFING and PLASTER BOND

We are district distributors for

R-N SILICA PLASTER—It adheres to Concrete
STEELCRETE EXPANDED METAL LATH
COVERT IMPROVED FIRE-PLACE DAMPERS

A complete stock of all of the above
materials is carried in Chicago

A telephone call to **Randolph 1332** will bring information regarding Crescent Products to your desk

CRESCENT SALES & MFG. CO.
110 S. DEARBORN STREET
CHICAGO

divisions which are not real or justifiable and thus bringing about waste of endeavor and plunging the whole labor movement into turmoil.

Men who use the same tools and employ the same materials naturally belong to the same group of craftsmen and naturally, if skilled in the craftsmanship involving the use of certain tools and material, can perform any work involving these tools and material with passing skill, possibly with not high efficiency. Continuous practice in doing one thing develops very great dexterity in performing that particular act, but has a demoralizing effect on the worker, for the very good reason that the continuous performance of the same operation eventually becomes automatic and is thus controlled by the subjective mind rather than the reasoning mind. Without useful occupation the reasoning mind falls into useless or dangerous occupation. Highly concentrated craftsmanship ceases to be craftsmanship and becomes merely automatic production. Art disappears and the moral tone of the operator gradually breaks down and a human being, one of the greatest assets to society, is made unfit to perform his natural community function; this from a moral standpoint. From an economic standpoint, the loss is fully as great. A manager is delighted at the great proficiency evidenced by the men who are kept employed on one small operation. He says to himself, "See what I have done to increase production." Next, symptoms begin to manifest themselves which are not to his liking. First, he is informed that the nervous tension induced by high speed, specialized production makes it impossible for the men to endure as long hours as formerly. Then he notes that after the hours are reduced a spirit of discontent is spreading among the operatives, jealousies arise as the result of one specialist encroaching on the work of another specialist. He finds that he must send not one but sometimes three or four men to perform the task that formerly one man would have performed in the same length of time and without complaint; and a little later he discovers that notwithstanding the apparent high efficiency of specialization he cannot produce a complete finished product, such as a completed building, at anywhere near the former cost. He further finds that he has a collection of men who are practically helpless outside of a few small functions. They have lost their ability to turn their skill to several tasks. They no longer are self-reliant, self-respecting citizens, they are merely specialized tools.

Probably ninety per cent. (there seems to be no exact statistics, one may only judge by experience) of all the jurisdictional controversies grow out of disagreements between arbitrary subdivisions of craftsmen in the same scientific group, that is, craftsmen who employ the same tools and materials. For illustration, in the mortar using trades, a brick mason finishes a little cement floor just as well as a cement finisher could do it,

or, at the least, passing well, and there is a strike on the job because a brick mason did a cement finisher's work. A cement finisher runs a sanitary base around a room, the floor pitches, part of the base is six inches high and part of it is more than six inches high. That portion of the base which is six inches or under is cement finisher's work; that portion of the base which is over six inches is plasterer's work. A strike is called. Absolutely senseless! A cement finisher can run the base as well or better than the plasterer and the plasterer may run the base passing well. What happens? In order to secure peace, the public is compelled to pay the two men to do the work which one might do as well. This cuts down per-capita production and reduces national wealth. It is not a question of the amount of gold that there is in a nation's treasury, but is a question of the per-capita production of wealth which determines a nation's real commercial status. If two men travel from their homes to a job and spend their day in performing a task which one could have performed without over-exertion, two men go home at night equally tired, equally broken down physically, but the product of their joint labors is only half what it would have been if each had gone to a separate building and performed a full day's service. The country has suffered and the men are not one whit better off.


It seems difficult for the average agitator to understand that high per-capita production instead of robbing men of jobs actually creates more jobs for men. But agitators as a rule are not thinkers. The simple answer is: High per-capita production means a lowering of cost of the product and the lowered cost of the product puts the product within the purchasing power of more people. More purchasers increase the demand and the ultimate result is more work for more men and more people who may have more conveniences than they formerly could have had. When the cost of building goes up, rents of necessity go up. When rents go up, more families live in the same flat and live under more unsatisfactory conditions, less buildings are built, less work is supplied for the workers and the whole community suffers.

BUILDING VALUES

It is felt that there is need for a new viewpoint in building valuation. In the past it would seem that too much stress has been laid on age, or rather lack of age, and immediate revenue as factors in building valuation. It would seem that the architect, owing to his peculiar training, is in a position to point out other very important factors entering into value makeup, which have not heretofore been considered in this locality; such as balance of structural design, adaptability to purposes intended, character of construction as influencing cost of upkeep.

Feeling that the stability of building investment can be better assured by taking the before mentioned factors into consideration, the Illinois Society of Architects has appointed a Building Valuation Committee to furnish the public with competent architectural valuation service. This Committee should form a real asset to the community.

Barrett Specification Roofs



This is a photograph of a cross-section cut from a Barrett Specification Roof.

Your Roof is not Finished Unless it has a Wearing Surface—

WHEN planning to cover any flat-roofed building, remember this:

No matter how good the roofing is, unless it has a wearing top surface, such as gravel, slag or tile, it is like a book without a cover—it isn't finished.

That is why, when The Barrett Specification was worked out years ago, the engineers insisted not only that it should be built up of the two most serviceable roofing materials in the world—pitch and felt in alternate layers—but that it should have a top-wearing surface of gravel, slag or tile.

It is imperative that every flat roof have such a wearing surface—

—to protect the roofing materials from the direct destructive action of rain, snow, ice and sun;

—to form a wearing surface to protect the roofing materials from scuffing feet and the dragging of heavy objects over the roof;

—to make the roof highly fire-resistant so as to secure the base rate of fire insurance.

Before specifying or closing contract for a Barrett Specification Bonded Roof, be sure to read carefully all the stipulations in the specification.

The Barrett Specification Type "AA" 20-Year Bonded Roof represents the most permanent roof covering it is possible to construct, and while we bond it for 20 years only, we can name many roofs of this type that have been in service over 40 years and are still in good condition.

Where the character of the building does not justify a roof of such extreme length of service, we recommend the Barrett Specification Type "A" Roof, bonded for 10 years. Both roofs are built of the same high grade materials, the only difference being in the quantity used.

Full details containing these Bonded Roofs and copies of The Barrett Specifications is at our disposal.

The **Barrett** Company 

New York Chicago Philadelphia Boston St. Louis
Cleveland Cincinnati Pittsburgh Detroit New Orleans
Birmingham Kansas City Minneapolis Dallas
Nashville Syracuse Salt Lake City Seattle Portland
Atlanta Duluth Milwaukee Barco Washington
Johnstown Lorain Youngstown Toledo Columbus
Richmond Detroit Bethlehem Elizabeth Buffalo
Baltimore Omaha Houston Denver Jacksonville

THE BARRETT COMPANY, LIMITED:

Montreal Toronto Winnipeg
St. John, N. B. Halifax, N. S.

THE ILLINOIS SOCIETY OF ARCHITECTS

CANONS OF PROFESSIONAL ETHICS

Preamble.

The architect is engaged in a profession which carries with it grave responsibilities to the public. These duties and responsibilities cannot be met unless the motives, conduct and ability of the members of the profession are such as to command respect and confidence.

The profession of architecture calls for men of the highest integrity, and executive and artistic ability.

The architect is entrusted with financial undertakings where his honesty of purpose must be above suspicion; he acts as professional adviser to his client, and his advice must be absolutely disinterested: he is charged with the exercise of judicial functions as between client and contractor, and must act with entire impartiality, and he has moral responsibilities toward his professional associates and subordinates.

The people of the State of Illinois have a right to expect a high standard of practice and conduct on the part of the architects whom they have licensed to practice. Because an architect is a quasi public official it is imperative that he assume no obligations which shall place official duty and self-interest in conflict.

The Canons of Ethics.

No set of rules can be framed which particularize all the duties of the architect in his various relations to the public, to his client, to the building trades and to his professional brethren.

The following canons of ethics cover certain broad principles which should govern the conduct of members of the profession and should serve as a guide in circumstances other than those enumerated:

I.—On Certain Duties to the Public.

The architect's more important work is of a character so permanent and enduring that he owes it to the public to use his best efforts to make it such as may raise the standard of taste in the community and be in itself a public ornament. He should design with due regard to surroundings and should endeavor to check any individualism, whether in himself or

his client, that is opposed to the public good. He should take part in those movements for public betterment in which his training and experience enable him to give useful service. He should insist on safe and sanitary construction and he should at all times hold the safe guarding of human life and health as of paramount importance to the interests of client, contractor or self.

II.—On the Architect's Status.

The architect's relation to his client is primarily that of professional advisor. This relation maintains throughout the entire period of his service. When, however, a contract is executed between his client and a builder or other person by the terms of which the architect becomes the official interpreter of its conditions and the judge of its performance, a new relation is created. In respect to the matters under contract, it is incumbent upon the architect to side neither with the client nor contractor, but to endeavor, in so far as his action may determine, that the contract be faithfully carried out according to its true spirit and intent.

It is not proper for the architect to assume to act as the owner's agent unless he has been specifically empowered so to act: by so doing he becomes a party to the contract and in a sense disqualified in his judicial capacity.

The fact that the architect's payment comes through the client does not invalidate his professional obligation to act with impartiality to both parties to the contract. It is essential, however, in order to eliminate the influence of self-interest, that the architect shall not enter into any contract with the client which shall condition his payment upon his decisions or advice.

III.—On Preliminary Drawings and Estimates.

The architect should impress upon his client at the outset the importance of sufficient time for the study and preparation of drawings and specifications. If, on the basis of approved preliminary

Otis Elevator Information To Architects

FACILITIES FOR SERVICE

Before installation: The Otis Elevator Company will cooperate in every way with the Architect in determining and planning proper elevator equipment. Otis Offices in over one hundred American cities facilitate practical personal service in the consideration of adequate equipment to Architects and prospective purchasers of Elevator apparatus.

After installation: Over one hundred and fifty Offices and Local Service Stations in all important cities afford every facility for inspection and proper maintenance work.

OTIS BUILT THROUGHOUT

Otis Elevators are Otis built throughout. Otis motors and controllers are designed and built in Otis plants specifically for elevator service, and are more efficient and economical in operation than adapted open market equipment.

ELECTRIC ELEVATORS

The superiority of the direct connected Electric Elevator is attested by the fact that it constitutes at least ninety per cent of the present day installations.

TRACTION ELEVATORS

The remarkable operating and space economy of the Traction Elevator as developed by the Otis Elevator Company for high buildings and universally adopted for important office building service have brought about the standardization of the Traction Elevator for practically every purpose.

GEARLESS TRACTION ELEVATOR

This type of elevator employs a slow speed high torque motor and carries the driving sheave directly on the armature shaft, thus eliminating all gearing and developing a remarkably high efficiency. It is used in important passenger service for 500 to 700 feet car speed. A modification of this type is the 2:1 Gearless Traction Elevator, which is used for service where 400 to 500 feet car speed is adequate.

WORM GEAR TRACTION ELEVATOR

In this type a high speed motor is connected to the driving sheave through a worm and gear reduction. This Elevator is used for the less important low rise

passenger service and for most freight work. The speeds range up to 350 or 400 F. P. M.

CONTROL SYSTEMS FOR ELECTRIC ELEVATORS

Hand rope control is fast becoming obsolete. It cannot compare with switch or push button control for facility in handling, and subjects the equipment to greater wear and tear. Control by switch in the car is the accepted form for most general passenger and all freight work which does not demand service without attendance. Push button or automatic control safely and practically meets the requirements of service without a regular operator. With the addition of the Micro Drive feature described below this type of control may be used with any speed and load. Otherwise, it should be limited to light duties and 100 to 150 feet car speed, such as is used in private houses, banking offices, hospitals, apartment houses, etc.

OTIS MICRO LEVELING ELEVATOR

An ingenious development of the electric elevator provides a service incorporating perfect stops wherein the car always registers level with the landing floor, whether the load be zero or maximum, and automatically maintains that position under all conditions of loading. This type of elevator may be controlled either by switch in the car or push buttons. It is particularly advantageous when used in connection with industrial truck service, assuring perfect stops, which facilitate truck wheel action.

OPERATORLESS ELECTRIC ELEVATOR:

In many large plants using batteries of freight handling elevators, automatic push button control micro leveling equipment may be advantageously introduced. Examples of this type of elevator are some of the big government built terminal warehouses in Brooklyn, Boston, etc., wherein groups of from six to ten elevators are controlled by a central dispatcher working with a conveniently located push button control board.

Illustrations and bulletins on elevator service for specific conditions, specifications and estimates furnished on request to our nearest office.

OTIS ELEVATOR COMPANY

Eleventh Ave. and Twenty-Sixth St., New York

600 West Jackson Boulevard, Chicago

Offices in All Principal Cities of the World

sketches, the approximate cost of the work has been mutually considered, the architect should endeavor to bring his working drawings to meet such approximate cost, provided that his client has requested no departure from the original basis of estimate. But at the same time he should acquaint his client with the conditional character of preliminary estimates. Complete and final figures can be had only from complete and final drawings and specifications. If an unconditional limit of cost is imposed before such drawings are made and estimated, the architect must be free to make such adjustments as seem necessary to that end.

IV.—On Superintendence and Expert Service.

On all work except the simplest, it is to the interest of the client to employ an inspector or clerk-of-the-works; in many engineering problems and in certain esthetic problems such as sculpture, decorative painting, gardening and the like, it is to the interest of the client to have specialized expert service. The architect should so inform the client and assist him in obtaining such service. In order to secure unified and harmonious working organization, only such persons should be selected by the owner for consulting experts as shall work in harmony with the architect and shall be approved by him.

V.—On the Architect's Charges.

The schedule of charges of the Illinois Society of Architects is recognized as a proper minimum of payment, but where no other architect is affected it is allowable for an architect to make such an arrangement with his client as is mutually satisfactory. He may not reduce his fee below the schedule of charges in an attempt to supplant another architect; it is reasonable and proper to charge higher rates than those of the schedule when his special skill and the quality of his service justify the increase.

A system of compensation based on the actual cost to the architect on a given piece of work plus an agreed professional fee, has much to commend it.

VI.—On Needless Expenditure.

The architect should scrupulously guard cost, and refrain from introducing need-

less expense or any extravagance in material or construction that may add to cost of building, without compensating gain to the client.

VII.—On Payments for Expert Service.

When retained as an expert, whether in connection with competitions or otherwise, the architect should receive a compensation proportionate to the responsibility and difficulty of the service. No duty of the architect is more exacting than such service, and the honor of the profession is involved in it. Under no circumstances should experts, knowingly, name prices in competition with each other for a given employment. Where governmental regulations prohibit adequate compensation for expert service, it is better to render such service without emolument than to accept a payment out of proportion to the importance of the service rendered.

VIII.—On the Selection of Bidders or Contractors.

The architect should advise his client in the selection of bidders and in the award of contract.

In selecting none but worthy bidders and in advising the award only to contractors who are honest and competent, the architect protects the interests of his client and helps to raise the ethical standard in building.

IX.—On Duties to the Contractor.

On the signing of a contract between owner and builder, the architect is placed in a judicial position and is bound to act with absolute fairness; he is also judge in his own right, deciding whether or not the intent of his plans or specifications is properly carried out, and exercising his judgment as to the true meaning thereof. He should, therefore, take special care to see that these drawings and specifications are complete and accurate, and he should never call upon the contractor to make good his own oversights or errors, or attempt to shirk responsibility by "blanket" clauses.

X.—On Engaging in the Building Trades.

The architect should not engage in any of the building trades, nor should he form any trade partnership or agreement with any person or firm connected therewith;

Elevator Company of America


Manufacturers of

Passenger and Freight Elevators

General Offices: 1216 State-Lake Building

Chicago, Illinois

Phone Central 323



GEARED TRACTION ELECTRIC ELEVATOR MACHINE

Floating Shoe Brake (Balanced Type)

AMERICA'S BEST ELEVATORS

*Contracted for by the Following Representative
Chicago Concerns*

Chicago Sporting Goods
Mfg. Co.
State-Lake Bldg.
Clara F. Bass
American Car & Fdry. Co.
Calumet Refrigerating Co.
E. J. Brach & Sons
Columbus Hospital
Anchor Leather Co.
B. Gelman
Jacobson Brothers
A. Pick & Co.
North Pier Terminal Co.
Klee Bros. & Co.
West End Hospital
Golden Rule Cutlery Co.
Great Northern Bldg.
Majestic Hotel
Chicago Star Line Lines
David Fireproof Storage
Warehouses

S. Birkenstein & Sons
City of Chicago
Webster Hotel
Illinois Smoked Meat Co.
Corn Products Refining Co.
Weyman-Bruton Co.
Park Gate Hotel
Elgin Motor Car Sales Co.
General Furniture Co.
Gutmann & Co.
Thos. E. Wilson Co.
Versailles Apt. Hotel
Lesserman Bros.
Chas. Hollenbach
Independent State Bank
Edward Greenstone Furni-
ture Co.
Steiger Trunk & Bag Co.
Chas. Lange & Bros. Co.
Theo. Renz
H. Emmerman
Wells Building Corp.

Geo. J. Kroeck
Garrick Building Corp.
Rainbow Chocolate Co.
Balaban & Katz
Clemetsen Desk Co.
L. Wolff Mfg. Co.
Morris Goldschmidt & Co.
G. & W. Electric Specialty
Co.
Arcus Ticket Co.
Glabman Brothers
Manufacturers' Exhibition
Bldg.
Sure Pure Ice Co.
Edward Ahlswede & Co.
Columbus Extension Hos-
pital
Zangerle & Peterson Co.
Regensteiner Colortype Co.
Griffin Wheel Co.
Sherwin-Williams Co.

nor should he have any financial interests in any building material or device of such a nature as to render his professional action liable to a suspicion of self-interest: if he have any interest in building material or device, he should not specify or use the same without the full knowledge and approval of his client.

XI.—On Accepting Commission or Favors.

The architect may not receive any commission or any substantial service or favor from a dealer, a contractor, or from any interested person other than his client.

XII.—On Encouraging Good Workmanship.

In his authority to interpret and enforce the provisions of the contract, the architect is vested with large powers which he should use with unbiased judgment. While he must condemn bad work, he should also make a point of commending that which is good.

Intelligent initiative, artistic or mechanical, on the part of craftsmen and workmen, should be promptly recognized and encouraged, and the architect should make evident his appreciation of the dignity and importance of their work.

XIII.—On Offering Service Gratuitously.

The offering of professional service on approval, unless warranted by personal or previous business relations, tends to lower the dignity and standing of the profession: also to provide motive for dishonest representation and is to be condemned.

XIV.—On Advertising.

Advertising in any form is to be discouraged as tending to lower the standing of the profession. The presentation of ordinary business cards is a matter of individual taste and not per se improper; but the solicitation of work by circulars or advertisements and the inspiring or inserting of self-laudatory notice in the press are unprofessional.

The best recommendation of an architect is a well-merited reputation for professional capacity and fidelity to trust.

XV.—On Signing Buildings and Use of Titles.

The signing of buildings has the indorsement of the Chicago Architect's Business Association. The use of the initials designating degrees or technical society membership is proper in connection with any professional service and is encouraged as helping to make known the nature of the honor they imply.

XVI.—On Competitions.

In no way does the architect come more conspicuously before the public than through competitions. It is especially desirable that in such circumstances he should conduct himself with self-respect and dignity. To under value and cheapen his service or to compete where a just

award is not safe guarded is inconsistent with this position. Competitions are undesirable from the standpoint of both the client and the architect and a member of the Association should discourage the holding of same. If a competition becomes inevitable, because of governmental regulations, he should not enter either as a competitor or a professional advisor unless the competition is to be conducted according to the best practice and usage of the profession as formulated from time to time by the American Institute of Architects. Except as an authorized competitor he may not attempt to secure work for which competition has been instituted.

He may not present drawings to secure work for which competition has been closed but not decided.

He may not attempt to influence the award in any competition.

XVII.—On the Expert's Future Status.

An architect may not undertake a further commission on any building or work after having acted in an expert capacity in formulating a program which later is put into effect, or after having acted in an advisory capacity in the matter of awards in competition. Having acted in either or both of such capacities should bar an architect from eligibility to execute commissions upon the work in question.

XVIII.—On Criticising the Work of Others.

An architect may not criticise publicly in the press the work of a fellow architect except over his own signature, or editorially; and he may not intentionally injure, directly or indirectly, the reputation, prospects or business of a fellow architect.

XIX.—On Undertaking the Work of Another.


An architect may not undertake a commission while the just claim of a fellow architect, who had previously undertaken it, remains unsatisfied; nor may he attempt to supplant a fellow architect or to obtain a commission after steps have been taken toward the appointment of another architect.

XX.—On Duties Toward the Student Draughtsman.

It is the duty of the architect to advise and assist those who intend making architecture their career. The intending student should be urged to secure a preparation of broad general culture equivalent to that required for the degree of A. B., concurrently with or followed by a thorough course in a well organized school of architecture.

In cases where such preparation is out of the question and the beginner must get his training in the office of an architect, the latter should assist him to the best of

THE UP-TO-DATE ELEVATOR




THAT IS MECHANICALLY AND ELECTRICALLY CORRECT

WHEELER ELEVATOR CO.

1100-6 Washington Boulevard
CHICAGO, ILLINOIS

TELEPHONES: MONROE 1050 AND MONROE 1051



Builders of V groove traction type electric elevators, suitable for any capacity and speed, for Passenger and Freight service, Car Switch, Push Button and Hand Rope Control, also V groove traction hand power elevators.

Prompt service on all repair and alteration work.

his ability by instruction and advice. An architect, should, as far as possible, urge his draughtsmen to avail themselves of educational opportunities. To this end he should give encouragement to all worthy schemes and institutions for architectural education.

Members of the society cannot too strongly insist that a thorough technical preparation for the practice of architecture should rest upon a foundation of general culture.

XXI.—On Duties Toward Building Authorities.

The architect should support all federal, state and municipal officials who have charge of matters relating to building and endeavor to maintain or improve the standards of their departments. His quasi public official capacity requires him to show respect for law by careful and conscientious compliance with all building regulations, and if any such appear to him unjust or unfair, he should endeavor to have such regulations altered, but until so altered he should comply with them. An architect because of his official relation to the state and of his moral obligation should not even under his client's instructions encourage any practices contrary to law or hostile to public interests; for he is not obliged to accept a given piece of work, hence he cannot urge in extenuation and to escape the condemnation attaching to his acts that he has but followed his client's instructions.

XXII.—On Professional Qualifications.

The assumption of the title of architect should be held to mean that the bearer has the professional knowledge, both theoretical and practical, and the natural ability needed for the proper invention, illustration and supervision of all building operations which he may undertake.

XXIII.—On Matters Adjudged Unprofessional.

The following code, based on a report of a special committee of the American Institute of Architects, is adopted by the Illinois Society of Architects as a general guide, yet the enumeration of partic-

ular duties should not be construed as the denial of the existence of others equally imperative though not specifically mentioned. It should also be noted that these sections indicate offenses of greatly varying degrees of gravity:

It is unprofessional for an architect—

1. To engage in any of the building trades or to form any trade partnership or agreement with any person or firm engaged therein.

2. To guarantee an estimate or contract by bond or otherwise.

3. To accept a commission or any substantial service or favor from a contractor, or anyone connected with the building trades.

4. To advertise in any form.

5. To enter any competition the terms of which are not in harmony with principles approved by the American Institute, especially if such terms have been specifically condemned by the American Institute or a local chapter thereof.

6. To attempt in any way except as a duly authorized competitor to secure work for which a competition has been instituted.

7. To attempt to influence the award of a competition.

8. To injure intentionally the fair reputation, prospects or business of another architect.

9. To criticise anonymously in the public prints, except editorially, the professional conduct or work of a fellow architect.

10. To undertake a commission while the just claim of another architect who has previously undertaken it remains unsatisfied.

11. To attempt to supplant a fellow architect after definite steps have been taken toward his employment.

12. To offer or perform services at rates lower than those approved as minimum by the Illinois Society of Architects in an attempt to supplant or underbid another architect.

13. To act in a manner detrimental to the best interests of the profession.

SCHEDULE OF PROPER MINIMUM CHARGES AND PROFESSIONAL PRACTICE OF ARCHITECTS RECOMMENDED BY THE ILLINOIS SOCIETY OF ARCHITECTS

1. The architect's professional services consist of the necessary conferences, the preparation of preliminary studies, working drawings, specifications, large scale and full size detail drawings, and of the general direction and supervision of the work, for which, except as hereinafter mentioned, the minimum charge is six per cent (6%), based upon the total cost of the work complete.

In case of the discontinuance or abandonment of the work, the architect's

charge shall be based upon an *estimated* total cost, which estimated total cost may be determined by the architect, by experts, or by the lowest bids of responsible contractors. *Total cost* is to be interpreted as the cost of all materials and labor necessary to complete the work, plus contractors' profits and expenses, as such cost would be if all materials were new and all labor fully paid, at market prices current when the work was ordered.

**The Pitt Engineering
Co are Builders of
Heavy Duty Passenger
and Freight Elevators
Electric and Hydraulic**

**We are at Your Service
in the Solution of Your
Elevator Problems**

**Phone
Franklin 452**

**120 W Kinzie St
Chicago Illinois**

2. On residential work, on alterations to existing buildings, on monuments, furniture, decorative and cabinet work, and landscape architecture, it is proper to make a higher charge than above indicated.

3. The architect is entitled to compensation for articles purchased under his direction, even though not designed by him.

4. If an operation is conducted under separate contracts, rather than under a general contract, it is proper to charge a special fee in addition to the charges mentioned elsewhere in this schedule.

5. Where the architect is not otherwise retained, consultation fees for professional advice are to be paid in proportion to the importance of the questions involved and services rendered.

6. Where heating, ventilating, mechanical, structural, electrical and sanitary problems are of such a nature as to require the services of a specialist, the owner is to pay for such services in addition to the architect's regular commission. Chemical and mechanical tests and surveys, when required, are to be paid for by the owner.

7. Necessary traveling expenses are to be paid by the owner.

8. If, after a definite scheme has been approved, changes in drawings, specifications or other documents are required by the owner; or if the architect be put to extra labor or expense by the delinquency or insolvency of a contractor, the architect shall be paid for such additional services and expense.

9. The architect's entire fee is itemized and proportionate payments on account are due the architect, as the following items are completed:

Preliminary Studies	2
General drawings	3
Specifications	1
Scale and full size details.....	1
General Supervision of the work....	3

Total1.00

Fee for complete services as agreed, see for paragraphs 1 and 12.

10. Items of service are comprehended as follows:

(a) **Preliminary Studies** consist of the necessary conferences, inspections, studies and sketches modified and remodified to determine the client's problem and illustrate a satisfactory general solution of same, both as to plan and elevation. Illustrative sketches for this purpose need not be to accurate scale, but should be approximately correct as to general dimensions and proportion.

(b) **General Drawings** include figured scale plans of the various stories, eleva-

tions of all the fronts, such general vertical sections as may be necessary to elucidate the design, and such details, drawn to still larger scale as, with the assistance of printed notes, and of the accompanying specifications, may make the whole scheme clearly evident to the mind of the competent builder and give him a full and complete comprehension of all the structure conditions as they affect the vital questions of quality and quantity of materials, of character of workmanship, and of cost.

(c) **Specifications** consist of a supplementary statement in words, of at least all those items of information regarding a proposed building which are not set forth in the drawings.

(d) **Detail Drawings** include all the necessary supplementary drawings required for the use of the builders, to enable them to so provide and shape their material that it may be adjusted to its proper place or function in the building with the least delay, and the smallest chance for errors and misfits. If not prepared until after the contract for the building is let they must not impose on the contractor any labor or material which is not called for by the spirit and intent of the "General Drawings" and "Specifications."

(e) The **Supervision** of an architect (as distinguished from the continuous personal superintendence which may be secured by the employment of a clerk-of-the-works or inspector of construction) means such inspection by the architect or his deputy, of work in studios and shops or a building or other work in process of erection, completion or alteration, as he finds necessary to ascertain whether it is being executed in general conformity with his drawings and specifications or directions. He has authority to reject any part of the work which does not so conform and to order its removal and reconstruction. He has authority to act in emergencies that may arise in the course of construction, to order necessary changes, and to define the intent and meaning of the drawings and specifications. On operations where a clerk-of-the-works or inspector of construction is required, the architect shall employ such assistance at the owner's expense.

11. Drawings and specifications, as instruments of service, are the property of the architect.

12. Exceptions.	
Dwellings costing less than \$10,000..	10%
Lofts not requiring special planning	
for machinery or arrangement....	5%
Additions and alterations to dwellings..	12%
Additions and alterations to business	
buildings	10%

N. B.—Above schedule is considered minimum for ordinary and usual professional service. It is not considered fair or reasonable for highly specialized service.

Fireproof ^{U.S.} & Products

Pyrobar Partition Tile

Pyrobar tile is the only material that has ever passed the Underwriters' Laboratories fire and water test for fireproof partitions. Strong, light weight, non-conductor of sound and heat. Used for partitions, turring, elevator enclosures, and steel protection.

Pyrobar Reinforced Roof Tile

Made of light, strong Structolite, is unequaled for roof decking. Its high insulating quality saves fuel. It stops condensation. It is resistive to smoke and sulphur fumes. It is quickly and economically erected in any kind of weather, can be adapted to any roof design or purlin spacing, and is ready for immediate application of any roof covering.

Pyrobar Reinforced Floor Tile

Are designed to replace either metal forms or clay tile voids in reinforced concrete construction. Uniform in size and shape, end pieces cast integral, provides ideal plastering surface for ceilings, light in weight, easy and economical to install.

Pyrofill Monolithic Roof Deck

An economical form of poured-in-place construction. Light in weight, of proved strength. Rapidly erected, quick to set, fire-proof, non-conductor of heat, minimizing condensation.

Sackett Plaster Board

Is a fire-proof plastering base. Nailed to the studding or joists, or applied on Jester system of channels and clips, and plastered with Gypsum Plaster, which bonds to it perfectly. Makes a strong, rigid wall, sound-deadening and non-warping. Its use eliminates warping, buckling wood lath.

Sheetrock—The Fireproof Wallboard

Made from rock, fire-proof. Cannot warp, shrink or buckle. Can be nailed or sawed like clear lumber. Requires no extra headers at chair rail, plate rail or picture mould. A unit material for walls and ceilings that is permanent.

Wall Plasters and Finishes

Are made of pure gypsum and are the world's recognized standards for every plastering purpose.

*Our Engineering Department is at your command
for consultation on estimates and building problems*

UNITED STATES GYPSUM COMPANY

World's Largest Producers of Gypsum Products

205 West Monroe Street

Chicago, Illinois

SALES OFFICES: New York, Buffalo, Boston, Washington, Philadelphia, Pittsburgh, Cleveland, Cincinnati, Detroit, Milwaukee, Minneapolis, St. Louis, Kansas City, Omaha, Denver, Los Angeles

LIST OF LICENSED ARCHITECTS

Members of the Profession who will be Permitted to Practice in the State of Illinois.


Every means has been used to get a correct List of Licensed Architects who are permitted to practice Architecture in the State of Illinois for the ensuing year. The names have been compared with the Official Records of the State of Illinois.

CHICAGO

- Aarens, Harry B., 3145 Edgewood Ave.
 Abbott, Frank B., 1649-140 S. Dearborn St.
 Ablamowicz, Sigmund V., 2937 N. Talman Ave.
 Ahlschlager, Walter W., 65 E. Huron St.
 Allen, Alfred P., 7501 N. Seeley Ave.
 Allen, James Roy, 64 E. Van Buren St.
 Allison, Lyman J., 115 S. Dearborn St.
 Almquist, Carl M., 118 N. La Salle St.
 Alschuler, Alfred S., 28 E. Jackson Blvd.
 Anderson, Helge A., 3116 Sunnyside Ave.
 Anderson, Pierce, 80 E. Jackson Blvd.
 Anderson, William C., 115 S. Dearborn St.
 Andresen, Theodore, 643 Barry Ave.
 Anis, Albert, 139 N. Clark St.
 Ansel, Anton, 5047 Cullom Ave.
 Apffelbach, Henry J., 2133 Fremont St.
 Archer, Chas. S., 6849 Dorchester Ave.
 Armstrong, John A., 127 N. Dearborn St.
 Aroner, Jacob S., 25 E. Jackson Blvd.
 Ashby, George William, 1511 W. Jackson Blvd.
 Ashby, Wilbert B., 1511 W. Jackson Blvd.
 Bailey, Cyrus, 28 E. Jackson Blvd.
 Bannister, George S., 115 S. Dearborn St.
 Barfield, William G., 58 W. Washington St.
 Bargman, Ewald F., 1408 Jarvis Ave.
 Barnes, Allen L., 1329 Birchwood Ave.
 Barrett, Fred L., 4354 N. Keeler Ave.
 Barthel, Bernard, 127 N. Dearborn St.
 Barton, F. M., 3426 S. Kedzie Ave.
 Baumeister, George E., 201 E. 70th St.
 Bean, Ralph H., 900 Wilson Ave.
 Beaudry, Ralph L., 7047 Princeton Ave.
 Beaumont, George, 25 N. Dearborn St.
 Beck, Willis J., 1221 Leland Ave.
 Beers, Herbert P., 53 W. Jackson Blvd.
 Behrns, Elmer F., 3429 N. Troy St.
 Beiler, Henry P., 1924 Waveland Ave.
 Bein, Maurice L., 501 S. Kilbourn Ave.
 Beman, Spencer S., 108 S. La Salle St.
 Bendus, William Quincy, 600-64 E. Van Buren St.
 Bennett, A. J. T., 38 S. Dearborn St.
 Bennett, Edward H., 1800-80 E. Jackson Blvd.
 Bennett, Wm. Arthur, 117 N. Dearborn St.
 Benson, Arthur E., 5520 Glenwood Ave.
 Benson, Edward, 5520 Glenwood Ave.
 Bentley, Harry H., 1124 Monroe Bldg.
 Bergmann, John, c/o Y. M. C. A. Hotel, 822 S. Wabash Ave.
 Berlin, Robert C., 19 S. La Salle St.
 Bernham, Felix M., 4630 Prairie Ave.
 Bernhard, Wilhelm, 138 N. La Salle St.
 Betts, Wm. B., 155 N. Clark St.
 Bialles, Theo. P., 3120 N. Kedzie Ave.
 Bicknell, Alfred H., 3801 N. Hoyne Ave.
 Bischof, Jacob H., 1324-10 S. La Salle St.
 Bishop, Thomas R., 35 S. Dearborn St.
 Bjork, David T., 5240 N. Sawyer Ave.
 Blondin, Edward A., 5 W. Garfield Blvd.
 Blourke, Pierce, 3323 W. Washington Blvd.
 Bodholdt, Arne, 137 S. La Salle St.
 Bollenbacher, J. C., 108 S. La Salle St.
 Booth, Herbert L., 722 Oakwood Blvd.
 Bouchard, Lewis C., 30 N. Dearborn St.
 Bounetheau, Harold D., 5152 Drexel Ave.
 Bourke, Robt. E., 10440 S. Seeley Ave.
 Bowen, Howard, 30 N. La Salle St.
 Bowes, Frederick Wm., 552 N. Pine Ave.
 Braband, Frank J. E., 901 Wrightwood Ave.
 Brabant, Gifford, 2717 N. Kedzie Ave.
 Brand, Herbert A., 1947-111 W. Washington St.
 Brandner, Louis T., 1432 Berteau Ave.
 Brandt, Berkeley, 30 N. Michigan Ave.
 Branitzky, Wm. Thomas, 64 W. Randolph St.
 Braucher, Ernest N., 6 N. Clark St.
 Braun, Isadore H., 19 S. La Salle St.
 Braun, Wm. T., 64 E. Van Buren St.
 Bright, Jasper T., 1507-139 N. Clark St.
 Bristle, Joseph H., 108 S. La Salle St.
 Britton, Frank, care Morris & Co., Arch'l Dept.
 Brown, Arthur George, 109 N. Dearborn St.
 Brown, Arthur V., 8 S. Dearborn St.
 Bruns, Benedict J., 1548 Belmont Ave.
 Brydges, E. Norman, 64 E. Van Buren St.
 Buck, Lawrence, 64 E. Van Buren St.
 Buck, Niels, 105 S. La Salle St.
 Buckett, Arthur C., 190 N. State St.
 Budina, Adolph Otto, 2753 Mildred Ave.
 Buerger, A. J., Jr., 4819 Gladys Ave.
 Bullock, Edwin C. A., 190 N. State St.
 Burnham, Daniel H., Jr., 209 S. La Salle St.
 Burnham, Hubert, 209 S. La Salle St.
 Burns, James, 64 W. Randolph St.
 Burt, Henry J., 1400-104 S. Michigan Ave.
 Byerly, Fred I., 11131 S. Irving Ave.
 Byrne, Francis B., 104 S. Michigan Ave.
 Cable, Max Lowell, 415 N. Western Ave.
 Cady, J. K., 179 W. Washington St.
 Caldwell, Will C., 1400-104 S. Michigan Ave.
 Camp, Ervin M., 4415 Malden St.
 Capraro, Alexander V., 72 W. Washington St.
 Carey, James L., 208 N. Laramie Ave.
 Carnegie, Wm. G., 189 W. Madison St.
 Carpenter, Martin R., 72 W. Washington St.
 Carr, George Wallace, 122 S. Michigan Ave.
 Cerny, Jerry J., 1444 S. Crawford Ave.
 Charles, Walter E., 913-155 N. Clark St.

2 PANES HIGH Y Height 3' 1 1/2" Z Height 3' 3 1/2"			
3 PANES HIGH Y Height 4' 0" Z Height 3' 3 1/2"			
4 PANES HIGH Y Height 4' 6" Z Height 3' 3 1/2"			
5 PANES HIGH Y Height 5' 0" Z Height 3' 3 1/2"			
6 PANES HIGH Y Height 5' 6" Z Height 3' 3 1/2"			
3 PANES WIDE Y Width 3' 2" Z Width 3' 8"		4 PANES WIDE Y Width 4' 2" Z Width 4' 10"	5 PANES WIDE Y Width 5' 2" Z Width 6' 0"

Y = 12" x 18" Glass Combine Y Widths with Y Heights
Z = 14" x 20" Glass Combine Z Widths with Z Heights



Glass Sizes—Ventilator lights which abut on the top or sides must be trimmed 1" along the abutting edge. Ventilator lights which abut on the sill must be trimmed 3/8" on the abutting edge. Any kind of glass from 1/8" to 3/8" can be used. Glazing clips furnished with the sash.

Fenestra Stock Sash for Service and Satisfaction

THE thirty types and sixty sizes of Fenestra Solid Steel Windows listed above are especially recommended for all types of industrial buildings.

They may be ordered for immediate shipment and in addition possess exclusive essential features that produce service and satisfaction.

The Joint—The patented interlocked Fenestra Joint retains 80% of the metal at the point of intersection.

The Butt—The External Adjustable Fenestra Butt is guarded against loosening by being double riveted through the sash bar and weathering. The mere turning of a nut allows ventilators to be adjusted into tight weathering contact.

Weathering—Fenestra has flat surface, double contact weathering which baffles air currents by turning them at right angles. Early makes of steel sash used curved weathering, or, at best, single contact.

Z-Bar Bracket—Fenestra Fittings don't come off. Both the Cam Latch and the Stay Oper-

ator are attached to the ventilator by a Z-Bar Bracket which is triple riveted to the sill of the ventilator. Made extra strong to stand extra stress put upon it.

The Cam Latch—The Fenestra Automatic Cam Latch locks the ventilator as it closes. It is fastened to the Z-Bar Bracket which is riveted to the sill of the ventilator. This latch is recognized as one of the biggest improvements in locking devices ever made for a steel sash.

T-Bar Mullion—T-Bar Mullions are used as standard equipment in combining two or more units of Fenestra. They assure good weathering and provide for variations in overall window dimensions. This is impossible where the old type narrow mullion is used.

For further information write for our catalog and set of installation details. Copies gladly sent on request.

DETROIT STEEL PRODUCTS COMPANY

Geo. P. Clayton, Manager

451-457 Conway Building

CHICAGO, ILLINOIS

Telephone—Main 2568-2569-2570

Large Stock of Sash Carried in Chicago Warehouse—Immediate Delivery

Fenestra
SOLID STEEL WINDOWS

Charvat, Anton, 2621 Millard Ave.
 Chase, Frank D., 645 N. Michigan Ave.
 Chatten, Melville C., 64 E. Van Buren St.
 Cheney, Howard Lovewell, 208 S. La Salle St.
 Childs, Frank A., 64 E. Van Buren St.
 Christenson, C. Werner, 1818 Greenleaf Ave.
 Christensen, John C., 3255 Evergreen Ave.
 Christiansen, Eli, 7047 Indiana Ave.
 Christie L. R., 2010 W. Van Buren St.
 Chubb, John D., 109 N. Dearborn St.
 Church, Walter S., 157 W. Division St.
 Clark, Edwin H., 8 E. Huron St.
 Clark, Leslie Doane, 6233 Greenwood Ave.
 Clark, Robert C., 7216 Harvard Ave.
 Clark, Wm. J., 4850 Blackstone Ave.
 Clay, William W., 538 S. Dearborn St.
 Cloyes, Frederick O., 400 S. Michigan Ave.
 Cobb, Wm. H., 2156 Sunnyside Ave.
 Coffin, Arthur S., 39 W. Adams St.
 Cohen, Isadore, 4933 Prairie Ave.
 Cohen, Joseph, 3937 W. 19th St.
 Colcord, Albert E., 6143 St. Lawrence Ave.
 Cole, Arthur W., 5413 Greenwood Ave.
 Coleman, John Nevin, 6257 St. Lawrence.
 Comm, Benjamin A., 3227 W. Division St.
 Cook, Norman W., 1283 Victor Ave.
 Coolidge, Charles A., 134 S. La Salle St.
 Coughlen, Gardner C., 127 N. Dearborn St.
 Crosby, Wm. S., 179 W. Washington St.
 Crowen, Samuel N., 400 N. Michigan Ave.
 Dalsey, H. I., 2321 W. North Ave.
 Darrell, George Chas., 7944 Burnham Ave.
 Davey, John Jeffery, 4440 N. Beacon St.
 Davidson, Frank E., 53 W. Jackson Blvd.
 Davis, Zachary T., 400 N. Michigan Ave.
 Dean, Arthur R., 137 S. La Salle St.
 De Golyer, Robt. S., 7 S. Dearborn St.
 De Money, Frank O., 5 N. La Salle St.
 Denell, Reuben A., 2248 Lunt Ave.
 Dennis, Charles A., 4031 Patterson Ave.
 Denson, James F., 5 N. La Salle St.
 Dewey, Charles, 4639 Prairie Ave.
 Dibelka, James B., 2743 W. 22nd St.
 Dillard, Frank G., 58 E. Washington St.
 Dinkelberg, Fred'k P., 400 N. Michigan Ave.
 Dippold, Albert P., 4747 Cottage Grove Ave.
 Doerr, Harold F., 11519 S. Irving Ave.
 Doerr, Jacob F., 105 N. Clark St.
 Doerr, W. Phillip, 105 N. Clark St.
 Doerr, Wm. P., Jr., 105 N. Clark St.
 Dornfeld, J. F., 2148 Washington Blvd.
 Dougherty, Floyd E., 35 N. Dearborn St.
 Dowling, Edward F., 6 N. Michigan Ave.
 Downton, Herbert E., 1340 N. Central Ave.
 Drummond, Wm. E., 10 S. La Salle St.
 Dublin, George H., 14 W. Washington St.
 Dublin, Henry, 14 W. Washington St.
 Duesing, Theodore, 6113 Dorchester Ave.
 Dunford, S. H., 38 S. Dearborn St.
 Dunning, N. Max, 310 S. Wabash Ave.
 Durkee, Arthur R., 6359 S. Peoria St.
 Dvorak, Jos., 3219 W. 22nd St.
 Dwen, Robert G., 8 E. Huron St.
 Dyer, Scott C., 38 S. Dearborn St.
 Eckstorm, Christian A., 5 N. La Salle St.
 Eich, George B., 39 S. State St.
 Eichberg, S. Milton, 64 W. Randolph St.

Ehmman, Wm. Frederick, 1461 Cullom Ave.
 Elmslie, Geo. C., 122 S. Michigan Ave.
 Erickson, Allan E., 105 W. Monroe St.
 Erickson, Carl A., 104 S. Michigan Ave.
 Ermeling, Ralph W., 64 E. Van Buren St.
 Eskridge, Fred A., 6654 Stewart Ave.
 Esser, Curt A., 1264 Montrose Ave.
 Esser, Paul F., 1304 Hood Ave.
 Ewer, Warren B., 1111 Ashland Ave.
 Fairclough, Stanley D., 7011 Jeffery Ave.
 Falls, Alexander S., 4408 Oakenwald Ave.
 Farrier, Clarence W., 5700 S. Peoria St.
 Faulkner, Chas. D., 140 S. Dearborn St.
 Fellows, Wm. K., 814 Tower Court.
 Ferrenz, Tirrell John, 5463 Ellis Ave.
 Fielder, Fred A., 4642 Woodlawn Ave.
 Filas, Thos. M., 15 E. Van Buren St.
 Finck, Sidney C., 1250 W. Madison St.
 Fischer, F. Wm., 9129 Commercial Ave.
 Fischer, John B., 140 S. Dearborn St.
 Fisher, Albert J., 2001 Greenleaf Ave.
 Fisher, Joseph G., 3804 Rokeby St.
 Fishman, M. Maurice, 118 N. La Salle St.
 Flaks, Francis A., 2743 W. 22nd St.
 Flesch, Eugene P., 5115 University Ave.
 Fletcher, Robert C., 179 W. Washington St.
 Flinn, Raymond W., 1412-8 S. Dearborn St.
 Flizikowski, John S., 3615 N. Harding Ave.
 Floto, Julius, 189 W. Madison St.
 Foehringer, Frederick, 2672 Orchard St.
 Fogel, R. W., 1839 Warner Ave.
 Foltz, Frederick C., 111 W. Washington St.
 Fortin, Joseph T., 600 Blue Island Ave.
 Foster, Arthur, 155 N. Clark St.
 Foster Winslow H., 9238 Pleasant Ave.
 Fournier, Lawrence A., 5417 Dorchester Ave.
 Fowler, Frank E., 750-332 S. Michigan Ave.
 Fox, Elmer J., 9209 University Ave.
 Fox, John J., 38 S. Dearborn St.
 Fox, William Paul, 38 S. Dearborn St.
 Foy, Wm. D., 1400-104 S. Michigan Ave.
 France, Roy F., 155 N. Clark St.
 Francisco, Ferris Le Roy, 39 S. La Salle St.
 Franklin, Robert L., 64 E. Van Buren St.
 Franzheim, H. Kenneth, 127 N. Dearborn St.
 Frazier, Clarence E., 30 N. Dearborn St.
 Friedl, Herman, 154 W. Randolph St.
 Friedman, Raphael N., 521 E. 60th St.
 Frodin, Rube S., 815-30 N. Michigan Ave.
 Frommann, Emil H., 64 W. Randolph St.
 Frost, Charles S., 105 S. La Salle St.
 Frost, Harry Talfourd, 1800 Railway Exch.
 Fry, Frank L., 140 S. Dearborn St.
 Fugard, John Reed, 212 E. Superior St.
 Fullenwider, Arthur E., 6 N. Michigan Ave.
 Fuller, Alex. A., 816 E. Marquette Rd.
 Fuller, Ravilo Franklyn, 1001 N. Dearborn.
 Furst, Wm. H., 140 S. Dearborn St.
 Garden, Hugh M. G., 104 S. Michigan Ave.
 Gardner, Horace C., 140 S. Dearborn St.
 Garnsey, Geo. O., 802-25 N. Dearborn St.
 Gassmann, Andrew P., 143 N. Lorel Ave.
 Gatterdam, Fred E., 154 W. Randolph St.
 Gauger, Wm., 36 W. Randolph St.
 Gaul, Hermann, 111 W. Washington St.
 Gerber, Arthur U., 20 W. Jackson Blvd.
 Gerhardt, Paul, 64 W. Randolph St.
 Gibb, William R., 117 N. Dearborn St.

Union Insulating and Construction Co.

Great Northern Company, Chicago

S. E. McPARTLIN
President

J. H. BRACKEN
Secretary

E. S. MAIN
Treasurer

Contractors for Corkboard Insulation for every type
of refrigerated building



Refrigerator Installed for Horn & Hardart Co., Chicago

Contractors for built-in refrigerators of every type in Hotels, Restaurants
Provision Houses, Hospitals, Public Institutions and Residences

These refrigerators are built in our shop in Chicago, are designed by Engineers
and insulated with Corkboard. They give the best of service
and are reasonable in price

South Deadening Felts for Homes and Apartments

Insulating Wall Boards, for painting or for plastering and for sound
deadening. Excellent in insulating value and low in price

*Members of this firm have specialized in
Heat and Cold Insulation for Twenty Years*

Estimates and sketches cheerfully furnished Telephone Harrison 1848

Gibson, Bayard K., 608 S. Dearborn St.
 Goodman, Wm. C., 2932 W. Adams St.
 Gormley, Jas. R., 3555 Ainslee St.
 Graham, Ernest R., 80 E. Jackson Blvd.
 Granger, Alfred H., 619 N. Michigan Ave.
 Graven, Auker S., 917 Windsor Ave.
 Green, Herbert H., 308 S. Wabash Ave.
 Greenfield, Geo. H., 4431 Berkeley Ave.
 Greengard, Bernhard C., 619 N. Michigan Ave.
 Gregori, Raymond, 1236 Eddy St.
 Griesser, Richard, 64 W. Randolph St.
 Griffin Walter B., 175 W. Jackson Blvd.
 Griser, Keith L., 2109 Leland Ave.
 Grotz, Chas. J., 3514 Wrightwood Ave.
 Grussing, George H., 154 W. Randolph St.
 Gubbins, Wm. F., 4059 W. Monroe St.
 Guenzel, Louis, 111 W. Washington St.
 Gurnee, Daniel S., 1426 E. 67th Pl.
 Haagen, Paul T., 155 N. Clark St.
 Hagerup, Leonard O., 1462 Carmen Ave.
 Hall, E. Stanford, 64 E. Van Buren St.
 Hall, Eric E., 123 W. Madison St.
 Hall, Lincoln N., 5251 Winthrop Ave.
 Hallberg, L. G., 116 S. Michigan Ave.
 Halperin, Casriel, 19 S. La Salle St.
 Hamilton, John L., 814 Tower Court.
 Hammond, Charles H., 64 E. Van Buren.
 Hanna, John Paul, 111 W. Washington St.
 Hanselmann, Herman, 57 W. Delaware Pl.
 Hansen, Christian O., 1037 N. Dearborn St.
 Hansen, Gunnard A., 7915 Evans Ave.
 Hansen, Harald M., 112 N. La Salle St.
 Hansen, Paul, 830 Lawrence Ave.
 Happell, Otto Gottlieb, 568 Arlington Pl.
 Harlev, William H., Jr., 117 N. Dearborn St.
 Harris, Mandel H., 1533 S. Central Park.
 Harris, Ralph W., 190 N. State St.
 Hartigan, W. B., 22 S. Albany Ave.
 Harvey, George L., 105 S. Dearborn St.
 Hatzfeld, Clarence, 7 S. Dearborn St.
 Hauber, Carl, 10 S. La Salle St.
 Hawk, A. T., 714 La Salle St., R. R. Station.
 Hawkinson, Carl W., 108 S. La Salle St.
 Hecht, Albert S., 225 E. Erie St.
 Hegsted, Martin A., 3725 Belden Ave.
 Heimbeck, Walter C., 1736 W. 102nd St.
 Heinz, Lorenz H., 128 N. La Salle St.
 Henschien, H. Peter, 37 W. Van Buren St.
 Herter, John T., 4738 Woodlawn Ave.
 Hetherington, John T., 38 S. Dearborn St.
 Hetherington, Murray D., 38 S. Dearborn St.
 Hettinger, John P., 4708 Dover St.
 Heun, Arthur, 64 E. Van Buren St.
 Hild, Edward G., 30 E. Ontario St.
 Himelblau, A. L., 179 W. Washington St.
 Hine, Cicero, 3221 Broadway.
 Hirschfeld, Leo S., 139 N. Clark St.
 Hocke, John, 836 64th Pl.
 Hodgdon, Charles, 134 S. La Salle St.
 Hodgdon, Frederick M., 1409 Greenleaf.
 Hoffman, Wm. L., Jr., 144 W. 47th St.
 Hogenson, Edward A., 5818 Magnolia Ave.
 Holabird, John Augur, 104 S. Michigan Ave.
 Holabird, Wm., 104 S. Michigan Ave.
 Holmboe, Leonard C. B., 2034 E. 72nd St.
 Holmes, Harold, 151 E. Chicago Ave.
 Holmes, Morris G., 8 S. Dearborn St.
 Holsman, Henry K., 310 S. Wabash Ave.
 Hooper, Wm. F., 2721 S. Michigan Ave.
 Horwich, Louis J., 6150 Greenview Ave.
 Hoskins, John M., 2837 W. Madison St.
 Hosmer, Clare C., 133 W. Washington St.
 Hotton, B. J., 1113 Drummond Pl.
 Howell, Leslie D., 1446 Jarvis Ave.
 Hubbard, Bert Charles, 225 N. Michigan Ave.
 Hubbard, Willis W., 1710 Greenleaf Ave.
 Huber, Julius H., 2039 Greenleaf Ave.
 Hughes, Andrew F., 7012 Eggleston Ave.
 Hulla, John, 140 S. Dearborn St.
 Hunt, Jarvis, 30 N. Michigan Ave.
 Hussander, Arthur F., 25 N. Dearborn St.
 Huston, Sanford K., Jr., 5468 Woodlawn
 Hyde, Robert M., 8 S. Dearborn St.
 Hyland, Paul V., 159 E. Ontario St.
 Ingalls, Arthur R., 7207 Yale Ave.
 Ingram, Horace, 5718 Kenwood Ave.
 Isensee, Frederic M., 6417 Minerva Ave.
 Jacobs, Arthur, 138 N. La Salle St.
 Jeckel, Philip F., 569 Arlington St.
 Jenkins, A. D., 6 N. Michigan Ave.
 Jensen, Clarence A., 310 S. Wabash Ave.
 Jensen, Elmer C., 39 S. La Salle St.
 Jensen, Jens J., 4815 N. Lawndale Ave.
 Jillson, B. H., 9111 S. Robey St.
 Jobson, C. Frank, 225 N. Michigan Ave.
 Johnck, Frederick, 140 S. Dearborn St.
 Johnson, Carl J., 5135 Bernard St.
 Johnson, Oscar, 4937 N. Talman Ave.
 Johnson, Robert V., 6809 N. Hillsdale Ave.
 Johnston, William K., 6805 Yale Ave.
 Johnstone, Percy T., 1254 Pratt Blvd.
 Jones, Wm. C., 19 S. La Salle St.
 Joy, Samuel Scott, 2001 W. 39th St.
 Kallal, Chas. W., City Hall.
 Kallenbach, Henry, Jr., 3428 N. Hamilton Ave.
 Kane, Robert L., 6643 Stewart Ave.
 Kilroy, John G., 112 W. Adams St.
 Kingsley, George S., 109 N. Dearborn St.
 Kirkpatrick, Robert A., 3966 Lake Park Ave.
 Klafter, David Saul, 64 W. Randolph St.
 Klafter, Joseph H., 849 Lawrence Ave.
 Klamt, Edward A., 304 S. Wabash Ave.
 Klein, Wm. J., 111 W. Washington St.
 Klewer, Arthur, 4507 Dover St.
 Klewer, Geo. W., 1005-5 N. La Salle St.
 Knapp, George Arnold, 212 E. Superior St.
 Knox, Arthur H., 7 W. Madison St.
 Knudsen, Johan F., 5122 Hutchinson St.
 Kocher, Jacques J., 6250 S. Halsted St.
 Koenig, Fred, 2252 Clifton Ave.
 Koenigsberg, Nathan, 8 S. Dearborn St.
 Kohfeldt, Walter G., 400 N. Michigan Ave.
 Koll, Henry C., 2155 Elston Ave.
 Koster, John L., 725 E. 50th St.
 Kramer, William F., 400 N. Michigan Ave.
 Krause, Edmund R., 22 W. Monroe St.
 Kuehne, Carl Oskar, 1572 N. Halsted St.
 Kupfer, Otto A., 1865 Millard Ave.
 Kurzon, Bernard R., 916 Lakeside Pl.
 Lagergren, Gustav P., 7708 S. Hermitage Ave.
 Laist, Theodore F., 7411 Greenview Ave.
 Lampe, Clarence W., 155 N. Clark St.



PUCKEY & JENKINS, Architects

MIDLAND TERRA COTTA

"because we take more pains"

MIDLAND TERRA COTTA COMPANY

Chamber of Commerce Building

CHICAGO, ILLINOIS

Land, Herbert Henry, 5410 Cortez Ave.
 Lang, Albert, 7 W. Madison St.
 Langille, Louis E., 1657 Juneway Tr.
 Larmon, Philip, care Libby, McNeil & Libby.
 Lautz, William H., 64 E. Van Buren St.
 Lawrence, Albin, 123 W. Madison St.
 Laver, Robert, 19 S. La Salle St.
 Leavell, John C., 6047 Kimbark Ave.
 Ledebuhr, Arthur E., 6447 Rhodes Ave.
 Lehle, Louis, 3810 Broadway.
 Lenske, Charles H., 3755 Irving Park Blvd.
 Leviton, Morton, 53 W. Jackson Blvd.
 Levy, Alexander L., 111 W. Washington St.
 Lewin, Edw. P., 919 S. Irving Ave.
 Lewis, Jacob, 5712 Indiana Ave.
 Lewis, Le Roy, Jr., 104 S. Michigan Ave.
 Lieberg, Hugo J., 154 W. Randolph St.
 Lindblad, Alfred G., 2349 S. Clifton Park Ave.
 Lindquist, Frederick, 179 W. Washington.
 Lindquist, Joseph B., 3923 Grand Blvd.
 Lindstrand, John A., 800 N. Clark St.
 Lindstrom, R. S., 15 E. Van Buren St.
 Liska, Charles O., 9601 Prospect Ave.
 Liska, Emil, 9601 Prospect Ave.
 Llewellyn, Joseph C., 38 S. Dearborn St.
 Llewellyn, Ralph C., 38 S. Dearborn St.
 Loewenberg, Israel S., 111 W. Monroe St.
 Lonek, Adolph, 1867 S. Avers Ave.
 Lorenc, Joseph A., 6712 Imlay St.
 Lovdall, Geo. F., 25 N. Dearborn St.
 Lovell, Sidney, 30 N. Michigan Ave.
 Lovell, McDonald, 30 N. Michigan Ave.
 Lowe, Elmo C., 108 S. La Salle St.
 Ludgin, J. G., 53 W. Jackson Blvd.
 Luebker, Otto, 643 Wellington Ave.
 Lund, Anders G., 453 W. 63rd St.
 Lurvey, Louis, 721 S. Western Ave.
 MacBride, E. Everett, 64 E. Van Buren St.
 Mahaffey, David, 118 N. La Salle St.
 Maher, George W., 157 E. Erie St.
 Maher, Harry E., 6611 Minerva Ave.
 Maher, Philip Brooks, 157 E. Erie St.
 Maiwurm, Arthur B., 82 W. Washington St.
 Marley, Joseph J., 2959 W. 39th St.
 Mallinger, John, 3626 N. Racine Ave.
 Mann, William D., 155 N. Clark St.
 Marienthal, Oscar B., 5124 University Ave.
 Marshall, Benj. H., 721 N. Michigan Ave.
 Martin, Edgar D., 104 S. Michigan Ave.
 Martin, Edwin D., 5 N. La Salle St.
 Martini, Elisabeth A., 155 N. Clark St.
 Marx, Sam'l A., 1336 N. Washington Blvd.
 Matteson, Victor Andree, 944 Leland Ave.
 Maurer, Wm., 2426 Augusta St.
 Mayer, Carl H., 1447 Balmoral Ave.
 Mayo, Ernest A., 53 W. Jackson Blvd.
 McArthur, Albert Chase, 39 W. Adams St.
 McCarthy, Charles A., 5174 Indiana Ave.
 McCarthy, Jos. W., 139 N. Clark St.
 McClellan, Edward G., 7439 Cottage Grove Ave.
 McCouley, Charles H., 1905 Am. Trust Bldg.
 McDonald, Luther Wilson, 849 E. 73rd St.
 McDougall, Walter A., 7006 South Park Ave.
 McGavick, J. P., 1036 E. 46th St.
 McGrath, Paul J., 845 Lakeside Pl.
 McLane, Cyrus D., 127 N. Dearborn St.
 McLaren, Robert J., 37 W. Van Buren St.
 McLaughlin, Daniel F., 2118 E. 73rd St.
 McMurry, Oscar L., 10405 S. Seeley Ave.
 Meldahl, Jens J., 104 S. Michigan Ave.
 Meles, Edmund J., 1048 N. Springfield Ave.
 Meredith, Davis D., 4819 N. Albany Ave.
 Meyer, Frederic H., 30 N. Dearborn St.
 Michaelsen, C. S., 3815 W. Congress St.
 Miller, Grant C., 6 N. Michigan Ave.
 Miller, H. Clyde, 112 W. Adams St.
 Miller, John W., 1650 Carmen Ave.
 Miller, Jos. A., 155 N. Clark St.
 Miller, Lee, 109 N. Dearborn St.
 Miller, Walter F., 50 E. Walton Pl.
 Miller, Wm. C., 204 N. Karlov Ave.
 Milman, Ralph E., 108 S. La Salle St.
 Minchen, Sidney H., 19 E. Jackson Blvd.
 Mohr, Frederick J., 721 N. Michigan Ave.
 Monaco, Armand R., 721 N. Michigan Ave.
 Morehouse, Merritt J., 343 S. Dearborn St.
 Morey, Arthur G., 4740 Hamilton Ave.
 Morgan, Charles L., 104 S. Michigan Ave.
 Morrison, James R. M., 64 W. Randolph St.
 Morphet, Archibald S., 6018 Harper Ave.
 Morrow, Archibald Wm., 105 W. Monroe St.
 Morsé, Harry Leon, 2639 W. Potomac Ave.
 Mosher, E. Bradford, 5830 Harper Ave.
 Mrazek, Joseph M., 1239 S. Tripp Ave.
 Mueller, Carl Oscar, 752 Buena Ave.
 Mueller, Herbert E., 3752 Rokeby St.
 Mulder, Herman A., 1702-140 S. Dearborn St.
 Mullay, Thomas H., 550 Surf St.
 Mundie, Wm. Bryce, 39 S. La Salle St.
 Nadherny, Joseph J., 38 S. Dearborn St.
 Nathan, Myer O., 30 N. La Salle St.
 Neebe, John, 2522 Aubert Ave.
 Nelson, Edward O., 1401-39 S. La Salle St.
 Nelson, Melvin A., 2612 Eastwood Ave.
 Nettenstrom, Joel W., 2425 Canton St.
 New, Matthew, 2514 E. 91st St.
 Newberry, Robert T., 1401 Astor St.
 Newbold, Roy E., 2457 Sunnyside Ave.
 Newhouse, Henry L., 4630 Prairie Ave.
 Newman, Edgar M., 107 N. Clark St.
 Nicholson, Jos. T., 7514 Chappel Ave.
 Nicholson, Wm. A., 6437 Harvard Ave.
 Nielsen, C., 1853 Greenleaf Ave.
 Nielsen, Elker Rosehill, 3059 Augusta St.
 Niemz, Arthur R., 847 Bradley Pl.
 Nimmons, George C., 122 S. Michigan Ave.
 Nitsche, Edward A., 64 E. Van Buren St.
 Norman, A. E., 1531 Devon Ave.
 Novy, Jos. J., 2434 Ridgeway Ave.
 Nyden, John A., 190 N. State St.
 Odgers, Phillip, 5913 E. Circle Ave.
 Ohlhaber, Wm., 6 N. Michigan Ave.
 Ohrenstein, Ernest J., 30 E. Ontario St.
 Oldefest, Edw. G., 66 E. Elm St.
 Oliver, Ralph H., 115 S. Dearborn St.
 Olsen, Leif E., 1615-155 N. Clark St.
 Olsen, Paul F., 127 N. Dearborn St.
 Olson, Benjamin Franklin, 19 S. La Salle St.
 Ording, Carl Henry, 1732 S. Michigan Ave.
 Ostergren, Robert C., 155 N. Clark St.
 Otis, Samuel Shockford, 6 N. Michigan Ave.
 Otis, Wm. A., 6 N. Michigan Ave.
 Packard, Allyn A., 7609 Eastlake Terrace.
 Pagels, Wm. F., 1412 Berteau Ave.



PERMANENT CLEANLINESS

Vitrolite's inherent qualities make it the preferred material for toilet partitions and wainscoting. Its hard, non-absorbent surface is impervious to stains and acids. Its pure lustrous whiteness is kept so with the minimum labor. No other material we know of approaches it in sanitation and lasting beauty.

Our sincere co-operation is at your call without obligation.

When writing ask for a copy of "Vitrolite."

THE VITROLITE COMPANY

618 Chamber of Commerce Building

CHICAGO, ILLINOIS

VITROLITE

"Better than Marble"

Park, John W., 817 N. Dearborn St.
 Parsons, Wm. Edward, 80 E. Jackson Blvd.
 Pashley, Alfred F., 431 S. Dearborn St.
 Patelski, Erich J., 2550 W. Jackson Blvd.
 Pearson, Gustav E., 1930 N. Keystone Ave.
 Perkins, Dwight Heald, 814 Tower Court.
 Perkins, Frank W., 7419 Stewart Ave.
 Perkins, Fred'k W., 64 E. Van Buren St.
 Perry, Walter E., 212 E. Superior St.
 Peterson, Stanley M., 4509 N. Paulina St.
 Pierce, Richard Gordon, 10 S. La Salle St.
 Piongrey, Roy E., 209 S. La Salle St.
 Piontek, Clement L., 3446 School St.
 Pischel, Frederick, 4451 N. Paulina St.
 Plains, Leo H., 544 S. Franklin St.
 Pomeroy, Jim T., 4921 N. Kedzie Ave.
 Pond, Allen Bartlit, 64 E. Van Buren St.
 Pond, Irving K., 64 E. Van Buren St.
 Pope, John Francis, 3227 W. Van Buren St.
 Poulsen, Edward J., 4019 N. Harding Ave.
 Poulsen, George F., 1374-208 S. La Salle St.
 Powers, Horace S., 5 N. La Salle St.
 Prather, Fred V., 400 N. Michigan Ave.
 Presto, Wm. C., 179 W. Washington St.
 Fridmore, John E. O., 38 S. Dearborn St.
 Prindiville, Chas. H., 58 E. Washington St.
 Probst, Edward, 80 E. Jackson Blvd.
 Proskauer, Adolph, 201 E. Ontario St.
 Pruyn, Wm. H., 122 S. Michigan Ave.
 Puckey, F. W., 6 N. Michigan Ave.
 Pugh, Myron E., 2915 Jackson Blvd.
 Quackenboss, Leonard G., 35 N. Dearborn.
 Quinn, James Edwin, 123 W. Madison St.
 Quitsow, Anthony H., 1036 Dakin St.
 Rabig, Charles E. Klari, 1361 E. 64th St.
 Raeder, Henry, 20 W. Jackson Blvd.
 Rapp, C. W., 190 N. State St.
 Rapp, Geo. L., 190 N. State St.
 Rappaport, Benjamin J., 6709 Lakewood Ave.
 Ratcliffe, H. E., 123 W. Madison St.
 Rawson, Chas. P., 1900 Ainslee St.
 Rawson, Lorin A., care C. H. Strong & Co.,
 180 N. Market St.
 Rebori, A. N., 410 S. Michigan Ave.
 Reed, Earl Howell, Jr., 108 N. Dearborn St.
 Reilly, S. L., 112 W. Adams St.
 Renwick, Edward A., 104 S. Michigan Ave.
 Repp, George W., 1743 W. 100th Pl.
 Reuter, Herman A., 45 N. Euclid Ave.
 Rezny, James B., 2202 S. Crawford Ave.
 Rice, Josiah L., 4213 N. Ashland Ave.
 Rich, Evert, 10420 Prospect Ave.
 Richards, H. H., 5467 Washington Blvd.
 Riddle, Herbert H., 122 S. Michigan Ave.
 Riddle, Lewis W., 122 S. Michigan Ave.
 Rinn, Charles, 3041 Leland Ave.
 Rippel, Fred O., 140 S. Dearborn St.
 Rissman, Maurice B., 139 N. Clark St.
 Ritter, Louis E., 1707 Marquette Bldg.
 Roberts, Eben E., 82 W. Washington St.
 Robertson, D., 8 S. Dearborn St.
 Robinson, Argyle E., 5227 Harper Ave.
 Robinson, Harry F., 137 S. La Salle St.
 Roche, Martin, 104 S. Michigan Ave.
 Roeddiger, F. W. C., 4936 Champlain Ave.
 Rognstad, Sigurd A., 3815 W. Congress St.
 Rohm, Jean Baptist, 138 N. La Salle St.
 Rohm, Wm., 138 N. La Salle St.
 Roller, Herman D., 64 E. Van Buren St.
 Root, John Wellborn, 104 S. Michigan Ave.
 Ross, Henry, 6741 Sheridan Road.
 Roth, Edgar, 7550 Saginaw Ave.
 Rother, Eugene Paul, 2507 N. Cullom Ave.
 Rouleau, Arthur, 4004 W. Van Buren St.
 Rowe, Charles Barr, 5510 Ingleside Ave.
 Roy, Franz, 7817 S. Shore Drive.
 Runde, Otto, 4831 Barry Ave.
 Rupert, Edward P., 154 W. Randolph St.
 Ruttenberg, Albert, 82 W. Washington St.
 Russell, Lewis E., 25 N. Dearborn St.
 Rusy, Anthony F., 1339 S. Avers Ave.
 Ryan, William, Jr., 154 W. Randolph St.
 Sailor, Homer G., 417 W. 61st St.
 Salisbury, Robert H., 118 N. La Salle St.
 Sandegren, Andrew R., 116 E. Oak St.
 Sandel, Monroe R., 1255 Elmdale Ave.
 Sanders, Lewis Miles, 3311 Wrightwood Ave.
 Saxe, Albert Moore, 64 E. Van Buren St.
 Saxe, Ira C., 351 Belden Ave.
 Schaffner, Daniel J., 139 N. Clark St.
 Schaub, Louis J., 3305 Wrightwood Ave.
 Scheller, Jesse E., 7606 Crandon Ave.
 Schenck, Rudolph, 122 S. Michigan Ave.
 Schimek, Alfred F., 1420 S. Ashland Ave.
 Schlacks, Henry John, 721 N. Michigan.
 Schmalz, Emil C., 5041 W. Madison St.
 Schmid, Richard G., 154 W. Randolph St.
 Schmidt, Frederic B., 7 S. Dearborn St.
 Schmidt, Hugo, 1165 N. Clark St.
 Schmidt, Richard Ernest, 104 S. Michigan.
 Schnakenberg, Henry, 3042 N. Keating Ave.
 Schneberger, John G., 2320 S. Trumbull Ave.
 Schock, Frederick R., 5804 Midway Park.
 Schoenfeldt, Frank, 4058 W. Madison St.
 Schreiber, Geo. F., 105 W. Monroe St.
 Schultz, Martin M., 1955 W. 20th St.
 Schulze, Carl Elliott, 1511 W. Jackson Blvd.
 Schulze, William, 2009 W. North Ave.
 Schwartz, Albert A., 118 N. La Salle St.
 Seator, Sinclair M., 35 N. Dearborn St.
 Seipp, Edwin A., 179 W. Washington St.
 Sexton, Frank A., 7 W. Madison St.
 Seyfarth, Robert E., 134 S. La Salle St.
 Shankland, Edward Clapp, 209 S. La Salle.
 Shannon, James S., 740, 608 S. Dearborn St.
 Shattuck, Walter F., 19 S. La Salle St.
 Shaw, H. Van Doren, 39 S. State St.
 Sheldon, Karl H., 400 N. Michigan Ave.
 Sierks, Henry, 117 N. Dearborn St.
 Sillani, Muzio, 2511 N. Clark St.
 Sladek, Victor R., 2242 S. Marshall Blvd.
 Slocombe, E. Harvey F., 2711 N. Kedzie Ave.
 Slovynec, John, 5138 S. Artesian Ave.
 Slupkowski, Joseph A., 1263 N. Paulina St.
 Smith, Geo. H., 415-37 W. Van Buren St.
 Smith, Robert S., 111 W. Monroe St.
 Smith, Wm. Jones, 64 E. Van Buren St.
 Smith, Z. Erol, 305 E. 55th.
 Soderberg, Andrew F., 7211 Harvard Ave.
 Sosna, Ned Irving, 3147 Argyle St.
 Spencer, Charles B., 37 W. Van Buren St.
 Spencer, Nelson S., 37 W. Van Buren St.
 Spencer, R. C., Jr., 5 N. La Salle St.
 Speyer, Oscar P., 6507 Greenview St.
 Spitz, Alexander H., 19 W. Jackson Blvd.
 Spitzer, Maurice, 115 S. Dearborn St.



As Good as New

*Residence of Edward
Watts, Des Moines, Ia.
Vorse, Kraetsch &
Kraetsch, Architects.
Chas. Weitz Sons,
General Contractors.*



FRESH and bright as if finished yesterday—but this attractive home was built five years ago. What's the secret?

Notice the mortar joints. They're as clean-cut and white as the day they were laid. And the flower vases, trim and spotless, play their part.

Medusa Stainless Waterproofed White Cement—that's the answer. Face brick laid in that material was specified by the architects, Messrs. Vorse, Kraetsch & Kraetsch of Des Moines. The foundation walls were back-plastered with cement waterproofed with Medusa Waterproofing Paste. The work was done by Chas. Weitz Sons, Contractors.

The stainless quality and permanence of Medusa products recommend them to architects and builders of fine structures. We'll gladly aid in making up the cement specifications. The Medusa Cement booklet describes the products fully.

THE SANDUSKY CEMENT COMPANY
Dept. A. Cleveland, Ohio

Spohr, George S., 1538 Greenfield Ave.
 Stanhope, Leon, 59 E. Madison St.
 Stanton, Frederick C. H., 621 Cornelia Ave.
 Steif, Benjamin L., 30 N. La Salle St.
 Steigley, Arthur, 21 N. La Salle St.
 Steinbach, J. G., 155 N. Clark St.
 Steinborn, Edward, 155 N. Clark St.
 Stephens, Burret H., 37 W. Van Buren St.
 Stern, Isaac S., 35 S. Dearborn St.
 Steuben, Theo., 1331 Newport Ave.
 Stevens, Chas. Whitney, 64 W. Randolph St.
 Stevens, Harry E., 4231 W. Monroe St.
 Stoetzel, Ralph E., 431 S. Dearborn St.
 Stone, John R., 8 S. Dearborn St.
 Strandel, Charles A., 118 N. La Salle St.
 Strauch, Moriz F., 1356 Diversey Parkway.
 Stuhr, Wm., 127 N. Dearborn St.
 Sturges, Howard P., 79 W. Monroe St.
 Sturm, Meyer J., 116 S. Michigan Ave.
 Sturnfield, Chas. H., 600 Blue Island Ave.
 Sullivan, Louis H., 1808 Prairie Ave.
 Swern, Perry W., 19 S. La Salle St.
 Taggart, John A., 19 S. La Salle St.
 Tallmadge, Thos. E., 189 W. Madison St.
 Teesdale, Lawrence V., 6949 Prairie Ave.
 Teich, Frederick J., 305 S. La Salle St.
 Teisen, Axel Valdemar, 4804 N. Kedzie Ave.
 Teutsch, Carl M., 2448 Calumet Ave.
 Thielbar, Frederick J., 1400-104 S. Michigan Ave.

Thislew, Charles, 4431 N. Paulina St
 Thomsen, Frederick W., 1949 Seminary Ave.
 Thoresen, Thorgils, 4231 Lake Park Ave.
 Thorud, Bert M., 3340 Wilson Ave.
 Tilton, John Neal, 5 N. La Salle St.
 Tocha, Anton A., 1225 N. Ashland Ave.
 Trowbridge, Raymond W., 4711 N. Albany Ave.
 Turbyfill, David W. T., 3760 Sheffield Ave.
 Turner, John W., 2103 Turner Ave.
 Tyson, Herbert, 325 N. Mason Ave.
 Urbain, Jules, Jr., 155 N. Clark St.
 Uffendell, William G., 39 S. State St.
 Underhill, Harold W., 711 E. 50th St.
 Urbanek, Chas. A., 1423 S. Avers Ave.
 Vade, Louis Henri, 216 S. Michigan Ave.
 Valerio, Francis M., 600 Blue Island Ave.
 Van Guilder, Arthur, 6552 Normal Ave.
 Van Gunten, Orlando, 800 N. Clark St.
 Varney, Ralph W., 105 S. La Salle St.
 Vedra, Charles, 4107 W. 21st Place
 Vesely, William J., 240 E. Huron St.
 Viehe-Naess, Ivar, 400 N. Michigan Ave.
 Vigeant, Xavier, 1336 W. Washington Blvd.
 Viker, Guttorm A., 4700 N. Campbell Ave.
 Vittner, Clement, 2420 S. Clifton Park Ave.
 Vitzthum, Karl M., 21 E. Van Buren St.
 Von Holst, Herman V., 72 W. Adams St.
 Wach, Edward F., 5338 S. Rockwell St.
 Waful, Edward E., 140 S. Dearborn St.
 Walcott, Chester H., 8 E. Huron St.
 Walcott, Russell S., 8 E. Huron St.
 Walker, Frank Chase, 20 W. Jackson Blvd.
 Walker, Fred G., 72 W. Adams St.
 Wall, Richard J., 2330 N. Halsted St.
 Wallace, Dwight G., 6 N. Clark St.
 Wallace, Maurice R., 1264 N. Lincoln St.
 Walter, Wayne M., 4730 Malden Ave.
 Warren, Wm. A., 10 S. La Salle St.

Waterman, Harry Hale, 10 S. La Salle St.
 Watson, Vernon S., 189 W. Madison St.
 Weber, Alfred P., 155 N. Clark St.
 Weber, Peter J., 343 S. Dearborn St.
 Weisfeld, Leo H., 133 W. Washington St.
 Weiss, John W., 53 W. Jackson Blvd.
 Wheeler, Chas. F., 4635 N. Kenton Ave.
 Wheelock, Harry B., 64 W. Randolph St.
 White, Chas. E., Jr., 343 S. Dearborn St.
 White, Howard J., 1417-80 E. Jackson Blvd.
 White, Kesson, 4321 S. Michigan Ave.
 Whitney, Wm. P., 122 S. Michigan Ave.
 Wiener, Jerome L., 4107 Grand Blvd.
 Williamson, Robert B., 19 S. La Salle St.
 Williamson, W. G., 19 S. La Salle St.
 Willson, Samuel H., 22 W. Monroe St.
 Wilmanns, August C., 35 S. Dearborn St.
 Winslow, Benj. E., 2617 N. Richmond St.
 Witherspoon, John M., 53 W. Jackson Blvd.
 Wittekind, Henry Jr., 1749 Jarvis Ave.
 Woerner, Adolph, 3166 Lincoln Ave.
 Woerner, Adolph, Jr., 4210 N. Lincoln Ave.
 Wolff, R. G., 7 W. Madison St.
 Woltersdorf, Arthur F., 138 N. La Salle St.
 Woodyatt, Ernest, 1045-209 S. La Salle St.
 Work, Robert G., 220 S. Michigan Ave.
 Works, William, 619 N. Michigan Ave.
 Worthmann, Henry, 155 N. Clark St.
 Wright, Clark C., 122 S. Michigan Ave.
 Wright, Wm. Campbell, 721 N. Michigan Ave.
 Wyeth, Walter H., 1124, 104 S Michigan Ave.
 York, J. Devereux, 1323 N. Clark St.
 Youngberg, J. E., 30 N. Dearborn St.
 Zaldokas, Mathew E., 1263 N. Paulina St.
 Zarbell, Iver C., 4132 Ellis Ave.
 Zarnowiecki, Joseph Corwin, 1859 W. Chicago Ave.
 Zidek, Jos., 4021 W. North Ave.
 Zimmerman, W. Carlys, 64 E. Van Buren
 Zimmerman, Ralph W., 64 E. Van Buren St.
 Zimmerman, Hugo H., 914 Waveland Ave.
 Zook, R. Harold, 1538 E. 61st St.

COOK COUNTY OUTSIDE OF CHICAGO

CICERO

Houda, Joseph F., 2523 S. 56th Court

CHICAGO HEIGHTS

Kelley, Irving W., 1536 Otto Blvd.

DES PLAINES

Winsauer, Louis M.

EVANSTON

Andrews, Alfred B., 847 Forest Ave.
 Ayars, Chas. A., 2419 Lincoln Ave.
 Blake, Edgar O., 802 Davis St.
 Markel, Charles H., 608 Sherman Ave.
 McCall, Thomas, 843 Ridge Ave.
 Saenger, Louis P., 2327 Park Pl.
 Small, John S., 748 Hinman Ave.
 Wright, Harvey, 2711 Woodbine Ave.

FOREST PARK

Bessler, Edw. W., 504 Marengo Ave.
 Burtar, Adolph G., 7616 Madison St.



Kawneer

SIMPLEX
REVERSIBLE WINDOW
FIXTURES

MADE OF SOLID BRONZE

50%

Saving

on

Window Up-Keep

Sash Equipped with Kawneer-Simplex Reversible Fixtures are easily cleaned from within—a most desirable feature for HOTELS and APARTMENTS.

SOLID BRONZE CONSTRUCTION

Assures Satisfactory Service

Chicago Office:
1260 Conway Building

THE KAWNEER COMPANY
Niles, Mich.



Kawneer
STORE FRONTS

Phone

State 6789

For Full Details

THE
Kawneer
COMPANY

1260 Conway Building
CHICAGO

GLENCOE

Graves, Geo. P., 570 Jackson Ave.

HIGHLAND PARK

Hoermann, Carl.

Wright, Geo. C., 263 Cedar Ave.

LA GRANGE

Hubbard, Archie H., 205 S. Madison Ave.

Krausch, Walter T., 40 S. Stone Ave.

MAYWOOD

Dunlap, Francis E., 130 S. 19th Ave.

Van Gunten, Tellman G., 1318 S. 7th St.

MELROSE PARK

Chiaro, John A., 145 Broadway Ave.

OAK PARK

Cabeen, Richard M., 614 N. Woodbine Ave.

Clare, Wm. H., 425 S. Maple Ave.

Ellis, Francis M., 231 S. Oak Park Ave.

Fiddelke, Henry G., 1024 North Blvd.

Fyfe, James L., 316 S. Euclid Ave.

Hotchkiss, Roy James, 115 N. Oak Park Ave.

La Belle, Edw. C., 410 Wisconsin Ave.

Manard, Robert P., 220 Iowa St.

Pray, Frank M., 426 N. Parkside Ave.

Randolph, S. M., 1024 N. Blvd.

Roos, Bernard L., 734 S. Elmwood Ave.

Stoddard, Herbert H., 411 N. Cuyler Ave.

Washburn, Fred R., 1012 Chicago Ave.

PARK RIDGE

Mills, Albert Brown, 370 Prospect Ave.

RAVINIA

Van Bergen, John S.

RIVERSIDE

Kattelle, W. R., 17 Addison St.

Keeber, C. Hamilton, Maplewood and Des-
plaines Aves.

Krieg, Wm. G., P. O. Box 133

WILMETTE

Anderson, Russell A., 809 Lake Ave.

Henderson, Chas. G., 1405 Forrest Ave.

Hyett, Robert Leal, 511 Maple Ave.

Naper, Herbert J., 1127 Lake Ave.

Rae, Robert, Jr., 431 Greenleaf Ave.

WINNETKA

Windes, Frank A., 598 Birch Ave.

**CITIES OUTSIDE OF CHICAGO AND
COOK COUNTY****ALHAMBRA (Madison Co.)**

Oswald, Fridolin, Main St.

ALTON (Madison Co.)

Maupin, James M., 518 Commercial Bldg.

Mozier, Harry P., c/o J. J. Wuelner & Sons.

Pfeiffenberger, Geo. D., 102 W. Third St.

Stelle, Oliver G., 3112 Leverett Ave.

ANTIOCH

Jyrch, Karl, Petite Park.

AURORA (Kane Co.)

Gray, Frank B., First National Bank Bldg.

Liska, Adolph C., 473 Lafayette St.

Malmer, Eugene, 97 W. Park Ave.

BELLEVILLE

Rubach, Otto W., 112 Kircher Pl.

BLOOMINGTON (McLean Co.)

Miller, George H., 400 N. Center St.

Moratz, Arthur M., 701 Peoples Bank Bldg.

Pillsbury, Arthur L., Peoples Bank Bldg.

Simmons, A. T., First Natl. Bank Bldg.

CARBONDALE

Thompson, Thomas S., 1000 Thompson St.

CAIRO

Kusener, Casper, 1907 Washington Ave.

CARTHAGE (Hancock Co.)

Payne, Edgar A., 429 Main St.

CHAMPAIGN (Champaign Co.)

Clark, Chas. R., 105 Chalmers St.

Kratz, Elvin V., 315 S. State St.

Ramey, George Edwin, Robeson Bldg.

Temple, Harry R., Lincoln Bldg.

Wright, George E., 256 Administration Bldg.

CHARLESTON (Coles Co.)

Maxwell, Benjamin R., 411 Harrison Ave.

Mitchell, Chas. D.

COLLINSVILLE (Madison Co.)

Eberhardt, Henry W., 207 E. Main St.

DANVILLE (Vermilion Co.)

Liese, Geo. C., Temple Bldg.

Ludwig, Geo. W., Temple Bldg.

McCoy, John F., Dale Bldg.

Skadden, Harvey F., 206 Dale Bldg.

Stuebe, L. F. W., Adams Bldg.

Yeager, Ralph O., 1002 Hazel St.

DECATUR (Macon Co.)

Aschauer, Chas. J., Citizens Bank Bldg.

Bramhall, Arthur E., 209 National Bank
Bldg.

Brooks, Barkley S., 209 Nat. Bank Bldg.

Clausen, Swen A., Milliken Bldg.

Dague, England D., 836 N. Church St.

McNabb, Willie O., 272 N. Williams St.

Scribbins, John A., Standard Life Bldg.

Stauffer, Ernest L., 315 West North Ave.

Waggoner, Arthur M., Citizens Title & Trust
Bldg.

DIXON

Vail, Morrison H., 811 E. Fallon St.

EAST ST. LOUIS (St. Clair Co.)

Brockmeyer, Edwin J., 603 N. 14th St.

Frankel, Albert B., 206 Collinsville Ave.

Kennedy, John W., First Natl. Bank Bldg.

Mueller, Bernhard A., 209 Arcade Bldg.

Riester, Frank P., Murphy Bldg.

EDWARDSVILLE (Madison Co.)

Kane, Michael B., Bohm Bldg.



STEEL SASH FOR ALL REQUIREMENTS

Lupton Pivoted Factory Sash
Lupton Counterbalanced Sash—Patented
Lupton Counterweighted Sash—Patented
Lupton Projected Ventilator Sash—Patented
Lupton Power House Sash—Patented
Lupton Steel Partitions and Doors
Lupton Steel Skylight—Patented
Pond Continuous Sash—Patented
Pond Operating Device—Patented

*"Today—the Sash
makes the Factory"*

STOCK SASH

carried in Chicago warehouse for immediate shipment, including certain sizes of Pivoted Factory Sash, Pond Continuous Sash and Pond Operating Device.


*Write for catalogs of Lupton
Steel Shelving & Factory
Equipment.*

DAVID LUPTON'S SONS COMPANY

1114 Steger Bldg., Chicago, Ill.

Factory, Philadelphia, Pa.

Drawing below shows a typical Pond Truss foundry building in cross-section. Pond Continuous Sash used in all openings.



ELGIN (Kane Co.)

Abell, Ralph Elliott, 44 Spurling Bldg.
 Morris, G. E., Sherwin Bldg.

FAIRBURY (Livingston Co.)

Schnetzler, Chas. H., 309 E. Locust St.

GALESBURG (Knox Co.)

Aldrich, Harry G., Mail Bldg.
 Aldrich, Norman K., Mail Bldg.
 Beadle, John Grant, 234 E. Main St.

GLEN ELLYN

Hoskins, Henry J. B., 293 Park Blvd.

GRANITE CITY

Pauly, Charles, 19th & C Sts.

HIGHLAND

Knoebel, Wilbert G.

HOOPESTON

Love, Robert James, Willdon Bldg.
 Richards, James V., Willdon Bldg.

JACKSONVILLE (Morgan Co.)

Buckingham, Clarence W., 839 Grove St.
 Pierson, James K. C., Argus Bldg.

JOLIET (Will Co.)

Cowell, Herbert, 1 Jefferson St.
 Coyle, John E., 821 Clay St.
 Hoen, Rudolph G., Joliet Natl. Bank Bldg.
 Jennings, John T. W., Natl. Bank Bldg.
 Tomlinson, Henry Webster, 717 Heggie Bldg.
 Bldg.
 Wallace, Chas. L., 227 Jefferson St.
 Wallace, Elizabeth B., 227 Jefferson St.
 Webster, Charles Woods, 400 Cutting Bldg.

KANKAKEE (Kankakee Co.)

Henry, Charles D., Arcade Bldg.

KEWANEE

Gustafson, Carl A., Box 99.
 Hay, Mark, Second and Chestnut Sts.

LAKE FOREST

Jones, F. W., 117 Oakwood Ave N.

LAWRENCEVILLE

Brunson, Elmer A., Gee Bldg.

LINCOLN (Logan Co.)

Deal, Joe Mindert, I. O. O. F. Bldg.
 Ginzel, Roland F., I. O. O. F. Bldg

LOMBARD

Shane, James L., Ash and Main Sts.

MACOMB (McDonough Co.)

Holmes, Willis B., 218 N. Campbell Ave.

METROPOLIS

Daly, Samuel L., 708 Upper Market St.

MOLINE (Rock Island Co.)

Eckerman, Oscar A., 640 10th St.
 Eckland, Henry, McKinnie Bldg.
 Schulzke, Wm. H., Peoples Bank Bldg.
 Whitsitt, H. W., Peoples Bank Bldg.

MOUNT MORRIS

Buser, Nathaniel E., Buser Bldg.

MURPHYSBORO

Gill, Rudolph Z., 1328 Walnut St.

OTTAWA (La Salle Co.)

Hanifen, John, Nertney Bldg.
 Richardson, Jason F., Jr., Central Life Bldg.

PEKIN

Zimmer, John E., 217 Court St.

PEORIA (Peoria Co.)

Baillie, John McLellan, 201 Mayer Bldg.
 Bullard, Clarke W., 1014 Peoria Life Bldg.
 Chaffee, Dudley C., 316 N. Maywood Ave.
 Burgess, Ralph R., 125 N. Jefferson St.
 Davis, Geo. H., 527 Moss Ave.
 Day, Warren W., 1014 Peoria Life Bldg.
 Dox, Hamilton B., 502 Lehmann Bldg.
 Emerson, Frank N., 1600 Peoria Life Bldg.
 Hercules, Jacob W., 308 W. Sherman St.
 Hewitt, Herbert, 1600 Peoria Life Bldg.
 Hotchkiss, Robert J., Central Natl. Bank
 Bldg.
 Hulsebus, Bernhard S., Jefferson Bldg.
 Kiefer, Albert, Jefferson Bldg.
 Klein, Frederick J., 331 Main St.
 Koch, Henry A., 722 Thrush Ave.
 Reeves, Wm. C., 145 N. Jefferson St.
 Sedgwick, Wm. C., 318 Melbourne Ave.
 Whitmeyer, Mark H., Cent. Nat. Bank Bldg.

PERU

Wachter, H. F., 504 Grant St.

PONTIAC (Livingston Co.)

Young, Richard A., Sterry Blk.

QUINCY (Adams Co.)

Batschy, J., Wells Bldg.
 Behrensmeyer, George A., 530½ Main St.
 Chattan, Harvey, Wells Bldg.
 Geise, Martin J., 800½ Main St.
 Hafner, Wilbert E., 614½ Payson Ave.
 Wood, Ernest M., 128 N. 8th St.

ROCKFORD (Winnebago Co.)

Barloga, Jesse A., 710 Trust Bldg.
 Bradley, Charles W., 519-20 Brown Bldg.
 Carpenter, Frank A., 226 S. Main St.
 Davis, Jerome R., 503 Church St.
 Eliel, Arthur G., 610 Stewart Bldg.
 Johnson, Gilbert A., Swedish Am. Nat. Bank
 Bldg.
 Peterson, Edward A., Swedish Am. Nat.
 Bank Bldg.
 Vander Meer, Wybe J., 214 Mead Bldg.
 Wolfley, Chester E. H., 610 Stewart Bldg.

ROCK ISLAND (Rock Island Co.)

Cervin, Olaf Z., Safety Bldg.
 Chapler, Elijah C., 1635 12th St.
 Corbey, Leon J., 923 21st St.
 Horn, Benjamin A., Safety Bldg.
 Lerch, Edward, 515 27th St.
 Lundeen, Curt, 1520 19th Ave.
 Stauduhar, George P., Best Bldg.

RUSHVILLE

Thompson, J. Arthur.

ILL. OF ILL. LIB.

The Corn Exchange National Bank

OF CHICAGO

Capital and Surplus, \$15,000,000

United States
Depository

Foreign
Exchange

Letters of
Credit Issued

Savings
Department



Corn Exchange Bank Building

OFFICERS

ERNEST A. HAMILL, Chairman of
the Board
EDMUND D. HULBERT, President
CHAS. L. HUTCHINSON, Vice-Prest.
OWEN T. REEVES, JR., Vice-Prest.
J. EDWARD MAASS, Vice-President

NORMAN J. FORD, Vice-President
JAMES G. WAKEFIELD, Vice-Prest.
EDWARD F. SCHNECK, Cashier
LEWIS E. GARY, Ass't Cashier
JAMES A. WALKER, Ass't Cashier
CHARLES NOVAK, Ass't Cashier
HUGH J. SINCLAIR, Ass't Cashier

DIRECTORS

WATSON F. BLAIR	CHAUNCEY B. BORLAND	EDWARD B. BUTLER
CHARLES H. HULBURD	CHARLES L. HUTCHINSON	
BENJAMIN CARPENTER	CLYDE M. CARR	ERNEST A. HAMILL
MARTIN A. RYERSON	J. HARRY SELZ	
EDWARD A. SHEDD	ROBERT J. THORNE	CHARLES H. WACKER
HENRY P. CROWELL	EDMUND D. HULBERT	
JOHN J. MITCHELL		

SANDWICH (De Kalb Co.)

Howison, Charles.

SPRINGFIELD (Sangamon Co.)

Bullard, Robert A., 318 Unity Bldg.
 Bullard, Samuel A., 318 Unity Bldg.
 Conway, Wm. H., 104 E. Side Square.
 Furrow, Edw., 301 Broadwell Bldg.
 Gault, James C., 12½ High St.
 Hamilton, Frank H., City Hall.
 Hanes, Murray S., 205½ S. 6th St.
 Hanes, Samuel J., 205½ S. 6th St.
 Helmle, George B., Ferguson Bldg.
 Helmle, George Henry, Ferguson Bldg.
 Helmle, Henry R., Ferguson Bldg.
 Meyer, Carl T., 719 E. Edwards St.
 Reiger, Harry J., Booth Bldg.
 Rinaker, John I., 1331 Noble Ave.

STERLING

Morrell, John, 18 E. Third St.

STREATOR (La Salle Co.)

Allen, Alonzo W., 302 Main St.
 Foster, Wm. G., 114 N. Monroe St.

URBANA (Champaign Co.)

Danely, Paul, 812 S. Race St.
 Harris, Chas., 256 Administration Bldg.
 Maxwell, Wymer W., 512 W. Oregon St.
 Provine, L. H., Prof., 401 Engineering Bldg.,
 U. of I.
 Ricker, Nathan C., 612 W. Green St.
 Royer, Joseph W., Flat Iron Bldg.
 White, James M., Administration Bldg.

WESTERN SPRINGS

Heimbrott, Carl Edward, 279 E. Blvd.

WHEATON

Mitchell, Lewis M., Manchester Rd.

**ARCHITECTS OUTSIDE OF THE
STATE OF ILLINOIS****ALABAMA****MAGNOLIA SPRINGS**

Church, Myron H.

CALIFORNIA**LEMON GROVE (San Diego County)**

Zippivald, Otto

LOS ANGELES

Crow, Ralph M., 3932 S. Main St.
 Mueller, Lloyd E., 1121 S. Western Ave.
 Nixon, U. S., Box 330, R. F. D. No. 2.
 Noerenberg, Clarence Eugene, 400-1060 S.
 Broadway
 Norton, Francis J., Box 1233.
 Postle, David E., 631 Van Nuys Bldg.
 Postle, George R., 613 Van Nuys Bldg.

OJAI

McBride, Owen Earl

OAKLAND

Hanifen, Arthur C., 3203 San Pablo Ave.

PASADENA

Gillette, Edwin F., 691 La Loma Rd.

Herr, Thornton A., 1966 Las Lunas St.

SACRAMENTO

Peterson, Jens C., Peoples Savings Bldg.

SANTA BARBARA

Seymour, Bud W., 9-10 Bothin Bldg.

SAN DIEGO

Johnson, Harold S., 401 L. A. Ry Bldg.

SAN FRANCISCO

Hoover, Ira W., 1325 1st Nat. Bank Bldg.
 Lansburgh, Gustav A., 709 Mission St.

COLORADO**DENVER**

Winkel, Benno, care Colo. Southern Ry. Co

TRINIDAD

Laughlin, John A., c/o Spanish Peaks Lbr. Co.

DELAWARE**WILMINGTON**

Lawrence, Edgar H., 1001 Rodney St.

DISTRICT OF COLUMBIA**WASHINGTON**

Drishler, Francis, 2609 War Trades Bldg.
 Jullien, Phillip M., 504 Com. Natl. Bank Bldg.

FLORIDA**MIAMI**

Newell, Frank V., 1012 S. W. 13th Ave.

GEORGIA**ATLANTA**

Stuhrman, E. A., 751 Candler Annex Bldg.

INDIANA**BRAZIL**

Johnson, McMillan, 210 N. Walnut St.

EVANSVILLE

Boyle, Harry E., Furniture Bldg.
 Schlotter, Frank J., 113½ Upper 4th St.
 Shopbell, Clifford, Furniture Bldg.

FORT WAYNE

Reidel, John M. E., Noll Bldg.

GARY

Cenek, Robert R., 673 Broadway.
 Pentecost, Douglas S., 705 Connecticut Bldg.

HAMMOND

Berry, Addison C., Ruff Bldg.
 Hutton, J. T., Hammond Bldg.

HOBARD

Dorr, John I., Box 612.

INDIANAPOLIS

Dietz, Henry Z., 147 E. Market St.
 Dunlap, Elmer Edgar, 909 State Life Bldg.
 Foltz, Herbert W., Lemcke Annex.
 Hill, Norman H., 911 State Life Bldg.
 Parker, Wilson B., 620 State Life Bldg.
 Sturges, Lewis H., 527 Board of Trade
 Bldg.

LA FAYETTE

Boonstra, Samuel P., 21 S. 26th St.
 Hoffman, Frank J., Ross Bldg.

LOGANSPOUT (Cass Co.)

Horn, Carl J., Citizens Loan & Trust Bldg.

SOUTH BEND

Austin, Ennis R., 111 N. La Fayette Blvd.
 Ellwood, W. W., 215 N. Scott St.

Casualty Insurance at Cost

The Builders & Manufacturers
Mutual Casualty Company

1301 CHAMBER OF COMMERCE BUILDING

FRANKLIN 2132-2133

DIRECTORS:

ANDREW LANQUIST, President
H. B. BARNARD, Vice-President
J. W. SNYDER
A. C. WARREN
J. P. MONAHAN
V. L. PAGE
J. B. NOELLE
A. E. COLEMAN

C. G. FANNING, Treasurer
O. C. HOLTZ, Secretary
GEO. M. GETSCHOW
F. VOIGTMANN
J. W. MOULDING
F. W. JUNGCLAUS
GUY MILLS
FREDERICK BULLEY

ORGANIZED — OWNED — OPERATED
BY BUILDERS

To Furnish:

First—Sound indemnity at its actual cost.

Second—Prompt and efficient service to employed and employers.

Third—Reduction in severity and number of accidents by co-operation.

Surplus Over All Liabilities

\$401,509.61

TERRE HAUTE (Vigo Co.)

Miller, Ewing H., 30 N. Fifth Ave.
 Miller, Warren D., 30 N. Fifth Ave.
 Vrydagh, Jupiter G., 1515 S. 8th St.
 Vrydagh, Robert T., 612 Ohio St.

VINCENNES (Knox Co.)

Bayard, John B., 302½ Main St.
 Gaddis, John W., Am. Nat. Bank Bldg.
 Osterhage, Louis H., 2nd Nat. Bank Bldg.
 Schucker, Rudolph W., 509 N. 8th St.
 Sutton, Byron, Citizens Trust Bldg.

IOWA**CLINTON**

Ladehoff, John H., 1309 W. Pleasant St.

DAVENPORT (Scott Co.)

Burrows, Parke Tunis, 208 Main St.
 Clausen, Rudolph J., 315 Central Bldg.
 Ebeling, Arthur H., 819 Kahl Bldg.
 Kirkland, Archibald F., 208 Main St.
 Temple, Seth Justin, 208 Main St.

DUBUQUE

Carkeek, Thos. T., Lincoln Bldg.
 Heer, Fridolin, Jr., Bank & Ins. Bldg.

OTTUMWA

Kerns, Geo. M., Chamber of Commerce Bldg.
 Rounds, Fred G., Board of Education Bldg.

SIOUX CITY

Beach, Wilfred W., 336 Commercial Bldg.

WATERLOO

Gamble, L. Jay, 5th and Locust Sts.
 Shockley, Clinton P., 720 Black Bldg.

KANSAS**ELDORADO**

Simon, Walter H., 208½ W. Central Ave.

KENTUCKY**LOUISVILLE**

Davis, Brenton B., 413 Norton Bldg.
 Rosen, Richard O., 106 Todd Bldg.

LOUISIANA**NEW ORLEANS**

Davis, Chas. G., 1401 Tulane Ave.

MARYLAND**BALTIMORE**

Long, Maurice A., 1523 Munsey Bldg.

MASSACHUSETTS**AMHERST**

Thomas, Stafford, Fox, 21 Woodside Ave.

BOSTON

Cram, Ralph Adams, 15 Beacon St.
 Ferguson, Frank W., 15 Beacon St.

BROOKLINE

Voss, Walter C., care Wentworth Institute

MICHIGAN**BENTON HARBOR**

Harper, Homer W., Farmers & Merchants Bank Bldg.

DETROIT

Bauer, Leo M., 233 John R St.
 Kahn, Albert, Marquette Bldg.

GRAND RAPIDS

Crow, Henry E., The Gilbert.

THREE RIVERS

Brompton, Jos. C.

WALLED LAKE

Dunlap, E. R., R. F. D. No. 2

MINNESOTA**MINNEAPOLIS**

Dunham, Arthur B., 512 Essex Bldg.
 Jones, Harry W., 215 Essex Bldg.
 Rowe, Lindley P., 240 La Salle Bldg.

ST. PAUL

Seymour, Bud W., care Union Stock Yards.
 Willson, Samuel H., 215 Essex Bldg.

MISSOURI**HANNIBAL**

Martin, Malcolm, 1001 Collier St.

KANSAS CITY

Gloyd, Galen V. R., 321 Reliance Bldg.
 Peterson, David B., 715 Minnesota Ave.
 Vigeant, Gregory, Jr., 911 Commerce Trust Bldg.

ST. LOUIS

Barnett, George D., Century Bldg.
 Barnett, T. P., Arcade Bldg.
 Bonsack, Frederick C., Laclede Gas Bldg.
 Clymer, Harry G., Wainwright Bldg.
 Craine, Jas. A., Holland Bldg.
 Davis, Neal C., 705 Olive St.
 Groves, Albert B., 314 N. 4th St.
 Gruen, Wm. H., 1520 Chestnut St.
 Haynes, John I., Century Bldg.
 Helfensteller, Ernest, Jr., Chemical Bldg.
 Imbs, Thomas F., 2442 N. Grand Ave.
 Ittner, Wm. B., 911 Locust St.
 Jacobs, Charles N., 3512 Alberta St.
 Janssen, Ernest C., 1301 Chemical Bldg.
 Kennerly, Geo. H., 1111 Title and Guaranty Bldg.
 Kirsch, Robert G., 4067 Magnolia Ave.
 Klipstein, Ernest C., Chemical Bldg.
 Klutho, Victor J., Syndicate Trust Bldg.
 Le Beaume, Louis C., 720 Compton Bldg.
 Levy, W., Dolph Bldg.
 Link, Theo. C., 1520 Chemical Bldg.
 Mauran, John Lawrence, Chemical Bldg.
 May, Charles F., 408 Olive St.
 Rathmann, Walter L., Chemical Bldg.
 Roach, H. F., 915 Olive St.
 Russell, E. J., Chemical Bldg.
 Schopp, Lawrence O., 822 Chestnut St.
 Stauder, Adolph F., 4932 Finkman Bldg.
 Walsh, Robert W., Wainwright Bldg.
 Watson, Jesse N., 1004 Chemical Bldg.



A SUGGESTION:

when asked by your clients

REGARDING
FINANCING

you will make no mistake in
recommending

BAIRD & WARNER

FOUNDED 1855

29 South La Salle Street

Central 8300



Wessbecher, Louis, 805 Pontiac Bldg.
Widmann, Fred, Wainwright Bldg.
Wuest, Gustav P., 922 Wainwright Bldg.
Young, Thomas C., 1876 Arcade Bldg.

NEBRASKA

OMAHA

Carr, Charles A., 1303 S. 28th St.
Ellert, Frank J., 1602 City Nat. Bank Bldg.
Wellman, William Thomas, 313 S. 27th St.

NEW JERSEY

BOONTON

Lee, Harry V., 432 Washington St.

BROOKLYN

Hoffman, E. J. S., 218 Garfield Pl.

NEW YORK

NEW YORK CITY

Barnes, Julian, 39 E. 8th St.
Fellheimer, Alfred, 7 E. 42d St.
Francisco, Ferris, Le Roy, 511 5th Ave.
Goodhue, Bertram G., 2 W. 47th St.
Hewitt, George, 25 W. Broadway
Jacobus, Robert F., 511 5th Ave.
Lee, Elsworth M., 25 W. Broadway.
Lindeberg, Harrie T., 2 W. 47th St.
Mann, Horace B., 70 E. 45th St.
Palmer, Geo. Carnegie, 63 William St.
Preis, Carl G., 120 Broadway.
Rogers, James Gamble, 367 Lexington Ave.
Torrance, James R., 85 9th Ave.
Visscher, Theodore C., 363 Lexington Ave.
Wenderoth, Oscar, 55 E. 60th St.
Westervelt, John C., 36 W. 34th St.
Zimmermann, Albert G., 85 9th Ave.

NIAGARA FALLS

Beck, Frederic H., 123 Buffalo Ave.

SYRACUSE

Ganung, Howard D., 209 Elk St.
McCullough, Ernest, 33 W. 39th St.

NORTH CAROLINA

ASHEVILLE

Dreyer, Detlef J., 78 Patton Ave.

NORTH DAKOTA

Dippel, George Frank, 117 Broadway

OHIO

AKRON

De Arment, Frank H., 317 Everett Bldg.

CANTON

Kelley, Ralph L., c/o W. S. Middleton

CLEVELAND

Elliot, John H., 906 Engineers Bldg.

TOLEDO

Mills, Geo. S., Ohio Bldg.

OKLAHOMA

BARTLESVILLE

Wallace, Wellington J., 323 Lannon Bldg.

STILLWATER

Patterson, Jos. J., 312 Knoblock St.

TULSA

Thorne, A. Thomsen, 1105 Casden Bldg.

OREGON

PORTLAND

Purcell, Wm. G., 812 Spaulding Bldg.

PENNSYLVANIA

PHILADELPHIA

McLanahan, Martin H., 1418 Walnut St.
Stuckert, F. Russell, 1420 Chestnut St.

SCRANTON

Miller, Chas. A., Jr., 644 Clay Ave.

PITTSBURGH

Cooley, Charles D., 530 4th Ave.
Hodgkins, Howard G., c/o Standard Steel
Car Co., Frick Bldg.
Hogner, Pierre R. L., 1506 Rockland Ave.,
Beechview
Kennedy, Julian, Bessemer Bldg.
Prack, Bernhard H., Keystone Bldg.

SOUTH CAROLINA

GREENVILLE

Gilbert, Geo. H., P. O. Box 628

TEXAS

EL PASO

Herlin, Geo. W., 202 Mills Bldg.
Wuehrmann, Wm. G., 505 Republic Bldg.

WEST VIRGINIA

CHARLESTON

Martens, Walter F., c/o Morgan Lumber &
Mfg. Co.

NITRO

Haviland, Chas. A., care Directors' Office.

WISCONSIN

BELOIT

Kemp, Frank H., 302 Highland Ave.

MADISON

Claude, Louis W., 8 S. Carroll Ave.
Dunlap, Matthew E., Forest Products Labo-
ratory
Mead, Daniel W., State Journal Bldg.
Potter, Ellis J., 1427 Rutledge St.

MILWAUKEE (Milwaukee Co.)

Barkhauser, Carl H., 79 Wisconsin St.
Bradley, Harold S., 712 Brunder Bldg.
Brielmaier, Joseph, 432 Broadway
Ephraim, George, 715½ Lloyd St.
Foster, John W., Caswell Bldg.
Hengels, Henry C., 1st Nat. Bank Bldg.
Hunt, Leigh, 443 Milwaukee St., R. 412
Martson, Louis H., Hartford Bldg.
Newlander, Manuel M., 1220 Pratt Bldg.

RACINE

Chandler, James G., 803 Lake Ave.

WAUSAU

Oppenhamer, William Adam, 605½ 3rd St.

WYOMING

CASPER

Webb, Rayburn S., 415 Oil Exchange Bldg.

OUTSIDE OF U. S.

CHINA

HONG KONG

Shank, Edward D., 52 Queens Rd.

PEKIN

Hussey, Harry H., 5 San Tias Huting East



An Installation Showing a Creosoted Wood Block Floor

Indiana Zinc Creosoting Co.

111 West Washington Street

CHICAGO

Manufacturers of

CREOSOTED WOOD BLOCKS

for

Warehouse, Machine Shop and Foundry Floors,
Loading Platforms, Driveways, Etc.

Creators of

Piling and Timbers for Heavy Construction

For durability—Creosoted Wood Block Floors

Plant

TERRE HAUTE, IND.

Illinois Society of Architects

OFFICERS

F. E. DAVIDSON, President	53 W. Jackson Blvd.
HERBERT E. HEWITT, 1st Vice-President	Peoria, Ill.
JOHN A. NYDEN, 2nd Vice-President	196 N. State St.
JOHN A. ARMSTRONG, Treasurer	127 N. Dearborn St.
RALPH C. HARRIS, Secretary	192 N. State St.
H. L. PALMER, Financial Secretary	1211, 19 S. La Salle St.

DIRECTORS

One Year

BYRON H. JILLSON	9111 S. Robey St.
ROBERT C. OSTERGRÉN	155 N. Clark St.

Two Years

EMERY STANFORD HALL	64 E. Van Buren St.
CHARLES HERRICK HAMMOND	64 E. Van Buren St.

Three Years

GEORGE BEAUMONT	25 N. Dearborn St.
HARRY B. WHEELOCK	64 W. Randolph St.

BOARD OF ARBITRATION

ALFRED S. ALSCHULER	28 E. Jackson Blvd.
ELMER C. JENSEN	39 S. La Salle St.
JOSEPH C. LLEWELLYN	38 S. Dearborn St.
GEORGE C. NIMMONS	122 S. Michigan Ave.
DWIGHT H. PERKINS	814 Tower Court.
IRVING K. POND	64 E. Van Buren St.
RICHARD E. SCHMIDT	104 S. Michigan Ave.

EDITOR MONTHLY BULLETIN

F. E. DAVIDSON	1448 Monadnock Block.
----------------	-----------------------

STANDING COMMITTEES

Membership Committee

BYRON H. JILLSON, Chairman	9111 S. Robey St.
ARCHIE H. HUBBARD	La Grange, Ill.
BERT C. HUBBARD	225 N. Michigan Ave.
WILLIAM C. JONES	19 S. La Salle St.
JAMES R. MORRISON	64 W. Randolph St.
H. L. PALMER	19 S. La Salle St.

Publication Committee

CHAS. HERRICK HAMMOND, Chairman	64 E. Van Buren St.
F. E. DAVIDSON	53 W. Jackson Blvd.
N. MAX DUNNING	310 S. Wabash Ave.


Legislative Committee

HARRY WHEELOCK, Chairman	64 W. Randolph St.
JOHN REED FUGARD	212 E. Superior St.
J. C. LLEWELLYN	38 S. Dearborn St.
DAVIS D. MEREDITH	4819 N. Albany Ave.
ROBERT C. OSTERGRÉN	155 N. Clark St.

Committee on Public Action

JOHN A. NYDEN, Chairman	196 N. State St.
FRANK A. CARPENTER	Rockford, Ill.
WARREN W. DAY	Peoria, Ill.
ROBERT S. DE GOLYER	7 S. Dearborn St.
RALPH C. HARRIS	192 N. State St.
GEORGE B. HELME	Springfield, Ill.
ARTHUR L. PILLSBURY	Bloomington, Ill.
HOWARD PUTNAM STURGES	79 W. Monroe St.
JOHN W. WEISS	53 W. Jackson Blvd.
H. W. WHITSITT	Moline, Ill.

The Mechanical Mfg. Co.




Manufacturers of

Friction
Elevators

Bumping
Posts

and



Packing House Equipment

For many years we have been known the country over as the largest and most enterprising manufacturers of packing house machinery in the world. Our well equipped plant and organization of trained men have placed us in an advantageous position to serve equally well architects and engineers with special machinery, boiler and tank work, Ellis and Durable railroad bumping posts, light and heavy sheet metal work, tinning, galvanizing, etc.

Our extended, practical experience in the manufacture and installation of this equipment has made it possible for us to gather together information of value to construction men and architects making layouts in packing houses for the installation of machinery and overhead tracking systems for cold storage plants.

We shall be pleased to have you call on us for assistance.

The Mechanical Mfg. Co.

Loomis Street and Pershing Road
CHICAGO, ILL.

Telephone Boulevard 2900

Committee on Education

HERBERT E. HEWITT, Chairman	Peoria, Ill.
SIDNEY LOVELL	30 N. Michigan Ave.
ARTHUR L. PILLSBURY	Bloomington, Ill.
FRANCIS W. PUCKEY	6 N. Michigan Ave.
PERRY W. SWERN	19 S. La Salle St.
PROF. JAMES M. WHITE	Urbana, Ill.

Publicity and Promotion Committee

KARL M. VITZTHUM, Chairman	400 N. Michigan Ave.
LEO H. PLEINS	544 S. Franklin St.
E. E. ROBERTS	82 W. Washington St.
PERRY W. SWERN	19 S. La Salle St.
MARK H. WHITMEYER	Peoria, Ill.

Materials and Methods Committee

EMERY STANFORD HALL, Chairman	64 E. Van Buren St.
MELVILLE C. CHATTEN	64 E. Van Buren St.
LEO H. PLEINS	544 S. Franklin St.
LEWIS W. RIDDLE	122 S. Michigan Ave.
N. S. SPENCER	37 W. Van Buren St.

Architectural Exhibits Committee

GEORGE W. MAHER, Chairman	157 E. Erie St.
HUBERT BURNHAM	209 S. La Salle St.
ARCHIE H. HUBBARD	La Grange, Ill.
CLARE C. HOSMER	133 W. Washington St.
CHARLES L. MORGAN	104 S. Michigan Ave.

Entertainment Committee

ROBERT C. OSTERGREN, Chairman	155 N. Clark St.
CHARLES D. FAULKNER	140 S. Dearborn St.
WILLIAM H. LAUTZ	64 E. Van Buren St.
WILLIAM ROHM	138 N. La Salle St.
H. L. PALMER, Secretary	19 S. La Salle St.

SPECIAL COMMITTEES

Committee on Jurisdictional Disputes and Co-operation with National Board of

Jurisdictional Awards


HENRY K. HOLSMAN, Chairman	310 S. Wabash Ave.
GEORGE BEAUMONT	25 N. Dearborn St.
JOSEPH C. LLEWELLYN	38 S. Dearborn St.

Historical Committee

ALL LIVING PAST PRESIDENTS

GEORGE BEAUMONT, Chairman	25 N. Dearborn St.
H. B. WHEELOCK	64 W. Randolph St.
E. S. HALL	64 E. Van Buren St.
E. M. NEWMANN	107 N. Clark St.
GEORGE L. PFEIFFER	Lemon City, Fla.
WILLIAM W. CLAY	538 S. Dearborn St.
IRVING K. POND	64 E. Van Buren St.
A. F. WOLTERSDORF	138 N. La Salle St.
JULIAN BARNES	39 E. 8th St., New York, N. Y.
ARGYLE E. ROBINSON	5227 Harper Ave.
MEYER J. STURM	116 S. Michigan Ave.
F. E. DAVIDSON	53 W. Jackson Blvd.
STAFFORD FOX THOMAS	21 Woodside Ave., Amherst, Mass.
GEORGE W. MAHER	157 E. Erie St.
ARTHUR F. HUSSANDER	25 N. Dearborn St.
C. H. HAMMOND	64 E. Van Buren St.

CYCLONE FENCE



Fencing-Wire or Iron-for Any Purpose

For country estates, city and suburban homes, private and public parks, hotels, automobile parking places, hospitals, schools, churches cemeteries, etc. Also fencing for factories of all kinds, city, county, state and national institutions, power and pumping stations, filtration plants and reservoirs.

Special Fencing and Gates, Wire or Iron, built in patterns to incorporate your individual ideas and original designs. We also manufacture Tennis Court Enclosures and Backstops, Bird and Animal Cages, Poultry Enclosures, Kennels, etc.

Our engineering facilities and experience are at the disposal of engineers and architects to solve any fencing problem. This service is gratis. On request, we will furnish, without charge, blue prints showing details of fence construction; also literature containing general information on Cyclone Fencing.

Phone, Wire or Write

CYCLONE FENCE COMPANY

WAUKEGAN, ILLINOIS. Phone, Waukegan 170

Chicago Offices: New York Life Bldg., Phone, State 5314

Branches in Principal Cities



Building Valuations Committee

HARRY B. WHEELOCK, Chairman	64 W. Randolph St.
M. C. CHATTEN	64 E. Van Buren St.
F. E. DAVIDSON	53 W. Jackson Blvd.
E. S. HALL	64 E. Van Buren St.
R. C. HARRIS	190 N. State St.
ELMER C. JENSEN	39 S. La Salle St.
GEORGE C. NIMMONS	122 S. Michigan Ave.
ROBERT C. OSTERGREN	155 N. Clark St.
RICHARD E. SCHMIDT	104 S. Michigan Ave.

Zoning Committee

CHAS. H. HAMMOND, Chairman	64 E. Van Buren St.
ALFRED GRANGER	619 N. Michigan Ave.
ELMER C. JENSEN	39 N. La Salle St.

Fire Prevention Committee

A. E. ROBINSON, Chairman	5227 Harper Ave.
T. J. FERRENZ	5463 Ellis Ave.
ELMER C. JENSEN	39 S. La Salle St.
CHAS. W. KALLAL	City Hall, Chicago, Ill.
GEORGE C. NIMMONS	122 S. Michigan Ave.

State Building Code Committee

RICHARD E. SCHMIDT, Chairman	104 S. Michigan Ave.
HENRY ECKLAND	Moline, Ill.
W. G. FOSTER	155 N. Clark St.
W. R. KATTELLE	Riverside, Ill.
LEROY LEWIS, JR.	104 S. Michigan Ave.
E. E. ROBERTS	82 W. Washington St.
K. H. SHELDON	400 N. Michigan Ave.
H. W. TOMLINSON	Joliet, Ill.
PROF. JAMES M. WHITE	Urbana, Ill.
A. C. WILMANNS	35 S. Dearborn St.

Committee on Permanent Quarters for Illinois Society, Illinois Chapter and Architectural Club

HOWARD J. WHITE, Chairman	80 E. Jackson Blvd.
ALFRED ALSCHULER	28 E. Jackson Blvd.
D. H. BURNHAM	209 S. La Salle St.
H. L. PALMER	1211, 19 S. La Salle St.
ALLEN B. POND	64 E. Van Buren St.

Committee on Co-operation with Chicago School of Architecture

PERRY W. SWERN, Chairman	19 S. La Salle St.
ALFRED S. ALSCHULER	28 E. Jackson Blvd.
CHAS. H. HAMMOND	64 E. Van Buren St.
ROBERT C. OSTERGREN	155 N. Clark St.
K. M. VITZTHUM	400 N. Michigan Ave.

Committee on Co-operation with Architectural Club

FRANCIS W. PUCKEY, Chairman	6 N. Michigan Ave.
B. C. GREENGARD	619 N. Michigan Ave.
MORTON LEVITON	53 W. Jackson Blvd.
CHAS. H. SIERKS	2525 Clybourn Ave.
IVAR VIEHE-NAESS	400 N. Michigan Ave.

Committee on Co-operation with Chicago Association of Consulting Engineers

BENJAMIN WINSLOW, Chairman	2617 N. Richmond St.
A. L. LEVY	111 W. Washington St.
L. H. PLEINS	544 S. Franklin St.
Representing the Illinois Society of Architects in the Illinois Chamber of Commerce	
CHAS. H. HAMMOND	64 E. Van Buren St.

Representing the Illinois Society of Architects in the National Housing Association

CHAS. H. HAMMOND	64 E. Van Buren St.
------------------	---------------------

Representing the Illinois Society of Architects in the American Society for Testing Materials

F. E. DAVIDSON	53 W. Jackson Blvd.
----------------	---------------------

Legal Service Committee

Composed of Entire Board of Directors


You Specify the Best When You Specify *Lawson Hinges*




No. 2434



No. 2834




No. 2234





No. 2534

Write us for other
applications



Application Lawson
Universal Spring Hinge



In upper circle: Top Pivot
In lower circle: Spring Hinge

Lawson can supply a spring hinge for every purpose.

Lawson Hinges are better, stronger, and more economical to apply.

*When you specify "Lawson"
you specify the best*

LAWSON MANUFACTURING CO.

228-230 West Superior Street
CHICAGO, ILLINOIS

1907

Normand S. Patton, President.
 Arthur F. Woltersdorf, 1st Vice-President.
 Irving K. Pond, 2d Vice-President.
 Samuel A. Treat, Treasurer.
 Emery Stanford Hall, Secretary.
 H. L. Palmer, Asst. Secretary.

1908

Irving K. Pond, President.
 Richard G. Schmid, 1st Vice-President.
 Edmund R. Krause, 2d Vice-President.
 Samuel A. Treat, Treasurer.
 Emery Stanford Hall, Secretary.
 H. L. Palmer, Asst. Secretary.

1909

George Beaumont, President.
 Samuel N. Crowen, 1st Vice-President.
 Leon E. Stanhope, 2d Vice-President.
 Samuel A. Treat, Treasurer.
 Emery Stanford Hall, Secretary.
 H. L. Palmer, Asst. Secretary.

1910

Arthur F. Woltersdorf, President.
 Robert C. Berlin, 1st Vice-President.
 Argyle E. Robinson, 2d Vice-President.
 Samuel N. Crowen, Treasurer.
 Emery Stanford Hall, Secretary.
 H. L. Palmer, Asst. Secretary.

1911

Julian Barnes, President.
 Argyle E. Robinson, 1st Vice-President.
 Peter J. Weber, 2d Vice-President.
 Samuel N. Crowen, Treasurer.
 Emery Stanford Hall, Secretary.
 H. L. Palmer, Asst. Secretary.

1912

Argyle E. Robinson, President.
 George W. Maher, 1st Vice-President.
 George Beaumont, 2d Vice-President.
 Samuel N. Crowen, Treasurer.
 Emery Stanford Hall, Secretary.
 H. L. Palmer, Asst. Secretary.

1913

Meyer J. Sturm, President.
 Arthur F. Woltersdorf, 1st Vice-President.
 Joseph C. Llewellyn, 2d Vice-President.
 Samuel N. Crowen, Treasurer.
 Emery Stanford Hall, Secretary.
 H. L. Palmer, Asst. Secretary.

1914

Emery Stanford Hall, President.
 Frank E. Davidson, 1st Vice-President.
 John Devereux York, 2d Vice-President.
 Samuel N. Crowen, Treasurer.
 John Reed Fugard, Secretary.
 H. L. Palmer, Financial Secretary.

1915

Frank E. Davidson, President.
 Stafford Fox Thomas, 1st Vice-President.
 Robert Seth Lindstrom, 2d Vice-President.
 Samuel N. Crowen, Treasurer.
 John Reed Fugard, Secretary.
 H. L. Palmer, Financial Secretary.

1916

Frank E. Davidson, President.
 Stafford Fox Thomas, 1st Vice-President.
 William G. Carnegie, 2d Vice-President.
 Samuel N. Crowen, Treasurer.
 John Reed Fugard, Secretary.
 H. L. Palmer, Financial Secretary.

1917

Stafford Fox Thomas, President.
 Arthur F. Hussander, 1st Vice-President.
 James B. Dibelka, 2d Vice-President.
 Samuel N. Crowen, Treasurer.
 John Reed Fugard, Secretary.
 H. L. Palmer, Financial Secretary.

1918

George W. Maher and Arthur F. Hussander,
 Presidents
 Arthur F. Hussander, President.
 James B. Dibelka, 1st Vice-President.
 George W. Maher, 2nd Vice-President.
 Samuel N. Crowen, Treasurer.
 George A. Knapp, Secretary.
 H. L. Palmer, Financial Secretary.

1919

Charles Herrick Hammond, President.
 Robert C. Berlin, 1st Vice-President.
 N. Max Dunning, 2nd Vice-President.
 Ralph C. Harris, Secretary.
 H. L. Palmer, Financial Secretary.

1920

Frank E. Davidson, President.
 Herbert E. Hewitt, 1st Vice-President.
 John A. Nyden, 2nd Vice-President.
 John A. Armstrong, Treasurer.
 Ralph C. Harris, Secretary.
 H. L. Palmer, Financial Secretary.

MEMBERS

Almquist, Carl M., 118 N. La Salle St.
 Alschuler, Alfred S., 28 E. Jackson Blvd.
 Armstrong, John A., 127 N. Dearborn St.
 Aroner, J. S., 25 E. Jackson Blvd.
 Aschauer, C. J., Citizens Bank Bldg., Decatur,
 Illinois.
 Bannister, Geo. S., 115 S. Dearborn St.
 Barnes, Allen L., 1329 Birchwood Ave.

Barrett, Frederick L., 4354 N. Keeler Ave.
 Barthel, J. Bernard, 127 N. Dearborn St.
 Barton, Francis M., 3426 S. Kedzie Ave.
 Beaudry, Ralph L., 7047 Princeton Ave.
 Beaumont, George, 25 N. Dearborn St.
 Baumeister, Geo. E., 201 E. 70th St.
 Beman, S. S., 108 S. La Salle
 Benson, Edward, 5520 Glenwood Ave.

"It's The Crinkle In The Shingle That Makes Cor-Du-Roy"

Mule-Hide
Cor-du-roy
4-unit

Pat. Aug. 7, 1915
Other patents pending

MULE-HIDE COR-DU-ROY

Trade Mark

*The Latest, Greatest Stride Toward
Roofing Perfection!*

We are glad to announce to the Architectural world, the latest MULE-HIDE Triumph—COR-DU-ROY—the result of Tom Lehon's determination to make his asphalt shingle the pinnacle of perfection in overhead protection.

In the words of one of the nation's foremost architectural designers, the MULE-HIDE COR-DU-ROY Shingle is spoken of as the "first and only great step from the monotone effect of the ordinary flat shingle roof." COR-DU-ROY is the Shingle BEAUTIFUL! Its rugged shadow effect harmonizes with any and every style of architecture.

In our new and scientific process of manufacturing the MULE-HIDE COR-DU-ROY Shingle, the selected all-rag felt base very slowly passes through, and is thoroughly saturated with, a dense, high-grade, refined Mexican Asphalt, which is tested periodically in our own chemical laboratory. The top surface is covered with the same good asphalt in which a protecting coat of richly colored slate is deeply and firmly imbedded by the corrugation. This makes a solid unit built for endurance and lasting beauty—so decidedly superior that it cannot be compared with the ordinary "scrawny" roofing.

Each individual shingle is rigidly inspected before leaving the factory. They reach the builder in as near perfect condition as human ingenuity can devise. To see this truly artistic shingle is to fully and finally appreciate its distinctive individuality.

Builders who demand the best are coming to realize that where they find the best stock of lumber and building materials, they find MULE-HIDE Roofing and Shingles.

MULE-HIDE COR-DU-ROY is made in Standard weight shingles, Extra Heavy shingles and Four-Unit, also in the new patented, Self-Spacing shingle—MULE-HIDE Lok-Level.




"NOT A KICK IN A MILLION FEET"

Berlin, R. C., 19 S. La Salle St.
 Bishop, Thomas R., 35 S. Dearborn St.
 Blondin, Edw. A., 5 W. Garfield Blvd.
 Bouchard, Louis C., 30 N. Dearborn St.
 Braband, F. J. E., 901 Wrightwood Ave.
 Bradley, Chas. W., Brown Bldg., Rockford, Ill.
 Brantitzky, Wm. Thomas, 64 W. Randolph St.
 Braun, Wm. T., 64 E. Van Buren St.
 Bristle, Joseph H., 108 S. La Salle St.
 Brockmeyer, Edwin C., 603 N. 14th St., East St. Louis, Ill.
 Buckingham, Clarence W., 339 Grove St. Jacksonville, Ill.
 Buerger, Albert J., Jr., 4819 Gladys Ave.
 Burnham, D. H., 209 S. La Salle St.
 Burnham, Hubert, 209 S. La Salle St.
 Buser, Nathaniel E., Mount Morris, Ill.
 Byerly, F. I., 11131 S. Irving Ave.
 Capraro, Alexander, 72 W. Washington St.
 Carnegie, Wm. G., 189 W. Madison St.
 Carpenter, Frank A., 226 S. Main St., Rockford, Ill.
 Carr, Chas. Alban, 1303 S. 28th St., Omaha, Nebraska.
 Cerny, Jerry J., 1444 S. Crawford Ave.
 Chaffee, Dudley C., 316 N. Maywood Ave., Peoria, Ill.
 Charvat, Anton, 2621 Millard Ave.
 Chatten, Melville C., 64 E. Van Buren St.
 Christensen, Chas. Werner, 1818 Greenleaf Ave.
 Christensen, John C., 3255 Evergreen Ave.
 Chubb, John D., 109 N. Dearborn St.
 Clark, C. R., 105 Chalmers St., Champaign, Ill.
 Clark, Edwin, 8 E. Huron St.
 Clark, Robert C., 7216 Harvard Ave.
 Cloyes, Frederick O., 400 N. Michigan Ave.
 Coffin, A. S., 39 W. Adams St.
 Cook, Norman W., 1283 Victor Ave.
 Coyle, John E., 821 Clay St., Joliet, Ill.
 Conway, Wm. H., 104 East Side Square, Springfield, Ill.
 Crowen, S. N., 400 N. Michigan Ave.
 Dalsey, Harry I., 2321 W. North Ave.
 Davey, John J., 4440 N. Beacon St.
 Davidson, F. E., 53 W. Jackson Blvd.
 Davis, George H., 527 Moss St., Peoria, Ill.
 Davis, Zachary T., 400 N. Michigan Ave.
 Day, Warren W., Peoria Life Bldg., Peoria, Ill.
 De Arment, Frank H., 317 Everett Bldg., Akron, Ohio.
 De Golyer, Robert S., 7 S. Dearborn St.
 De Money, Frank O., 5 N. La Salle St.
 Dibelka, James B., 2743 W. 22nd St.
 Dippold, Albert P., 4747 Cottage Grove Ave.
 Doerr, Harold F., 11519 S. Irving Ave.
 Doerr, W. Phillip, 105 N. Clark St.
 Dougherty, Floyd E., 35 N. Dearborn St.
 Dowling, E. F., 6 N. Michigan Ave.
 Dreyer, Detlef J., 78 Patton Ave., Asheville, N. C.
 Drummond, Wm., 10 S. La Salle St.
 Dubin, Geo. H., 14 W. Washington St.
 Dunford, Samuel H., 38 S. Dearborn St.
 Dunning, N. Max, 310 S. Wabash Ave.
 Dwen, Robert G., 8 E. Huron St.
 Eckerman, Oscar A., Moline, Ill.
 Eckland, Henry, McKinnie Bldg., Moline.
 Eckstrom, Christian A., 5 N. La Salle St.
 Eichberg, S. M., 64 W. Randolph St.
 Emerson, Frank N., 1600 Peoria Life Bldg., Peoria, Ill.
 Ermeling, Ralph W., 64 E. Van Buren St.
 Fairclough, Stanley D., 7011 Jeffrey Ave.
 Faulkner, Chas. D., 140 S. Dearborn St.
 Ferrenz, Tirrell J., 5463 Ellis Ave.
 Fiddelke, H. G., 1026 North Blvd., Oak Park.
 Fischer, F. W., 9129 Commercial Ave.
 Fischer, John B., 140 S. Dearborn St.
 Fishman, M. Maurice, 118 N. La Salle St.
 Flaks, Francis A., 2743 W. 22nd St.
 Fletcher, Robert C., 179 W. Washington.
 Flinn, Raymond W., 8 S. Dearborn St.
 Fogel, Reuben W., 1839 Warner Ave.
 Foltz, Frederick C., 111 W. Washington St.
 Fortin, Joseph T., 600 Blue Island Ave.
 Foster, Arthur, 155 N. Clark St.
 Foster, Wm. G., 114 N. Monroe St., Streator, Ill.
 Fox, Chas. E., 721 N. Michigan Ave.
 Fox, John J., 38 S. Dearborn St.
 Fox, Wm. P., 38 S. Dearborn St.
 Franklin, Robert L., 64 E. Van Buren St.
 Franzheim, H. Kenneth, 127 N. Dearborn St.
 Friedman, Raphael N., 521 E. 60th St.
 Frommann, Emil H., 64 W. Randolph St.
 Frost, Charles S., 105 S. La Salle St.
 Fry, Frank L., 140 S. Dearborn St.
 Fugard, John Reed, 212 E. Superior St.
 Furst, Wm. H., 140 S. Dearborn St.
 Gaddis, John W., Vincennes, Ind.
 Gatterdam, F. E., 154 W. Randolph St.
 Gauger, William, 36 W. Randolph St.
 Gaul, Herman J., 111 W. Washington St.
 Gerber, Arthur, 20 W. Jackson Blvd.
 Gerhardt, Paul, 64 W. Randolph St.
 Gibb, Wm. R., 117 N. Dearborn St.
 Gibson, Bayard K., 608 S. Dearborn St.
 Gill, Rudolph Z., Murphysboro, Ill.
 Gillette, Edwin F., 691 La Loma Rd., Pasadena, Calif.
 Granger, Alfred Frost, 619 N. Michigan Ave.
 Gray, Frank B., 1st Nat. Bank Bldg., Aurora, Ill.
 Green, H. H., 308 S. Wabash Ave.
 Greengard, Bernhard C., 619 N. Michigan Ave.
 Griesser, Richard, 64 W. Randolph St.
 Gubbins, Wm. F., 4059 W. Monroe St.
 Guenzel, Louis, 111 W. Washington St.
 Haagen, Paul T., 155 N. Clark St.
 Hall, E. Stanford, 64 E. Van Buren St.
 Hamilton, J. L., 814 Tower Court.
 Hammond, Chas. H., 64 E. Van Buren St.
 Hanifen, John, Nertney Bldg., Ottawa, Ill.
 Hansen, Paul, 830 Lawrence Ave.
 Harris, Ralph C., 192 N. State St.
 Hatzfeld, Clarence, 7 S. Dearborn St.
 Hauber, Carl, 108 S. La Salle St.
 Hecht, Albert S., 64 W. Randolph St.
 Heinz, L. H., 128 N. La Salle St.

Crescent Cork Insulation

Is the most adaptable type of Insulation for permanent Refrigerators and Cooling Rooms required in Hotels, Public Institutions, Hospitals, Clubs, Industrial Welfare Buildings, etc.



The above type of installation made completely of Crescent Pure Cork Board (no wood or metal, except doors) and permanent White cement finish. Permanently efficient, sanitary, always free from odors, no expense for repairs, adaptable to any location, minimum of space required. Let us give you the details and specifications of your next requirements

Specify and Use Crescent Pure Cork Board

Cork Board, Granulated Cork and Cold Storage Doors on hand at Chicago Warehouse at all times

United Cork Companies

110 South Dearborn St.

Phone Randolph 1961

CHICAGO, ILLINOIS

Helfensteller, Ernest, Chemical Bldg., St. Louis, Mo.
 Helmle, George B., Ferguson Bldg., Springfield, Ill.
 Helmle, Henry R., Ferguson Bldg., Springfield, Ill.
 Henry, Chas. D., Arcade Bldg., Kankakee.
 Henschien, H. Peter, 37 W. Van Buren St.
 Hercules, J. W., 308 W. Sherman Ave., Peoria, Ill.
 Hetherington, J. T., 38 S. Dearborn St.
 Hetherington, Murray, 38 S. Dearborn St.
 Hettinger, John P., 4708 Dover St.
 Hewitt, Herbert, 1600 Peoria Life Bldg., Peoria, Ill.
 Himelblau, A. L., 179 W. Washington St.
 Hine, Cicero, 3221 Broadway.
 Hirschfield, Leo S., 139 N. Clark St.
 Hodgdon, Charles, 134 S. La Salle St.
 Hodgkins, H. G., c/o Standard Steel Car Co., Frick Bldg., Pittsburgh, Pa.
 Hogner, Lt. Pierre R. L., 1506 Rockland Ave., Beechview, Pittsburgh, Pa.
 Holsman, Henry K., 310 S. Wabash Ave.
 Horn, Benjamin A., Safety Bldg., Rock Island, Ill.
 Hosmer, Clare C., 133 W. Washington St.
 Hubbard, Archie H., 204 S. Madison Ave., La Grange, Ill.
 Hubbard, Bert C., 225 N. Michigan Ave.
 Hubbard, Willis W., 1710 Greenleaf Ave.
 Huber, Julius H., 2039 Greenleaf Ave.
 Hulsebus, Bernard L., 1001 Jefferson Bldg., Peoria, Ill.
 Hunt, Jarvis, 30 N. Michigan Ave.
 Huston, Sanford K., Jr., 5468 Woodlawn Ave.
 Hussander, A. T., 25 N. Dearborn St.
 Hussey, Harry H., 5 San Tias Huting East, Pekin, China.
 Hyde, Robert M., 8 S. Dearborn St.
 Hyland, Paul V., 159 E. Ontario St.
 Jacobs, Arthur, 139 N. La Salle St.
 Jensen, Clarence A., 310 S. Wabash Ave.
 Jensen, Elmer C., 39 S. La Salle St.
 Jensen, Jens J., 4815 N. Lawndale Ave.
 Jillson, B. H., 9111 S. Robey St.
 Jobson, C. F., 225 N. Michigan Ave.
 Johnson, Gilbert A., Swedish Am. Nat. Bank Bldg., Rockford, Ill.
 Johnston, W. K., 6805 Yale Ave.
 Jones, Wm. C., 19 S. La Salle St.
 Joy, Samuel Scott, 2001 W. 39th St.
 Jyrch, Karl E., Petite Park, Antioch, Ill.
 Kallal, Charles W., City Hall, Chicago, Ill.
 Kane, Michael B., Bohm Bldg., Edwardsville, Ill.
 Kattelle, Walter R., Riverside, Ill.
 Kiefer, Albert, Jefferson Bldg., Peoria, Ill.
 Kingsley, Geo. S., 109 N. Dearborn St.
 Klamt, Edward A., 304 S. Wabash Ave.
 Klein, Wm. J., 1660, 111 W. Washington St.
 Knapp, George Arnold, 212 E. Superior St.
 Kocher, Jacques J., 6250 S. Halsted St.
 Koenigsberg, Nathaniel, 8 S. Dearborn St.
 Kohfeldt, Walter G., 400 N. Michigan Ave.
 Kupfer, Otto A., 1865 Millard Ave.
 Lagergren, Gustav P., 7708 S. Hermitage Ave.
 Lampe, Clarence W., 155 N. Clark St.
 Lautz, William H., 64 E. Van Buren St.
 Layer, Robert W., 19 S. La Salle St.
 Lehle, Louis, 3810 Broadway.
 Leviton, Morton, 53 W. Jackson Blvd.
 Levy, Alex. L., 111 W. Washington St.
 Lewis, Le Roy, Jr., 104 S. Michigan Ave.
 Liedberg, Hugo J., 154 W. Randolph St.
 Lindquist, F., 179 W. Washington St.
 Lindstrand, John A., 800 N. Clark St.
 Lindstrom, Robert S., 15 E. Van Buren St.
 Liska, Charles O., 9601 Prospect Ave.
 Liska, Emil, 9601 Prospect Ave.
 Llewellyn, J. C., 38 S. Dearborn St.
 Loewenberg, Israel S., 111 W. Monroe St.
 Lonek, Adolph, 1867 S. Avers Ave.
 Lovdall, George F., 25 N. Dearborn St.
 Lovell, Sidney, 30 N. Michigan Ave.
 Ludgin, Joseph H., 53 W. Jackson Blvd.
 Lund, A. G., 453 W. 63rd St.
 Mahaffey, D., 118 N. La Salle St.
 Maher, Geo. W., 157 E. Erie St.
 Maiwurm, Arthur B., 82 W. Washington St.
 Mallinger, John, 3626 N. Racine Ave.
 Malmer, Eugene, 97 W. Park St., Aurora, Ill.
 Marienthal, Oscar B., 5124 University Ave.
 Martin, Edgar D., 104 S. Michigan Ave.
 Martini, Elisabeth A., 155 N. Clark St.
 Matteson, Victor Andre, 944 Leland Ave.
 Maupin, James M., Commercial Bldg., Alton, Ill.
 Mauran, John Lawrence, Chemical Bldg., St. Louis, Mo.
 McArthur, Albert C., 39 W. Adams St.
 McCall, Thomas, 843 Ridge Ave., Evanston, Ill.
 McCarthy, Jos. W., 139 N. Clark St.
 McClellan, Edward George, 7439 Cottage Grove Ave.
 McDonald, Luther W., 849 E. 73d St.
 McLane, C. D., 127 N. Dearborn St.
 Meldahl, Jens J., 104 S. Michigan Ave.
 Meredith, Davis D., 4819 N. Albany Ave.

IMPERIAL ROOFING TILES

We publish a working hand book entitled "A DETAILED REFERENCE FOR THE USE OF ARCHITECTS" concerning our product and shall be pleased to send this one hundred paged bound volume to any Illinois practicing architect who has not received a copy, upon application from him direct, without charge.

LUDOWICI-CELADON
COMPANY

104 South Michigan Avenue
CHICAGO ILLINOIS

- Meyer, Frederic H., 30 N. Dearborn St.
 Miller, Chas. A., 644 Clay Ave., Scranton, Pa.
 Miller, John W., 1650 Carmen Ave.
 Miller, Joseph A., 155 N. Clark St.
 Miller, Lee, 109 N. Dearborn St.
 Morehouse, M. J., 343 S. Dearborn St.
 Morgan, Chas. L., 104 S. Michigan Ave.
 Morrell, John 18 E. 3rd St., Sterling, Ill.
 Morrison, James R. M., 64 W. Randolph St.
 Morse, Harry Leon, 2639 W. Potomac Ave.
 Mundie, W. B., 39 S. La Salle St.
 Nadherny, Joseph J., 38 S. Dearborn St.
 Neebe, John K., 2522 Aubert Ave.
 Newell, Frank V., 1012 S. W. 13th Ave.,
 Miami, Florida.
 Newhouse, Henry L., 4630 Prairie Ave.
 Newman, E. M., 107 N. Clark St.
 Nimmons, Geo. C., 122 S. Michigan Ave.
 Norman, Andrew, 1531 Devon Ave.
 Nyden, John A., 196 N. State St.
 Oliver, Ralph H., 115 S. Dearborn St.
 Olsen, Leif E., 1515-155 N. Clark St.
 Olsen, Paul F., 127 N. Dearborn St.
 Ostergren, Robert C., 155 N. Clark St.
 Otis, William A., 6 N. Michigan Ave.
 Pearson, Gustav E., 1930 N. Keystone Ave.
 Perkins, Dwight H., 814 Tower Court.
 Perkins, Frank W., 7419 Stewart Ave.
 Perkins, Frederick W., 64 E. Van Buren St.
 Perry, Walter E., 212 E. Superior St.
 Peterson, Edward A., Swedish Am. Nat.
 Bank Bldg., Rockford, Ill.
 Pfeiffenberger, Geo. D., 102 W. 3rd St.,
 Alton, Ill.
 Pillsbury, Arthur L., Peoples Bank Bldg.,
 Bloomington, Ill.
 Pleins, Leo H., 554 S. Franklin St.
 Pond, Allen B., 64 E. Van Buren St.
 Pond, Irving K., 64 E. Van Buren St.
 Postle, D. E., 631 Van Nuys Bldg., Los An-
 geles, Calif.
 Powers, Horace S., 5 N. La Salle St.
 Prather, Fred V., 400 S. Michigan Ave.
 Preis, Carl G., 120 Broadway, New York,
 N. Y.
 Pridmore, J. E. O., 38 S. Dearborn St.
 Prindeville, Chas. H., 58 E. Washington St.
 Probst, Edward, 80 E. Jackson Blvd.
 Pruynt, William H., Jr., 122 S. Michigan Ave.
 Puckey, Francis W., 6 N. Michigan Ave.
 Rae, Robert, 431 Greenleaf Ave., Wilmette.
 Raeder, Henry, 20 W. Jackson Blvd.
 Rapp, George L., 190 N. State St.
 Reiger, Harry J., Booth Bldg., Springfield, Ill.
 Rezny, J. B., 2202 S. Crawford Ave.
 Rich, Harry F., 431 S. Dearborn St.
 Richards, H. H., 5467 Washington Blvd.
 Richardson, Jason F., Central Life Bldg.,
 Ottawa, Ill.
 Riddle, Herbert H., 122 S. Michigan Ave.
 Riddle, Lewis W., 122 S. Michigan Ave.
 Rinaker, John I., 1331 Noble St., Springfield,
 Ill.
 Rissman, Maurice B., 139 N. Clark St.
 Roberts, E. E., 82 W. Washington St.
 Robertson, David, 8 S. Dearborn St.
 Robinson, Argyle E., 5227 Harper Ave.
 Roedigger, F. W. C., 4936 Champlain Ave.
 Rohm, Wm., 138 N. La Salle St.
 Rosen, Richard O., 1151 S. 2nd St., Louis-
 ville, Ky.
 Rother, Eugene Paul, 2507 Cullom Ave.
 Rowe, Charles B., 619 E. Crescent Ave., Park
 Ridge, Ill.
 Rowe, Lindley P., 240 La Salle Bldg., Minne-
 apolis, Minn.
 Roy, Franz, 7817 S. Shore Drive.
 Royer, Joseph W., Flat Iron Bldg., Urbana.
 Ruttenberg, Albert M., 82 W. Washington
 St.
 Rusy, Anthony F., 1339 S. Avers Ave.
 Ryan, Wm., Jr., 154 W. Randolph St.
 Sandegren, A., 116 E. Oak St.
 Sanders, Lewis Miles, 3311 Wrightwood Ave.
 Saxe, Albert Moore, 64 E. Van Buren St.
 Schenck, Rudolph, 122 S. Michigan Ave.
 Schlacks, H. J., 721 N. Michigan Ave.
 Schmidt, R. G., 154 W. Randolph St.
 Schmidt, Hugo, 1165 N. Clark St.
 Schmidt, Richard E., 104 S. Michigan Ave.
 Schoenfeldt, Frank, 4058 W. Madison St.
 Schulzke, Wm. H., People's Bank Bldg.,
 Moline, Ill.
 Schwartz, Albert A., 118 N. La Salle St.
 Seator, S. M., 35 N. Dearborn St.
 Shattuck, W. F., 19 S. La Salle St.
 Shaw, Howard, 39 S. State St.
 Sheldon, Karl H., 400 N. Michigan Ave.
 Shopbell, Clifford, Furniture Bldg., Evans-
 ville, Ind.
 Slupkowski, Jos. A., 1263 N. Paulina St.
 Smith, Harold, 37 W. Van Buren St.
 Spencer, Charles B., 37 W. Van Buren St.
 Spencer, N. S., 37 W. Van Buren St.
 Spitz, Alexander H., 19 W. Jackson Blvd.
 Spitzer, Maurice, 115 S. Dearborn St.
 Stanhope, Leon E., 59 E. Madison St.
 Stanton, Frederick C. H., 621 Cornelia Ave.
 Stauduhar, George, 1608 21st St., Rock
 Island, Ill.
 Stern, Isaac S., 35 S. Dearborn St.



FIRST NATIONAL BANK, DETROIT, MICH.—ALBERT KAHN, *Architect*

Entire Exterior Indiana Limestone Furnished by
The CENTRAL EOLITIC STONE CO.
Cut Stone Contractors

Sales Office: 2126 South Kedzie Ave., Chicago, Ill.

Mill & General Office:
 Bloomington, Indiana

ESTIMATES FURNISHED.

Address Correspondence
 to Our Chicago Office

Strandel, Charles A., 118 N. La Salle St.
 Stuhr, William, 127 N. Dearborn St.
 Sturges, Howard Putman, 79 W. Monroe St.
 Sturm, Meyer J., 116 S. Michigan Ave.
 Sturnfield, C. H., 600 Blue Island Ave.
 Swern, Perry W., 19 S. La Salle St.
 Teesdale, Lawrence V., 20 Dodwin Rd.,
 Allendale, Rangoon, Burma.
 Teich, Frederick, 305 S. La Salle St.
 Teisen, Axel V., 4804 N. Kedzie Ave.
 Teutsch, Carl M., 2448 Calumet Ave.
 Thomas, Stafford F., 21 Woodside Ave., Am-
 herst, Mass.
 Tocha, Anton, 1225 N. Ashland Ave.
 Tomlinson, H. Webster, 717 Heggie Bldg.,
 Joliet, Ill.
 Uffendell, Wm. Gibbons, 39 S. State St.
 Urbain, Jules, Jr., 155 N. Clark St.
 Urbain, Leon F., 101 ave. Maurice Berteaux,
 Le Vesinet (S&O), Paris, France.
 Urbanek, Chas. A., 76 W. Monroe St.
 Vail, Morrison H., Dixon, Ill.
 Van Bergen, John S., Ravinia, Ill.
 Van der Meer, Wybe J., 214 Mead Bldg.,
 Rockford, Ill.
 Van Gunten, Orlando, 800 N. Clark St.
 Viehe-Naess, Ivar, 400 N. Michigan Ave.
 Visscher, Theodore C., 363 Lexington Ave.,
 New York, N. Y.
 Vitzthum, Karl M., 21 E. Van Buren St.
 Wallace, Chas. L., 227 Jefferson St., Joliet.
 Wallace, Dwight G., 6 N. Clark St.
 Wallace, Maurice R., 1264 N. Lincoln St.
 Waterman, H. H., 10 S. La Salle St.
 Watson, Jesse N., Chemical Bldg., St. Louis,
 Mo.
 Watson, Vernon S., 189 W. Madison St.
 Weber, Alfred P., 155 N. Clark St.
 Weber, Peter J., 343 S. Dearborn St.
 Webster, Chas. Woods, Cutting Bldg., Joliet.
 Weisfeld, Leo H., 133 W. Washington St.
 Weiss, John W., 53 W. Jackson Blvd.
 Wheelock, H. B., 64 W. Randolph St.
 White, Howard J., 1417-80 E. Jackson Blvd.
 White, James M., Prof., Administration
 Bldg., Urbana, Ill.
 Whitmeyer, Mark H., Central Nat. Bank
 Bldg., Peoria, Ill.
 Whitsitt, H. W., Peoples Bank Bldg., Mo-
 line, Ill.
 Williamson, W. G., 19 S. La Salle St.
 Wilmanns, August C., 35 S. Dearborn St.
 Winkel, Benno, care Colo. Southern Ry. Co.,
 Denver, Colo.
 Winslow, Benj. E., 2617 N. Richmond St.
 Woltersdorf, A. F., 138 N. La Salle St.
 Woodyatt, Ernest, 1045-209 S. La Salle St.
 Worthmann, Henry, 155 N. Clark St.
 Wright, Clark C., 122 S. Michigan Ave.
 Young, Thomas C., Arcade Bldg., St. Louis,
 Mo.
 Youngberg, John E., 30 N. Dearborn St.
 Zarnowiecki, Jos. C., 1859 W. Chicago Ave.
 Zippwald, Otto, Lemon Grove, San Diego
 County, California.

HONORARY MEMBERS

Clay, W. W., 538 S. Dearborn St.
 Goodnow, Charles N., 38 S. Dearborn St.
 Hill, Henry W., 138 N. La Salle St.
 Palmer, H. L., 19 S. La Salle St.
 Pfeiffer, Geo. L., Lemon City, Florida.
 Randolph, S. M., 106 Parkside Bldg., Oak
 Park.
 Shepardson, Francis W., Springfield, Ill.
 Wight, P. B., 677 Summitt Ave., Pasadena,
 Calif.

In Memoriam

FREDERICK BAUMANN
 HAROLD M. HANSEN
 JOHN M. SCHROEDER



Federal Lockers of
Glenview Golf Club

Not a Federal product
photograph



Federal
Shelving
at
H. Channon Co.

FEDERAL STEEL

FIXTURE COMPANY

WHERE QUALITY PREVAILS

LOCKERS AND SHELVING

CHICAGO

METAL FURNITURE

SHELVING LOCKERS

*Federal Products Are
Designed to Give
Better Service*

**Federal Steel
Fixture Co.**
CHICAGO

Warehouse: 4245 W. Homer Street
Sales Office: 610 Wrigley Bldg.



THE AMERICAN INSTITUTE OF ARCHITECTS

THE OCTAGON HOUSE, WASHINGTON, D. C.

Alabama.—*George B. Rogers, Van Antwerp Bldg., Mobile. †Eugene H. Knight, 1607 Empire Bldg., Birmingham.
Arkansas.—*Eugene J. Stern, Gazette Bldg., Little Rock; †Lawson L. Delony, 2407 Louisiana St., Little Rock.
Baltimore.—*Howard Sill, 11 E. Pleasant St.; †Laurence Hall Fowler, 347 N. Charles St.
Boston.—*Charles A. Coolidge, 122 Ames Bldg.; †Edward H. Hoyt, 220 Devonshire St.
Brooklyn.—*T. Edward Snook, 261 Broadway, New York City; Thos. E. Snook, Jr., 261 Broadway, New York City.
Buffalo.—*Charles S. Wood, 19 West Huron St.; Louis Greenstein, Prudential Bldg., Buffalo, 222 Ellicott Square, Buffalo.
Central New York.—*Walter H. Whitlock, Security Mutual Bldg., Binghamton; †W. V. Madden, 125 Sibley Block, Rochester.
Cincinnati.—*Gustave W. Drach, Union Trust Bldg.; †Jos. G. Stenkamp, Mercantile Library Bldg.
Cleveland.—*Charles W. Hopkinson, 900 Rose Bldg.; †W. W. Sabin, 1900 Euclid Bldg.
Colorado.—*Arthur A. Fisher, Century Bldg., Denver; †R. O. Pary, 407 Clarkston St., Denver.
Columbus.—*J. M. Bradford, Ohio State University; †Charles L. Inscho, Brunson Bldg.
Connecticut.—*Louis A. Walsh, 51 Leavenworth St., Waterbury; †Delbert K. Perry, City Hall, New Britain.
Dayton.—*Louis Lott, Commercial Bldg.; †H. J. Williams, 908-920 Mutual Home Bldg.
Florida.—*George L. Pfeiffer, Villa Florence, Lemon City, Fla. †Henrietta C. Dozier, Bisee Bldg., Jacksonville, Fla.
Georgia.—*F. Thornton Marye (acting), Alfriend Bldg., Atlanta; †Arthur Neal Robinson, 623 Candler Bldg., Atlanta.
Illinois.—*Albert M. Saxe, 64 E. Van Buren St., Chicago; †John A. Armstrong, 127 N. Dearborn St., Chicago.
Indiana.—In care of Herbert W. Foltz, 843-6 Lemcke Annex, Indianapolis, Ind.
Iowa.—*Charles A. Dieman, Granby Bldg., Cedar Rapids; †Eugene H. Taylor, 222 South Third St., Cedar Rapids.
Kansas City.—*H. F. Hoyt, 607 Reliance Bldg.; †Samuel Greenbaum, 216 Scarritt Bldg.
Kansas.—*Lorenz Schmidt, 121 Market St., Wichita; †Prof. Cecil F. Baker, Kansas State Agricultural College, Manhattan.
Kentucky.—*E. T. Hutchins, 409 Columbia Building, Louisville; †Val P. Collins, 624 Paul Jones Bldg., Louisville.
Louisiana.—*Victor Wogan, Title Guarantee Bldg.; †Solis Seiferth, Maison Blanche Bldg., New Orleans.
Michigan.—*D. J. V. Snyder, 1103 Union Trust Bldg., Detroit; †A. G. Donaldson, 1314 Penobscot Bldg., Detroit.
Minnesota.—*Harry T. Downs, 619 New York Life Bldg., Minneapolis. †Jerome Paul Jackson, 2309 First Ave. South, Minneapolis.

Montana.—*John G. Link, Billings; †W. R. Plew, Bozeman.
Nebraska.—*H. W. Meginnis, 533 Bankers Life Bldg., Lincoln; †J. D. Sandham, World-Herald Bldg., Omaha.
New Jersey.—*H. T. Stephens, United Bk. Bldg., Paterson, N. J.; †Hugh Roberts, 1 Exchange Place, Jersey City.
New York.—*Charles Butler, 56 West 45th St., New York; †Richmond H. Shreve, 215 West 57th St., New York.
North Carolina.—*William H. Lord, 17½ Church St., Asheville; †Earl G. Stillwell, Hendersonville.
Oregon.—*W. G. Purcell, 812 Spaulding Bldg., Portland; †George M. Post, 619 Railway Exch. Bldg., Portland.
Philadelphia.—*Geo. I. Lovatt, 416 Walnut St.; †Paul A. Davis, III, 1713 Sansom St.
Pittsburgh.—*S. F. Heckert, Bessemer Bldg.; †Stanley L. Roush, City-County Bldg.
Rhode Island.—*F. Ellis Jackson, 1216 Turk's Head Bldg., Providence; †Norman M. Isham, 915 Turk's Head Bldg., Providence.
San Francisco.—*G. A. Applegarth, 1800 Claus Speckles Bldg.; †J. S. Fairweather, 1001 Balboa Bldg.
South Carolina.—*Nat. Gaillard Walker, Rock Hill; †H. Olin Jones, Greenville.
Southern California.—*Edwin Bergstrom, 1129 Citizens National Bank Bldg., Los Angeles; †R. G. Hubby, 6412 Hollywood Boulevard, Los Angeles.
Southern Pennsylvania.—*Edward Leber, 42 West Market St., York; †W. B. Billmeyer, 268 East Market St., York.
St. Louis.—*W. L. Rathmann, 1501 Chemical Bldg.; †W. O. Mullgardt, Chemical Bldg.
Tennessee.—*Waek C. Jones, Porter Bldg., Memphis, Tenn.; B. S. Cairns, Scimitar Bldg., Memphis, Tenn.; †Joseph W. Holman, 701 Stahlman Bldg., Nashville.
Texas.—*D. F. Coburn, Dallas; †Roy E. Lane, Waco.
Toledo.—*Harry W. Wachter, 908 Nicholas Bldg.; †Charles A. Langdon, Nicholas Building.
Utah.—*Leslie S. Hodgson, 2255 Madison Ave., Ogden; †Taylor Woolley, McIntyre Bldg., Salt Lake City.
Virginia.—*Fiske Kimball, University of Virginia, Charlottesville; †C. J. Calrow, New Moulal Bldg., Norfolk.
Washington, D. C.—*Percy C. Adams, Woodward Bldg.; †L. P. Wheat, Jr., 808 Seventeenth St., N. W.
Washington State.—*Charles H. Alden, 358 Empire Bldg., Seattle; †H. O. Sexsmith, University of Washington, Seattle.
Wisconsin.—*Peter Brust, Free Press Bldg., Milwaukee; †W. W. Judell, 445 Milwaukee St., Milwaukee.
Worcester.—(Merged with the Boston Chapter, November 1, 1917.)
 *Presidents. †Secretaries.


STATES REQUIRING ARCHITECTURAL REGISTRATION

Information as to registration laws now in force in the following states may be obtained as follows:

California—State Board of Architecture, Phelan Bldg., San Francisco. **Colorado**—State Board of Examiners of Architects, Atlanta. **Idaho**—Department of Law Enforcement, Boise. **Illinois**—Department of Education and Registration, Springfield. **Louisiana**—State Board of Architectural Examiners, New Orleans. **Michigan**—State Board for Registration of Architects, Detroit. **Minnesota**—State Board of Architectural Examiners, St. Paul, Minn. **Montana**—Board of Architectural Examiners, Helena. **New Jersey**—State Board of Architects, Trenton. **New York**—State Board of Registration of Architects, Albany. **North Carolina**—State Board of Architectural Examination and Registration, Greens-

boro. **North Dakota**—State Board of Architecture, Bismarck. **Oregon**—State Board of Architectural Examiners, Portland. **Pennsylvania**—State Board of Examiners of Architects, Harrisburg. **South Carolina**—State Board of Architectural Examiners, Columbia. **Tennessee**—Examining Board for Architects and Engineers, Nashville. **Utah**—State Board of Architecture, Salt Lake City. **Virginia**—State Board for the Examination and Certification of Architects, Professional Engineers and Land Surveyors, Richmond. **Washington**—State Board for Registration of Architects, Olympia. **Wisconsin**—Board of Examiners of Architects, Madison. Such laws are pending in Indiana, Iowa, and Minnesota.

ANY Sash Operated!



No matter how difficult the conditions, we have a Sash-Operator to meet them.

One of our most generally used styles is illustrated, but we have plenty of others.

Especial attention is given in our designs to sturdy construction that will stand the strain of long, hard service.

Ask us to suggest the form that will best satisfy your needs. Full engineering co-operation will be gladly given.

TYPICAL INSTALLATIONS

U. S. Penitentiary — Leavenworth, Kan.
Goodyear Tire & Rubber Co. — Akron, Ohio
Bursch Sulzer Diesel Engine Co. — St. Louis
Nordyke-Marmion Auto Co. — Indianapolis
Standard Forgings Co. — Indiana Harbor, Ind.
Pennsylvania Lines — U. S. A.
Marshall Field & Co. — Chicago, Ill.
American Shipbuilding Co. — U. S. A.
Timken Roller Bearing Co. — Canton, Ohio
Carnegie Steel Co. — U. S. A.
Aluminum Ore Company of America — Bethlehem Steel Co.
Sparrows Point, Md.

Metallic Sash Operator Co.

Chestnut and 23rd Streets

ST. LOUIS, MO.

Members Illinois Chapter American Institute of Architects

OFFICERS FOR 1921-22

ALBERT MOORE SAXE, President.

FRANCIS W. PUCKEY, 1st Vice-President.

JOHN ARCHIBALD ARMSTRONG, Secretary.

EDWIN H. CLARK, 2d Vice-President.

RICHARD E. SCHMIDT, Treasurer.

Fellows.

Beaumont, George, 25 N. Dearborn St.

Berlin, Robert C., 19 S. La Salle St.

Clay, W. W., 538 S. Dearborn St.

Conway, Wm. H., 104 E. Side Sq., Springfield, Ill.

Dunning, N. Max, 310 S. Wabash Ave.

Fellows, Wm. K., 814 Tower Court.

Frost, Charles S., 105 S. La Salle St.

Helmle, George H., Ferguson Bldg., Springfield, Ill.

Holabird, William, 104 S. Michigan Ave.

Jensen, Elmer C., 39 S. La Salle St.

Llewellyn, Joseph C., 38 S. Dearborn St.

Maher, George W., 157 E. Erie St.

Mundie, W. B., 39 S. La Salle St.

Nimmons, George C., 122 S. Michigan Ave.

Otis, William A., 6 N. Michigan Ave.

Pashley, Alfred S., 431 S. Dearborn St.

Perkins, Dwight H., 814 Tower Court.

Perkins, Frederick W., 64 E. Van Buren St.

Pond, A. B., 64 E. Van Buren St.

Pond, Irving K., 64 E. Van Buren St.

Prindeville, Chas. H., 58 E. Washington St.

Quackenboss, L. G., 35 N. Dearborn St.

Roche, Martin, 104 S. Michigan Ave.

Schmidt, Richard E., 104 S. Michigan Ave.

Shaw, Howard Van Doren, 39 S. State St.

Spencer, Robert C., Jr., 5 N. La Salle St.

Wheelock, Harry B., 64 W. Randolph St.

Woltersdorf, Arthur F., 138 S. La Salle St.

Zimmerman, W. Carby, 64 E. Van Buren.

Clark, William J., 4850 Blackstone Ave.

Crowen, Samuel N., 400 N. Michigan Ave.

Curtis, N. C., University of Ill., Urbana, Ill.

Davidson, F. E., 53 W. Jackson Blvd.

Davis, George H., 527 Moss Ave., Peoria, Ill.

Day, Warren Wm., Peoria Life Bldg., Peoria, Ill.

Dean, Arthur R., 137 S. La Salle St.

De Golyer, Robert S., 7 S. Dearborn St.

DeMoney, Frank O., 5 N. La Salle St.

Dinkelberg, Fred'k P., 400 N. Michigan Ave.

Dippold, Albert P., 4747 Cottage Grove Ave.

Emerson, Frank N., Peoria Life Bldg., Peoria, Ill.

Fletcher, Robert C., 179 W. Washington St.

Fox, Charles E., 721 N. Michigan Ave.

Frazheim, Henderson Kenneth, 127 N. Dearborn St.

Fugard, John Reed, 212 E. Superior St.

Furst, Wm. H., 140 S. Dearborn St.

Granger, Alfred H., 619 N. Michigan Ave.

Guenzel, Louis, 111 W. Washington St.

Hall, Emery Stanford, 64 E. Van Buren St.

Hallberg, Lawrence G., 116 S. Michigan Ave.

Hamilton, John L., 814 Tower Court.

Hammond, Charles H., 64 E. Van Buren St.

Harris, Ralph C., 190 N. State St.

Hatzfeld, Clarence, 7 S. Dearborn St.

Heun, Arthur, 64 E. Van Buren St.

Hewitt, Herbert E., Peoria Life Bldg., Peoria, Ill.

Holabird, John A., 104 S. Michigan Ave.

Holden, Benj. Edwin, c/o F. A. Holden, 56 W. 45th St., New York City.

Holmes, Morris G., 8 S. Dearborn St.

Holsman, Henry K., 310 S. Wabash Ave.

Hoover, Ira Wilson, 1325 1st Nat'l Bank Bldg., San Francisco, Calif.

Hoskins, John M., 2837 W. Madison St.

Hosmer, Clare C., 133 W. Washington St.

Hulsebus, Bernhard L., Jefferson Bldg., Peoria, Ill.

Hussander, Arthur F., 25 N. Dearborn St.

Jillson, Byron H., 9111 S. Robey St.

Johnck, Frederick, 122 S. Michigan Ave.

Kohfeldt, Walter G., 400 N. Michigan Ave.

Llewellyn, Ralph C., 38 S. Dearborn St.

Lovell, Sidney, 30 N. Michigan Ave.

Lowe, Elmo C., 108 S. La Salle St.

MacBride, Edward E., 1101-64 E. Van Buren St.

Marshall, Benj. H., 721 N. Michigan Ave.

Marx, Samuel A., 1336 Washington Blvd.

Matteson, Victor A., 944 Leland Ave.

McCarthy, Joseph W., 139 N. Clark St.

Institute Members.

Alschuler, Alfred S., 28 E. Jackson Blvd.

Armstrong, John A., 127 N. Dearborn St.

Beers, Herbert P., 53 W. Jackson Blvd.

Beman, S. S., 108 S. La Salle St.

Bennett, Edward H., 80 Jackson Blvd.

Blake, Edgar Ovet, 403 Century Bldg., Evanston, Ill.

Bollenbacher, J. Carlisle, 108 S. La Salle St.

Brown, Arthur George, 109 N. Dearborn St.

Buckett, Arthur C., 1133 Park Ave., Wilmette.

Bullard, Clark Wesley, Peoria Life Bldg., Peoria, Ill.

Burnham, Daniel Hudson, 209 S. La Salle St.

Burnham, Hubert, 209 S. La Salle St.

Carpenter, Frank A., Rockford, Ill.

Carr, George Wallace, 122 S. Michigan Ave.

Cervin, Olaf Z., Rock Island, Ill.

Chatten, Melville C., 64 E. Van Buren St.

Church, Walter S., 157 W. Division St.

Clark, Edwin H., 8 E. Huron St.



Colonial Fireplace Company CHICAGO

EVERYTHING
for the
FIREPLACE


THE COLONIAL HEAD-THROAT-DAMPER



THE OLD WAY

→ THE HEART OF THE
HOME IS THE FIREPLACE

→ THE BRAINS OF THE
FIREPLACE ARE IN
THE COLONIAL HEAD
THROAT AND DAMPER



THE COLONIAL WAY

**The ONLY FIREPLACE DAMPER made which
Provides for EXPANSION and CONTRACTION**

Not merely a casting, but a number of castings assembled built together like a stove—reinforced with steel angle and constructed into the COLONIAL HEAD THROAT and DAMPER providing for EXPANSION and CONTRACTION and DURABILITY in itself. Overcomes warping of castings and prevents cracking of Fireplace Facings.

EASY TO SET—EASY TO OPERATE—MEETS ALL CONDITIONS

Eleven Sizes—Four Styles Operating. Blue Prints on Request
See Sweets' Index, Page 279

ANDIRONS	HOODS
GRATES	DAMPERS
SCREENS	ASH TRAPS
FIRE SETS	ASH PIT
FENDERS	DOORS
GAS and	COAL CHUTES
ELECTRIC	BRASS
LOGS	THRESHOLDS



ANDIRONS
GRATES

COLONIAL FIREPLACE COMPANY

4626 Roosevelt Rd.
CHICAGO, ILL.

Morehouse, Merritt J., 343 S. Dearborn St.
Nyden, John A., 196 N. State St.
Ostergren, Robert C., 155 N. Clark St.
Parsons, Wm. E., 1800 Ry. Exchange Bldg.
Pillsbury, Arthur L., Peoples Bank Bldg.,
Bloomington, Ill.

Pingrey, Roy C., 209 S. La Salle St.
Powers, Horace S., 5 N. La Salle St.
Pridmore, John E. O., 38 S. La Salle St.
Puckey, Francis W., 6 N. Michigan Ave.
Raeder, Henry, 20 W. Jackson Blvd.
Renwick, Edward A., 104 S. Michigan Ave.
Rinaker, John I., 1331 Noble Ave., Springfield, Ill.

Robinson, Argyle E., 5227 Harper Ave.
Root, John W., 1400-104 S. Michigan Ave.
Saxe, Albert M., 64 E. Van Buren St.
Schlacks, H. J., 721 N. Michigan Ave.
Schmid, Richard G., 154 W. Randolph St.
Shattuck, Walter F., 19 S. La Salle St.
Smith, Wm. J., 64 E. Van Buren St.
Stanhope, Leon E., 59 E. Madison St.
Sturges, Howard Putnam, 79 W. Monroe St.
Sturm, Meyer J., 116 S. Michigan Ave.
Swern, Perry W., 19 S. La Salle St.
Tallmadge, Thomas E., 189 W. Madison St.
Teich, Frederick J., 305 S. La Salle St.
Tomlinson, H. Webster, 717 Hegg'e Bldg.,
Joliet, Ill.

Vail, Morrison H., Dixon, Ill.
Van Bergen, John S., Ravinia, Ill.
Viehe-Naess, Ivar, 400 N. Michigan Ave.
Von Holst, Hermann V., 72 W. Adams St.
Walcott, Chester H., 8 East Huron St.
Waterman, H. H., 10 S. La Salle St.
Weber, Peter J., 343 S. Dearborn St.
Weiss, John W., 53 W. Jackson Blvd.
White, Prof. James M., U. of I., Urbana, Ill.
Whitmeyer, Mark H., Cent. Nat. Bank Bldg.,
Peoria, Ill.

Winslow, Benjamin E., 2617 N. Richmond.
Woodyatt, Ernest, 1045-209 S. La Salle St.
Wright, Clark C., 122 S. Michigan Ave.
Wuehrmann, Wm. G., El Paso, Texas.
Yardley, R. Waldo, 814 Tower Court.
Youngberg, John E., 30 N. Dearborn St.
Zimmerman, Ralph W., 64 E. Van Buren St.

Chapter Members.

Brabant, Gifford, 2717 N. Kedzie Ave.
Cady, Jeremiah Kiersted, 179 W. Washington St.
Childs, Frank A., 122 S. Michigan Ave.
Colcord, Albert E., 6143 St. Lawrence Ave.
Graham, Ernest R., Ry. Exchange Bldg.
Hall, Gilbert F., 1309 Astor St.
Mayo, Ernest A., 53 W. Jackson Blvd.
Ramey, George E., Champaign, Ill.

Associates.

Bentley, Harry H., 1124-104 S. Michigan Ave.
Blourke, Pierre, 2907 Washington Blvd.
Cheney, Howard L., 208 S. La Salle St.
Cook, Norman W., 1228 Victor Ave.

Course, Redmond P., 5123 Sheridan Rd.
Dillard, Frank G., 1449 Granville Ave.
Fairclough, Stanley D., 7011 Jeffrey Ave.
Fuller, Ravilo F., 1101 N. Dearborn St.
Holmes, Harold G., 151 E. Chicago Ave.
Horn, Benjamin A., 310 Safety Bldg., Rock
Island, Ill.
Jackson, Emery B., 1614, 134 S. La Salle St.
Kurzon, R. Bernard, 7 S. Dearborn St.
Lagergren, Gustav P., 7708 S. Hermitage
Ave.
Livingston, Clarence A., 1045 Rookery Bldg.
Maher, Phillip B., 157 E. Erie St.
Martin, Edwin D., 5 N. La Salle St.
McLaren, R. James, 1600 Old Colony Bldg.
Morgan, Charles L., 104 S. Michigan Ave.
Reed, Earl H., 108 N. Dearborn St.
Stoetzel, Ralph E., 431 S. Dearborn St.
Walcott, Russell S., 8 E. Huron St.
Work, Robert G., 220 S. Michigan Ave.

Honorary Members.


Hill, Henry W., 138 N. La Salle St.
Hutchinson, Charles L., 134 S. La Salle St.
Taft, Lorado, 6016 Ellis Ave.
Wacker, Charles H., 134 S. La Salle St.
Whitehouse, F. M., Manchester, Mass.
Wight, Peter B., 677 Summit Ave., Pasadena, California.

Affiliated Members.

Alpha Rho Chi, 624 E. Green St., University
of Illinois, Champaign, Illinois.
American Federation of Arts, 1741 N. Y.
Ave., Washington, D. C.
Art Institute of Chicago and Ferguson Fund,
"Trustees."
Chicago Architectural Club, Elmer J. Fox,
c/o Howard Shaw, 39 S. State St., Chicago,
Ill.
Illinois Society of Architects, H. L. Palmer,
Fin. Secy., 19 S. La Salle St., Chicago, Ill.
Chicago Association of Commerce, Arch.
Div., E. C. Jensen, 10 S. La Salle St.,
Chicago, Ill.
Chicago Chapter, Am. Ceramic Society, Fred
B. Ortman, 2525 Clybourn Ave., Chicago,
Ill.
Community Service of Chicago, 108 S. La
Salle St.
Chicago Society of Artists, Carl R. Krafft,
218 S. Wabash Ave., Chicago, Ill.
Renaissance Society of University of Chi-
cago, Mr. Robertson, Secy., Chicago Uni-
versity, Chicago, Ill.
Associated General Contractors of America,
111 W. Washington St., Chicago, Ill.
Western Society of Engineers, Edgar S.
Nethercut, 1735 Monadnock Blk., Chi-
cago, Ill.
Western Society of Sculptors, Anna L.
Matthews, 6016 Ellis Ave.



The Equipment Behind the Plan



For Dining Room, Restaurant, Cafeteria, Lunch Room—for every eating place and every Kitchen—Albert Pick & Company equipment is specified for economy, efficiency and durability. We provide everything and anything required. Architects, in specifying Albert Pick & Company equipment, assure themselves and their clients of securing the equipment that best meets their requirements. Recent examples of our service are the Chicago Beach Hotel (completely equipped), the Drake Hotel and the Sheridan Plaza Hotel.

Our Engineering Department will assist in the preparation of plans for any type of installation without fee or obligation.

Available for Architects are: Portfolio AE11—Restaurant, Cafeteria and Lunch Room Equipment, and Portfolio AE127—Kitchen Equipment.

ALBERT PICK & COMPANY

208-224 WEST RANDOLPH ST., CHICAGO, ILLINOIS

Furnishings and Equipment for Public Service

Chicago Architectural Club

ART INSTITUTE, CHICAGO

1921-22

Officers

ELMER J. FOX, President
CURT A. ESSER, Vice-President
CHARLES H. MARKEL, Treasurer
JOSEPH B. LINDQUIST, Secretary

Directors


H. W. ANDERSON
G. BARRY
C. W. FARRIER
S. A. KANE

Associate

C. H. SIERKS W. L. PRINGLE

Active Members.

Ablamowicz, S. V., 2937 N. Talman Ave.
Allen, Lawrence E., 7001 Union Ave.
Alschuler, Alfred S., 28 E. Jackson Blvd.
Anderson, A. W., 6554 Normal Ave.
Anderson, Edwin F., 2015 Howe St.
Anderson, Herbert F., 1434 Argyle St.
Anderson, S. D., Lake Forest, Ill.
Archer, Charles S., 834 E. 64th Place
Applebach, Henry, 2133 Fremont St.
Barnum, George L., 4846 Hutchinson St.
Barry, Gerald, Jr., 926 N. Hamlin Ave.
Beach, G. S., 4857 Calumet Ave.
Beck, D. W., 7212 Yates Ave.
Behrends, Edward, 299 Park Ave., River Forest, Ill.
Behrens, Elmer, 3429 N. Troy St.
Blouche, Pierre, 2907 Washington Blvd.
Braun, Isadore H., 13319 Baltimore Ave.
Brown, Arthur R., 204 S. Madison Ave., La Grange, Ill.
Buell, Temple H., 250 Laurel Ave., Highland Park, Ill.
Bultman, Wm. C., 604 Hannah Ave., Lake Forest, Ill.
Budina, A. D., 2753 Mildred Ave.
Burdett, Samuel, 6464 Dorchester Ave.
Burnham, Hubert, 209 S. La Salle St.
Callahan, Carl, 2503 N. Racine Ave.
Carlborg, R. H., 5512 N. Paulina St.
Carlson, Clifford, 2442 N. Lawndale Ave.
Carlson, Elmer C., 6827 S. Morgan St.
Carlson, Richard J., 915 Fletcher St.
Casse, E. Jackson, 59 E. Monroe St. (A. H. Andrews & Co.)
Cheetham, F. K., 18 W. Chestnut St.
Christiansen, Roy T., 5417 N. Paulina St.
Conner, G. D., 3657 Pine Grove Ave.
Collins, Harry B., 939 Eastwood Ave.
Cramer, Ambrose C., Lake Forest, Ill.
Crombie, R. A., 6652 Kenwood Ave.
Dady, William E., 606 S. Michigan Ave., c/o International Harvester Co.
Dando, Robert E., 5612 Prairie Ave.
Downton, Herbert E., 1340 N. Central Ave.
Dunning, N. Max, 310 S. Wabash Ave.
Eischen, R. M., 1544 Addison St.
Erickson, Allen E., 2916 Wilson Ave.
Esser, Curt A., 1264 Montrose Ave.
Esser, Paul F., 1304 Hood Ave.
Evans, Floyd, 5460 Woodlawn Ave.
Eiseman, F., 4329 N. Kostner Ave.
Farrier, C. W., 5700 Peoria St.
Fellows, Wm. K., 814 Tower Court
Fox, Elmer J., 39 S. State St.
Franklin, Robert L., 64 E. Van Buren St.
Gibian, E. H., 2010 Howe St.
Gliatto, Leonard J., 722 Drake Ave.
Graham, Ernest R., 80 E. Jackson Blvd.
Gylleck, Elmer A., 1614 N. La Salle St.
Hauser, D. W., 1160 E. 54th Place
Henderson, A. W., 5206 Union Ave.
Heun, Arthur, 64 E. Van Buren St.
Hodgdon, Fred M., 1418 Lunt Ave.
Hoepfner, E. A., Brownsville, Cal.
Hougaard, Perry V., Elmhurst, Ill.
Hulfield, Jos., 4105 N. Mansfield Ave.
Jensen, Elmer C., 39 S. La Salle St.
Johnson, Ignwald L., 112 S. Homan Ave., Apt. 2
Johnson, Reuben H., 1445 Farragut Ave.
Kalthoff, F., Jr., 453 Fullerton Parkway
Kane, J. A., 1732 S. Michigan Ave.
Kennedy, Everatt L., 317 S. Maple Ave.
Klinger, E. A., 2628 Prairie Ave.
Knezicek, Wm. K., 1508 S. Keeler Ave.
Kruchton, C. K., 619 N. Michigan Ave. (A. Granger)
Larson, G. E., 4736 N. Bernard St.
Lawrence, A. J., 123 W. Madison St.
Leavell, John C., 6047 Kimbark Ave.
Ledebuhr, A. E., 6447 Rhodes Ave.
Lehman, L. E., 3307 Lemoyne Ave.
Le Vique, E. J., 4824 Champlain Ave.
Lewin, Edward P., 919 S. Irving Ave.
Lilleskau, John, 2447 Ballou St.
Lindbald, Alfred G., 2349 S. Clifton Park Ave.
Lindeberg, G. L., 11 N. 4th Ave., Maywood, Ill.
Lindquist, Jos. B., 3923 Grand Blvd.
Llewellyn, Ralph C., 38 S. Dearborn St.
Loeb, J., 1216 N. Shore Ave.
Lundberg, D. R., 928 Sheridan Rd.
Maher, Harry E., 6611 Minerva Ave.
Maher, Phillip B., 157 E. Erie St.
Manasse, DeWitt J., 1534 N. Maplewood Ave.
Markel, Charles H., 608 Sherman Ave Evanston, Ill.
Mayer, A. G., 190 N. State St. (Rapp & Rapp).
Maynard, Henry S., Jr., 64 W. Randolph St.
Malmquist, B., 1314 W. 64th St.
McCarthy, C. A., 5174 Indiana Ave.
McCoughy, W. F., Jr., 222 W. Cresent Ave., Park Ridge, Ill.
McConville, L. E., 6014 S. Carpenter St.



The "White" Door Bed



The "White" Door Bed is a *real* bed mechanically adjusted to smaller space—it is the only disappearing bed that can be equipped with a box spring. In comfort, appearance and durability it is equaled only by the finer type of stationary beds.

The "White" Door Bed eliminates wasted space, reduces building cost and increases rental value in Apartment Buildings, Apartment Hotels, Hotels, Clubs, Y. M. C. A's, Y. W. C. A's, Dormitories, Private Homes, etc. Complete furnishing for these establishments is a specialized service of Albert Pick & Company—we provide *everything* required, at a saving.

Ask for Portfolio AE130—The "White" Door Bed and Space-Saving Devices and Portfolio AE120—Complete Furnishings for Hotels, Apartment Hotels, Institutions, Etc.

ALBERT PICK & COMPANY

208-224 WEST RANDOLPH ST., CHICAGO, ILLINOIS

Furnishings and Equipment for Public Service

McGrath, Paul J., 845 Lakeside Place.
Monberg, H. Lawrence, 2505 N. Kedzie Ave.

Monberg, Otto, 3251 Belden Ave.
Morden, W. W., 5713 Drexel Ave.
Morgan, Charles L., 104 S. Michigan Ave.
Morgan, Harry T., 5820 W. Superior St.
Morphett, Archibald S., 6018 Harper Ave.
Mueller, H. E., 3715 Rokeby St.
Nedved, Geo. M., 2252 S. St. Louis Ave.
Newbold, Roy E., 2457 Sunnyside Ave.
Nimmons, George C., 122 S. Michigan Ave.

Norling, E., 4848 Cortez St.
Okeberg, E. N., 6229 Ingleside Ave.
Oldefest, Edward G., 11 E. Huron St.
Olson, E., 5445 S. Wells St.
Orth, Gustav, 664 Melrose St.
Poetsch, W. R., 4737 Dover.
Pringle, W. L., 1101-122 S. Michigan Ave.
Quinn, J. Edwin, 123 W. Madison St.
Rabig, C. E. K., 104 S. Michigan Ave.
(Holabird & Roche)

Rapp, George L., 190 N. State St.
Rehder, H. G. A., 2037 Fletcher St.
Rippel, Fred O., 4715 Flournoy St.
Rognstad, Sigurd A., 845 N. Leclair Ave.
Ross, Torey, Jr., 2934 N. Whipple St.
Rowe, C. B., 619 E. Crescent Ave., Park Ridge, Ill.
Ruge, P. H., 3934 N. Kostner Ave.
Sandegren, Andrew, 116 E. Oak St.
Sandstrom, R. S., 1342 Wunnamac Ave.

Savage, C. E., 11 E. Huron St.
Schierhorn, J., 4458 N. Whipple St.
Schlossman, N. J., 6209 S. Park Ave.
Schiewe, Ed. A., 1627 Crossing St.
Schimck, A. F., 1420 S. Ashland Ave.
Seabloom, Harry R., 2509 Kimball Ave.
Sevic, Wm., 1644 Blue Island Ave.
Sieja, E. W., 1851 N. Harding Ave.
Sierks, Charles H., 1505 Norwood St.
Silbert, I. J., 3141 Lexington St.
Sillani, Muzio, 2515½ N. Clark St.
Stanton, F. C. H., 621 Cornelia Ave.
Steinborn, Edward, 1047 N. Richmond Ave.
Swensson, Walter, 488 Grant Place
Taylor, Howell, 4040 Ellis Ave.
Thomsen, F. T., 650 Pierce St., Gary, Ind.
Thorud, Bet M., 3340 Wilson Ave.
Ticknor, James H., 45 Bellevue Place
Turner, J. W., 2193 Turner Ave.
Vesley, William J., 240 E. Huron St.
Wagner, Fritz, Jr., 561 Hawthorne Lane, Winnetka.
Wall, R. J., 2330 N. Halsted St.
Walker, Frank C., 20 W. Jackson Blvd.
Wallace, M. R., 1264 N. Lincoln St.
Webber, A. M., 1805 Wesley Ave., Evanston, Ill.
Webster, Maurice, 1403 Maple Ave., Evanston, Ill.
Wiersba, Alwin, 18 N. Lockwood Ave.
Wilkins, S. W., Pekin, Ill., c/o A. Laupett
Woolson, Theron, 615 Greenwood Ave., Glenco, Ill.
Wright, Wm. C., 7542 Harvard Ave.

Allied Members.

Armstrong, John Archibald, 127 N. Dearborn St.
Bannister, George S., 115 S. Dearborn St.
Beman, S. S., 108 S. La Salle St.
Bennett, Edward H., 1800-80 E. Jackson Blvd.
Berlin, Robert C., 19 S. La Salle St.
Blake, Edgar O., 403 Century Bldg., Evanston, Ill.
Bollenbacher, J. C., 108 S. La Salle St.
Capraro, Axel V., 72 W. Washington St.
Carnegie, Wm. C., 189 W. Madison St.
Charvat, Anthony, 2621 Millard Ave.
Chatten, Melville C., 64 E. Van Buren St.
Christensen, John C., 3255 Evergreen Ave.
Clark, Edwin H., 8 E. Huron St.
Clark, Wm. Jerome, 4850 Blackstone Ave.
Cloyes, F. O., 400 N. Michigan Ave.
Coffin, Arthur, 39 W. Adams St.
Davidson, F. E., 53 W. Jackson Blvd.
De Arment, F. H., 37 Everett Bldg. Akron, Ohio
De Golyer, Robert S., 7 S. Dearborn St.
De Money, F. O., 5 N. La Salle St.
Dougherty, F. E., 35 N. Dearborn St.
Dreyer, Detlef J., 78 Patton Ave., Asheville, N. C.
Eichberg, S. Milton, 64 W. Randolph St.
Faulkner, Chas. D., 140 S. Dearborn St.
Flaks, Francis A., 2743 W. 22nd St.
Fletcher, Robert C., 179 W. Washington St.
Foster, Arthur, 155 N. Clark St.


Fortin, Joseph T., 600 Blue Island Ave.
Fox, Charles E., 721 N. Michigan Ave.
Fox, John J., 38 S. Dearborn St.
Fox, Wm. Paul, 38 S. Dearborn St.
Franzheim, H. Kenneth, 127 N. Dearborn St.
Granzer, Alfred, 619 N. Michigan Ave.
Green, H. H., 308 S. Wabash Ave.
Greengard, B. C., 619 N. Michigan Ave.
Guenzel, Louis, 111 W. Washington St.
Hall, Emery Stanford, 64 E. Van Buren St.
Hall, Gilbert P., 1309 Astor St.
Hamilton, John L., 814 Tower Court
Hammond, Chas. Herrick, 64 E. Van Buren St.
Harris, Ralph C., 190 N. State St.
Hatzfield, Clarence, 7 S. Dearborn St.
Heinz, Lorenz, 128 N. La Salle St.
Henschien, H. Peter, 37 W. Van Buren St.
Hewitt, Herbert E., Peoria Life Bldg., Peoria, Ill.
Hine, Cicero, 3221 Broadway
Hodgdon, Charles, 134 S. La Salle St.
Holabird, John A., 104 S. Michigan Ave.
Holabird, Wm., 104 S. Michigan Ave.
Holmes, Morris G., 8 S. Dearborn St.
Holsman, Henry K., 310 S. Wabash Ave.
Hubbard, Archie H., 205 S. Madison Ave., La Grange, Ill.
Hyde, Robert M., 8 S. Dearborn St.
Jillson, Byron H., 9111 S. Robey St.
Joy, S. Scott, 2001 W. 39th St.

MIDWEST HARDWARE CO.

Distributors of




LOCKS and HARDWARE



Importers of
French and
English
Art
Hardware

Complete Systems
of Cranes, Hoists,
Trolleys.

Electric Industrial
Trucks.



Sales Office

56 West Randolph Street - Chicago, Ill.

TELEPHONES: STATE 6417 AND 6418

Koenigsberg, Nathan, 8 S. Dearborn St.
Lagergren, Gustav P., 7708 S. Hermitage Ave.

Layer, Robert, 19 S. La Salle St.
Lehle, Louis, 3810 Broadway
Leviton, Morton, 53 W. Jackson Blvd.
Levy, Alex L., 111 W. Washington St.
Lewis, Le Roy, Jr., 104 S. Michigan Ave.
Llewellyn, Joseph C., 38 S. Dearborn St.
Lovdall, George C., 25 N. Dearborn St.
Lowe, Elmo C., 108 S. La Salle St.
Maher, George W., 157 E. Erie St.
Mallinger, John W., 3626 N. Racine Ave.
Marshall, Benjamin H., 721 N. Michigan Ave.

Matteson, Victor Andre, 944 Leland Ave.
McCarthy, Joseph W., 139 N. Clark St.
McLaren, Robert J., 37 W. Van Buren St.
Morehouse, Merritt J., 343 S. Dearborn St.
Morrison, J. R. M., 64 W. Randolph St.
Neebe, John K., 2522 Aubert Ave.
Nyden, John A., 190 N. State St.
Ostergren, Robert C., 155 N. Clark St.
Palmer, H. L., 19 S. La Salle St.
Parson, Wm. E., 80 E. Jackson Blvd.
Perkins, Dwight H., 814 Tower Court
Pfeiffer, George L., Lemon City, Florida
Pingrey, Roy E., 209 S. La Salle St.
Pleins, Leo H., 544 S. Franklin St.
Powers, Horace S., 5 N. La Salle St.
Raeder, Henry, 20 W. Jackson Blvd.
Renwick, Edw. A., 104 S. Michigan Ave.
Riddle, Herbert H., 122 S. Michigan Ave.
Riddle, Louis W., 122 S. Michigan Ave.
Roberts, E. E., 82 W. Washington St.
Robinson, Argyle E., 5227 Harper Ave.
Roche, Martin, 104 S. Michigan Ave.
Root, L. P., 104 S. Michigan Ave.

Rother, Eugene P., 2507 N. Cullom Ave.
Rowe, L. P., La Salle Bldg., Minneapolis, Minn.

Royer, J. W., Flat Iron Bldg., Urbana, Ill.
Saxe, Albert Moore, 64 E. Van Buren St.
Shattuck, Walter F., 19 S. La Salle St.
Sheldon, Karl H., 400 N. Michigan Ave.
Spencer, Charles B., 37 W. Van Buren St.
Spencer, N. S., 37 W. Van Buren St.
Spitzer, Maurice, 115 S. Dearborn St.
Stanhope, Leon E., 59 E. Madison St.
Sturm, Meyer J., 116 S. Michigan Ave.
Sturnfield, Charles H., 600 Blue Island Ave.

Sturges, Howard P., 79 W. Monroe St.
Tallmadge, Thomas E., 189 W. Madison St.
Teich, Frederick J., 305 S. La Salle St.
Teisen, Axel V., 4804 N. Kedzie Ave.
Thisslew, Charles, 4433 N. Paulina St.
Tomlinson, Henry Webster, 717 Heggie Bldg., Joliet, Ill.

Uffendell, W. Gibbons, 39 S. State St.
Viehe-Naess, Ivar, 400 N. Michigan Ave.
Vitzthum, Karl M., 21 E. Van Buren St.
Weber, Alfred P., 155 N. Clark St.
Weiss, John W., 53 W. Jackson Blvd.
Wheelock, Harry B., 64 W. Randolph St.
White, Howard J., 80 E. Jackson Blvd.
White, James M., Prof., Administration Bldg., Urbana, Ill.

Wilmanns, August C., 35 S. Dearborn St.
Woodyatt, Ernest, 1045-209 S. La Salle St.
Work, Robert, 220 S. Michigan Ave.
Yardley, Ralph W., 814 Tower Court
Youngberg, John E., 30 N. Dearborn St.
Zimmermann, Ralph W., 64 E. Van Buren St.

Non-Resident Members.

Ashton, R. J., Salt Lake City, Utah.
Chase, Robert, Janesville, Wis.
Davis, Frank L., 1713 Flatiron Bldg., New York, N. Y.
Gillette, E. F., 628 St. John St., Pasadena, Calif.
Hoepfner, E. A., Brownsville, California
Larson, Roy, 3322 Walnut St., Philadelphia, Pa.
Matthes, Carl E., Biloxi, Miss.
McGrew, Kenneth A., Philadelphia, Pa.
Meadowcroft, Miner T., 710 Washington Arcade, Detroit, Mich.
Milliken, H. O., New York City.

Morin, H. J., Detroit, Mich.
Mork, R., Okmulgee, Okla.
Pastel, Alfred H., Springfield, Ill.
Norske, Helmut F.
Schuchardt, William H., 268 Knapp St., Milwaukee, Wis.

Somlyo, J., Peoria, Ill.
Spencer, C. B., San Francisco, Calif.
Wakeness, Leonard, New York, N. Y.
Wamness, L. B., New York City.
Williams, Paul Gilmore, Carew Bldg., Cincinnati, Ohio.
Zimmerman, A. G., New York City.

Honorary Members.

Allen, John K., Salisbury Road, Brookline, Mass.
Blake, Theodore L., 225 Fifth Ave., New York, N. Y.
Clark, Robert, Chicago, Ill.
Clow, William E., Harrison & Franklin Sts., Chicago.
Elcock, Edward G., 4806 Grand Blvd.
Gates, William D., 2008 Peoples Gas Bldg.
Gay, Henry Lord, McNeese Bldg., San Diego, Calif.

Lowrie, Harry, Caxton Bldg., Omaha, Neb.
McLean, Robert C., Western Architect, Minneapolis, Minn.
Mundie, William B., 39 S. La Salle St., Chicago.
Pond, Irving K., 1109 Steinway Hall, Chicago.
Puckey, Francis Williard, 6 N. Michigan Ave., Chicago.
Sullivan, Louis H., 1808 Prairie Ave., Chicago.
Taft, Lorado, 6016 Ellis Ave., Chicago.

WELLER

CONVEYING MACHINERY

To Handle the Raw Materials or Finished Products

GIVES THE SERVICE



WE MAKE

Apron Conveyors
Belt Conveyors
Chain Conveyors
Drag Conveyors
Spiral Conveyors
Bucket Elevators
Barrel Elevators
Package Elevators
Portable Elevators
Storage Bins
Coal and Ash Handling
Equipment
Heavy Sheet Metal
Work
Structural Steel Work
Etc.

For Over Thirty Years

The Weller Manufacturing Co. has made material handling machinery which is doing duty in a great number of the largest as well as small industrial plants in the world—our organization is fully equipped to take care of any material handling proposition put up to them.

Without Obligation on Your Part

Our engineers are at your service to assist and suggest the equipment best adapted to your requirements.

WELLER MFG. CO.

1820-1856 N. Kostner Ave.

CHICAGO, ILL.

Phone Albany 4200

BUILDING CONSTRUCTION EMPLOYERS' ASSOCIATION OF CHICAGO

807-808-809-810 Chamber of Commerce Bldg.

EDWARD HAUPT, President

GEO. MEHRING, 1st Vice-Pres.

SUMNER SOLLITT, 2nd Vice-Pres.

THOS. J. McNULTY, 3rd Vice-Pres.

A. H. GROTEFELD, 4th Vice-Pres.

E. F. PIERCE, Treasurer

E. M. CRAIG, Secretary

ASSOCIATIONS AFFILIATED WITH THE BUILDING CONSTRUCTION EMPLOYERS' ASSOCIATION OF CHICAGO

Builders' Association of Chicago.
Chicago Mantle & Tile Contractors' Association.
Chicago Marble Dealers' Association.
Chicago Master Plumbers' Association.
Chicago Master Steam-Fitters' Association.
Chicago Mosaic & Terrazzo Dealers' Association.
Composition Floor Manufacturers' Assn.
Concrete Contractors' Association.
Cut Stone Contractors' Association.
Decorating & Painting Contractors of Chicago.
Electrical Contractors' Association.
Employing Lathers' Association.

Employing Plasterers' Association.
Evanston-Wilmette-Kenilworth-Winnetka-Glencoe Master Plumbers' Assn.
Illinois Fireproof and Manufacturing Contractors' Association.
Iron League of Chicago.
Lighting Fixture Employers.
Master Floor Manufacturers' Association.
Master Roofers Association of Chicago.
Plate and Window Glass Jobbers
Pipe and Boiler Covering Employers' Association.
Sheet Metal Contractors' Association.
United Glass Manufacturers' Association.
Woodworkers' Employers' Association of Chicago.

MEMBERS OF EXECUTIVE BOARD—1921

L. Andersen
Andersen & Armstrong
H. N. Archibald
Vermont Marble Co.
V. M. Barbour
M. W. Powell Co.
Edgar S. Belden
George A. Fuller Co.
R. S. Blome
Blome-Sinek Co.
C. B. Borchardt
Standard Mosaic Tile Co.
A. E. Coleman
Ornamental Iron
H. J. Dettmers
Farwell Cornice Co.
John A. Dorsey
Hulbert & Dorsey
C. G. Fanning
C. G. Fanning & Co.
B. J. Farwell
Plumbing
O. C. FERENS
Keasbey Mattison Co.
W. H. Frazier
Velvetile Floor Co.
W. B. Graves
Graves Heating Co.
H. W. Grebe
Central Asbestos & Magnesia Co.
John Griffiths
John Griffiths & Son Co.

S. L. Haas
Advance Heating Co.
J. A. Hammett
National Fireproofing Co.
E. Haupt
Strobel Steel Construction Co.
W. H. Helmerich
Ornamental Glass
G. Hottinger
Northwestern Terra Cotta Co.
E. V. Johnson
E. V. Johnson Co.
O. W. Jovien
Steamfitter
T. F. Keating
M. Keating & Sons Co.
L. W. Kesling
Andres Stone & Marble Co.
W. G. Kimball
Pittsburgh Glass Co.
H. C. Knisely
Harry C. Knisely Co.
A. Lanquist
Lanquist & Illsley Co.
Jas. McCarty
McCarty Bros.
Wm. McGuineas
United Electrical Con. Co.

T. J. McNulty
McNulty Brothers Co.
George Mehring
Mehring & Hanson Co.
P. M. Murphy
Murphy Plumbing Co.
Henry Newgard
Henry Newgard & Co.
N. J. Nelson
W. P. Nelson Co.
F. M. Novak
Novak Mosaic Co.
Jas. Park
Steamfitting
A. H. Peterson
Thompson-Starrett Co.
E. F. Pierce
C. Everett Clark Co.
J. N. Pierce
Pierce Electric Co.
A. C. Preble
Harris-Preble Door Co.
Oscar A. Reum
Zander-Reum Co.
W. A. Riesch
Central Chandelier Co.
J. P. Rising
Rising Decorating Co.
Geo. L. Rood
Steamfitting

O. W. Rosenthal
O. W. Rosenthal-Cornell Co.
R. G. Saxer
Plumbing
C. W. Simon
Interior Tiling Co.
T. P. Shean
Shean Steel Window Co.
Sumner Sollitt
Sumner Sollitt Co.
W. W. Springer
North Chicago Roofing Co.
Carl Stein
Stein, Ebertshaeuser & Co.
J. P. Sullivan
Painting
E. A. Thomas
Thomas Elevator Operating Co.
J. P. Waddell
A. H. Revell Co.
A. C. Warren
Hoeffer & Co.
A. E. Wells
Wells Bros. Constr. Co.
A. E. Wernle
North Shore Stop Co.
Chas. L. West
West Woodworking Co.
H. E. Williams
Williams-Wendt Co.

EXECUTIVE COMMITTEE.

Wm. McGuineas
W. G. Kimball
E. F. Pierce
H. C. Knisely

John Griffiths
A. C. Warren
Geo. Mehring
T. J. McNulty

A. E. Coleman
A. Lanquist
E. V. Johnson
Edward Haupt

Oscar A. Reum
A. E. Wells
Sumner Sollitt
Edgar S. Belden

ESTABLISHED 1870

PHONE HARRISON 7111



ASPHALT MASTIC FLOORS
FOR
RAILROAD TERMINALS, FREIGHTHOUSES
WAREHOUSES, FACTORIES
SCHOOLS, COLLEGES

**ACID-PROOF
ASPHALT FLOORS**

Chemical Plants
Acid Manufacturing
Plants
Engravers and Etching
Plants
Plating Plants
Vinegar and Pickle
Plants
Fruit Preserving Plants

FLOORS INSTALLED

IN ALL
PARTS
OF U. S.
AND
CANADA

**ASPHALT MASTIC
WATER ROOFING**

Bridges
Viaducts
Sidewalks
Driveways
Floors
Concourses

ASPHALT MATERIALS

Fulton 1870 Brand Asphalt Mastic
Fulton 1870 Brand Acid Proof Mastic
Fulton 1870 Brand Water Proofing Mastic
Fulton 1870 Brand Pure Asphalts
Fulton 1870 Brand Asphalt Paints

MAIN OFFICES

709-10 Monadnock Block
CHICAGO, ILLINOIS

PLANTS

CLEARING, ILLINOIS
CHICAGO, ILLINOIS

50 YEARS OF SERVICE

THE ASSOCIATED BUILDERS OF CHICAGO

133 WEST WASHINGTON ST., ROOMS 1318

PHONE, FRANKLIN 4480

CHICAGO

OFFICERS:

ANDREW LANQUIST.....	<i>President</i>
GERHARDT F. MEYNE.....	<i>Vice-President</i>
FRED KLIPPEL.....	<i>Secretary</i>
H. J. COHLGRAFF.....	<i>Asst. Secretary</i>
H. B. BARNARD.....	<i>Treasurer</i>
WM. SCHLAKE.....	<i>Manager</i>
WM. MCKINLEY.....	<i>Asst. Manager</i>

DIRECTORS:

FRED BULLEY	J. W. KINNARE
F. M. STRESENREUTER	O. O. CARPENTER
HARRY HOMEWOOD	WM. E. SALOMON
FRED E. BROCKOB	H. D. MORELAND
WM. A. ILLSLEY	FRED KIPP
S. N. NIELSEN	CHAS. G. FANNING

THOS. McARTHUR

Total membership is approximately 817, and enters into agreements with the following trades:

Bricklayers and Stone Masons Union
Hod Carriers and Common Laborers Union
Stone Derrickmens Union
Carpenters Union
Stone Cutters Union

CARPENTERS' ARBITRATION BOARD

WILLIAM SCHLAKE, *Chairman*

L. A. ASHBECK	F. E. DOHERTY
WM. J. SCOWN	R. F. WILSON

MASONS' ARBITRATION BOARD

WILLIAM SCHLAKE, *Chairman*

J. W. SNYDER	JOS. NEUNKIRCHEN
J. E. ERICSSON	ALEXANDER SHAND



Deals Hotel, Chicago, Ill.

Arcade Steam Heating Co., Heating Contractors

ARCADE VAPOR VACUUM HEATING SYSTEM

Installed Complete by

Arcade Steam Heating Co.

JOHN J. BOYLSON, Pres.

126 West Kinzie Street

Phone: Main 4208

CHICAGO, ILL.

"THE ILLINOIS ARCHITECTURAL ACT"

ARCHITECTS LICENSE LAW STATE OF ILLINOIS

For an Act to provide for the licensing of architects and to regulate the practice of architecture as a profession and to repeal certain Acts therein named.

Section 1. Be it enacted by the People of the State of Illinois, represented in the General Assembly: It shall be unlawful for any person to practice architecture or advertise or put out any sign or card or other device which might indicate to the public that he or she is entitled to practice as an architect, without a certificate of registration as a registered architect duly issued by the Department of Registration and Education under this Act, and as provided for in the civil administrative code of Illinois.

Sec. 2. Any one, or any combination of the following practices by a person shall constitute the practice of architecture, namely: The planning or supervision of the erection, enlargement or alteration of any building or buildings or of any parts thereof, to be constructed for others. A building is any structure consisting of foundations, floors, walls, columns, girders, beams and roof, or a combination of any number of these parts, with or without other parts.

Sec. 3. No corporation shall be licensed to practice architecture in this State or be granted a certificate of registration under this Act, but it shall be lawful for a stock company or a corporation to prepare drawings, plans and specifications for buildings and structures as defined in this Act which are constructed, erected, built, or their construction supervised by such stock company or corporation, provided that the chief executive officer or managing agent of such stock company or corporation in the State of Illinois shall be a registered architect under this Act; And, provided, further, that the supervision of such buildings and structures shall be under the personal supervision of said registered architect and that such drawings, plans and specifications shall be prepared under the personal direction and supervision of such registered architect and bear the stamp of his official seal.

It shall be lawful, however, for one or more registered architects to enter into a partnership with one or more licensed structural engineers, licensed under the laws of this State, for the practice of their professions.

Sec. 4. Nothing contained in this Act shall prevent the draftsmen, students, clerks of works, superintendents and other employees of those lawfully practicing as registered architects under the provisions of this Act, from acting under the instruction, control or supervision of their employers, or to prevent the employment of superintendents of the construction, enlargement or alteration of buildings or any parts thereof, or prevent such superintendents from acting under the immediate personal supervision of the registered architect by whom the plans and specifications of any such building, enlargement or alteration were prepared. Nor shall anything contained in this Act prevent persons, mechanics or builders from making plans, specifications for or supervising the erection, enlargement or alteration of buildings or any parts thereof to be constructed by themselves or their own employees for their own use, provided that the working drawings for such construction are signed by the authors thereof with a true statement thereon of their relation to such construction and that the makers thereof are not architects.

Provided nothing in this Act contained shall be held or construed to have any application to any building, remodeling or repairing of any building or other structure outside of the corporate limits of any city or village, where such building or structure

is to be, or is used for residential or farm purposes, or for the purposes of outbuildings or auxiliary buildings in connection with such residential or farm premises, nor shall said Act apply to any building remodeling or repairing of any building or structure within the corporate limits of any city or village, where the total cost of said building, remodeling or repairing does not exceed the sum of seventy-five hundred dollars.

Sec. 5. Any person who is twenty-one years of age and of good moral character is qualified for an examination for a certificate of registration as a registered architect, provided he or she has graduated from a high school or secondary school, approved by the Department of Registration and Education, or has completed an equivalent course of study as determined by an examination conducted by the Department of Registration and Education, and has subsequently thereto completed such course in mathematics, history and language, as may be prescribed by said Department, and has had at least three years' experience in the office or offices of a reputable architect or architects.

Sec. 6. Upon payment of the required fee, an applicant who is an architect, registered or licensed under the laws of another state or territory of the United States, or of foreign country or province, may, without examination, be granted a certificate of registration as a registered architect by the Department of Registration and Education in its discretion upon the following conditions:

(a) That the applicant is at least twenty-one years of age, of good character and temperate habits; and

(b) That the requirements for the registration or licensing of architects in the particular state, territory, county or province, were, at the date of the license, substantially equal to the requirements then in force in this State.

Sec. 7. Every person who desires to obtain a certificate of registration shall apply therefor to the Department of Registration and Education in writing, upon blanks prepared and furnished by the Department of Registration and Education. Each application shall be verified by the applicant under oath and shall be accompanied by the required fee.

Sec. 8. The Department of Registration and Education shall hold examinations of applicants for certificates of registration as registered architects at such times and places as it may determine.

The examination of applicants for certificates of registration as registered architects shall consist of written tests and shall embrace the following subjects:

(a) The planning, designing and construction of buildings.

(b) The strength of building materials.

(c) The principles of sanitation and ventilation as applied to buildings.

(d) The ability of the applicant to make practical application of his knowledge in the ordinary professional work of an architect and in the duties of a supervisor of mechanical work on buildings.

The Department of Registration and Education may by rule prescribe additional subjects for examination.

Sec. 9. Whenever the provisions of this Act have been complied with by an applicant the Department of Registration and Education shall issue a certificate of registration to the applicant as a registered architect, which certificate shall have the effect of a license to the person to whom it is issued to practice architecture in this State, subject to the provisions of this Act.

Any license or certificate of registration heretofore issued under the laws of this State authorizing its holder to practice architecture shall, during the unexpired period for



Chicago Union Station Improvements, C. R. & Q. R. R., Canal St. Viaduct
800 feet in length
58,800 sq. ft. of Membrane Water Proofing



Ford Motor Service Bldg., Des Moines, Iowa. Albert Kahn, Architect, Detroit, Mich.
51,500 sq. ft. of Promenade Tile Roofing

THE EDWARD MOORE ROOFING CO.

ROOFING AND WATERPROOFING CONTRACTORS

FRANKLIN 134

Chamber of Commerce Building

CHICAGO, ILL.

which it was issued, serve the same purpose as the certificate of registration provided for by this Act.

Sec. 10. Any person licensed to practice architecture in this State or registered as an architect under this Act shall be exempt from the provisions of any and all Acts in force in this State regulating the practice of structural engineering.

Sec. 11. Every holder of a certificate of registration as a registered architect shall display it in a conspicuous place in his principal office, place of business or place of employment.

Every registered architect shall have a seal, the impression of which shall contain the name of the architect and the words "Registered Architect," "State of Illinois." He shall stamp with this seal all working drawings and specifications prepared by him or under his supervision. Any seal heretofore authorized under the laws of this State shall serve the same purpose as the seal provided for by this Act.

Sec. 12. Every registered architect who continues in active practice shall, annually, on or before the first day of July, renew his certificate of registration and pay the required renewal fee. Every license or certificate of registration which has not been renewed during the month of July in any year, shall expire on the first day of August in that year. A registered architect whose certificate of registration has expired may have his certificate restored only upon payment of the required restoration fee.

Any architect registered or licensed in this State who has retired from the practice of architecture for a period of not more than five (5) years may have his certificate of registration renewed, at any time within a period of five (5) years after so retiring, upon making application to the Department for such renewal and upon payment of all lapsed annual renewal fees.

Sec. 13. The Department of Registration and Education may refuse to renew, or may suspend, or may revoke, any certificate of registration for any one or any combination of the following causes:

- (a) Gross incompetency.
- (b) Recklessness in the construction of buildings or their appurtenances.
- (c) Dishonest practice.
- (d) When the architect has been twice convicted for a violation of any of the provisions of this Act.
- (e) A person who has by false or fraudulent representation obtained or sought to obtain a certificate of registration as an architect.

The Department of Registration and Education shall not refuse to renew, nor suspend, nor shall it revoke any certificate of registration for any of the above causes until the person accused shall have been given at least twenty (20) days' notice in writing of the charge against him and a public hearing upon such charge has been had by the Department of Registration and Education.

Upon the hearing of any such proceeding, the Director of Registration and Education, the Assistant Director of Registration and Education, or the Superintendent of Registration may administer oaths, and the Department of Registration and Education may issue subpoenas and procure and compel the attendance of and the giving of testimony by witnesses and may compel the production of any books and papers deemed relevant to the inquiry by the Department or by the persons designated by the Department under the Civil Administrative Code of Illinois to conduct such inquiry. The accused may have the subpoena of the Department of Registration and Education for his witnesses, and may be heard in person and by counsel, in open public hearing.

Any circuit court, or any judge of a circuit court, either in term time or in vacation, upon the application either of the Department of Registration and Education or of the ac-

cused may, by order duly entered, require the attendance and enforce the giving of testimony of such witnesses and require the production of such books and papers as are above in this section referred to before the Department of Registration and Education or the persons designated by said Department under said Civil Administrative Code to conduct the inquiry in any hearing relating to the refusal, suspension, renewal or revocation of any certificate of registration. Upon refusal or neglect to obey the order of the said court or judge, the said court or judge may compel, by attachment or proceedings for contempt of courts, or otherwise, obedience to the order.

Sec. 14. The fee to be paid by an applicant for an examination to determine his fitness to receive a certificate of registration as a registered architect shall be ten dollars (\$10).

The fee to be paid by an applicant for a certificate of registration as a registered architect shall be five dollars (\$5).

The fee to be paid for the restoration of an expired certificate of registration shall be five dollars (\$5).

The fee to be paid upon renewal of a certificate of registration shall be one dollar (\$1).

The fee to be paid by an applicant for a certificate of registration who is an architect registered or licensed under the laws of another state or territory of the United States, or of a foreign country or province, shall be fifteen dollars (\$15).

Sec. 15. The Department of Registration and Education shall adopt rules and regulations in accordance with the provisions of section 60 of said Civil Administrative Code, and not inconsistent with this Act, to carry out fully and enforce the provisions of this Act.

Sec. 16. Each of the following Acts constitutes a misdemeanor punishable upon conviction by a fine of not less than twenty-five dollars (\$25) nor more than two hundred dollars (\$200) for each offense:

- (a) The practice of architecture by any person or the advertising or putting out of any sign or card or other device which might indicate to the public that he or she is entitled to practice as an architect, without a certificate of registration as a registered architect issued by the Department of Registration and Education of this State.
- (b) The making of any willfully false oath or affirmation in any matter or proceeding where an oath or affirmation is required by this Act.
- (c) The affixing of a registered architect's seal to any plans, specifications or drawings which have not been prepared by him or under his immediate personal supervision.
- (d) The violation of any provision of Section 11 of this Act.

All fines and penalties shall inure to the Department of Registration and Education of this State.


Sec. 17. The Department of Registration and Education shall keep a record open to public inspection at all reasonable times of its proceedings relating to the issuance, refusal, renewal, suspension and revocation of certificates of registration. This record shall also contain the name, place of business and residence, and the date and number of registration of each registered architect in this State.

Sec. 18. The following Acts are hereby repealed: "An Act to provide for the licensing of architects and regulating the practice of architecture, as a profession," approved June 3, 1897, and in force July 1, 1897, and the following Acts amendatory thereof, to-wit: An Act approved April 19, 1899, and in force July 1, 1899. An Act approved May 16, 1905, and in force July 1, 1905; and an Act approved May 26, 1911, and in force July 1, 1911.

Sec. 19. This Act may be known and cited as "The Illinois Architectural Act."

Greer's Improved Pressure and Gravity Filters

*EVERY KIND—EVERY SIZE FOR
EVERY PURPOSE*



The Greer Chemical Co.

20 W. Jackson Boulevard, Chicago, Ill.

874 Broadway
New York

101 Pennsylvania Building
Philadelphia, Pa.

407 E. 13th Street, Kansas City, Mo.

Specifications and Illustrated Catalogue on Application

EXTRACTS FROM THE NEW CIVIL ADMINISTRATIVE CODE OF THE STATE OF ILLINOIS

Which Affects the practice of the Architectural Profession in this State

An Act in relation to the civil administration of the State government, and to repeal certain Acts therein named. [Approved March 7, 1917, in force July 1, 1917.]

GENERAL PROVISIONS.

Section 1. Be it enacted by the People of the State of Illinois, represented in the General Assembly: This Act shall be known as "The Civil Administrative Code of Illinois."

Sec. 2. The word "department," as used in this Act shall, unless the context otherwise clearly indicates, mean the several departments of the State government as designated in Section 3 of this Act, and none other.

Sec. 3. Departments of the State government are created as follows:

- The department of finance;
- The department of agriculture;
- The department of labor;
- The department of mines and minerals;
- The department of public works and buildings;
- The department of public welfare.
- The department of public health;
- The department of trade and commerce;
- The department of registration and education.

Sec. 4. Each department shall have an officer at its head who shall be known as a director, and who shall, subject to the provisions of this Act, execute the powers and discharge the duties vested by law in his respective department.

Sec. 5. In addition to the directors of departments, the following executive and administrative officers, boards and commissions, which said officers, boards and commissions in the respective departments, shall hold offices hereby created and designated as follows:

In the Department of Public Works and Buildings.

- Assistant director of public works and buildings;
- Superintendent of highways;
- Supervising architect;
- Supervising engineer;
- Superintendent of waterways;
- Superintendent of printing;
- Superintendent of purchases and supplies;
- Superintendent of parks.

In the Department of Registration and Education.

Assistant director of registration and education.

Superintendent of registration;

The normal school board, which shall consist of nine officers, together with the director of the department and the Superintendent of Public Instruction. The above named officers, and each of them, shall, except as otherwise provided in this Act, be under the direction, supervision and control of the director of their respective departments, and shall perform such duties as such director shall prescribe. [Amended by Act approved June 24, 1921.]

Sec. 6. Advisory and non-executive boards, in the respective departments, are created as follows:

In the Department of Registration and Education.

Neither the Director, Assistant Director, Superintendent of Registration, nor any other executive and administrative officer in the Department of Registration and Educa-

tion shall be affiliated with any college or school of medicine, pharmacy, dentistry, nursing, optometry, embalming, barbering, veterinary medicine and surgery, architecture, or structural engineering, either as teacher, officer or stockholder, nor shall he hold a license or certificate to exercise or practice any of the professions, trades or occupations regulated.

The Department of Registration and Education:

The director of registration and education shall receive five thousand dollars;

The assistant director of registration and education shall receive three thousand six hundred dollars;

The superintendent of registration shall receive four thousand two hundred dollars.

10. No member of an advisory and non-executive board shall receive any compensation.

11. Each executive and administrative officer, except the two food standard officers, the members of the mining board, and the members of the normal school board shall devote his entire time to the duties of his office and shall hold no other office or position of profit.

12. Each officer whose office is created by this Act shall be appointed by the Governor, by and with the advice and consent of the Senate. In any case of vacancy in such offices during the recess of the Senate, the Governor shall make a temporary appointment until the next meeting of the Senate, when he shall nominate some person to fill such office; and any person so nominated, who is confirmed by the Senate, shall hold his office during the remainder of the term until his successor shall be appointed and qualified. If the Senate is not in session at the time this Act takes effect, the Governor shall make a temporary appointment as in case of a vacancy.

14. Each officer whose office is created by this Act shall, before entering upon the duties of his office, take and subscribe the constitutional oath of office, which shall be filed in the office of the Secretary of State.

15. Each executive and administrative officer whose office is created by this Act shall, before entering upon the discharge of the duties of his office, give bond, with security to be approved by the Governor, in such penal sum as shall be fixed by the Governor, not less in any case than ten thousand dollars, conditioned for the faithful performance of his duties, which bond shall be filed in the office of the Secretary of State.

16. The director of each department is empowered to prescribe regulations, not inconsistent with law, for the government of his department, the conduct of its employees and clerks, the distribution and performance of its business and the custody, use and preservation of the records, papers, books, documents, and property pertaining thereto.

17. Each department shall maintain a central office in the capitol building at Springfield, in rooms provided by the Secretary of State. The director of each department may, in his discretion and with the approval of the Governor, establish and maintain, at places other than the seat of government, branch offices for the conduct of any one or more functions of his department.

18. Each department shall be open for the transaction of public business at least from eight-thirty o'clock in the morning until five o'clock in the evening of each day except

Daylighting the Factory with DROUVÉ Anti-Pluvius Puttyless Skylights



THE PACKARD MOTOR CAR CO., Detroit, Mich.

Albert Kahn, Architect; Ernest Wilby, Associate

Babcock Brothers Co., Inc. ENGINEERS

Underwriters Approved FIRE DOORS

OFFICE

533-4 Marquette Bldg.

PHONES

Randolph 1371
State 4572
State 4573

FACTORY

4235 W. Kinzie Street

PHONE

Kedzie 5862

CHICAGO, ILLINOIS

Sundays and days declared by the negotiable instrument Act to be holidays.

19. Each department shall adopt and keep an official seal.

20. Each department is empowered to employ, subject to civil service laws in force at the time the employment is made, necessary employees, and, if the rate of compensation is not otherwise fixed by law, to fix their compensation.

Sec. 25. Each director of a department shall annually on or before the first day of December, and at such other times as the Governor may require, report in writing to the Governor concerning the condition, management and financial transactions of his respective department. In addition to such reports, each director of a department shall make the semi-annual and biennial reports provided by the Constitution. The departments shall make annual and biennial reports at the time prescribed in this section, and at no other time.

26. The directors of departments shall devise a practical and working basis for co-operation and coordination of work, eliminating duplication and overlapping of functions. They shall, so far as practicable, co-operate with each other in the employment of services and the use of quarters and equipment. The director of any department may empower or require an employee of another department, subject to the consent of the superior officer of the employee, to perform any duty which he might require of his own subordinates.

27. The gross amount of money received by every department, from whatever source, belonging to or for the use of the State, shall be paid into the State treasury, without delay, not later in any event than ten days after the receipt of the same, without any deduction on account of salaries, fees, costs, charges, expenses or claim of any description whatever. No money belonging to, or for the use of, the State shall be expended or applied by any department except in consequence of an appropriation made by law and upon the warrant of the Auditor of Public Accounts.

35. The following offices, boards, commissions, arms, and agencies of the State government heretofore created by law, are hereby abolished, viz.:

State board of examiners of architects, State board of examiners of structural engineers, secretary of the State board of examiners of structural engineers, secretary-treasurer of the State board of examiners of architects, State inspector of masonry, public buildings and works, assistant State inspectors of masonry, public buildings and works, the board of administration.

The Department of Public Works and Buildings.

49. The department of public works and buildings shall have power:

1. To exercise the rights, powers and duties vested by law in the State highway department, the State highway commission, the chief State highway engineer, the assistant State highway engineer, and other officers and employees of the State highway service;

2. To exercise the rights, powers and duties vested by law in "The Canal Commissioners," their officers and employees;

3. To exercise the rights, powers and duties vested by law in the rivers and lakes commission of Illinois, its officers and employees;

4. To exercise the rights, powers and duties vested by law in the Illinois waterway commission, its secretary, chief engineers, its other officers and employees;

5. To exercise the rights, powers and duties vested by law in the Illinois park commission, its officers and employees;

6. To exercise the rights, powers and

duties vested by law in the Fort Massac trustees, their officers and employees;

7. To exercise the rights, powers and duties vested by law in the Lincoln homestead trustees, their officers and employees;

8. To exercise the rights, powers and duties vested by law in the board of commissioners of and for the Lincoln monument grounds, its officers and employees;

9. To exercise the rights, powers and duties vested by law in the superintendent of printing, his officers and employees;

10. To make contracts for and superintend the telegraph and telephone service for the several departments;

11. To purchase and supply all fuel, light, water and other like office and building services for the several departments except where the same are now supplied by the Secretary of State.

12. To procure and supply all furniture, general office equipment and general office supplies (other than stationery and office supplies distributed through the office of the Secretary of State) needed by the several departments;

13. To procure and supply all clothing, instruments and apparatus, subsistence and provisions for the charitable, penal and reformatory institutions;

14. To procure and supply all cots, beds, bedding, general room and cell equipment, table, kitchen and laundry equipment, agricultural implements, harness, stable and garage supplies, household supplies, periodicals, machinery and tools, medicines and medical supplies, plumbing, light and engine supplies, wagons and other vehicles and workshop supplies needed by the several departments;

14a. To purchase and supply all necessary tools, machinery, supplies and materials to be used by the State in or about constructing or maintaining State highways;

15. To prepare, or cause to be prepared, general plans, preliminary sketches and estimates for the public buildings to be erected for any department;

16. To have general supervision over the erection and construction of public buildings erected for any department, and over the inspection of all materials previous to their incorporation into such buildings or work;

17. To make contracts for, and supervise the construction and repair of buildings under the control of any department;

18. To prepare and suggest comprehensive plans for the development of grounds and buildings under the control of any department;

19. To make and provide all drawings, plans, specifications and models for the construction and perfection of all systems of sewerage, drainage and plumbing for the State in connection with the buildings and grounds under the control of any department;

20. To erect, supervise and maintain all public monuments and memorials erected by the State except where the supervision and maintenance thereof is otherwise provided by law;

21. To lease, for a term not exceeding two years, storage accommodations for the several departments;

22. To lease, for a term not exceeding two years, unproductive and unused lands or other property under the control of any department, unless longer leases thereof are expressly authorized by some law enforced by the department;

23. To lease, for a term not exceeding two years, office space in buildings for the use of the several departments;

24. To have general supervision and care of storerooms and offices leased for the use of the departments.

50. The advisory and non-executive boards in the department of public works shall discharge the following advisory powers and functions:

Anderson & Lind Mfg. Co.

Telephones: Humbolt 902-904

Manufacturers of

MILLWORK

2127-31 Iowa St.

CHICAGO, ILL.

The board of art advisors shall advise to the artistic character of State buildings, works and monuments, now or hereafter constructed, and to any work of a permanent character intended for decoration or commemoration;

The board of water resource advisors shall advise relative to riparian rights of the State, and the conservation, use and development of water resources;

The board of highway advisors shall advise relative to the construction, improvement and maintenance of State highways;

The board of park and buildings advisors shall advise relative to the construction, improvement and maintenance of State parks, buildings and monuments.

51. The director of public works is authorized, with the consent in writing of the Governor, to acquire, by private purchase or by condemnation under the eminent domain Act, the necessary lands for the public buildings and grounds for the departments.

52. All moneys received by the director of public works from rents, leases, sale of property or from any other source in connection with the management of the Illinois and Michigan Canal shall be covered into the State treasury, and shall be placed by the State Treasurer to the credit of a special fund to be known as the "Illinois and Michigan Canal fund."

The Department of Registration and Education.

58. The department of registration and education shall have power:

1. To exercise the rights, powers and duties vested by law in the board of education of the State of Illinois, the board of trustees of the Southern Normal University at Carbondale, the board of trustees of the Northern Illinois State Normal School at DeKalb, the board of trustees of the Eastern Illinois State Normal School at Charleston, and the board of trustees of the Western Illinois State Normal School at Macomb;

2. To exercise the rights, powers and duties vested by law in the board of veterinary examiners and the State board of live stock commissioners relating to the practice of veterinary medicine and surgery in the State of Illinois;

3. To exercise the rights, powers and duties vested by law in the board of examiners of horseshoers;

4. To exercise the rights, powers and duties vested by law in the State board of examiners of architects;

5. To exercise the rights, powers and duties vested by law in the State board of examiners of structural engineers.

60. The department of registration and education shall, wherever the several laws regulating professions, trades and occupations which are devolved upon the department for administration so require, exercise, in its name, but subject to the provisions of this Act, the following powers:

1. Conduct examinations to ascertain the qualifications and fitness of applicants to exercise the profession, trade or occupation for which an examination is held; and pass upon the qualifications of applicants for reciprocal licenses, certificates and authorities;

2. Prescribe rules and regulations for a fair and wholly impartial method of examination of candidates to exercise the respective professions, trades or occupations;

3. Prescribe rules and regulations defining, for the respective professions, trades and occupations, what shall constitute a school, college or university, or department of a university, or other institutions, reputable and in good standing and to determine the reputability and good standing of a school, college or university, or department of a university, or other institution, reputable and in good standing by reference to a com-

pliance with such rules and regulations;

4. Adopt rules providing for and establishing a uniform and reasonable standard of maintenance, instruction and training to be observed by all schools for nurses which are to be deemed reputable and in good standing and to determine the reputability and good standing of such schools for nurses by reference to compliance with such rules and regulations;

5. Establish a standard of preliminary education deemed requisite to admission to a school, college, or university, and to require satisfactory proof of the enforcement of such standard by schools, colleges and universities;

6. Conduct hearings on proceedings to revoke or refuse renewal of licenses, certificates or authorities of persons exercising the respective professions, trades or occupations, and to revoke or refuse to renew such licenses, certificates or authorities;

7. Formulate rules and regulations when required in any act to be administered.

None of the above enumerated functions and duties shall be exercised by the department of registration and education, except upon the action and report in writing of persons designated from time to time by the director of registration and education to take such action and to make such report, for the respective professions, trades and occupations as follows:

For the architects, five persons, one of whom shall be a member of the faculty of the University of Illinois, and the other four of whom shall be architects residing in this State, who have been engaged in the practice of architecture at least ten years;

For the structural engineers, five persons, one of whom shall be a professor in the civil engineering department of the University of Illinois, and the others of whom shall be structural engineers of recognized standing, who have had not less than ten years' practical experience, then practicing as structural engineers in this State.

The action or report in writing of a majority of the persons designated for any given trade, occupation or profession, shall be sufficient authority upon which the director of registration and education may act.

In making the designations of persons to act for the several professions, trades and occupations, the director shall give due consideration to recommendations by members of the respective professions, trades and occupations and by organizations therein.

Whenever the director is satisfied that substantial justice has not been done either in an examination or in the revocation of or refusal to renew a license, certificate or authority, he may order reexaminations or re-hearings by the same or other examiners.

61. All certificates, licenses and authorities shall be issued by the department of registration and education, in the name of such department, with the seal thereof attached.

Repeal.

64. The following Acts and parts of Acts are hereby repealed:

"An Act creating the office of supervising architect of the State of Illinois and defining his powers and duties," approved April 24, 1899, in force July 1, 1899;

"An Act creating the office of supervising engineer for the General Assembly, its members and committees, and the Board of Administration of the State of Illinois, and fixing his compensation," approved June 10, 1911, in force July 1, 1911;

"An Act to create a State art commission, and to define its powers and duties," approved June 4, 1909, in force July 1, 1909;

"An Act creating the office of State inspector of masonry, public buildings and works, and prescribing qualifications, duties and compensation," approved June 28, 1915, in force July 1, 1915.

EDWARD HINES, President
M. W. TEUFEL, Asst. to President

L. L. BARTH, Vice President
H. S. DEWEY, Asst. to Vice-President

C. F. WIELE, Secretary
EDWARD H. THOMAS, Treasurer

EDWARD HINES LUMBER COMPANY

Main Yards and Offices: LINCOLN STREET, South of Blue Island Ave., CHICAGO

SALES DEPARTMENT MANAGERS

P. W. HUSTON, Railroad Trade
F. E. O'DOWD, Contractors' Trade
ALBERT MARQUARDT, City Trade

Davis Street Station Yard:

Exhauston, Ill.

Telephone "Exhauston" 42

GEO. C. LAMONT, Mgr.

Church St. and Ashland Ave. Yard:

Exhauston, Ill.

Telephone "Exhauston" 42

GEO. C. LAMONT, Mgr.

Highland Park Branch Yard:

Highland Park, Ill.

Telephone "Highland Park" 21

C. R. DENNETT, Mgr.

Hawthorne & Morton Park Branch Yard:

19th Ave. and C. B. & Q. R. R.

Opp. Western Electric Works

Phones Chicago and Canal 349

Hawthorne, Ill.

F. V. VONESH, Mgr.

Glen View Branch Yard:

Glen View, Ill.

Telephone "Glen View" 4

MICHAEL SESTERHEN, Mgr.

Rosdill and Edgewater Branch Yard:

Balmain Ave. and C. & N. W. Ry. Track

Telephone "Edgewater" 3098

GEO. J. L. MOHRING, Mgr.

Austin Branch Yard:

Cor. Lake St. and Lawrence Ave.

Telephone "Austin" 23

CHAS. T. CLARK, Mgr.

Irving Park Branch Yard:

3839 Milwaukee Ave.

Telephone "Kildare" 3272

R. W. HART, Mgr.

Jefferson Park Branch Yard:

5124 Milwaukee Ave.

Telephone "Kildare" 5431

JAMES J. VONESH, Mgr.

Melrose Park Branch Yard:

Melrose Park, Ill.

Telephone "Melrose Park" 730

FRANK ANDREE, Mgr.

Park Ridge Branch Yard:

Park Ridge, Ill.

Telephone "Park Ridge" 15

EDWARD A. HARTMAN, Mgr.

**Headquarters for Anything and
Everything in**


**LUMBER, SHINGLES
AND LATH**

MAIN OFFICE AND YARD

Long Distance Phone:

"CANAL" 349

BIRD'S EYE VIEW OF THE LARGEST LUMBER YARDS IN THE WORLD



Bird's-eye view taken from tower 200 feet high, showing our three large yards, covering over 45 acres, and a water frontage of over one mile. The piling just opposite locomotive (over 1,000 in number) are 60 feet long and appear like a bundle of matches. This gives you a comparative idea of the enormous size of our plant.

**Largest Stock in City, Hence Can
Furnish All Sizes**

TIMBERS

**from 4x4—10 to 30x30—100 feet and
all sizes joists in**

**WHITE PINE, YELLOW
PINE, NORWAY and FIR**

**City Trade and Prompt
Deliveries Our Specialty**

CRATING, MANUFACTURING, MILL CONSTRUCTION AND HOUSE BILL LUMBER ALWAYS IN STOCK.

OFFICE PRACTICE

Circular of Advice by Illinois Society of Architects Adopted April 28, 1914.

Believing that uniform practice in various architects' offices is desirable for all concerned, this Society recommends that the following conditions prevail in architects' offices of the State of Illinois:

Classification of Employees.

First. That employees be classed as Regular and Special;

Second. Employees classified as "Regular" will be those continually engaged for a period of not less than one year, on a weekly salary basis; it is expected that such employees will assume greater responsibilities to their employers and be granted special privileges, in consideration of faithful service;

Third. Employees classified as "Special" will be those engaged temporarily. It is deemed proper that such employees be paid by the hour for actual service rendered, making no allowance for vacations or holidays, it being considered fair under these circumstances to allow these draughtsmen a slightly higher rate per hour than regular employees who enjoy privileges of vacations and holidays.

Office Hours.

First. It is understood that draughtsmen are expected to be in their respective offices ready to begin actual work at the hours stated, and that they will continue in service at least until the hours fixed for cessation of work;

Second. The regular opening time of offices shall be 8:30 A. M., throughout the year;

Third. Period of service for Monday, Tuesday, Wednesday, Thursday and Friday, in the morning, shall be four hours, extending to 12:30 P. M.; that the lunch hour shall be one hour, extending from 12:30 to 1:30 P. M.; that the afternoon period shall be four hours, extending from 1:30 to 5:30 P. M.;

Fourth. That the Saturday period of service shall consist of 4½ hours, extending from 8:30 A. M. continuously to 1:00 P. M.

Units of Service.

First. One week's service will consist of 44½ hours;

Second. One year's service will consist of 2,180½ hours.

Pay-Day.

First. That pay-day shall be on Monday of every week;

Second. That each pay-day draughtsmen be paid up to the Saturday night preceding.

Holidays and Vacations.

First. We recommend that "Regular" draughtsmen be given the following holidays on full pay: New Year's, Decoration Day, July Fourth, Labor Day, Thanksgiving, Christmas;

Second. That all "Regular" draughtsmen having been in the employ of an architect for more than one year be given two weeks' vacation on full pay, at time most convenient for employer;

Third. It should be understood that "Regular" draughtsmen, quitting the employer's service of their own volition, preceding the completion of any year's service, shall not be entitled to vacation allowance;

Fourth. "Regular" employees terminating service at the request of their employer shall be entitled to an allowance in cash proportionate to two weeks' salary allowed for vacation in the same ratio as period of service bears to one year;

Fifth. Vacations and holidays are understood to be granted to employees for rest and recuperation, the employee being understood to be in the service of the employer during vacation and holiday time just to the same extent as when regularly engaged in the office;

Sixth. It is recognized that an average of 44½ hours per week's service is the maximum efficient service that can be continuously rendered without detriment to the health or efficiency of the employee, and that where the employee engages in outside architectural service of any sort for others, he does so at the expense of his employer, and his employer should be credited for corresponding loss of time. The practice of employees of one employer working nights or holidays for another is condemned as detrimental to the best interests of both employer and employee;

Seventh. In case of emergencies of short duration, "Regular" employees are expected to work over-time for the employer without extra remuneration other than a reasonable allowance for the expense of taking meals away from regular lodging place. In such cases, however, the employees will be credited with off time on account of sickness or otherwise, equivalent to the amount of over-time service rendered in cases of emergency;

Eighth. Draughtsmen are encouraged, however, to make use of a portion of their time off for educational improvement.

Illinois Society of Architects,
1211-19 S. LaSalle.

WE CARRY A LARGE STOCK OF YELLOW PINE TIMBERS AND HEAVY JOISTS.

DOCK, PROPERTY AND YARDS OF
THORNTON-CLANEY LUMBER COMPANY
2315 ELSTON AVE. CHICAGO, ILL.

WE SOLICIT YOUR INQUIRIES AND ORDERS FOR OAK TIMBERS AND DIMENSIONS—
AND ALL KINDS OF STRUCTURAL AND FACTORY LUMBER

Illinois Society of Architects

Suite 1211, 19 S. La Salle Street, Chicago.

The following is a list of the publications of the Society; further information regarding same may be obtained from the Financial Secretary.

FORM NO. 21, "INVITATION TO BID"—Letter size, $8\frac{1}{2} \times 11$ in., two-page document, in packages of fifty at 75c, broken packages, two for 5c.

FORM NO. 22, "PROPOSAL"—Letter size, $8\frac{1}{2} \times 11$ in., two-page documents, in packages of fifty, at 75c, broken packages, two for 5c.

FORM NO. 23, "ARTICLES OF AGREEMENT"—Letter size, $8\frac{1}{2} \times 11$ in., two-page document, in packages of fifty, at 75c, broken packages, two for 5c.

FORM NO. 24, "BOND"—Legal size, 8×13 in., one-page document, put up in packages of twenty-five, at 25c per package, broken packages, three for 5c.

FORM NO. 25, "GENERAL CONDITIONS OF THE CONTRACT"—Intended to be bound at the side with the specifications, letter size, $8\frac{1}{2} \times 11$ in., ten-page document, put up in packages of fifty at \$2.50, broken packages, three for 25c.

FORM 26, CONTRACT BETWEEN ARCHITECT AND OWNER. Price, two for 5c, in packages of fifty, 75c.

THE ANNUAL—A handbook containing useful information for Architects and Builders and the building code of the City of Chicago, distributed free to Architects licensed to practice in Illinois. Price to others, cloth binding, \$2.00; leather binding, \$2.50.

FORM 1, BLANK CERTIFICATE BOOKS—Either stub or carbon copy, form 4×6 in., 100 blanks, price, 50c.

FORM 4, CONTRACT BETWEEN THE OWNER AND CONTRACTOR—(Old Form.) Price, two for 5c, five for 10c, put up in packages of 50 for \$1.00.

FORM E, CONTRACTOR'S LONG FORM STATEMENT—As required by lien law. Price, two for 5c, five for 10c.

FORM 13, CONTRACTOR'S SHORT FORM STATEMENT—Price, 1c each.

CODES OF PRACTICE AND SCHEDULE OF CHARGES—In mailing envelopes, 4×6 in. Price, 5c each.

These documents may be secured at the Financial Secretary's office, suite 1211, 19 S. La Salle St., telephone Cent. 4214. We have no delivery service. The prices quoted above are about the cost of production. An extra charge will be made for mailing or expressing same. Terms strictly cash, in advance, with the order; except that members of the Society may have same charged to their account.

JOHN E. BURNS LUMBER CO.

700 West Chicago Avenue Chicago.

TELEPHONE - MONROE 211.



SUGGESTIONS FOR FIRMS ISSUING CATALOGUES AND PRINTED MATTER

Architects are technically educated and are charged with selection on technical merit.

Exact and specific technical detail appeals to an architect because it enables him to judge quickly and correctly.

Drawings to scale of parts or the whole make arrangement or mechanism most quickly clear to the technically educated.

Testimonials from those technically incompetent to judge carry no weight with the competent.

Architects want authentic technical information about all building materials and devices.

Architects do not want to wade through a sea of laudatory verbiage in order to discover an islet of real usable information.

Architects must cover an immense variety and amount of detail in selecting the numerous materials that enter into a building.

Where much detail is handled by a single individual, success is dependent on system.

Information to be immediately available for architects must be classified so that each detail can be considered separately and in order.

Advertisers recognizing these principles and presenting exact technical information under proper classification, free from irrelevant matter and in convenient form for filing, so as to be available when that item is up for consideration, are most likely to secure satisfactory results from their efforts.

It is believed that most architects have their own particular system of filing and classification and would not take kindly to any advertising scheme contemplating the placing of filing cabinets in architects' offices and distribution by those interested in the promotion of advertising scheme. Architects do not take kindly to allowing outsiders access to their private catalogue filing cabinets, and it is impractical to have two filing systems in the same office.

Practical requirements in the preparation of specifications make it necessary for architects to divide their specifications into topics very similar to trade divisions brought about by divisions of labor promulgated by labor authorities, and no single division or chapter of a catalogue should contain matter pertaining to more than one trade; un-

less the material referred to is used by several trades. It is hoped that eventually the architects may agree on a satisfactory universal building material classification or index. But it is certain that this time has not yet arrived and that no person not actually having had extended experience in the preparation of architects' specifications is capable of preparing such an index that would be practical.

STANDARD SIZES Requested by Architects

Believing that uniform practice by the various publishers of catalogues and literature for distribution to architects is desirable for all concerned, and wishing to be in accord with the recommendations of the American Institute of Architects, the Illinois Society of Architects advise that all literature for this purpose be prepared to comply as nearly as possible with the conditions set forth, as follows:

First: That $8\frac{1}{2}" \times 11"$ shall be the standard sized page for all general catalogues and bulletins intended for permanent filing by architects; thus making a size convenient for filing in the standard letter-size vertical filing cabinets, such as may be procured from any concern dealing in office filing devices.

Second: That $3\frac{3}{4}" \times 8\frac{1}{2}"$ shall be the standard size for post cards and pocket editions intended for the use of architects; thus making a size convenient for filing three to the page, side by side, in standard letter-size vertical filing cabinets; or one to the page, on side, in standard vertical check files; or on end in standard legal document files; also convenient for mailing in standard legal size envelopes.

Third: That all catalogues should be issued in the form of separate bulletins, or chapters separated by a blank page, each treating of but one subject, on both sides of the same sheet, so as to make separation easy for classification purposes.

Fourth: That it is important to have pages cut to exact size; if over size in any particular they may not go into files; if under size, they may be overlooked in running through the files hastily.

Fifth: That these recommendations go into effect January 1, 1915, and that following that date, architects be advised to decline to receive literature for filing which does not comply with standard sizes.

Illinois Society of Architects

HERMAN H. HETTLER LUMBER CO.

2601 ELSTON AVENUE



View of Lumber Yard, Planing Mill and Hardwood Flooring Plant.

YELLOW PINE AND FIR TIMBERS—OUR SPECIALTY.

Telephone—Humboldt 200

NATIONAL COUNCIL OF ARCHITECTURAL REGISTRATION BOARDS

The National Council of Architectural Registration Boards is an organization to which the Illinois Society of Architects has given its hearty co-operation and support. In fact, the Society has played a very important supporting part in the formation of that organization.

Briefly stated, the Council constitutes a clearing house for the convenience of the registration authorities of the various states having laws regulating the practice of architecture. Its active membership is composed of such states. Its membership is not elected, but is constituted of those States whose registration authorities subscribe to its Constitution and By-Laws and pay the annual membership fee. No State which has a law regulating the practice of architecture can be denied membership in the Council, provided its legally constituted officials sign an application blank, pay the required membership fee, and deposit five copies of its Architectural Act and of the Rules and Regulations promulgated by its examining committee or board for the purpose of regulating examinations.

The franchise of the Council is inherent in its active members. In other words, the control of the Council is absolutely in the hands of the architectural registration authorities of the various States which are members of the Council, each State being entitled to only one vote, even though represented by several of its officials. The officers of the Council are elected by the active members to carry out their will.

Reciprocal Transfer of Registration.

It is expected that architects desiring reciprocal transfer of registration from one State to another will find it convenient and practical to effect this transfer through the medium of the National Council of Architectural Registration Boards. For in most cases where this method is followed, the applicant will be saved the necessity of a personal appearance and examination before any examining committee other than that of his home State. While the Council does not guarantee the acceptance of all applicants who apply for transfer of registration through the Council, it is in a position to and does furnish State examining committees with the results of an unprejudiced and disinterested investigation of the applicant's credentials, moral, educational, and legal. With this data in hand the examining authorities in the State to which the applicant desires transfer are furnished evidence which is usually considered sufficient upon which to predicate judgment as to the applicant's availability for registration in accordance with the laws of that State.

Examinations.

Because of its close relationship with the various examining authorities, the Council is in a position to facilitate uniformity of examinations. Where legal restrictions do not permit the local examining committees to give examinations equal in stringency to those recommended by the Council as just and proper, the Council with the co-operation of the local examining committees may arrange voluntary examinations meeting the minimum requirements recommended by the Council. The laws in the different States vary materially and probably always will vary, and since these laws affect examinations the legal examination requirements in different States may be expected to continue to differ. Some States emphasize preliminary education as of paramount importance and place very little credence in examinations. Other States emphasize the importance of examinations as a greater consideration than the educational record. Some States are only

concerned with the question of the applicant's proficiency in matters falling under the police power of the State (i. e., the conservation of life, health and property). Other States base their requirements on broad educational standards and value aesthetic skill as equal to skill in matter of safety to human life, conservation of property and protection of health. Many requirements are common to all States. Therefore, the successful passing of an examination in any State should eliminate further requirement for an examination on work passed in the State of first examination.

Standard N. C. A. R. Examinations.

The Council has devised an examination standard which it has been pleased to designate as the "Standard N. C. A. R. Examination" and which is intended to cover the minimum requirements for registration in all States. The Council suggests the advisability of supplementing the regular examination of the State of applicant's residence with this additional examination. It being understood that while the examination is conducted under the supervision of the National Council and in strict accord with the rules promulgated by that body, that it is actually conducted by the State examining committee of the State of applicant's residence. Preliminary to such examinations, the applicant must apply to the Council and have his record in practice very carefully investigated, written up, and furnished to the local examining committee as part of the material which it must use in determining the applicant's right to the status, "Registered in Accord with the Standard N. C. A. R. Examination Requirements."

Junior Examinations.

Junior applicants (i. e., men having had less than ten years' practice as principals), who have passed the regular State examination in their home States, are only required to pass a written examination covering the difference between their home State examination requirements and those of the National Council of Architectural Registration Boards; but they must submit evidence of attainment since entering practice and evidence of attainment before practice. Of course, if they have not been engaged in practice, they will only have to submit evidence of attainment before practice. But this fact should be emphasized—that no essential part of their records from the time that they left elementary school up until the date of their applications for examination shall be missed from the investigation. Baldly stated, they must never have been found guilty of dishonorable practice, recklessness, or carelessness in connection with the designing, erection, or supervision of buildings. Their preparation for practice must be shown to have been adequate and their practical skill in applying theoretical knowledge demonstrated both by written examination and by practical experience.

The Standard N. C. A. R. Examination is purely a voluntary examination. No one is compelled to take it and no one will be allowed to take it who does not seem to have had adequate preparation to justify such an examination. In the interests of fair play, large discretionary power and liberal instructions are given to the examining committee in determining the equivalent of prescribed preparation.

Senior Examination.

The Standard N. C. A. R. Examination for those falling under the Senior classification (i. e., men having had ten or more years' experience as principals) is based very largely on proved attainment in practice. The Council assumes that no competent man hav-

J. W. EMBREE, PRESIDENT


C. A. FLANAGIN, VICE-PRES.

H. W. CHANDLER, TREAS.

C. J. RITTENHOUSE, SECY

RITTENHOUSE & EMBREE CO.

35TH ST. YARD



GENERAL OFFICES
CHICAGO

YARDS:

3500 S. Racine Ave.
Belmont and Kimball Aves.

LUMBER OAK AND MAPLE FLOORING

Heavy Yellow Pine, Norway and White Pine Timber and Dimension

MILLS:

CHICAGO,
WARREN, ARK.,
EMBREE, S. C.,
and
RIGHTON, MISS.

ing had ten years' experience as a directing head of an architect's office should be entitled to take the status "Registered by N. C. A. R. Examination" who cannot demonstrate to the entire satisfaction of the examining jury that he has at some time during his practice actually been engaged in the competent performance of the five fundamental functions of an architect, namely: the preparation of preliminary studies, general drawings, specifications, details, and the general supervision of the work, including all incidental items of practice which go with the performance of these various functions. With this understanding, it might be possible for a man to have had unusually complete academic and technical school preparation and yet fail in the Senior Standard N. C. A. R. Examination, if it should be proved that he was unable to apply or never had applied his theoretical knowledge in the performance of each of the fundamental functions of an architect at some time during his architectural practice.

Service of Council.

To employ the services of the Council, an architect should proceed about as follows: To obtain reciprocal transfer from one State to another, the applicant should write to the Secretary of the National Council of Architectural Registration Boards, at 1107-64 East Van Buren Street, Chicago, Illinois, and ask for an Application Blank for reciprocal transfer from his home State or the State of his present registration to the State where he desires registration by transfer, stating the following facts:

1. Date and number of his home State registration.
2. A definite statement as to whether he was registered in his home State by examination or by exemption.
3. The number of years that he has been engaged in practice as a principal or one of the principal directing heads of an architect's office actually engaged in the practice of architecture as a profession.

The applicant should enclose with this letter a par value check for Fifteen Dollars (\$15.00) made payable to the National Council of Architectural Registration Boards, to cover the fee charged by the Council to defray the expenses of investigating the applicant's record and transmitting the results of that investigation to the State where the applicant desires transfer of registration.

Upon the receipt of the before-mentioned statement and payment of fee, the Secretary of the National Council will forward to the applicant an Application Blank and an Information Blank which should in due course be filled out by the applicant, certified to by a Notary Public and returned to the Council as a basis for its investigation. Too much emphasis cannot be laid on the importance of using great care in filling out the Information Blank and making the statements as completely comprehensive as space will permit. Since the Information Blank must be reproduced in facsimile, it is very important that the ink used in filling in answers to the various questions shall be black opaque, susceptible to photographic or blue-print reproduction. Common drafting ink is the most practical. The typewriter may be used if the paper is backed with a fresh black carbon, so as to form a good blue-print negative. Actual dates of attendance at school are important. Addresses of school principals, registrars, secretaries of societies, clients, and architectural references should be accurately given. Much delay has resulted from failure to give this information correctly. Inaccurate or incomplete information only delays the completion of the record, as no record will be forwarded to the examining authorities of the State where the architect wishes transfer until the required number of references have been heard from.

Either at the time of sending the Application and Information Blanks to the appli-

cant or at some time during the investigation of his references he will be informed by the National Council as to the amount of his preliminary fee which he must pay to the State examining authorities where he desires registration and, upon receipt of this information, he will forward to the Council a certified par value check covering the amount of that fee made out to the proper registration authorities of the State where he desires registration, as per instructions of the Council. This check will be held by the Council until applicant's record is finally completed, and will be forwarded to the State where he wishes registration along with the information collected concerning his record.

In investigating the applicant's record, the Council takes his Information Blank and writes, first, to the registrars or principals of the schools where he has received his training, asking for a certified copy of his school record while in attendance upon these various institutions.

Second, it writes to the examining authorities of his home State for a certificate as to his registration in that State and inquiring as to whether charges have ever been preferred against him involving recklessness or carelessness in the design or supervision of buildings or dishonest practice.

Third, inquiry is made of his former employers, if he comes under the junior classification, concerning his record and promise as an architectural employee.

Fourth, inquiry is also made from at least three of his clients as to his competency and faithfulness in the execution of trusts imposed in him.

Fifth, inquiry is made of at least three architects as to their knowledge of the character and competency of his practice.

Sixth, inquiry is also made of professional and technical societies as to his membership and his record for honorable practice.

Seventh, when replies to these inquiries are received, they are carefully copied and certified to by the Executive Secretary of the Council and forwarded to the examining authorities where the architect desires registration.

The originals are preserved in the Council office and become a part of the applicant's permanent record. Should he desire to transfer to additional States, he may have this transfer facilitated through the offices of the Council by applying for a transfer in the same manner as in the case of the original application, except enclosing a fee made payable to the Council of only Five Dollars (\$5.00). In such cases, the Council will simply send a duplicate copy of his record to the additional State where applicant desires registration, except in cases where a long time has elapsed between the original investigation and the time of application for an additional transfer. In such cases the Council will make further investigation to find out whether the applicant has continued to maintain the high standard indicated by the original investigation and will add the information thus obtained to the original record, proceeding otherwise as in the first case.

Standard N. C. A. R. Examination.

Should an applicant wish to take a Standard N. C. A. R. Examination he would proceed almost exactly in the same way as indicated in the foregoing upon making an application for reciprocal transfer, except that he shall include a fee of Twenty-five Dollars (\$25.00) to the Council instead of Fifteen Dollars. The Council will proceed to investigate his record in exactly the same way as set forth for the investigation of record in the case of reciprocal transfer, with the following exception, that when the record is received and the copy made, the original replies and the original application blank will be bound up in an application cover, certified to and forwarded to the State examining authorities in the State of the ap-

THE PILSEN LUMBER COMPANY

CHICAGO

LAFLIN AND TWENTY-SECOND STREETS

TELEPHONE CANAL 1031

EVERYTHING IN CONSTRUCTION
LUMBER



QUALITY

SERVICE

PRICE

plicant's residence, together with instructions to the State Examining Committee as to the additional examinations which the applicant must take over and above the regular State examination which he has already taken in order to qualify under the provision, "Registered by Standard N. C. A. R. Examination." In due course, the applicant will be notified to appear before his own State Examining Committee and take the prescribed examination, which, if he passes creditably, will entitle him to the status, "Registered by Standard N. C. A. R. Examination," a status which would seem to entitle him to registration in any State without further examination and which would actually be the means of securing registration in most States having laws regulating the practice of architecture. It would mean that the applicant had the endorsement of the National Council of Architectural Registration Boards. The Council endorses no one and expresses no opinion whatsoever with reference to those who have not taken the Standard N. C. A. R. Examination. It simply collects the information and forwards it for the judgment of the local examining committee.

In the case of Junior Standard N. C. A. R. Examinations, reproductions of the applicant's work in design are made a part of the record of the National Council and furnished to the State of transfer with each application for reciprocal transfer.

In the case of Senior examinations, the applicant is required to furnish with his application for the Senior N. C. A. R. Examination eighteen illustrations, of reduced size, representative of the varying character of his work. These illustrations shall be presented either in the form of photographic film negatives with two prints of each or photostatic negatives and two prints of each. The sheets are to be the architectural standard size, 8½" x 11"; each containing six illustrations, making a total of eighteen, on three sheets.

In both Senior and Junior cases, the applicant must furnish a small identification photograph of himself which will be printed on one of the sheets illustrative of his work. Copies of these illustrations are furnished by the Council to the authorities in the State of examination and to all transfer state authorities along with a certified copy of the other records.

Concerning Fees.

The fees charged by the Council barely defray the expenses of its investigations. The Council is an institution organized "not for profit." All Council fees are in addition to State examining and registration fees. Should complaint be urged that the fees charged by the Council constitute an excessive burden on architectural practitioners who wish to engage in inter-state business, it should be pointed out that there is no requirement compelling architects to make use of the services of the Council. They are always at liberty to appear before the examining committee of the State where they wish to be registered by reciprocal transfer, submit their proofs, and receive registration or denial of registration in that State in accordance with the merits of their case. But it should be pointed out to the architects that most examining committees meet not more than twice a year and that many examining committees meet only once a year and that by mutual understanding registration by reciprocal transfer cannot except in very special cases be made between member States except on the basis of a Council investigation or by the personal appearance of the applicant before the local examining committee at one of its regular or special meetings. Transportation and hotel expense would very quickly mount up to a sum in excess of the nominal fees charged by the Council for its work; particularly when it is borne in mind that after the first investigation subsequent fees are only Five Dollars.

REGISTRATION OF ARCHITECTS STATE OF ILLINOIS

RULES AND REGULATIONS General Statement

The Fifty-first General Assembly revised the law in relation to the regulation of the practice of architecture as a profession.

It is unlawful for any person to practice architecture or advertise or put out any sign or card or other device which might indicate to the public that he or she is entitled to practice as an architect, without a certificate of registration as a registered architect duly issued by the Department of Registration and Education.

Any one, or any combination of the following practices constitutes the practice of architecture, namely: The planning or supervision of the erection, enlargement or alteration of any building or buildings or of any parts thereof, to be constructed for others. A building is any structure consisting of foundations, floors, walls, columns, girders, beams and roof, or a combination of any number of these parts, with or without other parts.

The professional features of the law are administered by a professional committee of architects, consisting of five persons, appointed from time to time by the Director of Registration and Education. The administrative provisions of the law are exercised by the Department of Registration and Education. The powers and duties of the professional committee are as follows:

1. To conduct examinations to ascertain the qualifications and fitness of applicants for registration, and pass upon the qualifications of applicants for reciprocal registration.

2. To prescribe rules and regulations for conducting examinations.

3. To decide the schools of architecture from which graduation will be accepted as the equivalent of two years of the prescribed office experience.

4. To conduct hearings on proceedings to revoke certificates of registration.

Applications

A person is qualified to receive a certificate of registration as a registered architect:

- (a) Who is at least twenty-one years of age.

- (b) Who has graduated from a high school or secondary school approved by the Department, or has completed an equivalent course of study as determined by an examination conducted by the Department, and has subsequently thereto completed such courses in mathematics, history and language as may be prescribed by the Department.

- (c) Who has had at least three years' experience in the office or offices of a reputable architect or architects. A certificate of graduation from an approved school of architecture will be accepted as the equivalent of two years of the prescribed office experience; and

- (d) Who has passed an examination conducted by the Department to determine his fitness to receive a certificate of registration as a registered architect.

Examinations

Examinations of applicants for certificates of registration as registered architects are held at such times and places as the Department of Registration and Education may determine, and embrace the following subjects:

Evanston, Ill.
119 Chicago Ave.
Tel. Evanston 3950

L. W. Crow, *Pres.*
J. R. Duthie, *Vice-Pres.*

Chicago Telephone
Rogers Park 8270

Established 1852

MEARS-SLAYTON BUILDING MATERIAL COMPANY

Successors to Mears-Slayton Lumber Co.

Manufacturers and Dealers in

ALL KINDS OF LUMBER

Sash, Doors, Interior Finish, Etc.

All Kinds of Building Paper
Wall Board and Asphalt
Shingles

Exclusive Agents for
"Upson" Wall Board

Clark and Howard Sts.

CHICAGO, ILL.

1. The planning, designing and construction of buildings.

2. The strength of building materials.

3. The principles of sanitation and ventilation as applied to buildings.

4. The ability of the applicant to make practical application of his knowledge in the ordinary professional work of an architect and in the duties of a supervisor of mechanical work on buildings.

The Department of Registration and Education may, by rule, prescribe additional subjects for examination.

All examinations are conducted in the English language without the use of an interpreter, and are divided into six sections, A, B, C, D, E and F.

Examination A—The Science of Planning and the Art of Designing Buildings. This examination is held the first day with a time allowance of eight hours continuous session, consisting:

First—Of a test in the science of planning, particularly with reference to practical, logical and economical arrangement; the securing of comfort and the safeguarding of life and health of the proposed occupants of the building. (Grade value 100.)

Second—Of a test in the art of designing, particularly with reference to orderly and consistent expression of purpose, logical meeting of conditions and pleasing harmonious presentation. It is not a test in a knowledge of historical styles. The grades will be based solely on the degree of perfection in meeting the before mentioned elemental requirements of good design. (Grade value 100.)

The test under "A" problem requires plans, elevations, sections and some detail drawings for a building the nature of which will be set forth in a program such as a well informed owner might be expected to give to an architect.

Time—8:30 A. M. to 4:30 P. M. en loge.

No reference books will be permitted.

Examination B—Graphic Statics and Truss Design. This examination is held the morning of the second day with a time allowance of two and one-half hours continuous session. It consists of a test in the science of graphic statics as applied to a truss problem, assuming that the preliminary designs of a building are complete, loads determined and diagram of truss settled upon. The candidate is required to determine the maximum stress in each member and its section, and to detail one or more designated joints. (Grade value 100.)

Time—8:30 A. M. to 11:00 A. M.

Free use of reference books is permitted.

Examination C—General Details. This examination is held the morning of the second day with a time allowance of one and one-half hours, consisting of a test in the knowledge of principles general detailing as shown by scale and full size details of such parts of buildings as are encountered in the usual practice of an architect. (Grade value 100.) One-half of the grade will be based on Examination C and the other half on the knowledge of detailing indicated by the other examinations.

Time—11:00 A. M. to 12:30 P. M.

No reference books or plates may be used.

Examination D—Specifications, Practice and Precedent. This examination is held the afternoon of the second day with a time allowance of three and one-half hours continuous session, consisting:

First—Of a test in the knowledge of specification writing, knowledge of the essence of the contract and of general architectural practice, as it pertains to relationship between the public, the owner, the contractor and the architect. (Grade value 80.)

Second—Of a test of general knowledge of the history of architecture and its place in social economy. (Grade value 20.)

Time—1:30 P. M. to 5:00 P. M.

No reference books may be used.

Examination E—Mechanics of Materials. This examination is held the morning of the third day, with a time allowance of four hours continuous session, consisting of a test in the science of determining the strength of materials and the applicant's knowledge of applied mechanics. The test requires the applicant to design the various parts of a structure and show ability to determine the safe, practical working sizes and shapes of footings, piers, columns, beams, girders and floors. Sketches will be furnished the applicant showing conditions and loading. (Grade value 100.)

Time—8:30 A. M. to 12:30 P. M.

Free use of reference books is permitted.

Examination F—Reinforced Concrete Design. This examination is held the afternoon of the third day, with a time allowance of three and one-half hours' continuous session, consisting of a test in the science of computing stresses in reinforced concrete structures and involving exercises to show the applicant's knowledge of the correct design and detailing of reinforced concrete structural parts, such as footings, columns, girders, beams and floor slabs, assuming that the preliminary designs of the building are complete, loads determined, story heights and column spacing fixed. The candidate is required to compute stresses and detail parts which are safe, practical and economical for the purposes intended. (Grade value 100.)

Time—1:30 P. M. to 5:00 P. M.

Free use of reference books is permitted.

Grading of Examination Papers

Examination papers are graded as follows:

The maximum allowed on Examination A is 200; on Examinations B, C, D, E, and F, 100 each. The grade given the applicant on the whole examination is obtained by dividing the total A, B, C, D, E, and F by seven.

To be successful, an applicant must make a general average of 75 with no grade in any subject below 60. If an applicant fails in his first examination, he will be permitted, upon the payment of a second examination fee, to take a second examination in those subjects in which he fell below 75 at any regular examination within eighteen months from the date of the first examination. If the applicant fails in his second examination and desires to appear for a third, it will be necessary for him to file another examination fee and be examined in ALL subjects.

Reciprocity

Upon payment of the required fee, an applicant who is an architect, registered or licensed under the laws of another state or territory of the United States, or of a foreign country or province, may, without examination, be granted a certificate of registration as a registered architect by the Department of Registration and Education in its discretion upon the following conditions:

(a) That the applicant is at least twenty-one years of age, of good moral character and temperate habits;

(b) That the requirements for the registration or licensing of architects in the particular state, territory, country or province were, at the date of the license, substantially equal to the requirements then in force in this State; and,

(c) That the applicant appears before the committee at one of its regular meetings with exhibits of his work.

Annual Renewal

Every registered architect who continues in active practice, shall annually, on or before the first day of July, renew his certifi-

Torpedo Sand Gravel

Crushed Limestone
Limestone Screenings

and

Portland Cement

For Every Kind of

Concrete Construction

also

Bank Sand and Lake Sand

CARLOAD OR TRUCK DELIVERIES

Quality and Satisfactory Service is Best
and Least Expensive. We are Prepared
to Give You Both. No Delays on Job.

CONSUMERS COMPANY

Conway Building, 111 West Washington Street

CHICAGO, ILLINOIS

Franklin 6400

cate of registration and pay the required renewal fee. Every license or certificate of registration which has not been renewed during the month of July in any year, shall expire on the first day of August in that year. A registered architect whose certificate of registration has expired may have his certificate restored only upon the payment of the required restoration fee.

Any architect registered or licensed in this State who has retired from the practice of architecture for a period of not more than five years, may have his certificate of registration renewed at any time within a period of five years after so retiring, upon making application to the Department for such renewal and upon payment of all lapsed renewal fees.

Fees

The fee to be paid by any applicant for an examination to determine his fitness to receive a certificate of registration as a registered architect is ten (\$10.00) dollars.

The fee to be paid by any applicant for a certificate of registration as a registered architect is five (\$5.00) dollars.

The fee to be paid for the restoration of an expired certificate of registration is five (\$5.00) dollars.

The fee to be paid upon renewal of a certificate of registration is one (\$1.00) dollar.

The fee to be paid by an applicant for a certificate of registration who is an architect registered or licensed under the laws of another state or territory of the United States, or of a foreign country or province, is fifteen (\$15.00) dollars.

Seal

Every registered architect shall have a seal, the impression of which shall contain the name of the architect and the words "Registered Architect, State of Illinois." He shall stamp with this seal all working drawings and specifications prepared by him or under his supervision.

Instruction to Candidates

All candidates must appear at 8:00 A. M. on the days set for the examination at the place designated on their admission cards. They must bring all necessary drawing instruments, a 36-in. T-square triangle, scales, thumb tacks, etc., for examinations A, B, and C. For examinations D, E, and F, scales and triangles alone will be sufficient. The use of slide rules for mathematical calculations is permitted, but special slide rules for concrete and steel design are not to be used.

For the first day's work, applicants must bring six sheets of medium weight tracing paper 20 by 30 inches, and one sheet of heavy detail paper 24 by 36 inches. Candidates will not be allowed to leave the room on the first day, but may bring lunch.

For examinations B and C, applicants must bring three sheets of heavy tracing paper.

The paper for other examinations will be furnished by the Department.

Penalties

Each of the following acts constitutes a misdemeanor punishable upon conviction by a fine of not less than twenty-five dollars (\$25.00) nor more than two hundred dollars (\$200.00) for each offense:

(a) The practice of architecture by any person or the advertising or putting out of any sign or card or other device which might indicate to the public that he or she is entitled to practice as an architect, without a certificate of registration as a registered architect issued by the Department of Registration and Education.

(b) The making of any wilfully false oath or affirmation in any matter or proceedings where an oath or affirmation is required by this Act.

(c) The affixing of a registered architect's seal to any plans, specifications or drawings, which have not been prepared by him or under his immediate personal supervision.

(d) Neglect or failure of the holder of a certificate of registration to display it in a conspicuous place in his principal office, place of business, or place of employment.

(e) Neglect or failure of a holder of a certificate of registration to stamp with his seal all working drawings and specifications prepared by him or under his supervision.

All fines and penalties shall inure to the Department of Registration and Education.

Suspensions—Revocations

The Department of Registration and Education may refuse to renew, or may suspend, or may revoke, any certificate of registration for any one or any combination of the following cases:

(a) Gross incompetency.

(b) Recklessness in the construction of buildings or their appurtenances.

(c) Dishonest practice.

(d) When the architect has been twice convicted for a violation of any of the provisions of this Act.

(e) A person who has by false or fraudulent representation obtained or sought to obtain a certificate of registration as an architect.


All correspondence in regard to applications, examinations, etc., should be addressed to the Department of Registration and Education, Springfield, Illinois.

Published by order of

DEPARTMENT OF REGISTRATION AND
EDUCATION:

W. H. H. MILLER,
Director.

F. C. DODDS,
Superintendent of Registration.



SECTION OF ROSING HEAVY DUTY TILE WALL

Hollow Clay Building Tile of All Kinds

FIRE CLAY FLUE LINING
VITRIFIED SEWER PIPE
VITRIFIED WALL COPING
STEAM CONDUITS

GYPSUM TILE
FIRE BRICK
LIME, SAND
GRAVEL, CEMENT

ASTRID  **ROSING**
INC.

111 WEST MONROE STREET
CHICAGO

OLD AND NEW WAGES IN BUILDING TRADES

The following list is a tabulated comparison of the wage scale in the building trades, showing the effect of the decision of Judge Landis:

	New scale. per hour.	Old scale. per hour.
Plumbers	\$.95	\$1.25
Bricklayers	1.10	1.25
Boilermakers	1.00	1.25
Steamfitters95	1.25
Hoisting engineers—For operation of high pressure boilers and engines, cable ways, derricks, pile drivers, cranes and cable hoists.....	1.10	1.25
Hoisting engineers (all others).....	.85	1.25
Tile layers (fire-proofers).....	1.12½	1.25
Cement finishers85	1.25
Composition floor finishers.....	.97½	1.25
Cement workers (laborers—Local No. 76).....	.72½	1.00
Stone derrickmen90	1.25
Drain layers82½	1.25
Electricians	1.10	1.25
Gas fitters95	1.25
Ornamental iron workers.....	.95	1.25
Structural iron workers.....	1.05	1.25
Common laborers72½	1.00
Caisson men (windlass and niggerhead men).....	.85	1.12½
Caisson men (diggers and ladders).....	.97½	1.25
Laborers (plasterers).....	.78¾	1.06¼
Composition floor laborers.....	.72½	1.00
Lathers	1.00	1.25
Machinery movers and riggers.....	.85	1.15
Marble setters87½	1.25
Marble setters' helpers.....	.70	1.00
Marble rubbers and polishers.....	.75	1.00
Scagliola rubbers and polishers.....	.75	1.00
Mosaic and tile workers.....	1.02½	1.25
Mosaic and tile helpers.....	.70	1.00
Pipe and boiler coverers.....	.95	1.25
Composition roofers.....	.92½	1.25
Slate and tile roofers.....	1.00	1.25
Stone cutters	1.02½	1.25
Stone carvers.....	1.25	1.25
Stone planer men.....	.82½	1.05
Terrazzo mechanics.....	.95	1.25
Terrazzo mechanics' assistants.....	.80	1.00
Terrazzo helpers70	1.00
Tuck pointers	1.00	1.25
Sprinkler fitters92½	1.25
Sprinkler fitters' helpers.....	.70	1.00
*Excavating labor (Local No. 225).....	.47½	.65
*Excavating labor (wall men—Local No. 225).....	.55	.75
Composition roofer teamsters.....	30.00 per wk.	37.00


The following trades were in the arbitration but for one cause or another did not submit acceptable agreements. The Arbitrator announced "That if agreements are later made, based upon the Uniform Agreement, the Uniform Suggestions and Principles previously announced that a fair wage rate for these trades would not be greater than the following:

Elevator Constructors	\$0.95	Glaziers	\$0.95
Fixture Hangers	1.00	Sheet Metal Workers.....	.95


And that for the three trades not in the arbitration, equally fair working agreements and rules would justify the following maximum wage rates:

Carpenters.....	\$1.00	Painters.....	\$0.95	Plasterers.....	\$1.10
-----------------	--------	---------------	--------	-----------------	--------

(*These rates are fixed in accordance with express agreement with employer and employees.)




STIFF
LEGGED
DERRICK





DOUBLE
BOOM
DERRICK




"A" FRAME





STANDARD
DERRICK




R SETTER





PEERLESS
DERRICK



TP
SETTER






STEEL
CHAMPION
DERRICK



**SASGEN STANDARD WITH
ELECTRIC MOTOR OR
GASOLINE HOIST**

This makes a very practical time and labor saving machine, and indispensable to Contractors who build from 2 to 6 story buildings. The derrick swings a full circle. The machine has a capacity of 1,500 pounds.



For Derricks & Winches
Write or Call

SASGEN DERRICK CO.

3101 Grand Ave., Chicago
Telephone Nevada 800-801

No job too big or too small where a **Sasgen Derrick** cannot be used to good advantage. Will pay for themselves on any fair sized job. We send Derricks on trial to reliable contractors. Our Derricks are built of best malleable and crucible steel fittings. No cast iron.

CITY HALL AND COUNTY BUILDING INFORMATION AND GUIDE.

TAXES: When and Where to Pay.

GENERAL TAXES: State, County and City.

Annually at **County Treasurer's Office**, County Building, 1st floor, north end. Must be paid before May 1 of each year. Failure to pay before May 1 means a penalty of one (1%) per cent per month until sold. (Then heavier penalty; and trouble.)

SPECIAL ASSESSMENTS: (Street Paving, Water Pipes, etc.)

Payable before July 1 at City Collector's Office, City Hall, first floor, south end.

Payable on and after August 1 at County Treasurer's Office, County Building, first floor, north end.

WATER TAX:

At Bureau of Water, City Hall, 1st floor, north end.

DOG TAX:

City Clerk, 1st floor, south end.

OFFICES—CITY HALL.

Ambulance Service, Bureau of, vault floor, south end.

Architect, City, 10th floor, south end.

Board of Election Commissioners, 3rd floor, south end.

Board of Examiners:

Motor Vehicle Operators, 180 N. LaSalle St.
Moving Picture Operators, 6th floor, south end.

Plumbers, 10th floor, south end.

Stationary Engineers, 10th floor, south end.

Board of Inspectors of Public Vehicles, 3rd floor, 180 N. LaSalle St.

Board of Local Improvements:

General Offices, 2nd floor, south end.
Public Hearing Room, 1st floor, north end.
Law Department, 2nd floor, south end.

Boiler Inspection, 1st floor, Washington St. entrance.

Buildings, Department of, 7th floor, north end.

Bridge Division, 4th floor, north end.

Business Agent, vault floor, north end.

City Attorney, 6th floor, north end.

City Clerk, 1st floor, south end.

City Collector, 1st floor, south end.

City Comptroller (5th floor, north end):

General Office.
Auditor.
Paymaster.
Real Estate Agent.

City Council:

Council Chamber, 2nd floor, north end.
General Committee Rooms, 2nd floor, north end.

Committee on Finance, 3rd floor, north end.
Committee on Local Transportation, 2nd floor, north end.

City Electrician, 6th floor, south end.

City Forester, 10th floor, north end.

City Hall:

Engineer, basement, south end.
Chief Janitor, basement.

City Sealer, 8th floor, south end.

City Statistician, 10th floor, north end.

City Treasurer, 2nd floor, center.

Civil Service Commission:

General Offices, 6th floor, south end.
Examining Room, 10th floor, center.

Compensation, Bureau of, vault floor, south end.

Corporation Counsel, 5th floor, south end.

Dog Pound, W. 29th St. and S. Sacramento Ave.

Education, Board of, 646 So. Clark St.

Engineering, Bureau of (City Engineer), 4th floor, north end.

Election Commissioners, Board of, 3rd floor, center.

Electricity, Department of, 6th floor, south end.

Electrical Supervisor, R. 613, south end.

Fire Department:

Fire Marshal, 1st floor, north end.
Fire Alarm Telegraph, 6th floor, center.
Firemen's Pension Fund, Secretary of Board of Trustees (City Clerk), 1st floor, south end.

Department Attorney, 1st floor, south end

Fire Prevention & Public Safety, Bureau of, 6th floor, north end.

Foods, Markets & Farm Products, Bureau of, 10th floor, north end.

Gas & Electricity, Dept. of, R. 614, center.

Gas Litigation Committee, 139 N. Clark St.

Gas, Oil & Electric Light, Committee on, 2nd floor, north end.

Gas Supervisor, 6th floor, south end.

Harbor Board, R. 406, south end.

Harbor Division, 4th floor, north end.

Health, Department of, 7th floor.

Commissioner of Health.
Bureau of Food Inspection.
Bureau of Sanitary Inspection.
Bureau of Contagious Diseases.
Bureau of Vital Statistics.

High Cost of Living Commission, R. 1003, north end.

House of Correction, W. 26th St. and S. California Ave.

Laboratory, Health Department, R. 713, south end.

Law, Department of:

Corporation Counsel, 5th floor, south end.
City Attorney, 6th floor, north end.
Prosecuting Attorney, 6th floor, north end.
Special Assessment Attorney, 2nd floor, south end.

Library, Chicago Public, N. Michigan Ave. and E. Washington St.

Library, Municipal Reference, 10th floor, north end.

Local Transportation, Committee on, 2nd floor, north end.

Maps and Plats, Bureau of, 4th floor, south end.

Mason Contractors, Board of Examiners of, R. 1008, south end.

Mayor's Office, 5th floor, center.

Morals Commission, R. 710, south end.

Motor Vehicle Operators, Board of Examiners, 180 N. La Salle St.

Moving Picture Operators, Board of Examiners, 6th floor, south end.

Municipal Court:

Chief Justice, 9th floor, south end.
Bailliff, 8th floor, north end.
Clerk, 8th floor, south end.
Court Rooms, 8th, 9th and 11th floors.



Federal Reserve Bank
Building

Chicago, Illinois

Graham, Anderson,
Probst & White,
Architects

*Equipped with 110 ton
capacity air cooling plant*

*25 ton capacity kitchen
refrigerator and drinking
water cooling plant*

Wittenmeier Machinery Company

850 N. Spaulding Ave.

Chicago, Ill.

Telephone, Van Buren 601

Manufacturers of

CO₂ REFRIGERATING MACHINES

FOR ALL PURPOSES

Specialists in Air Cooling Installations

Municipal Lodging House, 162 N. Union Ave.
Municipal Pension Fund, R. 1005, north end.
Municipal Pier, foot of East Grand Ave.
Municipal Reference Library, 10th floor, north end.
Oils, Inspector of, 10th floor, south end.
Parks, Playgrounds & Bathing Beaches, Bureau of, 10th floor, north end.
Physician, City, 25 E. Washington St.
Plan Commission, Chicago, Hotel Sherman.
Police Department:

General Superintendent, 5th floor, north end.

Assistant General Superintendent, 3rd floor, north end.

Police Pension Fund, 10th floor, north end.

Plumbers, Board of Examiners of, 10th floor, south end.

Prosecuting Attorney, 6th floor, north end.

Public Service, Dept. of, R. 613, south end.

Public Welfare, Dept of, 139 N. Clark St.

Public Works:

Commissioner, 4th floor, center.

Bureau of Engineering, 4th floor, north end.

Bridge Division, 4th floor, north end.

Harbor Division, 4th floor, north end.

Bureau of Maps and Plats, 4th floor, south end.

Bureau of Sewers, 4th floor, south end.

Bureau of Streets, 4th floor, south end.

Bureau of Water, 1st floor, north end.

Water Pipe Extension Division, 4th floor, north end.

Railway Terminal Commission, 170 N. Dearborn St.

Sanitary Inspection, Bureau of, 7th floor, north end.

Schools, Supt. of, 646 S. Clark St.

Sewers, Bureau of, 4th floor, south end.

Smoke Inspection, Bureau of, R. 704, 7th floor.

Special Assessments (Board of Local Improvements), 2nd floor, south end.

Special Assessments (Law Department), 2nd floor, south end.

Stationary Engineers, Board of Examiners of, 10th floor, south end.

Statistician, City, 10th floor, north end.

Steam Boilers and Steam Plants, Department of Inspection of, 1st floor, Washington St. entrance.

Streets, Bureau of, 4th floor, south end.

Supervising Engineers, Board of, 105 S. La Salle St.

Supplies, Department of (Business Agent), vault floor, north end.

Telephone Supervisor, R. 612, south end.

Transportation Supervisor, R. 613, south end.

Treasurer, City, 2nd floor, center.

Tuberculosis Sanitarium, Municipal, 105 W. Monroe St.

Vehicles, Board of Inspectors of, 180 N. La Salle St., 3rd floor.

Waste Disposal, Bureau of, W. Pershing Rd. and Iron St.

Water, Bureau of, 1st floor, north end.

Water Pipe Extension Division, 4th floor, north end.

Weights and Measures, Department of, 6th floor, south end.

OFFICES—COUNTY BUILDING.

APPELLATE COURT, CLERK OF:

R. 1400 Michigan Blvd. Bldg.

BOARD OF ASSESSORS:

Members of the Board:

Charles Ringer,
Wm. H. Weber,
Adam Wolf,
George K. Schmidt,
Charles Krutckoff.

Chief Clerk:

Paul H. Wiedel,
R. 312, 3rd floor.

BOARD OF REVIEW:

Members of Board:

Edward Litsinger,
P. A. Nash,
Charles V. Barrett.

Chief Clerk:

Stephen D. Griffin.
R. 337, 3rd floor:

CIRCUIT COURT:

Clerk:

August W. Miller.
R. 412, 4th floor.

Judges:

Hon. Victor P. Arnold,
Hon. John R. Caverly,
Hon. David M. Brothers,
Hon. Harry M. Fisher,
Hon. Hugo M. Friend,
Hon. Frank Johnston, Jr.,
Hon. George Kersten,
Hon. Thomas J. Lynch,
Hon. David F. Matchett,
Hon. Donald L. Morrill,
Hon. George Fred Rush,
Hon. Ira Ryner,
Hon. Kickham Scanlan,
Hon. Philip L. Sullivan,
Hon. John A. Swanson,
Hon. Thomas Taylor, Jr.,
Hon. Charles M. Thomson,
Hon. Oscar M. Torrison,
Hon. Francis S. Wilson,
Hon. Thomas G. Windes,

CIVIL SERVICE COMMISSION:

Harry A. Lipsky.
James M. Whalen.
Ralph L. Peck, Secretary.
R. 547, 5th floor.

CLERK, COUNTY:

Robert M. Sweitzer,
R. 233, 2nd floor.

COMPTROLLER, DEPUTY COUNTY:

William J. Graham.
R. 511, 5th floor.

CORONER:

Peter M. Hoffman.
R. 500, 5th floor.

COUNTY AGENT:


Wm. H. Ehemann.
213 S. Pecunia St.

COUNTY CLERK:

Robert M. Sweitzer,
R. 233, 2nd floor.



Channon Building, Market and Randolph Sts., Chicago, Ill. Alfred S. Aschuler, Architect



The Clemetsen Co. Building, Homan Ave. and Division St. Mundie & Jensen, Architects

R. F. WILSON & COMPANY

Building Construction

Phone Haymarket 1836-37

1841-51 Elston Ave., CHICAGO

COUNTY COMMISSIONERS, BOARD OF:

Daniel Ryan, President.

Commissioners, City Districts:

Charles N. Goodnow,
Robert W. McKinlay,
Frank J. Wilson,
Emmett Whealan,
Joseph M. Fitzgerald,
Bartley Burg,
Albert Nowak,
Daniel Ryan,
Thos. Murray.

Country Districts:

William Busse,
Joseph Carolan,
Dudley D. Pierson,
George A. Miller,
William H. McLean.

Committee Clerk:

Peter J. Ellert.
R. 537.

COUNTY COURT:

Frank S. Righeimer, Judge.
R. 602, 6th floor.
Robert M. Sweitzer, Clerk.
R. 600, 6th floor.

COUNTY HOSPITAL:

Michael Zimmer, Warden.
Harrison and Wood Sts.

COUNTY SUPERINTENDENT OF SCHOOLS:

Edward J. Tobin.
R. 1122, 11th floor.

COUNTY TREASURER:

Patrick J. Carr.
Office, R. 212, 2nd floor.
General Office, 1st floor, north end.

CUSTODIAN, COUNTY BUILDING:

Albert F. Peters.
R. 1026, 10th floor.

FOREST PRESERVE COMMISSIONERS, BOARD OF:

R. 547, 5th floor.

HIGHWAYS, SUPERINTENDENT OF:

R. 1126, 11th floor.

JURY COMMISSIONERS:

Joseph H. Barnett.
Chas. W. Seinwerth.
B. J. Mullaney
Martin Peterson, Clerk
R. 824, 8th floor.

JUVENILE COURT:

Hon. Victor P. Arnold, Judge.
9th floor.

MORGUE, COUNTY:

Harrison and Wood Sts.

OAK FOREST INFIRMARY:

H. L. Bailey, Superintendent.
Oak Forest, Illinois.

PROBATE COURT:

Hon. Henry Horner, Judge.
R. 643, 6th floor.
John F. Devine, Clerk.
R. 623, 6th floor.

RECORDER OF DEEDS:

Joseph F. Haas.
1st floor, south end

REGISTRAR OF TITLES (Torrens System):

Joseph F. Haas.
1st floor, south end.

REVIEW, BOARD OF:

R. 337, 3rd floor.

SHERIFF:

Chas. W. Peters.
R. 423, 4th floor.

SOCIAL SERVICE, BUREAU OF:

Miss Katherine Meade, Superintendent.
R. 1130, 11th floor.

STATE'S ATTORNEY:

Robert E. Crowe.
Austin and Dearborn Aves.

SUPERIOR COURT:**Judges:**

Hon. Albert C. Barnes,
Hon. William Fennimore Cooper,
Hon. Theodore Brentano,
Hon. Joseph B. David,
Hon. William E. Dever,
Hon. Joseph H. Fitch,
Hon. Charles M. Foell,
Hon. Martin B. Gridley,
Hon. Harry A. Lewis,
Hon. Jacob H. Hopkins,
Hon. Oscar Hebel,
Hon. Joseph Sabath,
Hon. Marcus A. Kavanagh,
Hon. Charles A. MacDonald,
Hon. M. L. McKinley,
Hon. Hugo Pam,
Hon. Denis E. Sullivan,
Hon. John J. Sullivan,
Hon. William J. McSurely,
Hon. John M. O'Connor.

Clerk:

Samuel E. Erickson.
R. 437, 4th floor.

SUPERINTENDENT OF PUBLIC SERVICE:

Henry A. Zender.
R. 519, 5th floor.

SUPERINTENDENT OF SCHOOLS (COUNTY):

E. J. Tobin.
R. 1122, 11th floor.

SURVEYOR:

Ben H. Suhr.
R. 726, 7th floor.

TAX EXTENSION DEPARTMENT:

M. J. O'Brien, Chief.
R. 217, 2nd floor.

TORRENS SYSTEM:

Joseph F. Haas, Registrar.
1st floor, south end.

COUNTY ARCHITECT:

Erick E. Hall.
123 W. Madison St.

TREASURER, COUNTY:

Office, R. 212, 2nd floor.
General Offices, 1st floor, north end.

CLERK OF CRIMINAL COURT:

Wm. R. Parker.
Austin and Dearborn Aves.



The Federal Reserve Bank Bldg., Chicago

Graham, Anderson, Probst & White, Archts., Chicago

John Griffiths & Son Co.

BUILDERS

CHICAGO

CITY OFFICIALS

WM. HALE THOMPSON	Mayor.
JOHN M. KELLY	Secretary to the Mayor
HUGH NORRIS	Oil Inspector.
WM. STOCKER	City Sealer.
GEORGE F. HARDING	City Comptroller.
LOUIS E. GOSSELIN	Deputy City Comptroller.
CHARLES R. FRANCIS	Commissioner of Public Works.
CLAYTON F. SMITH	City Treasurer.
JAMES T. IGOE	City Clerk.
EDWARD J. PADDEN	Chief Clerk, City Clerk's Office.
J. WYATT McGAFFEY	Reading Clerk, City Council.
WM. G. KEITH	City Electrician.
JAMES REA	Department of Supplies.
AGE ZYLSTRA	City Collector.
ALEXANDER RAMSAY	Deputy City Collector.
JOHN DILL ROBERTSON	Health Department.
DR. GOTTFRIED KOEHLER	Asst. Comr. of Health.
DR. HEMAN SPAULDING	Chief Medical Inspector.
THOS. H. BYRNE	Superintendent of Streets.
JOS. P. GEARY	
CHAS. E. FRAZIER	} Civil Service Commission.
ALEX. J. JOHNSON	
HARRY E. WALLACE	Secretary, Civil Service Commission.
CHAS. BOSTROM	Building Commissioner.
ROBERT KNIGHT	Chief Deputy, Building Commissioner.
CHAS. C. FITZMORRIS	Chief of Police.
JOHN H. ALCOCK	1st Deputy Sup't of Police.
PHILIP R. CRIPPEN	Department Inspector.
SAMUEL A. ETTIELSON	Corporation Counsel.
WM. H. DEVENISH	City Attorney.
LOUIS P. PIQUETT	City Prosecutor.
JOHN D. RILEY	Map Department.
DR. W. J. POLLOCK	City Physician.
DR. CLARA P. SEIPPEL	Asst. City Physician.
WILLIAM J. McCOURT	Superintendent, Bureau of Water.
WM. H. REID	Comr. of Public Service.
EDW. F. MOORE	
PHILIP M. GIESELER, Pres.	} Board of Examining Engineers.
FRANK A. WEST	
MICHAEL HUGHES	Chief Detective Bureau.
GEO. E. NYE	Inspector of Steam Boilers and Steam Plants
N. E. MURRAY	Superintendent of Sidewalks.
DR. E. V. HILL	Chief of Sanitary Bureau.
EDWARD PRITCHARD	Secretary, Health Department.
SIMON MAYER	Secretary of Police.
ALEXANDER MURDOCH	City Engineer.
M. J. FAHERTY (Prest.)	
DAVID W. CLARK	
OSCAR WOLFF	} Board of Local Improvements.
MRS. IRENE MONTONYA	
LEONARD WITHALL	
EDWARD J. GLACKIN	Secretary of Board of Local Improvements.
THOS. O'CONNOR	Fire Marshal.
GEO. E. McGRATH	Supt. of Sewers.
FREDERICK REX	Municipal Reference Librarian.
JOS. B. McDONOUGH	Chairman, Special Park Commission.
H. J. HAENISCH	Supt. Bureau of Compensation.
JOS. SIMAN	Supt. House of Correction.
CHARLES W. KALLAL	City Architect.
LOUISE O. ROWE	Supt. of Public Welfare.
CHARLES TODD	
WM. W. PETRIE (Journeyman)	} Board of Examining Plumbers.
CHAS. STEWART (Member)	
WM. P. CROWE (Member)	} Board of Examining Mason Contractors.



*Warehouses for Griswold & Walker Co., extending from Morgan St. to Peoria St.,
between the B. & O. R. R. and N. W. R. R. tracks at 15th St.
A. S. Alschuler, Architect, Steger Bldg., Chicago*

Telephones: Harrison 5926 and 1846

J. W. Snyder Company

General Contractors

MASONRY, CARPENTRY
REINFORCED CONCRETE

Peoples Gas Building

CHICAGO, ILLINOIS

THE CITY COUNCIL, CHICAGO

WILLIAM HALE THOMPSON, Mayor

JAMES T. IGOE, City Clerk

EDWARD J. PADDEN, Chief Clerk

1ST WARD	MICHAEL KENNA, D, 311 S. Clark st.....	Har.	872
	JOHN J. COUGHLIN, D, 17 N. La Salle st.....	Main	1157
2ND WARD	LOUIS B. ANDERSON, R, 508, 184 W. Washington st.....	Frank.	2717
	ROBERT R. JACKSON, R, 3300 S. State st.....	Douglas	2344
3RD WARD	JOHN H. JOHNTY, 4503 Oakenwald av.....	Kenwood	8045
	U. S. SCHWARTZ, D, 906, 6 N. Clark st.....	Frank.	640
4TH WARD	TIMOTHY A. HOGAN, D, 3038 Throop st.....	Drover	9155
	JOHN A. RICHERT, D, 2603 S. Halsted st.....	Yards	1148
5TH WARD	JOS. B. McDONOUGH, D, 538 W. 37th st.....	Yards	1951
	ROBERT J. MULCAHY, D, 3357 Archer av.....	Lafayette	3869
6TH WARD	CHARLES S. EATON, R, 500, 35 N. Dearborn st.....	Rand.	281
7TH WARD	GUY GUERNSEY, R, 1515 Harris Trust bldg.....	Rand.	901
8TH WARD	ROSS A. WOODHULL, D, 9117 Commercial av.....	S. Chgo.	1800
	MARTIN S. FURMAN, D, 8745 Commercial av.....	S. Chgo.	296
9TH WARD	GUY MADDERM, R, 11030 S. Michigan av.....	Pull.	264
	SHELDON W. GOVIER, D, 11350 Forrestville av.....	Pull.	1991
10TH WARD	JAMES McNICHOLS, D, 1322 Washburne av.....	Canal	2866
11TH WARD	DENNIS A. HORAN, 1914 S. Ashland av.....	Canal	4555
	LEONARD RUTKOWSKI, 1727 W. 18th st.....	Canal	864
12TH WARD	ANTON J. CERMAK, D, 3347 W. 26th st.....	Lawndale	3200
	JOSEPH CEPAK, 2604 W. 21st Pl.....	Rockwell	759
13TH WARD	SAMUEL O. SHAFFER, R, 3916 W. Van Buren St.....	Cent.	6442
	JOHN G. HORNE, D, 3230 W. Madison st.....	Kedzie	3370
14TH WARD	GEO. M. MAYPOLE, D, 3523 Fulton st.....	Garfield	9128
	JOSEPH H. SMITH, D, 2342 W. Superior st.....	Seeley	135
15TH WARD	EDWARD J. KAINDL, D, 2600 W. Chicago av.....	Humb.	5684
	OSCAR H. OLSEN, R, 1905, 139 N. Clark st.....	Cent.	1625
16TH WARD	JOHN CZEKALA, 1839 Evergreen av.....	Humb.	6678
	JOHN A. PIOTROWSKI, D, 1459 Blackhawk st.....	Monroe	342
17TH WARD	THOMAS P. DEVEREUX, 751 N. Racine av.....	Mon.	85
	S. S. WALKOWIAK, D, 1317, 139 N. Clark st.....	Rand.	3564
18TH WARD	JOHN J. TOUHY, D, 1339 W. Adams st.....	Haymarket	2629
	MAURICE F. KAVANAGH, D, 666 W. Madison st.....	Mon.	6130
19TH WARD	JOHN POWERS, D, 1284 Macalister pl.....	Mon.	1215
	JAMES B. BOWLER, D, 631 S. Ashland av.....	Monroe	4943
20TH WARD	HENRY L. FICK, D, 559 W. Roosevelt rd.....	Canal	584
	MATT. FRANZ, D, 1700 S. Halsted st.....	Canal	3046
21ST WARD	DORSEY R. CROWE, D, 755 N. Dearborn st.....	Sup.	8843
	CHARLES J. AGNEW, 40 E. Elm st.....	Sup.	1452
22ND WARD	ARTHUR F. ALBERT, 1700 N. Halsted st.....	Lincoln	8545
	LEO C. KLEIN, 1426 Mohawk st.....	Diversey	8071
23RD WARD	THOS. O. WALLACE, R, 846 Center st.....	Lincoln	705
	WALTER P. STEFFEN, R, 545 Belmont Ave.....	Wellington	7140
24TH WARD	LEO M. BRIESKE, 3037 Lincoln av.....	Graceland	81
	JOHN HADERLIN, D, 1917 Barry av.....	Wellington	8963
25TH WARD	E. I. FRANKHAUSER, 522, 38 S. Dearborn st.....	Dearborn	1636
	FRANK J. LINK, R, 430 Orleans st.....	Main	1026
26TH WARD	CHARLES G. HENDRICKS, 1201-69 W. Washington st.....	Randolph	440
	THOS. R. CASPERS, 1770 Cullom av.....	Wellington	5125
27TH WARD	EDWARD R. ARMITAGE, R, 5826 Berenice ave.....	Kildare	4530
	CHRIST A. JENSEN, 4226 N. Sawyer av.....	Monticello	1028
28TH WARD	HENRY SCHLEGEL, 2930 Lyndale st.....	Armitage	7508
	MAX ADAMOWSKI, D, 2812 Fullerton av.....	Armitage	300
29TH WARD	JAMES F. KOVARIK, D, 5022 S. Marshfield av.....	Repub.	322
	THOMAS F. BYRNE, D, 6743 S. Irving av.....	Prospect	1259
30TH WARD	WM. J. LYNCH, 509 W. 43rd pl.....	Yards	3510
	WM. R. O'TOOLE, D, 1048 W. 55th st.....	Drover	180
31ST WARD	SCOTT M. HOGAN, R, 912 Ashland blk.....	Rand.	649
	TERRANCE F. MORAN, D, 5634 S. Ada st.....	Englewood	6593
32ND WARD	BENJAMIN S. NELSON, 7240 Yale ave.....	Stewart	2028
	JOHN H. LYLE, R, 300-4, 108 S. La Salle st.....	Main	935
33RD WARD	JOHN P. GARNER, R, 5615 W. Lake st.....	Austin	1756
	ALBERT O. ANDERSON, R, 4346 Fullerton av.....	Belmont	78
34TH WARD	JOS. O. KOSTNER, 402 Ashland blk.....	State	6060
	JOHN TOMAN, D, 4141 W. 21st pl.....	Lawndale	4986
35TH WARD	JOHN S. CLARK, D, 4259 W. North av.....	Belmont	8810

(Continued on Page 129)

The Policy of a Square Deal

WELLS BROTHERS have an enviable record of re-deal-peat orders, the result, we believe, of a square policy.

Nine times we have served Montgomery Ward & Co. and on the Fixed-Fee basis, which tests not only the builder's experience and skill but also his honesty of purpose and conscientious regard for the owner's rights.

In 1920 we built their branch mail order house at St. Paul, 878,000 square feet of floor, *on time and below the estimate of cost.* The type of construction was difficult and the period one of trying delays and rising costs. Yet we justified their trust.

Would not the same capable organization, serving for a moderate fee and spurred to economy by a share in the savings, relieve you and your client of worry and trouble? Then, too, the time is one in which substantial savings are almost certain.

Frequently we have won work in lump-sum competition and then saved money for the owner by turning to the Fixed-Fee contract. We can serve you similarly.

Montgomery Ward
& Co.'s
Branch Mail Order
House at St. Paul



WELLS BROTHERS CONSTRUCTION CO.

1871—1921

STANDING COMMITTEES

1921-22

WILLIAM F. HARRAH, Sergeant-at-Arms.
Residence Phone, Lake View 9609.

THOMAS J. COURTNEY, Asst. Sergeant-at-Arms.

JOHN TWOHIG, Asst. Sergeant-at-Arms.

HENRY SONNENSCHIEIN, Asst. Sergeant-at-Arms.

JOHN DOHNEY, Asst. Sergeant-at-Arms.

Finance. Meets on Fridays at 1:00 P. M.—**RICHERT**, L. B. Anderson, Schwartz, Guernsey, Woodhull, Cermak, Maypole, Powers, Crowe, Steffen, Armitage, Adamowski, Moran, Lyle, A. O. Anderson, Garner, Kostner, Clark.

Local Transportation. Meets on Thursdays at 2:30 P. M.—**SCHWARTZ**, L. B. Anderson, T. A. Hogan, Mulcahy, Guernsey, Madderom, Shaffer, Smith, Olsen, Walkowiak, Bowler, Franz, Wallace, Link, Jensen, Byrne, W. J. Lynch, Garner, Toman.

Railroads, Industries and Compensation. Meets on Tuesdays at 2:30 P. M.—**CERMAK**, L. B. Anderson, Schwartz, McDonough, Eaton, Guernsey, McNichols, Horan, Horne, Smith, Olsen, Walkowiak, Touhy, Bowler, Franz, Wallace, Haderlein, Link, Caspers, Armitage, Byrne, O'Toole, S. M. Hogan, Kostner, Clark.

Gas, Oil and Electric Light. Meets on Fridays at 2:30 P. M.—....., Jackson, T. A. Hogan, Furman, Madderom, McNichols, Horan, Cepak, Horne, Kaindl, Walkowiak, Bowler, Haderlein, Link, Armitage, Adamowski, O'Toole, Moran, Toman.

Judiciary. Meets on Mondays at 2:00 P. M.—**OLSEN**, Coughlin, Jackson, Schwartz, T. A. Hogan, Guernsey, Woodhull, Govier, Rutkowski, Maypole, Walkowiak, Powers, Agnew, Steffen, Brieske, Frankhauser, S. M. Hogan, Lyle, A. O. Anderson.

Buildings and Zoning. Meets on Tuesdays at 10:30 A. M.—**O'TOOLE**, Jackson, Johntry, T. A. Hogan, Mulcahy, Madderom, McNichols, Cepak, Shaffer, Smith, Kaindl, Piotrowski, Kavanagh, Powers, Fick, Klein, Adamowski, Kovarik, S. M. Hogan.

Schools, Fire and Civil Service. Meets on Thursdays at 11:00 A. M.—**ARMITAGE**, Coughlin, Jackson, Madderom, Horan, Shaffer, Kaindl, Piotrowski, Devereux, Kavanagh, Fick, Albert, Hendricks, Schlegel, O'Toole, S. M. Hogan, A. O. Anderson, Kostner.

Harbors, Wharves and Bridges. Meets on Wednesdays at 11:00 A. M.—**WOODHULL**, Kenna, Rutkowski, Shaffer, Smith, Piotrowski, Powers, Agnew, Albert, Wallace, Haderlein, Caspers, Jensen, Lyle, Garner.

Public Health. Meets on Fridays at 11:00 A. M.—**GARNER**, Kenna, Jackson, Johntry, Furman, Rutkowski, Cermak, Horne, Czekala, Devereux, Kavanagh, Brieske, Frankhauser, Caspers, Moran, Wilson,

Track Elevation. Meets on Wednesdays at 11:00 A. M.—**MAYPOLE**, Coughlin, Mulcahy, Furman, Govier, McNichols, Horan, Cermak, Devereux, Touhy, Fick, Crowe, Klein, Hendricks, Jensen, Kovarik, W. J. Lynch, Moran, Kostner.

Police and Municipal Courts. Meets on Mondays at 11:30 A. M.—**STEFFEN**, Kenna, Johntry, McDonough, Eaton, Woodhull, Rutkowski, Cepak, Horne, Maypole, Czekala, Franz, Agnew, Frankhauser, Hendricks, Schlegel, Byrne, Wilson, A. O. Anderson.

Streets and Alleys. Meets on Mondays at 10:30 A. M.—**TOMAN**, Coughlin, T. A. Hogan, Mulcahy, Govier, Rutkowski, Cepak, Czekala, Devereux, Kavanagh, Powers, Fick, Agnew, Klein, Jensen, Adamowski, Kovarik, W. J. Lynch, Moran.

High Costs and High Rents. Meets on Saturdays at 10:30 A. M.—**GOVIER**, Mulcahy, Furman, Kaindl, Czekala, Devereux, Touhy, Albert, Steffen, Brieske, Caspers, Schlegel, Kovarik, S. M. Hogan.

Public Markets. Meets on Tuesdays at 11:30 A. M.—**KAVANAGH**, Furman, McNichols, Walkowiak, Bowler, Franz, Albert, Brieske, Hendricks, Jensen, Schlegel, Kovarik, Lyle, A. O. Anderson, Clark.

Municipal Institutions and City Hall. Meets on Mondays at 2:00 P. M.—**SHAFFER**, Johntry, McDonough, Touhy, Fick, Crowe, Haderlein, Hendricks, Schlegel, Byrne, W. J. Lynch, Wilson, Toman.

Efficiency, Economy and Rehabilitation. Meets on Thursdays at 11:00 A. M.—**EATON**, Richert, Olsen, Klein, Steffen, Frankhauser, Caspers, Wilson, Garner, Clark.

License. Meets on Tuesdays at 11:30 A. M.—**PIOTROWSKI**, Coughlin, Richert, Govier, Horan, Kaindl, Czekala, Franz, Klein, Wallace, Toman.

Redistricting. Meets on Saturdays at 10:00 A. M.—**BYRNE**, Kenna, Richert, Eaton, Madderom, Cermak, Horne, Smith, Olsen, Bowler, Agnew, Wallace, Link, Armitage, W. J. Lynch, Lyle, Clark.

Parks, Playgrounds and Beaches. Meets on Wednesdays at 11:00 A. M.—**MCDONOUGH**, Kenna, L. B. Anderson, Johntry, Cepak, Piotrowski, Touhy, Albert, Haderlein, Brieske, O'Toole.

Gas Litigation. Meets subject to call of Chairman.—**GUERNSEY**, L. B. Anderson, Schwartz, Richert, McDonough, Eaton, Woodhull, Crowe, Frankhauser, Kostner,

Aviation. Meets on Mondays at 4:00 P. M.—**LINK**, Maypole, Crowe, Adamowski, Wilson.

Committees and Rules. Meets subject to call of Chairman.—**SCHWARTZ** (alternate Guernsey), Cermak (alternate, Woodhull), Bowler (alternate, Fick), Armitage (alternate, Adamowski), O'Toole (alternate, S. M. Hogan).



ST. MARY'S OF THE LAKE THEOLOGICAL SEMINARY

AREA, ILLINOIS

JOSEPH W. McCARTHY
Architect
Chicago

THOMPSON STARRETT CO.
General Contractors
Chicago

Thompson-Starrett Company

Building Construction

INSURANCE EXCHANGE BUILDING
CHICAGO

Telephone, Wabash 1384

MECHANICS LIEN LAW

State of Illinois

1. "Contractor" defined—lien upon real estate for material or labor furnished.
2. Liens for labor or material furnished by mistake.
3. Husband and wife.
4. Breach of contract by owner—recovery of material—other provisions.
5. Claims of sub-contractor—notice of to owner—owner's duty—contractor's liability—exceptions.
6. Time for completing contract.
7. Limitation as against third parties—claim for lien—proof of delivery sufficient.
8. Assigning liens or claims for liens.
9. Suit—how brought—joint suits—cross bill—dismissal—surprise—limitation.
10. Personal representatives—death of parties in interest.
11. "Parties in interest" defined—dismissal—notice.
12. Practice—powers of court—receivers.
13. Practice—answer—defense—counter claim.
14. Trials—delay—order for sale.
15. Preferences.
16. Incumbrances—pro rata benefits.
17. Costs—attorney fees.
18. Sales of estates—partial sales.
19. Proceeds of sale—application—preferences—deficiency and surplus.
20. Redemption.
21. "Sub-contractor" defined—preferences—limit of ability—abandonment of contract.
22. Partner after contract—statement of sub-contractor—failure—penalty.
23. Lien against public funds—public improvements—liability and duty of official.
24. Notice by sub-contractor—agents, architects and superintendents to be notified—form of notice.
25. Notice to non-residents.
26. Preferential liens.
27. Owners' duty after notice—preferences.
28. Suits by sub-contractor—proceedings.
29. Judgment before justice—transcript—executions.
30. General settlement—procedure.
31. Failure to complete contract—owner's liability to sub-contractor.
32. Wrongful payment of owner to contractor.
33. Limitation as to suit of sub-contractor.
34. General provisions.
35. Neglect—penalty.
36. Wrongful sale or removal of material—penalty.
37. Liens against water craft.
38. Filing claims—circuit clerk's duties—fees.
39. Construction of Act.
40. Repeals of Act of 1895.

AN ACT

To Revise the Law in Relation to Mechanics' Liens; To Whom, What For and When Lien Is Given; Who Is a Contractor; Area Covered by and Extent of Lien; When the Lien Attaches. (Approved May 18, 1903; in Force July 1, 1903; as Amended by Act Approved June 16, 1913, in Force July 1, 1913.)

Section 1. **When Lien Given.)** Be it Enacted by the People of the State of Illinois, Represented in the General Assembly: That any person who shall by any contract or contracts, express or implied, or partly expressed or implied, with the owner of a lot or tract of land, or with one whom such owner has authorized or knowingly permitted to contract for the improvement of, or to improve the same, furnish material, fixtures, apparatus or machinery, forms or form work used in the process of construction where cement, concrete or like material is used for the purpose of or in the building, altering, repairing or ornamenting any house or other building, walk or sidewalk, whether such walk or sidewalk be on the land or bordering thereon, driveway, fence or improvement or appurtenances thereto on such lot or tract of land or connected therewith, and upon, over or under a sidewalk, street or alley adjoining; or fill, sod or excavate such lot or tract of land, or do landscape work thereon or therefor; or raise or lower any house thereon or remove any house thereto; or perform services as an architect or as a structural engineer for any such purpose; or furnish or perform labor or services as superintendent, timekeeper, mechanic, laborer or otherwise, in the building, altering, repairing or ornamenting of the same; or furnish material, fixtures, apparatus, machinery, labor or services, forms or form work used in the process of construction where concrete, cement or like material is used, on the order of his agent, architect, structural engineer or superintendent having charge of the improvements, building, altering, repairing or ornamenting the same, shall be known under this Act as a contractor, and shall have a lien upon the whole of such lot or tract of land and upon the adjoining or adjacent lots or tracts of land of such owner constituting the

same premises and occupied or used in connection with such lot or tract of land as a place of residence or business; and in case the contract relates to two or more buildings, on two or more lots or tracts of land, upon all such lots and tracts of land and improvements thereon for the amount due to him for such material, fixtures, apparatus, machinery, services or labor, and interest from the date the same is due. This lien shall extend to an estate in fee, for life, for years, or any other estate or any right of redemption, or other interest which such owner may have in the lot or tract of land at the time of making such contract or may subsequently acquire therein, and shall be superior to any right of dower of husband or wife in said premises, provided the owner of such dower interest had knowledge of such improvement and did not give written notice of his or her objection to such improvement before the making thereof; nor shall the taking of additional security by the contractor or sub-contractor be a waiver of any right of lien which he may have by virtue of this Act, unless made a waiver by express agreement of the parties; and this lien shall attach as the date of the contract. (As amended by Act approved June 28, 1919.)

Section 2. **Liens for Work or Materials by Mistake Put Upon Land Other Than the Contracting Parties.)** Any person furnishing services, labor or material for the erection of a building, or structure, or improvement, by mistake, upon land owned by another than the party contracting as owner, shall have a lien for such services, labor or material upon such building, or structure, or improvement, and the court, in the enforcement of such lien, shall order and direct such building, structure or improvement to be separately sold under its decree, and the purchaser may remove the same within such reasonable time as the court may fix.

Section 3. **Liens for Work or Materials Under Contract with Husband on Land of Wife.)** If any such services or labor are performed upon or materials are furnished for lands belonging to any married woman, with her knowledge and not against her protest in writing, as provided in Section 1 of



Hirsh, Blum, Co. Inc. — Graham, Anderson, Prosser & White Architects

Lanquist & Illsley Company

BUILDERS

First structural steel column set August 8, 1920

Interior completed Jan. 29, 1921

Occupied April 1, 1921

Telephones:

**Superior 207
and - 2049**

1100 North Clark St.

CHICAGO

this Act, in pursuance of a contract with the husband of such married woman, the person furnishing such labor or materials shall have a lien upon such property, the same as if such contract had been made with (the) married woman, and in case the title to such lands upon which improvements are made is held by husband and wife jointly, the lien given by this Act shall attach to such lands and improvements, if the improvements be made in pursuance of a contract with both of them, or in pursuance of a contract with either of them, and in all such cases no claim of homestead right set up by a husband or wife shall defeat the lien given by this Act.

Section 4. Breach of Contract by Owner—Recovery for Material—Partial Performance—Quantum Meruit—Right to Reclaim—Unused Material.) When the owner of the land shall fail to pay the contractor moneys justly due him under the contract at the time when the same should be paid, or fails to perform his part of the contract in any other manner, the contractor may discontinue work, and the contractor shall not be held liable for any delay on his part during the period of, or caused by, such breach of contract on the part of the owner; and if, after such breach for the period of ten days, the owner shall fail to comply with his contract, the contractor may abandon the work, and in such case the contractor shall be entitled to enforce his lien for the value of what has been done, and the court shall adjust his claim and allow him a lien accordingly. In such cases all persons furnishing material which has not been incorporated in the improvement shall have the right to take possession of and remove the same if he so elects.

Section 5. Contractors to Notify Owners of Sub-Contracts and Amounts of Their Claims—Owner's Duty with Regard Thereto and Rights in Case of Default—Contractor's Liability for Failure to Give Statement—Contractors to Whom This Section Does Not Apply.) It shall be the duty of the contractor to give to the owner, and the duty of the owner to require of the contractor, before the owner or his agent, architect or superintendent, shall pay or cause to be paid to said contractor or to his order any moneys or other consideration due or to become due such contractor, or make or cause to be made to such contractor any advancement of any money or any other consideration, a statement in writing, under oath or verified by affidavit, of the names of all parties furnishing materials and labor, and of the amounts due or to become due each. Merchants and dealers in materials only shall not be required to make statements herein provided for.

Section 6. Time for Completion of Contract.) In no event shall it be necessary to fix or stipulate in any contract a time for the completion or a time for payment in order to obtain a lien under this Act: Provided, that the work is done or material furnished within three years from the commencement of said work or the commencement of furnishing said materials.

Section 7. Limitations as Against Third Parties—Claim for Lien—What Shall Consist of—When Claim May be Filed and When Amended—As to Errors in—Proof of Delivery of Material, Not Use, Sufficient—Delivery of Material at One Building Good for All Buildings.) No contractor shall be allowed to enforce such lien against or to the prejudice of any other creditor or incumbrancer or purchaser, unless within four months after completion, or if extra or additional work is done or material is delivered therefor within four months after the completion of such extra or additional work or the final delivery of such extra or additional material, he shall either bring suit to enforce his lien therefor or shall file with the clerk of the Circuit Court in the county in which the building, erection or other improvement to

be charged with the lien is situated, a claim for lien, verified by the affidavit of himself, or his agent or employee, which shall consist of a brief statement of the contract, the balance due after allowing all credits, and a sufficiently correct description of the lot, lots or tracts of land to identify the same. Such claim for lien may be filed at any time after the contract is made, and as to the owner may be filed at any time after the contract is made and within two years after the completion of said contract, or the completion of any extra work or the furnishing of any extra material thereunder, and as to such owner may be amended at any time before the final decree. No such lien shall be defeated to the proper amount thereof because of an error or overcharging on the part of any person claiming a lien therefor under this Act unless it shall be shown that such error or overcharge is made with intent to defraud; nor shall any such lien for material be defeated because of lack of proof that the material after the delivery thereof, actually entered into the construction of such building or improvement, although it be shown that such material was not actually used in the construction of such building or improvement: Provided, it is shown that such material was delivered either to said owner or his agent for such building or improvement, to be used in said building or improvement, or at the place where said building or improvement was being constructed, for the purpose of being used in construction or for the purpose of being employed in the process of construction as a means for assisting in the erection of the building or improvement in what is commonly termed forms or form work where concrete, cement or like material is used, in whole or in part: And, provided, further, that in case of the construction of a number of buildings under contract between the same parties, it shall be sufficient in order to establish such lien for material, if it be shown that such material was in good faith delivered at one of the said buildings for the purpose of being used in the construction of any one or all of such buildings, or delivered to the owner or his agent for such buildings, to be used therein; and such lien for such material shall attach to all of said buildings, together with the land upon which the same are being constructed, the same as in a single building or improvement: And, provided, further, that in the event the contract relates to two or more buildings on two or more lots or tracts of land, then all of said buildings and lots or tracts of land may be included in one statement of claim for a lien. (As amended by Act approved June 16, 1913, in force July 1, 1913.)

Section 8. Assignability of Liens or Claims for Liens—Rights of Assignee.) All liens or claims for lien which may arise or accrue under the terms of this Act shall be assignable, and proceedings to enforce such liens or claims for lien may be maintained by and in the name of the assignee, who shall have as full and complete power to enforce the same as if such proceedings were taken under the provisions of this Act by and in the name of the lien claimant.

Section 9. When, How and in What Court Suit May be Brought—Two or More Lien Holders May Join in Bringing Suit—Answers Stand as Cross-Bills—Original Bill Cannot be Dismissed Without Consent of Parties—Lien Claimants May Contest Each Other's Claims Without Formal Issues of Record—Rights in Case of Surprise—Limitation.) If payment shall not be made to the contractor having a lien by virtue of this Act of any amount due when the same becomes due, then such contractor may bring suit to enforce his lien by bill or petition in any court of competent chancery jurisdiction in the county where the improvement is located, and in the event that the contract relates to two or more buildings or two or more lots or tracts of land, then all of said buildings and lots or tracts of land may be in-

MUELLER CONSTRUCTION CO.

CLARENCE T. SEIPP

EDWARD L. LONERGAN



HARBOR APARTMENTS, CHICAGO

PETER J. WEBER, ARCHITECT

MUELLER CONSTRUCTION CO.

179 West Washington Street, Chicago, Illinois

cluded in one bill or petition. Any two or more persons having liens on the same property may join in bringing such suit, setting forth their respective rights in their bill or petition; all lien claimants not made parties thereto may, upon application, become defendants and enforce their liens by answer to the bill or petition in the nature of an intervening petition, and the same shall be taken as a cross-bill against all the parties to such suit; and the said bill or petition shall not thereafter be dismissed as to any such lien claimant, or as to the owner or owners of the premises without the consent of such lien claimant. The complainant or petitioner, and all defendants to such bill or petition may contest each other's right without any formal issue of record made up between them other than that (shown) upon the original bill or petition, as well with respect to the amount due as to the right to the benefit of the lien claimed. Provided, that if by such contest by co-defendants any lien claimants be taken by surprise, the court may, in its discretion, as to such claim grant a continuance. The court may render judgment against any party summoned and failing to appear, as in other cases of default. Such suit shall be commenced or answer filed within two years after the completion of the contract, or completion of the extra or additional work, or furnishing of extra or additional material thereunder.

Section 10. Personal Representatives—Death of Parties in Interest.) Suits may be instituted under the provisions of this Act in favor of administrators or executors, and may be maintained against the representatives in the interest of those against whom the cause of action accrued, and in suits instituted under the provisions of this Act, the representatives of any party who may die pending the suit shall be made parties.

Section 11. Who Are Parties in Interest—How and When Made—Or May Become Parties to Suit—Publication, Service of Process on Non-Resident—Claims Not Due, Etc.—Pleading, Requisites of Bill or Petition—Diligence Required in Prosecuting Claim—When and How Party Bringing Suit May Dismiss Same.) The bill or petition shall contain a brief statement of the contract or contracts on which it is founded, the dates when made and when completed, if not completed, why, and it shall also set forth the amount due and unpaid, a description of the premises which are subject to the lien, and such other facts as may be necessary to a full understanding of the rights of the parties. Where plans and specifications are by reference made a part of the contract, it shall not be necessary to set the same out in the pleadings or as exhibits, but the same may be produced on the trial of the suit. The complainant or petitioner shall make all parties interested, of whose interest he is notified or has knowledge, parties defendant, and summons shall issue and service thereof be had as in suits in chancery; and when any defendant resides or has gone out of the State, or on inquiry cannot be found, or is concealed within the State, so that process cannot be served on him, the complainant or petitioner shall cause a notice to be given to him in like manner and upon the same conditions as is provided in suits in chancery, and his failure to so act with regard to summons or notice shall be ground for judgment or decree against him as upon the merits. The same rule shall prevail with cross-petitioners with regard to any person of whose interest they have knowledge, and who are not already parties to the suit or action. Parties in interest, within the meaning of this Act, shall include persons entitled to liens thereunder, whose claims are not, as well as are, due at the time of the commencement of suit, and such claim shall be allowed subject to a reduction of interest from the date of judgment to the time the claim is due; also all persons who may have any legal or equitable claim to the whole or any part of the premises upon which a lien may be attempted to be enforced under the

provisions thereof, or who are interested in the subject matter of the suit. Any such persons may, on application to the court wherein the suit is pending, be made or become parties at any time before final judgment. No action or suit under the provisions of this Act shall be voluntarily dismissed by the parties bringing the same without due notice to all parties before the court and leave of court upon good cause shown and upon terms named by the court.

Section 12. Practice—Powers of Courts—When Receivers May be Appointed.) The court shall permit amendments to any part of the pleadings, and may issue process, make all orders requiring parties to appear, and requiring notice to be given, that are or may be authorized in proceedings in chancery, and shall have the same power and jurisdiction of the parties and subject matter, and the rules of practice and proceedings in such cases shall be the same as in other cases in chancery, except as is otherwise provided in this Act. The court shall have power to appoint receivers for property on which liens are sought to be enforced in the same manner, for the same causes and for the same purposes, as in cases of foreclosure of mortgages, as well as to complete any unfinished building where the same is deemed to be to the best interest of all the parties interested.

Section 13. Practice—Answer—Defense—Right to Recover on Counter Claim.) Defendant shall answer the bill or petition under oath, unless the oath is waived by the claimant or petitioner. The owner shall be entitled to make any defense against the contractor by way of set-off, recoupment or counter claim that he could in any action at law, and shall be entitled to the same right of recovery on proof of such in excess of the claim of the contractor against the contractor only, but for matters not growing out of the contract such recovery shall be made without prejudice to the rights of the subcontractors thereunder for payment of the contract price or fund; and in event that the court shall find, in any proceeding in chancery, that no right to a lien exists, the contractor shall be entitled to recover against the owner as at law, and the court shall render judgment as at law for the amount which the contractor is entitled to, together with costs, in the discretion of the court. In any proceedings to enforce a lien, it shall only be necessary for all persons seeking a lien on account of wages due for labor to file in such proceedings an affidavit, giving the amount due, between what dates the same was performed and the kind of labor performed, and the court shall direct the amount due for wages as therein specified to be paid within a short day to be fixed by the court, unless within ten days after the filing of said claim for wages the amount claimed is contested by the owner or some other party to the suit, and in order to contest the amount due for wages it shall be necessary for the party making such contest to file an affidavit in which he shall state the defense he has to the allowance of such claim, and the court shall proceed at once to hear such evidence as the parties may adduce, and determine the merits as to the allowance of such claim for wages, and in the event that the allowance for wages is not paid within the time fixed by the court, then the court shall order the premises sold to pay such amount, in such manner as the court shall direct.

Section 14. Trials—Parties Ready Not to be Delayed—When Court May Delay Order for Sale or Distribution.) In no case shall the want of preparation for trial of one claim delay the trial in respect to others, but trial shall be had upon issues between such parties as are prepared, without reference to issues between other parties; and when one creditor shall have obtained a decree or judgment for the amount due, the court may order a sale of the premises on which the lien operates, or a part thereof, so as to satisfy the decree or judgment;



CHANNEL CHEMICAL CO.
15th and Western Avenue, Chicago, Ill.

DAVIDSON & WEISS, ARCHITECTS
CHICAGO, ILLINOIS

A. LUND COMPANY

General Contractors

1117-1118 Association Building

19 South La Salle Street

Chicago, Ill.



TELEPHONE RANDOLPH 911

ESTABLISHED 1877

Provided, that the court may, for good cause shown, delay making any order for sale or distribution until the rights of all the parties in interest are ascertained and settled by the court.

Section 15. Preference to Laborers—No Preference to First Contractors.) Upon all questions arising between different contractors having lien under this Act, no preference shall be given to him whose contract was made first, except the claim of any person for wages by him personally performed shall be a preferred lien.

Section 16. Incumbrances—Apportionment—On Improvements Made After Record of Incumbrance—Lien Holders Have Pro Rata Benefit in What Owner Pays For—Fraudulent Incumbrances—Disposition of.) No incumbrance upon land, created before or after the making of the contract under the provisions of this Act, shall operate upon the building erected, or materials furnished, until a lien in favor of the persons having done work or furnished material shall have been satisfied, and upon questions arising between incumbrances and lien creditors, all previous incumbrances shall be preferred to the extent of the value of the land at the time of making of the contract, and the lien creditor shall be preferred to the value of the improvements erected on said premises, and the court shall ascertain by jury or otherwise, as the case may require, what proportion of the proceeds of any sale shall be paid the several parties in interest. All incumbrances, whether by mortgage, judgment or otherwise, charged and shown to be fraudulent, in respect to creditors, may be set aside by the court, and the premises freed and discharged from such fraudulent incumbrance.

Section 17. Costs—How Taxed—Attorneys' Fees.) The costs of proceedings, as between all parties to the suit, shall be taxed equitably against the losing parties, and where taxed against more than one party shall be so taxed against all in favor of the proper party, but equitably as between themselves; and the costs, as between creditors aforesaid in contests relative to each other's claims, shall be subject to the order of the court, and the same rule shall prevail in respect to costs growing out of the proceedings against and between incumbrances. In all cases where liens are enforced, the court shall, in its discretion, order a reasonable attorney's fee taxed as a part of the costs in favor of the lien creditor.

Section 18. What Estate to be Sold—Manner of Making Sales, When Part May be Sold.) Whatever right or estate such owner had in the land at the time of making the contract may be sold in the same manner as other sales of real estate are made under decrees in chancery. If any part of the premises can be separated from the residue, and sold without damage to the whole, and if the value thereof is sufficient to satisfy all the claims proved in the cause, the court may order a sale of that part.

Section 19. Proceeds of Sale—Application of Pro Rata—Labor Claims Preferred—Deficiency Decrees—Excess, to Whom Paid.) The court shall ascertain the amount due each lien creditor, and shall direct the application of the proceeds of sale to be made to each in proportion to their several amounts, according to the provisions of this Act, but the claims of all persons for labor, as provided in Section fifteen (15) shall first be paid. If, upon making sale under this Act, of any or all premises, the proceeds of such sale shall not be sufficient to pay all claims of all parties, according to their rights, the decree shall be credited by the amount of said sale, and execution may issue in favor of any creditor whose claims are not satisfied for the balance due as upon a deficiency decree in the foreclosure of a mortgage in chancery, and such deficiency decree shall be a lien upon all real estate and other property of the party against whom it is entered to the same extent and under the same limitations as a judgment at

law; and in cases of excess of sales over the amount of the decree, such excess be paid to the owner of the land, or to the person who may be entitled to the same, under the direction of the court.

Section 20. Redemption.) Upon all sales under this Act, the right of redemption shall exist in favor of the same persons, and may be made in the same manner as is or may be provided for redemption of real estate from sales under judgments and executions at law.

Section 21. Sub-Contractors — Liens of Sub-Contractors—Who Are—Extent of Their Liens Superior to Creditors or Contractors on Money Due Contractors—Duty of Owner and Contractor to File Notice of Waiver of Lien—Limit of Owner's Liability—Owner Liable for Sub-Contracts Performed After Notice Thereof—Rights of in Case Contractor Default May Complete, If Contractor Abandons.) Every mechanic, workman or other person who shall furnish any materials, apparatus, machinery or fixtures, or furnish or perform services or labor for the contractor, or shall furnish any material to be employed in the process of construction as a means for assisting in the erection of the building or improvement in what is commonly termed form or form work where concrete, cement or like material is used in whole or in part, shall be known under this Act as a sub-contractor, and shall have a lien for the value thereof, with interest on such amount from the date the same is due, from the same time, on the same property as provided for the contractor, and, also, as against the creditors and assignees, and personal and legal representatives of the contractor, on the material, fixtures, apparatus or machinery furnished, and on the moneys or other considerations due or to become due from the owner under the original contract. If the legal effect of any contract between the owner and contractor is that no lien or claim may be filed or maintained by any one, such provision shall be binding; but the only admissible evidence thereof as against a sub-contractor or material man, shall be proof of actual notice thereof to him before any labor or material is furnished by him; or proof that a duly written and signed stipulation or agreement to that effect has been filed in the office of the recorder of deeds of the county or counties where the house, building or other improvement is situated, prior to the commencement of the work upon such house, building or other improvement, or within ten days after the execution of the principal contract or not less than ten days prior to the contract of the sub-contractor or material man. And the recorder of deeds shall record the same at length in the order of time of its reception in books provided by him for that purpose, and the recorder of deeds shall index the same, in the name of the contractor and in the name of the owner, in books kept for that purpose, and also in the tract or abstract book of the tract, lot, or parcel of land, upon which said house, building or other improvement is located, and said recorder of deeds shall receive therefor a fee, such as is provided for the recording of instruments in his office.

In no case, except as hereinafter provided, shall the owner be compelled to pay a greater sum for or on account of the completion of such house, building or other improvement than the price or sum stipulated in said original contract or agreement, unless payment be made to the contractor or to his order, in violation of the rights and interests of the persons intended to be benefited by this Act; Provided, if it shall appear to the court that the owner and contractor fraudulently, and for the purpose of defrauding sub-contractors fixed an unreasonably low price in their original contract for the erection or repairing of such house, building or other improvement, then the



W. G. Uffendell, Architect

Edison Electric Appliance Co. Office Building

AVERY BRUNDAGE

GENERAL CONTRACTOR

110 S. Dearborn St.

Central 7762-3

CHICAGO



Fultz & Brandt, Architects

Chevrolet Motor Co. Warehouse

court shall ascertain how much of a difference exists between a fair price for labor and material used in said house, building or other improvement, and the sum named in said original contract, and said difference shall be considered a part of the contract and be subject to a lien. But where the contractor's statement, made as provided in Section five (5), shows the amount to be paid to the sub-contractor, or party furnishing material, or the sub-contractor's statement, made pursuant to Section twenty-two (22), shows the amount to become due for material; or notice is given to the owner, as provided in Sections twenty-four (24) and twenty-five (25), and thereafter such sub-contract shall be performed, or material to the value of the amount named in such statements or notice, shall be prepared for use and delivery, or delivered without written protest on the part of the owner previous to such performance or delivery, or preparation for delivery, then, and in any of such cases, such sub-contractor or party furnishing or preparing material, regardless of the price named in the original contracts, shall have a lien therefor to the extent of the amount named in such statements or notice. Also, in case of default or abandonment by the contractor, the sub-contractor or party furnishing material, shall have and may enforce his lien to the same extent and in the same manner that the contractor may under conditions that arise as provided for in Section four (4) of this Act, and shall have and may exercise the same rights as are therein provided for the contractor. (As amended by Act approved June 16, 1913, in force July 1, 1913.)

Section 22. Where Partners Taken in After Contract—Lien for Material Furnished to Sub-Contractor—Lien of Sub-Contractor—Statement of Sub-Contractor to Owner or Contractor—Penalty for Failure to Give Statement.) Whenever, after a contract has been made, the contractor shall associate one or more persons as partners or joint contractors, in carrying out the same, or any part thereof, the lien for materials or labor furnished by a sub-contractor to such contractor and his partners or associates, as originally agreed upon, shall continue the same as if the sub-contract had been made with all of said partners. When the contractor shall sub-let his contract, or a specified portion thereof, to a sub-contractor, the party furnishing material to or performing labor for such sub-contractor shall have a lien therefor and may enforce his lien in the same manner as is herein provided for the enforcement of liens by sub-contractors. Any sub-contractor shall, as often as requested in writing by the owner or contractor, or the agent of either, make out and give to such owner, contractor or agent, a statement of the persons furnishing material and labor, giving their names and how much, if anything, is due or to become due to each of them, and which statement shall be made under oath if required. If any sub-contractor shall fail to furnish such statement within five (5) days after such demand, he shall forfeit to such owner or contractor the sum of fifty (\$50) dollars for every offense, which may be recovered in an action of debt before a justice of the peace, and shall have no right of action against either owner or contractor until he shall furnish such statement, and the lien of such sub-contractor shall be subject to the liens of all other creditors.

Section 23. Lien Against Fund Due or to Become Due—Contractors for Public Improvements, Notice—Duty and Liability of Officer Notified.) Any person who shall furnish material, apparatus, fixtures, machinery or labor to any contractor having a contract for public improvement for any county, township, school district, city or municipality in this State, shall have a lien on the money, bonds or warrants due or to become due such contractor under such contract: Provided such person shall, before payment or delivery thereof is made to such contrac-

tor, notify the official or officials of the county, township, school district, city or municipality whose duty it is to pay such contractor of his claim by a written notice; and, provided further, that such lien shall attach only to that portion of such money, bonds or warrants against which no voucher or other evidence of indebtedness has been issued and delivered to the contractor by or on behalf of the county, township, school district, city or municipality, as the case may be, at the time of such notice. It shall be the duty of any such official so notified to withhold a sufficient amount to pay such claim until the same is admitted by the contractor, or adjusted by the agreement of the parties, or there has been an adjudication of the same in a court of competent jurisdiction, and thereupon to pay the amount so determined to be due such claimant, if any, and to that end the said county, township, school district, city or municipality, or any of the other parties interested may institute suit in the same manner as is provided herein in case of privately owned real estate to determine the rights of the parties when such claim is filed.

Any person who shall furnish material, apparatus, fixtures, machinery or labor to any contractor having a contract for public improvement for the State, may have a lien on the money, bonds or warrants due or about to become due such contractor under the contract, by filing with the official whose duty it is to pay such contractor a sworn statement of the claim showing with particularity the several items and the amount claimed to be due on each; but the lien shall attach to only that portion of the money, bonds or warrants against which no voucher or other evidence of indebtedness has been issued and delivered to the contractor by or on behalf of the State.

The person so claiming a lien shall, within thirty (30) days after filing notice with the State official, commence proceedings by bill in equity for an accounting, making the contractor to whom such material, apparatus, fixtures, machinery or labor was furnished, party defendant, and shall, within the same period notify the official of the State of the commencement of such suit by delivering to him a certified copy of the bill filed: provided, that suit shall be commenced and a copy of the bill served upon the State official not less than fifteen (15) days before the date when the appropriation from which such money is to be paid, will lapse. It shall be the duty of the State official after the sworn statement has been filed with him, to withhold payment of a sum sufficient to pay the amount of such claim, for the period limited for the filing of suit, unless otherwise notified by the person claiming the lien.

Upon the expiration of this period the money, bonds or warrants so withheld shall be released for payment to the contractor unless the person claiming the lien shall have instituted proceedings and served the official of the State with the certified copy of the bill as herein provided, in which case, the amount claimed shall be withheld until the final adjudication of the suit is had: Provided, the State official may pay over to the clerk of the court in which such suit is pending, a sum sufficient to pay the amount claimed to abide the result of such suit and be distributed by the clerk according to the decree rendered.

Any payment so made to such claimant or to the clerk of the court shall be a credit on the contract price to be paid to such contractor. Any officer violating the duty hereby imposed upon him shall be liable on his official bond to the claimant serving such notice for the damages resulting from such violation, which may be recovered in an action at law in any court of competent jurisdiction. There shall be no preference between the persons serving such notice, but all shall be paid pro rata in proportion to the amount due under their respective contracts. (As amended by Act approved June 28, 1919.)

RUDOLPH S. BLOME

WILLIAM J. SINEK

ESTABLISHED 1866

BLOME SINEK Co.

A CO-PARTNERSHIP

Building Construction

CHICAGO

CITY HALL SQUARE BUILDING

NEW YORK, NATIONAL CITY BUILDING

Section 24. Notice to the Owner by Sub-Contractor—Limitation for Service of—May be Served on Owner, Agent, Architect or Superintendent in Charge—Duties and Liabilities of Agents, Architect and Superintendent Notified—Excuse of Notice—Sub-Contractors Protected to Amount Named in—Form of.) Sub-contractors, or party furnishing labor or materials, may at any time after making his contract with the contractor, and shall within sixty (60) days after the completion thereof; or, if extra or additional work or material is delivered thereafter, within sixty (60) days after the date of completion of such extra or additional work or final delivery of such extra or additional material, cause a written notice of his claim and the amount due or to become due thereunder, to be personally served on the owner or his agent or architect, or the superintendent having charge of the building or improvement: Provided, such notice shall not be necessary, when the sworn statement of the contractor or sub-contractor provided for herein shall serve to give the owner notice of the amount due and to whom due, but where such statement is incorrect as to the amount, the sub-contractor or material man named shall be protected to the extent of the amount named herein as due or to become due to him.

The form of such notice may be as follows: To (name of owner): You are hereby notified that I have been employed by (name of contractor) to (state here what was the contract or what was done, or to be done, or what the claim is for) under his contract with you, on your property at (here given substantial description of the property) and that there was due to me, or is to become due (as the case may be) therefor, the sum of dollars.

Dated at this day of A. D.

Signature

Section 25. Notice to Non-Resident Owner by Filing Claim with Circuit Court, What Claim Shall Consist of—When Itemized Account Not Necessary.) In all cases where the owner, agent, architect or superintendent cannot, upon reasonable diligence, be found in the county in which said improvement is made, or shall not reside therein, the sub-contractor or person furnishing materials, fixtures, apparatus, machinery, labor or services may give notice by filing in the office of the clerk of the Circuit Court against the person making the contract and the owner a claim for lien verified by the affidavit of himself, agent or employee, which shall consist of a brief statement of his contract or demand, and the balance due after allowing all credits, and a sufficient correct description of the lot, lots or tract of land to identify the same. An itemized account shall not be necessary.

Section 26. Lien of Laborers Preferred—Limitation as to Laborer's Notice.) The claim of any person for wages as a laborer under Sections fifteen, twenty-one and twenty-two of this Act shall be a preferred lien.

Section 27. Owner's Duty to Retain and Pay Money After Notice—Preference to Laborers—Manner in Which He Shall Make Payment—Liability of Owners.) When the owner or his agent is notified as provided in this Act, he shall retain from any money due or to become due the contractor, an amount sufficient to pay all demands that are or will become due such sub-contractor, tradesman, materialmen, mechanic or workmen of which claim he is notified, and shall pay over the same to the parties entitled thereto.

Such payments shall be as follows:

First—All claims for wages shall be paid in full.

Second—The claims of tradesmen, materialmen and sub-contractors, who are entitled to liens, pro rata, in proportion to the amount due them respectively. All payments made as directed shall, as between such owner and contractor, be considered the same as if paid to such contractor. Any

payment made by the owner to the contractor after such notice, without retaining sufficient money to pay such claims, shall be considered illegal and made in violation of the rights of the laborers and sub-contractors, and the rights of such laborers and sub-contractors to a lien shall not be affected thereby, but the owner shall not be held liable to any laborer and sub-contractor or other person whose name is omitted from the statement provided for in Sections five (5) and twenty-two (22) of this Act, nor for any larger amount than the sum therein named as due such person (provided such omission is not made with the knowledge or collusion of the owner), unless previous thereto or to his payment to his contractor, he shall be notified, as herein provided, by such person of their claim and the true amount thereof.

Third—The balance, if any, to the contractor.

Section 28. Suits to Enforce Lien by Sub-Contractors—When Can be Brought, Pleadings, Action at Law Against Owner and Contractor—Proceedings, Extent of Owner's Liability.) If any money due to the laborers or sub-contractor be not paid within ten (10) days after his notice is served, as provided in Sections five (5), twenty-four (24), twenty-five (25) and twenty-seven (27), then such person may either file his petition and enforce his lien as hereinbefore provided for the contractor in Sections nine (9) to twenty (20), inclusive, of this Act, except as to the time within which suit shall be brought, or he may sue the owner and contractor jointly for the amount due him in any court having jurisdiction of the amount claimed to be due, and a personal judgment may be rendered therein, as in other cases. In such actions at law, as in suits to enforce the lien, the owner shall be liable to the plaintiff for no more than the pro rata share that such person would be entitled to with other sub-contractors out of the funds due to the contractor from the owner under the contract between them, except as hereinbefore provided for laborers, and such action at law shall be maintained against the owner only in case the plaintiff establishes his right to the lien. All suits and actions by sub-contractors shall be against both contractor and owner jointly, and no decree or judgment shall be rendered therein until both are duly brought before the court by process of publication, and in all courts, including actions before a justice of the peace and police magistrate, such process may be served and publication made as to all persons except the owners, as in suits in chancery. All such judgments, where the lien is established, shall be against both jointly, but shall be enforced against the owner only to the extent that he is liable under his contract as by this Act provided, and shall recite the date from which the lien thereof attached according to the provisions of Sections one (1) to twenty (20) of this Act, but this shall not preclude a judgment against the contractor personally, where the lien is defeated.

Section 29. Judgment Before Justice of the Peace—When Transcript of May be Filed—Execution Thereon—Liens Thereof.) If the execution issued on a judgment obtained before a justice of the peace or police magistrate shall be returned not satisfied, a transcript of such judgment may be taken to the Circuit Court and spread upon the records thereof, and execution issued thereon as in other cases except that the lien of the same shall be preserved as a preferred lien on the property improved from the date recited in the judgment, and enforced thereon the same as if a decree had been rendered by the Circuit Court in a suit to enforce such lien under the provisions of this Act.

Section 30. Proceedings for General Settlement—Interpleader—How Liens and Claims Cut Off and Judgments Thereon Stayed in Such Proceedings.) If there are several liens under Sections twenty-one (21) and twenty-two (22) upon the same prem-



Henry E. Legler Regional Branch, Chicago Public Library, Alfred S. Alschuler, Architect, Chicago, Ill.



D. C. Murray Building, Streator, Ill., Geo. C. Nimmons & Co., Architect, Chicago, Ill.

Geo. V. Dahl, President

Fred Winter, Vice-Pres.

E. W. Stedman, Secy. & Treas.

DAHL-STEDMAN CO. BUILDERS

Telephone Randolph 219
Randolph 3277

Lumber Exchange Building, Chicago

ises, and the owner or any person having such a lien shall fear that there is not a sufficient amount coming to the contractor to pay all such liens, such owner or any one or more persons having such lien may file his or their bill or petition in the Circuit Court of the proper county, stating such fact and such other facts as may be sufficient to a full understanding of the rights of the parties. The contractor and all persons having liens upon or who are interested in the premises, so far as the same are known to or can be ascertained by the claimant or petitioner upon diligent inquiry, shall be made parties. Upon the hearing the court shall find the amount coming from the owner to the contractor, and the amount due to each of the persons having liens, and in case the amount found to be coming to the contractor shall be insufficient to discharge all the liens in full, the amount so found in favor of the contractor shall be divided between the persons entitled to such liens pro rata after the payments of all claims for wages in proportion to the amount so found to be due them respectively. If the amount so found to be coming to the contractor shall be sufficient to pay the liens in full, the same shall be so ordered. The premises may be sold as in other cases under this Act. The parties to such suit shall prosecute the same under the requirements as are directed in Section eleven (11) of this Act, and all persons who shall be duly notified of such proceedings and who shall fail to prove their claims, whether the same be in judgment against the owner or not, shall forever lose the benefit of and be precluded from their liens and all claims against the owner. Upon the filing of such bill or petition the court may, on the motion of any person interested, and shall, upon final decree, stay further proceedings upon any suit against the owner on account of such liens, and costs in such cases shall be adjusted as provided for in Section seventeen (17).

Section 31. Failure to Complete Contract by Contractor—Requisites and Manner of Sub-Contractor's Suit in Case of—Owner's Liability in Case of.) Should the contractor, for any cause, fail to complete his contract, any person entitled to a lien as aforesaid may file his petition in any court of record against the owner and contractor, setting forth the nature of his claim, the amount due, as near as may be, and the names of the parties employed on such house or other improvements subject to liens; and a notice of such suit shall be served on the persons therein named, and such as shall appear shall have their claim adjudicated. The premises may be sold as in other cases under this Act. The parties to such suit shall prosecute the same under like requirements as are directed in Section eleven (11) of this Act.

Section 32. Payment of Owner to Contractor—When Wrongful.) No payments to the contractor or to his order of any money or other considerations due or to become due to the contractor shall be regarded as rightfully made, as against the sub-contractor, laborer or party furnishing labor or materials, if made by the owner without exercising and enforcing the rights and powers conferred upon him in Sections five (5) and twenty-two (22) of this Act.

Section 33. Limitation as to Suit of Sub-Contractors to Enforce Lien.) Petition shall be filed or suit commenced to enforce the lien created by Sections twenty-one (21) and twenty-two (22) of this Act within four months after the time of the final payment is due the sub-contractor, laborer or party furnishing material.

Section 34. General Provisions—Suit to be Commenced or Answer Filed by Lien Claimants, and Within Thirty (30) Days on Demand of Owner, Lienor or Interested Party.) Upon written demand of the owner, lienor or any person interested in the real estate, or their agent or attorney, served on the person claiming the lien, or his agent or attorney, requiring suit to be commenced to

enforce the lien, or answer to be filed in a pending suit, suit shall be commenced, or answer filed within thirty days thereafter, or the lien shall be commenced or answer filed within thirty days thereafter, or the lien forfeited, and same released if a claim for a lien has been filed with the clerk of the Circuit Court.

Section 35. Neglect to Satisfy Lien Paid or to Release Where Not Sued on Time—Penalty.) Whenever a claim for lien has been filed with the clerk of the Circuit Court, either by the contractor or sub-contractor, and is afterward paid with cost of filing same, or where there is a failure to institute suit to enforce the same after demand, as provided in the preceding section, within the time by this Act limited, the person filing the same or someone by him duly authorized in writing so to do shall acknowledge satisfaction or release thereof, in the proper book in such office, in writing on written demand of the owner, and on neglect to do so for ten days after such written demand, he shall forfeit to the owner the sum of twenty-five (25) dollars, which may be recovered in an action of debt before a justice of the peace.

Section 36. Penalty for Wrongful Sale, Use or Removal of Materials.) Any owner, contractor, sub-contractor or other person who shall purchase material on credit and represent at the time of purchase that the same are to be used in a designated building or buildings, or other improvement, and shall thereafter sell, use or cause to be used, the said materials in the construction of, or remove the same to any building or improvement other than that designated or dispose of the same for any purpose, without the written consent of the person of whom the materials were purchased, with intent to defraud such person, shall be deemed guilty of a misdemeanor and, on conviction, shall be punished by a fine not exceeding five hundred dollars (\$500), or confined in the county jail not exceeding one year, or both so fined and imprisoned.


Section 37. Liens Against Boats, Barges and Water Craft.) Any architect, contractor, sub-contractor, materialman or other person furnishing services, labor or material for the purpose of or in constructing, building, altering, repairing or ornamenting a boat, barge or other water craft, shall have a lien on such boat, barge or other water craft for the value of such services, labor or material in the same manner as in this Act provided for services, labor or material furnished by such parties for the purpose of building, altering, repairing or ornamenting a house or other building. And such lien may be established and enforced in the same manner as liens are established and enforced under this Act, and the parties shall be held to the same obligations, duties and liabilities as in case of a contract for building, altering, repairing or ornamenting a house or other building.

Section 38. Circuit Court Clerk's Duties with Regard to Claims Filed—Abstract Fee.) When claims for liens are filed pursuant to the provisions of Sections seven (7) and twenty-five (25), the clerk of the Circuit Court shall endorse thereon the date of filing, and make an abstract thereof, in a book kept for that purpose and properly indexed, containing the name of the person filing the lien, the amount of the lien, the date of filing, the name of the person against whom the lien is filed, and a description of the property charged with the lien, for which the person filing the lien shall pay one dollar (\$1.00) to the Clerk.

Section 39. This Act is and shall be liberally construed as a remedial Act.

Section 40. An Act entitled, "An Act to revise the law in relation to mechanic's liens," approved and in force June 26, 1895, and all other Acts and parts of Acts inconsistent with this Act are hereby repealed: Provided, that this section shall not be construed as to affect any rights existing or actions pending at the time this Act shall take effect.

Hurd's Rev. St. 1916, p. 1655, chap. 82, sec. 15.



CURTIS DESIGNS

Curtis Woodwork is now available in four different architectural expressions. With Curtis designs you can carry out in correct detail any of your plans for Colonial, English, Southern or Western houses, without taking your time for detailing the woodwork.

We have developed Curtis designs in cooperation with Trowbridge and Ackerman, of New York. A sufficiently large number of Curtis designs and sizes are standardized to enable you to carry out your own and your client's ideas in economical standardized woodwork.

Your knowledge and use of Curtis Woodwork will broaden your field and will make your needed service available to larger numbers of the country's average home builders.

For more about Curtis Woodwork, please write on your business stationery.

CURTIS DOOR & SASH COMPANY

1414 So. Western Ave. CHICAGO Telephone Canal 4900

1866
CURTIS
WOODWORK

"The Permanent Furniture for Your Home"

INDEX TO BUILDING ORDINANCE

Copyrighted—1920 by H. L. Palmer

See Pages 143-279 for Special Ordinances, and Special Rulings See Pages 251-277

A

Access to room, Class VI:	
Requirements	455
Accident: Elevator (lift) accidents; duty of owner to report.....	666 (c)
Acetylene Gas: Building requirement and location, Class I.....	247 (d)
(See also Fire Prevention and Public Safety Ordinance.)	
Air Requirement. (See ventilation.)	
Aisles—	
Class IVa	296-7
Class IVb	313
Class IVc	333, 336
Class IVd	356
Class V	381, 402
Class VII	475
Class VIII	490
(See also Fire Prevention and Public Safety Ordinance.)	
Alcove Room: Definition and requirement	433, 462
Alley or Yard, rear of: Class VI structures; requirement	428
Alteration—	
Conformity with governing law.....	499-501
Construing provisions of building law relating to alteration.....	501 (a)
Notice to Commissioner of use for which building is intended.....	501 (c)
Notice to owner, etc., to comply with law	501 (b)
Retroactive provisions to control, when	501 (a) (b)
Room in existing tenement: Provision for certain floor and window area	462-3
School (Class VIII): Requirement.....	482 (f)
Wall: Increasing thickness of—requirement	508
Amusement Building Structures: Compliance with law before operation....	698
Amusement Park—	
Buildings within: Requirement.....	361
Frame buildings—space between.....	362
Included in Class IVd.....	353
Moving picture theater to comply with Class IVc	361 (c)
Roller coasters—all requirements.....	359-364
Apartment Building or House—	
Definition	419 (b)
(But see "Tenement and Apart. House.")	
Included in Class VI.	
Arbitration—	
Appeal for arbitration.....	207 (a) (b)
Appeal from decision of arbitrators.....	207 (c)
Deposit to cover cost of proceedings.....	207 (c)
Form of decision.....	207 (c)
Oath of arbitrators.....	208
Power to examine witnesses.....	208
Arches: Segmental and flat; requirement in F. P. construction.....	624-5
Architect: Certification of plans.....	232, 239, 604
(See also "Structural Engineer.")	
Area—	
Class III: Habitable room	276
Class IVb: Vent or flue pipes over stage	322
Class IVc: Vent or flue pipes over stage	347
Class VI: Courts.....	429
Class VI: Percentage of lot allowed to be covered.....	427
Class VI: Room requirements.....	462-4
Class VII: Floor (maximum).....	470
Towers, domes and spires—limitation.....	576
Asbestos chimney lining.....	566
Ash chute in wall, construction.....	571
Ashtar facing, when considered part of wall	522
Assembly Hall—	
Included in Class IV.	
Definition	302
Asylum: Included in Class IId and Class III.	

Athletic Park—

Included in Class IVd.
Included in Class IVi.

Attic—

Class VI, height and cubic feet or air space—use for sleeping room..... 463
Dry cleaning structure, not allowed in 247 (h) || Habitable room..... | 276 (b), 432, 463 |

Automatic Sprinkler System.

(See "Sprinkler System.")

Automobiles: Buildings for housing and storage 247 (e) (f) | Repair shop: Restriction as to distance from church. (See Ordinance, March 10, 1920, Council Journal.) Bakeries— Included in Class II. Ventilation requirement 258 (d) | Balcony (as part of ladder fire escape)— General specifications 657 || Hospital specifications | 270 | **Balcony (over street):** Permit for erection prerequisite 231 (d) | Balcony (theater, etc.)— Class IVb: Designation—exit and entrance 311-12 || Class IVc: Number allowed..... | 335 | | Class V: Designation | 380 | **Barn:** Included in Class I and Class III. **Baseball Park:** Included in Class IVd. Basement— (See also "Cellar.") Class VII: Structural requirement—salesroom allowed 469 || Concrete floor requirement..... | 444, 585 ½ | | Definition, Class VI..... | 419 (h) | | Definition, general | 584 | | Definition as applied to three-story and basement high tenement..... | 441 (b) | | Dry cleaning structure, not allowed in | 247 (h) | | English basement | 419 (h) | | Floor (concrete) requirement..... | 444, 585 ½ | | Frame building: Requirement where basement or story is placed beneath | 644 | | Garage: Prohibited in—exception..... | 247 (e) | | Habitable room in cellar prohibited—exception | 436 | | In a moved house (brick or frame)—height and walls—living rooms..... | 464 (b) | | Living rooms—when permitted in Class VI | 464 | | Nuisance—when declared | 465, 696 | | Prohibited in garage structures—exception | 247 (e) | | Salesroom permitted (sub-basement)..... | 469 | | School—when used for class room (Class VIII) | 495 | | Sub-basement and cellar: Structural requirement and limitation..... | 585 | | Tenement: Masonry or concrete walls; concrete floor—damp-proofing | 444 | | Two and three-story building: Thickness of basement wall..... | 506 (d) (e) | Bath Room— Class III: Requirement 278 || Class VI: Requirement..... | 435 | Bay Window— Construction, Class III..... 279 || Construction, general | 588 | | Wall material, Class VI..... | 445 | Beams— Metal: Allowable stress 528 || Reinforced concrete design..... | 535 | | T-Beams: Limit of flange width.... | 537 | Beams, Girders and Trusses: Covering in F. P. construction..... 618 | Beams (Spandrel), Girders and Lintels: Covering in F. P. construction..... 617 | **Bearing:** Rivets and pins..... 528 (a) | **Belt Course:** (See "Cornice.") **Bending:** Allowance 528 (a) | Billboards, Signboards and Signs: General provisions governing..... 670-685 || Alteration or repair: Requirement.... | 677 | 145

Bond (penal) requirement.....	681	Classes built in conjunction with Class V: Connecting door requirement...	373
Duty of Commissioner of Buildings.....	680	Complaints and inspections—record to be kept	213
Erection and maintenance: Requirement	676	Conflict between special and general provisions—Special provisions to govern—Exception	243
Face: Size limitation and material within fire limits.....	671-2	Construction, alteration and repair (including sheds), and inspection. Fees	234-5
Fire Limits: Erection within.....	671-2	Construction in relation to height: Class I	246
Fire Limits: Erection without.....	671	Construction or wrecking in violation of law—Power of Commissioner of Buildings	204-5-6
Flat against surface of building: Requirement	670	Contractors for Buildings—Registration	706
Frontage consent	682	Damage or depreciation: Percentage to govern matter of repair or rebuilding (Class VI)	459
Height above ground of existing structures	679	Distance between buildings on same lot—Provision for one-story structures in rear.....	426
Height allowed outside fire limits....	674	Drains connecting with sewer, etc.: No plans to be approved unless, etc.	715
Height allowed within fire limits.....	672	Eeroachment (foundation or structure) on public highway—notice to Dep't Buildings (accompanied by plans), 231d. (See also ordinance, April 27, 1914, page 4753, Council Journal.)	
Illuminated and other Roof Signs: Governing provisions ...685 (a) to (f)		Enforcement of law: Duty of Police.	210
Inspection of Signs and Billboards.....	680-1	Entry and closure: Power given to certain officials....229, 285-6, 367-8, 498	
Material to be used.....	671-4	Erection under special Council order: Permit fees fixed.....231 (f), (g), (h)	
Owners' name on structure.....	680	Exposition purposes: Seats, boxes, booths, etc., allowed (Class IVb)....	306
Penalty for unlawful construction or maintenance	682	Fees for permits for construction and repair (including sheds), and inspection	234-5
Plan requirements	676-7, 680	Foundry, machine shop or factory using pneumatic hammers, etc.: Building or use prohibited within 260 feet of residence	710
Prohibited maintenance of existing structures when in violation of law.	679	Frame: Basement placed beneath: Requirement	644
Real estate signboards: Requirement.	673	Chimney requirements	645
Roof: Not to be placed upon or above Similar structures: Provisions of this Article (XXIII) to apply.....	675	Construction within fire limits: Regulation	640
Tearing down: Power of Commissioner of Buildings.....	680	Fire wall—Requirement for more than one on same lot.....	646
Wind pressure: Construction requirement	678	Flats, conversion into: Requirement as to interior walls (within fire limits)	641
Block: Definition of word in connection with frontage consents.....	686, 711	Height limitation outside fire limits	640 (b)
Boarding Stable. (See "Stables and Barns" and Frontage Consents.)		Lot: Area limitation of building or buildings	646
Boiler (Steam): Dry cleaning establishment. Location	247 (h)	More than one on same lot: Requirement	646
Garage: Boiler room regulations.....	247 (e)	Moving: Requirement	690
Permit (general regulations).....	573	Raising or changing one-story to two-story: Requirement	643
Bond (Penal): Billboard, Signboard, etc., construction, etc.	681	Raising: Requirement	642
Building operations—protection of city against damage, etc.....	234 (a)	Repair within fire limits: Regulation	639
Department of Buildings: Commissioner	200 (c)	Roof: Change of gable or hip to flat roof: Requirement.....	642
Subordinates	227	Uniform height (where raised): Requirement	643
Illuminated Roof Sign.	685 (c)	Veneer of Brick: Limitation....640 (c)	
Street obstruction	600	Where prohibited: Exception—Requirement	640 (a)
Wreckers	236 (b)	Front and rear of lot (Class VI): Restrictions as to building.....	426
Bonding: (See "Brickwork" under "Brick.")		Garage: Regulating location.....	732
Brick: Brickwork. Requirements	524	Icemaking house or cooling plant: Frontage consents	705
Building used for automobile housing: Requirement	247 (f)	Manufacturing purposes: Class VII: Requirement	469
Class III: Wall on wood sill.....	280	Permit: Temporary withholding.....	711
Laying: Manner prescribed. Bricks—Soft: Limitation as to use.....	523	Plans. (See "Plans.")	
Veneer for frame building.....	640 (c)	Projection of any part into street prohibited unless by permit.....	231 (d)
Brick Buildings: Requirements as to moving	502	Rear of lot: Provision for one-story structures	426
Building— Alterations on stamped plans prohibited—Exception	233	Residential districts: Appointment of zoning commission in connection with Residential districts: Business of a store permit for erection requirement	694
Amusement structures to comply with law before being allowed to operate	698		
Annual inspection: Several duties of Commissioner of Buildings, owners, etc.	238		
Building operation at night in residential districts, prohibited.....	705		
Building, Unclassified: Class to be determined by Com'r of Buildings.....	241 (r)		
Certificates and notices: Commissioner to keep record—open to inspection	211		
Class: Two or more: Used for any particular class: Requirement.....	242		
Class IVb: Existing building used for Class IVb and other purposes: Restriction	305		
Class IVb: Seats not fixed: Computed space for each person.....	307		
Class IVc hereafter constructed: Requirement	332		
Class V now in existence: Construction	371-2		

Residential districts: Building operations at night prohibited.....	705	Ceiling: Erection of structures over—	
Residential districts: Foundry, machine shop or factory using pneumatic hammers, etc., prohibited within 200 feet.....	710	Class IVb: Requirement.....	320
Residential districts: Temporary withholding of permits.....	711	Class IVc: Requirement.....	344
Seats in Class IVb where not fixed: Computed space for each person...	307	Class V: Requirement (hereafter erected).....	408
Space requirements between building and lot line.....	276 (b)	Class VI: Requirement.....	443
Stoppage of unlawful construction or wrecking.....	206	Cellar—	
Store: Building designed for use as: Requirement as to permit.....	694	Definition.....	419 (i)
Unclassified Building: Requirement of structure subject to determination by Commissioner of Buildings, etc.....	241 (r)	Habitable rooms prohibited in: Exception.....	436
Unsafe building or structure: Notice to owner—Sign on structure—Power to tear down or cause evacuation.....	203, 204, 205, 206	Nuisance—when.....	465, 696
Water used in connection with building operation: Fees.....	234 (b)	Cellar and Sub-basement—	
Workmen: Provision for toilet facilities.....	707	Limitation—structural requirement...	585
Wreckers and wrecking. (See "Wrecking.")		Cement—	
Zoning: (See "Residential District" above.)		Basement floor requirement.....	444, 585½
Zoning Commission: Appointment ..	711	Mortar affected by frost—prohibited use	516
Building or other structure or obstruction (including fence, porch, steps or gallery) prohibited in street.....	703	Portland only to be used in reinforced concrete construction—test.....	542
Buildings, Department of—		Cement: (See also "Concrete.")	
Establishment of department, the various officials, bond requirements, etc.....	199-222	Certificates and Notices: Record of issuance—open to inspection.....	211
Bonds:		Certification of Plans, by either licensed architect or structural engineer.....	232
Commissioner.....	200	Chimney—	
Subordinates.....	227	Class VI: Requirement (including flue)	447
Building Inspector in charge and assistants.....	218-19	Class VI: Boiler chimney as distinguished from domestic flue.....	562
Certificates—issuance, etc.....	211	Encroachment upon street or alley prohibited (external location).....	568
Clerical assistants.....	226	Flue: Insulating lining—Requirement.....	564
Commissioner: Appointment—Duties, Powers and Responsibilities, 200, 201-206, 209-211, 220, 240, 241 (r) and	698	Flue: Requirement (Class VI).....	447
Deputy Commissioner.....	200, 214	Flue: Walls forming—Requirement.....	570
Elevator Inspector in charge and assistants.....	211-212	Frame structure: Structural requirement.....	645
Engineer in charge, assistants and engineering staff.....	215, 217	Heating apparatus in tenement and apartment house not considered as flues used for domestic purposes...	562
Fees—annual report.....	212	Height above roof: What determines.....	563
Fire escape inspector in charge and assistants.....	223-4	Interior: Requirement.....	567
Inspections and Complaints record...	213	Isolated: Requirement.....	569
Plans:		Metal in fireproof building.....	560
Examination and approval.....	213	Metal: Insulating material.....	566
Certification.....	232	Metal, in Ordinary, Slow-burning or Mill construction.....	565
Police to assist, when, etc.....	210	New: Connected with steam plant—permit requirements. (See Section 2355, Code of 1911.)	
Records, inspection open to city officials.....	211	Reinforced concrete.....	560-1
Secretary of Department.....	225	Repair: Permit required. (See Section 2357, Code of 1911.)	
Buildings erected under special provision from Council: Permit fees fixed.....	231 (f), (g), (h)	Stack (metal): Insulating material..	566
Bulkhead—		Note: (See also Fire Prevention and Pub. Safety Ordinance.)	
Class VI: Roof—Requirement.....	448	Church—	
Bunting and Draperies: Limitation as to uses.....	306	Included in Class IV.	
Buttress—		Church:	
In connection with enclosing wall—requirement.....	506-j-k-l	Aisle requirement.....	296
In connection with wall of altered structure.....	508	Construction requirement.....	292
C		Doors, corridors, hallways and passageways: Requirement.....	297
Caisson Foundation. (See "Foundation.")		Doors to open outward.....	299
Canopy (or Marquise)—		Emergency exit.....	299
Erection: Requirement.....	231 (d)	Exit and entrance.....	294
Erection: Special requirement.....	586	Exposure (street frontage) requirement.....	290-1
(See ordinance, July 28, 1913, p. 1788, as to compensation for privileges.)		Floor level and limitation.....	293
Capacity: Allowance for church where seats are not fixed.....	300	Gallery: Exit and entrance.....	295
Capacity (number of persons) allowed for each room in theaters: Commissioner of Buildings to determine, etc.....	324, 348, 392, 414	Lighting service requirement.....	301
Catchbasin—Class VI: Requirement..	458b-c	Live load allowance.....	294
		Seats: Number in a row.....	298
		Seats not fixed: Capacity.....	300
		Stable or barn: Distance regulation.....	601 (c)
		Stairway requirement.....	294
		Chute: Ash and Rubbish: Wall forming — Requirement.....	571
		Cinder Concrete. (See "Concrete.")	
		Classes of Buildings: Not to be changed unless, etc.....	500-501
		Classification (in general).....	241
		When in doubt, to be determined by Commissioner of Buildings.....	241 (r)
		Classification of Buildings—	
		Class I: Embraces structures designed for merchandise (other than department stores); barns, stables and garages or for housing automobiles with a ground area of 500 or more square feet.....	244-254
		Class II (Subdivisions IIa, IIb, IIc): Embraces structures designed for office and club house (sleeping accommodations for less than twenty persons	

(IIa); hotel, club, lodging or rooming house (sleeping accommodations for 20 or more persons (IIb); hospital (sleeping accommodations for more than 10 persons), "Home," day nursery or asylum (housing more than 10 bed-ridden or decrepit persons), jail, house of correction or detention (IIc).....	255-270
Class III: Embraces structures designed for private residence, hospital (sleeping accommodations for ten or less persons), home, day nursery or asylum (accommodating twenty or less persons or not more than ten bed-ridden or decrepit persons), and barn, stable or garage with ground area of less than five hundred square feet.....	271-281
Class IV (Subdivisions IVa, IVb, IVc, IVd): Embraces structures designed for church (IVa); hall (parish, lodge, dance, banquet, assembly, exposition and exhibition, instruction [other than public school]), skating rink; also existing hall used for theatrical purposes at time of passage of this law, except those included in IVa, IVc, IVd and V (IVb); moving picture and vaudeville shows (seating capacity not to exceed three hundred—existing buildings to comply with Class IVc) (IVc); grandstand and baseball, athletic and amusement park (IVd).....	282-364
Class V: Embraces theater buildings of the first class.....	365-416
Class VI: Embraces structures designed for tenements and apartments.....	417-465
Class VII: Embraces structures designed for so-called department stores.....	466-479
Class VIII: Embraces structures designed for school purposes.....	480-498
Class IX: Embraces building required by city for police station purposes.....	498 (a) to 498 (k)
Clay Tile: Wiring on columns.....	612
Cleaning Windows: Safety device required.....	589
Closing a Building for a Cause: Class IV.....	286
Class V.....	368
Class VIII.....	498
Clubhouse: Included in Class II.	
Coal, etc., Shed. (See "Shed.")	
Column— Bracing also covering Trusses, Walls, etc., in steel skeleton construction.....	555
(Consult Department of Buildings as to special ruling in connection therewith.)	
Cast iron: Length limit.....	528 (g)
Cast iron: Limitation as to use.....	528 (h)
Clay tile, wiring on.....	612
Dead and live load requirement (with tables).....	505
Fireproof construction: Requirements.....	610-12
Maximum allowable stress.....	528 (c-d-e)
Reinforced concrete construction: Requirement.....	538
Skeleton Steel Construction: Requirements.....	555
Steel: Filled with or encased in concrete—Allowable stress.....	528 (d)
Steel: Filled but not encased in concrete—Allowable stress.....	528 (e)
Steel (structural): Filled with concrete—Allowable stress.....	539
Terra Cotta Hollow Tile: Requirement.....	553 (c-d)
Commissioner of Buildings and Assistants. (See "Buildings, Department of.")	
Claims: Record to be kept.....	213
Compression: Metals.....	528 (a), 531
Concrete— Approved cement and ingredients (fireproof construction).....	613-14
Basement Floor: Requirements.....	441, 585 1/2
Cinder concrete—composition.....	554
Cinder concrete used in conjunction with mill construction.....	636 (b)
Filling in steel columns: Stress allowed.....	525 (d), 528 (e), 539
Fireproof concrete construction.....	550-552
Hollow block wall: When allowed (Classes III and VI).....	506 (q)
Not to be mixed on street. (See Section 2472, Code 1911.)	
Piling for foundations: Test piles and tests.....	518
Reinforced construction. (See "Reinforced Concrete Construction.")	
Sand and stone used in: Quality demanded.....	544, 614 (b-c)
Steel rails or beams embedded in concrete: Requirement.....	519
Note— See also "Reinforced Concrete Construction."	
Conductor Pipes. (See "Pipes from Roof.")	
Conduit: Embedment in connection with Fireproof construction.....	615 (b)
Conflict of Sections Relating to Classes: Class VI to govern in respect to tenements.....	420
Construction: Contrary to approved plans: Avoidance of permit.....	210
To comply with all provisions of Building laws.....	499
Types of: (See "Fireproof," "Mill," and "Slow-burning" construction.)	
Violation of law: Authority to tear down or stop.....	204 6
Contractors: Mason contractors: Licensing, etc.....	706
Cooling Plant. (See "Ice House" and "Ice Making House.")	
Corner Lot Defined.	424
Cornice: Requirement as to material, etc., on buildings over 50 feet high.....	575
Cornice, Belt Course, Water Table: Allowable projection.....	231 (d)
Corridor: Definition.....	419 (f)
Corridors and Passageways: Width: Computation: Class IVc.....	337
Class V.....	382, 403
Court, Light and Vent Shafts: Definition.....	419 (d)
Class III: Requirement.....	276 (b)
Class VI: Requirement.....	429, 443, 454
Class VI: Requirement (as to drainage).....	454
Class IX: Requirement.....	511 (f)
General construction requirements.....	587-8
Court Room (City Courts): Class IX Exits: Requirement.....	511 (j)
Coves. (See "Hospitals.")	
Crushed Stone, Sand and Gravel: Regulating sale. (See Ordinance, Oct. 19, 1914, page 1832, Council Journal.)	
Cupola (Foundry): Construction requirements.....	574
Curtain— Sliding curtains in schools (Class VIII): Requirement.....	493
Class IVb: Requirement.....	319
Curtain: Asbestos, Iron or Steel— Class IVc: Requirement.....	342
Class V: Requirement.....	386, 405
Curtain Wall. (See "Wall.")	
D	
Damage by Fire: Proportion of to govern rebuilding or repair (Class VI).....	459
Dangerous or Unsafe Building: Duty of Commissioner on complaint of citizen—Removal by Fire Department.....	202, 205
Day Nursery: Included in Class IIc and Class III. (See also "Homes.") (See also Ordinance, Dec. 28, 1917, Council Journal.)	
Definition: Alcove room.....	433
Apartment (by itself).....	419 (b)
Balcony or gallery (Class IVb).....	311
Basement.....	419 (h), 584
(See also 441 (b).)	
Block, as used in this (XVI) Chapter in connection with frontage consents.....	686
Block: Definition in connection with temporary zoning in residence districts.....	711
Cellar.....	419 (i)

Of Class I.....	244	Connecting doors built in conjunction with Class V: Requirement.....	373
Of Class II.....	255	Court and light shaft: Construction requirement.....	587
Of Class IIa.....	259	Dividing wall: Character and construction.....	559
Of Class IIb.....	261	Elevator (lift): Equipment and locking device.....	664
Of Class IIc.....	265	Elevator hatch door or closer: Construction and other requirements.....	665
Of Class III.....	271	Incombustible: Requirement.....	558, 559
Of Class IV.....	282	Iron: Requirement.....	558 (b)
Of Class IVa.....	289	Metal or metal-clad: Requirement, Class I.....	247 (e-f)
Of Class IVb.....	302	Requirement, Class V.....	385 (c-d) 404 (c)
Of Class IVc.....	330	Requirement, Class VII.....	478
Of Class IVd.....	353	Requirement (In the several classes).....	558 (a)
Of Class V.....	365	Opening outward: Class IVa.....	299 (b)
Of Class VI.....	417	Class IVb.....	317
Of Class VII.....	466	Class IVc.....	340
Of Class VIII.....	480	Class V.....	385 (c-h) 404 (c-h)
Of Class IX (Article XIa).....	511 (a)	Class VIII.....	489
Corner lot.....	424	Class IX.....	511 (k)
Court (Class VI): "Inner," "Lot Line" and "Outer".....	419 (d)	Revolving: Requirement: Class I.....	248
Fire Limits.....	695	Class VII.....	477
Fireproof Construction.....	605	(See also Fire Prevention and Pub. Safety Ordinance.)	
Fireproof material.....	606	Stage wall openings: Self-closing fireproof doors.....	343
Habitable room.....	276	Width: Computation: Class IV.....	337
Hall (public).....	419 (f)	Class V.....	382-383, 403
Hall (stair).....	419 (g)	Wired glass: Requirement.....	558
Illuminated Roof Sign.....	685	Doors, Windows and Openings, and use of Metal Frames and Wired Glass: Requirement (not applicable to frame buildings or to certain structures outside fire limits).....	558
Loads (live and dead).....	503	Downspout. (See "Pipe.")	
Masonry (First class).....	521 (b)	Drain Plans: Approved necessary before permit may issue for construction, etc., of building.....	731
Mill construction.....	635	Draperies and Bunting: Limitation as to use.....	306
Ordinary construction.....	638	Dry Cleaning— Boiler location.....	247 (h)
Primary bearing wall (Terra cotta construction).....	553 (e)	Frontage consents.....	699
Reinforced concrete.....	532	Dry Cleaning Structure: Included in Class I.	
Reinforced Terra Cotta Hollow Tile.....	553	Structural requirement.....	247 (h)
Rubble, coursed and ordinary.....	521 (b)	(See also Fire Prevention and Pub. Safety Ordinance.)	
Scenery (Class IVb).....	326	Dumb Waiter— Enclosure in fireproof construction.....	616 (a)
Scenery (Class V).....	415	Enclosure in non-fireproof construction.....	663
Shaft (in connection with tenement building).....	419 (e)	E	
Slow-burning construction.....	632	Eaves— Projection allowed.....	231 (d)
Story.....	419 (j)	Requirement as to buildings over 50 feet high.....	575
Tenement house (new).....	417, 419 (a)	Electric Lighting. (See "Lighting Service Requirement.")	
Wall: Length.....	506 (i)	Electric Service: Cut-out box, etc., not to encroach on F.P. covering.....	623
Wall: Primary bearing.....	553 (e)	Elevator (dumb waiter): Shaft enclosure—Requirement.....	616 (a), 663
Wall: Terms used in construction.....	521	Elevator (grain)— Class I: Fireproof construction requirement.....	254
Yard.....	419 (c)	Tile (terra cotta) cylindrical construction.....	553 (f)
Department of Buildings:		Elevator (lifts)— Enclosure in garage building.....	247 (e)
Employs not to engage in outside employment.....	228	Enclosure of machinery on roof.....	579, 583
Establishment.....	199	General provisions governing construction and enclosing.....	660-9
Officers: Appointment—Bond—Duties—Powers and Limitations.....	199-229	Hospital: Requirement.....	269
Note: Other duties and powers of the several officers will also be found in various sections all through this (XVI) chapter.		Power to stop operation.....	669
Department Store:		Emergency Exits: Provisions governing—Class III.....	281
Basement. (See "Sub-basement" below.)		Class IVa.....	293b, 294, 295, 299
Construction: Type of.....	468	Class IVb.....	316, 325
Courts and light shafts: Requirement.....	473	Class IVc.....	339, 349
Doors: Requirement.....	477-8	Class V.....	385, 398 (d), 404
Exit signs and lights: Requirement.....	476	Class VI.....	449
Floor areas: Limitations.....	470-1	School.....	491
Galleries, mezzanine or intermediate floors: Provisions concerning.....	472	Employees in Department of Buildings not to engage in another business....	228
Loads: Allowance for live.....	479		
Locker provisions.....	469		
Manufacturing purposes: Requirement.....	469 (a)		
Stairs and stairways: Requirements.....	475		
Stories: Designation of first story, etc. (Class VII).....	474		
Sub-basement: Sale of goods allowed—when.....	469		
"Department Store" Building: Included in Class VII.			
Deposits and Fees.	234-5		
(See also "Fees.")			
Derrick. (See "Sidewalk and Street, Etc.")			
Dividing Wall. (See "Wall.")			
Domes. (See "Towers," Etc.)			
Door— Automatic rolling and steel shutter in Classes I, II, IV, V, VII and VIII.....	558 (a)		
Class IVb: Width computation (also applies to corridors, hallways and passageways).....	314		
Class VI: Requirement as to water closet.....	456		
Class VII: Requirement.....	477-8		

Encroachment of foundation, etc., on public highway—Notice to Department of Buildings	231 (d)
Engineering Practice: Application of principles	294 (a), 293 (f), 555 (b), 577
"English" Basement	419
Entry: Power given to certain officials	229, 285, 367
Exits: Revolving doors, where credited as exits	248
Explosives: Building for storage; Class I—Requirement	247 (c)
Exposition Buildings: Temporary seats; boxes, showcases, platforms and booths of combustible material: When allowed (Class IVb)	306
Exposure (street frontage)— Class IVa	299, 291
Class IVb	302
Class IVc	331
Class V	395 (a)
F	
Factory Using Pneumatic Hammers, Etc.: Restrictions as to location	710
Fee:	
Annual accounting of fees paid in by Commissioner of Buildings	212
Annual inspection of a building 235 (c), 238	
Arbitration proceedings (in case of appeal)	207-8
Billboard or signboard erection and inspection	235 (c), 681
Building (alteration or repair)	235 (b)
Building (other than sheds), erection	235 (a)
Canopy: Erection permit	586
Chimney (isolated): Erection	235 (c)
Curtain (asbestos): Inspection	235 (c)
Curtain (iron or steel): Inspection	235 (c)
Elevator (lift): Inspection	235 (c)
Elevator (lift): Installation or alteration	235 (c)
Fire Escape: Erection	235 (c), 654
Floor strength placard	252 (c)
Illuminated and other roof signs (under Sec. 685): Erection and inspection	685 (c)
(See also Sec. 235 (c))	
Placard (floor strength)	252 (c)
Raising permit	235 (b)
Roller coaster permit	363
Shed erection	235 (a)
Street obstruction permit (during building construction)	600
Tank on roof (substructure)	557
Tank or tower on roof: Installation; (in excess of 400-gallon capacity)	235 (c)
Water used in building operation	234 (b)
Wrecking	235 (c), 236
Fence—	
Construction requirements	684
Erection in public street: Approval necessary. (See Sec. 2467, Code 1911.) (See also ordinance prohibiting as an encroachment on street, April 27, 1914, page 4753, Council Journal.)	
Film Storage: Building and vault requirement	274 (i)
(See also Ordinance passed June 28, 1918, page 586, and July 17, 1918, pages 643-4, Council Journal.)	
Fire Alarm System: When required. (See Fire Protection and Pub. Safety Ordinance.)	
Fire Apparatus: Portable. (See Fire Protection and Pub. Safety Ordinance.)	
Fire Escape—	
General provisions governing	653-8
Balcony (on ladder or stairway type): General specifications	656 (b), 657
Change in construction or position prohibited, unless, etc.	658
Class IIc: Requirement	270
Class III: Requirement thereafter erected	281
Class VI: Requirement	453
Class VIII: Requirement	497
Construction allowed in courts and light shafts	587-8
Hospitals: Requirement	270
Inspection of unsafe escapes where complaint is made	202
Inspectors and assistants: Duties	223-4
Prohibited use of building until equipped	651 (m)
Fire Limits	695
Fire Protection Apparatus. (See Fire Protection and Pub. Safety Ordinance.)	
Fire Station Buildings included in Class IX. (See Sec. 498 (d) to (k).)	
Fire Stops: Class IIb (non-fireproof buildings)	263 (c)
Fireproof Construction:	
Definition	605
General provisions	605-631
Arches: Requirement	624-5
Belt, cable wire, conduit, conveyor, dumb-waiter or pipe: Enclosure requirement	616 (a)
Bin (storage), grain elevators and warehouses: Cylindrical construction	553 (f)
Buildings (of other classes) built in conjunction with Class V to be fireproof	396
Casings, doors, windows, etc., surrounding floor openings: Construction requirement	616 (c)
Cement (approved)	613
Cinder concrete	554
Class I: Requirement	246 (a-b)
Class IIa: Requirement	260 (a-b)
Class IIb: Requirement	262 (a-b)
Class IIc: Requirement	266 (b)
Class III: Requirement	273 (a-b)
Class IV: Requirement	288
Class IVa: Requirement	292
Class IVb: Requirement	304 (a-b-c), 305, 306, 308 (b)
Class IVc: Requirement (in part)	330, 332, 334
Class IVd: Requirement (grandstand)	355 (a)
Class IVd: Requirement (Amusement Park)	361 (b)
Class V: Requirement	372-3, 394-6, 610-11
Class VI: Requirement	437, 443
Class VII: Requirement	468
Class VIII: Requirement	482 (c-d)
Class IX: Requirement (Article XIa)	511 (c-b)
Columns: Exterior and interior	610-611
Concrete: Approved cement	613
Concrete: Cinder	554
Concrete ingredients	614
Concrete construction	550-53
Covering for spandrel beams and beams, girders and lintels: Requirement	617-18
Electric service box, etc.: Not to encroach on thickness of fireproofing	623
Enclosure requirement for belt, cable wire, conduit, conveyor, dumb-waiter or pipe	616 (a)
"Equally good" fireproofing material: Tests	558 (j), 607
Explosives: Dividing wall in building for	247 (c)
Film storage: Requirement	247 (i)
(See also ordinances passed June 28 and July 17, 1918, pages 586 and 643, respectively, Council Journal.)	
Floor construction	625
Floor openings: Material in doors, casings, windows, etc.	616
Garage: Dividing wall	247 (e)
Grain elevator	254
Grain elevator: When of cylindrical construction	553 (f)
Gutter or sheet-metal support: Requirement	631
Incombustible material: When so considered	608
Motion picture film storage structure	247 (i)
Mullions: Requirement	619
Partition requirements	627-8
Pipe not to be enclosed in the fireproofing of columns or other structural members: Exception	615

Pipe or conduit: Embedment.....	615 (b)
Pipe or conduit, etc.: Enclosure.....	616 (a)
Reinforced concrete: When acceptable.....	550
Roof construction.....	625
Roof: Rise above wall height.....	630
Shaft enclosing pipe, conduit, dumb waiter, cable wire, conveyor or belt, etc.: Requirement.....	616 (a)
Shaft enclosure: When omitted.....	616 (d)
Skeleton wall: Independent support.....	621
Smoking meats: Requirement.....	247 (g)
Structural members: Covering.....	620
Terra Cotta Hollow Tile Construction: Requirements.....	553
Tests of mode or manner of constructing or installation of "equally good".....	558 (j), 607
Wall facing support.....	622
Walls enclosing steel skeleton structures: Requirement.....	609
Wood floor and nailing strips: Use prescribed.....	626
Fireproof Material—	
Definition.....	606
Tests of "equally good".....	558 (j), 607
Fireworks Storage Building. (See "Storage Structures.")	
Flange: T Beams—limit of width.....	537
"Flat" Building:	
Included in Class VI.....	419 (a)
Frame converted into flats: Requirements.....	641
(See also "Tenement and Apartment House.")	
Flat Slab	535-6
Floor—	
Basement: Concrete requirements.....	444, 600½
Class I: Requirement (intermediate).....	247 (e)
Class I: Requirement (film storage).....	247 (i)
Class III: Requirement.....	275
Class IVa: Requirement.....	294
Class IVb: Requirement.....	309
Class IVd: Requirement.....	354
Class V: Requirement (hereafter erected).....	399-401
Class VI: Requirement (area in altered room).....	463
Class VII: Requirement (areas).....	470-1
Class VII: Requirement (intermediate).....	472
Class IX: Requirement.....	511 (c)
Film storage: Requirement (Class I).....	247 (i)
Fireproof requirement.....	625
Floor system (structural): Use of anchor—joists—splicing.....	506 (m)
Garage: Mezzanine: When considered an additional floor (Class I).....	247 (e)
Intermediate or mezzanine floor: Requirement (including permit and plans), Class VII.....	472
Levels requirement:	
Class IVa.....	293
Class IVb.....	308
Class IVc.....	333
Class V (now in existence).....	374, 377
Class V (hereafter erected).....	397
"Main floor" in Class V: Designation. Mezzanine. (See "Intermediate" above.)	380
Opening in garage structures (Class I).....	247 (e)
Opening protection in F. P. construction.....	616
Strength placard: Requirement—Fee (Class I).....	252
Temporary, in buildings under construction: Provision for.....	591
Wood in fireproof construction: Use—Requirement.....	626
Floor Loads. (See "Loads.")	
Flue. (See "Chimney.")	
Forms used in concrete work: Removal requirement.....	551
Foundation—	
Allowable stress—Bearing on soils.....	512
Bed rock: Foundation to rest upon, in made ground.....	514 (a)
Borings required: When.....	517 (a)
Caisson: Requirement.....	231 (c-d)
Concrete piles allowable: Requirement.....	518
Construction: Material entering into, and mortar.....	515
Encroachment or extension into street, etc.: Permit—Conditions—Removal reservation.....	231
Extension below surface: Requirement.....	514 (a-b)
Footing to rest on hard soil or rock in made ground.....	514 (a)
Frost, and matter of protection against.....	516
Joint foundation, new and old walls: Requirement.....	516
Load limitation on various soils.....	512
Made ground or loam, etc.: Prohibited laying—Exception.....	514 (a)
Pile (wood and concrete): Requirement.....	517-8
Projecting into street, etc.: Subject to removal by city for interference.....	231 (d)
Steel rails or beams in concrete.....	519
Stress allowance for masonry.....	520
Support below ground on city-owned construction prohibited.....	514
Wall, old and new—requirement where there is an increase in thickness.....	516
Wet soil requirement.....	513
Foundry Cupola: Construction—height above roof.....	574
Foundry or Machine Shop: Restrictions as to building within 200 feet of residence.....	710
Frame Building: (See "Building.")	
Frontage: (See "Exposure.")	
Frontage Consent—	
Acid (sulphuric, nitric or hydrochloric) manufacture.....	687
Ammonia manufactory.....	687
Amusement building.....	691
Amusement: Out-door exhibitions, etc.....	357
Amusement Park.....	360
Amusements: Frontage consents and prohibitions. (See Sec. 117, Code 1911.)	
Asphalt manufacture or refining.....	687
Automobile repair shops. (See Ordinance March 10, 1920, p. 2129, Council Journal.)	
Barns and Stables.....	601 (b) 687
Billboard or Signboard.....	682
Billiard and Pool Table Establishment and Bowling Alleys. (See Sec. 169, Code of 1911.)	
Blacksmith Shop.....	687
Block: Definition of word in connection with subject-matter.....	686
(See also Ordinance, July 21, 1919, as amended Sept. 9, 1919, Council Journal.)	
Boarding or livery stable or stable for more than five horses.....	687
Boiler making.....	687
Bones or wood distillation: Place for.....	687
Bowling alleys. (See Sec. 169, Code 1911.)	
Brass or copper works.....	687
Buildings in provisional fire limits.....	695 (m)
Celluloid manufactory.....	687
Cement or plaster-of-Paris manufactory.....	687
Chlorine or bleaching powder manufactory.....	687
Class IVc. buildings.....	352
Class IVd. (Grandstands and amusement parks).....	355, 360
Class IVd. (Temporary seating structure).....	357
Cooling plants.....	709
Copper or brass works.....	687
Day nurseries. (See Sec. 1232, Code 1911.)	
Dextrine (or glucose) manufactory.....	687
Dry cleaning establishment.....	699
Factory (combined with a foundry).....	687
Factory (textile).....	687
Fertilizer manufactory.....	687
Frame building moving.....	690 (a)
Fraudulent frontage petitions. (See Ordinance, April 27, 1914, Council Journal, concerning.)	
Garage (public).....	700
Gas manufactory.....	687

Gas reservoir	687	Undertaking Establishments. (See Sec. 1238, Code 1911.)	
Gasoline storage. (See "Inflammable Liquids" below.)		Varnish or Paint manufactory.....	687
Gelatine or size manufactory.....	687	Wood or Bones, distillation: Place for.....	687
Glucose or dextrine manufactory.....	687	Wood working establishment.....	687
Gum factory.....	687	Wool scouring: Place for.....	687
Hides or skins, storing or scraping.....	687	Yard (in connection with second-hand stores).....	687
Holiday occasions, shows, out-door exhibitions, etc.	357	Frost: Protection of foundation against.....	516
"Homes." (See Sec. 1231, Code 1911, includes also Day Nurseries.)		Furnace and Oven, etc.: Construction, installation and other requirements. (See Fire Prevention and Pub. Safety Ordinance.)	
Horseshoeing shop.....	687	Furring: On brick wall—Requirement.....	507 (c)
Hospital.....	267	Fuse Box—	
(See also Sec. 1219, Code 1911.)		Class IVb: Requirement.....	323
Ice house or cooling plant.....	709	Class V: Requirement.....	389 (d), 409 (d)
Incineration or reduction of garbage, etc., plant.....	687	G	
Inflammable liquids: Storage tanks. (See Ordinance, March 29, 1915, p. 4226, C. J., Sec. 5-a.)		Gable Roof. (See "Roof.")	
Iron or steel works.....	687	Gallery—	
Junk store or yard. (See Sec. 2266, Code 1911.) (See also "Yard" below.)		Class IVb: Designation—exit and entrance.....	311-12
Lamp black manufactory.....	687	Class IVc: Limitation.....	335
Laundry run by machinery.....	687	Class V: Designation.....	380 (b)
Lime kiln.....	687	Class VII: Area and other requirements.....	472
Linoleum manufactory.....	687	Prohibited as an encroachment on street.....	703
Livery, sale or boarding stable.....	687	Garage (500 or more sq. ft. ground area): (Included in Class I.)	
Lumber yard: Establishment of. (See Sec. 336, Fire Prevention and P. S. Ordinance.)		Garage (Less than 500 sq. ft. ground area): (Included in Class III.)	
Meats: Business of selling.....	694	Garage—	
Medical Dispensary.....	687	Automobile storage: Structural requirement.....	247 (e-f)
Metal Refinery.....	687	(See also "Garage" under Fire Prevention and P. S. Ordinance.)	
Monumental works (run by machinery).....	687	Boiler in basement: When permitted.....	247 (e)
Moving frame building.....	690	Buildings erected or altered for garage purposes, Class I: Structural requirement — Equipment — Limitations, etc.....	247 (e-f)
Oil cloth manufactory.....	687	Dividing wall in fireproof construction.....	247 (e)
Oil or Turpentine manufactory.....	687	Fireproof construction or with sprinkler system: Structure must be one or the other.....	247 (e)
Out-door Exhibitions, etc.....	357	Floor openings in non-fireproof building: Requirement.....	247 (e)
Packing House.....	687	Frontage consents.....	700
Paint or Varnish manufactory.....	687	General provisions relating to safety. (See Fire Prevention and Public Safety Ordinance.)	
Planing (or saw) mill.....	687	Living rooms in connection with.....	247 (f)
Plaster-of-Paris or Cement manufactory.....	687	Location as to school, hospital or church. (See ordinance passed June 29, 1917, pages 971-2, Council Journal.)	
Printing ink manufactory.....	687	Metal frame windows.....	247 (e)
Reduction or Incineration of Garbage plant.....	687	Structural requirements.....	247 (e-f)
Reformatory.....	689	Gas Lighting: (See "Lighting Service Requirement.")	
Rendering plant.....	687	Gas Reservoir:	
Rubber manufacture (from crude material).....	687	Frontage consents.....	687
Sale, etc., stable.....	687	Location limited as to school.....	603
Saw or planing mill.....	687	General provisions covering building operations	449-604
Seating structure (temporary.) Class IVd.....	357	(Indexed also according to subject-matter.)	
Second-hand store or yard.....	687	Girder:	
Shavings, sawdust and excelsior storage building.....	692	Plate: Flanges—compression—stress webs.....	531
Shed (shelter) for coal, brick or ice purposes.....	648	Reinforced concrete design.....	535
Sheet metal works.....	687	Slow-burning construction: Requirement.....	633
"Sheltering" Institutions.....	689	Glass: Wired, in Class IIb partitions—area of percentum allowed.....	263 (b)
Shoddy manufacture or wood scouring.....	687	(See also "Window.")	
Shows, out-door exhibitions or special occasions.....	357	Grade of Street adjacent to Tenement House (Class VI): Determining factor.....	419 (i)
Size or gelatine manufactory.....	687	Grain Elevator: (See "Elevator (grain).")	
Slaughter house.....	687	Grandstand: Structural and other requirements.....	555-6
Smelter.....	687	Gravel Roof: (See "Roof.")	
Smoke house curing meats or fish.....	687	Gunpowder and Explosives: Construction of Buildings. (See Fire Prevention and Pub. Safety Ordinance.)	
Soap factory.....	687		
Stable (more than five horses).....	687		
Stable and barn.....	601 (b)		
Stable (boarding, livery or sale).....	687		
Starch factory.....	687		
Steel or iron works.....	687		
Stock yards.....	687		
Stone or monumental works (run by machinery).....	687		
Store (retail).....	688, 693		
Storing or baling junk, scrap paper or rags.....	687		
Tannery.....	687		
Tar distillation or manufactory.....	687		
Tar roofing, Tar paper, or Tarred fabric manufactory.....	687		
Temporary seating structure (Class IVc).....	357		
Textile factory or manufactory.....	687		
Theaters. (See Sec. 117 (as amended), Code 1911.)			
Turpentine or Oil manufactory.....	687		

Gutter—	
Requirement on buildings over 50 feet high	575
Wood support limitation in fireproof construction	631

H

Habitable Room—	
Altered room: Floor requirement—ceiling height (Class VI)	463
Attic room: Requirement	432 (b)
Basement or cellar (Class VI): When permitted	436, 464
Definition: Structural requirement (Classes III and VI)	276
Minimum sizes (including attic): Requirement	432
New tenement (Class VI): Requirement	435-6
Pilasters, etc.: Limitation	433 (c)
Space under roof in fireproof construction: Prohibited uses	630

Hall—	
Assembly hall, Class IVb: Definition	302
Schools (assembly): Requirements	485
Hall or Corridor. Definition (Class VI)	419 (f)

Height—	
Building height determined by width of street (Class VI)	425
Determining factor as to fireproof or non-fireproof construction	246
Fireproof and non-fireproof structure (260 foot for fireproof)	583
Frame building outside fire limits: Restrictions	640 (b)
Limited to 260 feet from sidewalk level (fireproof buildings)	583
Roller coaster device	359
Story height determined by wall thickness	506 (n)
Structural limitations within and without fire limits	577
Towers, domes and spires: Limitation	576
Width of street determining factor (Class VI)	425

Height Limitation—	
Class I	246
Class I: (Increase in existing building)	249
Class IIa	260
Class IIb	262
Class IIc	266
Class III	273
Class IV	288
Class IVb	304
Class VI	425

Hip Roof. (See "Roof.")	
Hoists: Erection, etc., requirements... ..	667
(See also "Elevators.")	

Hoists: Use during building operations	667 (r)
---	---------

"Homes": Included in Class IIc and Class III. (See also Section 1232, Code 1911.)	
(See also ordinances covering subject-matter May 16, 1916, March 12, 1917, April 22, 1918, and June 17, 1918, Council Journals.)	

Horses: Stables and barns—Regulations concerning stabling distance from school, church, hospital, public park or public playground	601 (c)
---	---------

Hospital—	
Included in Class IIc and Class III.	

Note: Beds: Number in hospital determines class, i. e., more than 10, Class IIc, less than that number, Class III. (See also Sections 1215, 1220 and 1229, Code 1911, as amended June 17, 1918.)	
Elevator (lift) requirement	269
Fire escape	270
Frontage consents	267
Garage (public): Not to be built within 200 feet of a hospital	700
Location limited	702
Playground: Distance limitation. (See Sec. 1220, Code 1911.)	
Stables and barns: Distance, limitation	601 (c)
Hotel: Included in Class IIb.	

House of Correction: Included in Class IIc.	
--	--

House Mover, House Raiser or Shorer. (See Sections 2117 to 2126, Code 1911, as amended January 14, 1918, pages 1897-8, Council Journal.)	
---	--

House Moving—	
Brick: Requirements	502
Frame: Permit—frontage consent, etc.	690
Moving or tearing down by Fire Department	205

I

Ice House: Structural requirement for exclusive storage house	649
--	-----

Ice-making House—	
Church, hospital or school	708
(Prohibited within 400 feet of.)	
Frontage consent requirement	709

Ice-making Machinery: Prohibited in theater building	411
---	-----

Illuminated Roof Sign: Definition, construction, etc.	685
---	-----

Imbecile, Infirm or Sick Institution Buildings: Included under Class II. (See also Day Nurseries and "Homes.")	
---	--

Inspection—	
Billboards and signboards (annual inspection)	680 (1)
Building inspectors: Duties	218-220
Buildings: Several duties of Commissioner of Buildings, owners, etc.	238
Curtain: Class V, hereafter erected	405
Elevator (lift) semi-annual	668
Elevator inspectors—duties	222
Fire escape inspectors: Duties	223-4
Fire escapes reported unsafe: Duty to inspect	202
Records to be kept	213
Roller coaster, scenic railway, etc.	363
Stairways and means of egress (in connection with inspection of buildings)	202, 238
Unsafe or dangerous building, stairways, fire escapes, etc., in factory or workshop: Duty of Commissioner of Buildings where complaint is made	202
Insulating Material for Chimneys and Stacks	566

J

Jail: Included in Class IIc.	
-------------------------------------	--

Joist:	
Class IIb, brick fire-stop between	263 (c)
Classes III and VI: Support, requirement	504
Class VIII: Support requirement	506 (c)
General requirement as to Classes I, II, IV, V, VII and VIII	507

L

Lath—	
Metal (in conjunction with skeleton construction)	247 (a)
Partitions in Mill construction: Wood lath prohibited	636
Wallboard or plasterboard used in lieu of lath and plaster—when permitted	590
Wood: Requirement	590
Wood lath prohibited (including studs and furring) in mill construction	636 (a)

Ledges: Joist support — corbeling (Classes I, II, IV, V, VII and VIII)	507
---	-----

License issued in compliance with this Chapter (XVI): Revocation	369
---	-----

Light Shaft: Class III (wholly within walls of two-story building): Requirement	279
--	-----

Lighting Service Requirement—	
Class IVa	301
Class IVb	325
Class IVc	349
Class V	391, 412
Electric service cut-out box not to encroach on fireproof covering	623

Living Apartment in connection with Garage Building	247 (f)
(See also "Habitable Room.")	

Living Room in Basement, when permitted	464
--	-----

Loads (live and dead)—	
Class I	247 (a), 253
Class II	257
Class III	275
Class IVa	294
Class IVb	309

Class IVd	354	Requirement, Class IVa	292 (a)
Class V	375, 397	Requirement, Class IVb	304, 306
Class VII	479	Requirement, Class VII	468
Class VIII	503 (d)	Requirement, Class IX (Art. XIa)	511 (c)
Class IX	511 (d)	Motion Picture Building—	
Designing structural detail for all		Included in Class I.	
buildings (with table)	503-4	Amusement Park: Structure to com-	
Eccentric loading to be provided for.	505 (e)	ply with provisions of Class IVc.	361 (c)
Reinforced concrete construction:		Film storage structure (including	
Test	552	vault): Requirement	247 (i)
Roof construction—allowance in addi-		(See also Ordinance passed June 28,	
tion to weight	503 (e)	1918, pages 585-9, Council Journal,	
Stairways: Requirement as to live.	503 (f)	pertaining to Film Storage.)	
Stress (general provisions)	529	Motor Vehicle Building: Requirement	
Theaters (Class V): Requirements	375	(Class I)	247 (e-f)
Timber piling (maximum)	517 (e)	Moving a building, one location to an-	
Wall, pier and columns: Full live to		other (brick, stone, frame or concrete):	
be taken on in connection with roof.	505	Alteration to conform, etc.	502
Wind resistance in relation to dead		"Moving Picture Building," etc. (See	
load	503 (b)	"Motion Picture Building.")	
Wood follower not to be used in deter-		Mullions: Fireproof Construction: Re-	
mining safe load (pile foundation)		quirement	619
.....	517 (f)	N	
Lodging or Rooming House: Included		Noise of Building Operations at night	
in Class IIc.		(residential district), prohibited	705
Lot—		Nuisance: Building or structure main-	
Alley or yard in rear (Class VI): Re-		tained in violation of law	406, 696
quirement	428	(See also Ordinance, April 23, 1914,	
Building to be entirely within limits:		pages 4753-4, Council Journal.)	
Exception as to foundation	231 (d)	O	
Class VI: Building requirements	429 (f-g-h)	Obstruction: Street, Alley, etc.: Build-	
Class VI: Distance between buildings		ing, fence, porch, steps, etc., prohibited.	
on same lot—Provisions for one-		(See Ordinance, April 27, 1914, pages	
story structures in rear	426	4753-4.)	
Class VI: Percentage of area allowed		Office Building: Included in Class IIa.	
to be covered	427	Old People's Homes: Included in	
Corner defined	424	Classes IIc and III.	
Definition of "Lot line court" and re-		"Ordinary" Construction—	
quirement	419 (d), 429 (c-e)	Definition	638
Frame building: Distance from line—		Requirement, Class IIa	260 (c)
Dimensions	646	Requirement, Class IIb	263 (a)
Front and rear occupation with build-		Requirement, Class IIc	266 (a)
ings (Class VI): Restrictions	426	Requirement, Class III	273 (c)
Lot line and residence building: Space		Requirement, Class IVa	292
between	276 (b)	Requirement, Class IVb	306
Plat of portion to be occupied by		Requirement, Class IVc	332
building: Submission to Commis-		Requirement, Class VII	468
sioner of Buildings	423	Requirement, Class VIII	482 (b)
Rear of tenement: Provision for one-		Requirement, Class IX	511 (c), 511 (c-b)
story structures	426	Oven and Furnace: Construction, etc.	
Lot Line: Space between residence		(See Fire Prevention and Pub. Safety	
building and lot line: Requirement.	276 (b)	Ordinance.)	
Lumber: Storage (yard). See Section		Overturning Moment, Due to Wind	
36 (new) of Fire Prevention and Pub.		Pressure: Not to exceed, etc.	503
Safety Ordinance.		P	
M		Pantry: Requirement (Class III)	278
Machine Shop or Foundry: Restriction		Parapet Wall: (See "Wall.")	
as to building within 200 feet of resi-		Park or Playground (public): Stable or	
dence	710	barn—Distance regulation	691 (c)
Magnesia Block Insulation (chimneys).	566	Partition—	
Main Floor. (See "Floor.")		Class I: (Film storage building) ..	247 (i)
Marquise. (See "Canopy.")		Class I: (Occupied by more than one	
Mason Contractors: Licensing, etc.	704	business)	250 (b)
Masonry—		Class IIb:	263 (a-b)
Allowable stresses on plain concrete		Class III: Requirement	276 (c)
and stone	520	Class IVb: (Dressing room)	329
Definition of "First Class"	521 (b)	Class IVc: (Dressing room)	351
Merchandise, Sale, Storage or Manufac-		Class V: (Dressing room)	384, 413
tory Structure: Included in Class I.		Eight-inch construction: Height limit	
Metal or Metal-clad Door. (See "Door.")		506 (d)
Metal Frames, etc., and Fire-Resisting		Film storage structure: Require-	
Glass: Claims of superior con-		ment	247 (i)
struction and installation: Laboratory		Fireproof construction	627-8
test expense authority to use	558 (j)	Habitable room: Ventilation require-	
Metal Lath. (See "Lath.")		ment	433 (d)
Metal Structural Roof Members: Omi-		Mill construction: Requirement	636
sion of fireproofing—when allowed ..	632	Slow-burning construction: Require-	
Metals: Tension, compression, bending,		ment	633
shear and bearing: Maximum allow-		Smoke pipe passing through: Require-	
able stresses (with table)	528	ment	572
"Mill" Construction—		Terra cotta, in fireproof construction:	
Definition: Requirement	635	Requirement	616 (b)
Fireproofing (partitions in mill con-		Theater dressing room: Composition	
struction)	636	(Class V)	413
Requirement, Class I	246 (b)	(See also "Wall," under "Dividing.")	
Requirement, Class IIa	260 (b)	Party Wall. (See "Wall.")	
Requirement, Class IIb	263	Penalty—	
Requirement, Class IIc	266 (a)	Billboards, etc.: Violation of govern-	
Requirement, Class III	273 (b)	ing provisions	683
Requirement, Class IV	288	Building ordinance violation (general).	697

Illuminated roof signs: Violation of provisions governing.....	685 (f)
Neglect of safety provisions for workmen	591 (g)
Permit—	
Application for by owner or agent.....	231 (a)
Billboard and signboard construction or alteration	676-7, 680
Boiler (steam)	573
Business of store in restricted district	694
Canopy	586
Change or alteration in tenement (Class VI)	421
Drain plan approval necessary prior to building, etc., construction.....	711
Elevator (lift) construction.....	660
Fees for building permits.....	235
Fire escape erection.....	654
Foundation encroachment into streets, etc.	231 (e)
Frame building: Moving.....	690
Frame building: Raising.....	642
Issuance: Duty of Commissioner of Buildings	211
Mezzanine or intermediate floor (Class VII)	472 (e)
Moving frame building.....	690
Partition in room in existing building: Requirement	276 (c)
(Class III.)	
Raising frame building.....	642
Revocation and Re-issue.....	237
Roof: Change gable or hip to flat... ..	642
Shows, outdoor exhibitions, holiday occasions, etc.	357
Sidewalk and street obstruction (building construction)—Revocation	600
Store (business of) in restricted district	694
Void if not used within six months after issuance	230
Wrecking	235 (c), 236
Picker or Shredder Rooms: Structural requirements. (See Fire Prevention and Pub. Safety Ordinance.)	
Picture Machine Booth: Class IVc—Requirement	345
Picture Machine Booth: Schools—When allowed	494
Piers—	
Dead and live load requirement (with tables)	505
In connection with enclosing wall: Requirement	506 (j)
Isolated: Height prescribed unless, etc.—Weight computation	520 (f-g)
Pilaster—	
Enclosing wall: Requirement	506 (j)
Habitable room: Requirement.....	433 (c)
File Foundation. (See "Foundation.")	
Pipe—	
Downspouts (water conductors): Buildings over 50 feet high—Requirement	575
Embedment in connection with fireproof construction	615 (b)
Fireproof construction: Not to be enclosed—Exception	615
Pipes and Other Conveyors Passing from Floor to Floor: Enclosure requirements	
	616 (a)
Placards Indicating Floor Strength. (See "Floor.")	
Plan—	
Adequate drains to be provided for before issue of permit for building construction	711
Alteration on stamped plan not permitted without permission: Exception	233
Approval by officials other than Commissioner of Buildings.....	231 (b-c)
Billboards, signboards, etc.: Construction and repair.....	676-7, 680
Canopy	586
Certification by architect or structural engineer	232, 239, 604
Class III: Partition plan to be filed, etc., prior to construction.....	276 (c)
Conformity with building law requisite: Architect's certificate.....	232, 239
Deviation: How dealt with.....	240
Deviation from stamped plan: Requirement	
	233
Elevator (lift) construction: Requirement	
	660 (b)
Essentials (scale to which drawn, distances and dimensions, lot lines, location of plumbing and certain signatures)	
	232
Examination: Approval—Filing	
	213, 231 (a-b-c-d), 232
Filing and return.....	
	231 (a)
Foundation encroachment into street, etc., to be shown.....	
	231 (d)
Illuminated roof sign.....	
	685 (c)
Mezzanine or intermediate floor: Requirement (including permit and plans), Class VII	
	472 (e)
On the job: To be kept.....	
	231 (e)
Pile foundation: Requirement.....	
	517 (g)
Plumbing to be shown.....	
	232
Reinforced concrete: Submission of plan—Detail—Test	
	532
Retention by Commissioner after six months not obligatory.....	
	231 (a)
Signing by licensed architect or licensed structural engineer required.	
	232
Structural engineer: Signature and seal	
	232
Tenement and apartment house: Change or alteration. Requirement	
	421
Plasterboard. (See "Lath.")	
Plastering: Requirement	
	590
Plate Girders: Provisions governing..	
	531
Plumbing—	
Location to be shown on plan.....	
	232
Tenement house: Requirement.....	
	456-458
(See also Act, Approved June 10, 1897, and Sections 1775 to 1906, Code 1911.)	
Police—	
Assist Commissioner of Buildings when called upon.....	
	210
Station buildings: Provisions governing (under Class IX)	
	511 (a) to 511 k)
Porch—	
Construction inside fire limits.....	
	556
Prohibited as an encroachment on street. (See Ordinance, April 27, 1914, page 4753, Council Journal.)	
Structural requirements as to existing and new buildings.....	
	446
Portico Construction Inside Fire Limits.	
	556
Portland Cement: Prescribed use in reinforced concrete construction.....	
	542
Post (wood): Slow-burning construction: Requirement	
	633
Private Residence: Included in Class III.	
Private Stable. (See "Stables and Barns.")	
Projection of Cornice, Belt Courses over Street. (See "Cornice.")	
Projection of Foundation into Streets, Etc. (See "Foundation.")	
Provisions (general)	
(Indexed according to subject-matter.)	
Provisions, General and Special: Conflict between—What governs.....	
	243
Public Hall: Definition	
	419 (f)
Public Highway or Ground: Prohibited erection upon	
	231 (d)
R	
Railing on Fence in Public Street: Approval necessary. (See Section 2467, Code 1911. See also Ordinance, April 27, 1914, page 4753, Council Journal.)	
Red Light: Use during building operations	
	599
(See also Section 2464, Code 1911.)	
Reinforced Concrete Construction:	
Definition	
	532
Cement finish: Calculation.....	
	549
Columns: Requirement	
	538-9
Concrete placed in freezing and in warm weather: Requirement.....	
	547-8
Curtain wall, skeleton construction: Requirement	
	540
Design for beams, girders and slabs..	
	535
Drenching with water.....	
	548
Fireproof construction: Requirement	
	550
Flat slab construction.....	
	534, 535

(Consult Department of Buildings on its ruling on these sections.)	
Form filling around reinforcing steel: Requirement	546
Forms: Removal	551
Hollow tile construction in connection with reinforced concrete construction: Definition and provisions	553 (a)
Load test: Requirement	552
Mixing concrete: Requirement	545
Moments of external forces: Calculations	556
(Consult the Department of Buildings in reference to its ruling on this section.)	
Portland cement only to be used: Test	542
Ratio of moduli of elasticity: Adhesion—Bond	533
Sand: Quality requirement	543
Slab construction: Calculation as to ribs, etc.	537
(Consult Department of Buildings in reference to its ruling on this section.)	
Steel used in: Bending and elongation requirements	541
Stone requirement	544
Stress (unit) for steel-and-concrete	534
(Consult the Department of Buildings as to its ruling on this section.)	
Stress in connection with reinforced concrete construction	553 (a)
Reinforced Hollow Tile. (See "Reinforced Concrete Construction." See also "Terra Cotta Hollow Tile Construction.")	
Removal of Buildings:	
Brick, stone or frame (including tenements)	502
Fire Department to remove or tear down: When	205
Residence (private): Included in Class III.	
Residential Districts—	
Building operations at night prohibited	705
Foundry, machine shop or factory using pneumatic hammers, etc., prohibited	710
Permits for buildings: Temporary withholding. (See Ordinance, July 21, 1919, as amended Sept. 9, 1919, page 279.)	
Zoning Commission: Appointment	712
Revocation of Building or Wrecking Permit, for Cause	237
Revolving Door: (See "Door.")	
Riveting: Tension	530
Roller Coaster Device: Height restriction	359
Roller Coaster, Scenic Railway, etc.: Certificate of test, etc.	363
Roof—	
Bulkhead, Class VI: Requirement	448
Composition: Requirement	581
Construction requirement	580
Enclosures upon roof	579
Fireproof requirement	625
Frame building: Changing gable or hip to flat	642
Full live load to be taken on wall, pier and column	505
Gable or hip: Changing to flat roof (frame buildings): Requirement	642
Gravel: Requirement	581
Housing (elevators, tanks, skylights, scuttles, etc.)	583 (d)
Load requirement in addition to its own weight	503 (a)
Over sidewalk during building construction	594
Pitch	580
Shingle, gravel or composition: Requirement	581
Space under roof in fireproof construction: Prohibited uses	630
Spectatorial purposes. (See "Use" below.)	
Structures upon (skylights, water tank and elevator machinery enclosures): Requirement	579, 583
Tank: Permit fee	557
Use: When considered as story of building (Class IVd)	358
Water from roof—how carried to ground	575
Room: Habitable. (See "Habitable Room.")	
"Rubble," defined	521 (b)
Rulings of Department of Buildings on Mooted Points (See end of Ordinance)	
Runways or Viaducts for Live Stock: Provisions concerning wood structure	577
S	
Safety of Building or Part Thereof: Commissioner's decision final	209
Safety Devices:	
Elevator (lift)	664, 666
Floor (temporary during building operations)	591
Roller coaster	363
Scaffold	591
Window cleaners	589
Sale Stables. (See "Stables and Barns.")	
Sand—	
Fireproof construction: Quality demanded	614 (b)
Reinforced concrete construction: Quality demanded	543
Sand, Gravel and Crushed Stone: Regulating sale. (See Ordinance, Oct. 19, 1914, page 1832, Council Journal.)	
Scaffold or Temporary Floor: Requirement	591
Scenery—	
Class IVb: Definition—Fireproofing—Amount allowed	326-8
Class IVc: Stationary, etc.	350
Class V: Framing	406
Class V: Definition	415
Class VIII: Restrictions	493
Scenery: Miscellaneous Provisions Pertaining to. (See Fire Prevention and Pub. Safety Ordinance.)	
Schools—	
Garage (public) in relation to proximity to a school. (See Ordinance, June 29, 1917, page 971, Council Journal.)	
Gas reservoir in relation to proximity to school	603
General provisions governing construction, etc.	480-498
Lighting (gas and electric) provision	492
Moving picture machines: Provision governing	494
Portable buildings of frame: Restrictions	484
Power of officials to close for violation of building provisions	498
Scenery and curtains: Provisions governing	493
School building: Included in Class VIII.	
Stables or barns in relation to proximity to a school	601 (c)
Scuttles: Structure Above Roof.	583 (d)
Seats—	
Measurements:	
Class IVa	298
Class IVb	315
Class IVc	338
Class V	378, 399
Not fixed: Space computation:	
Class IVa	300
Class IVb	307
Number in row and measurement:	
Class IVa	298
Class IVb	315
Class IVc	338
Class V	378, 399
Schools: Provisions	485
Temporary seating accommodations for outdoor occasions	357
Shaft—	
Definition	419 (c)
Enclosure may be omitted in F. P. construction	616 (d)
Shear—	
Hollow tile (stress)	553 (a)
Rivets and pins, steel shapes, plate girders, webs and brackets	528 (a)

Shed—
Automobile: Requirement247 (f)
Brick, cement, coal, salt and stone shed
(open shelter) and sheds for icing
cars: Requirement 648
Garage of brick or frame: Require-
ment247 (f)
Near navigable water or railroad
tracks for storage..... 648
Open shelter: Requirement..... 647
Prohibited for dwelling purposes or as
an addition647 (d)
Sheet-metal Work: Support of in fire-
proof construction 631
Shelter Shed. (See "Shed.")
Shingle Roof. (See "Roof.")
Shorer. (See "House Mover, etc.")
Shows and Outdoor Entertainments:
Temporary seating structures: Re-
quirement 357
Sick, Infirm or Imbecile Persons:
Buildings for. (Included in Class II.)
Sidewalk: Roof over during building
operations: Requirement 594
(See also "Streets.")
Sidewalk and Street: Occupation during
building construction592-600
(See also "Streets.")
Sign—
"Dangerous building": Requirement
as to posting 203
Illuminated roof signs: Definition and
general requirements 685
Sign. (See also "Billboards and Sign-
boards.")
Signal Lights: Requirement as to street
obstructions 599
(See also Section 2464, Code 1911.)
Sill— Class III: Level allowed..... 280
Door and window: Structural require-
ment (except in Classes III and VI). 582
Sink: Class VI: Requirement..... 457
Skating Rink: Included in Class IVb.
Level above grade.....308 (c)
Skeleton Construction:
Term as applied and requirements... 555
(Consult Department of Buildings in
reference to ruling as to bracing.)
Skeleton Steel Construction—
Curtain wall requirement..... 540
Independent support 621
Skeleton Steel Wall. (See "Wall.")
Skewback: Requirement624 (c-d)
Skylights—
Class III: Construction requirement. 274
Class VI: Construction requirement..
..... 431 (a-c)
Class VIII: Construction requirement. 492
General: Construction requirement... 578-9, 583
Slabs: Reinforced concrete design...535-6
Sleeping Porch. (See "Porch.")
Sleeping Stalls in Rooms, when al-
lowed 264
Slow-burning Construction—
Definition and requirements.....632-634
Requirement, Class I246 (b)
Requirement, Class IIa260 (b)
Requirement, Class IIb262 (b), 263 (a)
Requirement, Class IIc266 (a)
Requirement, Class III273 (b)
Requirement, Class IV288
Requirement, Class IVa292 (a)
Requirement, Class IVb304 (a), 306
Requirement, Class VI437, 443
Requirement, Class VII468
Requirement, Class VIII482 (c)
Requirement, Class IX, Art. XIa, (Po-
lice Station)511 (c)
Slow-burning, Fireproof Mill, and Ordinary
Construction: Construction in
relation to height..... 246
Smoke Pipe: Passing through partition:
Requirement 572
Smoking Meats or Fish: Structural re-
quirement for building.....247 (g)
(See also Fire Prevention and Pub.
Safety Ordinance.)
Soils: Foundation loads and other re-
quirements512-14, 516-17
Space allowed between Residence Build-
ing and Lot Line on either side.....276 (b)
Special Council order for permission to
erect buildings: Fees.....231 (f), (g), (h)
Special Provisions: To govern when in
conflict with general provisions..... 243
Special Rulings of the Department of
Buildings on Mooted Points in the
Building Ordinance. (Consult the De-
partment of Buildings.)
Spires. (See "Towers, Domes and
Spires.")
Sprinkler System—
Class I: Requirement251 (b)
Class I: (Garage building).....247 (e)
Class V390, 410
Class VII469
Elevator (lift) hoistways in non-fire-
proof structures: Equipment..... 661
Mill construction building..... 635
Note: (See also Fire Prevention and
Pub. Safety Ordinance.)
Spiral Stairs or Winders. (See "Stairs
and Stairways.")
Stables and Barns—
Five hundred or more sq. ft. (Included
in Class I.)
Less than five hundred sq. ft. (In-
cluded in Class III.)
Regulations: (Including floor con-
struction, frontage consent, distance
from school, church, hospital, pub-
lic park or playground)..... 601
School, church, hospital, public park
or public playground: Distance reg-
ulation601 (c)
Stack. (See "Chimney.")
Stage: Construction, Class V.....387, 406
Stair Hall: Definition.....419 (g)
Stairs and Stairways—
Change in stairway, only by permit.. 658
Class I (garage)247 (e-f)
Class II (hereafter erected)..... 281
Class IV293-4
Class IVb310, 316
Class IVc334
Class V (now in existence)..... 376
Class V (hereafter erected)..... 398
Class VI449, 452
Class VII475
Class VIII486
Class IX (Police Stations).....498 (i)
Garage: Living room connection with
ground247 (e-f)
General provisions covering construc-
tion in ordinary mill, slow-burning
and fireproof building (Classes I,
II and VII).....629, 634, 637, 650-2
Housing on Roof: Stair provision.583 (d)
Inspection requirement 238
Live load requirement.....503 (f)
Location and other requirements. (See
Fire Prevention and Pub. Safety Or-
dinance.)
Schools: Requirements 486
Spiral stairs (and winders): Re-
quirements—Exception .486 (d), 652 (k)
Sub-basement or cellar: Leading to or
from 585
Standpipe and Hose on Stage: Require-
ment, Class IVb and Class IVc..321, 346
Steel—
Bending and elongation: Conforma-
tion to requirements..... 541
Columns: When used in connection
with reinforced concrete work.... 539
"T" Beams: Width of flange in con-
nection with reinforced concrete
work 537
Steel Rails or Beams Used in Founda-
tions. (See "Foundations.")
Steps: Prohibited as encroachment on
street. (See Ordinance, April 27, 1914,
page 4753, Council Journal.)
Stone:
Fireproof construction: Quality dem-
anded614 (c)
Reinforced concrete construction:
Quality demanded 544
Stoppage of Construction When in Viola-
tion of Law 206
Storage Structures—
Requirement for:
Acetylene gas247 (d)

Automobile	247 (d-f)
Film (moving picture)	247 (f)
Fireworks and Explosives	247 (c)
Grain elevator	254
Shavings, sawdust, etc.	692
Sheds (when so used)	648
Store—	
Business of, in restricted district: Permit requirement	694
Erection or remodeling in restricted district: Permit requirement	694
Store front: Structural requirement (Classes III and VI excepted)	582
Store (other than "Department" Store). Included in Class I	
Story: Definition	419 (j)
Street Frontage—	
Tenement and apartment house: "Corner lot" computation in relation to "lesser" frontage	424
(See also "Exposure.")	
Towers, domes and spires: Limitation of space to be occupied of a building front on street	576
Street Frontages: (See "Exposure.")	
Street Obstruction: Building structure, fence, porch, steps, etc., forbidden	703
Street and Sidewalk: Occupation during building construction	592-600
Streets—	
Building or structure, fence or rail- ing, forbidden in streets	703
(See also Section 2467, Code 1911.)	
Occupation during building operations	592-600
Public highway or public ground: structures prohibited — exception	231 (d), 703
(See also Section 2467, Code 1911.)	
Red lantern display	599
(See also Section 2464, Code 1911.)	
Sidewalk and street: Occupation dur- ing building construction	592-600
Signal lights: Requirement	599
(See also Section 2464, Code 1911.)	
Stress—	
Beams, trusses and girders (metal) ..	528
Columns (steel)	528 (d-e), 539
Eccentric loading to be provided for, etc.	528 (f)
Foundations	512
Girders (plate)	531
Grain bin, elevator, warehouse (terra cotta tile)	553 (f)
Hollow tile columns	553 (a)
Live and dead load (general provi- sions)	529
Masonry foundation	520
Metals: Maximum allowable stresses and special requirements	528
Steel-and-concrete (unit)	534
Steel used in reinforced concrete: Bending and elongation require- ments	541
Structural steel columns	539
Terra cotta hollow tile construction: Tile and tile columns	553 (a-c)
Timber	526
Structural Detail—	
Arch construction requirement: Test	504 (e)
Designing requirements	504
Parapet wall	504
Strength test	504
Tests (by owner, on demand, etc.) as to load requirements	504 (e)
Walls (general provisions)	504, 505, 506
Structural Engineer: Signature and seal on plans	232
Structural Limitations Within and With- out Fire Limits	577
Structure Over Ceiling: Construction—	
Class IVb: Requirement	329
Class IVc: Requirement	344
Class V: Requirement (hereafter erected)	408
Class VI: Requirement	443
Struts for Windbracing: Least radius of gyration	528 (g)
Sub-basement. (See "Basement.")	
Survey, and Duty of Bureau of Fire Prevention and Pub. Safety in Rela-	
tion Thereto. (See Fire Prevention and Pub. Safety Ordinance.)	
T	
"T" Beams: Width of flange in connec- tion with reinforced concrete con- struction	537
(Consult Department of Buildings in reference to its ruling on this sec- tion.)	
Tank—	
Inflammable liquid storage. (See Fire Prevention and Public Safety Ordi- nance.)	
Roof: Permit—Fee	557
Tannery: Location limitation	602
Temporary Floor or Scaffold: Require- ment	591
Temporary Seating Structures (Shows and Outdoor Entertainments): Re- quirement	357
Tenement and Apartment House—	
Definition and class	417, 419 (a)
Access to room: Requirement	455
Addition to frame within fire limits prohibited	439
Additional room or hall: Compliance with law	461
Air: Quantity requirement	434
Alcove: Definition—Requirement ..	433
Alley or yard in rear: Requirement ..	428
Apartments to be divided by masonry wall	442
Attic room: Requirement	432 (b)
Basement living rooms: When per- mitted	436, 464
Bath, etc., room: Window area	435
Bay window, court and shaft: Wall material	445
Bulkhead in roof: When required ..	448
Ceiling over stores (new non-fireproof tenement): Requirement	443
Cellar. (See "Basement, etc." above.) Change or alteration: Permit—Plan ..	421
Class VI: Provisions to govern in case of conflict of sections	420
Court and shaft: Enclosing wall sup- port	443
Courts: Inner and outer—Minimum widths—Lot line passages and courts	429
Distance between buildings	426
Drainage of courts and shafts	454
Entrance hall (new tenement): Mason- ry and wall requirement	440-1
Existing building moved: Character of foundation	439
Existing buildings exempt from pro- visions of this Article except, etc.	460
Fire, etc., damage: Rebuilding or re- pair: Concerning	459
Fire escape provisions	453
Fireproof and slow-burning construc- tion (new tenement): Determined by height	437
Flue and chimney requirement	447
Foundation required for moved struc- ture	439
Foundation requirement for story or basement	464 (b)
Foundation walls (new tenement): Material—Dimension—Dampproofing: Requirement	444
Frame: Addition within fire limits prohibited	439
Frame apartment: Incombustible partitions	438
Habitable rooms in basement: Re- quirement as to use	436, 464
Habitableness: Certificate necessary prior to occupation of new tenement ..	422
Height, as determining character of construction	437
Height: How determined by width of street	425
Inspection of new tenement as work progresses: Certificate—violation ..	422 (b-c-d)
Lot area: Percentage of occupation ..	427
Lot frontage: What constitutes	424
Masonry dividing walls	442
Metal lath, etc., requirement in ordi- nary construction	412

Moved from one lot to another: Base- ment or story in new location: Re- quirement	464 (b)
Moving of existing building: Char- acter of foundation.....	439
New tenement: Certificate of habitable- ness	422
Nuisance: When considered.....	465
Occupation of part before completion: Requirement	422 (b)
Pantry room: Window area.....	435
Partitions in frame (outside fire lim- its): Incombustible construction...	438
Plat of lot, etc.: Submission prior to obtaining permit to build, etc.....	423
Plumbing requirements	456-458
Porch: Requirement	446
Room: Alteration must conform to certain floor and window area.....	462-3
Room and hall in tenement hereafter constructed in existing structure: Requirement	461
Rooms: Size—Height—Attic room— Window required in sub-divided room	432
Scuttle in roof: Requirement.....	448
Skylight: Requirement	431 (c)
Stair and stairway requirements.....	431 (a-b), 441, 449-452
Story or basement—foundation re- quirement	464 (b)
Vent shaft: Minimum width and area...	430
Wood supports under moved tenement prohibited	439
Tension of Rivets.	530
Terra Cotta Hollow Tile Construction— Definition	553 (a)
Columns: Requirement	553 (c-d)
Drenching with water.....	553 (b)
Joints: Treatment	553 (b)
Load: Minimum time within which to place after finish of work.....	553 (d)
Partitions in fireproof construction: Plastering	616 (b)
Reinforced concrete construction: Pro- visions applicable when, etc.....	553 (a)
Stresses and values.....	553 (a-f)
Tile: Quality	553 (a)
Use: Minimum of time between finish of work before placing of load there- on	553 (d)
Wall (primary bearing): Definition, height, thickness, etc.....	553 (e)
Workmanship: Special provisions.....	553 (b)
Theater— Above first floor level declared a nu- isance: Exception	701
Built in conjunction with other than Class V, to be fireproof.....	396
Capacity (number of persons) allowed: Commissioner of Buildings to certi- fy, etc.	324, 348, 392, 414
Changing existing Class IV to Class V structure: Requirement.....	416
Class IV, IVb and IVc: Requirements	283-352
Class V: General requirements.....	365-369
Class V: Now in existence.....	370-393
Class V: Hereafter erected.....	394-416
Closing by authorities.....	286, 368
Exposure (street frontage): Require- ment	290-1, 303, 331, 395 (a)
First Class: Included in Class V. Frame building: Prohibited in (note exception in 393).....	287, 332, 393
Hall used for theatrical purposes in existing buildings. (Included in Class IVb.)	
Ice making machinery or ammonia ap- paratus prohibited in building.....	411
License, cause for revocation.....	369
Moving picture structure within amuse- ment park: Compliance with Class IVc restrictions.....	361 (c)
Moving picture and vaudeville (not exceeding 300 seats): Included in Class IVc.	
Prohibited above first floor level. (See Ordinance, July 22, 1912, Council Journal.)	
Prohibited in frame building (except- tion to be found in 393).....	287, 332, 393
Stage constructions, vents, etc. (See Fire Prevention and Pub. Safety Ordinance.)	
Street frontage requirement.. (See "Exposure," above.)	
Timber— Columns: Limitation as to use.....	526
Quality prescribed.....	527
Stress allowance (with table): Maxi- mum length.....	526
Tin-clad Door. (See "Door.")	
Toilet Facilities for Workmen	707
Towers, Domes and Spires: Require- ments	576
Trusses, Columns, Walls, Etc., in Steel Skeleton Construction: Bracing re- quirement	555
Tunnels: Theater construction.....	379
U	
Unclassified Building. (See "Building.")	
Unsafe Building: (See "Building.")	
V	
Vaudeville Theater: Included in Class IV and Class V.	
Vault: Film storage (motion picture): Requirement	247 (i)
Veneer (Brick). (See "Brick.")	
Vent or Flue Over Stage: Require- ment— Class IVb	322
Class IVc	347
Class V	389, 409
Ventilation: Air requirement in tenement room (Class VI)	434
Attic: Class VI.....	463
Class II: Requirement	258, 264
Class III: Requirement	276
Class VI: Requirement.....	434, 463
Class IV, V, VII and VIII (general): Requirement (see also "vent shafts" below)	659
Hotel and restaurant vent systems in connection with ranges. (See Fire Prevention and Pub. Safety Ordina- nce.)	
Room: Altered, etc., Class VI.....	462-3
Sleeping stalls in rooms: Air require- ment per person.....	264
Theater dressing room: Class IVb	329
Class IVc	351
Class V	384, 413
Vent shafts (solely for water closet, bath room or pantry): Class III	278
Class VI (area).....	430, 456
Class VI (wall construction).....	445 (b)
General construction requirement (ex- cept Class III).....	588
Wall forming ventilating duct: Re- quirement	571
Window and floor area of room or attic: Class VI.....	462-3
Window and mechanical ventilation (Class II)	258
Veranda Construction Inside Fire Limits 556	
Vestibule: Class V—For stage door.....	388, 407
Viaducts or Runways for Live Stock: Requirements	577
Violations: Record of complaints.....	213
Volume: In relation to towers, domes and spires	576
W	
Wall— Altered building: Increase in thick- ness—requirement	508
Anchorage	506 (l)
Area division (fireproof construction)	247 (c-e)
Area division (ordinary construction), Class I	251
Ash and rubbish chute: Wall forming —requirement	571
Ashlar facing: When part of masonry wall	522
Basement: Requirement—Class VI...	444
Basement of frame building: Require- ment	644
Bracing during erection.....	510, 555

Bracing in skeleton steel construction: Requirements.....	255	Walls, piers and columns: Provisions relating to (with tables).....	506
Brick on wooden sills—level of sills..	280	Wind pressure:	
Building converted into flats: Division wall requirement.....	641	Class I: Requirement.....	247 (a)
Class I: Requirements.....	247, 251	Designs: Requirement.....	503 (b)
Class II: Requirements.....	263	Isolated wall (fence): Requirement.....	684
Class III: Requirements.....	506 (q)	Requirement as to certain structures.....	577
Class IV: Requirements.....	394, 318, 344	Wallboard and Plasterboard. (See "Lath.")	
Class V: Requirements.....	386, 394, 405	Walls, Piers and Columns: Provisions relating to (with tables).....	506
Class VI: Requirements.....	413-4, 506 (c)	Warehouse: Tile (Hollow) construction.	553 (f)
Class VIII: Requirements.....	506 (c)	Water: Use of during building construction	234
Clay tile or hollow concrete block allowed—when.....	506 (q)	Water Closets and Urinals—	
Concrete (hollow) block, or hollow clay tile (Classes III and VI): When allowed.....	506 (q)	Class III: Requirement.....	278
Corrugated iron: When allowed as enclosing wall.....	247 (b)	Class VI: Requirement.....	435, 456
Court, light shaft and light court: Structural requirement.....	587-8	Closets for workmen during building operations: (Ordinance, passed July 10, 1916, pages 1484-6, Council Journal.)	
Curtain: Skeleton construction—requirement.....	540	Water Table. (See "Cornice.")	
Curtain wall of tile construction (subject to Sec. 533).....	506 (f)	Water Tank Enclosure on Roof. (See "Roof.")	
Dead and live load requirement (with tables).....	505	Wind Pressure or Resistance—	
Definition of "primary bearing" in terra cotta tile construction.....	553 (e)	Class I: Requirement.....	247 (a)
Definition of terms used in construction.....	521	Designs for all buildings to include provisions for.....	503 (b)
Dividing: Character and construction of incombustible doors.....	559	Fence or isolated wall.....	684
Dividing: When required.....	551	Overturning moment not to exceed, etc.	503 (b)
During construction: Height allowed in comparison to other walls of same building.....	510	Requirement as to certain structures.....	577
Enclosing: Basement to sixteenth story—Requirements (with table).....	506	Winders. (See "Stairs and Stairways.")	
Enclosing, built not less than fifty feet from any lot, etc.: Corrugated iron construction.....	247 (b)	Window—	
Enclosing (miscellaneous provisions).....	577	Casement: Requirement.....	558 (g)
Facing support in fireproof construction.....	622	Class I: Metal frame and wired glass requirement.....	247 (i), 250 (c)
Fire wall in buildings occupied by more than one firm, etc.: Class I—Requirement.....	250	Class III: Area in habitable room.....	276 (b)
Fireproof construction: Independent support of skeleton.....	621	Class VI: Area in habitable room.....	435 (a)
Forming smoke flue: Requirement.....	570	Class VI: Area in altered room.....	462
Foundation: Projection into public streets.....	231 (c)	Court and light shaft: Construction requirement.....	587
Frame building where changed into flats: Incombustible construction.....	641	Distance above floor, Class III.....	276 (b)
Garage: Dividing—Openings—Door protection: Class I.....	247 (e)	Garage: Metal framing.....	247 (e)
Increase in thickness in new and old: Requirement as to foundation.....	516	Metal frame: Reinforcement.....	558 (h)
Independent (F. P. Construction): Support requirement.....	621	Metal frames and sash and wired glass: Requirement.....	558 (c)
Interior brick used to support fireproof floor: Requirement.....	506 (r)	Opening: Protection in Classes I, II, IV, V, VII and VIII.....	558 (a)
Isolated (fence): Requirement.....	684	Prism glass in lieu of wired glass.....	558 (i)
Length: Computation and measurement.....	506 (i)	Safety device for cleaners.....	589
New and old: Foundation requirements (general provisions).....	516	Sash (metal): Requirement.....	588 (d-e-f-g)
Parapet: Structural requirement—when dispensed with.....	511	Water closet: Class III.....	278
Party: Application of provisions of Section 508 in certain cases.....	509	Water closet: Class VI.....	435 (a), 456 (b)
"Primary bearing": Definition in connection with terra cotta construction.....	553 (e)	Wired glass (metal framed).....	247 (i), 250 (c), 558
Proscenium, Class V.....	386, 405	Window and Mechanical Ventilation. (See "Ventilation.")	
Skeleton steel: Class I: Requirement.....	247	Wiring. (See "Fire Prevention and Public Safety Ordinance.")	
Skeleton steel: Curtain wall requirement.....	540	Wood Lath. (See "Lath.")	
Skeleton steel: Enclosing wall requirement.....	609	Work—	
Smoke Box Requirement.....	570	Not to begin until, etc.....	240 (c)
Structural detail (including strength test).....	504	Power to stop.....	240 (b)
Structural requirement in conjunction with buttresses, piers or pilasters.....	506 (j)	Workmen: Comfort and safety provisions—	
Terra cotta hollow tile: Requirement.....	554	Elevator (lift) device.....	666
Unfinished and Wall Lathing.....	571	Floor (temporary).....	591
		Scaffolds.....	591
		Toilet facilities during building construction.....	707
		Window cleaners.....	589
		Wrecking—	
		Permit: Fee—Bond.....	236
		Revocation of permit.....	237
		Unsafe building: Authority to direct Fire Department to tear down.....	205
		Violation of law: Notice to owner—Power of Commissioner.....	204-206
		Y	
		Yard—	
		Defined.....	419 (a)
		Rear of tenement: Alley or yard required.....	428
		Z	
		Zoning—	
		Appointment of Commission on.....	712
		Residence districts: Temporary withholding of permits for certain buildings. (See Ordinance passed July 1, 1919, as amended Sept. 9, 1919.)	

BUILDING ORDINANCE

OF THE CITY OF CHICAGO

(Originally passed by the City Council December 5, 1910, and incorporated in the Chicago Code of 1911.)

The Building Ordinances of the City of Chicago were radically revised and passed by the City Council on June 25, 1917. This revision necessitated an entirely new arrangement which has afforded an opportunity of changing the plan of publication, which we believe will prove a great benefit to the users of the Hand Book.

To eliminate obscurity in the meaning of the ordinances, a plan of illustrating the difficult passages by means of illustrative diagrams has been adopted with the approval of the Commissioner of Buildings. All diagrams used, having first been submitted to the commissioner to determine their correctness of interpretation and are published with his sanction.

The illustrative drawings and diagrams with their description and arrangement are copyrighted and the system protected and all rights are reserved in this as well as other cities of the United States.

Comprising Chapter XVI, Sections 199 to 698, inclusive, of The Chicago Code of 1911, with all amendments thereto up to and including August 22, 1921.

Attention is called to the several new ordinances following the building ordinance, having to do, or in connection with the erection or location of buildings, and which are given numbers for convenience in indexing.

Particular attention is directed to numerous rulings of the Department of Buildings on certain disputed sections in the Building Ordinance, and which follows at the end thereof.

(Copyright by H. L. Palmer, 1920.)

CHAPTER XVI.

Buildings.

ARTICLE I.

199. Department of Buildings Established—Officers.) There is hereby established an executive department of the municipal government of the City of Chicago which shall be known as the Department of Buildings and which shall embrace a Commissioner of Buildings, a Deputy Commissioner of Buildings, an Engineer in charge, a Building Inspector in charge, an Elevator Inspector in charge, a Fire Escape Inspector in charge, a Secretary to the Commissioner of Buildings and such number of Assistant Engineers in charge, Assistant Building Inspectors in charge, Building Inspectors, Elevator Inspectors, Fire Escape Inspectors and such other officers, assistants and employees as may be from time to time provided for in the annual appropriation ordinance.

200. Building Commissioner—Appointment—Bond—Other Officers—Offices Created.) (a) There is hereby created the office of Commissioner of Buildings. He shall be the head of said department of buildings and shall be an experienced architect, or a civil, structural or architectural engineer or a building contractor or an efficient building mechanic and shall have been engaged as an architect or a civil, structural or architectural engineer or building contractor or building mechanic for a period of not less than ten years prior to his appointment; and during his term of office as Commissioner of Buildings he shall not be engaged in any other business.

(b) He shall be appointed by the Mayor, by and with the advice and consent of the City Council.

(c) The Commissioner of Buildings before entering upon the duties of his office shall execute a bond to the city in the sum of twenty-five thousand dollars, with such sureties as the City Council shall approve, conditioned for the faithful performance of his duties as the Commissioner of Buildings.

(d) There are hereby created the offices of Deputy Commissioner of Buildings, Engineer in charge, Building Inspector in charge, Elevator Inspector in charge, Fire Escape Inspector in charge, Secretary to the Commissioner of Buildings, Assistant Engineer in charge and of such number of Assistant Building Inspectors in charge, Building Inspectors, Elevator Inspectors and Fire Escape Inspectors as may be from time to time provided for in the annual appropriation ordinance. The incumbents of these offices shall be known and designated by their respective titles as herein set forth.

201. Appointment of Subordinates—Duties of Commissioner—Responsibility of Commissioner—Power to Pass upon Ordinances.)

(a) The Commissioner of Buildings shall have the management and control of all matters and things pertaining to the department of buildings, and shall appoint, and may remove according to law, all subordinate officers and assistants in his department. All subordinate officers, assistants, clerks and employees in said department shall be subject to such rules and regulations as shall be prescribed from time to time by said Commissioner.

(b) The Commissioner of Buildings shall institute such measures and prescribe such rules and regulations for the control and guidance of his subordinate officers and employees as shall secure the careful inspection of all buildings while in process of construction, alteration, repair or removal and the strict enforcement of the several provisions of this chapter.

(c) It shall be the duty of said commissioner and his assistants to enforce all ordinances relating to the erection, construction, alteration, repair, removal or the safety of buildings.

(d) In all cases where any action is taken by the Commissioner of Buildings to enforce the provisions of any of the sections contained in this chapter or to enforce the provisions of any of the building ordinances of the city now or at any time hereafter in force, whether such action is taken in pursuance of the express provisions of such sec-

alone or ordinance or in a case where discretionary power is given by the ordinances of said city to the Commissioner of Buildings, such acts shall be done in the name of and on behalf of the City of Chicago, and the said Commissioner of Buildings in so acting for the city shall not render himself liable personally, and he is hereby relieved from all personal liability, for any damage that may accrue to persons or property as a result of any such act permitted in good faith in the discharge of his duties, and any suit brought against the said Commissioner of Buildings by reason thereof shall be defended by the Department of Law of said city until the final termination of the proceedings therein.

(e) The Commissioner of Buildings shall have full power to pass upon any question arising under the provisions of this chapter, subject to the conditions, modifications and limitations contained therein.

202. Inspection of Buildings or Structures Where Complaint is Made—Duty of Commissioner—Unlawful to Continue Use of Buildings Not in Compliance with Ordinances.) (a) It shall be the duty of the Commissioner of Buildings where any citizen represents that any building or structure or part thereof is in an unsafe or dangerous condition, or that the stairways, corridors, exits or fire escapes in any factory or workshop or other place of employment are insufficient for the escape of employees in case of fire, panic or accident, or the stairways, exits and fire escapes of any building or structure in the city do not comply with the requirements of this chapter, to make an examination of such building or structure, and if such representation is found to be true the said Commissioner shall give notice in writing to the owner, occupant, lessee or person in possession, charge or control of such building or structure to make such changes, alterations or repairs as safety or the ordinances of the city may require. Upon failure of parties so notified to comply with the requirements of said notice the matter shall be placed in the Department of Law of the City of Chicago for prosecution.

(b) It shall be unlawful to continue the use of such building until the changes, alterations or repairs found necessary by the Commissioner of Buildings to make such building or part thereof safe or to bring it into compliance with this Chapter, shall have been made.

203. Buildings Found in Unsafe Condition—Notice to Owner—Authority of Commissioner.) (a) Whenever the Commissioner of Buildings shall find any building, or structure or part thereof in the city in such an unsafe condition as to endanger life, but in such condition that by the immediate application of precautionary measures such danger may be averted, he shall have authority, and it shall be his duty, to forthwith notify, in writing, the owner, agent or person in possession, charge or control of such building or structure or part thereof, to adopt and put into effect such precautionary measures as may be necessary or advisable in order to place such building or structure or part thereof in a safe condition; such notice shall state briefly the nature of the work required to be done and shall specify the time within which the work required to be done shall be completed by the person, firm or corporation notified, which shall be fixed by said Commissioner of Buildings, upon taking into consideration the condition of such building or structure or part thereof, and the danger to life or property which may result from its unsafe condition.

(b) Whenever such Commissioner of Buildings shall be unable to find the owner of such building, structure or part thereof, or any agent or person in possession, charge or control thereof, upon whom such notice

may be served, he shall address, stamp and mail such notice to such person or persons at their last known address, and in addition thereto shall place or cause to be placed the notice herein provided for upon such building at or near its principal entrance, and shall also post or cause to be posted in a conspicuous place at each entrance to such building, in large letters, a notice as follows:

"THIS BUILDING IS IN A DANGEROUS CONDITION AND HAS BEEN CONDEMNED BY THE COMMISSIONER OF BUILDINGS."

(c) It shall be unlawful for any person, firm or corporation to remove said notice or notices without written permission from the Commissioner of Buildings.

(d) If at the expiration of the time specified in such notice for the completion of the work required to be done by the terms of such notice, in order to render the building or structure safe, said notice shall not have been complied with, and said building or structure is in such an unsafe condition as to endanger life or property, it shall be the duty of the Commissioner of Buildings to proceed forthwith to tear down or destroy that part of said building or structure that is in such unsafe condition as to endanger life or property, and in cases where an unsafe building or structure cannot be repaired or rendered safe by the application of precautionary measures, such building or structure, or the dangerous parts thereof, shall be torn down by said Commissioner of Buildings or by his order and the expense of tearing down any part of such building or structure shall be charged to the person owning or in possession, charge or control of such building or structure or part thereof, and the said commissioner shall recover or cause to be recovered from such owner or person in possession, charge or control thereof the cost of doing such work, by legal proceedings prosecuted by the Law Department.

(e) If the owner, agent or person in possession, charge or control of such building or structure, or part thereof, when so notified, shall fail, neglect or refuse to place such building or structure, or part thereof, in a safe condition, and to adopt such precautionary measures as shall have been specified by said commissioner within the time specified in such notice, in such case, at the expiration of such time it shall be unlawful for any person, firm or corporation to occupy or use said building or structure, or any part thereof, until said building or structure or part thereof is placed in a safe condition, and in case where a building or structure, or part thereof, is in a dangerous or unsafe condition and has not been placed in a safe condition within the time specified in the notice of the Commissioner of Buildings, such building or structure, or such part thereof, shall be forthwith vacated, and it shall be unlawful for any person or persons to enter same except for the purpose of making repairs required by the Commissioner of Buildings and the ordinances of the City of Chicago.

204. Building or Part of Building Constructed or Being Constructed in Violation of Chapter—Authority of Commissioner to Tear Down.) (a) Whenever it shall be found that any building or structure, or part thereof, is being, or shall have been constructed or built in violation of any of the provisions of this chapter, the Commissioner of Buildings shall forthwith notify the owner, agent, superintendent or architect of, or the contractor engaged in erecting such building or structure, or part thereof, of the fact that such building or structure, or part thereof, has been, or is being, constructed or erected contrary to the provisions of this chapter and shall

specify briefly in such notice in what manner the provisions of this chapter or any of them, have been violated, and shall require the person so notified to forthwith make such building, structure, or part thereof, conform to and comply with the provisions of this chapter, specifying in such notice the time within which such work shall be done.

(b) If, at the expiration of the time set forth in such notice, the person so notified shall have refused, neglected or failed to comply with the request made in such notice and to have such building or structure, or part thereof, concerning which notice was sent, changed so as to conform to and comply with the provisions of this chapter, the Commissioner of Buildings shall have the authority, and it shall be his duty to proceed forthwith to tear down or cause to be torn down such building or structure, or such part thereof as shall or may have been erected and constructed in violation of the provisions or any of the provisions of this chapter, and the cost of such work shall be charged to and recovered from the owner of such building or structure or from the person for whom such building or structure is being erected, in legal proceedings prosecuted by the Law Department.

205. May Direct Fire Department to Remove.) The Commissioner of Buildings shall have authority to direct the Fire Marshal to tear down any defective or dangerous wall or structure or any building or structure or part thereof which may be constructed in violation of the terms of this chapter, after written notice has been served upon the owner, lessee, occupant, agent or person in possession, charge or control, directing him or them to tear down or remove any defective wall, building or structure, or any part thereof, which is in a dangerous condition, which has been, or is being, constructed or maintained in violation of the terms of this chapter. In case of the destruction or partial destruction of buildings by fire, decay or otherwise, when any department of the city government, pursuant to the ordinances of the city, shall make an outlay of money or incur any liability for the payment of any expense on behalf of the city in an effort to preserve or prevent the destruction of such building or buildings, or structure, or for the preservation of life of its citizens, it shall be the duty of the Commissioner of Buildings to ascertain the amount of such outlay or expenditure and present a bill therefor to the owner or owners of any such building or buildings, or its or their agent or agents, and it shall be the duty of said Commissioner of Buildings to refuse to issue a permit for the construction, re-construction, alteration or repair of any building or buildings or structure by any such owner or owners, lessee, occupant, agent or person in possession, charge or control thereof until such outlay or expenditure shall be repaid to the city by the owner, lessee, occupant, agent or person in possession, charge or control of such building or buildings thus totally or partially destroyed in the manner aforesaid. Said commissioner shall also proceed forthwith to collect the amount of such bill from such owner or owners, by legal proceedings prosecuted by the Law Department.

206. May Stop Construction and Wrecking of Buildings.) (a) Said commissioner shall have power to stop the construction of any building or the making of any alterations or repairs of any building within said city when the same is being done in a reckless or careless manner or in violation of any ordinance, and to order, in writing or by parole, any and all persons in any way or manner whatever engaged in so constructing, altering or repairing any such building, to stop and desist therefrom.

(b) And the said commissioner shall have power to stop the wrecking or tearing down of any building or structure within said city when the same is being done in a reckless or careless manner or in violation of any ordinance or in such a manner as to endanger life or property, and to order any and all persons engaged in said work to stop and desist therefrom. When such work has been stopped by the order of said commissioner, it shall not be resumed until said commissioner shall be satisfied that adequate precautions will be taken for the protection of life and property, and that said work will be prosecuted carefully and in conformity with the ordinances of the city.

207. Arbitration—Appeal from Decision.)

(a) In all cases where discretionary power is given to the Commissioner of Buildings to estimate damage to buildings, as also in questions relating to the security of any building or buildings or structures, or part thereof, and in all other cases where discretionary powers are given by ordinance to the Commissioner of Buildings, any party or parties believing themselves injured or wronged by the decision of the Commissioner of Buildings must, before instituting any suit, make an appeal for arbitration as follows, to-wit:

(b) Any person wishing to make an appeal shall do so within five days after written notice of the decision or order of the Commissioner of Buildings has been given. An appeal made later than five days after the serving of the notice of the Commissioner of Buildings shall not entitle the appellant to any arbitration. The request for arbitration shall be in writing and shall state the object of the proposed arbitration and the name of the person who is to represent the appellant as arbitrator.

(c) The Commissioner of Buildings shall thereupon inform the appellant of the cost of such arbitration and such appellant shall, within twenty-four hours from the receipt of such information, deposit with the Commissioner of Buildings the sum of money requested for defraying the expense of the same, which sum shall be fixed in each case by said commissioner in proportion to the time it will take and the difficulty and importance of the case, but shall in no case be more than the cost of similar service in the course of ordinary business of private individuals or corporations. As soon as such sum of money shall have been deposited with him, the Commissioner of Buildings shall appoint an arbitrator to represent the city and the two arbitrators thus chosen shall, if they cannot agree, select a third arbitrator, and the decision of any two of these arbitrators shall, after investigation and consideration of the matter in question, be final and binding upon the appellant as well as the city unless an appeal is taken therefrom, as provided in case of an appeal under a statutory arbitration, within five days thereafter.

208. Arbitrators to Take Oath—Power to Examine Witnesses.) The arbitrators shall themselves, before entering upon the discharge of their duties, be placed under oath by the City Clerk, to the effect that they are unprejudiced as to the matter in question and that they will faithfully discharge the duties of their position. They shall have the power to call witnesses and place them under oath, and their decision or award shall be rendered in writing, both to the Commissioner of Buildings and to the appellant. The fee deposited by the appellant with the Commissioner of Buildings shall be paid by the Commissioner of Buildings to the arbitrators upon the rendering of their report and shall be in full of all costs incident to the arbitration; but should the decision of said board of arbitration be

rendered against the Commissioner of Buildings, then the money deposited by the applicant must be returned to him and the entire cost of such arbitration shall be paid by the city.

109. In Urgent Cases—Commissioner's Power Final.) Whenever the decision of the Commissioner of Buildings upon the safety of any building or any part thereof is made in a case which is so urgent that failure to properly carry out his orders to demolish or strengthen such building or part thereof may endanger life and limb, the decision and order of the Commissioner of Buildings shall be absolute and final.

210. Duty of Police to Assist Commissioner in Enforcing Provisions of this Chapter.) Whenever it shall be necessary, in the opinion of the Commissioner of Buildings, to call upon the Department of Police for aid or assistance in carrying out or enforcing any of the provisions of this chapter, he shall have the authority so to do, and it shall be the duty of the Department of Police, or of any member of said department, when called upon by said commissioner, to act according to the instructions of, and to perform such duties as may be required by said commissioner in order to enforce or put into effect the provisions of this chapter.

211. Certificates—Notices—Register.) (a) The Commissioner of Buildings shall sign or cause to be signed all certificates and notices required to be issued from the Department of Buildings and shall keep a record of the same, and shall issue or cause to be issued all permits authorized by this chapter.

(b) He shall also keep a proper record of all transactions and operations of the department and such record shall be at all times open to the inspection of the Mayor, Comptroller, Superintendent of Police, Fire Marshal and members of the City Council.

212. Must Keep Account of Fees Paid—Annual Reports and Estimates.) (a) Said commissioner shall keep in proper books for that purpose an accurate account of all fees charged, giving the name of person to whom same is charged, date on which said charge is made, and the amount of each such fee.

(b) He shall also, annually, on or before the first day of February in each year prepare and present to the City Council a report showing the receipts and expenditures and entire work of the Department of Buildings during the previous fiscal year and he shall on or before November first of each year prepare and submit to the Comptroller an estimate of the whole cost and expense of providing for and maintaining his office during the ensuing fiscal year.

213. Examination and Approval of Plans—Record of Inspections and Complaints.) The Commissioner of Buildings and his assistants shall pass upon all questions relating to the strength and durability of buildings or structures; shall examine and approve all plans before a permit is issued for the construction of any building or structure. The Commissioner of Buildings shall cause to be kept a complete record showing the location and character of every building or other structure for which a permit is issued and shall cause to be filed every report of inspection made on such building, which reports shall bear the signatures of the inspectors making such inspections. He shall cause to be kept a record of all complaints of violations of the building laws and shall cause all such complaints to be investigated.

214. Deputy Commissioner of Buildings—Duty.) (a) There is hereby created the office of Deputy Commissioner of Buildings.

He shall be appointed by the Commissioner of Buildings according to law. The person certified to fill this office shall be either a civil, structural or architectural engineer or an architect, an experienced building contractor or an efficient building mechanic with at least five years' experience and training.

(b) The Deputy Commissioner of Buildings shall act as Commissioner of Buildings in the absence of the Commissioner of Buildings from his office and while so acting shall discharge all the duties and possess all the powers imposed upon or vested in the Commissioner of Buildings.

(c) The deputy commissioner of buildings shall, under the direction of the Commissioner of Buildings, have general control of all matters and things pertaining to the work of the Department of Buildings and shall perform such other duties as may be required of him by the Commissioner of Buildings.

215. Engineer in Charge—Duties.) (a) There is hereby created the office of Engineer in Charge, of the Department of Buildings. He shall be appointed by the Commissioner of Buildings according to law. The person certified to fill this position shall be a civil, structural, or architectural engineer of at least five years' experience and training.

(b) The Engineer in Charge shall be in immediate charge of the engineering work and staff of the Department of Buildings. The examination of plans submitted for the purpose of obtaining a permit, except as to matters elsewhere expressly assigned by law to some other department of the city government, shall be the duty of the Engineer in Charge and the engineering staff under his charge. The approval and stamp of the Engineer in Charge shall be required on the plans for the erection, enlargement, alteration, repair or removal of every building before a permit for such erection, enlargement, alteration, repair or removal shall be issued. The Engineer in Charge shall have charge of all tests of materials and systems of construction submitted for the approval of the Commissioner of Buildings. The Engineer in Charge shall pass upon the number, location, width and design of all fire-escapes required for new buildings, and he shall also pass upon the number, location, width and design of fire-escapes to be erected on existing buildings wherever such existing buildings are being enlarged, altered or remodeled under a building permit issued for such enlargement, alteration or remodeling. He shall perform such other duties as may be required of him by the Commissioner of Buildings.

216. Assistant Engineer in Charge—Duties.) (a) There is hereby created, the office of Assistant Engineer in Charge, of the Department of Buildings. He shall be appointed by the Commissioner of Buildings according to law. The person certified to fill this position shall be a civil, structural or architectural engineer of at least five years experience and training.

(b) In the absence of the Engineer in Charge, the Assistant Engineer in Charge shall act as Engineer in Charge. The Assistant Engineer in Charge shall perform such other duties as may be required of him by the Engineer in Charge.

217. Engineering Staff.) (a) The Commissioner of Buildings shall appoint according to law at least four Architectural Engineers, and such other engineers and assistants as the City Council may by ordinance provide, for service on the engineering staff of the Department of Buildings. Every person certified to fill the position of Architectural Engineer shall be a civil, structural or architectural engineer of at least five years' training and experience.

(b) The Architectural Engineers shall, under the direction of the Engineer in Charge, examine all plans submitted for the purpose of obtaining a permit. They shall also examine and verify the figures on all floor load placards before such placards are approved for posting. They shall perform such other duties as may be required of them by the Engineer in Charge.

218. Building Inspector in Charge—Duties.) (a) The office of Assistant Deputy Commissioner of Buildings is hereby abolished and in lieu thereof there is hereby created the office of Building Inspector in Charge of the Department of Buildings. He shall be appointed by the Commissioner of Buildings according to law. The person certified to fill this position shall be a civil, structural, architectural or fire protection engineer, or an architect, or a building superintendent or a building mechanic with at least five years' experience in general building construction.

(b) In the absence of the Commissioner of Buildings and the Deputy Commissioner of Buildings from their offices the Building Inspector in Charge shall act as Commissioner of Buildings, and while so acting he shall discharge all of the duties and possess all of the powers imposed upon or vested in the Commissioner of Buildings.

(c) He shall have immediate charge of the periodical inspection of buildings and of the inspection of buildings and structures being erected, enlarged, altered or repaired, excepting only such inspection as is expressly assigned to the elevator or fire-escape inspectors or is by law assigned to some other department of the city government.

219. Assistant Building Inspectors In Charge.) (a) The Commissioner of Buildings shall appoint, according to law, at least four Assistant Building Inspectors in Charge.

(b) Every person certified to fill the position of Assistant Building Inspector in Charge shall be a civil, structural, architectural or fire protection engineer, or an architect, or a building superintendent or a building mechanic with at least five years' experience in general building construction. The Assistant Building Inspectors in Charge shall have immediate charge of the several districts assigned to them by the Commissioner of Buildings and shall perform such other duties as the Commissioner of Buildings shall require them.

220. Building Inspectors.) (a) The Commissioner of Buildings shall appoint according to law such Building Inspectors as may be necessary.

(b) Every person certified to fill the position of Building Inspector shall be a civil, structural, architectural or fire protection engineer, or an architect, or a building superintendent or a building mechanic with at least five years' experience in general building construction. The Building Inspectors shall, under the direction of the Building Inspector in Charge, examine all buildings and structures in the course of erection, enlargement, alteration, repair or removal, as often as is required for efficient supervision, and shall make such periodical examinations of existing structures as shall be assigned to them. They shall examine all buildings, structures and walls reported to be in dangerous condition. They shall examine all buildings and other structures for the enlarging, altering, raising or removing of which, application for permit shall be made.

(c) Every building inspector shall make written reports daily to the Commissioner of Buildings as to the condition in which he found each building examined and as to violations, if any, of the ordinances which

the Commissioner of Buildings is required to enforce, together with the street and number of the premises where such violations, if any, were found, the names of the owner, agent, lessee and occupant thereof, and of the architect and the contractor engaged in and about the work in question. The Building Inspectors shall perform such other duties as may be required of them by the Commissioner of Buildings.

221. Elevator Inspector in Charge.) (a) There is hereby created the office of Elevator Inspector in Charge. He shall be appointed by the Commissioner of Buildings according to law.

(b) The person certified to fill the position of Elevator Inspector in Charge, shall be a graduate in engineering from a recognized technical school, shall be versed in the essentials of both mechanical and electrical engineering and shall have had at least five years experience in shop or construction work.

(c) The Elevator Inspector in Charge shall examine all plans for the installation of elevators and for the installation of mechanical devices and apparatus in theaters, amusement parks and the like, and, no such elevator, mechanical device or apparatus shall be installed or operated without the approval of the Elevator Inspector in Charge. The Elevator Inspector in Charge shall cause such inspection to be made of all new installations, as may be necessary to insure the carrying out of the approved plans and shall cause such periodic inspection to be made of existing installations of such mechanisms, devices and apparatus, as may be required by the Commissioner of Buildings, and shall perform such other duties as may be required of him by the Commissioner of Buildings.

222. Elevator Inspectors.) (a) The Commissioner of Buildings shall appoint according to law such Elevator Inspectors as may be necessary.

(b) Every person certified to fill the position of Elevator Inspector shall be a mechanical engineer, machinist or elevator builder, and shall be well grounded in the rudiments of mechanical and electrical engineering.

(c) The Elevator Inspectors shall inspect all elevators and such other mechanisms, devices and apparatus as shall be assigned to them by the Inspector in Charge, both existing and in process of being erected or installed, together with all the equipment and enclosures thereof. They shall make written reports daily to the Commissioner of Buildings as to the condition in which they find the elevators, equipment, enclosures, mechanisms, devices and apparatus, inspected by them, and of any violations of the requirements of this Chapter pertaining to such matters, together with the street and number of the premises where such violations, if any, occur, the names of the owner, agent, lessee and occupant thereof, and of the architect and contractor engaged in or about the construction and installation of such elevators, equipment, enclosures, mechanisms, devices or apparatus. They shall perform such other duties as may be required of them by the Commissioner of Buildings.

223. Fire-escape Inspector in Charge.)

(a) There is hereby created the office of Fire-escape Inspector in Charge. He shall be appointed by the Commissioner of Buildings according to law.

(b) The person certified to fill the position of Fire-escape Inspector in Charge shall be a civil, structural or architectural engineer, or a man who has had not less than five years' experience in the design and erection of structural steel or in the design

and construction of fire-escapes, and he shall be qualified to make all necessary computations as to the strength of any fire-escape, the design of which may be submitted for approval and to pass upon the relative merits of such various types of design as may be so submitted.

(c) The Fire-escape Inspector in Charge shall have immediate charge of the inspection of the erection of all fire-escapes and of the periodic inspection of fire-escapes, and shall pass upon the number, location, width and design of fire-escapes to be erected upon existing buildings, except where the existing building is being enlarged, altered or remodeled under a building permit issued for such enlargement, alteration or remodeling, in which case the Engineer in Charge shall pass upon the number, location, width and design of all fire-escapes required for new buildings. The Fire-escape Inspector in Charge shall also perform such other duties as may be required of him by the Commissioner of Buildings.

224. Fire-escape Inspectors.) (a) The Commissioner of Buildings shall appoint according to law such Fire-escape Inspectors as may be necessary.

(b) Every person certified to fill the position of Fire-escape Inspector shall be a person who has had at least four years' experience in superintending the erection of buildings, or in the design or erection of fire-escapes or other steel construction, or who is a graduate of a recognized technical school.

(c) The Fire-escape Inspectors shall, under the direction of the Fire-escape Inspector in Charge, inspect all fire-escapes in course of erection and shall make periodic inspection of the fire-escape equipment of existing buildings. Every such inspector shall make, daily, a written report to the Commissioner of Buildings as to the condition of the fire-escape equipment of each building or premises examined, as to the accessibility of and means of egress to such equipment, as to the presumptive adequacy of such equipment, and as to any violations of any ordinance in relation to such equipment, together with the street and number of the building or premises inspected, the names of the owner, agent, lessee and occupant thereof and of the architect and contractor, if any, engaged in operation in connection with such equipment. The Fire-escape Inspectors shall perform such other duties as may be required of them by the Commissioner of Buildings.

225. Secretary—Duties.) (a) There is hereby created the office of Secretary to the Commissioner of Buildings. He shall be appointed by the Commissioner of Buildings according to law.

(b) The Secretary to the Commissioner of Buildings shall, under the supervision and direction of the Commissioner of Buildings, preserve and keep all books, records and papers belonging to the office of the Department of Buildings or which are required by law to be filed therein. He shall perform such other duties as may be required of him by the Commissioner of Buildings.

226. Clerical Assistants.) The Commissioner of Buildings shall appoint according to law, such clerical assistants, stenographers and messengers as may be necessary; and they shall perform such duties as may be required of them by the Commissioner of Buildings.

227. Bonds.) The Deputy Commissioner of Buildings, the Engineer in Charge, the Assistant Engineer in Charge, the Building Inspector in Charge, the Assistant Building Inspectors in Charge, the Elevator Inspector in Charge, the Fire-escape Inspector in

Charge and the Architectural Engineers shall, before entering upon the duties of their offices or positions, each execute to the City of Chicago a bond, conditioned for the faithful performance of their duties, with such sureties as the City Council shall approve in the following sums: The Deputy Commissioner of Buildings, ten thousand dollars; the Engineer in Charge, the Assistant Engineer in Charge, the Building Inspector in Charge, the Assistant Building Inspectors in Charge, the Elevator Inspector in Charge, the Fire-escape Inspector in Charge, and the Architectural Engineers, five thousand dollars each.

228. Employees Not to Engage in Another Business.) Every employee in the Department of Buildings shall devote his entire time to such employment and shall not be engaged in any other business or vocation.

229. Power of Entry.) The Commissioner of Buildings and his Assistants are empowered to enter any building or structure or premises, whether completed or in process of erection, for the purpose of determining whether the same has been or is being constructed and maintained in accordance with the provisions of this chapter and it shall be unlawful to exclude them from any such building, structure or premises.

ARTICLE II.

230. Permits—When Required—Limitations of Time For.) Before proceeding with the erection, enlargement, alteration, repair or removal of any building or structure in the city, a permit for such erection, enlargement, alteration, repair or removal shall first be obtained by the owner or his agent from the Commissioner of Buildings, and it shall be unlawful to proceed with the erection, enlargement, alteration, repair or removal of any building or of any structural part thereof within the city unless such permit shall have first been obtained from the Commissioner of Buildings. And if after such permit shall have been granted, the operations called for by the said permit shall not be begun within six months after the date thereof, or if such operations are not completed within a reasonable time, then such permit shall be void, and no operations thereunder shall be begun or completed until an extended permit shall be taken out by the owner or his agent, and a fee of twenty-five per cent. of the original cost of permit shall be charged for such extended permit, provided, however, that in no case shall a permit be issued or renewed for a less fee than two dollars.

231. Permits—Application For—Approval and Filing of Plans—Approval of Plans by Other City Departments—Encroachments Beyond Street or Alley Line—Plans to Be Kept on Work.) (a) Application for building permits shall be made by the owner or his agent to the Commissioner of Buildings. When such application is made, plans in conformity with the provisions of this chapter which have been examined and approved by the Commissioner of Buildings and his assistants, as hereinbefore provided for, shall be filed with the Commissioner of Buildings. He shall then issue a permit, and shall file such application, and shall apply to such plans a final official stamp, stating that the drawings to which the same has been applied comply with the terms of this chapter. The plans so stamped shall then be returned to such applicant. True copies of so much of such plans as may be required in the opinion of the Commissioner of Buildings to illustrate the features of construction and equipment of the building referred to, shall be filed with the Commissioner of Buildings, and shall remain on file in his office for a period of six months after the occupation of such

building, after which such drawings shall be returned by the Commissioner of Buildings to the person by whom they have been deposited with him, upon demand. It shall not be obligatory upon the Commissioner of Buildings to retain such drawings in his custody for more than six months after the occupation of the building to which they relate.

(b) All plans and drawings for the construction or alteration of any building or other structure for which building permits are required shall, before such permits are issued, be presented to the Commissioner of Health for examination and approval as to the proposed plan for the ventilation of rooms, light and air shafts, windows, the ventilation of water closets, drainage and plumbing. They shall also be presented to the Chief of Fire Prevention and Public Safety for examination and approval with regard to such ordinances as are his duty to enforce. They shall also be presented to the Boiler Inspector and the Smoke Inspector in all cases where permits from these departments are required to be procured by the ordinances of the City.

(c) All plans and drawings for the construction or alteration of any building or other structure for which a building permit is required may, at the option of the applicant for a building permit and by payment of a fee of one dollar for each plan, be filed in the office of the Commissioner of Buildings, and a receipt or check will be given for said plans which must be presented for the return of same after they have been examined and passed upon. The Commissioner of Buildings shall appoint a clerk with such necessary assistants whose duty it shall be, under the direction of the Commissioner of Buildings, to receive, take charge of and return all plans and drawings filed as aforesaid. Every plan or drawing so filed in the office of the Commissioner of Buildings shall be forwarded by him successively to the Department of Smoke Inspection, the Department of Boiler Inspection, the Department of Public Works, the Bureau of Fire Prevention and Public Safety, and the Sanitary Bureau, and there submitted to the proper officials of these respective departments and bureaus for examination and approval, and after said plans have been examined and passed upon, the Commissioner of Buildings shall cause said plans or drawings to be returned to his office where they shall be taken up for examination and approval by the Commissioner of Buildings. At the proper time notice shall be given by the Commissioner of Buildings to the applicant that his plans have been examined and are ready to be returned to him, and if such plans have been approved as submitted by the various departments and bureaus as aforesaid, the Commissioner of Buildings then shall, according to ordinance, issue a permit for the construction or erection of such building or structure.

The Commissioner of Buildings may issue permits for buildings for which it is contemplated that there shall be projections of the foundation, or a part or parts thereof, into a public street, a public alley or a public thoroughfare under the following conditions: Where such street, alley or thoroughfare is sixteen (16) feet or more in width such foundations shall have no projection at the sidewalk or alley grade, but may project at the ratio of four and one-half (4½) inches to one (1) foot for each one (1) foot of depth such foundation may extend below the sidewalk or alley grade to a maximum projection of thirty-six (36) inches at a depth of eight (8) feet below said sidewalk or alley grade, and such foundations, or such part or parts thereof, which are higher than a point twenty (20) feet below city datum and are lower than a point eight (8) feet below the sidewalk or alley grade may project into such street,

alley or thoroughfare for a distance not to exceed thirty-six (36) inches for that part of their extent as is included between a point eight (8) feet below the said sidewalk or alley grade and a point twenty (20) feet below said city datum, and, where said street, alley or thoroughfare is less than sixteen (16) feet in width, foundations, or any part or parts thereof, may project into such street, alley or thorough-




Fig. 1.

FOUNDATIONS.

See Section 231c.

- (A) Width of street.
Provision made for 16' 0" or over.
Provision made for less than 16' 0".
- (B) Allowable projection.
A ratio of 4½" to every foot of (C).
- (C) Depth of foundation below inside sidewalk grade or alley grade—See (B).
- (D) Maximum allowable projection at point (E) 8' 0" below said sidewalk or alley grade = 36' 0".
- (E) Point at depth of formation (8' 0") below sidewalk or alley grade where maximum projection begins. See (D).
- (F) Allowable maximum projection from (E) to 20' 0" below plus or minus 0 city datum = 36' 0".
- (G) For streets, alleys, etc., less than 16' 0" in width. Foundations may not be built nearer than (G) 5' 0" to middle line of streets or alleys, etc.
- (H) Allowable projection below 20' 0" city datum to be determined so far as in the opinion of the Commissioner of Buildings is necessary.

be at a ratio of four and one-half (4½) inches of projection to one (1) foot of depth, but no foundation, or part or parts thereof, shall be built nearer than five (5) feet to the middle line of such street, alley or thoroughfare. No foundation, or any part or parts thereof, shall project into a public street, a public alley or a public thoroughfare in such manner as to add area to the superstructure of any building or structure.

The construction of caisson and other types of foundations, part or parts of which may extend to a greater depth than twenty (20) feet below city datum, shall conform to the requirements of this section as hereinbefore contained in such part or parts as are higher than twenty (20) feet below city datum and lower than eight (8) feet below the sidewalk or alley grade and in such part or parts as are higher than eight (8) feet below the sidewalk or alley grade, but such part or parts of such last mentioned foundations as are constructed lower than twenty (20) feet below city datum may project into a public street, a public alley or a public thoroughfare so far as, in the opinion of the Commissioner of Buildings, is necessary for the stability of the building or structure of which they are a part.

It is expressly made a condition in the issuance of any permit for the construction of a building or structure whose foundations, or any part or parts thereof, project into a public street, a public alley or a public thoroughfare at any point higher than twenty (20) feet below city datum that if during the construction of or after the completion of such structure or building the said foundation, or any part or parts thereof, shall project in such a manner as to interfere with or be an obstruction to the building of, maintaining, conducting or operating any public utility now or hereafter to be constructed, or any part or parts of any construction in connection therewith, that such projecting foundations, projecting part or projecting parts thereof, shall be subject to removal upon notice from the Commissioner of Public Works so to do. Such notice shall be in writing and shall allow such length of time as said Commissioner of Public Works shall deem a reasonable time for the purpose of making the changes required thereunder, but the owner or owners of the said building or structure shall proceed at once upon receipt of said notice to remove all projecting part or parts of such foundations without any expense, loss or damage accruing to the City of Chicago. Upon failure of such owner or owners to comply with said notice by beginning the work required thereunder within thirty (30) days after the receipt of such notice or upon failure to complete same within such reasonable time thereafter as the said Commissioner of Public Works shall deem sufficient, the Commissioner of Public Works may proceed at once to remove such projecting part or parts of such foundations and the City of Chicago may recover the cost and expense of such removal, unless otherwise reimbursed, by an action at law against the owner or owners, lessee or tenants of said premises.

(d) The Commissioner of Buildings shall not issue any permit authorizing the construction, erection, repair or alteration of any building or structure unless the plans submitted for his approval clearly show that such building or structure with all its appurtenances, foundations and attachments can be erected entirely within the limits of the lot or tract of land upon which it is proposed to erect such building or structure, except as hereinafter provided and except as provided by the ordinances of the City of Chicago, and no permit to erect, alter or alter any building or structure shall be issued for the purpose of any work to be done on any public ground for the construction or maintenance of such

building or structure except as hereinafter provided and except as provided by the ordinances of the City of Chicago, nor shall any permit be issued for the construction or maintenance of any balcony or canopy extending over any public highway or other public ground unless permits therefor have been obtained from the proper department of the city government pursuant to an ordinance, specifically authorizing the same. The plans of every building or structure which show that any part of said building or structure or any of its appurtenances, or attachments thereto, extend over any part of any public highway or other public ground other than hereinafter provided for shall, previous to being submitted to the Commissioner of Buildings, be submitted to the Commissioner of Public Works and notice thereby given to him of the proposed encroachment upon any public highway or other public ground. Proof of such notice to the Commissioner of Public Works must accompany plans when same are presented to the Commissioner of Buildings.

The Commissioner of Buildings may issue permits for horizontal cornices and belt courses so called to be constructed on buildings as follows:

Where all parts of a cornice of any building or structure are more than twelve feet above the inside grade of the sidewalk, and where the sidewalk grade varies, are more than twelve feet above the average or mean inside grade of the sidewalk and where such cornice extends in whole or in part along the street frontage of a building, and where the return of such cornice if any along an alley wall is not longer than a distance equal to the width of the alley, such cornice may project into the street or alley a distance of twenty-four inches. For each additional one foot in height such cornice is placed above the height of twelve feet as aforesaid up to the limits of height fixed by ordinances for the particular building of which such cornice is a part, such cornice may project into the street or alley an additional one-quarter inch, until the total projection has reached the maximum of four feet six inches where the width of the street is less than sixty-six feet and to a maximum of five feet where the width of the street is sixty-six feet or more.

Horizontal belt courses, water tables and other horizontal architectural features, which do not add floor area to a building or structure and which extend in whole or in part along the street frontage of a building with a return if any around an alley wall not longer than a distance equal to the width of the alley, and where all parts of such horizontal belt courses, water tables and other horizontal architectural features are more than twelve feet above the inside grade of the sidewalk, may project into the street or alley a distance not to exceed eighteen inches.

The Commissioner of Buildings may issue permits for buildings for which it is contemplated that there shall be projections of the foundation, or a part or parts thereof, into a public street, a public alley or a public thoroughfare under the following conditions: Where such street, alley or thoroughfare is sixteen (16) feet or more in width such foundations shall have no projection at the sidewalk or alley grade, but may project at the ratio of four and one-half (4½) inches to one (1) foot for each one (1) foot of depth such foundation may extend below the sidewalk or alley grade to a maximum projection of thirty-six (36) inches at a depth eight (8) feet below said sidewalk or alley grade, and such foundations, or such part or parts thereof, which are higher than a point twenty (20) feet below city datum and are lower than a point eight (8) feet below the sidewalk or alley grade, may project into such street, alley or thoroughfare for a distance not to

exceed thirty-six (36) inches for that part of their extent as is included between a point eight (8) feet below the said sidewalk or alley grade and a point twenty (20) feet below said city datum, and, where said street, alley or thoroughfare is less than sixteen (16) feet in width, foundations, or any part or parts thereof, may project into such street, alley or thoroughfare at a ratio of four and one-half ($4\frac{1}{2}$) inches of projection to one (1) foot of depth, but no foundation, or part or parts thereof, shall be built nearer than five (5) feet to the middle line of such street, alley or thoroughfare. No foundation, or any part or parts thereof, shall project into a public street, a public alley or a public thoroughfare in such manner as to add area to the superstructure of any building or structure.

The construction of caisson and other types of foundations, part or parts of which may extend to a greater depth than twenty (20) feet below city datum, shall conform to the requirements of this section as hereinbefore contained in such part or parts as are higher than twenty (20) feet below city datum and lower than eight (8) feet below the sidewalk or alley grade and in such part or parts as are higher than eight (8) feet below the sidewalk or alley grade, but such part or parts of such last mentioned foundations as are constructed lower than twenty (20) feet below city datum may project into a public street, a public alley or a public thoroughfare so far as, in the opinion of the Commissioner of Buildings, is necessary for the stability of the building or structure of which they are a part.

It is expressly made a condition in the issuance of any permit for the construction of a building or structure whose foundations, or any part or parts thereof, project into a public street, a public alley or a public thoroughfare at any point higher than twenty (20) feet below city datum that if during the construction of or after the completion of such structure or building the said foundation or any part or parts thereof, shall project in such a manner as to interfere with or be an obstruction to the building of, maintaining, conducting or operating any public utility now or hereafter to be constructed, or any part or parts of any construction in connection therewith, that such projecting foundations, projecting part or projecting parts thereof, shall be subject to removal upon notice from the Commissioner of Public Works so to do. Such notice shall be in writing and shall allow such length of time as said Commissioner of Public Works shall deem a reasonable time for the purpose of making the changes required thereunder, but the owner or owners of the said building or structure shall proceed at once upon receipt of said notice to remove all projecting part or parts of such foundations without any expense, loss or damage accruing to the City of Chicago. Upon failure of such owner or owners to comply with said notice by beginning the work required thereunder within thirty (30) days after the receipt of such notice or upon failure to complete same within such reasonable time thereafter as the said Commissioner of Public Works shall deem sufficient, the Commissioner of Public Works may proceed at once to remove such projecting part or parts of such foundations and the City of Chicago may recover the cost and expense of such removal, unless otherwise reimbursed, by an action at law against the owner or owners, lessee or lessees of said premises.

In addition to the general plan of the building or structure as required in other sections of this ordinance, a detailed plan drawn to a large scale of any proposed cornice or any projection contemplated in this section, shall be submitted to the Com-

missioner of Buildings for his examination and approval.

(e) In all cases, the approved plan, together with building permits, must be kept on the job while the work is in progress.

(f) Whenever an application is made for the issuance of a special permit which is in violation of the building Code of the City of Chicago and for the issuance of which permit it is necessary to secure an order of the City Council of the City of Chicago authorizing the erection or construction of the building or structure in question, the Building Commissioner shall cause an investigation to be made of the proposed structure prior to the introduction of such order into the City Council. Said applicant shall file with the Building Commissioner at the time of filing said application a check for the fees hereinbefore provided.

(g) The Building Commissioner, upon the completion of such investigation, shall determine the particular class in which said building would, if in compliance with the Building Code, be classified and shall forward said application to the City Council, together with his recommendation as to whether the City Council should or should not authorize the proposed violation, and with his recommendation for the fee to be charged for the issuance of such permit.

(h) The fees to be charged for building permits for which a Council order is to be secured for the erection and completion of any buildings, sheds or other structures, shall be a fee not exceeding one hundred per cent (100%) of the original fee charged in addition to the fee as prescribed by ordinance for a permit for such building, shed or other structures.

232. Plans—Essentials of.) All plans and drawings for buildings or for structures other than buildings shall be presented to the Commissioner of Buildings for his approval, and each set of plans presented shall be approved by the Commissioner of Buildings before a permit will be granted. All such plans and drawings shall be drawn to a scale of not less than one-eighth of an inch to the foot, on paper or cloth, in ink, or by some process that will not fade or obliterate. All distances and dimensions shall be accurately figured, and drawings made explicit and complete, showing the lot lines and the entire sewerage and drain pipes and the location of all plumbing fixtures within such building or structure. No permit shall be granted or plans approved unless such plans are signed and sealed either by a licensed architect or provided in "An Act to provide for the licensing of architects and regulating the practice of architecture as a profession in the State of Illinois," approved June 3, 1897, or by a licensed structural engineer as provided in "An Act to provide for the licensing of structural engineers," approved July 5, 1915, or both, as may be required by said Acts.

233. Plans—Alterations Upon Stamped Plans Not Permitted Without Permission—Certain Alterations Excepted.) It shall be unlawful to erase, alter or modify any lines, figures, or coloring contained upon such drawings so stamped by the Commissioner of Buildings or filed with him for reference. If, during the progress of the execution of such work, it is desired to deviate in any manner affecting the construction or other essentials of the building from the terms of the application, or drawing, notice of such intention to alter or deviate shall be given to the Commissioner of Buildings, and his written assent shall first be obtained before such alteration or deviation may be made; but alterations in buildings which do not involve any change in their structural parts or of their stairways, elevators, fire-escapes or other means of communication or ingress or egress or in lighting or ventilation and

that are not in violation of any of the provisions of this chapter, may be made without the permission of the Commissioner of Buildings.

234. Deposit With Water Department—How Made—Indemnifying Bonds—Fees for Water Used.)

(a) Before the Commissioner of Buildings issues a permit as aforesaid he shall require evidence from the applicant that payment has been made to the Bureau of Water of the city for the water to be used or for a water meter for measuring all the water to be used in the construction of such building, under the regulations of the Bureau of Water. Such applicant shall produce evidence that he has filed with and had approved by the Commissioner of Public Works of the city an indemnifying bond protecting the city against any and all damage that may arise to the streets or alleys upon which such building abuts, and to the city and to any person in consequence, or by reason of, the proposed operations to be authorized by such permit, or by reason of any obstruction or occupation of any street or sidewalk in and about such building operations.

(b) The fees to be paid for water used in connection with the erection of buildings shall be as follows, to-wit:

At the rate of five cents for every one thousand bricks, wall measure, used in connection therewith.

At the rate of six cents for every one hundred cubic feet of rubble stone used in connection therewith.

At the rate of eight cents for every one hundred cubic feet of concrete used in connection therewith.

At the rate of fifteen cents for every one hundred yards of plastering used in connection therewith.

At the rate of five cents for every one hundred cubic feet of hollow tile arch, partition or fireproof covering used in connection therewith.

235. Amount of Permit Fees.

(a) The fees to be charged for building permits shall be as follows: For sheds not exceeding three hundred square feet in area, two dollars; for open shelter sheds, at the rate of two dollars for each one thousand cubic feet or fractional part thereof; for all buildings or other structures, other than sheds and open shelter sheds, as hereinafter described, the fee for the permit shall be at the rate of twenty cents for every one thousand cubic feet or fractional part thereof for buildings containing not to exceed two hundred thousand cubic feet of volume. For buildings exceeding two hundred thousand cubic feet in volume twenty cents per cubic feet for the first two hundred thousand cubic feet and forty cents per one thousand cubic feet for each additional one thousand cubic feet of volume or fractional part, the cubic contents being measured to include every part of the building from the basement floor to the highest point of the roof, and to include all bay windows and other projections; but in no case shall any permit be issued for a less fee than two dollars, except that a fee of two dollars shall be charged for recovering or re-coating the roof of any building.

(b) The fee to be charged for permits issued for alterations and repairs in or to any building or other structure shall be based on the cost of such alterations and repairs and shall be at the rate of two dollars for the first one thousand dollars expended, one dollar additional for each one thousand dollars expended; or parts thereof to be expended therefor. The fee for permit to raise any building other than a frame building shall be for raising, shoring up, underpinning or moving any building other than a frame building ten cents per one thousand cubic feet of volume or fractional part thereof. Provided, however, that in no case shall a permit be issued for a less fee than five dollars.

(c) In addition to the above permit fees for buildings, permit and inspection fee shall be charged as follows:

For erection of fire-escape, four dollars minimum to include fire-escapes up to four stories in height; and fifty cents additional for each story above four stories in height; For installation or alteration of elevator, five dollars;

For semi-annual inspection of elevator, four dollars;

For erection of billboards or signboards, five dollars; for every twenty-five lineal feet or fractional part thereof;

For erection of illuminated and other roof signs under Section 685 of this chapter, fifty dollars for the first five hundred square feet of superficial area or fractional part thereof and five cents for each additional square foot area;

For annual inspection of billboard or signboard, one dollar for every twenty-five lineal feet of billboard or signboard or fractional part thereof;

For annual inspection of illuminated and other roof under Section 685, fifty dollars for the first five hundred square feet or fractional part thereof, five cents additional for each additional square foot area over five hundred square feet;

For annual inspection of building required by Section 238 of this chapter, three dollars for each twenty-five thousand square feet or fractional part thereof;

For semi-annual inspection of iron or steel curtain, ten dollars;

For semi-annual inspection of asbestos curtain, five dollars;

For permit for tank on roof or tower in excess of four hundred gallon capacity, five dollars;

For permit for isolated chimneys or for chimneys extending over fifty feet above the roof of any building, five dollars;

For annual inspection of dry cabarets, which include all restaurants, refreshment parlors and summer gardens in which music, dancing or entertainment is furnished or conducted, a fee of five dollars shall be charged. For annual inspection of shooting galleries a fee of five dollars shall be charged. For annual inspection of penny arcades and walk-around shows a fee of five dollars shall be charged.

236. Permit for Wrecking Building.)

(a) Before proceeding with the wrecking or tearing down of any building or other structure more than one story in height, a permit for such wrecking or tearing down shall first be obtained by the owner or his agent from the Commissioner of Buildings, and it shall be unlawful to proceed with the wrecking or tearing down of any building or structure or any structural part of such building or structure unless such permit shall first have been obtained. Application for such permit shall be made by such owner or his agent to the Commissioner of Buildings, who shall issue such permit upon such application and the payment of the fee herein provided for. Such application shall state the location and describe the building which it is proposed to wreck or tear down. The fee for such permit shall be five (\$5.00) dollars for every twenty-five feet, or fractional part thereof, of frontage. Upon the issuance of such permit, such building may be wrecked or torn down, provided that all the work done thereunder shall be subject to the supervision of the Commissioner of Buildings and to such reasonable restrictions as he may impose in regard to elements of safety and health, and provided, further, that the work shall be kept sprinkled and sufficient scaffolding be provided to insure safety to human life.

(b) Before any permit is issued granting authority to wreck a building or structure for which such permit is required, the person, firm or corporation engaged in the work of wrecking same shall file with the City Clerk a bond with sureties to be approved by the City Comptroller to in-

demnify, keep and save harmless the City against any loss, cost, damage, expense, judgment or liability of any kind whatsoever which the City may suffer, or which may accrue against, be charged to or be recovered from said City, or any of its officials, from or by reason or on account of accidents to persons or property during any such wrecking operations, and from or by reason or on account of anything done under or by virtue of any permit granted for any such wrecking operations. Such bond in each case shall extend to and cover all such wrecking operations carried on through permits obtained thereunder by such person, firm or corporation during any fiscal year beginning January first and ending December thirty-first, and no permit shall be issued for any wrecking work except as hereinbefore otherwise provided during such fiscal year until such bond is filed. Said bond shall be in the penal sum of twenty thousand dollars for all wrecking operations on such buildings and other structures not more than three stories in height, and there shall be an additional bond filed in the penal sum of twenty thousand dollars or a bond in the penal sum of forty thousand dollars shall be filed in the first instance in case of wrecking operations on buildings and other structures four or more stories in height. Upon the filing of such bond or bonds the person, firm or corporation engaged in the work of wrecking such buildings and other structures may obtain permits for such wrecking operations as are authorized under the said bond or bonds as hereinabove provided for during the fiscal year in which the same is or are filed: Provided, that, in case of accident or casualty in the progress of any wrecking operations carried on under any permit so issued, or the happening of any circumstance which might in the opinion of the Commissioner of Buildings render such bond or bonds inadequate, the said Commissioner may, in his discretion, require such additional bond as he may deem necessary to fully protect the city from loss resulting from the issuance of such permits before he allows the work to proceed or before any additional permits are issued by him.

237. Permit—Revocation of.) If the work in, upon or about any building or structure shall be conducted in violation of any of the provisions of this chapter, it shall be the duty of the Commissioner of Buildings to revoke the permit for the building or wrecking operations in connection with which such violation shall have taken place. It shall be unlawful, after the revocation of such permit, to proceed with such building or wrecking operations unless such permit shall first have been re-instated or re-issued by the Commissioner of Buildings. Before a permit so revoked may be lawfully re-issued or re-instated, the entire building and building site shall first be put into condition corresponding with the requirements of this chapter, and any work or material applied to the same in violation of any of the provisions of this chapter shall be first removed from such buildings.

238. Annual Inspection of Buildings—Stairways and Means of Egress—Inspection Fee.) (a) The Commissioner of Buildings and his assistants shall make an annual inspection of all theaters and places of amusement, worship, instruction or entertainment, and also of all other buildings over two stories in height, except residences, and except buildings in which automobiles are housed, and except tenements three stories or less in height. It shall be the duty of every owner, agent, lessee or occupant of any such building as is referred to in this section and of the person in charge or control of same to permit the making of such annual inspection by the Commissioner of Buildings, or by a duly authorized Build-

ing Inspector, at any time upon demand being duly made.

(b) Whenever any such inspection shows the building to be in compliance with the requirements of this Chapter with respect to stairways, means of egress, and in all other respects, it shall be the duty of the Commissioner of Buildings to issue, or cause to be issued, a certificate setting forth the result of such inspection, containing the date thereof, and a statement to the effect that such building complies in all respects with the provisions of this Chapter, upon the payment of the inspection fee herein required.

(c) It shall be the joint and several duty of the owner, agent, lessee or occupant of the building so inspected and of each and every person in charge and control of the same to frame the said certificate and place it in a conspicuous place near the main entrance of such building.

(d) It shall be the joint and several duty of the owner, agent, lessee or occupant of every building described in this section to provide a typical floor plan of such building reproduced on a sheet eight by ten inches in size. Said plan shall be drawn on as large a scale as will be practicable on such sheet, and said sheet shall also state the street address of such building, and shall give the class of the building, the kind of construction used therein, the height and number of stories contained therein and the nature of the occupancy.

(e) It shall also be the joint and several duty of such owner, agent, lessee or occupant to deliver a copy of said sheet to the Commissioner of Buildings and to frame a copy of said sheet and place the same near the framed certificate hereinabove required.

(f) It shall also be the joint and several duty of the said owner, agent, lessee or occupant to substitute a new sheet for the sheet on file with the Commissioner of Buildings, and also the sheet framed as above required, whenever such changes or alterations are made in such building as will affect the substantial accuracy of the sheet previously furnished such Commissioner and framed as above required.

(g) Where the result of such inspection shall show that such building fails in any respect to comply with the requirements of this Chapter, it shall be the duty of the Commissioner of Buildings to notify the owner, agent, lessee or occupant of such building to this effect and to specify wherein such building fails to comply with the requirements of this chapter; and it shall thereupon become the joint and several duty of such owner, agent, lessee or occupant to proceed forthwith to make whatever changes or alterations may be necessary to make such building comply in all respects with the requirements of this chapter and to complete such changes and alterations within thirty days after the receipt of such notice.

(h) Upon making such annual inspection, it shall be the duty of the owner to pay to the City Collector an annual inspection fee for the same, amounting to three dollars for each 25,000 square feet of floor area, or fractional part thereof: Provided, however, that no charge for such annual inspection shall be made against religious, charitable or educational institutions.

239. Architect Must Certify That Plans Comply With the Building Ordinances.) It shall be unlawful for any architect, or other person permitted under the laws of the state to make plans, to prepare or submit to the Commissioner of Buildings for his approval any final plans for any building or structure which do not comply with the structural requirements of this chapter. It shall be the duty of the Commissioner of Buildings to require that all plans submitted to him for approval for any building or structure shall be accompanied by a certifi-

cate of such architect or such other person preparing such plans that the plans submitted comply with the structural requirements of this chapter.

136 Constructing Buildings Contrary to Approved Plans—Permit Made Void by Deviation from Plans—Power to Stop Work.)

It shall be unlawful for any owner, agent or architect, or for any contractor or builder engaged in erecting, altering or repairing any building, to make any departure from the plans as approved by the Commissioner of Buildings of such nature that such departure involves any violation of the requirements of this chapter as to buildings of the class in which such building is, or to make any changes in plans or construction affecting means of egress, ventilation, natural lighting, or sanitary conditions without first obtaining the written consent of the Commissioner of Buildings and of the Commissioner of Health to such changes. Any such departure from the approved plans involving a violation of the requirements of this chapter or any such change in the plans or construction without the consent of the Commissioner of Buildings and the Commissioner of Health being obtained, as required herein, shall operate to annul the permit which has been issued for such work and shall render the same void.

(b) In case any work is done under a permit authorizing the erection, alteration or repair of a building or structure, which work is contrary to the approved plans, the Commissioner of Buildings or the Commissioner of Health and their assistants shall have power to at once stop such work and to order all persons engaged therein to stop and desist therefrom. Such work shall not be resumed until satisfactory assurance has been given to the Commissioner of Buildings or the Commissioner of Health that it will be done according to the approved plan or until said Commissioner of Buildings or Commissioner of Health has consented in writing to the changes made in such approved plans and if such changes in the approved plan involve additional work a new permit or an extended permit shall be issued for which an additional fee shall be paid by the contractor doing such work.

(c) No contractor or builder shall begin any work on any building or structure for which a permit is required until such permit shall have been secured. In case any work is begun on the erection, alteration, repair or removal of any building or structure without a permit authorizing the same being issued therefor, the Commissioner of Buildings and his assistants shall have power to at once stop such work and to order any and all persons engaged therein to stop and desist therefrom until the proper permit is secured.

ARTICLE III.

Classification of Buildings.

137 Buildings—Class Of.) All buildings other than sheds and shelter sheds as hereafter described, now existing or hereafter erected, altered or enlarged, shall be classified as follows:

(b) **Class I.)** In Class I shall be included every building used for the sale, storage or manufacture of merchandise, other than department stores as described in this chapter. Also such buildings, structures or places with a ground area of five hundred square feet or more used as and for the purposes of a barn, stable or a garage or for the housing or keeping of automobiles.

(c) **Class II.)** In Class II shall be included every building referred to in subdivisions Class IIA, Class IIB and Class IIC.

(d) In Class IIA shall be included every building used for office purposes, and also where sleeping accommodations are provided for less than twenty persons.

(e) In Class IIB shall be included every building used for hotel, club, lodging or rooming house purposes where such building has sleeping accommodations for twenty or more persons.

(f) In Class IIC shall be included every building used for a hospital where sleeping accommodations for more than ten persons are provided in such building, and every building used for a home, day nursery or asylum where any such building shall have accommodations for more than twenty persons or where more than ten bedridden or decrepit persons are housed, and every building used for a jail, house of correction or detention.

(g) **Class III.)** In Class III shall be included every building used as a private residence, also every building used for a hospital where sleeping accommodations for ten or less persons are provided in such building, and every building used for a home, day nursery or asylum where any such building shall have accommodations for twenty or less persons or where not more than ten bedridden or decrepit persons are housed, and also every building, structure or place with a ground area of less than five hundred square feet used as and for the purposes of a barn, stable or garage or for the housing or keeping of automobiles.

(h) **Class IV.)** In Class IV shall be included every building referred to in subdivisions Class IVA, Class IVb, Class IVC, and Class IVD, as follows:

(i) In Class IVA shall be included every building used as a church or place of worship.

(j) In Class IVb shall be included every building having a parish hall, Lodge hall, dance hall, banquet hall, skating rink, assembly hall, halls used for the purpose of exposition and exhibition, and buildings having a hall for the purpose of instruction other than schools, included in Class VIII, and also every existing building having a hall used for theatrical purposes at the time of the passage of this ordinance, except such buildings as are included in Classes IVA, IVC, IVD, and V.

(k) In Class IVC shall be included every building hereafter erected used for moving picture and vaudeville shows and similar entertainments, where an admission fee is charged and regular performances are given, and where the seating capacity does not exceed three hundred, provided, that every building of Class IVC existing at the time of the passage of this ordinance shall comply with the provisions of Class IVb.

(l) In Class IVD shall be included every grand stand and every baseball athletic and amusement park.

(m) **Class V.)** In Class V shall be included every building which is used as a public theatre where an admission fee is charged and in which movable scenery is used, and every assembly hall hereafter erected having a seating capacity of over 300 and containing a permanent stage on which scenery and theatrical apparatus are used and regular theatrical vaudeville performances are given; provided, however, that public halls and club halls with a seating capacity of less than 600, although occasionally used for theatrical presentations, shall not be construed to be public theatres within the meaning of the term as used in this section, notwithstanding the fact that movable scenery is used upon the stages thereof on such occasions, and such public halls and club halls shall not be considered as buildings of Class V as herein defined. Such public halls and club halls shall be included in Class IVb, as defined in this section.

(n) **Class VI.)** In Class VI shall be included every tenement and apartment house or building or portion thereof which is used or intended to be used as a home or resi-

dence for two or more families living in separate apartments.

(o) **Class VII.)** In Class VII shall be included every building used for the sale at retail of dry goods and other articles of general merchandise and commonly known and described as a department store.

(p) **Class VIII.)** In Class VIII shall be included every building used for school purposes and every building containing class rooms for special or general instruction, other than halls for the purpose of instruction as included in Class IV, where such building so used shall have a seating capacity of more than fifty students.

(q) **Class IX.)** In Class IX shall be included every building maintained by the City of Chicago for police station purposes.

(r) Requirements with regard to buildings not within any of the above classes shall be determined by the Commissioner of Buildings subject to arbitration in the same manner as provided in Sections 207 and 208 of this chapter.

242. Buildings Used for the Purposes of More Than One Class.) Where any building is used for the purposes of two or more classes, as herein specified, and defined, such portion of any such building as is devoted to the uses and purposes of any particular class shall be constructed, operated and maintained in accordance with the requirements of this chapter relating to such class, unless such construction shall, in the opinion of the Commissioner of Buildings, prove impracticable, or unless there would be a conflict between the provisions of this chapter relating to the construction of buildings, in either of which cases the provisions which relate to and govern the construction of buildings of the class requiring the best and safest form of construction shall govern the entire building.

243. Conflict Between Special and General Provisions.) Whenever any provision or requirement of this chapter relating specifically to the construction, equipment, maintenance, or operation of any building or part of a building used for the purpose of any specified class, shall conflict with the general provisions of this chapter relating to the construction, equipment, maintenance and operation of buildings generally, the special provisions shall govern in each case, except in the case of Section 501, which shall govern in all cases coming within its provisions.

ARTICLE IV.

Class I.

244. Class I Defined.) In Class I shall be included every building used for the sale, storage or manufacture of merchandise, other than department stores as described in this chapter. Also such buildings, structures or places with a ground area of five hundred square feet or more used as and for the purpose of a barn, stable or a garage or for the housing or keeping of automobiles.

245. Must Comply With General and Special Provisions.) Every building of Class I shall comply with the general provisions of this chapter, and shall, in addition, comply with the following special provisions:

246. Buildings—Construction of—In Relation to Height.) (a) The construction of buildings of Class I shall be as follows: Buildings of Class I which are more than 100 feet in height shall be built of fireproof construction.

(b) Buildings of Class I which are less than 100 feet in height and more than 50 feet in height shall be built of slow-burning, mill or fireproof construction. Buildings of Class I of slow-burning or mill construction shall not be built more than seven stories in height.

(c) Buildings of Class I of ordinary construction shall not be built more than four stories in height.

247. Skeleton Steel Walls—Metal Lath and Solid Cement Plaster Covers—Buildings for Explosives—Buildings for Housing Motor Driven Vehicles—Buildings for Smoking Meats—Buildings for Dry Cleaning.) (a) A one or two story building used for the purposes of Class I, no part of which is within twenty feet of any lot line, alley line or street line, having a complete self-supporting steel frame consisting of wall columns, supporting steel trusses, with steel trusses and steel diagonals, designed to resist safely, within the safe limits of stress provided by this chapter, a wind pressure of twenty pounds per square foot, for each and every exterior surface exposed to the wind, in addition to the dead weight of the completed structure, and in addition to the live load of 100 pounds per square foot provided for by this chapter, and any other live loads which may be imposed on such structure, may have exterior walls measuring not less than one and one-third inches thick of metal lath or metal fabric plastered on both sides with a mortar consisting only of Portland cement and torpedo sand. Complete reinforced concrete framework, built in every manner equally as strong and as safe as provided for a steel frame, in this section, may have exterior walls built in the same manner, of the same materials and of the same thickness.

(b) The enclosing walls of buildings which are built not less than fifty feet from any lot, alley or street line may be constructed of corrugated iron, supported on a steel frame built as specified in this section.

(c) Buildings for the storage of fireworks and of similar substances or articles of an explosive nature shall have walls of masonry construction, shall not exceed one story in height, shall not exceed sixteen hundred (1,600) square feet in area unless such building is divided into areas of sixteen hundred (1,600) square feet or less by dividing walls the construction of which and the equipment of openings in same being in compliance with the requirements of Section 251 of this chapter. The roof of such building may be constructed of wood joists and roof boards covered with incombustible material or of wood joists covered with sheet metal or of common glass set in metal frames, but in every case at least thirty (30%) per cent of the area of such roof shall be constructed of common glass and metal frames. Such buildings shall be situated not less than one hundred feet from any other building or structure and shall be situated not less than one hundred feet from any lot line, or where such lot line abuts a street, alley or public thoroughfare said building shall be situated not less than one hundred feet away from the opposite side of such street, alley or public thoroughfare.

(d) Buildings erected for the collection or compression of acetylene gas at a pressure of exceeding fifteen (15) pounds to the square inch shall be of fireproof construction throughout and shall be located at least two hundred and fifty feet away from any other building or structure and at least two hundred and fifty feet from any lot line and any street, alley or public thoroughfare.

(e) Every building or structure hereafter erected and every existing building or structure hereafter increased in size or otherwise altered or hereafter converted or used for the purpose of housing five or more self-propelled vehicles or other wheeled machines, containing in the tanks thereof volatile inflammable liquid for fuel or power, and all adjoining buildings and structures not separated therefrom by dividing walls of brick or concrete extending at least three feet above the roof and having openings, if any, protected on both sides by approved automatic fire doors, where such building or structure is more than one story and less than four stories in height shall be of fireproof construction throughout, or shall be equipped throughout with an automatic

sprinkler system. Where any such building is two stories or less in height and complies in all other respects with the requirements for fireproof construction and the second floor area is co-extensive with the area of the building and without openings other than for stairs and elevators, such one or two-story building as aforesaid may have a roof of ordinary, slow-burning or mill construction. Where any such building two stories or less in height has a mezzanine floor or floors with a total area larger than twenty per cent of the area of the building it shall be considered an additional floor and that part or those parts of building containing such additional floor or floors shall be separated from every other part of said building by a wall of brick or concrete built of thickness as required for enclosing walls by the provisions of this chapter, and such parts of building so separated by such dividing wall shall have no openings in their floors from story to story other than is required for stairs and elevators. The openings connecting the different areas of such buildings shall be protected by double automatic fire door equipment. Every such building or structure more than three stories in height shall be of fireproof construction throughout and shall be equipped throughout with an automatic sprinkler system. In all such buildings more than two stories in height all window openings, except in walls that adjoin a public street fifty feet or more in width, shall be equipped with approved metal frames and sash glazed with wired glass. Buildings less than three stories high shall comply with the requirements of Section 558 of this chapter. All floor openings in non-fireproof buildings shall be enclosed in walls of masonry of such thickness as required by the provisions of this chapter and shall extend from the ground through the roof of the building; in fireproof buildings, all elevator shafts and other vertical shafts except stairways shall be enclosed in every story with walls of brick, tile, plain or reinforced concrete at least eight inches thick, all stairways shall be enclosed in every story with walls of brick, tile or reinforced concrete at least four inches thick and all openings in such enclosing walls shall be equipped with approved automatic or self-closing fire doors. There shall be no basement in any such building, except for boiler room purposes, unless such building, including the roof and the protection of the roof beams and roof girders, is of fireproof construction throughout and is equipped throughout with an automatic sprinkler system, and with no floor openings between the basement and other floors, except for stairs and elevators, and such openings shall be enclosed in both the basement and first floor by walls of brick or concrete at least eight inches thick or of fireproof tile at least twelve inches thick and equipped with doors as hereinbefore specified. There shall be no openings from the boiler room except to the outside of the building. Where such building is on a lot that adjoins two streets or a street and an alley whose established grades are not at the same elevation the story whose floor is higher than two feet below the lower of these grades shall, for the purpose of this section, be deemed the first story of said building.

(f) Every building, structure or place not now used for the housing of four or less vehicles containing volatile inflammable liquid in the tanks thereof but hereafter converted to such use, and every building or structure hereafter erected for the housing of four or less such vehicles, where so used, must be occupied and used exclusively for such purposes under the following conditions and with the exceptions hereinafter noted:

Frame sheds or buildings may be so used if such shed stands at least five feet from every other building or structure on the

same lot or plot of ground provided, however, that in frame buildings used exclusively for Class I purposes a portion of such building may be so used if the part so occupied is separated from all other parts of the building by a brick dividing wall extending three feet above the highest point of the roof, and in such dividing wall all openings, if any, shall be equipped with standard automatic or self-closing fire doors on each side of the wall.

Brick buildings with roof of ordinary construction may be so used if they are located three feet or more from every other building or structure upon the same lot or plot of ground. In buildings of ordinary, slow-burning or mill construction used exclusively for Class I purposes, four or less such vehicles may be housed providing that part of the building so occupied is separated from all other parts of such building by a brick wall extending three feet above the highest point of the roof and in which the openings, if any, are equipped with approved automatic or self-closing fire doors on each side thereof. If such building is more than one story high in lieu of extending hereinbefore required wall through upper stories and through the roof as described, the floor system immediately above space in which such vehicles are kept may be built of fireproof construction connecting with wall separating such space from other parts of the building and which is carried through the story so occupied by such vehicles.

Brick buildings with a roof of fireproof construction may be so used and may adjoin any other building or structure, but no openings shall connect the same with any building other than a building of Class I.

Buildings containing not to exceed one living apartment and in which four or less vehicles containing volatile inflammable liquid are housed, must have brick or masonry walls and not exceed two stories in height. The floor of the second story shall be of fireproof construction throughout or if of combustible material shall be protected on the underside for the entire area of such floor by two complete coverings of metal lath and fire-resisting plaster applied separately. There shall be two stairways from said apartment to the ground placed as far apart as practicable, one of such stairways may be an outside stairway. The interior stairway or stairways shall be enclosed on the first floor by partitions of four-inch tile or partitions of metal lath and plaster on metal studding in such a manner that exit by means of the stairway shall be direct to the outside of building, and there shall be no doorways or other openings from enclosure containing such stairway into the first story.

(g) Buildings or structures for the purpose of smoking meats or fish shall have brick walls and shall have a roof of fireproof construction. No combustible material shall be used in the erection of such building. Where smoke houses are built inside of another building, they shall be constructed entirely of metal or have brick walls with a fireproof roof or ceiling and no combustible material shall be used in their construction.

(h) Buildings in which machinery and equipment is installed for the purpose of dry cleaning shall stand at least three feet from any lot line and not nearer than three feet to the nearest point of approach of any other buildings or structure upon the same lot. Such buildings shall be of fireproof construction, shall not be over two stories in height and shall have no basement or attic. Walls shall be at least twelve inches thick. All window openings in outside walls shall be equipped with approved metal frames, metal sash and wired glass. All exterior and interior door openings shall be equipped with an approved three-ply laminated door covered with sheet metal or its equivalent in fire-resisting quality. There shall be

no floor openings except for one interior stairway and said stairway shall be enclosed upon the first floor in such a manner as to give direct exit from stair and stair hall to the outside without any doorway or other opening from stair or stair hall to first story of building. An additional outside metallic stairway or additional stairways at least three feet wide shall also be provided. The boiler shall be located in a separate building and so situated that the line of travel for gases between any opening in boiler room and the opening in the dry cleaning or dry room shall be not less than twenty feet. Such dry cleaning and dry room shall be provided with vent holes at the floor line not less than sixteen square inches in area, at least six feet apart.

(1) Buildings for the storage of more than two thousand (2000) feet of motion picture films, or buildings in which more than two thousand (2000) feet of motion picture films are stored shall be of ordinary, slow-burning, mill or fireproof construction and not more than two stories high, unless of fireproof construction. In all buildings in which motion picture films are stored all elevators and stairs shall be enclosed in all stories where such film storage occurs, and in all stories above such stories where motion picture films are stored. In buildings of ordinary construction such stair and elevator enclosure shall be of brick walls at least twelve (12) inches thick supported on the ground or upon fire-proofed structural steel. In fireproof buildings all elevators and stairs shall be enclosed with brick walls at least eight (8) inches thick, or with reinforced concrete or with fireproof tile at least four (4) inches thick.

Vaults for the storage of motion picture films in non-fireproof buildings shall be of brick or reinforced concrete at least twelve (12) inches thick. The floors and tops of such vaults shall be of brick or of concrete or of reinforced hollow tile at least twelve (12) inches thick, or of reinforced concrete at least eight (8) inches thick. In fireproof buildings vault walls shall be of fireproof tile or of brick or of concrete or of reinforced concrete. The floors and tops shall be of brick or of concrete at least twelve (12) inches thick, or of reinforced concrete at least eight (8) inches thick, or of fireproof tile or of reinforced hollow tile at least ten (10) inches thick. The thickness of vault walls shall be the same as herein specified for floors and tops where the same material is used for their construction, except that walls of fireproof tile shall be at least twelve (12) inches thick.

The vent flues for vaults shall be of the same construction as is required for smoke flues of the same area for such buildings. In fireproof buildings such vent flues may have walls at least four (4) inches thick of stone or gravel concrete reinforced with three-eighths ($\frac{3}{8}$) inch diameter round steel rods. Rods shall be set both vertically and horizontally, shall be spaced twelve (12) inches on centers where set horizontally and shall be spaced eighteen (18) inches on centers where set vertically. Or the walls may be four (4) inches thick of hollow clay tile set with the voids vertical and having all voids filled with stone or gravel concrete and with all joints filled with cement mortar and have metal bands at least one-fourth ($\frac{1}{4}$) inch thick by one (1) inch wide embedded within the horizontal joints on all sides of the flue at intervals of not less than four (4) feet in height, said bands being secured to metal plates four (4) inches square and one-fourth ($\frac{1}{4}$) inch thick placed flat against the outside face of the tile, or bands shall be secured to each other in a manner to effectually prevent walls of the flue from spreading when subjected to heat. Where two or more flues are built together the bands may extend from outside to out-

side of the group or be arranged in such a manner as to effectually prevent the spreading of the walls of any flue within the group. Where tile is used for flues the exterior walls of detached flues or the outside walls of a group of flues shall be covered with two coats of cement plaster on wire lath brought close to the intersecting walls, floors and ceiling. Above the roof level tile walls shall be encased with four (4) inches of brick laid in cement mortar. Vent flues for vaults which are located in the top story of a fireproof building may be constructed of No. 14 U. S. gauge metal from the vault connection to the termination of the flue, and all that portion of the flue which is within the building and that portion eighteen (18) inches above the roof shall have a coating of asbestos plaster at least two (2) inches thick covered with two coats of cement plaster on metal lath. Such other construction of vent flues will be permitted as will meet with the approval of a Board consisting of the Commissioner of Buildings and the Chief of Fire Prevention and Public Safety as being equal in character and fire-resisting qualities to the foregoing.

In buildings of fireproof construction rooms for examining and for repairing motion picture films shall be enclosed in partitions of fireproof or incombustible material at least four (4) inches thick.

In buildings of fireproof construction rooms used for receiving, distributing or the shipping of motion picture films shall be enclosed in partitions or walls of brick or concrete or fireproof tile at least eight (8) inches thick, or of reinforced concrete at least six (6) inches thick.

Such partitions and the enclosing walls of such rooms, except where same face upon a public street at least fifty (50) feet wide, shall have window openings in same equipped with approved metal frames and sash and glazed with wired glass, and all door openings shall be equipped with approved single automatic-closing fire doors.

In non-fireproof buildings in addition to all of the above requirements, the floors and ceilings of such rooms or compartments must be of fireproof construction as defined in this chapter.

248. Door Openings—Revolving Doors.)

(a) The aggregate width of door openings at or approximately at the street level in buildings of Class I shall be equal to the aggregate width of stairways, as specified in Section 650 of this chapter for buildings of Class I. Where locks are used on exit doors or on doors or gates leading to hallways or stairways which lead to exit doors they shall be so arranged that the door or gate may be opened from the inside without the use of a key. Where locks are used on automatic fire doors in stair shafts of buildings in which approved sprinkler systems are installed, said doors may contain just above the locking device a fire-resisting glass panel containing not less than 81 square inches nor more than 450 square inches of exposed fire-resisting glass. In every building of this class every door to an exit which is a means of egress for twenty or more persons shall open outward, and every door which is a means of exit from any floor above the first, shall open outwardly from the space or hallway in which the stairway from such upper floor is located. A door or doors when open shall not project over a public sidewalk or public space.

(b) Revolving doors shall not be installed in any door opening of any building unless the revolving wings of such revolving doors are so arranged that, by the application of a force slightly more than is necessary to revolve said doors and which one person of ordinary strength is capable of exerting, all the wings of said door fold flat on each other and in an outward direction, or unless the revolving wings of said

revolving doors are so arranged that they may be readily collapsed or removed by means of simple mechanical means to be approved by the Commissioner of Buildings, and leave sufficient opening for two or more persons to pass through with a minimum width of not less than twenty-two inches on each side of said collapsed doors.

Where revolving doors are used as exits they shall be credited as exits only to the extent of the clear space remaining when the doors are collapsed and all deficiency of required exits must be made up by additional doors.

249. Existing Buildings of Class I—Increasing Height of. In all cases where buildings of Class I of ordinary construction built prior to the passage of this ordinance, are to be increased in height above the height of fifty feet, or of mill or slow-burning construction above the height of ninety feet, the additional parts of such buildings shall be constructed as herein provided for buildings over fifty feet in height or over ninety feet in height, respectively, and said additional parts shall be made to conform in all respects to the requirements for buildings of this class more than fifty feet in height or more than ninety feet in height, respectively, before it shall be lawful to occupy them.

250. Fire Walls. (a) Buildings occupied by more than one person, firm or corporation, or for more than one business enterprise conducted by the same person, firm or corporation, in separate enclosures on any one floor, shall have a brick dividing wall for every fifty feet of street frontage, if of ordinary construction, or for every eighty feet of street frontage, if of slow-burning or mill construction, and such dividing walls shall extend from the front to the rear wall and such dividing walls and the doors therein shall be built in accordance with the provisions of Section 559 of this chapter.

(b) All of the partitions between the parts of such buildings occupied by different persons, firms or corporations, shall be built of incombustible material from the floor to the floor boards or roof boards next above such story or stories so occupied.

(c) Only metal framed windows glazed with one-quarter inch thick wire glass may be used in such partitions.

251. Dividing Walls—When Required. (a) Dividing walls will be required in buildings of Class I as follows:

(b) Every building of ordinary construction having a greater area than 9,000 square feet shall be divided into areas of 9,000 square feet or less by dividing walls; provided, however, that buildings of ordinary construction more than one story in height and having in addition to the requirements of this ordinance relating to buildings of ordinary construction with areas not greater than 9,000 square feet, a frontage on at least two public thoroughfares, and having all stairways and elevator shafts and other floor openings enclosed with brick masonry walls with all openings in same protected with approved automatic fire doors and all stair halls at street or ground level to open directly or through a fireproof tunnel to a street or public alley and equipped throughout on all floors and basement with an automatic sprinkler system meeting with the approval of the Chief of Fire Prevention and Public Safety may be built with an area of 12,000 square feet, and if of greater area shall be divided into areas of 12,000 square feet or less by dividing walls; every building of slow-burning or mill construction more than one story in height having greater area than 12,000 square feet, shall be divided into areas of 12,000 square feet or less by dividing walls; provided, however, that buildings of slow-burning or mill construction more than one story in height and having in addition to the requirements of this ordinance relating to buildings of slow-

burning and mill construction having areas not greater than 12,000 square feet, a frontage on at least two public thoroughfares, and having all stairways and elevator shafts and other floor openings enclosed with brick masonry walls with all openings in same protected with approved automatic fire doors and all stairhalls at street or ground level to open directly or through a fireproof tunnel to a street or public alley and equipped throughout on all floors and basement with an automatic sprinkler system meeting with the approval of the Chief of Fire Prevention and Public Safety may be built of an area of 16,000 square feet and if of greater area shall be divided into areas of 16,000 square feet or less by dividing walls.

Every fireproof building more than two stories in height and having greater area than 30,000 square feet, shall be divided into areas of 30,000 square feet or less by dividing walls.

(c) Where dividing walls are required in any of the above mentioned buildings, such building shall be subdivided by brick walls, built of the thickness given in the table for the thickness of enclosing walls and all doors or other openings in such walls shall have at each side of the same, iron doors, tin clad doors or shutters, as described in Section 559 of this chapter, and said buildings as subdivided shall be provided with stairs and fire escapes the same as hereinafter required; provided, however, that one-story buildings of ordinary mill or slow-burning construction and two-story buildings of fireproof construction of any size when used as one store, room or workshop and occupied by only one person, firm or corporation, may be erected without any dividing walls.

252. Display of Placard—Indicating Floor Strength. (a) It shall be the duty of the owner of every building of Class I now in existence or hereafter erected, or of his agent, or of the occupant, or person in possession, charge or control of same, to affix and display conspicuously on each floor of such building, a placard, stating the uniformly distributed load per square foot of floor surface, which may with safety be applied to that particular floor, as provided by this chapter, or if the strength of different parts of any floor varies, then there shall be such placards for each varying part of such floor. It shall be unlawful to load any such floors or any part thereof to a greater extent than the loads indicated upon such placards.

(b) It shall be the duty of the occupants of such buildings to maintain such placards during their occupation of the premises and of the owners of buildings, or their agents, to cause the same to be properly affixed with each change of occupation. It shall be the duty of the owner, agent or lessee of each such building, now in existence, as well as hereafter erected, to procure and submit evidence of the correctness of the figures on such placards to the Commissioner of Buildings. Whenever such evidence as to the correctness of the figures shall be satisfactory to the Commissioner of Buildings, he shall approve such placards. Such placards so approved by the Commissioner of Buildings shall then be affixed upon the respective floors of the different buildings. The calculations and loads shall be in accordance with the provisions of this chapter.

(c) It shall be the duty of the owner, agent or lessee to pay to the City Collector a fee amounting to five dollars for each ten thousand square feet of floor area or less, for more than ten thousand square feet of floor area and not to exceed fifty thousand square feet of floor area ten dollars, for each additional fifty thousand square feet of floor area in excess of the first fifty thousand square feet of floor area ten dollars additional, and for issuing new placards in place of lost placards, for ten thousand square

feet or less two dollars, and for issuing new placards in place of lost placards for more than ten thousand square feet, five dollars. For the purpose of determining the amount of the fee herein required to be paid, every part of a structure separated by dividing walls as required by Section 251 of this chapter shall be considered as a separate building.

253. Live Loads for Floors.) The floors of all buildings of Class I hereafter erected shall be designed and constructed in such a manner as to be capable of bearing, in addition to the weight of floor construction, partitions, permanent fixtures and mechanisms that may be set upon the same, a live load of one hundred pounds for every square foot of surface, and the strength of such building shall be increased above the capacity to carry such a live load of one hundred pounds per square foot of floor surface, when the uses to which such building, or part thereof, is to be applied, involve greater stress. The calculations and loads shall be in accordance with the provisions of this chapter. In every building of Class I now constructed and in use, whenever it shall be found by the Commissioner of Buildings that the floors of same, or any part or parts thereof, are not capable of bearing, in addition to the weight of the floor construction, partitions, permanent fixtures and mechanisms that may be upon the same, a live load of forty pounds for every square foot of surface, he shall condemn the same and order such floor or floors to be repaired or reconstructed within a reasonable time by the owner or occupant thereof, and shall proceed in the manner prescribed in sections 202 and 203 of The Chicago Code of 1911, and in such case it shall be unlawful for the owner or occupant to continue to use such building until the said floors shall be repaired or reconstructed in accordance herewith.

254. Elevator Buildings.) Elevator buildings intended solely for the receipt, storage and delivery of grain in bulk, shall be of fire-proof construction as described in this chapter.

ARTICLE V.

Class II.

255. Class II Defined.) (a) In Class II shall be included every building referred to in subdivisions Class IIa, Class IIb and Class IIc.

(b) In Class IIa shall be included every building used for office purposes, and also every building used for clubhouse purposes where sleeping accommodations are provided for less than twenty persons.

(c) In Class IIb shall be included every building used for hotel, club, lodging or rooming house purposes where such building has sleeping accommodations for twenty or more persons.

(d) In Class IIc shall be included every building used for a hospital where sleeping accommodations for more than ten persons are provided in such building, and every building used for a home, day nursery or asylum where any such building shall have accommodations for more than twenty persons or where more than ten bedridden or decrepit persons are housed, and every building used for a jail, house of correction or detention.

256. Must Comply with General and Special Provisions.) Every building of Class II shall comply with the general provisions of this chapter, and in addition to the general provisions shall comply with the following special provisions:

257. Requirements for Load Bearing Capacity of Floors in Buildings of Class II.) For all buildings of Class II the floors shall be designed and constructed in such a manner as to be capable of bearing in all their parts, in addition to the weight of floor

construction, partitions, permanent fixtures and mechanisms that may be set upon the same, a live load of fifty pounds per square foot of surface, and such floor bearing capacity shall be computed in accordance with the provisions of this chapter.

258. Windows and Mechanical Ventilation.) (a) In every building hereafter erected for or converted to the purposes of this class, courts shall be of the minimum widths and areas prescribed in Section 429 of this chapter, and vent shafts as defined in Section 419 of this chapter, shall be of the following minimum width and areas:

Height of Shaft.	Least Width in Feet.	Square Feet.
1 story	3	21
2 stories	3	22½
3 stories	3	27
4 stories	3	36
5 stories	5	48
6 stories	6	72
7 stories	8	96
8 or more stories	8	120

(b) In every building hereafter erected for or converted to the purposes of this class, every room used as a private sitting room or as a sleeping room, shall have at least one window which opens directly upon a street, alley, yard or court. The total glass area of such window or windows opening directly upon a street, alley, yard or court shall be not less than one-tenth of the floor area of such room. The top of at least one such window shall be at least seven feet above the floor and at least the upper half of such window shall be capable of being opened. No such window shall have a glass area of less than ten square feet unless it be a window in excess of the one-tenth of the floor area as required by this paragraph. Provided that sleeping cells in prisons, jails, police stations and houses of detention need not have each a window opening directly on a street, alley, yard or court if such cells are in a cell block which has windows with a glass area equal to one-fourth of the floor area of such block and arranged so that each window may be opened for one-half of its area, and provided further that such cell block and cells shall be equipped with a system of mechanical ventilation approved by the Commissioner of Health.

(c) In every building hereafter erected for or converted to the purposes of this class, every pantry, bath room and water closet and urinal compartment shall have at least one window which opens directly upon a street, alley, yard, court or vent shaft; the total glass area of such window or windows opening directly upon a street, alley, yard, court or vent shaft shall be not less than one-tenth of the floor area of such room or compartment. The top of at least one such window shall be at least seven feet above the floor and at least the upper half of such window shall be capable of being opened; and no such window shall have a glass area of less than six square feet or a glass width of less than one foot; provided, however, that such room or compartment, if located in the upper story of any such building, may be lighted and ventilated by means of a skylight having a glass area equal to one-tenth of the floor area of the room it serves and be equipped with an efficient ventilator or ventilators equal in effective area to one-twentieth of the floor area of such room; and provided further, that any such room or compartment in a building used for office, club, hospital or hotel purposes, in lieu of such window or windows, may be ventilated by an approved mechanical ventilation system which shall effect at least six complete changes of air per hour.

(d) In every building hereafter erected for or converted to office, hotel or club purposes, every room, except a room used as a bakery, which is below street grade and

which is frequented by the public or in which there are regularly employed five or more persons, shall be ventilated by an approved mechanical ventilating system which shall effect at least six complete changes of air per hour; provided that in case of store rooms below street grade having 1,500 cubic feet of space per person employed therein two changes of air per hour will be deemed sufficient. In buildings of this class every room, either above or below grade,

used as a bakery, shall comply with the provisions of the ordinances of the City of Chicago in respect to bakeries.

(e) In every building hereafter erected for or converted to the purposes of this class, every room not otherwise specifically provided for in this section shall, where practicable, have a window or windows, with a total glass area not less than one-tenth of the floor area of such room, opening directly onto a street, alley, yard or




Fig. 2.

WINDOWS.

Section 258b, 261, 276, 435, 462, 463, 558, 589.

- (A) Where measurement of glass is taken.
- (B) Top of window.
- (C) One-half of window.
- (D) Detail of sash showing where (A) is taken, under ordinary conditions.
- Area of glass would be $(A \times A)$.
- Total area would be summation of all $(A \times A)$.
- Windows to be constructed so that upper half (C) can be opened.
- (E) If E is less than 15 ft. wide, metal frames and wire glass to be used; and the glazed portion

- of frames to be set with fire resisting glass, as provided in ordinance. (Sec. 558).
- (F) If F is less than 30 ft., metal frames and wire glass to be used; and the glazed portion of frames to be set with fire resisting glass, as provided in ordinance. (Sec. 558).
- For exceptions where steel rolling shutters, etc., are used see ordinance (Sec. 558a).
- (G) Provision made for safety device in cleaning of windows. (Sec. 589).

court, and no such window shall have a width of less than one foot or a total glass area of less than ten square feet, unless such window is in excess of the ten per cent of floor area requirement; provided that, if it be impracticable to ventilate any such room by windows as aforesaid, such rooms shall be ventilated by an approved mechanical ventilating system which shall effect at least six complete changes of air per hour; the air supply being taken from the outer air at a point not less than ten feet above the street level.

(f) It shall be the duty of the owner, agent, architect, or party in possession or control of any building in which a mechanical system of ventilation shall have been installed under the requirements of this section, upon completion of such system, to notify the Commissioner of Health in writing at least twenty-four hours in advance of the making of a test of such system; and each such system or unit shall be tested for volumetric efficiency by the owner or his representative in the presence of the representative of the Commissioner of Health and such system shall not be considered as meeting the requirements of this section until it shall have been approved by the Commissioner of Health. Every such mechanical ventilating system shall at all times be kept in good repair and in operation so as to insure the required ventilation of all rooms and compartments planned to be ventilated thereby, during all hours of human occupancy.

Class IIA.

259. **Class IIA Defined.)** In Class IIA shall be included every building used for office purposes, and also every building used for club house purposes where sleeping accommodations are provided for less than twenty persons.

260. **Buildings—Construction of—Height of.)** (a) Buildings of Class IIA which are ninety feet or more in height shall be built entirely of fireproof construction.

(b) Buildings of Class IIA less than ninety feet and more than fifty feet in height shall be built either of slow-burning, mill or fireproof construction.

(c) Buildings of Class IIA not exceeding fifty feet in height may be built of ordinary construction.

Class IIB.

261. **Class IIB Defined.)** In Class IIB shall be included every building used for hotel, club, lodging or rooming house purposes where such building has sleeping accommodations for twenty or more persons.

262. **Buildings—Construction of—Height of.)** (a) Buildings of Class IIB more than five stories and basement high shall be of fireproof construction.

(b) Buildings of Class IIB more than three stories and basement high but not more than five stories and basement high shall be of slow-burning or fireproof construction. In case slow-burning construction be required the cellar and basement construction, including the floor construction of the first story above the cellar or basement, shall be of fireproof construction.

263. **Walls—Divisions and Partitions—Fire Stops.)** (a) In buildings hereafter erected used wholly, or in part for the purposes of Class IIB of ordinary, slow-burning or mill construction, there shall be for every eight rooms in any one story, dividing walls or partitions of incombustible material separating such eight rooms from the contiguous spaces.

(b) In all buildings hereafter erected to be used wholly or in part for the purposes of Class IIB, all elevators and stairs shall be enclosed in partitions of incombustible or fireproof material, and the partitions of all

corridors leading to such elevators and stairs shall be of fireproof or incombustible material. Such partitions shall be carried on self-supporting masonry or a framework of steel or iron. Where glass is used in said partitions, the same shall be wired glass set in metal frames but such glass shall not exceed sixty per centum of the superficial area of said partitions.

(c) In all non-fireproof buildings of Class IIB there shall be between joists a stop of brick, concrete or tile not less than four inches in thickness, extending the full height of joists and spaced not more than twenty-five feet apart, measured in the direction of the length of the joist.

264. **Sleeping Stalls in Rooms—When Allowed.)** Sleeping stalls shall not be constructed or used in any room in any building now existing or hereafter erected and devoted, in whole or in part, to the purposes of a lodging or rooming house unless such room has two or more windows which open directly upon a street, alley, yard or court and which windows have a total area equal to at least one-tenth of the floor area of such room, nor unless the semi-partitions forming such stalls are so constructed that there is a clear and unobstructed interval of at least thirty inches between the top of such semi-partitions and the ceiling of the room, nor unless each such stall shall open directly into an aisle or passageway leading directly to a stairway or stairway fire escape, the location of which is indicated by a red sign and at night by a red light also. Such sleeping stalls shall not be installed in any such room in such numbers that there shall be less than 400 cubic feet of air per person when all stalls are occupied to their full capacity. The semi-partitions forming such stalls hereafter constructed shall be of incombustible material.

(See Illustration Sec. 258b).

Class IIC.

265. **Class IIC Defined.)** In Class IIC shall be included every building used for a hospital where sleeping accommodations for more than ten persons are provided in such building and every building used for a home, day nursery or asylum where any such building shall have accommodations for more than twenty persons or where more than ten bedridden or decrepit persons are housed, and every building used for a jail, house of correction or detention.

266. **Buildings—Construction of—Height of.)** (a) All buildings of Class IIC not more than two stories and basement in height may be of ordinary, mill or slow-burning construction.

(b) All buildings of Class IIC more than two stories and basement in height shall be of fire-proof construction.

267. **Frontage Consents for Hospitals.)** It shall be unlawful for any person, firm or corporation to build, construct, maintain, conduct or manage in any block in which two-thirds of the buildings fronting on both sides of the street or streets on which the proposed hospital may front are devoted to exclusive residence purposes, any hospital unless the owners of a majority of the frontage in such block and the owners of a majority of the frontage on the opposite side or sides of the street or streets on which said building faces consent in writing to the building, constructing or maintaining, managing or conducting of any such hospital in said block. Such written consents of the majority of said property owners shall be filed with the Commissioner of Health before a permit shall be granted for the building or constructing, or a license be issued for the maintaining, conducting or managing of any such hospital.

268. **Coves in Rooms and Corridors of Hospitals.)** In every building hereafter

constructed for or converted to hospital purposes, in all corridors and rooms used by patients, all intersections of walls, floors and ceilings shall be formed with tangent coves.

269. Elevators in Hospitals.) Every building over three stories in height hereafter constructed for or converted to hospital purposes shall have at least one elevator, the floor dimensions of which shall be not less than seven feet by five feet, and said elevator shall be enclosed in a fireproof shaft with incombustible doors closing off each opening and shall comply with all the general provisions of this chapter.

270. Fire Escapes, Balconies, Platforms.) All buildings of Class IIc shall be equipped with stairway fire escapes not less than three feet in width which shall, in number, location and structural features, comply with the general provisions of this chapter relating to fire escapes. The balconies and platforms of such fire escapes shall be not less than three feet in width and may be made with a smooth surface of incombustible material laid flush with the floor and with a pitch of one-third inch to the foot.

ARTICLE VI.

Class III.

271. Class III Defined.) In Class III shall be included every building used as a private residence, also every building used for a hospital where sleeping accommodations for ten or less persons are provided in such building, and every building used for a home, day nursery or asylum where any such building shall have accommodations for twenty or less persons or where not more than ten bedridden or decrepit persons are housed, and also every building, structure or place with a ground area of less than five hundred square feet used as and for the purposes of a barn, stable or garage or for the housing or keeping of automobiles.

272. Must Comply With General and Special Provisions.) Every building of Class III shall comply with the provisions of this chapter, and, in addition to the general provisions, shall comply with the following special provisions:

273. Buildings—Construction of—Height of—Space Occupied on Lot.) (a) Every building of Class III which is ninety feet or more in height shall be built entirely of fireproof construction.

(b) Every building of Class III less than ninety feet and more than fifty feet in height shall be built entirely of slow-burning, mill or fireproof construction.

(c) Every building of Class III less than fifty feet in height may be built of ordinary construction.

(d) The amount of space occupied on any lot by Class III buildings shall comply with the requirements of Section 427 of this chapter.

(e) Buildings used for garage purposes only, having a ground area of four hundred (400) square feet or less, may be built with enclosing walls and roof of corrugated iron or galvanized sheet steel supported on a frame of steel construction.

274. Skylights—Construction of—Glass in.) (a) The skylight on the roof of every building of Class III erected within the fire limits shall have its sides, sashes and frames constructed of metal or of metal-clad wood on all exterior surfaces.

(b) Such skylights shall be covered by a strong wire netting with mesh not more than one and one-half inches square placed not less than six inches above the glass, supported on uprights of incombustible material, unless wired glass is used.

275. Allowance of Live Loads in Construction of Floors.) In every building of

Class III, the floors shall be designed and constructed in such manner as to be capable of bearing in all their parts, in addition to the weight of the floor construction, partitions, permanent fixtures and mechanisms that may be set upon the same, a live load of 40 pounds for every square foot of surface.

276. Habitable Rooms—Definition of—Requirements as to Size and Ventilation.)

(a) For the purposes of this chapter the term "habitable room" shall be held to include every room in every building of Classes III and VI, and every room in buildings of other classes if such rooms are used for the purposes of Classes III and VI, in which a family or the individual members thereof regularly sleep or eat or carry on their usual domestic or social vocations or avocations. Laundries, bath rooms, water closet compartments, serving and storage pantries, storage rooms and closets, boiler and machinery rooms, cellars, corridors, and similar spaces used neither frequently nor during extended periods, shall not be deemed as coming within the scope of this term.

(b) In every building hereafter erected for or converted to the purposes of Class III, every habitable room shall have a window or windows with a total glass area equal to at least one-tenth of its floor area, opening onto a street, alley, or yard, as defined in Section 419 of this chapter; provided, that there shall be a space of at least three feet between the building and the lot line on one side, and a space of at least one foot between the building and the lot line on the other side. None of such required windows shall have a glass area of less than ten square feet; and each such window shall have its top not less than seven feet above the floor and shall be so constructed that at least its upper half may be opened its full width. No such habitable room shall have a floor area of less than eighty square feet, nor a clear height from floor to ceiling of less than eight feet and six inches; provided that attic rooms need not be eight feet six inches high for more than one-half of their area, and that such attic rooms shall have total cubic contents of not less than seven hundred and fifty cubic feet each.

(c) No living room shall be partitioned off or constructed in any existing building or portion thereof, until plans of such building and room have been filed with, and a permit for such partitioning or constructing obtained from the Commissioner of Buildings and the Commissioner of Health; and every room so partitioned off or constructed shall comply with all the requirements for habitable rooms as contained in this section.

(See Illustration Sec. 258b).

277. Alcoves.) Every alcove and alcove room shall comply with the requirements of Section 433 of this chapter.

278. Pantries, Bath Rooms, Water Closet and Urinal Compartments—Requirements in Relation Thereto.) In every building hereafter erected for or converted to the purposes of Class III, every pantry, bath room, water closet or urinal compartment shall have at least one window with a glass area of at least six square feet and a minimum width of at least one foot opening upon a street, alley, or yard as defined in Section 419 of this chapter, or upon a vent shaft not less in area than said window; and no habitable room shall open into or connect with a vent shaft thus used.

279. Bay Windows and Light Shafts—Materials For.) Bay or oriel windows may be built of combustible material on front or rear elevations of buildings of Class III of two stories or less in height, within the fire limits, provided such bay and oriel windows shall not have a greater width than twelve feet at the wall line of the building, and, provided, that the outside walls, roofs

and soffits of such bay or oriel windows, when so constructed, shall be covered with sheet metal or other incombustible material. Light shafts wholly within the walls of a two-story building of Class III may be built of combustible material covered with sheet metal or other incombustible material. In all other cases, bay and oriel windows and light shafts and their supports shall be constructed entirely of incombustible material.

280. Walls—Brick Walls Upon Wooden Sills—Level of Sills Allowed.) Every building of Class III not exceeding one story or twenty feet in height from top of sills to the highest point of the roof, and with the side walls not exceeding fourteen feet in height, and with floor area not exceeding twelve hundred square feet, may have brick walls not less than eight inches in thickness erected upon wooden sills, the sills supported on iron, masonry, or concrete supports extending four feet below the surface of the ground, provided that the portion of the supports above the ground may consist of cypress or cedar posts. The foundations under such supports shall be of concrete, stone or brick, each covering not less than five square feet area and not more than eight feet apart, to support with safety the weight that may rest upon them; sills shall be placed not higher than four feet above the established grade of the street upon which the lot fronts and upon which lot the building is erected, where grades are established, and not exceeding seven feet above the ground where grades are not established. Every building more than one story and less than two stories high, having a gable or hip roof with a rise of not more than thirty degrees, may have eight-inch walls of solid brick or stone masonry, provided the side walls do not exceed fourteen feet in height measured from the first floor joist, and provided such building has a floor area not exceeding 1,200 feet and is not over 22 feet in width.

281. Stairways in Buildings of Class III Hereafter Erected Three Stories or More in Height.) (a) In every building of Class III hereafter erected, and three stories or more in height, there shall be either two stairways from the first to the top story or one such stairway and a stairway fire escape.

(b) In every building of Class III now in existence, and three stories or more in height with a floor area of 1,000 square feet above the second floor, which is not equipped with two stairways or with one stairway and a stairway fire escape, safe and adequate means of egress from all floors shall be provided by the erection of additional stairways or stairway fire escapes, or such other means as in the judgment of the Commissioner of Buildings are required for the safety of the occupants of such building or the public.

(c) In every building of Class III now in existence or hereafter erected used for hospital, home, day nursery or asylum purposes there shall be provided at least two stairways located as far apart as practicable and extending from the top story to the ground. A separate door exit shall be provided for each stairway to the outside of the building.

ARTICLE VII.

Class IV.

282. Class IV Defined.) (a) In Class IV shall be included every building referred to in subdivisions Class IVa, Class IVb, Class IVc and Class IVd, as follows:

(b) In Class IVa shall be included every building used as a church or place of worship.

(c) In Class IVb shall be included every building having a parish hall, lodge hall, dance hall, banquet hall, skating rink, as-

sembly hall, halls used for the purpose of exposition and exhibition, and buildings having a hall for the purpose of instruction, other than schools, included in Class VIII, and also every existing building having a hall used for theatrical purposes at the time of the passage of this ordinance, except such buildings as are included in Classes IVa, IVc, IVd, and V.

(d) Class IVc shall include every building hereafter erected used for moving picture and vaudeville shows and similar entertainments, where an admission fee is charged and regular performances are given, and where the seating capacity does not exceed three hundred; provided, that every building of Class IVc existing at the time of the passage of this ordinance shall comply with the provisions of Class IVb.

(e) In Class IVd shall be included every grandstand and every baseball, athletic and amusement park.

283. Must Comply With General and Special Provisions.) Every building or structure of Class IV shall comply with the general provisions of this chapter and shall, in addition, comply with the following special provisions:

284. Must Comply With All Ordinances.) It shall be unlawful for any person, firm or corporation to construct or alter any theatre except in conformity with the ordinances of the City of Chicago relative thereto, or to operate any theatre that does not conform thereto.

285. City Officials Empowered to Enter.) The Commissioner of Buildings, Commissioner of Health, City Electrician, Fire Marshal, Superintendent of Police, and their respective assistants, shall have the right to enter any building used in whole or in part for the purposes of Class IV at any reasonable time, and at any time when occupied by the public, in order to examine such building, and it shall be unlawful for any person to interfere with them in the performance of their duties.

286. City Officials Empowered to Close.) The Commissioner of Buildings, Commissioner of Health, Fire Marshal, City Electrician, or Superintendent of Police, or any one of them, shall have the power, and it shall be their joint and several duty, to order any building used wholly or in part for the purposes of Class IV, to be closed, where it is discovered that there is any violation of any of the provisions of this chapter, and kept closed until the same are complied with.

287. Theaters in Frame Buildings Prohibited.) On and after June 1, 1911, no frame building or part thereof shall be used as a moving picture, vaudeville or other theatre.

288. Buildings — Height — Construction — When Used in Part as Class IV.) Every building higher than sixty feet, used in whole or in part for the purposes of Class IV or connected with or made part of any building so used, shall be entirely of fireproof construction. Every such building less than sixty feet in height shall be made of fireproof, slow-burning or mill construction, except as provided in this chapter.

CLASS IVA

289. Class IVA Defined.) In Class IVA shall be included every building used as a church or place of worship.

290. Frontage—Seating Less Than Eight Hundred.) Every building of Class IVA hereafter erected containing an aggregate capacity of 800 persons or less, shall have for the auditorium a frontage upon two open spaces, of which at least one shall be a street, and the other, if not a street, shall be a public or private alley, not less than

ten feet wide, opening directly on a public street or alley.

291. Frontage—Seating Over Eight Hundred.) Every building of Class IVa hereafter erected containing an aggregate seating capacity greater than eight hundred persons, shall have a frontage upon three open spaces of which at least one shall be a public street and the others, if not streets, shall be public or private alleys of a width of not less than ten feet each, opening directly on a public street or alley, with at least one exit into each open space.

292. Construction of.) (a) Every building of Class IVa, which has a seating capacity of less than 600 may be built of ordinary construction. Every building of Class IVa having a seating capacity of more than 600 and less than 1,800 shall be built of slow-burning, mill or fireproof construction.

(b) Every building of Class IVa having an aggregate seating capacity greater than 1,800 persons shall be built of fireproof construction.

293. Limitations of Floor Level in Class IVa—Height Above Sidewalk.) (a) The limitations of floor levels in buildings hereafter erected, occupied either wholly or in part for the purposes of Class IVa, shall be as follows:

(b) No auditorium of a greater seating capacity than 1,000, shall have the highest part of its main floor at a greater distance than 10 feet above the adjacent sidewalk grade. No room or rooms having a greater seating capacity than five hundred shall be at a greater distance above the sidewalk grade than twenty feet. No room or rooms used for the purposes of Class IVa having a greater seating capacity than two hundred shall be at a higher level above the sidewalk grade than thirty feet; provided, however, that in the case of a building used either wholly or in part for the purposes of Class IVa, and built of fireproof construction, a room or rooms to be used for the purposes of Class IVa and of an aggregate seating capacity of less than five hundred may be located in any story thereof, but in such case, there shall be at least two separate and distinct flights of stairs from the floor or floors in which such room or rooms are located, to the ground, each of which stairs shall be not less than 4 feet wide in the clear and shall be equipped with emergency exits and not less than one stairway fire escape.

294. Allowance for Live Loads in Construction of Floors of Buildings of Class IVa—Stairways—Entrances and Exits. Width of.) Every floor in buildings of Class IVa shall be designed and constructed in such a manner as to be capable of bearing in all its parts, in addition to the weight of floor construction, partitions, and permanent fixtures that may be set upon same, a live load of 100 pounds for every square foot of surface on such floor. The width of stairways in buildings of this class shall be twenty inches for every one hundred of the aggregate seating capacity, and for fractional parts of one hundred seating capacity, a proportionate part of twenty inches shall be added to the width of such stairway, but no stairway in such building shall be less than four feet wide in the clear, except as hereinafter provided, and provided further, that in any such building having a gallery, the seating capacity of which does not exceed two hundred and fifty persons, two separate and distinct stairways, each not less than three feet wide, shall be permitted.

295. Galleries—Exit and Entrance.) Distinct and separate exits shall be provided for each gallery. A common place of exit and entrance may serve for the main floor of the auditorium and the gallery or gal-

leries, provided its capacity be equal to the aggregate capacity of all aisles or corridors leading from the main floor and such gallery or galleries to such place of exit or entrance. Not more than two galleries, placed one above the other, shall be permitted in any building of Class IVa.

296. Width of Aisles—Steps in Aisles—Class IVa.) Aisles in buildings of Class IVa shall, in the aggregate, be eighteen inches in width for each 100 of the seating capacity of the auditorium, and for fractional parts of 100, a proportionate part of 18 inches shall be added, but no aisle shall be less than two feet six inches in width in its narrowest part. Steps shall be permitted in aisles only as extending from bank to bank of seats, and whenever the rise from bank the bank of seats is less than 5 inches, the floor of the aisles shall be made on an inclined plane; and where steps occur in outside aisles or corridors, they shall not be isolated, but shall be grouped together, and there shall be a light so placed as to illuminate such steps in such outside aisles or corridors.

297. Corridors, Passageways, Hallways and Doors—Width of.) The width of corridors, passageways, hallways and doors, adjacent to, connected with, or a part of the auditorium, shall be computed in the same manner as is herein provided for stairways and aisles, excepting, however, that no such corridor, passageway or hallway shall be less than four feet in width, and no such doorway shall be less than three feet in width.

298. Seats, Number of, in Rows.) There shall not be more than fourteen seats in any one row between aisles. Rows of seats shall not be less than two feet eight inches from back to back, and no bank of seats shall be of greater rise than twenty inches.

299. Emergency Exits—All Doors to Open Outward.) (a) Emergency exits and outside stairways shall be provided for every building of Class IVa, which has a larger seating capacity than 800. Such emergency exits shall be one-half the aggregate width of the main exits, but no such emergency exits shall be less than three feet in width. Provided, that such stairways may be built inside the walls of the building in a corridor or passageway not less than seven feet wide and enclosed by a fireproof partition not less than four inches thick. Such stairway shall be of fireproof construction. All emergency exits and stairways therefrom shall be kept free from obstructions of any kind including snow and ice.

(b) All doors affording egress, directly or indirectly from the auditorium to a street or alley, shall open outward. Exit doors shall not be obscured by draperies and shall not be locked or fastened in any manner during the time that the building is occupied, and shall be so constructed and maintained that they may be easily opened from within.

300. Buildings in Which Seats are Not Fixed—Seating Capacity.) In computing the seating capacity of any room or building used for the purposes of this class in which the seats are not fixed, an allowance of six square feet of floor area shall be made for each person, and all space between the walls or partitions of such room or building shall be measured in this computation. Provided, that in buildings of Class IVa standing at least seven feet from any other building and not having more than two stories and each floor having its own separate exits, the seating capacity of such floor shall be estimated alone as determining the kind of construction under this article.

301. Lighting Service Requirement—Class IVa.) Gas or electricity or both may be used for illuminating purposes in buildings

of Class IVa. Provisions shall be made to properly light every portion of a building of Class IVa and every outlet therefrom leading to the outside of the building, and all open courts, passageways and emergency exits. Lights in vestibules, halls, corridors, passageways, stairways, and other means of egress from the building and premises shall be on an independent system or circuit or service and shall be controlled separately and exclusively by a switch or a shutoff located near the main entrance. In rooms, halls and auditoriums used for the purpose of Class IVa provisions shall be made to furnish a light above, if possible, otherwise closely adjoining every opening to an exit or emergency exit from the room, hall or auditorium. Where the capacity of the room, hall or auditorium is 400 or less provisions shall be made to supply such light with either gas or electricity. Where the capacity of the room, hall or auditorium is greater than 400 provisions shall be made to supply such light by gas only.

Class IVb.

302. Class IVb Defined.) In Class IVb shall be included every building having a parish hall, lodge hall, dance hall, banquet hall, skating rink, assembly hall, halls used for the purpose of exposition and exhibition, and buildings having a hall for the purpose of instruction, other than schools, included in Class VIII, and also every existing building having a hall used for theatrical purposes at the time of the passage of this ordinance, except such buildings as are included in Classes IVa, IVc, IVd, and V.

303. Frontage—Seating Less Than Eight Hundred—Seating More Than Eight Hundred.) (a) Every building of Class IVb, containing a hall or halls of an aggregate seating capacity of 800 persons or less, shall have a frontage upon two public spaces, of which at least one shall be a street, and the other, if not a street, shall be a public or private alley, not less than ten feet wide, opening directly on a public street or alley.

(b) Buildings of Class IVb, containing halls or rooms, used for the purpose of Class IVb, of greater aggregate seating capacity than 800, shall have a frontage upon three open spaces, of which at least one shall be a public street, while the other two, if not streets, shall be public or private alleys, of a width of not less than ten feet, each opening directly on a public street or alley; provided that a fireproof passageway at grade level, and not less than seven feet in width may be used in place of one such alley, if such passageway connects with a public thoroughfare.

304. Auxiliary Buildings—Height and Construction of—Communicating Doors.) (a) Every building hereafter erected and connected with or made part of any building used in whole or in part for the purposes of Class IVb, shall, if sixty or less feet in height, be of fireproof, mill or slow-burning construction, except as otherwise provided in this chapter, and, if more than sixty feet in height, of fireproof construction.

(b) No existing building, other than of fireproof construction, shall be connected to any building of Class IVb now existing or hereafter constructed, unless there is, between such buildings, a fire wall constructed as required by Section 506 of this chapter and extending from the ground to and through the roof.

(c) In all such cases where both buildings are not of fireproof construction, each opening in the intervening walls shall be equipped with automatic double fire-doors as required by Section 559 of this chapter.

305. Existing Buildings—Used for Class IVb and for Other Purposes.) No part of

an existing building, other than of fireproof construction shall be used for the purposes of Class IVb unless such part is separated from all portions of the same building used for other purposes by a fire wall constructed as required by Section 506 of this chapter and extending from the ground to the roof and unless all openings in such fire wall are equipped with automatic double fire doors as required by Section 559 of this chapter; in which case such other portions may be constructed in the manner permitted for separate buildings of such class.

306. Construction—Depending on Capacity.) Every building used for the purpose of Class IVb, hereafter erected, containing a hall or room of an aggregate seating capacity of not more than 1,500 persons, except as hereinafter provided, shall be built of mill, slow-burning or fireproof construction provided, that every building hereafter erected used in whole or in part for the purpose of Class IVb containing a hall or room of an aggregate seating capacity of not more than 300 persons, where such building does not exceed two stories and basement in height and the floor level of the hall or room is not more than eight feet above the grade of the street on which such building fronts, shall be built of ordinary, mill, slow-burning or fireproof construction. If a hall or room or halls or rooms have a total seating capacity of more than 1,500 persons, such building shall be built of fireproof construction; provided, that buildings mainly used for exposition or exhibition purposes, and not used for theatrical purposes, and not exceeding two stories in height which have for public use only a main floor and one gallery and which have their walls and structural members of incombustible material and which comply with the provisions of this ordinance as to stairways, exits and fire escapes, may have their temporary seats, boxes, show cases, platforms, or booths, constructed of combustible material; provided, however, that any and all draperies, buntings, or other inflammable decorations shall be treated with a fire-retarding solution, subject to the approval of the Chief of Fire Prevention and Public Safety.

307. Buildings in Which Seats Are Not Fixed—Seating Capacity.) In computing the seating capacity of any room or building used for the purposes of this Class, in which the seats are not fixed, an allowance of six square feet of floor area shall be made for each person, and all space between the walls or partitions of such room or building shall be measured in this computation. Provided, that in buildings of Class IVb standing at least seven feet from any other building and not having more than two stories and each floor having its own separate exits, the seating capacity of each floor shall be estimated alone as determining the kind of construction under this article.

308. Limitations of Floor Levels—Height Above Sidewalks—Skating Rinks.) (a) The following limitations of floor levels in buildings hereafter erected, occupied either wholly or in part for the purposes of Class IVb, other than skating rinks, shall be as follows: No auditorium of a greater seating capacity than one thousand shall have the highest part of its main floor at a greater distance than fourteen feet above the adjacent sidewalk grade. No room or rooms having a greater seating capacity than five hundred shall be at a greater distance above the sidewalk grade than twenty feet. No room or rooms used for the purposes of Class IVb having a greater seating capacity than two hundred shall be at a higher level above the sidewalk grade than thirty feet; provided, however, that in the case of a building used either wholly or in part for the purposes of Class IVb, and built of fireproof construction, a room or rooms to be used for the

purposes of Class IVb and of an aggregate seating capacity of less than five hundred may be located in any story thereof, but in such case, there shall be at least two separate and distinct flights of stairs from the floor or floors in which such room or rooms are located, to the ground, each of which stairs shall be not less than four feet wide in the clear and such floor or floors shall be equipped with emergency exits and have not less than one stairway fire escape.

(b) In buildings of fireproof construction hereafter erected, banquet halls or ball rooms having a seating capacity of not more than 900 may be located on any floor. Such banquet halls or ball rooms shall have access to at least two interior stairways and not less than one stairway fire escape, the combined width of which shall be equal to at least 18 inches for each one hundred persons for whom accommodations are provided in said banquet hall or ball room.

(c) No room or hall used for the purposes of a skating rink shall be constructed, operated or maintained with its main floor level more than two feet above the inside sidewalk grade of the street upon which such building containing same fronts, or more than one foot above the ground level in front of such building when it does not face upon a street, or more than one foot below the inside sidewalk grade of the street upon which such building fronts, or more than one foot below the ground level in front of such building when it does not face upon a street.

309. Allowance for Loads in Construction of Floors.) All floors of all buildings of Class IVb shall be designed and constructed in such a manner as to be capable of bearing in all their parts, in addition to the weight of floor construction, partitions, permanent fixtures and mechanisms that may be set upon the same, a live load of one hundred pounds for every square foot of surface in such floor, in accordance with the general provisions of this chapter.

310. Stairways—Entrances and Exits—Width of.) The width of stairways in buildings used wholly or in part for the purposes of Class IVb, shall be 18 inches for every 100 persons of the aggregate seating capacity of all rooms used for the purposes of Class IVb in such buildings; but no stairway in such building shall be less than four feet wide in the clear; provided, that in any such building having a room or rooms, balcony or gallery, used for the purposes of Class IVb, the aggregate seating capacity of which does not exceed 250 persons, two separate and distinct stairways, each three feet wide, shall be permitted, but no such building hereafter erected shall have less than two interior stairways of the width required by this ordinance, and located as far apart as practicable. Every hall or room used for the purposes of Class IVb in a building hereafter erected, * * * shall have access to not less than two stairways. Every stairway shall have handrails on each side thereof; stairways which are over seven feet wide shall have double intermediate handrails with end newel posts at least five and a half feet high; no stairway shall ascend a greater height than 13 feet 6 inches without a level landing, which landing shall be not less than four feet wide measured in the direction of the run of the stairs. Every stairway leading to a box or boxes shall be independent of all other stairs or seats; and such stairway shall not be less than 2 feet 6 inches wide in the clear when such box or boxes seat not to exceed thirty people, and an additional width of one inch shall be added to such stairway for each additional five persons for whom seating capacity is provided.

311. Balconies and Galleries—Designation of.) Where there are balconies or galleries, the first balcony or gallery shall be design-

nated "balcony" and the second and third balconies or galleries shall be designated respectively "gallery" and "second gallery."

312. Balconies and Galleries—Exit and Entrance.) Distinct and separate places of exit and entrance shall be provided for each gallery. A common place of exit and entrance may serve for the main floor of the auditorium and the balcony, provided its capacity be equal to the aggregate required capacity of all aisles or corridors leading from the main floor and such balcony to such place of exit and entrance.

313. Aisles—Steps in Aisles—Passageways—Cross Aisles Leading to Emergency Exits.)

(a) Aisles in rooms used for the purposes of Class IVb shall have in the aggregate a width of 18 inches for each 100 of the seating capacity of such room, and for fractional parts of 100 a proportionate part of 18 inches shall be added; but no aisle shall be less than two feet six inches in width.

(b) Steps shall be permitted in aisles only as extending from bank to bank of seats, and whenever the rise from bank to bank of seats is less than five inches the floor of the aisles shall be made as an inclined plane, and where steps occur in outside aisles or corridors, they shall not be isolated, but shall be grouped together, and there shall be a light so placed as to illuminate such steps in such outside aisles or corridors.

314. Corridors, Passageways, Hallways and Doors—Width of.) The width of corridors, passageways, hallways and doors adjacent to, connected with or a part of such rooms, shall be computed in the same manner as is herein provided for stairways and aisles, excepting, however, that no such corridor, passageway or hallway shall be less than four feet in width, and no such door shall be less than three feet in width.

315. Seats—Number in Rows.) There shall be not more than fourteen seats in any one row between aisles, and in a room or rooms used for the purposes of Class IVb, of a seating capacity greater than 400 persons, there shall be an aisle on each side of any bank of seats, where there are over seven seats in a row. Rows of seats shall not be less than thirty-two inches from back to back and no bank of seats shall be of a greater rise than twenty inches.

316. Emergency Exits.) (a) Emergency exits and stairways shall be provided outside of any and all rooms used for the purposes of Class IVb which have a seating capacity larger than eight hundred, and such emergency exits shall have a width equal to one-half of the width provided for the main exits and such emergency exits shall lead directly to a public thoroughfare. Provided, however, that any room or rooms used for the purposes of Class IVb in any building hereafter erected, having a seating capacity of more than 400, shall have emergency exits outside of the walls of such building equal in width to one-half of the exits required for the main exits, and such emergency exits shall lead directly to a public thoroughfare. Doors leading to emergency exits shall not be less than three feet wide. Stairs shall be not less than four feet wide. Such emergency exits and stairways may be built inside the walls of such building of a width not less than four feet, provided that they are enclosed by a fireproof partition not less than 4 inches thick; and further provided, that the stairs themselves are constructed of incombustible material. Emergency stairways may descend into open spaces or passageways, provided they do not obstruct more than one-half of the width of such open spaces or passageways.

(b) Every stairway fire escape shall be located and constructed in accordance with the requirements of Sections 653, 654 and 657, but in no case shall any room used for

the purposes of Class IVb located above the third story of any building have less than one stairway fire escape.

317. Doors to Open Outward.) All doors affording access directly or indirectly to the street, alley or corridor from any room used for the purposes of Class IVb shall open outward.

318. Walls Between Auditorium and Stage.) There shall be a solid brick wall of the same thickness as required for outside walls between the auditorium and stage in buildings hereafter erected for or converted to the use of Class IVb and used either wholly or in part for that purpose; and in existing non-fireproof buildings such wall must extend to a height of three (3) feet above the roof. Provided, however, that in existing buildings any room used for the purposes of Class IVb at the date of the passage of this ordinance having a greater seating capacity than four hundred (400) shall have a proscenium wall built of masonry or incombustible material.

319. Curtain Shall Be of Iron, Steel or Asbestos—Inspection of—Fee.) The main curtain opening in any such room shall have a wrought iron or steel or three-ply asbestos curtain with a wire mesh imbedded therein, which shall be inspected by the Building Department semi-annually, for which inspection a charge of five dollars shall be made, and all other openings in the proscenium wall shall have self-closing iron doors.

320. Structures Over Ceiling—Construction.) If any structure intended to be occupied by people is built over the ceiling of any room, used wholly or in part for the purposes of Class IVb, the girders or trusses supporting the same shall be of steel protected with fireproofing as required for interior columns in Section 611.

321. Standpipe and Hose on Stage.) In every room used for the purpose of Class IVb and having a seating capacity of 250 or more, and where scenery is used, a standpipe with hose connection and hose shall be installed on each side of the stage under the direction of the Chief of Fire Prevention and Public Safety.

322. Vents or Flue Pipes.) (a) One or more vents of flue pipes of metal construction or other incombustible material approved by the Commissioner of Buildings shall be built over the stage, and shall extend not less than ten feet above the highest point of the roof, and shall be equivalent in area to one-twentieth of the area of the stage.

(b) In buildings where additional stories are built above the stage, such vents or flue pipes may be carried out near the top of the stage walls, and shall be continued and run up on the exterior of the building to a point five feet above the highest point of the additional stories.

(c) All such flues or vents shall be provided with metal dampers which shall be controlled or operated by a small tarred hempen cord and also by two electric switches, one at the electrician's station on the stage, which station shall be fireproof, and the other at the stage fireman's station on the opposite side of the stage; the arrangement of said cord and said electric switches shall be such that the cord will operate as a fusible link between the electric control and the damper and will release said damper, should the switches, or either of them, fail to operate. Such stations shall be located in such places on the stage as may be determined by the Fire Marshal, subject to the provisions of this paragraph, and each switch shall have a sign with plain directions as to the operation of the same printed thereon.

323. Fuse Boxes.) Every fuse box shall be surrounded by two thicknesses of fireproof material with an air space between, and no fuse shall be exposed to the air between the switchboards; all electrical equipment in such rooms shall be installed and maintained to the satisfaction and approval of the City Electrician.

324. Capacity—Certification for License.) (a) The Commissioner of Buildings shall determine the number of persons which every room used for the purposes of Class IVb may accommodate according to the provisions of this chapter, and shall certify the same to the City Clerk.

(b) No amusement license shall be issued for any room used for the purposes of Class IVb until the Commissioner of Buildings shall first have certified, in writing, that such room complies with the provisions of this chapter in every respect.

325. Lighting Service Requirement—Class IVb.) Gas or electricity or both may be used for illuminating purposes in buildings of Class IVb but the use of gas is prohibited in that part of the building known as the stage side of the proscenium wall. Provisions shall be made to properly light every portion of a building of Class IVb and every outlet therefrom leading to the outside of the building, and all open courts, passageways and emergency exits. Lights in vestibules, halls, corridors, passageways, stairways and other means of egress from the building and premises shall be on an independent system or circuit or service, and shall be controlled separately and exclusively by a switch or a shutoff located near the main entrance. In rooms, halls and auditoriums used for the purposes of Class IVb provisions shall be made to furnish a light above, if possible, otherwise closely adjoining every opening to an exit or emergency exit from the room, hall or auditorium. Where the capacity of the room, hall or auditorium is 400 or less provisions shall be made to supply such light with either gas or electricity. Where the capacity of the room, hall or auditorium is greater than 400 provisions shall be made to supply such light by gas only.

326. Scenery—Definition—Movable Scenery.) (a) "Scenery" as used in this chapter shall include all scenery, drop curtains and wings which are constructed or made of cloth, canvas or combustible material, whether stationary or movable.

"Movable scenery" shall include all scenery, drop curtains, borders and wings which are made movable for the purpose of changing scenery and substituting another set during or between the various stage acts.

327. Scenery to be Non-Inflammable.) All scenery or stage paraphernalia of any sort used upon the stage of any room used for the purpose of Class IVb shall, previous to such use, be treated with a fireproof solution and shall be tested and approved by the Chief of Fire Prevention and Public Safety.

328. Amount of Scenery Allowed—Sprinkler System.) Two sets of house scenery and three drops, exclusive of asbestos fire curtain and picture screen shall be allowed in existing rooms used for theatrical purposes in buildings of Class IVb where the same are on the first floor level, or in a building of fireproof construction or which conformed with the requirements of fireproof buildings at the time same was erected, and the same shall also be allowed in such existing rooms used for theatrical purposes above the first floor level when the seating capacity of such room does not exceed 300. Such scenery shall be known and designated upon the licenses issued by the city as "Permanent House Scenery," and the use and moving of such scenery shall not be construed as placing said building, hall, room

or theater within the provisions of the ordinance relating to Class V buildings.

A set of house scenery as contemplated by this section is hereby defined to mean sufficient scenery to make one stage setting, such scenery being in continuous use in such house; provided, however, that the lowering of a drop shall not constitute a new stage setting.

No other scenery except as above enumerated shall be permitted on, above or underneath the stage.

Every existing Class IVb theatre affected by this section shall be equipped with an approved sprinkler system and also with stand-pipe and hose subject to the approval of the Chief of Fire Prevention and Public Safety.

No existing Class IVb theatre affected by this section shall increase its seating capacity after the passage of this ordinance.

No scenery or stage paraphernalia of combustible materials shall be used on the stage of any room or theatre used for the purposes of Class IVb, unless such scenery and paraphernalia shall have been treated with a paint or chemical solution which shall make it non-inflammable, and which treated scenery or stage paraphernalia, or both, shall be tested and approved by the Chief of Fire Prevention and Public Safety.

329. Dressing Room Partitions.) Partitions forming dressing rooms, except where already built, shall be constructed of incombustible material, and such dressing rooms shall be properly ventilated.

CLASS IVc.

330. Class IVc Defined—Moving Picture and Vaudeville Shows—Seating Capacity.)

Class IVc shall include every building hereafter erected used for moving picture or vaudeville shows and similar entertainments, where an admission fee is charged and regular performances are given, and where the seating capacity does not exceed three hundred, provided that every building of Class IVc existing at the time the passage of the ordinance known as The Chicago Code of 1911 shall comply with the provisions of Class IVb. All buildings hereafter erected for moving picture and vaudeville shows and similar entertainments, where an admission fee is charged and regular performances are given, with a seating capacity of over three hundred, and for the exhibition of moving pictures only, where the seating capacity is more than one thousand, shall be built to conform with the requirements for buildings of Class V hereafter erected as contained in this chapter. Buildings for the exhibition of moving pictures only and with a seating capacity of over three hundred, but not to exceed one thousand, shall also be built to conform with the requirements for buildings of Class V hereafter erected, in all their structural requirements and equipment except in so far as such requirements and equipment are modified in Sections 331 and 332 hereof.

331. Frontage of Class IVc—Frontage, Open Spaces and Fireproof Passageways of Moving Picture Theatres Containing a Seating Capacity of more Than Three Hundred.) Every room used for the purposes of Class IVc shall have a frontage upon at least two public thoroughfares, of which at least one shall be a street, and the other a street or a public or private alley not less than ten feet wide and opening directly on a public street or alley.

Buildings for the exhibition of moving pictures only, with a seating capacity of over three hundred but not to exceed one thousand, shall be located so that they adjoin at least two public thoroughfares, one of which shall be a public street and the other may be a public alley not less than ten feet

provided, the audience room of such building shall have either a public thoroughfare or an open space unobstructed from the ground to the sky on each side thereof. Such open space, when the audience room has a capacity not to exceed six hundred seats, shall be five feet wide, and six inches shall be added to the width of same for every additional one hundred seats in said audience room up to the maximum of one thousand seats. In all cases where there is a public alley in the rear of such building, said open space must connect directly with the alley. In case the entire audience is seated on the ground level said open spaces shall extend alongside of the audience room so as to connect with exit doors placed approximately in the middle of the audience room between the opposite ends of same. Where there is a balcony or gallery installed, such open spaces must extend along the entire length of the audience room so as to connect with exits from the balcony or gallery at their highest and lowest levels. Where such a building is located on a corner lot and adjoins a public street on one side and a public street or an alley not less than ten feet wide on two of the remaining sides and the building is so located that it adjoins such public thoroughfares on three sides for its entire extent, it shall not be necessary to construct an open space on the remaining side thereof, but in all such cases there shall be either an open space unobstructed from the ground to the sky or a fireproof passageway at least five feet wide leading from the side of the audience room not bordering on a street or other public space to the street in front of the theatre and another leading to the alley or other public space in the rear of the theatre. If the seating capacity of such theatre is over six hundred, six inches shall be added to the width of such open space or passageway for every one hundred seats or fraction thereof in excess of six hundred and up to the maximum of one thousand. If access to the street and alley or other public space as herein provided is by means of a fireproof passageway, such fireproof passageway must be constructed in all respects according to the provisions of Section 395 of The Chicago Code of 1911, except as herein otherwise provided.

332. Construction.) Buildings of Class IVc hereafter erected, of a seating capacity not to exceed three hundred, shall not be built more than thirty feet in height and may be built of ordinary construction, but the enclosing walls shall be constructed of masonry. No moving picture, vaudeville or theatrical show shall hereafter be installed in a frame building. No room or hall used for the purposes of Class IVc shall hereafter be installed underneath any living or sleeping room.

Buildings for the exhibition of moving pictures only with a seating capacity of more than three hundred but not to exceed one thousand, when the same shall be located as provided for in Section 331 hereof, may be built as herein provided. Said buildings shall contain no stage, proscenium wall nor scenery of any description. The screen for the display of the pictures must be attached to the rear wall of the building, not to exceed six inches away from same. No decorative walls or paintings or other effects shall be constructed inside the audience room in such a manner as to allow any rooms or spaces between same and the enclosing walls of the building. An open platform not to exceed seventy-two square feet in area may be built before the picture screen. On the main floor of such building there shall be at least two main aisles with direct exits at front and rear and two cross aisles with direct exits from the side. When such building contains a balcony or gallery there shall be emergency exits from the highest and lowest levels of same on one side and on the other side there shall be either emergency

exits or enclosed interior stairs from the highest level of the balcony, and the lowest level of the balcony shall be connected with such side stairs by means of a tunnel. All seats in the audience room shall be at least twenty inches wide and space thirty-four inches from back to back. The booth for the moving picture machine must be of construction in conformity with the requirements for such machine booths in buildings of Class IVc; in all other respects such buildings shall comply both in structural requirements and equipment with the provisions of the ordinances relating to theatres of Class V hereafter erected.

Provided, however, that where such building has no balcony or gallery and the seats in the audience room are all on the ground floor of same, and where no portion of the building connected with or made a part of or used in conjunction therewith exceeds two stories in height, and where the lobbies and entrances leading to such part of the building used for purposes of Class IVc have brick dividing walls separating them from the portions of the building connected therewith used for the purpose of any other class as defined in this ordinance, and the floors of said lobbies and entrances and the floors and ceilings above such lobbies and entrances are of fireproof construction and there are no doors or windows leading from such lobbies and entrances to any portion of the said building used for any other purpose than Class IVc, such portion of said building as is not used for purposes of Class IVc may be built in accordance with the provisions of the ordinances designating the manner of construction for such classes.

333. Floor Levels—Limitations.) The following limitations of floor levels shall apply to every building used for the purposes of Class IVc; the highest part of the auditorium floor shall not exceed four feet above the sidewalk level. The floor level at the entrance shall not be at a greater height than eight inches above the sidewalk. The aisles shall not have a greater incline than $1\frac{1}{2}$ inches to the foot.

334. Stairways.) Where external stairways are required, such stairways shall be at least six inches wider than the exits, and shall have treads not less than ten inches wide and risers not more than 8 inches high, and shall be provided with suitable handrails on each side thereof, and the width of such stairs shall comply with the requirements of Class IVb.

335. Balconies and Galleries.) In non-fireproof buildings hereafter erected for, or converted to the purposes of Class IVc, not more than one balcony and no galleries shall be constructed.

336. Width of Aisles—Steps in Aisles.) Aisles and rooms used for the purpose of Class IVc shall have in the aggregate a width of not less than twenty inches for each 100 of seating capacity of such room and for fractional parts of 100 a proportionate part of twenty inches shall be added, and no aisles shall have a width of less than two feet six inches. When side emergency exits are permitted, there shall be a cross aisle not less than three feet wide, leading directly to said exit. Steps shall not be permitted in any aisle or in any portion of the auditorium floor.

337. Corridors — Passageways — Doors — Width Of.) The width of corridors, passageways and doors shall be computed in the same manner as provided in Sections 313 and 314.

338. Seats—Size—Location.) There shall not be more than ten seats in any one row between aisles, nor more than six seats between an aisle and side wall. Seats shall not be less than thirty-two inches from back to back and shall not be less than twenty inches in width measured at the top

of the seat back, and shall be secured firmly to the floor.

339. Exits.) In every building of Class IVc, there shall be provided at least two entrance doors. No entrance doors shall be less than four feet in width. If the rear of the building abuts upon an alley, there shall be provided not less than two emergency exits leading directly to the said alley. Wherever emergency exits pass over or under the stage floor level, they shall be enclosed with walls of masonry nine inches in thickness, or four-inch hollow tile, or of two-inch solid plaster, composed of iron studs and metal lath and plaster, and shall have floors and ceilings of slow-burning, mill, or fireproof construction. If the side of the auditorium abuts upon a street or alley, such emergency exits shall be located as follows: one exit shall be located at a distance not greater than five feet from the proscenium wall or stage, and the other exit shall be located at a distance half way between the foyer and the stage wall. Exits by means of stairways or stairway fire escapes, equal in width to eighteen inches for each one hundred persons, shall be provided, and for fractional parts of one hundred, proportionate part of eighteen inches shall be added. No such exit shall be less than two feet six inches in width.

340. Doors to Open Outward.) All doors affording ingress or egress in buildings of Class IVc shall open outward, and no door shall be less than three feet wide. Such doors shall be so constructed that they may be easily opened from within.

341. Walls Between Auditorium and Stage.) Where the area of the stage exceeds 72 square feet, there shall be provided a proscenium wall of solid masonry of not less than nine inches in thickness, extending from ground to the roof. Where the stage area is less than 72 square feet its proscenium wall may be constructed of two-inch solid plaster walls, composed of metal studs and metal lath and plaster or three-inch hollow tile. In no case shall the underside of ceiling or roof over stage house behind proscenium wall be at a higher level than three feet over the highest point of main proscenium opening. And there shall be no trap doors or other openings in the stage floor.

342. Curtain.) (a) The main curtain in the opening of the proscenium wall shall be composed of long fibre asbestos twisted on brass wire and woven into a close cloth. The laps shall be sewed with two lines of brass and asbestos stitching, which laps shall not be less than one-inch wide. Said cloth shall be lapped at least four times around the top and around the bottom bars with at least three lines of the stitching above specified.

(b) The edge of the curtain shall be continuously reinforced by lapping and stitching and also with pieces of sheet metal for clips. The curtain shall be at least thirty inches wider and higher than the masonry opening, and shall have steel top and bottom bars of not less than two square inches in cross section which bars shall be connected by four three-sixteenth-inch steel cables.

(c) There shall be three-eighth-inch spanning cables with upper ends secured to steel brackets fastened to the wall and the lower ends sufficiently counter-weighted to keep the cables taut and where cables pass through the stage floor, the holes shall be metal bushed.

(d) The curtain shall have hard wood eyelets not over eighteen inches center to center, around the standing cables on both vertical edges, which eyelets shall be secured to the curtain by bent brass clips riveted to the curtain with double sheet metal reinforcing.

(e) There shall be steel lifting cables, one-half inch in diameter, at each end of the curtain and at intermediate points not over ten feet apart attached to drums on shafts located above the curtain.

(f) The operating machinery shall be built according to good mechanical engineering practice.

(g) There shall be emergency chains midway between the lifting cables, to hold the curtain which shall be equal in strength and efficiency to the lifting cables.

(h) There shall be steel guides of not less than three-eighth-inch metal on each side of the curtain from the stage floor to the level of the overhead sheaves. The metal guides shall lap the edges of the curtain not less than four inches. The curtain shall be incombustible in all its parts and its operating devices.

(i) The painting and the manner of tripping the curtain and the number of and the location of places for tripping shall be subject to the approval of the Chief of Fire Prevention and Public Safety.

(j) A permit shall be obtained from the Department of Buildings for the erection of each such curtain. The Commissioner of Buildings shall inspect each such curtain semi-annually for which semi-annual inspection, a fee of \$5.00 shall be charged.

343. Other Openings in Stage Walls.) Every other opening in the proscenium wall or in the other walls of the stage shall have self-closing incombustible doors.

344. Structure Over Ceiling—Construction.) A structure may be built over the ceiling or roof of any building used wholly or in part for the purposes of Class IVc, provided such space is not used for sleeping or living purposes. Girders or trusses supporting same shall be of steel protected by fireproofing as required in Section 611 and the entire ceiling shall be covered with incombustible material subject to the approval of the Commissioner of Buildings.

345. Picture Machine Booth.) The walls, floor and ceiling of every moving picture booth or machine house shall be built of four-inch hollow tile or four-inch solid concrete, supported on iron beams or columns, the door of operating room to be metal clad and swing outwards. There shall be a metal smoke or flue pipe eighteen inches in diameter extending from ceiling to three feet above roof of machine house and terminating in the open air.

346. Standpipes and Hose on Stage.) Where the stage area exceeds seventy-two square feet and any scenery is used on stage, there shall be a standpipe system installed on said stage subject to the approval of the Chief of Fire Prevention and Public Safety.

347. Vent or Flue Pipe Over Stage.) (a) When the stage exceeds seventy-two square feet in area and combustible scenery is used, one or more flue pipes of incombustible material and equivalent to one-twentieth of the area of the stage shall be built over the stage and shall extend eight feet above the highest point of roof.

(b) All such flues or vents shall be provided with metal dampers which shall be controlled or operated by a small tarred hempen cord and also by two electric switches, one at the electrician's station on the stage, which station shall be fireproof, and the other at the stage fireman's station on the opposite side of the stage; the arrangement of said cord and said electric switches shall be such that the cord will operate as a fusible link between the electric control and the damper and will release said damper, should the switches or either of them fail to operate. Such stations shall be located in such places on the stage as may be determined

by the Fire Marshal, subject to the provisions of this paragraph, and each switch shall have a sign with plain directions as to the operation of the same printed thereon.

348. Capacity—Certification for License.) The Commissioner of Buildings shall determine the number of persons any room used for the purposes of Class IVc may accommodate according to the provisions of this chapter, and shall certify the same to the City Clerk.

349. Lighting Service Requirement—Class IVc.) Gas or electricity or both may be used for illuminating purposes in buildings of Class IVc but gas shall not be used in that part of the building known as the stage side of the proscenium wall. Provisions shall be made to properly light every portion of a building of Class IVc and every outlet therefrom leading to the outside of the building, and all open courts, passageways, and emergency exits. Lights in vestibules, halls, corridors, passageways, stairways and other means of egress from the building and premises shall be on an independent system or circuit or service, and shall be controlled separately and exclusively by a switch or a shutoff located near the main entrance. In rooms, halls or auditoriums used for the purposes of Class IVc provisions shall be made to furnish a light supplied by gas, above if possible, otherwise closely adjoining every opening to an exit or to an emergency exit from the room, hall or auditorium. Where the capacity of the room, hall or auditorium is greater than three hundred, provisions shall be made to furnish a light supplied by electricity and on the same circuit as the corridor and vestibule lights, above if possible, otherwise closely adjoining every opening to an exit or an emergency exit from such hall or auditorium, in addition to the gas light in such location previously required.

350. Scenery Shall Be Stationary—Chief of Fire Prevention and Public Safety to Approve Same—Metal and Asbestos Scenery.) All scenery on the stage shall be made stationary, and shall consist of not over two asbestos curtains, three stationary wings on each side and four stationary border drops. All scenery and stage paraphernalia shall be treated with a fire-retarding solution subject to the test and approval of the Chief of Fire Prevention and Public Safety. Where all scenery is made of metal upon metal supports, framing and attachments or where all scenery is of pure long fibre asbestos twisted on brass wire and woven into a close cloth with metal framing, supports and attachments, it shall not be considered as scenery within the meaning of the term as used in this chapter.

351. Dressing Room Partitions.) Partitions forming dressing rooms, except where already built, shall be constructed of incombustible material, and such dressing rooms shall be properly ventilated.

352. Frontage Consents Required.) No building of this class shall hereafter be constructed for, or converted to the use of said class, unless frontage consents are secured as required by the ordinances of the City of Chicago and filed with the Commissioner of Buildings.

CLASS IVd

353. Class IVd Defined.) In Class IVd shall be included every grand stand and every baseball, athletic and amusement park.

354. Loads—Allowance for Live Loads.) The floors and stairs of grand stands and bleacher stands, existing or hereafter built, shall be designed and constructed in such manner as to be capable of bearing in all their parts and supports, in addition to the weight of the floor construction, partitions and permanent fixtures, that may be set

upon the same, a live load of not less than one hundred pounds for every square foot of surface of said floors, and a live load of not less than one hundred and fifty pounds for every square foot of the bearing surface of the stairs.

355. Grandstands—Frame within Fire Limits—Grandstands Hereafter Constructed—Fireproof—Frontage Consents.) (a)

Wooden grandstands or tiers of seats commonly known and described as grandstands now constructed or in the process of construction may be erected, repaired or enlarged within the fire limits where no part of any such structure shall be within sixty feet of any other building or structure. All grandstands hereafter erected within the fire limits, except as hereinafter provided, shall be made of fireproof or unprotected steel construction. The enclosing walls, if enclosed, shall be made of fireproof or incombustible materials, but the seats may be made of wood. Grandstands outside the fire limits, or inside the fire limits where the seating capacity does not exceed five thousand persons, may be constructed of wood, but no part of any such structure shall be within less than sixty feet of any other building or structure. The braces, supports and the underside of all seats, including bleacher seats, shall be treated with a fire-retarding solution once a year before opening up the premises containing such stand to the public.

(b) Every person, firm or corporation desiring a permit for the construction of a grandstand, except in connection with such as are now in existence, shall first obtain the consent in writing of the owners of a majority of the frontage on both sides of the street or streets on each side of the block or square in which it is desired to erect such grandstand.

(c) The Commissioner of Buildings shall inspect or cause to be inspected all tiers of seats and grandstands each year before same are opened to the public for the purpose of ascertaining as to their compliance with the City ordinances and the rules and regulations of the Department of Buildings. A fee shall be charged for such annual inspection as follows:

Where the seating capacity is 5,000 or less the fee shall be \$10.00.

Where the seating capacity is more than 5,000 the fee shall be \$25.00.

356. Width of Aisles and Exits—Number of Seats Between Aisles.) (a)

The width of aisles and exits in all grandstands contemplated in Section 353, hereafter constructed, shall be in no case less than 36 inches and such width shall be increased toward the exits which serve as regular entrances, such width being computed at the rate of eighteen inches per 100 seats or fractional part thereof in non-fireproof grandstands, and at the rate of twelve inches for each 100 seats or fractional part thereof in fireproof grandstands.

(b) The number of seats between aisles in any row shall not exceed twenty in non-fireproof grandstands, nor thirty in fireproof grandstands.

357. Temporary Seating Structures.)

Temporary seating structures for shows and outdoor exhibitions and the observation of holidays and special occasions may be built of combustible material, providing they are built structurally strong enough to support a live load of one hundred pounds per square foot, and comply with the provisions of Class IVb in regard to means of exit, aisles and rows of seats; and provided, further, that a permit be secured from the Commissioner of Buildings, which shall in no case be issued by him until the party desiring to erect said temporary seating structure shall secure the written consent of a majority of the property owners or their

duly authorized agents, on both sides of the street between the two nearest intersecting streets on which said temporary seating structure is to be located. And further provided that any permit issued for any such temporary seating structure as hereinabove provided for in this section shall not entitle the person so receiving said permit to use said temporary seating structure for more than ten consecutive days from the first day on which it is so used; and further provided that any temporary seating structure provided for in this section shall be removed within ten days after the use of the same as provided for in this section, and if not so removed it shall be the duty of the Commissioner of Buildings to order the same to be removed or torn down by the Fire Marshal.

358. Use of Roofs—Requirements.) Whenever the roof of any building is used for any purposes whatever, it shall be considered as a story of the building and subject to such restrictions of use and such requirements of construction as are provided for the building by the ordinances of the City of Chicago.

Amusement Parks.

359. Roller Coaster Devices.) No roller coaster, scenic railway, or other riding, sliding, or rolling device, shall be hereafter erected of a greater height from the ground than 55 feet. All such coasters, railways, riding or other devices shall be equipped with safety clutches. The cars, or any receptacles, which persons are permitted to occupy, or in which they are permitted to travel, ascend or descend, shall have hand rails of sufficient number and height to prevent people from being thrown therefrom, and of such character as shall be approved by the Commissioner of Buildings.

360. Frontage Consents Required.) It shall hereafter be unlawful for any person, firm or corporation, to build, construct, establish, produce or carry on, any amusement within any ground, garden or enclosure of the kind commonly known and described as amusement parks, wherein shows of different classes are offered or presented by one or more concessionaries, without first securing written frontage consents as required by the ordinances of the City of Chicago. Such frontage consents shall be filed with the Commissioner of Buildings before a permit shall be issued for the construction of any building or structure connected in any way with such amusement park.

361. Requirements.) (a) Buildings hereafter erected within an amusement park, located outside the fire limits, shall comply, except as herein otherwise specified, with the provisions of Class IVb.

(b) Buildings hereafter erected within amusement parks located outside of the fire limits and not exceeding one story in height and which do not contain more than one balcony may be built with a self-supporting steel frame designed as required by this chapter. Such structures may be enclosed with metal lath covered with cement plaster, which plaster shall be not less than one and one-third inches thick, or such structures may be enclosed with galvanized iron. The roofs of such structures may be of ordinary construction supported on steel trusses and covered with a gravel or composition roof, approved by the Commissioner of Buildings.

(c) Every moving picture theatre hereafter built within an amusement park shall comply with the provisions of Class IVc.

362. Open Space Between Buildings.) There shall be an open and unobstructed space of not less than four feet between

each and every frame building hereafter erected in an amusement park, where the buildings do not exceed twenty feet in height, and of not less than six feet where the buildings are over twenty feet and less than thirty feet in height, and of not less than ten feet where the buildings are over thirty feet in height. Where brick or concrete or other fireproof walls of full seventeen inches in thickness are used between such buildings and where such buildings are built of slow-burning construction, these spaces shall not be required, but, in such cases, there shall be a space of ten feet in width at intervals of every two hundred feet.

363. Roller Coasters—Scenic Railways, Etc.—Permit Fee—Certificate of Test and Safety.) (a) Before any roller coaster, scenic railway, water chute or other mechanical riding, sailing, sliding or swinging device is erected, either in existing or new amusement parks, a detailed plan shall be submitted to the Commissioner of Buildings, for his approval or rejection, and, if approved, a permit shall be procured by the person, firm or corporation desiring to erect such device. The permit fee shall be fifty dollars for each such device. Before such device is opened to the public each season, a certificate of inspection, signed by a competent engineer, approved by the Commissioner of Buildings, must be furnished, certifying to the practicability, strength and safety of such devices, and all such device or devices shall be examined by the Commissioner of Buildings or his employees upon completion and each year before opening up to the public.

(b) The Commissioner of Buildings shall inspect or cause to be inspected all buildings to be used for purposes of exhibition, amusement or entertainment which the public are attending that are within or connected with an amusement park, each year before said buildings are open to the public, for the purpose of ascertaining as to their compliance with the City ordinances and the rules and regulations of the Department of Buildings. The fee for such annual inspection shall be five dollars for each building so inspected.

The Commissioner of Buildings shall inspect or cause to be inspected all amusement devices, mechanisms and structures other than riding devices and other than buildings within an amusement park, for the purpose of ascertaining as to their compliance with the City ordinances and the rules and regulations of the Department of Buildings; and the fee for such annual inspection shall be ten dollars for each device, mechanism and structure so inspected.

The Commissioner of Buildings shall inspect or cause to be inspected all amusement devices operated by animals or by other motor power and all other riding, sliding, sailing, swinging or rolling devices situated on any lot or trace of land outside of the amusement park before said devices are open to the public. Where said devices are taken down, removed and reassembled or re-erected in another location, the Commissioner of Buildings shall inspect or cause to be inspected said devices after each removal and before said devices are open to the public, for the purpose of ascertaining as to their compliance with the City ordinances and the rules and regulations of the Department of Buildings. A fee of five dollars shall be made for every such inspection or removal inspection.

364. Must Comply With All Ordinances.) It shall be unlawful for any person, firm or corporation to construct, alter or operate any amusement park or any building or structure therein unless they comply with the ordinances of the city relative thereto.

ARTICLE VIII.

(Note: See end of ordinance, page 277, for special ordinance on regulations for operation of theatres.)

365. Class V Defined.) In Class V shall be included every building which is used as a public theater where an admission fee is charged and in which movable scenery is used, and every assembly hall hereafter erected having a seating capacity of over 300 and containing a permanent stage on which scenery and theatrical apparatus are used and regular theatrical vaudeville performances are given; provided, however, that public halls and club halls with a seating capacity of less than six hundred, although occasionally used for theatrical presentation, shall not be considered as public theatres within the meaning of the term as used in this section, notwithstanding the fact that movable scenery is used upon the stages thereof on such occasions, and such public halls and club halls shall not be considered as buildings of Class V as herein defined. Such public halls and club halls shall be included in Class IV as defined in this section.

366. Must Comply With General and Special Provisions.) Every building of Class V shall comply with the general provisions of this chapter and shall also comply with the following special provisions:

367. City Officers Empowered to Enter Buildings.) The Commissioner of Buildings, Commissioner of Health, Fire Marshal, City Electrician, Superintendent of Police, or any of them, and their respective assistants, shall have the right to enter any building used wholly or in part for the purposes of Class V, and any and all parts thereof, at any reasonable time, and at any time when occupied by the public, in order to examine such buildings, to judge of the condition of the same and to discharge their respective duties, and it shall be unlawful for any person to interfere with them, or any of them, in the performance of their duties.

368. City Officers Empowered to Close.) The Commissioner of Buildings, Commissioner of Health, Fire Marshal, City Electrician and the Superintendent of Police, or any one of them, shall have the power, and it shall be their joint and several duty, to order any building used wholly or in part for the purposes of Class V, closed, where it is discovered that there is any violation of any of the provisions of the chapter, and keep same closed until such provisions are complied with.

369. License—Mayor Shall Revoke.) Upon a report to the Mayor by the Commissioner of Buildings, Commissioner of Health, Fire Marshal, City Electrician or the Superintendent of Police that any requirement of this chapter or that any order given by them or any of them in regard thereto has been violated, or not complied with, the Mayor shall revoke the license of any such theatre or place of amusement so reported and cause the same to be closed.

Buildings of Class V Now in Existence.

370. Buildings of Class V Now in Existence.) The following provisions shall apply to Class V buildings in existence at the time of the passage of this ordinance:

371. Walls—Outside—Must Comply with Requirements of Section 506.) The outside walls of all such buildings in existence at the time of the passage of this ordinance, the roofs or ceilings of which are carried on trusses or girders of a span of fifty feet or more shall comply with the requirements of Section 506.

372. Columns in Walls—Alterations.) If iron or steel columns are introduced in the walls referred to in Section 371, the

brick work around the same shall be bonded into that of the connecting walls, and each of such columns shall be fireproofed as provided in Sections 610 and 611 of this chapter. All alterations in such existing buildings, to make them comply with the requirements of this chapter may be executed with the same kind of materials as those originally used in the construction of such buildings; provided, that after the said building is brought into compliance with the provisions of this chapter, then all subsequent alterations, enlargements, repairs, replaced or strengthened structural parts damaged by fire, wear and tear, or otherwise, shall be made of fireproof construction or iron or steel construction covered with fireproof materials, as provided by this chapter.

373. Other Classes Built in Conjunction with Class V—Doors for Openings Between Connecting Buildings.) In all cases where existing buildings used wholly or in part for the purposes of Class V are built in conjunction with or as part of buildings devoted to the uses of other classes and where such buildings of the other classes, as specified in this ordinance, are not built entirely of fireproof construction, double iron doors shall be placed at each connecting opening between such buildings of Class V and the building connected therewith.

374. Floor Levels—Limitations of.) (a) Any audience room used for the purposes of Class V now in existence containing in the aggregate not more than five hundred seats, if in a fireproof building, may be maintained in any story thereof, but in such case there shall be at least two stairways to the ground, from the floor or floors on which each such room is located, each of which stairways shall be not less than four feet in width in the clear.

(b) In existing buildings of fireproof construction, having an audience room with a seating capacity of more than five hundred and less than fifteen hundred, the lowest bank of seats of the main floor thereof shall be not more than twelve feet above the street level, and every such building shall in all other respects conform to the requirements of this ordinance. The main floor of any existing theatre of any kind of construction shall not be raised above its present elevation.

375. Loads—Allowance for Live Loads in Construction of Floors of Class V.) For all buildings of Class V all floors shall be designed and constructed in such manner as to be capable of supporting in all their parts, in addition to the weight of floor construction, partitions and permanent fixtures and mechanisms that may be set upon the same, a live load of one hundred pounds for every square foot of surface in such floors.

376. Stairways—Entrances and Exits.) (a) Stairways, affording egress from any room or rooms used for the purposes of Class V shall be equivalent in width to twenty inches for every one hundred of seating capacity of such room, and for fractional parts of one hundred a proportionate part of twenty inches shall be added, but no such stairway shall be less than four feet wide in the clear, except as hereinafter provided in this section.

(b) All such stairways shall have hand railings on each side thereof and shall not ascend to a greater height than thirteen feet six inches without a level landing, and the length and width of such landing shall not be less than the width of the stairs. No run of stairs shall consist of less than six risers between platforms, and risers shall not be placed on return platforms. Stairways which are over 7 feet wide shall

have double intermediate handrails with end newel posts at least 5½ feet high.

(c) Steps shall not have a greater rise than 8 inches, treads shall not be narrower than 10 inches, and winders shall not be used on any staircase, except where circular staircases are expressly permitted.

(d) In existing theatres every balcony and gallery shall have separate and distinct entrance stairways from the sidewalk level, except that in cases where the vestibule or entrance to any such theatre is not more than fifteen inches, or two steps, above the sidewalk level and such steps are at or near the building line, the stairways to such balcony and gallery may ascend from the floor of such vestibule or entrance, but if the run of the stairs at the bottom is not toward the street, there shall be a hand rail or rails, three feet above the floor constructed from the foot of such stairways for a distance of not less than five feet leading toward the street. All doors intervening between such stairways and the street shall, during each and every performance, be kept unfastened.

(e) There shall be an iron stairway or stairways from the stage to the fly galleries and gridiron, continuing to the roof of the building or to some fireproof passageway or exit. Such stairways may be circular. Such circular stairways, however, shall not be used for access to the dressing rooms.

(f) Every stairway leading to a box or boxes shall be independent of all other stairs or seats; and such stairway shall not be less than two feet eight inches wide in the clear, when such box or boxes seat not to exceed thirty people, and an additional width of one inch shall be added to such stairway for each additional five persons for whom seating capacity is provided.

(g) Every stairway on the stage side of the proscenium wall shall be not less than two feet six inches wide.

(h) Instead of increasing the width required for entrances, aisles, exits and stairways to that required by this chapter, the owner, lessee or manager of any such theatre shall have the privilege of reducing the number of permanent seats therein until the same ratio between such width and number of seats as hereinbefore provided for shall be established, and if such privilege be taken advantage of, it shall be the duty of the Commissioner of Buildings to make inspection and certify that such ratio actually exists before a license for the operation of any such theatre shall be issued.

377. Floors and Exits.) Floors at all exits shall be level and flush with adjacent inside floors and shall extend for an unbroken width of not less than four feet in front of each exit, and shall be two feet wider than such exit.

378. Seats in Rows Between Aisles.) (a) Not more than ten seats in any row shall be permitted between aisles in any gallery. On the main floor and balcony not more than eleven seats shall be permitted between aisles; except in rows of seats which are within twenty feet from the exits, in which case thirteen seats shall be permitted between aisles.

(b) Seats shall be not less than twenty inches in width measured at the top of the seat backs. Rows of seats shall be not less than two feet eight inches from back to back.

No bank of seats shall be of greater rise than twenty-two inches.

(c) All groups of seats shall be so arranged that there shall be an aisle at each side of each group, except that groups of

five seats or less may abut upon a tunnel at one side and an aisle at the other. And except that a bank of seats abutting boxes or walls on main floor, balcony, and gallery, of not over five seats in a row, shall be required to abut upon one aisle only.

(d) The number of banks of seats on the main floor shall not exceed fifteen unless an intervening or cross aisle is provided between each fifteen banks of seats or unless a direct exit is provided for each aisle.

(e) The number of banks of seats in the balcony shall not exceed nine unless an intervening or cross aisle is provided between each nine banks of seats or unless a direct exit be provided for each aisle.

329. Limits of Vertical Rise and Requirement for Tunnels in Cross Aisles—Openings in Foyer Wall.)

(a) There shall be no more than twelve feet rise measured vertically in any aisles in any floor or in any balcony or in any gallery without a direct exit by tunnel or otherwise to a corridor with free opening on to the gallery stairs or other direct discharge to the street, or at such elevation of twelve feet an intervening or cross aisle leading directly to an exit. No tunnel shall be less than three feet wide in the clear.

(b) There shall be no openings in the foyer wall between the foyer and theatre proper other than the exit openings.

330. Main Floor—Balcony and Gallery—Designation of.)

(a) The lower floor of all theatres shall be designated the "Main Floor."

(b) Where there are balconies or galleries, the first balcony or gallery shall be designated the "Balcony," and the second and third balcony or gallery shall be designated, respectively, "Gallery" and "Second Gallery."

331. Aisles—Width of—Shall Lead Direct to Exit—Steps in Aisles.)

(a) The minimum width of aisles with diverging sides in any room used for the purposes of Class V shall be two feet eight inches at the end near the stage and not less than three feet at the other end.

(b) The minimum width of aisles with parallel sides shall be three feet.

(c) Every aisle shall lead as nearly as possible directly to an exit, but in no case shall the center line of such exit be more than three feet from the center line of any such aisle leading thereto.

(d) Steps shall not be permitted in aisles except as extending from bank to bank of seats, and no riser shall be greater than 8 inches, and no tread shall be less than 10 inches, and whenever the rise from bank to bank of seats is less than five inches, the floor of the aisles shall be made as an inclined plane, and where steps are placed in

outside aisles or corridors they shall not be isolated, but shall be grouped together and a light shall be maintained so that every place where there are steps in inclosing aisles or corridors shall be clearly lighted.

332. Corridors, Passageways, Hallways and Doors—Width of.)

(a) The width of corridors, passageways, hallways and doors shall be computed in the same manner as that hereinbefore provided for stairways, excepting, however, that no corridor shall be anywhere less than four feet in width, and no door less than three feet wide, except as otherwise herein provided.

(b) All corridors, passageways, hallways and stairways leading from any balcony or gallery to any toilet room, retiring room, smoking room, check room or private office, shall lead directly to an outer exit of the building. Such corridors, passageways, hallways and stairways shall be at least three feet in width in every part, and shall be unobstructed in every part except by doors, not less than three feet in width in the clear, which shall swing outward and which shall not have locks or catches of any kind whatever.

333. Doors—Entrance.)

(a) The width of entrance doors to every theatre shall be computed on the basis of twenty inches in the clear to each one hundred permanent seats in the audience room and in addition thereto a proportionate part of twenty inches for the fractional part of one hundred seats shall be added.

(b) No mirror or architectural feature shall be so arranged as to give the appearance of a doorway, exit, hallway or corridor where none exists.

334. Dressing Room Partitions.)

Partitions forming dressing rooms, except where already built, shall be constructed of incombustible material, and such dressing rooms shall be properly ventilated.

335. Emergency Exits—Width—Emergency Stairs—Width—Emergency Exits Inside Walls of Buildings—Fire Escapes, Construction—Fire Escapes Leading to Street or Alley—Doors Open Outward.)

(a) Emergency exits and stairways shall be provided separately for each floor, balcony and gallery and shall be of the same aggregate width as that provided for the main exits, and shall not be less than three feet in width. Such emergency exits shall be kept free of obstructions of every kind, including snow and ice.

(b) Such emergency exits and stairways may be built inside the walls of the building, provided they are enclosed by a fire-proof partition not less than four inches thick separating the exits and stairways from the audience room or auditorium.




Fig. 3.
EMERGENCY EXITS.
Section 335c.

Suggestion how to swing doors, so as not to obstruct passageway

(c) If said emergency exits lead outside the building, the opening leading thereto shall have metal doors with wired glass panels. The doors shall open outward, and shall be hung from the inside corner of the jambs, and so constructed as not to project, when opened, beyond the outside face of the wall. Outside shutters will not be permitted, except when they open automatically from the interior, without resistance, and when used or open will automatically fasten, securely, flat against the wall, so as not to obstruct the passage on the outside; all such automatic devices or attachments to said doors or shutters shall be subject to the approval of the Commissioner of Buildings and the Fire Marshal of the City of Chicago.

(d) Whenever any such emergency stairway passes over an exit door, window or other opening, such stairway shall be completely inclosed for a space of five feet greater in width than such opening, by iron, steel or other incombustible material.

(e) All such emergency exits and stairways shall land at the ground level in a public thoroughfare or in some space that connects directly with a street or alley, and direct and immediate exit to such public thoroughfare shall not be obstructed by any doors, gates, bars or obstruction of any character.

(f) Every court in which there is an emergency stairway shall have direct and unobstructed access along the surface of the ground to a street, alley or yard opening into an alley, or street, without entering into or passing through or over any building unless by a fireproof passage at least four feet wide and seven feet high on the court or ground level.

(g) All doors in openings from any and all exits and stairways shall be so constructed that when opened they shall not obstruct any portion of any other doorway, opening or passageway.

(h) All doors affording ingress to or egress from any theatre shall open outward and such doors shall be so constructed and maintained as to require no special knowledge or effort to open them from the interior.

336. Proscenium Wall—Curtain—Requirements for Other Openings in Proscenium Wall.) (a) There shall be in every theatre a solid brick wall of the same construction and thickness as is required in outside walls between the auditorium and the stage. The main proscenium opening shall have a substantial steel curtain vertically operated and fireproofed on the stage side, which shall be raised and lowered by mechanical power and shall be in constant use as the regular curtain and act drop.

(b) No combustible material other than painted decorations shall be applied to the audience side of such curtains.

(c) Plans for such curtains shall be approved by the Commissioner of Buildings and a permit obtained previous to its erection. The Commissioner of Buildings shall inspect such curtain semi-annually, for which inspection a fee of five dollars shall be charged.

(d) All other openings in such proscenium wall shall have iron doors, frames and thresholds.

337. Stage—Construction of—Framing for Scenery.) The framing for the floor of every stage shall be of iron, steel, or reinforced concrete. The stage floor may be of wood not less than one and three-quarters inches thick, provided the underside of stage floor shall be saturated with a fireproof solution satisfactory to the Chief of Fire Prevention and Public Safety. The entire floor construction and the floor of fly galleries, rigging lofts and paint gallery,

all railings and supports and stanchions thereon, and all stairways, passageways and their supports, shall be of iron, steel or reinforced concrete. All framing for scenery and all stage paraphernalia shall be saturated with a fireproof solution the same as prescribed for stage flooring.

338. Vestibule for Stage Doors.) All doorways and openings in the rear or sides of the stage shall be vestibuled or arranged in a manner satisfactory to the Commissioner of Buildings so as to protect the curtain, scenery and auditorium against draughts of air.

339. Vents—Flue Pipes, Size of—Dampers—Switches for Dampers.) (a) One or more vents, or flue pipes, of metal construction or other incombustible material, suitable for carrying away smoke, approved by the Commissioner of Buildings, and extending not less than fifteen feet above the highest point of the roof and equivalent in area to one-twentieth of the area of the stage, shall be built over the stage.

(b) In buildings where additional stories are built above the stage, such vents or flue pipes may be carried out near the top of the stage walls and shall be continued and run up on the exterior of the building to a point five feet above the highest point of such additional stories.

(c) All such flues or vents shall be provided with metal dampers which shall be controlled or operated by a fused cord and by two electric switches, one at the electrician's station on the stage, which station shall be fireproof, and the other at the stage fireman's station on the opposite side of the stage; the arrangement of said cord and said electric switches shall be such that the cord will operate as a fusible link between the electric control and the damper and will release said damper, should the switches or either of them fail to operate. Such stations shall be located in such places on the stage as may be determined by the Chief of Fire Prevention and Public Safety, subject to the provisions of this paragraph, and each switch shall have a sign with plain directions as to the operation of the same printed thereon.

390. Automatic Sprinklers.) (a) A system of automatic sprinklers subject to the approval of the Chief of Fire Prevention and Public Safety, shall be provided and installed in every theatre.

(b) Where water for such system of automatic sprinklers is supplied from a tank, the supports and installation of such tank or tanks shall be subject to the approval of the Commissioner of Buildings.

391. Lighting Requirements—Buildings Class V Now in Existence.) Lighting of every building of Class V shall comply with the requirements for buildings of Class V hereafter erected.

392. Capacity—Certification for License.) The Commissioner of Buildings shall determine the number of persons which every room used for the purpose of Class V may accommodate according to the provisions of this chapter and shall certify the same to the City Clerk. No more than the number so certified shall be allowed in such room at any one time.

393. Theatres in Frame Buildings Prohibited.) On and after July first, 1911, no frame building, or part thereof, within the city, shall be used as a moving picture, vaudeville or other theatre; provided, that nothing herein contained shall be held to apply to any frame building existing at the time of the passage of this ordinance and in which a moving picture, vaudeville or other theatre is being maintained at the time of the passage of this ordinance, where all the scenery, if any, used in connection with such moving picture, vaudeville or other theatre is in.

and where the distance of exit space for such theatre is at least fifty (50) inches for each one hundred (100) seats therein contained, and where there is no living apartment of any kind used, maintained or occupied in some or any part of said building.

To Buildings of Class V Hereafter Erected.

The following provisions shall apply to buildings of Class V hereafter erected and used wholly or in part for such purposes:

(a) Construction—Walls—Outside Walls—Structures.) All buildings of Class V hereafter erected shall be built of fireproof construction.

(b) Frontage—Open Spaces—Fireproof Passageways.) (a) All buildings hereafter erected used wholly or in part for the purposes of Class V shall be located so that they adjoin at least two public thoroughfares, one of which shall be a public street and the other may be a public alley not less than ten (10) feet in width.

(b) The audience room of every such building, used for the purposes of Class V shall have either a public thoroughfare or an open space not less than ten feet wide extending from the lowest first floor level to the sky, on each of the two sides other than the proscenium and the foyer. Exit doors shall open onto such public thoroughfare or the bottom of such open space from the respective sides of the stage and of the main floor of the audience room, and onto balconies or platforms built in such public thoroughfare or open space at both the highest and the lowest floor levels of each and every balcony and gallery and the doors opening into such public thoroughfare or open space from any balcony or gallery or from the main floor shall comply with all the requirements prescribed in Section 410 of this chapter.

Provided, however, where such building has a seating capacity of not to exceed 1,000 persons, and in which the seats for the entire audience are located upon the main floor, and where no part of the main floor is higher than four (4) feet above the inside sidewalk grade of the street opposite the main entrance to such building, and where every part of every building connecting thereto or built in conjunction therewith is of fireproof construction, the provisions for open spaces alongside audience room as contained in Section 331 applicable to buildings of Class IV where the entire audience is seated on the ground level shall govern with respect to open spaces, and the provisions of Section 332 shall govern with respect to main floor aisles and direct exits from same.

Where two theatres are erected simultaneously in the same building or in adjoining buildings under the same ownership, and where the aggregate seating capacity of both theater audience rooms taken together does not exceed a total of 2,500 persons, and where said building or adjoining buildings have a frontage upon three public thoroughfares, the said audience rooms may have in common an open space not less than ten feet in width in every part thereof from the line of the proscenium wall along and directly adjacent to each audience room to the public street upon which such building or buildings face. Such open space shall be clear and unobstructed from the bottom thereof to the sky, and may be considered the equivalent of an open space for each audience room as required by this section.

(c) All such balconies or platforms shall be connected with stairway fire escapes leading to the street level or to the bottom of such open space and in the latter case they shall have their bottom run toward the public thoroughfare and such balconies or platforms and such fire escapes shall comply with all the requirements prescribed in Sections 653, 654 and 657 of this chapter.

Every such open space, if it does not open into a public thoroughfare shall communicate with the public thoroughfare at the front side of the theatre by a fireproof passageway leading from the bottom level of such open space to the sidewalk level. Where there is a public thoroughfare behind the stage every such open space shall also communicate with such public thoroughfare by a fireproof passageway leading from the bottom level of such open space to the level of the public thoroughfare behind the stage, and passing under the stage.

(d) The walls of a fireproof passageway shall be not less than four inches thick, and each and every part of such passageway, including each and all of its supports, shall be built of fireproof construction as required in the general provisions of this chapter relating thereto.

(e) Radiators for warming passageways shall be in recesses sufficient in depth to prevent them from obstructing the passageway.

(f) There shall be no steps or risers in fireproof passageways, but where necessary, inclined floors of the full width of the fireproof passageway may be built; the incline of the floor shall not exceed two and one-half inches in height per foot measured horizontally, and no such incline shall be less than ten feet in length. No fireproof passageway shall be less than ten feet wide and eight feet high in any part thereof except at doors, and these door openings shall be not less than eight feet wide and seven feet high.

(g) If the principal entrance corridor of a theatre is at one side and approximately at right angles to the central axis of the audience room, then the center line extended of such principal entrance shall intersect the center axis of the stage and the audience room between the back of the seat most remote from the stage, on said center axis of the stage and the audience room and at a point midway between such seat and the wall opposite the proscenium wall.

396. Buildings of Other Classes Built in Conjunction with Class V.) If buildings used wholly or in part for purposes of Class V, are built in conjunction with or as part of buildings devoted to the uses of other classes, then such buildings of other classes shall be built of fireproof construction.

397. Floor Levels—Live Loads.) (a) The floor level of the highest bank of seats on the main floor shall not be more than three feet above the sidewalk level and the floor level of the lowest bank of seats shall not be more than eight feet below the sidewalk level.

(b) All floors shall be designed and constructed in such manner as to be capable of bearing in all their parts, in addition to the weight of floor construction, permanent fixtures and mechanisms that may set upon the same, a live load of one hundred pounds for every square foot of surface in such floors.

398. Stairways—Entrances and Exits.)

(a) Stairways affording ingress to or egress from any room used for the purposes of Class V shall be in width equivalent to twenty inches for each one hundred of seating capacity of such room, and for fractional parts of one hundred a proportionate part of twenty inches of width shall be added, but in no event shall any such stairways be less than four feet in the clear, except as hereinafter provided.

(b) All such stairways shall have hand rails on each side thereof, and shall not ascend to a greater height than thirteen feet six inches without a level landing, and the length and width of such landing shall be not less than the width of the stairs; no run of stairs shall consist of less than six risers between platforms, and risers




Fig. 4.

STAIRWAYS.

Sections 398, 441, 449, 452, 486, 659, 652 and others.

Fig. 4 (A) Shows measurement of stairways where hand rails are required on each side.
(B) Shows measurement of landing.

Fig. 5. Measurement of stairway where hand rail is required on one side only.

Fig. 6 (A) Landing.

(B) Stairways shall not ascend to an unlimited height (B) without a landing (A), and (A) shall not be less in width and length than (A) Fig. measurement of stairs.



Fig. 7.

Fig. 8.

Fig. 7. Over 7' 0" (for exceptions see ordinance) wide stairways (C) shall have double intermediate hand rails (Fig. 7). In plan (Fig. Sec. AA).

(B) Measurement of stairs where double intermediate hand rails occur.

(C) Measurement of stairs where double intermediate hand rails do not occur, as in general case, Fig. 4 (A).

Fig. 8. Newel post 5' 1/2' 0" high (A) required for stairs as referred to in Fig. 8.

shall not be placed on return platforms. Stairways which are over seven feet wide shall have double intermediate hand rails with end newel posts at least five and one-half feet high.

(c) Steps shall not have a greater rise than eight inches, treads shall not be narrower than eleven inches, and winders shall not be used on any staircase.

(d) Every balcony and gallery shall have one or more separate and distinct exits and stairways to the sidewalk level. All gallery stairways shall lead to the top gallery and there shall be doors in same at each floor for exit purposes only. The bottom run of the stairs shall be directly toward the street. Such stairs may ascend from the vestibule or entrance inside of the buildings, but the bottom riser of such stairs shall be not more than sixty-five feet from the building line. All doors between such stairs and the street shall be kept unlocked and unfastened during each and every performance and until the audience has left the building.

(e) There shall be an iron stairway or stairways from the stage to the fly gallery and gridiron, continuing to the roof of the building or to some fireproof passageway or exit. Such stairway may be circular. Such circular stairways, however, shall not be used for access to the dressing rooms.

(f) Stairs leading to a box or boxes seating not to exceed thirty people in the aggregate shall be independent of all other stairs and seats, and not less than two feet eight inches wide in the clear. For each additional twenty-five persons for whom seating capacity is provided, or major portion thereof, in such box or boxes there shall be an additional five inches in width of such stairway.

(g) All stairways on the stage side of the proscenium wall shall be not less than two feet six inches wide.

399. **Floors at Exits—Seating.)** (a) Floors at all exits shall be level and flush with adjacent inside floors and shall extend for an unbroken width of not less than four feet in front of each exit, and shall be two feet wider than such exit.

(b) There shall not be more than ten seats in any one row between aisles.

(c) Seats shall not be less than twenty inches in width, measured at the top of the seat backs.

(d) Rows of seats shall not be less than two feet ten inches from back to back.

(e) No bank of seats shall have a greater rise than twenty inches. A bank of seats abutting boxes or wall on main floor, balcony or gallery of not over five seats in a row, shall be required to abut upon one aisle only.

(f) Seats in loges and boxes shall be limited in the ratio of one seat for every six hundred and eighty square inches of floor area in such loge or box.

(g) All groups of seats shall be so arranged that there shall be an aisle at each side of each group, provided groups of five seats or less may abut upon a tunnel at one side and an aisle on the other side.

(h) The number of banks of seats on the main floor shall not exceed fifteen, unless an intervening or cross aisle is provided between each fifteen banks of seats or a direct exit is provided for each aisle. The number of banks of seats in the "balcony" and "galleries" shall not exceed nine, unless an intervening or cross aisle is provided between each nine banks of seats or a direct exit is provided for each aisle.

100. Limit of Rise in Floors—Openings in Foyer Wall.) (a) There shall be no more than eleven feet rise, measured vertically, in any main floor or in any gallery or in any balcony without a direct exit by tunnel or otherwise, to a corridor with free opening onto the gallery stairs or other direct discharge to the street or at any such elevation of eleven feet an intervening or cross aisle leading directly to an exit. No tunnel shall be less than four feet wide in the clear.

(b) There shall be no openings in the foyer wall between the foyer and theatre proper other than the exit openings.

101. Main Floor—Balcony and Gallery—Designation of.) (a) The lower floor shall be designated the "Main Floor."

(b) Where there are balconies or galleries, the first balcony or gallery shall be designated the "Balcony" and the second and third balcony or gallery shall be designated, respectively, "Gallery" and "Second Gallery."

102. Width of Aisles—Exit from Aisles—Steps in Aisles.) (a) The minimum width of aisles with different sides in any room used for the purpose of Class V shall be two feet eight inches at the end nearest the stage and not less than three feet at the other end. The minimum width of aisles with parallel sides shall be three feet.

(b) Every aisle shall lead directly to an exit. An exit located at the end of any aisle and at right angles thereto shall be considered a direct exit.

(c) Steps shall not be permitted in aisles except as extending from bank to bank of seats, and no riser shall be more than eight inches in height, and no tread shall be less than ten inches in width, and wherever the rise from bank to bank of seats is less than five inches, the floor of the aisle shall be made as an inclined plane, and where steps are placed in outside aisles or corridors they shall not be isolated but shall be grouped together, and a light shall be installed so that every place where there are steps in such aisles or corridors shall be clearly lighted.

103. Corridors—Passageways—Hallways and Doors—Width of—Leading from Toilet Rooms and Cloak Rooms to Outer Exits of the Building—Width of Entrance Doors.)

(a) The width of corridors, passageways, hallways and doors shall be computed in the same manner as that hereinbefore provided for stairways, excepting however, that no corridor shall be less than five feet in width and no doorway less than three feet wide, except as otherwise herein provided.

(b) Every toilet room, retiring room, smoking room, cloak room, check room or private office which is accessible from any corridor, passageway, hallway or stairway leading from any floor, balcony or gallery shall, in addition to the entrance thereto, have an exit arranged in such manner as to permit of direct passage through such room or office, without returning, to an outer exit of the building. Corridors, passageways, hallways and stairways shall be at least four feet in width in every part between such balcony or gallery and such outer exit, and shall be unobstructed in every part, except by doors not less than three feet in width in the clear, which shall swing outward and which shall not be provided with locks or

(c) The width of entrance doors to every theatre shall be computed on the basis of twenty inches in the clear to each 100 permanent seats in the audience room, and in addition thereto a proportionate part of twenty inches for the fraction part of 100 seats remaining shall be added.

404. Emergency Exits and Stairs—Width of—Emergency Stairs—Construction of, Requirements—Shall Not be Obstructed—Emergency Exits Inside Walls of Buildings—Doors to Open Outward.) (a) Emergency exits and stairways shall be provided separately for each floor, balcony or gallery and shall be of the same aggregate width as that provided for the main exits, and shall not be less than three feet in width. Such emergency stairway shall be made of iron, steel or other incombustible material.

(b) Such emergency exits and stairways may be built inside the walls of the building, provided they are enclosed by a fire-proof partition not less than four inches thick, separating the exits and stairways from the audience room or auditorium.

(c) If such emergency exits lead outside the building, the openings leading thereto shall have metal doors with wired glass panels. The doors shall open outward, and shall be hung from the inside corner of the jambs, and so constructed as not to project, when opened, beyond the outside face of the wall, and outer shutters shall not be permitted.

(d) Whenever such emergency stairway passes above an exit door, window or other opening, such stairway shall be completely enclosed by iron, steel or other incombustible material for a space of five feet greater in width than such opening, and such openings below such emergency stairway shall be equipped with approved metal frames and doors or metal sash and wired glass.

(e) All such emergency exits and stairways shall land at the ground level in a public thoroughfare or in some space that connects directly with a street or alley, and direct and immediate exit to such public thoroughfare shall not be obstructed by any door, gate, bars or obstructions of any character.

(f) Every court in which there is an emergency stairway shall have direct and unobstructed access along the surface of the ground to a street, alley or yard opening into an alley or street, without entering into or passing through or over any buildings unless by a four-foot wide fire-proof passage on the court or ground level.

(g) All doors in openings from emergency exits and stairways shall be so constructed that when opened they will not obstruct any portion of any other doorway, opening or passageway.

(h) All doors affording ingress to or egress from any theatre shall open outward.

405. Proscenium Wall Curtain and Requirements for Same—Permit for and Inspection of Curtain.) (a) There shall be a solid masonry wall of the same construction and thickness as is required in the outside walls of the building in which such theatre is located between the auditorium and the stage.

(b) The main proscenium opening shall have a vertically operated steel curtain which shall, when it is lowered, completely close such proscenium opening. The curtain shall be raised and lowered by hydraulic power, and shall be in constant use as the regular curtain and act drop.

(c) The lowering of the curtain shall be controlled from not less than two points in the building, one of which shall be from the stage level and the other shall be designated by the Commissioner of Buildings.

(d) The curtain shall have a steel covering on the outer or auditorium side. The

stage side covering shall be of a non-heat-conducting substance of such a thickness and such material as shall stand a test of two thousand degrees Fahrenheit on the stage side for fifteen minutes without heating the opposite side to a higher temperature than three hundred and fifty degrees Fahrenheit.

(e) All metal work with the exception of the frame shall be covered with such non-heat-conducting substances on the stage side.

(f) The curtain shall operate vertically in steel guides of such a cross section that the edges shall engage and secure the edges of the curtain and prevent the curtain from leaving the guiding channel or channels if the curtain should tend to buckle or bag either inward or outward. No metal in the guide channel or in the engaging edge of the curtain shall be less than three-eighths of an inch thick. The joints of the curtain with the proscenium wall, with the stage floor and with the head of the opening shall be made gas tight as nearly as practicable.

(g) The calculations for the strength of the curtain, the curtain guides and the guide anchors, and the workmanship, shall be according to the best modern engineering practice. The stresses in the material and in the various sections of steel shall be within the safe limits of stress described in this ordinance.

(h) No part of a curtain or of the curtain guides shall be supported by or fastened by any combustible material.

(i) The supports of the curtain and the curtain guides and edges and the curtain shall be of sufficient strength to safely resist either inward or outward a pressure of five pounds for each and every square foot of the curtain.

(j) No combustible material other than painted decorations shall be applied to the audience side of any such curtain.

(k) Plans for every such curtain shall be approved by the Commissioner of Buildings and a permit obtained therefor previous to its erection. The Commissioner of Buildings shall inspect such curtain semi-annually, and for each such inspection a fee of five dollars shall be charged.

(l) Every other opening in such proscenium wall shall have self-closing regulation standard iron fire doors and iron frames and thresholds; such doors and frames shall be built in such a manner as to resist warping.

408. Stage—Construction of—Framing for Scenery.) The framing for the floor of every stage shall be of iron, steel or reinforced concrete. The stage floor may be of wood not less than two and three-quarters inches thick, provided the underside of stage floor shall be saturated with a fireproof solution satisfactory to the Chief of Fire Prevention and Public Safety. The entire floor construction and the floor of fly galleries, rigging lofts and paint gallery, all railings and supports and stanchions thereon, and all sheaves, pulleys and permanent cables and their supports shall be of iron, steel or reinforced concrete. All framing for scenery and all stage paraphernalia shall be saturated with a fireproof solution the same as prescribed for stage flooring.

407. Vestibules for Stage Doors.) All doorways and openings in the rear or sides of the stage shall be vestibuled or arranged in a manner satisfactory to the Commissioner of Buildings, so as to protect the curtain, scenery and auditorium against draughts of air.

408. Structures Over Ceiling—Construction.) If any structure is built over the ceiling or roof of any theater, the different members of the girders or trusses supporting same shall be fireproofed in the manner prescribed for columns of fireproof

buildings as specified in the General Provisions of this chapter.

409. Vents—Size of—Flue Pipes—Dampers—Switches for Dampers.) (a) One or more vents or flue pipes of metal construction, or other incombustible material, suitable for carrying away smoke, and approved by the Commissioner of Buildings, and extending not less than fifteen feet above the highest point of the roof, and equivalent in area to one-twentieth of the area of the stage, shall be built over the stage.

(b) In buildings where additional stories are built above the stage, such vents or flue pipes may be carried out near the top of the stage walls and shall be continued and run up on the exterior of the building to a point five feet above the highest point of such additional story.

(c) All such flues or vents shall be provided with metal dampers which shall be controlled or operated by a small tarred hempen cord and also by two electric switches, one at the electrician's station on the stage, which station shall be fireproof, and the other at the stage fireman's station on the opposite side of the stage; the arrangement of said cord and said electric switches shall be such that the cord will operate as a fusible link between the electric control and the damper and will release said damper, should the switches or either of them, fail to operate. Such stations shall be located in such places on the stage as may be determined by the Fire Marshal, subject to the provisions of this paragraph, and each switch shall have a sign with plain directions as to the operation of the same printed thereon.

(d) All fuse boxes shall be surrounded by two thicknesses of fireproof materials, with an air space between, and no fuses shall be exposed to the air between the switchboards.

410. Standpipes—Automatic Sprinklers—Tanks for Water.) (a) A system of standpipes and of automatic sprinklers subject to the approval of the Chief of Fire Prevention and Public Safety, shall be provided and installed in every theatre.

(b) The supports and installation of all tanks used to supply water to such system of standpipes and such automatic sprinkler system shall be subject to the approval of the Commissioner of Buildings.

411. Ice Making Machinery—Prohibition of.) It shall be unlawful to install any machinery or compressors of any description to be used in conjunction with ammonia in the manufacture of artificial ice in the auditorium or stage parts of any building of Class V, and it shall be unlawful to convey ammonia or to install any piping for the conveying of ammonia into any building of Class V for the purpose of manufacturing artificial ice from any machinery or compressors situated outside of any building of Class V.

412. Lighting Service Requirements—Class V—Hereafter Erected.) Gas or electricity or both may be used for illuminating purposes in buildings of Class V hereafter erected. Gas shall not be used in that part of the building known as the stage side of the proscenium wall. Provisions shall be made to properly light every portion of a building of this class and every outlet therefrom leading to the outside of the building and all open courts, passageways and emergency exits. Lights in vestibules, halls, corridors, passageways, stairways and other means of egress from the building and premises shall be on an independent circuit or service and shall be controlled separately and exclusively by a switch or shutoff located near the main entrance. In rooms, halls and auditoriums used for the purposes of this class, provisions shall be made to furnish a light supplied by gas

and a light supplied by electricity above if possible, otherwise closely adjoining every opening to an exit or to an emergency exit from the room, hall or auditorium.

Dressing Room Partitions.) Partitions forming dressing rooms shall be constructed of incombustible material, and such dressing rooms shall be properly ventilated.

414. Capacity—Certificate for License.) (a) The Commissioner of Buildings shall determine the number of persons which each room used for the purpose of Class V may accommodate according to the provisions of this chapter, and shall certify the same to the City Clerk. No more than the number so certified shall be allowed in such room at any one time.

(b) Before a license shall be issued for the operation of a theatre the Commissioner of Buildings shall first certify, in writing, that such theatre complies with the provisions of this chapter in every respect.

415. Scenery—Definition—Movable Scenery.) (a) "Scenery" as used in this chapter shall include all scenery, drop curtains, borders and wings which are constructed or made of cloth, canvas or combustible material, whether stationary or movable.

(b) "Movable Scenery" shall include all scenery, drop curtains, borders, and wings which are made movable for the purpose of changing an entire set of scenery and substituting another set during or between the various stage acts.

416. Changing from Class IV to Class V.) Whenever an existing Class IV theatre is changed into a Class V theatre, the same shall be made to comply with all of the provisions for Class V theatres hereafter erected.

ARTICLE IX.

Class VI.

417. Class VI Defined.) In Class VI shall be included every tenement and apartment house or building or portion thereof, which is used or intended to be used as a home or residence for two or more families living in separate apartments.

418. Requirements—General.) Every building of Class VI shall comply with the provisions of this chapter, and in addition to the general provisions shall comply with the following special provisions:

—Definition of "New Tenement House"
"Apartment"—"Yard"—"**Court**"—"Shaft"
"Public Hall"—"Stair Hall"—"**Basement**"
"Cellar"—"Story"—"**Solid Masonry**".

(a) "New tenement house" shall include every tenement, flat and apartment house hereafter erected and every tenement house which shall be increased or diminished in size or otherwise altered after its erection and every building now or hereafter in existence not now used as a tenement house but hereafter converted or altered to such use.

(b) "Apartment" is a room or suite of two or more rooms occupied or intended or designed to be occupied as a family domicile.

(c) "Yard" is an open unoccupied space on the same lot with a tenement house, separating every part of every building on the lot from the rear line of the lot.

(d) "Court" is an open, unoccupied, unobstructed space other than a yard, on the same lot with a tenement house; a court entirely surrounded by a tenement house is an "inner court"; a court bounded on one side and both ends by a tenement house, and on the remaining side by a lot line is a "lot line court"; a court extending to a street, alley or yard is an "outer court."

(e) "Shaft" includes exterior and interior shafts, whether for air, light, elevator, dumb waiter or any other purpose; a "vent shaft" is one used solely to ventilate or light a water closet compartment, bath room, or pantry.

(f) "Public Hall" is a hall, corridor or passageway not within an apartment.

(g) "Stair Hall" includes the stairs, stair landings and those portions of the public halls through which it is necessary to pass in getting from the entrance floor to the top story.

(h) "Basement" is a story partly, but not more than one-half below the level of the inside sidewalk grade of the street nearest the building. If the floor of such basement is less than two feet (2 ft.) below such grade or if the ceiling of such basement is more than seven feet, six inches (7 ft. 6 in.) above said grade, said story shall be classed as the first story of the building in which it occurs. Provided, however, that the ceiling height may be raised above the height of seven feet, six inches (7 ft. 6 in.) heretofore given, not more than one-third of an inch for every foot of such distance said building




Fig. 9.

DEFINITION OF BASEMENT, ETC. See 419.

- (A) Height of basement (above to ceiling).
- (B) Distance from street line against the building.
- (C) Distance from sidewalk grade.
- (D) Distance from ceiling of basement to ceiling of first story.
- (E) Distance from ground level to ceiling of basement.
- (F) Distance from ground level to ceiling of first story.
- (G) Distance from ground level to ceiling of second story.
- (H) Distance from ground level to ceiling of third story.

Explanation:

- (A) Basement is a story partly, but not more than one-half below the level of the inside sidewalk grade.
- (B) If the floor of basement is less than 2 ft. (2 ft.) below such grade, or if ceiling of such basement is more than 7' 6" (F) above said grade, said story shall be classed as first story.
- (C) The ceiling height of (D) may be raised not more than 1" for every 3' of distance.
- (E) Equals distance from ground to line of first floor.
- (F) For yard ground levels or walks or other improvements for a distance of 12' 0" at every point from all outside walls. (G) shall not be lower than 8' 3".

See 414.

- (A) Not to be less than 12". (See Sec. 506 for exceptions).
- (B) 12" (1 ft.) from street line.
- (C) 6" sand or cinders required.

is set back from the street line of the street nearest the building, but in no case shall any rise of ceiling be allowed for any distance beyond thirty feet (30 ft.) said building may be set back from the line of the street nearest the building, and in such cases all rises in the basement ceiling shall be computed according to the distance between the street line and the outside wall of

the building nearest to said street line. And further provided, that the yard or ground level, or walks, or other improvements thereon for a distance of twelve feet (12 ft.) at every point from all outside walls of said building shall not be lower than eight feet three inches (8 ft. 3 in.) below the floor level of the first story of said building.

(i) "Cellar" is a story more than one-half below the level of the inside sidewalk grade of the street nearest the building.

Where the grade of a street adjacent to a tenement house varies, the average grade of such street opposite the lot containing the tenement house shall be regarded as the grade of such street within the meaning of this chapter.

(j) "Story" is that portion of a building between the top of any floor beams and the top of the floor or ceiling beams next above.

420. Sections—Where Conflicting With Other Sections.) In cases of direct conflict with the provisions of other sections of this ordinance relating to other classes, the provisions of the sections relating to Class VI shall govern in respect to tenement houses.

421. Changes or Alterations—Permits.) Every new tenement house and every change or alteration in any existing tenement house shall conform to the requirements of this chapter. No new tenement house shall be begun, nor shall any changes or alterations in any existing tenement house, such as are referred to in this chapter, be begun until a permit therefor shall have been issued by the Commissioner of Buildings. Such permit shall be issued only upon an application by the person, firm or corporation for whom the building is to be erected or altered, and after approval of the plans and specifications for such tenement house or for such changes or alterations by the Commissioner of Health whenever such approval is required by the ordinances of the City of Chicago.

422. New Tenement House—When to be Occupied.) (a) No new tenement house shall be occupied in whole or in part for human habitation until the issuance of a certificate by the Commissioner of Health that said building conforms to the requirements of this chapter relative to light and ventilation, plumbing and drainage applicable to said buildings, nor until the issuance by the Commissioner of Buildings of a certificate that the said building conforms to the requirements of this chapter relative to fire escapes and means of egress applicable to new tenement houses. Within five days from date of application for any certificate above mentioned, such certificate shall be issued or the official concerned shall state in writing his reasons for his refusal to issue said certificate.

(b) The certificate above referred to may be issued in the case of a new tenement building comprising more than three apartments so as to allow the occupation of any section of the building extending from cellar to roof in advance of the completion of the other portions of the building.

(c) When the outer walls of a new tenement house have been erected so as to outline the position of the courts and shafts required for the lighting and ventilation of habitable rooms, the owner of the building or his representatives shall be entitled, upon application in writing, to an inspection of the same by the Commissioner of Buildings, and if the work to that point is in compliance with the provisions regarding the size of shafts and the location of the building, to a certificate setting forth those facts.

(d) When the work of constructing partitions has advanced to a degree on any floor, that the rooms on that floor are determined in their dimensions, the owner or his representatives shall be entitled to an inspection from the Commissioner of Build-

ings, and if the rooms thus outlined conform in their dimensions to the plans filed and to the requirements of this chapter, to a certificate stating that fact.

(e) If a new tenement house is occupied as a place of habitation in any of its parts in violation of this section, it shall forthwith be subject to notice from the Commissioner of Buildings and shall be vacated upon such notice and shall not again be occupied until made to conform with the provisions of this chapter nor until after the issuance of the two certificates required in this section.

423. Plat to be Filed.) At the time of applying for a permit for the erection of, alteration of, addition to or moving of a tenement house or for the erection, alteration, adding to or moving of any building upon a lot upon which a tenement house stands, the applicant shall submit to the Commissioner of Buildings a plat of the lot, showing the dimensions of the same and the position to be occupied by the proposed building or by the building to be altered or added to or by the building to be moved thereon, and the position of any other building or buildings that may be on the lot. The measurements shall in all cases be taken at the top of the first story and shall not include any portion of any street or alley.





Fig. 10.

424. Corner Lot Defined—Frontages.) By "corner lot" is meant a lot situated at the junction of two streets or of a street and a public alley at least sixteen feet wide, provided that if such alley be less than sixteen feet wide, and the lot be estimated on a line sixteen feet from the opposite side of the alley, such lot may be considered a corner lot. Any portion of the width of such lot distant more than fifty feet from such junction shall not be regarded as part of a corner lot, but shall be subject to the provisions of this chapter respecting other than corner lots. Where, in corner lots, the two frontages are of unequal length, the lesser street frontage shall be taken as the width of the lot. Street frontage alone, and not alley frontage shall be considered in determining such lesser frontage.

425. Height—How Measured.) (a) The height of a new tenement house shall not exceed by more than one-half the platted width of the widest street on which it abuts, and no existing tenement house shall be increased beyond such height.

(b) Provided, however, that any distance the building sets back from the lot line



PLAN

Fig. 11.

SECTION A-A


Height of Tenement House, How Measured.
A—width of widest street on this case 3rd St.
B—width of widest street on this case 2nd St.
C—distance tenement house No. 2 abuts.
D—distance tenement house No. 2 sets back from 2nd St.
D—width of 1st St., other street on which tenement house No. 2 abuts.
E—distance tenement house No. 2 sets back from 1st St.
F—allowable height, which in this illustration is measured as shown by the perpendicular distance from the inside sidewalk grade of the street nearest the building, to the highest point of the external bearing walls. For exceptions, where elevator enclosures and cornices or bulkheads are used, see Section 426, last paragraph.

Explanation:

1. Tenement house No. 1 shall not exceed 11 1/2 ft.
2. Tenement house No. 2 shall not exceed 11 1/2 ft.
3. Tenement house No. 3 shall not exceed 11 1/2 ft.
4. Tenement house No. 4 shall not exceed 11 1/2 ft.
5. Tenement house No. 5 shall not exceed 11 1/2 ft.

shall be added to the width of the street in making this computation. Such height shall be the perpendicular distance from the inside sidewalk grade of the street nearest the building to the highest point of the external bearing walls and shall not include any cornice or bulkhead less than eight feet high or any elevator enclosure less than sixteen feet high. Where such street grade varies, the mean or average grade thereof opposite such building shall be the data from which such height is measured.

426. **Distance Between Buildings.)** No existing tenement house shall hereafter be enlarged or its lot be diminished, so that the rear line of any building on such lot approaches nearer than ten feet to the rear line of the lot, unless the rear of the lot upon which it stands, abuts upon a public alley, in which case the rear line of such building shall be not less than sixteen feet from the opposite side of such alley. Where a tenement house, now existing or hereafter erected, stands upon a lot other than a corner lot, no other building shall hereafter be placed upon the front or rear of that lot, unless the minimum distance between such buildings be at least ten feet, if neither building exceeds the height of one story; or fifteen feet, if either building exceeds the height of one story, but not the height of two stories, and so on, five additional feet to



PLAN

Fig. 12.




Fig. 13.

SECTION A-A

A—height from the base of addition to present tenement house No. 1, to rear line of lot.

B—distance from rear line of addition, to present tenement house No. 2, to rear line of lot, abutting public alley.

C—distance from rear line of addition, to present tenement house No. 2, to opposite side of such alley.

D—distance from present tenement house No. 3, standing on an inner lot, to new building.

Explanation:

A shall not be less than 10 ft. either by addition to, or diminishing present tenement house No. 1.

If B is less than 10 ft., then C must not be less than 16 ft. Sections a, b, c, are explanatory diagrams of different cases of required distances D, between tenement house No. 3 and new house. Exception to this rule is stated in last paragraph of Section 426.

be added to such minimum distance of ten feet for every story more than one, in the height of the highest building on such lot; Provided, that a one-story building without basement, and not used for habitation, may be placed on the rear of a lot containing a tenement house, if a minimum distance of ten feet is maintained between every point of such building and the tenement house.

427. **Percentage of Area Allowed to be Covered.** No existing tenement house shall hereafter be enlarged nor its lot be diminished, nor other buildings be placed on its lot, nor a tenement house be moved on a lot on which there is an existing building, so that after such change a larger proportion of any corner lot or other lot upon which it is situated is covered by buildings, than the following proportions, respectively: No new tenement house alone or with other buildings now or hereafter erected, shall occupy above the first story more than eighty-five per centum of the area of a corner lot, provided that in the case of a fireproof building, in which the windows of every habitable room open directly on a street, the portion of the lot covered may be ninety per centum of the area of said lot, subject to the requirement that a ten foot space must be left above the first story opposite the lesser frontage; or more than ninety per centum of the area of such corner lot if such corner lot is bounded on at least three sides by streets or alleys; or more than seventy-five per centum of the area of any other lot, provided that the space occupied by fire escapes, constructed and erected according to law and not more than four feet wide, shall be deemed unoccupied. Provided, however, that in case of a lot, triangular or irregular in shape bounded on two or more sides by a street and having a number of lineal feet street frontage exceeding one-twentieth of the number of square feet in the area of such lot, it shall not be necessary to comply with the conditions of this section as to percentage of lot which may be covered.

428. **Must Have Alley or Yard in Rear—Size of Yard Increased.** At the rear of every lot containing a tenement house, there shall be a yard open and unobstructed from the earth to the sky, except by fire escapes not more than four feet wide, constructed and erected according to law, unless the rear of such lot abuts upon a public alley at least ten feet wide, in which case the rear line of such building shall be not less than 16 feet from the opposite side of such alley; every part of such yard shall be directly accessible from every other part thereof; such yard shall have an area of at least eight per centum of the superficial area of the lot on corner lots except as otherwise provided in this section; and on other lots, such yards shall have an area of at least ten per centum of the superficial area of the lot. Every such yard shall be increased one per centum of the superficial area of the lot for every story above three stories in height of the tenement house situated thereon.

429. **Courts—Inner—Outer—Lot Line.)** (a) "Inner courts" of all new tenement houses as defined in Section 419 of this ordinance, shall have minimum widths at every point and minimum areas as follows:

Courts—	Least width	Least area
Height of	in feet	in square feet.
1 story	6	100
2 stories	6	120
3 stories	8	160
4 stories	8	160
5 stories	12	260
6 stories	16	400
7 stories	20	625
8 stories or more	24	840

(b) The height of a court shall be the number of stories having habitable rooms with windows in its walls.

(c) "Outer courts" and "lot line courts" of all new tenement houses as defined in Section 419 of this chapter shall have minimum widths at every point equal to one-half of the minimum widths required by this section, and lot line courts shall have minimum areas equal to one-half of the minimum areas required herein for "inner courts." If an outer court or lot line court has windows on opposite sides, its minimum width shall conform to the width given in the table.

(d) The minimum widths hereinbefore specified for outer courts and the minimum widths and areas specified for lot line courts are to be provided irrespective of the presence of or dimensions of courts on other premises bounded by the same lot line.

(e) Every "inner court" and every "lot line court" of every new tenement shall be connected directly with a street, alley, yard, or outer court by an opening extending from grade at the building to a height of at least fifteen feet, and kept unobstructed save by an openwork grill or gate, such opening to be at least two feet wide for an inner court and one foot wide for a lot line court. In case of a three-story tenement on a lot twenty-five feet or less in width, a continuous lot line passage open to the sky, and six inches in width, shall be accepted for the opening specified above as one foot wide for a lot line court. If such inner court or lot line court starts from any point above finished grade at building, such starting point shall be considered as grade for purpose of determining the location of the opening to outer air herein specified.

(f) In case of a three-story tenement on a lot of twenty-five feet or less in width a continuous lot line passage open to the sky, and at least three feet wide, shall be accepted in lieu of a lot line court or outer court hereinbefore specified in Paragraph (a). In case of a three-story tenement on a lot thirty feet or less in width, a continuous lot line passage open to the sky, and at least three feet six inches wide shall be accepted in lieu of a lot line court or outer court hereinbefore specified in Paragraph (a).

(g) In case of a two-story tenement on a lot twenty-five feet or less in width, a lot line court having an area of at least fifty square feet shall be accepted in lieu of a lot line court heretofore specified in Paragraph (a) of this section, and in case of a three-story tenement on a lot of twenty-five feet or less in width, a lot line court having an area of at least sixty square feet shall be accepted in lieu of a lot line court hereinbefore specified and required by Paragraph (a) of this section.

(h) In case of two or three-story tenement buildings on lots twenty-five feet or less in width, where there is only one apartment on each story containing not more than four rooms in such apartment, the light courts hereinbefore specified in Paragraph (a) may be omitted, provided there is a continuous passageway open to the sky and not less than three feet wide on one side of said building.

430. **Vent Shafts—Area Of.)** (a) "Vent shafts" of all new tenement houses, as defined in Section 441 of this ordinance, shall have minimum widths at every point and minimum areas as follows:

Vent shafts	Least width	Least area
Height of	in feet	in square feet.
1 story	3	21
2 stories	3	22½
3 stories	3	27
4 stories	3	36
5 stories	5	48
6 stories	6	72
7 stories	8	96
8 stories or more	8	120

(b) Every such vent shaft in every new tenement house more than two stories high, shall be connected directly with a street, alley, yard or court by one or more horizontal ducts or intakes at a level not lower than the finished grade of building nor higher than second story floor; the total area of such ducts to be not less than three per cent of the area of such vent shaft, and no single duct to be of less area than one hundred square inches; such total and individual duct area shall be net over and above all obstructions.

431. Stair Hall and Shaft—Well-Hole Dimensions.) (a) Every public stair hall in every new tenement house shall, for each story, have a window of an area of at least twelve square feet, opening directly on a street, alley, yard or court; or on a shaft of minimum area, as hereinafter provided; or shall have an unobstructed vertical well-hole of the following minimum area at each floor line above the first, and, directly over such well-hole, there shall be a skylight of twice the following minimum area:

Building— Least area in square feet of Height of stair shaft or well hole.

2 stories—if there is more than one apartment on a floor.....	8
3 stories—if there is more than one apartment on a floor.....	13
4 stories	19
5 stories	25
6 stories or more.....	33

(b) Such window, if any, shall be so placed that light may pass directly to the opposite end of the hall, or else there shall be at least one window opening directly upon a street, alley, yard or court in every twenty feet in length or fraction thereof of such hall, except in so much of any entrance hall as lies between the entrance and the flight of stairs nearest the entrance. In any such public hall, recesses or returns, the length of which does not exceed twice the width of the hall, will be permitted, without an additional window, but, otherwise, each recess or return shall be regarded for the purposes of this section as if it were a separate hall. Any part of a public hall which is shut off from any other part by a door or doors shall be deemed a separate public hall within the meaning of this section.

(c) Skylights shall be ventilating skylights and shall have over them a wire netting mounted on wire frame and 6-inch iron legs, of wire not lighter than No. 12 and with mesh not coarser than one inch by one inch, unless constructed of wired glass or prismatic light glass.

432. Rooms—Sizes and Height Of—Attic Rooms.) (a) In every new tenement house, all habitable rooms shall be of the following minimum sizes:

(b) In each apartment, there shall be at least one room containing not less than one hundred twenty square feet of floor area, and every other room shall contain at least eighty square feet of floor area, provided, however, that in the case of a room having a window not less than eighteen feet in area opening upon a public street, the floor area need not be greater than seventy feet. Each room shall be in every part not less than eight feet six inches high from the finished floor to the finished ceiling; provided, however, an attic room need be eight feet six inches high in but one-half of its area, provided there are not less than 750 cubic feet of air space therein.

433. Alcoves and Alcove Rooms.) (a) For the purpose of buildings of Classes III and IV, an alcove shall be defined as a recess connected with or at the side of a larger room. The floor of such an alcove shall be counted as a part of the floor area

and its cubic contents as a part of the cubic contents of the room with which it is connected.

(b) In every new tenement house every alcove shall be deemed a separate room for all purposes within the meaning of this chapter, except an alcove that has a floor area of not to exceed thirty-five square feet and that has an unobstructed opening, equal in area to twenty per centum of its entire wall surface, into an adjoining habitable room; provided that in constructing additional habitable rooms by raising or altering existing one story dwellings, the limitation of the floor area of an alcove may be disregarded, provided such alcove has an unobstructed opening, equal to the floor area of such alcove, into an adjoining habitable room.

(c) This section shall not be construed as forbidding the erection of pilasters or other decorative effects projecting not more than eighteen inches from the plane of the wall of a habitable room.

(d) No part of any room in a tenement house shall be enclosed or sub-divided at any time, wholly or in part, by a curtain, portiere, fixed or movable partition or other contrivances or device, unless each part of the room so enclosed or sub-divided shall contain a separate window as herein required, and shall have a floor area of not less than 80 square feet as herein required for habitable rooms, except as heretofore provided in this section.

434. Air—Quantity of for Each Person.) No room in any tenement house shall be occupied so that the allowance of air to each adult person living or sleeping in such room shall at any time be less than four hundred cubic feet or less than two hundred cubic feet for each person under twelve years of age.

435. Habitable Rooms—Bath Rooms—Pantry—Requirement as to Ventilation and Lighting.) (a) In every new tenement house every habitable room shall have a window or windows with a total glass area equal to at least one-tenth of its floor area opening onto a street, alley, yard or court. None of such required windows shall have a glass area of less than ten square feet, and each such window shall have its top not less than seven feet above the floor and shall be so constructed that at least its upper half may be opened its full width.

(b) In every new tenement house every bath room, water closet, or urinal compartment shall have at least one window with a glass area of at least six square feet and a minimum width of one foot, opening upon a street, alley, yard, court or vent shaft.

(c) In every new tenement house every pantry shall have at least one window of not less than six square feet in area, with a width of not less than one foot, opening into a street, alley, yard, court or vent shaft, which vent shaft shall be at least six square feet in area.

(See Illustration Sec. 258b.)

436. New Tenements—Habitable Rooms in Basements—Prohibited in Cellars.) In no new tenement house shall any room in the cellar be constructed, altered, converted or occupied for living purposes; and no room in the basement of a new tenement house shall be constructed, altered, converted or occupied for living purposes unless such rooms shall be at least eight feet six inches high in the clear and shall have at least one-half of such height above the finished grade of said premises at the building, and at least four feet three inches of such height above the average street grade at the building. "Provided that only (1) living apartment not exceeding six (6) rooms shall be allowed in the basement of any tenement house hereafter to be constructed."

437. Tenement Houses—Requirements for Fireproof and Slow-burning Construction.) Every new tenement house more than five stories and basement high shall be of fireproof construction. Every new tenement house more than three stories and basement high, but not more than five stories and basement high shall be of slow-burning or fireproof construction. In case slow-burning construction be required, the cellar and basement construction, including the floor construction of the first story above the cellar or basement, shall be of fireproof construction.

438. Frame Tenement—Requirements.) In every new frame tenement house outside the fire limits, each suite of apartments shall be separated from the next suite in such building by a partition of four-inch tile or of metal studding and metal lath, and the enclosing walls around the stairs, where there are two or more apartments on a floor, shall be of fireproof construction or of solid masonry of the same dimensions as are required by Section 506.

439. Frame Additions to Frame Tenement Houses Within Fire Limits Not Permitted—removal of Frame Tenement Houses.) No frame addition shall be permitted to any frame tenement house within the fire limits, either by adding to its height or its superficial area.

If a tenement house, standing on wooden supports, is moved to another lot, it shall not again be placed on wooden supports, but shall be placed on a masonry or concrete foundation.

If a frame tenement house, not more than two stories high, is moved from one location to another upon the same lot, it may be set upon wooden posts and a basement or cellar not to exceed six feet six inches in height from the floor to the ceiling thereof may be maintained thereunder, and no habitable rooms shall be constructed or occupied in said basement or cellar.

440. Entrance Halls—Solid Masonry—Exceptions—Ceilings.) Every main entrance hall in a new tenement house shall be at least three feet six inches wide in the clear from the entrance up to and including the stair enclosure and beyond this point at least three feet wide in the clear. In every new non-fireproof tenement house, except where there be only one apartment on each floor, such entrance hall shall be inclosed with solid masonry walls and with ceilings covered with incombustible material and shall comply with all the conditions of the following sections of this ordinance as to the construction of stair halls. If such main entrance is the only entrance to more than one flight of stairs, the several portions of such main entrance hall which separate the entrance of the building from the several flights of stairs, respectively, shall be increased respectively at least one foot in width for each additional flight of stairs.

441. Stair Halls—Construction Of.) The stairs and stair halls in all new tenement houses more than three stories and basement or cellar high shall be constructed of incombustible material throughout, except that the treads of stairs may be of wood not less than one and three-eighths inches thick and all handrails may be of hardwood.

(b) In every new non-fireproof tenement house all stair halls shall be enclosed on all sides with walls of solid masonry of the dimensions required by Section 506. All windows in stair halls, except where same open into a street, alley, outer court, or yard, shall have metal frames and sashes, glazed with wired glass. This section shall not apply to tenement houses which are not more than three stories and basement high with only one apartment on each floor. Where the main entrance vestibule and all





Fig. 14.



SECTION A-A · SECTION B-B ·

Fig. 15.

SECTION 441 B.

Beginning, where the main entrance vestibule, etc. If walls F H G I, also floor and ceiling of entrance hall A, and floors and ceiling of vestibule B, are of fireproof construction, and door C is a fireproof door with fireproof frames, the vestibule B may be built 2' above level of outside grade without changing the definition of the word "basement" see section 419.

Doors C and D do not have to be fireproof see section AA and BB for condition at hand.

trance hall or corridor of said building, including the floor and ceiling thereof, are of fireproof construction as defined in this chapter, from the outside face of the building at said entrance to and including the floor of stair hall, and all doors leading therefrom or thereto except the street doors are fire retarding doors, the floor of said entrance and vestibule may be built at a level of two inches (2 in.) above the level of the outside grade of the building at the entrance of same, without changing the definition of the word "Basement" with regard to height of floors, as contained in Section 419 of The Chicago Code of 1911, as amended.

(See Illustration Sec. 439E.)

442. Apartments Divided by Masonry.)

(a) There shall be a wall of solid masonry of thickness as required by Section 506 extending from the ground to the roof between each set of apartments and around each court and each light shaft, except as hereinafter provided; (a) provided, however, that a wall between apartments and extending from the main stair hall to the outer wall of the building may be offset at the second story floor line to some point nearer the center of the building, or of the group of apartments, to admit of an even

distribution of space in the rooms adjacent to such wall, if such wall is supported at the second story floor line on fireproofed steel or iron beams which extend from the brick wall surrounding the main stair hall to the outer wall of the building; and provided, further, that such offset wall may be reduced to the thickness of eight inches, if supported at each floor line above the first story on fireproofed steel or iron beams carried by masonry walls as above specified; (b) and provided, however, that, in case there is a store or stores in the first story of a building of this class, a masonry dividing wall between apartments may begin at the second story floor line, if such dividing line wall is supported on fireproofed steel or iron beams carried by masonry; and provided, further, that such dividing wall may be reduced to the thickness of eight inches, if supported at each floor line above the first story on fireproofed steel or iron beams carried by masonry. And provided that in buildings of fireproof construction the partitions between apartments, and around stairs may be of burnt clay tile not less than three inches in thickness or reinforced concrete partitions not less than three inches in thickness.

(b) In buildings of ordinary construction two separate thicknesses of metal lath and fire-resisting plaster shall be used as fireproofing as required by this section.

442. Ceilings Over Stores—Courts and Shafts Beginning Above First Story.) (a) In every new non-fireproof tenement house in which there is a store or stores in the first story, if the building is three stories or less in height, the portions of the first story ceiling directly under all public halls shall be of slow-burning construction, and if the building is four or more stories in height the entire basement and first story construction and the second story floor construction shall be of fireproof construction.

(b) In every new non-fireproof tenement house the masonry walls enclosing every court or light or vent shaft beginning above the first story shall be supported on fireproofed steel or iron beams carried by masonry or by fireproofed steel or iron columns; and such court or shaft enclosing walls may be reduced to the thickness of eight inches if supported at every intersecting floor line on fireproofed steel or iron beams carried as above specified.

444. Damp-Proofing—Basement Walls to Be Masonry—Cement Floor.) In every new tenement house constructed of brick or frame, the foundations and basement walls shall be built of masonry or concrete not less than twelve inches in thickness, except as provided in Section 506 and shall have all outside walls below the adjacent ground level plastered on the outside with Portland cement or treated with other approved damp-proofing material, and such walls, as high as the ground level, shall be laid in cement mortar. The basement or cellar of every existing and new tenement house shall have a floor of Portland cement concrete not less than three inches in thickness laid on not less than six inches of sand or cinders.

(See Illustration See. 449.)

445. Bay Windows—Courts—Vent Shafts.) (a) The walls of every bay window and every court in masonry constructed new tenement houses shall be built of brick or other fireproof construction as required for exterior walls.

(b) The walls of every interior vent shaft in masonry constructed tenement houses shall be built of masonry or of fireproof material not less than four inches in thickness, supported by steel or iron.

446. Porches.) (a) Where porches are constructed in courts of now existing or new

tenement houses, the amount of area of unobstructed space in such courts shall be exclusive of space occupied by stairs and porches. No additional rear porch shall be constructed on any existing tenement house in such way that the buildings on the lot with all their porches shall occupy a greater proportion of the lot than is permitted in Section 427 of this chapter. No rear porch on any existing tenement house where the total area of buildings and all porches exceeds the proportion of the lot permitted in Section 427 of this chapter shall be reconstructed until the plan for such reconstruction shall have been submitted to and approved by the Commissioner of Buildings. No rear porch built of combustible materials and more than eight feet in width, excepting stairways, shall be constructed on any new tenement house nor added to, nor reconstructed on any existing tenement house.

(b) Front porches of buildings in existence at the time of the passage of this amendatory ordinance may be enclosed temporarily from the first day of November in each year to the first day of the following May with wood sash glazed with ordinary glass; provided that the glass area shall be as large as is consistent with good construction and the ordinances of the city; and further provided, that the sashes are fitted with hinges or hung in such a manner as to allow them to open at least one-half of their area, or that one-half of all the sash installed are so fitted or hung as to open their entire area, and the area of such open sash shall be at least twice the area of all windows from adjacent rooms opening on to porches so enclosed, unless such room adjoining said porch shall have windows opening on to a street, alley, yard or court of proper legal dimensions as required by this chapter for habitable rooms in addition to the windows opening on to the porch, in which case the amount of movable sash in porch enclosure shall be not less than ten per cent of the floor area of said porch and in no case less than ten square feet of glass area.

(c) Rear porches and side porches of buildings in existence at the time of the passage of this amendatory ordinance, where every part of said porch is at least ten feet distant from any other building, porch or structure located upon the same lot with the building of which such porch is a part, may be enclosed temporarily from the first day of November in each year to the first day of the following May with wood sash glazed with ordinary glass; provided, that the glass area of the enclosure shall be as large as is consistent with good construction and the ordinances of the city; and further provided, that the sashes are fitted with hinges or hung in such a manner as to allow them to open at least one-half their area, or that one-half of all the sash installed are so fitted or hung as to open their entire area, and in no case shall be less than three times the area of all windows, doors and transoms opening on to said porch, and that in every case the top of the sash in such enclosure shall be at least six inches higher than the top of the windows and doors opening on to such porch. The framing of the porch enclosure may be of wood, and the glass area of each side and of each end of such porch shall be not less than fifty per cent of the entire side or end of such porch enclosure measured from the floor of the porch to the under side of joists immediately above such porch in each story.

(d) In every building erected after the passage of this amendatory ordinance, every front porch, rear porch or side porch which is intended to be enclosed must have enclosing walls as required by the ordinances of the city for enclosing walls of a building of the type of which said porch is a part, and every porch so enclosed shall be considered a separate habitable room and shall comply with all the requirements of this

chapter for habitable rooms, and such porch enclosure shall not in any manner intercept the light or the ventilation of any adjoining room.

(e) Where buildings do not exceed three stories in height the stairways in rear porches may be partially enclosed as follows; the end of the porch outside the stairway, also the back of the porch around said stairway not to exceed eleven feet in extent, may be enclosed with wood or frame construction and a window with glass area of nine square feet shall be placed in the back enclosure or in that part of the porch facing the yard or court on each story.

447. Flues and Chimneys.) In every building used for the purposes of Class VI, the flues or chimneys shall conform to the following regulations: For one stove opening, the flue area shall not be less than forty-nine square inches. For more than one stove opening and one furnace opening, the flue area shall not be less than seventy-seven square inches. All such flues shall be constructed according to the requirements of Section 570 of this chapter.

448. Bulkhead in Roof—Construction of—When Required.) There shall be in the roof of every new tenement house, unless the pitch of the roof thereof exceeds one foot rise in four foot run, at least one bulkhead or scuttle, fireproof or covered with fireproof material, with stairs or ladder leading thereto; no such roof opening shall be less than two feet by three feet. Where such tenement house is provided with rear stairs, there shall be a bulkhead or scuttle accessible from each of such rear stairs. No scuttle or bulkhead door shall have any lock on it but may be fastened on the inside by movable bolts or hooks.

449. Stairways—Width and Construction of.) (a) Every now existing and every new tenement house shall have at least two flights of stairs, which shall extend from the entrance floor to the top story, and which stairs shall be as far apart as practicable. One of said stairways shall be an interior stairway. Such stairs and the public halls in every tenement house shall each be at least three feet wide in the clear, and every apartment shall be directly accessible from both such flights of stairs without going through any other apartment. An apartment whose gross floor area does not exceed 1,000 square feet and having not to exceed six habitable rooms in an existing tenement house and which at the time of the passage of this ordinance had not access to two stairways, may have exit to a second stairway through another apartment, providing the door between the two apartments is equipped with a glass panel not less than five feet high and twenty inches wide, with the bottom of same not less than eighteen inches above the floor. Or where the floor level of said apartment is not more than twelve feet above the surface of the yard or ground surrounding the building, a balcony with an area not less than eighteen square feet equipped with a drop ladder to the ground may be attached to the outside wall of said building accessible by a door or window from such apartment and may be considered as a secondary means of exit from said apartment, if in the judgment of the Commissioner of Buildings such glass panel door, balcony and ladder will afford safe means of exit for any such apartment. Where halls or stairs in an existing tenement house have been damaged by fire or otherwise to an extent greater than one-half the value thereof, such halls or stairs so damaged shall be repaired so as to conform to the requirements of this chapter with regard to halls and stairways relating to new tenement houses.

(b) All enclosed stairs in every tenement house shall have at least one handrail, and where the width of such stairs is

greater than 3 feet 6 inches, such stairs shall have a handrail on each side thereof. All open stairs shall be provided with suitable and substantial handrails on each side.

(See Illustration Sec. 398.)

450. Stairs in Non-Fireproof Buildings, Eighty or More Rooms.) Every new non-fireproof tenement house containing over eighty rooms, exclusive of bath rooms, shall have one additional flight of stairs, over and above the flights hereinbefore provided for, for every additional eighty rooms, or fraction thereof; but if such building contains not more than one hundred and twenty rooms, exclusive of bath rooms, at the owner's option, in lieu of an additional stairway, the stairs and public halls throughout the entire building shall be at least one-half wider than is provided in this chapter.

451. Stairs in Fireproof Buildings, One Hundred and Twenty Rooms and Upward.) Every new fireproof tenement house containing over one hundred and twenty rooms, exclusive of bath rooms, shall have one additional flight of stairs, over and above the flights hereinbefore provided for, for every additional one hundred and twenty rooms or fraction thereof; but if such building contains not more than one hundred and eighty rooms, exclusive of bath rooms, at the owner's option, in lieu of an additional stairway, the stairs and public halls throughout the entire building may be made at least one-half wider than is provided in this chapter.

452. Stairs—Entrance to—Treads and Risers.) Every flight of stairs required in a tenement house shall have an entrance on the entrance floor from a street or alley, or from a yard or court which opens into a street or alley. All stairs except rear stairs, in new tenement houses, shall have risers not more than seven and three-quarters inches high and treads not less than nine and one-half inches wide exclusive of nosings, except in winding stairs, where all treads at a point eighteen inches from the strings on the well side shall be at least nine and one-half inches wide, exclusive of nosings.

(See Illustration Sec. 398.)

453. Fire Escapes.) Every tenement house four or more stories in height shall be provided with a fire escape or fire escapes, such as are required by this chapter. In every case each separate apartment shall have direct access to at least one such fire escape unless such apartment shall have direct access, without passing through any other apartment, to at least two separate flights of stairs leading to the ground, one of which is placed in front and one in the rear of such building, and one of which may be placed outside of the building; but where such separate apartment shall not have access to two such flights of stairs, then such apartment shall have direct access to a stairway fire escape. Every court in which there is a fire escape shall have direct and unobstructed access along the surface of the ground to a street or alley or to yard opening into an alley or street without entering into or passing through or over any building unless by a four foot wide fireproof passage on the court or ground level. Except as herein specifically provided, the number, location, material and construction of fire escapes shall be controlled by the general provisions of this chapter on fire escapes.

454. Shafts, Courts, Yards, Graded—Concrete—Drained.) In every now existing and new tenement house, the bottom of all shafts, courts or yards shall be provided with sanitary drainage and shall be graded or paved.

455. Access to Rooms—Otherwise than Through Bedroom.) In each apartment in every new tenement house, access to every

water closet and bathroom and to at least one water closet compartment shall be had without passing through any bedroom.

Water Closets—Windows in—Artificial Light.) (a) In every new tenement house there shall be a separate water closet in a separate compartment within each apartment, except that where there are apartments consisting of only one or two rooms, in which case there shall be at least one water closet for every two apartments.

(b) Every water closet compartment in every existing tenement house shall be ventilated by such a window, or else by a vent shaft of at least one-half the minimum area required in Section 439. Every water closet compartment in every tenement house shall be provided with proper means of artificially lighting the same. If fixtures for gas or electricity are not provided in any such compartment, then the door thereof shall have ground glass panels or transoms.

Sinks—Requirements.) In every new tenement house there shall be in each apartment at least one kitchen sink with running water. In every existing tenement if there be not one such sink in each apartment there shall be on every floor at least one kitchen sink with running water, accessible to all the tenants of the floor, without passing through any other apartment. In no tenement house shall there be wood-work inclosing sinks; the space underneath sinks shall be left entirely open.

Pipes Through Floors—Catch Basins—Water Closets.) (a) In every new tenement house where plumbing or other pipes pass through floors or partitions, the openings around such pipes shall be sealed tight with plaster or other incombustible material, so as to prevent the passage of air or the spread of fire from one floor to another or from room to room.

(b) In the premises of a tenement house the catchbasin shall, whenever practicable, be placed in a court or yard, and shall be covered with a stone or iron cover, flush with the surface so that access to such basin shall be convenient.

(c) Where it is for any reason impracticable to place a catchbasin in a court or yard, the Commissioner of Health may authorize the use of an iron catchbasin with air-tight cover, located in the cellar or basement.

Buildings Damaged by Fire, Etc.) If any existing tenement house is hereafter damaged by fire or other cause, including ordinary wear, so that at any time its value be less than one-half its original value exclusive of the value of the foundations, such building shall not be repaired or rebuilt except in conformity with the provisions of this ordinance applicable to new tenement houses.

Provisions of this Article Not to Apply to Existing Buildings, Except Under Certain Circumstances—Then Commissioner to Notify.) (a) Nothing in this Article contained shall be construed as requiring alterations in the construction or equipment of buildings in existence at the time of the passage of this Article and which at the time of their construction were built in compliance with the ordinances then in force, unless they are in conflict with the requirements of Sections 434, 453, 457, 462, 463, 464, 454, (475) or unless such buildings shall not have sufficient or adequate means of egress therefrom, by reason of insufficient or inadequate stairways, improperly located or insufficient or inadequate elevators or elevator equipment, doors, fire escapes, windows or other means of egress or ingress.

(b) Where it shall appear to the Commissioner of Buildings that any such building has insufficient means of egress there-

from as aforesaid, he shall notify the owner, agent or person in possession, charge or control of such building of such fact and direct him forthwith to make such alterations and changes in the construction or equipment of such building, as are necessary to be made in order to promote the safety of the occupants of such building and of persons using the same and of the public.

Rooms and Halls—Additional.) Every room or hall that may hereafter be constructed or created in an existing tenement house shall comply in all respects with the provisions of this ordinance as to size, arrangement, light and ventilation of rooms and halls.

Rooms—Change in Existing.) No room in any now existing tenement house shall hereafter be constructed, altered, converted or occupied for living purposes, unless it contains a window having a superficial area not less than one-twelfth of the floor area of the room, which window shall open upon a street or alley or upon a yard or court having a superficial area of not less than twenty-five square feet and a minimum width of not less than two feet six inches, or unless such room adjoins another room in the same apartment, which other room shall have such a window opening upon such a street, alley, yard or court, between which two adjoining rooms there shall be an alcove opening equal in extent to at least 20 per cent of the entire wall surface of said room, provided, however, that all of the requirements of Sections 426 and 427 of the Chicago Code of 1911 shall be complied with.

Where a frame tenement house is moved from one lot to another, or from one location to another on the same lot, it shall comply with the provisions of Section 439 of this Chapter.

(See Illustration See, 2580.)

Windows—Courts—Attic.) No room in any now existing tenement house, which has no such window as aforesaid, opening upon a street or alley or upon a yard or court having a superficial area of not less than twenty-five square feet, shall hereafter be constructed, altered, converted or occupied for living purposes, unless it contains a floor area of at least sixty square feet and also at least six hundred cubic feet of air space; nor unless every part of the finished ceiling of such room be at least seven feet six inches distant from every part of the finished floor thereof; provided, that an attic room need be seven feet six inches high in but one-half of its area, and, provided, further, that such attic room has not less than seven hundred fifty cubic feet of air space therein; and such attic room shall not be used for purposes of human habitation other than as a sleeping room.

(See Illustration See, 2580.)

Existing Tenements—Living Rooms in Cellars or Basements—When Permitted.)

(a) In every existing tenement house, no room in an existing cellar or basement shall be occupied for living purposes unless such room shall be at least seven feet six inches high in the clear, and have not more than four feet eight inches of such cellar or basement below the finished grade at building; provided that no such room shall be used for living purposes unless such room shall have a window opening upon a street, alley, yard or court, and, provided, that when the windows of any living room front solely upon a street and the floor of such basement is four feet eight inches below the sidewalk grade, such windows shall be located not less than three feet back of the lot line; provided, however, that in every case where the height of ceiling of any living room is less than eight feet six inches in the clear, the window area of such room shall be at least 15 per centum of the floor area.

(b) When a brick or frame tenement house is moved from one lot to another, or from one location to another on the same lot and a basement or story, or both, is constructed under the same, the total height of which is more than six feet six inches from the floor to the ceiling, the walls of such basement shall be constructed of masonry according to the provisions of Section 644 of The Chicago Code of 1911, and the habitable rooms therein shall comply with the provisions of Section 462 of The Chicago Code of 1911, and the space on the lot shall comply with the provisions of Section 427 and Section 417 of The Chicago Code of 1911.

465. Insanitary Conditions — Nuisance.) A tenement house or part thereof which is in an insanitary condition by reason of the basement or cellar being damp or wet, or by reason of the floor of such basement or cellar being covered with stagnant water or by reason of the presence of sewer gas, or by reason of any portion of such building being infected with disease, or being unfit for human habitation, or which by reason of any other insanitary condition is a source of producing sickness among the inhabitants of this city, or which in any way endangers the public health, is hereby declared to constitute a public nuisance.

ARTICLE X.

Class VII.

466. Class VII Defined.) In Class VII shall be included every building used for the sale at retail of dry goods and other articles of general merchandise and commonly known and described as a department store.

467. Must Comply With General and Special Provisions.) Every building of Class VII shall comply with the general provisions of this chapter, and, in addition to the general provisions, shall comply with the following special provisions:

468. Buildings of Class VII—Construction of.) Buildings three stories or less in height, used either wholly or in part for the purpose of Class VII, may be of ordinary construction. Such buildings more than three and not exceeding five stories in height shall be of slow-burning, mill or fireproof construction. Such buildings over five stories in height shall be of fireproof construction.

469. Stores Used for Retail Sale of Goods or Manufacturing Purposes—Occupation of Basement—Lockers.) (a) Not more than the lower twelve stories above the street grade shall be used for the retail sale of goods, or for locker provisions in excess of accommodations for the number of employees on the floor on which they are employed, or for manufacturing purposes in a building devoted wholly or in part to purposes of Class VII except as hereinafter provided; provided, however, the stories above the twelfth story may be used for these or other purposes when equipped with an approved automatic sprinkler system approved further by the Chief of Fire Prevention and Public Safety; and provided, that all such buildings hereafter erected to be used for these purposes, or so used, above the twelfth story shall in addition to being equipped with an approved automatic sprinkling system have enclosed stairways.

(b) Not more than one floor of any basement or cellar shall be used for the retail sale of goods. Such floor shall be the floor nearest to the inside street grade. Such floor used for the retail sale of goods shall not be more than twenty feet below the inside street grade: Provided, however, that in all existing buildings of fireproof construction having a floor not more than thirty-two feet

below the inside street grade, and having a partial intermediate floor or gallery between such floor and the level of the inside street grade, with an opening through such intermediate floor not less than forty feet by forty feet in area, and having direct exits on such floor and intermediate floor or gallery connecting on substantially the same levels with the floors of adjacent buildings of fireproof construction, the retail sale of goods shall be permitted on such floors not more than thirty-two feet below the inside street grade if such floors shall be properly and thoroughly ventilated and mechanically supplied with not less than two thousand cubic feet of air per hour for each twenty square feet of floor area, exclusive of walls, stairs and elevators, and if such buildings are equipped throughout and on such floors below the inside street grade with an automatic sprinkler system approved by the Chief of Fire Prevention and Public Safety, and if the number and character of stairways and emergency exits comply with the provisions of this chapter applicable to buildings of Class VII of fireproof construction; and further provided, that in addition to the foregoing requirements there shall be at least one fireproof stairway enclosed in a fireproof tower extending from such sub-basement to the first floor of such building with no openings into said tower except from the sub-basement and first floor.

(c) Except as above provided in paragraph (b) of this section in relation to existing buildings, no sub-basement, cellar or part of a basement below such floor shall be used for the sale of any goods in any manner, but locker and dressing rooms may be placed in the sub-basement, provided the space thus occupied be separated from the remainder of the basement by fireproof partitions, and that there be at least two flights of stairs placed as far apart as practicable leading therefrom to the first floor, enclosed in fireproof partitions. Such stairs from such locker or dressing rooms shall be, in addition to other stairways required by this chapter for such buildings, and at least one of such stairways shall open directly on a street, alley or court opening on a street or alley, or on a fireproof passage leading to the street, alley or such court. Where more than five lockers are in one room, such lockers shall be of incombustible material.

(d) Where stories above the twelfth story are used for the purposes of Class VII as hereinbefore described for locker provisions in excess of accommodations for employees on the floor on which they are employed, then the stairways from the first to the topmost floor shall be built and enclosed as described in Section 652, but the stairways shall be in number and aggregate width as required in the table for stairways set forth in Section 650 of this chapter.

NOTE: Section 469 was amended July 6, 1917, but through error given section number "480."

470. Floor Areas—Maximum.) (a) The floor area, except as hereinafter provided, of any one story or portion of a story used for the purposes of Class VII of any building of ordinary construction shall not exceed nine thousand square feet.

(b) The floor area, except as hereinafter provided, of any one story or portion of a story used for the purposes of Class VII of any building of slow-burning or mill construction shall not exceed twelve thousand square feet.

(c) The floor area, except as hereinafter provided, of any one story or portion of a story used for the purposes of Class VII of any building of fireproof construction shall not exceed 25,000 square feet, unless the building is completely equipped with an approved automatic sprinkler system, but in no case shall such area exceed 30,000 square feet.

471. Floor Areas—Exceeding the Maximum Limits Defined in Section 470.)

(a) Where any floor or portion of a floor used for the purposes of Class VII in any building shall exceed in area the maximum number of square feet allowed in the preceding section for the type of construction of such building in which such floor is contained, each such maximum amount of floor area so used shall be separated from other parts of such floor by fire walls, or dividing walls built in accordance with the provisions of Section 251 of this chapter relating to dividing walls in buildings of Class I.

(b) Where any such floor so used is divided by such fire walls or dividing walls, each such division of such floor shall be provided with stairs, aisles, exits, and fire escapes as required in this chapter for separate and distinct buildings, and each such division shall be considered as a separate building, except as provided in Section 497 of this chapter.

472. Galleries.) (a) The area of any or all of the galleries, mezzanine or intermediate floors in any one story used wholly or in part for the purposes of Class VII in any building shall not exceed ten per centum of the area of such story. Galleries, mezzanine or intermediate floors of a larger size than the above shall be considered as full stories.




Fig. 16.

SECTION 472 C.

A—height from floor of any gallery, mezzanine or intermediate floor to ceiling over same.

B—space between the bottom of such gallery, mezzanine or intermediate floor and the floor of the story in which such gallery, etc., is placed.

Explanation:

A—shall not be less than 7'0".

B—shall not be less than 7'0".

(b) Every gallery, mezzanine or intermediate floor shall have at least one stairway not less than three feet wide.

(c) The height from the floor of any gallery, mezzanine or intermediate floor to the ceiling over same shall not be less than seven feet, and there shall be not less than seven feet of space between the bottom of such gallery, mezzanine or intermediate floor and the floor of the story in which such gallery, mezzanine or intermediate floor is placed.

(d) Every gallery, mezzanine or intermediate floor in any building used for the purposes of Class VII shall be built to conform to the construction applicable to such building, but galleries not exceeding five per centum of the area of such story, may be built of incombustible material without fireproof protection.

(e) No gallery, mezzanine or intermediate floor shall be built without a permit from the Department of Buildings, and plans showing the construction and size of such proposed gallery, mezzanine or intermediate

floor shall be filed with the Department of Buildings when a permit is applied for.

473. Courts of Class VII Buildings.) (a) Every court or light shaft of every building used wholly or in part for the purposes of Class VII shall be open and unobstructed from the bottom of such court to the sky, with the exception that fire escapes may be built therein, and such courts shall have walls constructed in the same manner as is required for the exterior walls of such buildings; provided, that no walls inclosing such courts are required on street or alley lot lines.

(b) All windows, doors or other openings in court walls of such buildings shall have metal frames, metal sashes and metal doors, with the glazed portions thereon of wired glass.

474. Stories—Number of.) The first story above the inside street grade shall be designated and known as the first story for all purposes of this chapter, and the stories above shall be numbered consecutively, the second, third, and so on.

475. Stairs—Halls—Passageways and Aisles—Signs and Lights.) (a) The stair halls, passageways and stair aisles shall be unobstructed and be as wide as the stair and not less than four feet wide in the clear.

(b) The exit door or doors between floors and stair halls shall be not less than ninety per centum of the width of the stairway to which they afford access, and for each elevator opening into such a stair hall, the doors to floors shall be increased six inches in width.

(c) The stairways and stair halls of any building used wholly or in part for the purposes of Class VII shall be illuminated by gas or electric light, and the gas piping and the electric wiring shall be accomplished by piping and circuits separated and distinct from the general illuminating piping and circuits of the premises. Each stair light shall have a red glass inclosure.

(d) At the bottom of each such stairway there shall be an illuminated red glass sign with the number of the story in which it is situated inscribed thereon in letters not less than six inches high.

476. Exit Signs and Lights.) (a) All exits in buildings used wholly or in part for the purposes of Class VII shall be clearly indicated by illuminated red signs with the word "Exit" thereon in letters not less than six inches high. At the bottom of each stairway on the street floor level there shall be similar signs indicating the direction of the nearest exit to a street or alley.

(b) Fire escape doors or windows shall be indicated by illuminated red signs with the words "Fire Escape" thereon in letters not less than six inches high.

477. Doors at Street Level—Revolving Doors.) The clear width of the exit openings shall be computed in the same manner as that provided in this article for main aisles, and no door openings shall be less than five feet wide, and all doors shall swing outward. Revolving doors shall not be considered as complying with this section unless the revolving wings of such revolving doors are so arranged that by the application of a force slightly more than is necessary to revolve said doors and which one person of ordinary strength is capable of exerting, all the wings of said doors fold flat on each other and in an outward direction, or unless the revolving wings of said revolving doors are so arranged that they may be readily collapsed or removed by pressure or simple mechanical means, to be approved by the Commissioner of Buildings, and leave sufficient opening for two or more persons to pass through with a minimum width of not less than twenty-two inches on each side of said collapsed doors.

Where revolving doors are used as exits they shall be credited as exits only to the extent of the clear space remaining when the doors are collapsed, and all deficiency of required exits must be made up by additional doors.

478. **Doors in Dividing Walls.)** (a) Door openings may be built in dividing walls of such buildings; provided, however, that such door openings shall be not less than five feet in width and shall be provided with fireproof doors built as described in Section 559 of this chapter, and that each door shall have an efficient closing device which will operate automatically in the event of a fire in close proximity to either side of such door.

(b) Each such opening shall have exit signs and lights as provided for street doors and exits in Section 476 of this chapter.

479. **Loads—Allowance for Live Loads in Construction of Floors of Buildings of Class VII.)** For all buildings of Class VII the floor shall be designed and constructed in such a manner as to be capable of supporting, in addition to the weight of the floor construction, partitions, permanent fixtures and mechanisms that may be set upon the same, a live load of one hundred pounds for every square foot of surface in such floors, and shall be figured in accordance with Section 503 of this chapter.

ARTICLE XI.

Class VIII.

480. **Class VIII Defined—Provisions of.)** In Class VIII shall be included every building used for school purposes and every building containing class rooms for special or general instruction, other than halls for the purpose of instruction as included in Class IV, where such building so used shall have a seating capacity of more than fifty students.

481. **Must Comply With General and Special Provisions.)** All buildings of Class VIII shall comply with the general provisions of this chapter wherever the same are applicable thereto, and in addition to the general provisions shall comply with the following special provisions:

482. **Construction of.)** (a) All buildings hereafter erected and used or intended to be used wholly for the purposes of Class VIII shall be constructed in accordance with the provisions of this chapter relating to Class VIII; and existing school buildings shall comply with the provisions of Class VIII with reference to stairs, exits and fire escapes.

(b) Buildings which have a seating capacity of two hundred or less and which are not over two stories and basement in height, may be built of ordinary construction; provided, that no portion of such building shall be used for assembly hall purposes.

(c) Buildings which have a greater seating capacity than two hundred and not exceeding four hundred, and which are not over three stories and basement in height, shall be built of slow-burning or fireproof construction.

(d) Buildings which have a greater seating capacity than four hundred, or which are more than three stories and basement in height, shall be built entirely of fireproof construction.

(e) Additions to existing buildings shall be built of the several types of construction required by this section; provided, however, that the sum total of the seating capacity of the entire building, including additions, shall be counted in determining the type of construction required for such addition.

(f) All alterations in existing buildings used for the purposes of Class VIII, other

than new additions thereto, and intended to make them comply with the requirements of this chapter, may be executed in the same kinds of materials originally used in such buildings, unless otherwise distinctly provided herein.

483. **Walls—Window Openings in.)** No wall of any building used for the purposes of Class VIII and containing a window opening shall be nearer than five feet to any lot line of adjoining property, street and alley lines not included.

484. **Portable Frame Buildings.)** Portable frame buildings used wholly for the purposes of Class VIII, not larger than 28 by 36 feet and not over one story high, may be erected, provided exterior walls and roof of same are covered with metal or other incombustible material, and the interior woodwork painted with fire-retarding paint approved by the Commissioner of Buildings; and, provided, further, that the location of such buildings shall be approved by the Commissioner of Buildings. Such portable buildings shall not be located nearer than ten feet to any other building, and shall not be maintained on any one lot or block for a longer period than two years after the date of the issuance of the original permit.

485. **Assembly Halls—Limitations as to Seating Capacity and Floor Level.)** (a) The limit of height at floor level and the maximum seating capacity of assembly halls or auditoriums or other single rooms in buildings of this Class must not exceed the numbers given in the following table, for the specified type of construction, to-wit:

Floor - Height of Above Grade.	Type of Construction— Slow burning or Mill Construction Having Fireproof		
	Fireproof Construction.	Stairs and Corridors.	Ordinary Construc- tion.
	Persons. Persons. Persons.		
Over 60 ft.	500	100	...
60 ft. or less..	600	300	...
45 ft. or less..	700	500	...
30 ft. or less..	1000	800	250
20 ft. or less..	1500	900	500
10 ft. or less..	2000	1000	800
5 ft. or less..	2500	1200	1000

(b) All assembly halls or other single rooms having a seating capacity larger than that given in the above table must have the highest part of the main floor within not more than one foot of grade level and must have exits leading directly to three streets, public alleys, or to open public grounds.

(c) Seating capacity of all assembly halls in buildings of this Class shall include the total aggregate seating capacity of all balconies, galleries, stages and platforms as well as the main portion of such assembly hall or rooms.

(d) Heights of assembly hall floors shall be measured from sidewalk level at entrance of building or open school grounds to highest part of main floor of such assembly hall or rooms.

486. **Stairways—Width of.)** (a) Stairways in buildings used for the purposes of Class VIII shall be equivalent in width to fifteen inches for every hundred of seating capacity in such building as measured by the aggregate seating capacity of the auditorium, assembly rooms and school rooms; provided, however, that the number of persons allowed in such buildings at any one time shall be limited by the width of stairways available as exits therefrom.

(b) No stairway shall be less than four feet in the clear, except where more than two stairways lead down from any floor, in which case stairways three feet in width in the clear may be counted in the total width of stairs required.

486. Where two or more stairways are used, they shall be placed at opposite ends of the building or as far apart as practicable, and all such buildings hereafter erected shall have at least two separate and distinct stairways from the ground floor to the top floor, and all existing buildings shall have two such separate and distinct stairways, or one stairway and one sliding or stairway fire escape.

(d) All stairways in buildings of Class VIII shall have hand railings on each side thereof. No stairway shall ascend a greater height than thirteen feet six inches without a level landing, the dimensions of which, in the direction of the run of the stairs, shall not be less than four feet, or which, if at a turn of the stairs, shall be of not less width than the width of the stairs. No winder shall be permitted in any stairs. Stairways which are over nine feet wide shall have double intermediate hand rails with end newel posts at least five and one-half feet high at each stair landing. All stairways shall discharge at the bottom directly to a public thoroughfare or open ground.

(See Illustration Sec. 398.)

487. **Stairways in Buildings Hereafter Erected—Fireproof.)** In buildings hereafter erected more than two stories and basement in height, the stairways and their enclosing walls shall be of fireproof construction.

488. **Width of Corridors, Passageways, Hallways and Doorways.)** The width of corridors, passageways, hallways and doorways shall be equivalent in width to eighteen inches for every one hundred of seating capacity of such portions of building as will be required to use same for exit. No corridor, passageway or hallway shall be less than five feet in width, and no doorway less than three feet in width, except where two or more doors, each two feet eight inches or more in width, are grouped together.

489. **Doors to Open Outward—Covering of.)** All doors in such buildings shall open outward. All exit doors from assembly halls to other parts of the building shall be covered with metal or other fireproof material approved by the Commissioner of Buildings.

490. **Aisles—Width of—In Assembly Halls and in Recitation and Study Rooms.)** (a) Aisles in assembly halls in buildings of Class VIII shall be equivalent in width to eighteen inches for every one hundred seating capacity in such assembly hall, but no such aisles shall be less than two feet six inches in its narrowest part. All groups of seats shall be so arranged that they shall have an aisle on each side, and not more than twelve seats in any one row shall be placed between aisles.

(b) Aisles in class rooms, recitation rooms and study rooms of such buildings shall be equivalent in width to eighteen inches for every one hundred permanent seats in any such room, but no aisle shall be less than sixteen inches in width and no main or cross aisle be less than two feet six inches in width.

491. **Emergency Exits for Assembly Rooms—Aggregate Width of.)** All assembly halls of such buildings having a seating capacity of eight hundred or more shall be provided with at least two emergency exits. The aggregate width of such emergency exits, which shall be provided for each floor, balcony or gallery of such assembly hall, shall be not less than nine inches in width for every one hundred of seating capacity or portion thereof. No emergency exit or stairway shall be less than three feet in width. Emergency exits must be located as far apart and as far from main exits as practicable, subject to the approval of the Commissioner of Buildings.

492. **Lights in Buildings—Windows—Skylights.)** (a) Provisions shall be made to properly light every portion of any such building devoted to the uses or accommodations of the public and all outlets therefrom leading to the street, including the open courts and corridors, stairways and exits, during the entire time such building is in use.

(b) All gas or electric lights in the class rooms of main building and in halls, corridors, lobbies, stairs and exits leading from the assembly halls shall be independent of lights in assembly hall. By "independent" shall be construed a separate pipe from meter or separate circuits from switch-board.

(c) The total glass area of outside windows and skylights of each class room, recitation room or study room in such buildings shall be not less than one-fifth of the floor area of such room.

(d) Class rooms, recitation rooms and study rooms that have exterior windows on one side only must have the top of glass in such windows at a height above the floor of such room of not less than one-half of the distance to the opposite parallel wall or partition.

(e) Such rooms having exterior windows on two opposite sides of the room shall have the top of glass in such windows not less than one-fourth the distance between walls in which the windows are placed. The height of windows in corner rooms having windows in adjacent walls shall be computed from nearest wall or partition to opposite window.

(f) Where skylights or skylights and windows of sufficient size to give the proper glass area are used these heights of windows shall not be required.

493. **Scenery—Sliding Curtains—Screens.)** No curtains or scenery shall be used in any assembly hall, except only, that it shall be permissible to use a pair of sliding curtains hung on horizontal metal rods not over twelve feet above the floor of stage and portable screens set on the floor and not over eight feet high. Provided, however, in assembly halls located on the first floor or ground floor of a fireproof building, it shall be permissible to use curtains hung from the ceiling or top of proscenium opening.

494. **Moving Picture Machines.)** Moving picture machines may be installed and used in assembly halls located on the first floor or ground floor of fireproof buildings of Class VIII. When moving picture machines are so used they shall be located in booths constructed of fireproof materials with metal clad doors and a vent duct to the outside air having a cross sectional area of at least two square inches.

495. **Basement When Used for Class Rooms.)** (a) In every such building in which the lower or basement floor is below the surface of the ground surrounding such building, and is used in part or as a whole for heating or ventilating apparatus, such floor shall be considered the basement story of such building.

(b) Class rooms, recitation rooms or study rooms shall not be allowed in basements less than twelve feet in height in the clear nor where the floor is more than two feet below the level of the sidewalk at nearest entrance of building nor in basements which are not properly lighted by windows or skylights as defined elsewhere in this Chapter for such rooms.

496. **Stories—Height of.)** No story above the basement shall be less than twelve feet in height in the clear.

497. **Fire Escapes.)** (a) Every building used for the purposes of Class VIII of four

or more stories in height shall be provided and equipped with stairway fire escapes or sliding fire escapes as herein provided.

(b) All such buildings having a seating capacity of less than two hundred on any one floor above the second floor shall have at least one such fire escape.

(c) All such buildings having a seating capacity of over two hundred but less than four hundred in any one story above the second floor shall have at least two such fire escapes.

(d) All such buildings having a seating capacity of more than four hundred but less than six hundred on any floor above the second floor shall have at least three such fire escapes.

(e) At least one additional stairway or sliding fire escape shall be provided for every increase of two hundred seating capacity in any one story above the second floor.

(f) Stairway fire escapes shall be built in accordance with the requirements of Sections 653, 654 and 657, and shall be subject to the approval of the Commissioner of Buildings.

(g) Sliding fire escapes shall be securely anchored or fastened to the building and shall have a radius or width of not less than thirty-six inches, and the inner side of the same shall be entirely smooth and made of metal. There shall be an entrance to each sliding fire escape from each floor above the first story. They shall be of a pitch of not less than thirty degrees nor more than forty-five degrees for straight runs. They shall be so constructed that they will discharge people not more than twenty-four inches from the adjacent ground or floor. They shall be of such pattern and design as will best secure the safety of the public, and their construction, location and maintenance shall be subject to the approval of the Commissioner of Buildings. Spiral sliding fire escapes shall have two complete turns for each story height of more than thirteen or less than sixteen feet.

(h) All the provisions of this Chapter relating to outside sliding or stair fire escapes shall apply to buildings of Class VIII, unless such buildings are fireproof, in which case interior fire escapes from ground to roof may be substituted for exterior fire escapes, provided such interior fire escapes shall comply with each and all of the following conditions:

(i) Interior fire escapes in fireproof buildings shall be enclosed in brick or concrete walls on all sides from top to bottom, and shall be enclosed at the top with a fireproof penthouse. The treads and risers of such interior fire escapes shall be the same as those used for stairs elsewhere in the building and the width of such fire escapes shall not be less than forty inches in their narrowest part between hand rails.

(j) The landings of such fire escapes shall, exclusive of and in addition to the space covered or occupied by swinging doors, be at least equal to the stairs in width. All doors leading to such fire escapes shall be incombustible doors and the glass portion thereof shall be glazed with polished wired glass not less than one-quarter of an inch thick, which shall be large enough to enable persons to see other persons on the opposite side of the door. The combined width of said doors on each landing shall exceed the stair width twenty-five per cent, but no single door shall be more than three feet wide. They shall be hinged and equipped with automatic opening and closing devices and shall open outward. Windows lighting such fire escapes shall have metal frames and sash and wired glass.

(k) The number and capacity of such interior fire escapes shall in no case be less than is elsewhere in this Chapter required for outside fire escapes, and the locations of the same shall be as far apart as practicable and so placed as to best secure the safety of the persons using the same in case of fire, accident or panic.

(l) Such interior fire escapes which comply with all the conditions above enumerated may be used daily as ordinary stairs.

498. **The Commissioner of Buildings, the Chief of Fire Prevention and Public Safety, City Electrician and Superintendent of Police Shall Close Buildings for Violations.)** The Commissioner of Buildings, the Chief of Fire Prevention and Public Safety, City Electrician and Superintendent of Police, or any of them, shall have the power to close or order closed any building used wholly or in part for the purposes of Class VIII wherein there is any violation of any ordinance which it is their duty to enforce, and to keep the same closed until such provisions are complied with.

ARTICLE XI-a.

Class IX.

498a. **Class IX Defined.)** In Class IX shall be included every building maintained by the City of Chicago for police station purposes.

498b. **Requirements General.)** Every building of Class IX shall comply with the general provisions of this chapter and in addition to the general provisions shall comply with the following special provisions:

498c. **Construction.)** (a) All buildings of Class IX not more than two stories and basement in height may be of ordinary mill, slow-burning or fireproof construction.

(b) All buildings of Class IX more than three stories and basement high shall be built of fireproof construction.

All buildings of Class IX containing a court room or court rooms above the second story shall be built of fireproof construction.

All buildings of Class IX three stories and basement or less in height which do not contain a court room or court rooms above the second story may be built of ordinary construction excepting that part of the building containing the cell room or lockup and the patrol wagon quarters, or either of them, which part shall be built of fireproof construction and shall be separated from all other parts of the same building by a wall of the same character and thickness as is required by this chapter for the outside walls of such building and where necessary by a fireproof floor and ceiling of the same thickness as the brick walls by which said floor and ceiling is supported.

(c) Buildings erected for or converted to the use of police stations for temporary purposes may be of mill or slow-burning construction not more than ninety feet in height from the average inside sidewalk grade of the street in front of the building to the highest part of the roof of the building.

498d. **Allowance for Live Loads and Construction of Floors of Class IX.)** The floors of all buildings of Class IX shall be designed and constructed as follows:

In all buildings of Class IX the floors of all court rooms, and of all public corridors, and of all stairways leading to same, shall be designed and constructed in such a manner as to be capable of bearing in all their parts, in addition to the weight of floor construction, partitions, permanent fixtures and mechanisms that may be set upon the same, a live load of one hundred pounds for every square foot of surface, and all other floors, or parts thereof, shall be designed as aforesaid capable of carrying a live load of fifty

buildings for every square foot of floor surface, and such floor-bearing capacity shall be computed in accordance with the provisions of this chapter.

498. Windows.) (a) In every building of Class IX every room, including court rooms, public and private offices, shall have at least one window opening directly upon a street, alley, yard or court; the total glass area of such window or windows shall not be less than one-tenth of the floor area of such room. The top of such windows shall be at least seven feet above the floor and at least the upper half of such windows shall be capable of being opened. Such window shall have a glass area of at least ten square feet unless it be a window in excess of one-tenth of the floor area as required by this paragraph. Cell blocks shall have at least three outside walls of same to face upon a street, alley, yard or court and where windows are placed in the three sides with a total glass area equal to one-fourth of the floor area of such block and each window is arranged so that it may be opened for one-half of its area, it shall not be required that each cell open onto a street, alley, yard or court. No sleeping rooms or cell rooms shall be allowed below the first floor level in any building of Class IX.

(b) In every building of Class IX every pantry, bath room, water closet and urinal compartment shall have at least one window which opens directly upon a street, alley, yard, court or vent shaft; the total glass area of such windows shall be not less than one-tenth of the floor area of such room or compartment. The top of such windows shall be at least seven feet above the floor and at least the upper half of such windows shall be capable of being opened; and no such windows shall have a glass area of less than six square feet or a glass width of less than one foot; provided, however, that such room or compartment, if located on the upper story of such building, may be lighted and ventilated by means of a skylight having a glass area of at least one-tenth the floor area of the room it serves and is equipped with an efficient ventilator or ventilators equal in effective area to one twentieth the floor area of such room.

498f. Courts and Shafts.) In every building of Class IX courts shall be of the minimum width and area as prescribed in Section 442 of this chapter and vent shafts shall be of the minimum width and area as prescribed in Section 443 of this chapter.

498g. Height of Rooms.) In every building of Class IX the height of all rooms except basement rooms shall be not less than ten feet from the level of the floor to the ceiling thereof, and the height of court rooms, if any, shall not be less than eleven feet from the level of the floor to the ceiling thereof.

498h. Thickness of Walls.) The walls of every building of Class IX shall comply in thickness with the requirements of Section 519 of this chapter as therein prescribed for buildings of Class I.

498i. Stairways and Fire Escapes.) Every building of Class IX shall be equipped with stairways and fire escapes in number and dimensions as follows:

In buildings of ordinary, slow-burning or mill construction which do not contain a court room or court rooms and with a floor area of 5,000 square feet or less, two stairways.

With floor area of 5,000 to 9,000 square feet, three stairways.

In buildings of ordinary, slow-burning or mill construction which contain court rooms and with a floor area of less than 5,000 square feet, two stairways and one stairway fire escape.

With floor area of 5,000 to 9,000 square feet, three stairways and one stairway fire escape.

In buildings of fireproof construction with a floor area of 1,000 square feet or less, two stairways.

With floor area of 7,000 to 15,000 square feet, three stairways.

With floor area of 15,000 to 21,000 square feet, four stairways.

All buildings over four stories in height must be equipped with stairway fire escapes as follows:

With a floor area of 7,000 square feet or less, one stairway fire escape, three feet in width.

With a floor area of 7,000 to 21,000 square feet, two stairway fire escapes not less than three feet in width.

No stairways in buildings of Class IX shall be less than four feet in width between hand rails.

In buildings less than three stories high and in buildings three stories high which may be built of ordinary construction by the provisions of this article, stairways may be of ordinary construction enclosed in brick walls of thickness as required by paragraph (h), Sec. 519 of this chapter, or stairways may be of fireproof or incombustible material enclosed in partitions of fireproof or incombustible material.

498j. Exits from Court Rooms.) (a) There shall be two direct exits located as far apart as practicable from every court room in a building of this class; the width of such exits shall be computed on a basis of twenty inches for each 100 persons of the aggregate capacity of such court room, and for fractional parts of 100 capacity, a proportionate part of twenty inches shall be added to the width of such exits, but no such exits shall be less than three feet wide in the clear. One of such exits shall open onto a public corridor not less than six feet wide from which there is a stairway leading to the ground at least four feet wide in the clear between hand rails. Where there is but one stairway from such public corridor an additional exit from each court room must be afforded by a stairway at least four feet wide in the clear between hand rails or by means of an outside iron stairway not less than three feet wide; the platform of which shall be placed approximately level with the floor of the court room and accessible by a door not less than three feet in width.

498k. Doors to Open Outward.) In buildings of Class IX all doors which afford ingress or egress from all rooms, except private offices, shall open outward.

ARTICLE XII.

General Provisions.

499. Construction or Alteration of Building—Requirements.) Every building or structure or part thereof, hereafter constructed, erected, altered, enlarged, repaired or changed within the City shall be so constructed, erected, altered, enlarged, repaired or changed, in accordance with the provisions of this Chapter.

500. Class of Buildings Not to Be Changed Without Conforming to Provisions of This Chapter.) If buildings, the uses of which bring them within any of the classes mentioned in this Chapter, are to be applied to the uses of any other class for which a better system of construction is required by this Chapter, the construction and equipment of such buildings shall first be made to conform to the requirements of this Chapter as specified for their intended use. And it shall be unlawful to use any such building for a new or different purpose from that to which its structure and equipment adapts it under this Chapter, unless the require-

ments of this Chapter for such new or different use shall first have been complied with, and a permit for such alteration or use shall have been first obtained from the Commissioner of Buildings.

501. Alterations of Existing Buildings.)

(a) In construing the several sections of this Chapter, said sections shall not be construed as requiring alterations in the construction or equipment of buildings or structures in existence at the time of the passage of this Chapter, except where specifically provided, unless such buildings shall not have sufficient or adequate means of egress therefrom or ingress thereto, by reason of insufficient or inadequate stairways or stairways improperly located or insufficient or inadequate elevators or elevator equipment, doors, fire escapes, windows or other means of egress or ingress and except also in sections which are herein made retroactive.

(b) Whenever an Inspector of Buildings shall make a report to the Commissioner of Buildings that any such building has inadequate or insufficient means of egress therefrom or ingress thereto, as aforesaid, the Commissioner of Buildings shall notify the owner, agent, or person in possession, charge or control of such building of such fact and direct him forthwith to make such alterations and changes in the construction or equipment of such building as are necessary to be made in order to make such building comply with the requirements of this Chapter.

(c) If, however, it is desired to enlarge, or in any manner materially modify the construction of any existing building, or to make a change in its use or occupation which will transfer it from one class as recognized by this Chapter to another class, then, before such enlargement or structural change or modification of building is made, or before such change in its use or occupation may be made, written notice shall be given to the Commissioner of Buildings of the intention to change the character of the use, and the entire building shall be reconstructed or modified in such manner as to bring the same, when enlarged or altered, or when occupied for its new and different purposes, into compliance with the provisions of this Chapter.

502. **Removal of Brick, Stone, Frame or Concrete Buildings.)** It shall be unlawful for any person, firm or corporation to move any brick, stone, frame or concrete building from one location to another, unless the same shall be altered or re-constructed so as to conform to the ordinances governing the construction of such building at the time of moving the same and in its new location; provided, however, that whenever a tenement house is moved, the same shall be made to comply with the requirements of Section 462 and Section 464 of The Chicago Code of 1911, as amended.

503. **Live and Dead Loads—Wind Resistance.)** (a) The "dead load" shall include all permanent portions of the building, also partitions and permanent fixtures and mechanisms supported by the building.

(b) All buildings shall be designed to resist a horizontal wind pressure of 20 lbs. per square foot for every square foot of exposed surface. In no case shall the overturning moment due to wind pressure exceed seventy-five per cent of the moment of stability of the building due to the dead load only.

(c) The "live" loads per square foot of floor areas, except stairs, for the classes of buildings except portions of Class VIII as hereinafter provided shall be not less than the following:

	Pounds.
Class I.....	100
Class II.....	50
Class III.....	40
Class IV.....	100
Class V.....	100
Class VI.....	40
Class VII.....	100
Class VIII.....	75

(d) Provided, however, that in Class VIII the portions of the building exclusive of the floors in assembly halls, the corridors and the stairs, shall not be required to be constructed to support a live load in excess of 40 pounds per square foot.

(e) The roofs of all buildings shall be designed and constructed in such a manner that they will bear a load in addition to the weight of their structure and covering, of at least twenty-five pounds for each square foot of horizontal surface.

(f) The live loads on stairways for buildings of all classes shall not be less than 100 pounds per square foot of treads and landings.

504. **Structural Details—Strength Tests—How Made.)** (a) All structural details and workmanship shall be in accordance with accepted engineering practice, and subject to the approval of the Commissioner of Buildings.

(b) Floors, joists and beams shall be designed for the full dead and live loads. Floor girders shall be designed for the full dead and not less than eighty-five per cent of the live load.

(c) In buildings of Classes III and VI, except frame buildings, where the distance between enclosing walls or intermediate walls is more than twenty-five feet in the clear, intermediate supports for the joists shall be either brick, or concrete, or iron, or steel columns, beams, trusses, or girders.

(d) If brick walls are used for this purpose, they may, in all cases where the thickness of walls is given, in Section 506, as 16 inches or more, be made four inches less in thickness than the dimensions stated.

(e) Tests shall be made by the owner, upon the demand of the Commissioner of Buildings, on all forms of floor construction involving spans over eight feet. Such tests shall be made to the approval of the Commissioner of Buildings, and must show that the construction will sustain a load equal to twice the sum of the live and dead loads, for which it was designed, without any indication of failure. The construction may be considered as part of the test load. Each test load shall remain in place at least twenty-four hours. On arch construction, this test load shall be placed on one-half of the arch, covering the area from the support to the crown of the arch.

505. **Walls, Piers and Columns—Dead and Live Loads.)** (a) The full live load on roofs of all buildings shall be taken on walls, piers, and columns.

(b) The walls, piers and columns of all buildings shall be designed to carry the full dead loads and not less than the proportion of the live load given at top of page 214.

(c) The proportion of the live load on walls, piers, and columns on buildings more than seventeen stories in height shall be taken in same ratio as the above table.

(d) The entire dead load and the percentage of live load on basement columns, piers and walls shall be taken in determining the stress in foundations.

(e) In addition to the entire dead loads, not less than the following proportion of the percentage of live load on the basement columns, piers and walls shall be taken in

Floor.....	17	16	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1
17.....	85	per cent.															
16.....	80	85															
15.....	75	80	85														
14.....	70	75	80	85													
13.....	65	70	75	80	85												
12.....	60	65	70	75	80	85											
11.....	55	60	65	70	75	80	85										
10.....	50	55	60	65	70	75	80	85									
9.....	50	50	55	60	65	70	75	80	85								
8.....	50	50	50	55	60	65	70	75	80	85							
7.....	50	50	50	50	55	60	65	70	75	80	85						
6.....	50	50	50	50	50	55	60	65	70	75	80	85					
5.....	50	50	50	50	50	50	55	60	65	70	75	80	85				
4.....	50	50	50	50	50	50	50	55	60	65	70	75	80	85			
3.....	50	50	50	50	50	50	50	50	55	60	65	70	75	80	85		
2.....	50	50	50	50	50	50	50	50	50	55	60	65	70	75	80	85	
1.....	50	50	50	50	50	50	50	50	50	55	60	65	70	75	80	85	

determining the number of piles for pile foundations and the area of concrete caissons.

Classes I and VII..... 75 per cent.

Classes II, III and VI..... 50 per cent.

Classes IV, V and VIII..... 25 per cent.

In all foundations eccentric loading must be provided for.

506. Requirements for Enclosing Walls—Table of Thickness—Exceptions—Definition of the Length of Wall—Provisions Where

	Base- ment.	Stories											
		1	2	3	4	5	6	7	8	9	10	11	12
One-story.....	12												
Two-story.....	16	12	12										
Three-story.....	16	16	12	12									
Four-story.....	20	20	16	16	12								
Five-story.....	24	20	20	16	16	16							
Six-story.....	24	20	20	20	16	16	16						
Seven-story.....	24	20	20	20	20	16	16	16					
Eight-story.....	24	24	24	20	20	20	16	16	16				
Nine-story.....	28	24	24	24	20	20	20	16	16	16			
Ten-story.....	28	28	28	24	24	24	20	20	20	16	16		
Eleven-story.....	28	28	28	24	24	24	20	20	20	16	16	16	
Twelve-story.....	32	28	28	28	24	24	24	20	20	20	16	16	16

(b) In Class VIII buildings the thickness of surrounding walls and of all dividing walls carrying loads of floors and roof shall be as indicated in the following table, to-wit:

	Base- ment.	Stories				
	in.	1	2	3	4	5
One story.....	16	12				
Two stories.....	16	16	12			
Three stories.....	16	16	16	12		
Four stories.....	20	20	16	16	12	
Five stories.....	24	20	20	16	16	16

(c) In Class VIII buildings, walls around stairs, elevators and air shafts and joist supports shall comply with the requirements of Section 627 of this Chapter.

(d) The basement walls of two-story buildings and the first story walls of three-story buildings in Classes III and VI may be twelve inches in thickness. The first story walls of one-story buildings and the second story walls of two-story buildings in Classes III and VI may be eight inches in thickness, provided that where a pressed brick face is used no wall shall be less than twelve inches in thickness, and an eight-inch brick or solid concrete partition wall may be built in a building of any class, but in no case shall any eight-inch brick wall be more than fourteen feet in height.

(e) The basement walls of two-story buildings in Classes II, III and VI may be 12 inches in thickness.

(f) In buildings of skeleton fireproof construction, the thickness of walls shall be governed by Section 609 of this Chapter.

(g) Walls less than fifty feet in length and walls less than fifty feet between cross walls, may be built four inches less in thick-

Buttresses, Piers or Pilasters are Used—Provisions for Inserting Columns in Walls—Anchorage of Walls and Floors—Definition and Limits for Height of Stories—Requirements for Curtain Walls—Interior Walls to Support Fireproof Floor Construction. (a)

The walls of all buildings, excepting the enclosing walls of frame buildings, shall be of brick, stone or concrete. The walls shall be solid and of solid material and except as otherwise herein provided shall be of the thickness in inches indicated in the following table:

ness than the thickness given in the aforesaid table, but no such wall in such buildings shall be less than twelve inches in thickness, provided, however, that such walls in buildings of Classes III and VI may be sixty-five feet in length; and further provided, that eight-inch walls may be used in one-story brick buildings and in the second story of two-story brick buildings of said last mentioned classes where said eight-inch walls are not more than fourteen feet in height and are supported by a foundation or wall not less than twelve inches in thickness.

(h) A brick wall not more than twenty-five feet long and forming one side of a brick shaft for stair, elevator or other purposes, need not exceed sixteen inches in thickness, nor its upper fifty feet twelve inches in thickness, provided that in no case shall the load on such brick wall exceed the safe load for brickwork prescribed by this ordinance.

(i) The length of a wall shall be the distance in which the wall extends in a straight line and shall be measured between angles of the masonry or between exterior and cross walls.

(See illustration on following page.)

(j) Where masonry buttresses or piers or pilasters are employed on either or both sides of a wall, then said walls may be reduced in thickness by one-half of the projection or projections of the buttresses or piers or pilasters, but no wall shall be reduced to less than twelve inches in thickness. The reduction in thickness may be made throughout the height of the wall, except that no twelve-inch wall shall be higher than thirty feet and no sixteen-inch wall shall be higher than fifty feet. The stress

in the brickwork in any part of such walls shall not exceed the stress per square inch allowed by this chapter on the kind of masonry employed. Buttresses or piers or pilasters shall be at least one-tenth as wide, measured on face of same, as the spacing between the buttresses or pilasters. Twelve-inch walls between buttresses or piers or pilasters shall not be used where the distance between buttresses or piers or pilasters is greater than eighteen feet. Sixteen-inch walls shall not be used between buttresses or piers or pilasters where the distance between buttresses or piers or pilasters is greater than twenty-four feet. Twenty-inch walls shall not be used between buttresses or piers or pilasters where the distance between the buttresses or piers or pilasters is greater than thirty feet.

(k) Where buttresses are used, they shall be so placed that the principal girders and trusses shall bear on them.

(l) If the loads carried by trusses and girders are supported by iron, steel, or reinforced concrete columns, then such buttresses as are herein described shall not be required except for the fireproofing of steel and iron columns. The walls between such

tems or between such structural floor systems and structural roof systems and shall be as follows:

Where 12-inch walls are used, the story height shall not exceed 18 feet.

Where 16-inch walls are used, the story height shall not exceed 24 feet.

Where 20-inch walls are used, the story height shall not exceed 30 feet.

(o) Where the story height is greater than thirty feet, the walls shall not be of less thickness than the following: The upper fifteen feet shall be not less than sixteen inches in thickness, and the walls shall be increased four inches in thickness at each interval of fifteen feet or fractional part thereof of height.

(p) Curtain walls in skeleton construction buildings may be built of hollow clay tile subject to the requirements and limitations of paragraph (e), Section 553 of this chapter, or may be constructed of reinforced concrete subject to the provisions and limitations of Section 540 of this chapter.

(q) The walls of buildings to be used for the purposes of Classes III and VI and




Fig. 17.

THICKNESS OF WALLS. Section 506j.

A = thickness of wall.

A' = thickness of wall after reduction.

B = projection of buttresses, piers or pilasters.

C = width of buttresses, piers or pilasters.

Explanation:

A may be reduced by $\frac{1}{2}$ B as at A'.

C = 1-10 D.

columns shall be built as required by this Chapter, and said walls shall be anchored to such columns by metal anchors in every seven feet to the height of such column.

(m) A structural floor system shall extend from one wall to an opposite wall, and the walls shall be anchored to floor joists or girders or both with iron anchors placed opposite one another, secured to the same joists or girders in pairs, every seven feet or less of length of said walls. Where said joists or girders are of such length that it is not practicable to make them of one piece, then the several pieces shall be joined at each splice or joint by the tie plates or tie bars or other metal connections of the same strength as the anchors. Such anchors shall have not less than four-tenths of a square inch of metal in its smallest cross-sectional area. The spikes, bolts or screws, securing said anchors and tie plates, shall be of such number and size as to transmit the tensile strain which the anchor is capable of resisting into the joists or girders to which said anchors are connected. All pin anchors shall extend at least eight inches into the supporting masonry.

(n) The story height of buildings shall be the distance between structural floor sys-




Fig. 18.

Explanatory diagram of maximum allowable height spacing and length of walls with or without buttresses, piers or pilasters.

not more than two stories in height may be of hollow clay tile or moulded hollow concrete blocks not thinner than the thickness herein required for brick walls, subject to the approval of the Commissioner of Buildings.

(r) Interior brick walls used to support fireproof floor construction, where brick walls are not required by this chapter, may be built thinner than the thickness required by the provisions of paragraph (a) of this section, provided the proportion between the thickness of such walls and the free height between floors does not exceed fifteen, and further provided the unit stresses do not exceed the stresses allowed by this chapter, and provided, also, that no such wall shall be constructed of a thickness less than twelve inches.




Fig. 19.




Fig. 20.




Fig. 21.

LEDGES JOIST SUPPORTS.

Section 507a, b, c.

Fig. 19 (A) Corbelling to be not less than four courses of brick.

(B) Upper course shall project four inches.

(C) The joists shall be protected from top to bottom by brick.

Fig. 20 (A) Metal joist hanger allowable.

(B) $\frac{1}{4}$ inch metal required.

Fig. 21 (A) Brick shall project between joists

(B) Projection of brick to be two inches.

507. **Ledges—Joist Supports.)** (a) In buildings two stories or more in height wherever party walls or partition walls twelve inches or less in thickness are used for the support of wood joists in buildings of Classes I, II, IV, V, VII and VIII the joists shall be supported on ledges of brick formed by corbelling not less than four courses of brick and the upper course shall project four inches beyond the face of the wall, and the joists shall be protected from the bottom to the top of same for the distance of the projection of the corbel by solid brick work laid in mortar.

(b) Wherever iron or steel joist and girder boxes having five complete sides of iron, nowhere less than $\frac{1}{4}$ -inch in thickness, are used, corbels and ledges as herein specified may be omitted.

(c) In buildings of every class where wood furring is used on brick walls, the brick between joists shall be projected from the bottom of the joist to the top of the joist for the full thickness of the furring and in no case shall such projection be less than two inches.

508. **Walls of Altered Buildings—Increasing Thickness of.)** If the walls of a building are not of sufficient thickness to comply with the requirements of this Chapter for an enlarged or modified building, then the thickness of the existing walls shall be increased by building alongside of them a new wall, which shall not, however, be less in any part thereof than twelve inches thick,

and which shall be increased in thickness by four inches for at least every forty feet in the height of such wall. Such new wall shall be laid in Portland cement mortar and shall be anchored to the old wall, but bonding with brick or masonry will not be considered as complying with this Chapter; and if an increase in the height of the building is contemplated, the wall from the top of the old wall shall be built jointly upon the new and old walls. If solid masonry buttresses are introduced in connection with such thickening and strengthening of existing walls, the intervening wall may be reduced to eight inches in thickness, provided such buttresses are sufficient in number and in area to make the resultant structure of equal strength with the solid wall already specified. Provided, however, that steel or

iron columns or beams may be used instead of such new wall, such columns or beams to be bolted or bonded to the existing wall in a manner satisfactory to and approved by the Commissioner of Buildings.

509. **Walls—Party.)** The provisions of the preceding section shall also apply to all cases where existing party walls are to be joined to for the erection of new buildings. But in the case of party walls, which at the time of their erection were built in accordance with the terms of the city ordinances then in force, such walls, if sound and in good condition, may be used without increase of thickness for any building not higher than and of the same class as the building for which the original wall was built.

510. **Walls—Erection of—Walls and Skeleton Framework Securely Braced.)** In the erection of buildings of masonry construction, no wall shall be carried up at any time more than two stories above another wall of the same building. The walls and skeleton framework of all buildings shall be kept securely braced and otherwise protected against the effects of the weather during all building operations.

511. **Parapet Walls—When Required on Walls and Porches—Thickness and Height of.)** (a) On all flat roof buildings parapet walls shall be erected, except as hereinafter provided, on all exterior walls and on all partition walls required by this ordinance by reason of the area of such buildings;

provided, that such parapet walls may be dispensed with on any wall of a fireproof building, and on street and alley walls and on yard and court walls of buildings of other types where the entire framing and materials of the roof are strictly fireproof or where all portions of the roof nearer than fifteen feet to the lot line of such street or alley or bounding such yard or court are protected against fire by a continuous covering of porous or hollow tiles, not less than two inches thick and surfaced with mortar, on top of the roof boards.

(b) Such parapet walls may be eight inches thick wherever this ordinance permits the use of eight-inch walls; elsewhere they shall be not less than twelve inches in thickness.




Fig. 22




Fig. 23.

Fig. No. 22.

A—distance from division lot line to building line.
B—height of parapet wall above roof on division lot line side.
C—parapet wall on other sides when required.

Explanation:

If A is less than 3'0", B shall be 3'0".

C shall be not less than 18".

SECTION 511 D.

Fig. No. 23.

A—distance from division lot line to building line.
B—height of parapet wall above roof, with a greater pitch than 3" per horizontal foot, on division lot line side.

C—parapet wall on other sides when required.

If A is less than 3'0", B shall be 3'0".

C shall be not less than 18".

For exceptions where fireproof construction is used see ordinance Sec. 511 d, second paragraph.

(c) Such parapet walls shall extend at any point not less than three feet vertically above the roof on all such required partition walls and on all other walls within less than three feet of any division lot line and approximately parallel therewith; elsewhere they shall extend not less than eighteen inches above the roof.

(d) On all buildings whose roofs have a greater pitch than three inches per horizontal foot, parapet walls, of thickness and height as above specified, shall be erected on required partition walls, on exterior walls approximately parallel with and less than three feet distant from a division lot line, and on walls abutting on another building. Provided, that such parapet walls may be dispensed with where the entire framing and materials of the roof are fireproof or where the cornice and roof covering are of incombustible material and the

top of the roof boards is protected against fire for at least five feet up from such wall by a coating of plaster on porous or hollow tiles at least two inches thick; and further provided that such parapet walls and such protection against fire may be dispensed with on buildings of Classes III and VI, three stories or less in height when such buildings have cornices of incombustible material and roof coverings of slate or terra cotta roofing tile.

(511a to 511k, see 498a to 498k.)

512. Allowable Stresses and Special Requirements for Foundations—Bearing on Various Soils.) (a) If the soil is a layer of pure clay at least fifteen feet thick, without admixture of any foreign substance other than gravel, it shall not be loaded to exceed 3,500 pounds per square foot. If the soil is a layer of pure clay at least fifteen feet thick and is dry and thoroughly compressed, it may be loaded not to exceed 4,500 pounds per square foot.

(b) If the soil is a layer of firm sand fifteen feet or more in thickness, and without admixture of clay, loam or other foreign substance, it shall not be loaded to exceed 5,000 pounds per square foot.

(c) If the soil is a mixture of clay and sand, it shall not be loaded to exceed 3,000 pounds per square foot.

513. Foundations in Wet Soil—Trenches to Be Drained.) In all cases where foundations are built in wet soil, it shall be unlawful to build the same unless trenches in which the work is being executed are kept free from water by bailing, pumping, or otherwise, until after the completion of work upon the foundations and until all cement has properly set. In all cases a connection with the street sewer shall be established before beginning the work of laying foundations.

514. Foundations—Where no. Permitted —Depth Below Surface—Independent of Underground Construction Owned or Controlled by the City.) (a) Foundations shall not be laid on filled or made ground or on loam, or on any soil containing admixture of organic matter, and must rest on hard, sound soil. Foundations shall in all cases extend at least four feet below the finished surface of the ground upon which they are built, unless footings rest on bed rock.




Fig. 24.




Fig. 25.

FOOTINGS.

Sections 514a, b.

Fig. 24 (B) Shall in all cases extend 4' 0" below finished grade at building, unless footings rest on bed rock—Sec. 514a.

Fig. 25 (C) Buildings 100 ft. or more in height; footings shall extend at least to a depth drained by sewer in adjacent streets and alleys.

Exception if sewer is greater than 10 ft. below sidewalk grade. Such foundation need not extend to a greater depth than 10 ft. if soil conditions are as per ordinance. Sec. 514b.

526 **Allowable Stresses and Special Requirements for Timber.)** The maximum allowable stresses in pounds per square inch on actual sections for timber shall be as follows

	Extreme Fibre Stress and Tension with Grain.	Compression with Grain.	Compression Across Grain in Build- ings Hereafter Erected.	Compression Across Grain in Existing Buildings.	Shear with Grain.
Douglas Fir and Long Leaf Yellow Pine....	1,300	1,100	250	400	130
Oak.....	1,200	900	500	600	200
Short Leaf Yellow Pine.....	1,000	800	250	300	120
Norway Pine.....	800	700	200	300	80
White Pine.....	800	700	200	300	80
Hemlock.....	600	500	150	300	60

The unit stress on timber posts shall comply with the formula:

$$C \left(1 - \frac{L}{80D}\right)$$

In which formulæ:

C equals compressive strength of timber with the grain as given in the table

L equals length in inches.

D equals least diameter inches.

The maximum length of a timber post shall not exceed thirty diameters.

Timber columns shall not be used in buildings of greater height than twice the width of the building nor in buildings over one hundred feet in height.

527. **Quality of Timber.)** Timber used for building purposes shall be sound, well manufactured, close grained, free from wind shakes, or from dead, loose, decayed, encased or pitch knots, or knots and other defects that will materially impair its strength and durability.

528. **Maximum Allowable Stresses and Special Requirements for Metals.)** (a) The maximum allowable stresses in pounds per square inch in steel and iron shall not exceed the following:

	Rolled Steel.	Cast Steel.	Wrought Iron.	Cast Iron.
Tension on net section.....	16,000	16,000	12,000
Maximum compression on gross section.....	14,000	14,000	10,000	10,000
Bending on extreme fibre.....	16,000	16,000	12,000
Bending on extreme fibre tension.....	3,000
Bending on extreme fibre compression.....	10,000
Bending on extreme fibres of pins.....	25,000
Shear: shop driven rivets and pins.....	12,000
Shear: field driven rivets.....	10,000
Shear on rolled steel shapes.....	12,000
Shear plate girder webs; gross section.....	10,000
Shear on brackets.....	2,000
Bearing, shop driven rivets and pins.....	25,000
Bearing, field rivets.....	20,000

(b) The allowable compressive stresses per square inch shall be determined by the following formulæ:

$$\begin{aligned} \text{Steel} & \dots\dots\dots 16,000 - 70 \frac{L}{R} \\ & \dots\dots\dots \frac{L}{R} \\ \text{Wrought Iron} & \dots\dots\dots 12,000 - 60 \frac{L}{R} \\ & \dots\dots\dots \frac{L}{R} \\ \text{Cast Iron} & \dots\dots\dots 10,000 - 60 \frac{L}{R} \end{aligned}$$

In the above formulæ:

L equals length in inches.

R equals least radius of gyration in inches.

(c) In no case shall the allowable compressive stress exceed that given in paragraph (a) of this section.

(d) For steel columns filled with, and encased in concrete extending at least three inches beyond the outer edge of the steel, where the steel is calculated to carry the entire live and dead load, the allowable stress per square inch shall be determined by the following formulæ:

$$18,000 - 70 \frac{L}{R}$$

but shall not exceed 16,000 pounds.

(e) For steel columns filled with, but not encased in, concrete the steel shall be calculated to carry the entire live and dead load. In this case the above formulæ may be used, but the allowable stress shall not exceed 14,000 pounds.

(f) Stress due to eccentric loading shall be provided for in all compressive members.

(g) The length of rolled steel compressive members shall not exceed one hundred twenty times the least radius of gyration, but the limiting length of struts for wind bracing

only may be one hundred fifty times the least radius of gyration. The limiting length for cast iron columns shall be seventy times the least radius of gyration.

(h) Cast iron columns shall not be used in buildings of greater height than twice the least width, or in buildings over 100 feet high.

(See Special Ruling VIII, Page 301.)

529. **Live and Dead Loads—Stress.)** (a) Wherever the live and dead load stresses are of opposite character, only 70 per cent of the dead load stress shall be considered as effective in counteracting the live load stress.

(b) For stresses produced by wind forces combined with those from live and dead load, the unit stress may be increased fifty per cent. over those given above; but the section shall not be less than required if wind forces be neglected.

530. **Riveting—Tension.)** (a) In proportioning tension members the diameter of the rivet holes shall be taken one-eighth of an inch larger than the nominal diameter of the rivet.

(b) In proportioning rivets the nominal diameter of the rivet shall be used.

(c) Pin-connected riveted tension members shall have a net section through the pin-hole at least 25 per cent in excess of the net section of the body of the member and the net section back of the pin-hole, parallel with the axis of the member, shall not be less than the net section of the body of the member.

531. **Plate Girders — Flanges — Compression.)** (a) Plate girders shall be proportioned either by the moment of inertia of their net section, or by assuming that the flanges are concentrated at their centers of gravity and a unit stress used such that the extreme fibre stress does not exceed 16,000 pounds per square inch, in which case one-eighth of the gross section of the web, if properly spliced, may be used as flange section.

(b) The gross section of the compression flanges of plate girders shall not be less than the gross section of the tension flanges; nor shall the stress per square inch girder of a longer length than 25 times the in the compression flange of any beam or width exceed.

$$\frac{L}{B} = 20,000 - 160 \frac{L}{B}$$

In which formula

L equals unsupported distance and

B equals width of flange.

(c) The flanges of plate girders shall be connected to the web with a sufficient number of rivets to transfer the total shear at any point in a distance equal to the effective depth of the girder at that point combined with any load that is applied directly on the flanges.

(d) Webs of plate girders shall be provided with stiffeners over all bearing points, under all points of concentrated loading and elsewhere when required by good engineering practice.

Reinforced Concrete.

(See Special Ruling II and III, Page 291.)

532. **Reinforced Concrete — Definition — Plans.)** The term "Reinforced Concrete" means any combination of metal imbedded in concrete to form a structure so that the two materials assist each other to sustain all the stresses imposed. Before a permit to erect any reinforced concrete structure is issued, complete plans and specifications shall be filed with the Commissioner of Buildings, showing all details of the construction, including detail of working joints, the size and position of all reinforced rods, stirrups or other forms of metal, and giving the composition and proportion of the concrete; provided, however, that permission to erect any reinforced concrete structure does not in any manner approve the construction until after tests have been made of the actual construction to the satisfaction of the Commissioner of Buildings.

(See Special Ruling III, Page 291.)

533. **Ratio of Moduli of Elasticity—Adhesion—Bond.)** (a) The calculations for the strength of reinforced concrete shall be based on the assumed ultimate compressive strength per square inch designated by the letter "U" given in the table below for the mixture to be used.

(b) The ratio designated by the letter "R" of the modulus of elasticity of steel to that of the different grades of concrete shall be taken in accordance with the following table:

Mixture.	U	R
1 cement, 1 sand, 2 broken stone, gravel or slag	2,900	10
1 cement, 1½ sand, 3 broken stone, gravel or slag	2,400	12
1 cement, 2 sand, 4 broken stone, gravel or slag	2,000	15
1 cement, 2½ sand, 5 broken stone, gravel or slag	1,750	18
1 cement, 3 sand, 7 broken stone, gravel or slag	1,500	20

(See Special Ruling II, Page 291.)

534. **Unit Stresses for Steel and Concrete.)** (a) The stresses in the concrete and the steel shall not exceed the following limits:

(b) Tensile stress in steel shall not exceed one-third of its elastic limits and shall not exceed 18,000 pounds per square inch.

(c) Shearing stress in steel shall not exceed 12,000 pounds per square inch.

(d) The compressive stress in steel shall not exceed the product of the compressive stress in the concrete multiplied by the elastic modulus of the steel and divided by the elastic modulus of the concrete.

(e) Direct compression in concrete shall be one-fifth of its ultimate strength. Bending in extreme fibre of concrete shall be thirty-five one-hundredths of the ultimate strength.

(f) Tension in concrete on diagonal plane shall be one-fiftieth of the ultimate compressive strength.

(g) For a concrete composed of one part of cement, two parts of sand and four parts of broken stone, the allowable unit stress for adhesion per square inch of surface of imbedment shall not exceed the following:

	Pounds Per Sq. Inch.
On plain round or square bars of structural steel	70
On plain round or square bars of high carbon steel	50
On plain flat bars, in which the ratio of the sides is not more than 2 to 1	50
On twisted bars when the twisting is not less than one complete twist in eight diameters	100

(h) For specially formed bars, the allowable unit stress for bond shall not exceed one-fourth of the ultimate bond strength of such bars without appreciable slip which shall be determined by tests made by the person, firm or corporation to the satisfaction of the Commissioner of Buildings, but provided that in no case shall such allowable unit stress exceed 100 pounds per square inch of the specially formed bars.

535. **Design for Slabs, Beams and Girders.)** Reinforced concrete slabs, beams and girders shall be designed in accordance with the following assumptions and requirements:

(a) The common theory of flexure shall be applied to beams and members resisting bending.

(b) The adhesion between the concrete and the steel shall be sufficient to make the two materials act together.

(c) The steel to take all the direct tensile stresses.

(d) The stress strain curve of concrete in compression is a straight line.

(e) The ratio of the moduli of elasticity of concrete to steel shall be as specified in the table in Section 533.

(See Special Ruling II and IV, Pages 291 and 301.)

536. **Moments of External Forces.)** (a) Beams, girders, floor or roof slabs and joists shall be calculated as supported, or with fixed ends, or with partly fixed ends, in accordance with the actual end conditions, the number of spans and the design.

(b) When calculated for ends partly fixed for intermediate spans with an equally distributed load where the adjacent spans are of approximately equal lengths:

Bending moment at center of spans shall not be less than that expressed in the formula

$$\frac{WL^2}{12} \text{ for intermediate spans and } \frac{WL^2}{10} \text{ for end spans.}$$

526. **Allowable Stresses and Special Requirements for Timber.)** The maximum allowable stresses in pounds per square inch on actual sections for timber shall be as follows

	Extreme Fibre Stress and Tension with Grain.	Compression with Grain.	Compression Across Grain in Build- ings Hereafter Erected.	Compression Across Grain in Existing Buildings.	Shear with Grain.
Douglas Fir and Long Leaf Yellow Pine....	1,300	1,100	250	400	130
Oak	1,200	900	500	600	200
Short Leaf Yellow Pine.....	1,000	800	250	300	120
Norway Pine	800	700	200	300	80
White Pine	800	700	200	300	80
Hemlock	600	500	150	300	60

The unit stress on timber posts shall comply with the formula:

$$C \left(1 - \frac{L}{80D} \right)$$

In which formula:

C equals compressive strength of timber with the grain as given in the table

L equals length in inches.

D equals least diameter inches.

The maximum length of a timber post shall not exceed thirty diameters.

Timber columns shall not be used in buildings of greater height than twice the width of the building nor in buildings over one hundred feet in height.

527. **Quality of Timber.)** Timber used for building purposes shall be sound, well manufactured, close grained, free from wind shakes, or from dead, loose, decayed, encased or pitch knots, or knots and other defects that will materially impair its strength and durability.

528. **Maximum Allowable Stresses and Special Requirements for Metals.)** (a) The maximum allowable stresses in pounds per square inch in steel and iron shall not exceed the following:

	Rolled Steel.	Cast Steel.	Wrought Iron.	Cast Iron.
Tension on net section.....	16,000	16,000	12,000	10,000
Maximum compression on gross section.....	14,000	14,000	10,000	10,000
Bending on extreme fibre.....	16,000	16,000	12,000	10,000
Bending on extreme fibre tension.....	3,000
Bending on extreme fibre compression.....	10,000
Bending on extreme fibres of pins.....	25,000
Shear: shop driven rivets and pins.....	12,000
Shear: field driven rivets.....	10,000
Shear on rolled steel shapes.....	12,000
Shear plate girder webs; gross section.....	10,000
Shear on brackets	2,000
Bearing, shop driven rivets and pins.....	25,000
Bearing, field rivets	20,000

(b) The allowable compressive stresses per square inch shall be determined by the following formulæ:

$$\begin{aligned} \text{Steel} & \dots\dots\dots 16,000 - 70 \frac{L}{R} \\ \text{Wrought iron} & \dots\dots\dots 12,000 - 60 \frac{L}{R} \\ \text{Cast iron} & \dots\dots\dots 10,000 - 60 \frac{L}{R} \end{aligned}$$

In the above formulæ:

L equals length in inches.

R equals least radius of gyration in inches.

(c) In no case shall the allowable compressive stress exceed that given in paragraph (a) of this section.

(d) For steel columns filled with, and encased in concrete extending at least three inches beyond the outer edge of the steel, where the steel is calculated to carry the entire live and dead load, the allowable stress per square inch shall be determined by the following formulæ:

$$18,000 - 70 \frac{L}{R}$$

but shall not exceed 16,000 pounds.

(e) For steel columns filled with, but not encased in, concrete the steel shall be calculated to carry the entire live and dead load. In this case the above formulæ may be used, but the allowable stress shall not exceed 14,000 pounds.

(f) Stress due to eccentric loading shall be provided for in all compressive members.

(g) The length of rolled steel compressive members shall not exceed one hundred twenty times the least radius of gyration, but the limiting length of struts for wind bracing

only may be one hundred fifty times the least radius of gyration. The limiting length for cast iron columns shall be seventy times the least radius of gyration.

(h) Cast iron columns shall not be used in buildings of greater height than twice the least width, or in buildings over 100 feet high.

(See Special Ruling VIII, Page 301.)

529. **Live and Dead Loads—Stress.)** (a) Wherever the live and dead load stresses are of opposite character, only 70 per cent of the dead load stress shall be considered as effective in counteracting the live load stress.

(b) For stresses produced by wind forces combined with those from live and dead load, the unit stress may be increased fifty per cent. over those given above; but the section shall not be less than required if wind forces be neglected.

530. **Riveting—Tension.)** (a) In proportioning tension members the diameter of the rivet holes shall be taken one-eighth of an inch larger than the nominal diameter of the rivet.

(b) In proportioning rivets the nominal diameter of the rivet shall be used.

(c) Pin-connected riveted tension members shall have a net section through the pin-hole at least 25 per cent in excess of the net section of the body of the member and the net section back of the pin-hole, parallel with the axis of the member, shall not be less than the net section of the body of the member.

531. **Plate Girders — Flanges — Compression.** (a) Plate girders shall be proportioned either by the moment of inertia of their net section, or by assuming that the flanges are concentrated at their centers of gravity and a unit stress used such that the extreme fibre stress does not exceed 16,000 pounds per square inch, in which case one-eighth of the gross section of the web, if properly spliced, may be used as flange section.

(b) The gross section of the compression flanges of plate girders shall not be less than the gross section of the tension flanges; nor shall the stress per square inch girder of a longer length than 25 times the in the compression flange of any beam or width exceed.

$$\frac{L}{B} = 20,000 - 160$$

In which formula

L equals unsupported distance and
B equals width of flange.

(c) The flanges of plate girders shall be connected to the web with a sufficient number of rivets to transfer the total shear at any point in a distance equal to the effective depth of the girder at that point combined with any load that is applied directly on the flanges.

(d) Webs of plate girders shall be provided with stiffeners over all bearing points, under all points of concentrated loading and elsewhere when required by good engineering practice.

Reinforced Concrete.

(See Special Ruling II and III, Page 291.)

532. **Reinforced Concrete — Definition — Plans.** The term "Reinforced Concrete" means any combination of metal imbedded in concrete to form a structure so that the two materials assist each other to sustain all the stresses imposed. Before a permit to erect any reinforced concrete structure is issued, complete plans and specifications shall be filed with the Commissioner of Buildings, showing all details of the construction, including detail of working joints, the size and position of all reinforced rods, stirrups or other forms of metal, and giving the composition and proportion of the concrete; provided, however, that permission to erect any reinforced concrete structure does not in any manner approve the construction until after tests have been made of the actual construction to the satisfaction of the Commissioner of Buildings.

(See Special Ruling III, Page 291.)

533. **Ratio of Moduli of Elasticity — Adhesion — Bond.** (a) The calculations for the strength of reinforced concrete shall be based on the assumed ultimate compressive strength per square inch designated by the letter "U" given in the table below for the mixture to be used.

(b) The ratio designated by the letter "R" of the modulus of elasticity of steel to that of the different grades of concrete shall be taken in accordance with the following table:

Mixture.	U	R
1 cement, 1 sand, 2 broken stone, gravel or slag	2,900	10
1 cement, 1½ sand, 3 broken stone, gravel or slag	2,400	12
1 cement, 2 sand, 4 broken stone, gravel or slag	2,000	15
1 cement, 2½ sand, 5 broken stone, gravel or slag	1,750	18
1 cement, 3 sand, 7 broken stone, gravel or slag	1,500	20

(See Special Ruling II, Page 291.)

534. **Unit Stresses for Steel and Concrete.** (a) The stresses in the concrete and the steel shall not exceed the following limits:

(b) Tensile stress in steel shall not exceed one-third of its elastic limits and shall not exceed 18,000 pounds per square inch.

(c) Shearing stress in steel shall not exceed 12,000 pounds per square inch.

(d) The compressive stress in steel shall not exceed the product of the compressive stress in the concrete multiplied by the elastic modulus of the steel and divided by the elastic modulus of the concrete.

(e) Direct compression in concrete shall be one-fifth of its ultimate strength. Bending in extreme fibre of concrete shall be thirty-five one-hundredths of the ultimate strength.

(f) Tension in concrete on diagonal plane shall be one-fiftieth of the ultimate compressive strength.

(g) For a concrete composed of one part of cement, two parts of sand and four parts of broken stone, the allowable unit stress for adhesion per square inch of surface of imbedment shall not exceed the following:

Pounds Per
Sq. Inch.

On plain round or square bars of structural steel	70
On plain round or square bars of high carbon steel	50
On plain flat bars, in which the ratio of the sides is not more than 2 to 1	50
On twisted bars when the twisting is not less than one complete twist in eight diameters	100

(h) For specially formed bars, the allowable unit stress for bond shall not exceed one-fourth of the ultimate bond strength of such bars without appreciable slip which shall be determined by tests made by the person, firm or corporation to the satisfaction of the Commissioner of Buildings, but provided that in no case shall such allowable unit stress exceed 100 pounds per square inch of the specially formed bars.

535. **Design for Slabs, Beams and Girders.** Reinforced concrete slabs, beams and girders shall be designed in accordance with the following assumptions and requirements:

(a) The common theory of flexure shall be applied to beams and members resisting bending.

(b) The adhesion between the concrete and the steel shall be sufficient to make the two materials act together.

(c) The steel to take all the direct tensile stresses.

(d) The stress strain curve of concrete in compression is a straight line.

(e) The ratio of the moduli of elasticity of concrete to steel shall be as specified in the table in Section 533.

(See Special Ruling II and IV, Pages 291 and 301.)

536. **Moments of External Forces.** (a) Beams, girders, floor or roof slabs and joists shall be calculated as supported, or with fixed ends, or with partly fixed ends, in accordance with the actual end conditions, the number of spans and the design.

(b) When calculated for ends partly fixed for intermediate spans with an equally distributed load where the adjacent spans are of approximately equal lengths:

Bending moment at center of spans shall not be less than that expressed in the formula

$$\frac{WL^2}{12} \text{ for intermediate spans and } \frac{WL^2}{10} \text{ for end spans.}$$

(c) The moment over supports shall not be less than the formula $\frac{WL^2}{18}$ and the sum of the moments over one support and at the center of span shall be taken not less than the formula $\frac{WL^2}{6}$.

In the formula hereinabove given "W" is the load per lineal foot and "L" the length of span in feet.

(d) In case of concentrated or special loads the calculations shall be based on the critical condition of loading.

(e) For fully supported slabs, the free opening plus the depth, for continuous slabs, the distance between centers of supports, is to be taken as the span.

(f) Where the vertical shear, measured on the section of a beam or girder between the centers of action of the horizontal stresses, exceeds one-fifth of the ultimate direct compressive stress per square inch, web reinforcement shall be supplied sufficient to carry the excess. The web reinforcement shall extend from top to bottom of beam, and loop or connect to the horizontal reinforcement. The horizontal reinforcement carrying the direct stresses shall not be considered as web reinforcement.

(g) In no case, however, shall the vertical shear, measured as stated above, exceed one-fifteenth of the ultimate compression strength of the concrete.

(h) For T beams the width of the stem only shall be used in calculating the above shear.

(i) When steel is used in the compression side of beams and girders, the rods shall be tied in accordance with requirements of vertical reinforced columns with stirrups connecting with the tension rods of the beams or girders.

(j) All reinforcing steel shall be accurately located in the forms and secured against displacement; and inspected by the representative of the architect or engineer in charge before any surrounding concrete be put in place. It shall be afterwards completely inclosed by the concrete, and such steel shall nowhere be nearer the surface of the concrete than $1\frac{1}{2}$ -inch for columns, $1\frac{1}{4}$ inch for beams and girders, and $\frac{1}{2}$ -inch, but not less than the diameter of the bar, for slabs.

(k) The longitudinal steel in beams and girders shall be so disposed that there shall be a thickness of concrete between the separate pieces of steel of not less than one and one-half times the maximum sectional dimension of the steel.

(l) For square slabs with two-way reinforcements the bending moment at the center of the slab shall not be less than that

expressed in the formula $\frac{WL^2}{24}$ for intermediate spans, and $\frac{WL^2}{20}$ for end spans.

(m) The moment over supports shall not be less than the formula $\frac{WL^2}{36}$ and the sum of the moments over one support and at the center of the span shall be taken not less than the formula $\frac{WL^2}{12}$.

In which above formula "W" is the load per lineal foot and "L" the length of the span.

(n) For squares or rectangular slabs, the distribution of the loads in the two dimensions, shall be inversely as the cubes of the two dimensions.

(o) Exposed metal of any kind will not be considered a factor in the strength of any part of any concrete structure, and the plaster finish applied over the metal shall not be deemed sufficient protection unless applied of sufficient thickness and so secured as to meet the approval of the Commissioner of Buildings.

(p) Shrinkage and thermal stresses shall be provided for by introduction of steel.

(See Special Ruling II, Page 291.)
537. Limiting Width of Flange in "T" Beams.)

(a) In the calculation of ribs, a portion of the floor slab may be assumed as acting in flexure in combination with the rib. The width of the slab so acting in flexure is to be governed by the shearing resistance between rib and slab, but limited to a width equal to one-third of the span length of the ribs between supports and also limited to a width of three-quarters of the distance from center to center between ribs.

(b) No part of the slab shall be considered as a portion of the rib, unless the slab and rib are cast at the same time.

(c) Where reinforced concrete girders support reinforced concrete beams, the portion of floor slab acting as flange to the girder must be reinforced with rods near the top, at right angles to the girder, to enable it to transmit local loads directly to the girder and not through the beams.

(See Special Ruling IV, Page 301.)
538. Reinforced Concrete Columns—Limit of Length—Per Cent of Reinforcement—Bending Moment in Columns—Tying Vertical Rods.)

(a) Reinforced concrete may be used for columns in which the concrete shall not be leaner than a 1:2:4 mixture and in which the ratio of length to least side or diameter does not exceed twelve, but in no case shall the cross section of the column be less than 64 square inches. Longitudinal reinforcing rods must be tied together to effectively resist outward flexure at intervals of not more than twelve times least diameter of rod and not more than 18 inches. When compression rods are not required, reinforcing rods shall be used, equivalent to not less than one-half of one per cent (.005) of the cross sectional area of the column; provided, however, that the total sectional area of the reinforcing steel shall not be less than one square inch, and that no rod or bar be of smaller diameter or least dimensions than one-half inch. The area of reinforcing compression rods shall be limited to three per cent. of cross sectional area of the column. Vertical reinforcing rods shall extend upward or downward into the column, above or below, lapping the reinforcement above or below enough to develop the stress in rod by the allowable unit for adhesion. When beams or girders are made monolithic with or rigidly attached to reinforced concrete columns, the latter shall be designed to resist a bending moment equal to the greatest possible unbalanced moment in the beams or girders at the columns, in addition to the direct loads for which the columns are designed.

(b) When the reinforcement consists of vertical bars and spiral hooping, the concrete may be stressed to one-fourth of its ultimate strength as given in Section 533, provided, that the amount of vertical reinforcement be not less than the amount of the spiral reinforcement, nor greater than eight per cent. of the area within the hooping; that the percentage of spiral hooping be not less than one-half of one per cent, nor greater than one and one-half per cent.; that the pitch of the spiral hooping be uni-

form and not greater than one tenth of the diameter of the column, nor greater than three inches; that the spiral be secured to the verticals at every intersection in such a manner as to insure the maintaining of its form and position, that the verticals be spaced so that their distance apart, measured on the circumference be not greater than nine inches, nor one-eighth the circumference of the column within the hooping. In such columns, the action of the hooping may be assumed to increase the resistance of the concrete equivalent to two and one-half times the amount of the spiral hooping figured as vertical reinforcement. No part of the concrete outside of the hooping shall be considered as a part of the effective column section.

539. Structural Steel Columns.) When the vertical reinforcement consists of a structural steel column of box shape, with lattice or battenplates of such a form as to permit its being filled with concrete, the concrete may be stressed to one-fourth of its ultimate strength as given in table in Section 533, provided that no shape of less than one square inch section be used and that the spacing of the lacing or battens be not greater than the least width of the columns.

(See Special Ruling X, Page 303.)

540. Curtain Walls in Skeleton Construction Buildings.) Buildings having a complete skeleton construction of steel or of reinforced concrete construction, or a combination of both, may have exterior walls of reinforced concrete eight inches thick; provided, however, that such walls shall support only their own weight and that such walls shall have steel reinforcement of not less than three-tenths of one per cent in each direction, vertically and horizontally, the rods spaced not more than twelve-inch centers and wired to each other at each intersection. All bars shall be lapped for a length sufficient to develop their full stress for the allowable unit stress for adhesion. Additional bars shall be set around openings, the verticals wired to the nearest horizontal bars, and the horizontal bars at top and bottom of openings shall be wired to the nearest vertical bars. The steel rods shall be combined with the concrete and placed where the combination will develop the greatest strength, and the rods shall be staggered or placed and secured so as to resist a pressure of thirty pounds per square foot, either from the exterior or from the interior on each and every square foot of each wall panel.

541. Bending and Elongation of Steel.) The bending and elongation of steel used in reinforced concrete construction shall conform to the following requirements: (a) Steel having a diameter of three-fourths of an inch or less shall be capable of bending cold ninety degrees over a diameter equal to twice the thickness of the piece without fracture; steel over three-fourths inch in diameter shall be capable of bending cold to ninety degrees over a diameter equal to three times the diameter of the piece.

(b) The material of reinforcement shall be such form that it will not elongate under working stress to exceed one fifteen-hundredth.

(c) Reinforcing steel used in reinforcing concrete construction shall not be painted, but shall be free from all mill scale and loose rust.

542. Cement Tests.) (a) Only Portland cement shall be used in reinforced concrete construction. All cement shall be tested in car load lots when delivered, or in quantities equal to the same. Cement failing to meet the requirements of accelerated test shall be rejected.

(b) Pats of neat cement must be allowed to harden twenty-four hours in moist air, and then be submitted to the accelerated test as follows: A pat is exposed in any convenient way in an atmosphere of steam, and above boiling water, in a loosely closed vessel for three hours, after which before the pat cools, it is placed in the boiling water for five additional hours. To pass this test satisfactorily, the pat shall remain firm and hard, and show no signs of cracking, distortion or disintegration.

(c) Portland cement when tested shall have a minimum tensile strength as follows: Neat cement after one day in moist air shall develop a tensile strength of at least 200 pounds per square inch; after one day in air and six days in water shall develop a tensile strength of at least 500 pounds per square inch, and after one day in air and twenty-seven days in water, shall develop a tensile strength of at least 600 pounds per square inch. Cement and sand tests composed of one part of cement and three parts of sand shall after one day in air and six days in water, develop a tensile strength of at least 175 pounds per square inch; and after one day in air and twenty-seven days in water, shall develop a tensile strength of at least 240 pounds per square inch.

(d) A certificate that the cement used has been tested and has met the requirements of this section and that the tests have been made in accordance with the standard methods prescribed by the American Society for Testing Materials, on pages 149 to 164, both inclusive, of the proceedings of the Eleventh Annual Meeting of the American Society for Testing Materials, adopted August 15, 1908, shall be furnished by the architect or engineer in charge to the Commissioner of Buildings.

543. Sand.) The sand to be used for concrete shall be clean, hard, coarse sand, of the grade known as torpedo sand, and free from loam or dirt, not less than 45 per centum shall be returned on a screen of 400 mesh to the square inch.

544. Stone.) The stone to be used in concrete shall be clean crushed hard stone or clean crushed blast furnace slag or gravel of a size to pass through a one-inch square mesh. If limestone or slag is used, it shall be screened to remove all dust; if gravel is used, it shall be thoroughly washed. Stone shall be drenched immediately before using. If slag is used, it shall be of such character that when made into concrete the concrete will develop a crushing strength equal to that specified for stone or gravel concrete.

545. Mixing.) All concrete shall be mixed in a mechanical mixer except when limited quantities are required, or when the conditions of the work make hand mixing preferable; hand mixing to be done only when approved by the Commissioner of Buildings. In all mixing, the separate ingredients shall be measured and shall be thoroughly mixed and must be uniform in color, appearance and consistency before placing.

546. Placing Concrete.) In filling in concrete around reinforcing steel, the concrete must be worked continuously with suitable tools, as it is put in place. Filling the forms completely and puddling afterward will not be permitted. In placing the concrete, the work shall be so laid out that partly set concrete will not be subjected to shocks from men wheeling or handling material over it.

547. Concrete Placed in Freezing Weather.) When concreting is carried on in freezing weather, the material must be heated, and such provisions made that the concrete can be put in place without freezing. The use of frozen, lumpy sand, or stone depend-

ing on hot water used in mixing to thaw it out will not be permitted. All reinforced concrete shall be kept at a temperature above freezing for at least forty-eight hours after being put in place. All forms under concrete placed in freezing weather shall remain until all evidences of frost are absent from the concrete and the natural hardening of the concrete has proceeded to the point of safety.

548. Concrete Placed in Warm Weather.) Concrete laid in warm weather shall be drenched with water twice daily, Sunday included, during the first week after being put in place.

549. Cement Finish.) Cement finish added to the top of slabs, beams, or girders, shall not be calculated in the strength of a member unless laid integrally with the rough concrete. No greater unit stress shall be allowed on such cement finish than on the rough concrete.

(See Special Ruling IV, Page 301.)

(See Special Ruling IX, Page 303.)

550. Fireproof Concrete Construction.) Reinforced concrete construction will be accepted for fireproof buildings if designed as prescribed in this paragraph. The aggregate for such concrete shall be clean, broken stone or clean crushed blast furnace slag, or clean screened gravel, together with clean, coarse sand of the grade known as torpedo sand; stone, slag or gravel shall be of a size to pass through a screen of three-quarter inch mesh. The minimum thickness of concrete surrounding the reinforcing members of reinforced concrete beams and girders shall be two inches on the bottom, and one and one-half inches on the sides of said beams and girders. The minimum thickness of concrete under slab rods shall be one inch; and all reinforcement in columns shall have a minimum protection of two inches of concrete except as hereinafter provided. If a supplementary metal fabric is placed in the concrete surrounding the reinforcing, simply for holding the concrete, the thickness of concrete under the reinforcing may be reduced by one-half inch, then such fabric shall not be considered as reinforcing metal.

551. Removal of Forms.) In no case shall the props and shores used in reinforced concrete construction be removed from under floors and roofs in less than two weeks, except as is provided herein. Column forms shall not be removed in less than four days. The centering from bottom of slabs and sides of beams and girders may be removed after the concrete has set for one week, if the floor has obtained sufficient hardness to sustain the dead weight of the said floor. No load or weight shall be placed on any portion of the construction until the concrete has fully set and the centers have been removed.

552. Tests.) The contractor for the reinforced concrete construction shall make load tests on any portion of the work within a reasonable time after erection, as may be required by the Commissioner of Buildings. Such tests must be made under the direction of the Commissioner of Buildings in his presence or in the presence of his representative, and must show that the construction will sustain a load twice the sum of the live and dead loads for which it was designed, without any sign of failure. The construction may be considered as part of the test load. Each test load shall cover two or more panels and shall remain in place at least twenty-four hours. The deflection under the full test load at the expiration of twenty-four hours shall not exceed one eight-hundredth of the span. These tests shall be considered as tests of workmanship only.

553. Reinforced Terra Cotta Hollow Tile.)

(a) The term reinforced hollow tile is hereby defined to mean a system of hollow burned clay tile in combination with reinforced concrete, in which combination the hollow tile may be used to resist compressive and shearing stresses subject to the following provisions:

The provisions relating to reinforced concrete construction shall hold as far as applicable to this system.

All tile to be hard burned terra cotta tile of uniform quality, free from shrinkage cracks, with true beds and having an ultimate compressive strength of not less than 4,000 pounds per square inch of net area of surface tested.

The following stresses and values shall not be exceeded: Extreme fibre stress (compressive) on hollow tile, 500 pounds per square inch.

Shearing stress on hollow tile, 200 pounds per square inch.

Adhesion between tile and 1:2.4 concrete to 1:3 cement mortar, 40 pounds per square inch.

Ratio of modulus of elasticity of steel to that of tile with cement mortar joints, 10.

(b) **Special Provisions as to Workmanship in Reinforced Hollow Tile Construction.)** The hollow tile shall be thoroughly soaked with water at the time concrete is poured and be kept drenched for at least thirty-six hours afterwards. The joints between tiles shall be staggered, buttered and slushed full of mortar consisting of one (1) part of Portland cement and three (3) parts of clean, sharp sand, thoroughly mixed.

(c) **Terra Cotta Tile Columns.)** Columns of solid terra cotta or of hollow terra cotta in which the sectional area of the open holes in each block shall not exceed twenty (20) per cent of the gross sectional area of such block, may be used for structural purposes provided the height of such column shall not exceed twelve times the least dimension.

The allowable stress shall not exceed 350 pounds per square inch and shall be subject to the reduction formula given in Section 539 in paragraph f.

All terra cotta tile used for construction of columns shall be hard burned terra cotta tile of uniform quality, free from shrinkage cracks, with true beds and having ultimate compressive strength of not less than 6,000 pounds per square inch of net area of cross section of samples tested.

Mortar used in setting terra cotta tile walls and columns to be composed of one (1) part Portland cement and three (3) parts clean, sharp sand, thoroughly mixed.

(d) **Special Provisions as to Workmanship in Tile Column Construction.)** All terra cotta tile must be thoroughly wet before using and when used in columns must be set on end with the voids running vertically and directly over each other, and with the webs in direct line of pressure.

All vertical joints must stagger and terra cotta blocks must be of proper dimensions to meet this condition as no broken tile will be allowed.

All work to be set plumb, with uniform horizontal joints, thickness to average three-eighths (3/8) of an inch. The minimum time which shall elapse between the finishing of the work and before any load is placed thereon shall be not less than seven days.

(e) **Terra Cotta Tile Walls.)** Hollow tile may be used for building primary bearing walls, which are defined as walls that may be used to receive directly the loads from floors or roofs in addition to their acting as partition walls, provided the proportion

between thickness of wall and free height between the floors does not exceed fifteen (15) and the load including the weight of the construction does not exceed three hundred and fifty (350) pounds per square inch of net sectional area of tile, and shall be of the thickness specified by this chapter for brick walls. Hollow terra cotta tile may be used for exterior walls, but when so used the thickness and height of the work must conform to the dimensions required for brick walls in this chapter, but must in no case exceed four stories in height in any building. The thickness of walls shall be calculated as the outside dimensions of the tile and each tile shall be full thickness of wall. The thickness of the plastering is not to be included as a part of the thickness of the wall. Walls having a thickness of 4 inches may be used when the height does not exceed five (5) feet. The quality of the tile and mortar and special provisions as to workmanship as specified for terra cotta columns shall apply to terra cotta tile walls.

(f) **Terra Cotta Grain Bin Construction.)** Fireproof storage bin, grain elevators and grain warehouses may be built in cylindrical form with terra cotta tile of such height, diameter and thickness as is allowed by safe engineering practices, provided that the material shall not be stressed in excess of the limits prescribed in this chapter for walls and columns.

554. **Cinder Concrete.)** (a) Cinder concrete construction may be used for all buildings in which fireproof construction is mandatory by this chapter, or where ordinary construction, mill construction or slow-burning construction may be used.

(b) Only clean, thoroughly burnt, steam boiler cinders, free from matter other than cinders may be used. The cinders used shall be of such size that they will pass through a one-inch square mesh. Cinder concrete piers or walls shall not be permitted to carry loads and shall not be given credit therefor.

(c) The ultimate compressive strength per square inch of cinder concrete shall be taken as not exceeding seven hundred pounds. The ratio of the modulus of elasticity of steel divided by the modulus of elasticity of cinder concrete shall be taken as thirty.

(d) There shall not be less than one part of Portland cement to seven parts of cinders and sand of the grade known as torpedo sand in cinder concrete. All other special requirements and methods of calculation for reinforced concrete as required in this chapter shall modify and regulate the use of cinder concrete in buildings.

(e) All steel and all metal pipe and conduits enclosed in cinder concrete shall be protected by a coating of cement grout or plastered with good lime mortar before the cinder concrete is placed.

(f) For fireproof construction, the minimum thickness of cinder concrete covering on structural metal shall be the same as required for brick or concrete covering for fireproof buildings by this chapter. In slow-burning or mill construction buildings, the minimum thickness of cinder concrete covering on structural metal shall be three inches on columns and two inches on beams, girders and other structural steel or iron members.

(g) Wherever cinder concrete is used for the covering of columns, beams, girders or other structural steel members of a building the cinder concrete covering shall have metal binders, or wire fabric, imbedded in and around said columns, beams, girders or other structural steel members. If wire is used for said metal binders, it shall not be smaller than No. 8 gauge wire and shall be

spaced not less than sixteen inches apart along the length of the steel member covered.

(h) Where cinder concrete construction is used for a building which, by this chapter, is required to be of fireproof construction, all parts that carry weights or resist strains, shall be made entirely of incombustible material, and all metallic structural members shall be protected against the effects of fire by cinder concrete proportioned, mixed, applied and secured as herein described.

(i) All other parts of a building of cinder concrete construction, built where fireproof construction is mandatory by this chapter, shall be built and made of the material required by this chapter for buildings of fireproof construction; provided, however, that cinder concrete as described herein, and of the same thickness elsewhere specified, may be used for all protective covering of structural metal, after such metal has been protected by a coating of cement grout or plastered with good lime mortar, as required by this chapter.

Skeleton Construction.

*(See Special Ruling I, Page 291.)

555. **Skeleton Construction.)** (a) The term "Skeleton Construction" shall apply to all buildings wherein all external and internal loads and stresses are transmitted from the top of the building to the foundations by a skeleton or framework of metal or reinforced concrete.

(b) In metal frame skeleton construction the beams and girders shall be riveted to each other at their respective junction points. If columns made of rolled iron or steel are used, their different parts shall be riveted to each other, and the beams and girders shall have riveted connections to unite them with the columns. If cast iron columns are used, each successive column shall be bolted to the one below it by at least four bolts not less than $\frac{3}{4}$ inch in diameter, and the beams and girders shall be bolted to the columns. Bolt holes in flanges for connection from column to column shall be drilled. At each line of floor or roof beams, lateral connections between the ends of the beams and girders shall be made in such manner as to rigidly connect the beams and girders with each other in the direction of their length.

(c) All steel trusses shall be riveted and the steel work in buildings more than 100 feet high and in a building whose height exceeds twice its width shall be riveted.

(d) Wherever it is found impossible to rivet connections as herein described and such connections are bolted, cold rolled or turned bolts of exact fit and diameter in reamed holes may be used in place of rivets with the same allowable stresses as field driven rivets.

(e) All structural members which are temporarily bolted together shall be well bolted in every alternate hole.

(f) After the bases or base plates and columns have been set in place, both shall be protected by a covering of cement concrete applied direct to the metal, measuring not less than two and one-half inches thick from the extreme projection of the metal, filled solid into all spaces, and forming a continuous concrete mass from the grillage or other foundations to an elevation six feet above the floor level nearest the column base plate or column stool.

(g) All metal shall be clean and shall be free from loose rust and scale, and all metal except that to be embedded in concrete shall be protected with at least two coats of metal protecting paint.

(h) All structural details and workmanship shall be in accordance with accepted engineering practice.

(i) All trusses shall be held rigidly in position, both temporarily and permanently by efficient lateral and sway bracing.

Miscellaneous Provisions

155. Porches—Verandas—Porticos—Construction of Inside Fire Limits. (a) The enclosing walls of porches, verandas, or porticos shall be of incombustible material on buildings inside the fire limits, except that where such porches, verandas, or porticos constitute part of a storm house or of a storm door enclosure, they may be of combustible material, providing, that they be not more than twelve feet high, nor occupy a greater frontage than two feet more than the width of the inner doors protected by such storm enclosure.

(b) On buildings more than three stories in height, porches hereafter erected, if of combustible material, shall not exceed one story in height. Where porches of incombustible material are continuous and extend fifty feet or more across the rear of buildings, there shall be a partition of incombustible material separating each fifty feet of porch from the adjacent porch.

156. Tanks on Roofs—Permits—Fees. (1) It shall be unlawful for any person, firm or corporation to construct, maintain or allow, or permit to remain in or upon the roof of any building in the city, any tank of a larger capacity than four hundred gallons, unless such tank shall rest upon a good and sufficient foundation of solid brick or stone masonry, or upon iron girders set on steel plates which rest upon a good and sufficient foundation of solid brick or stone masonry, or upon iron or steel construction. No tank of a capacity exceeding four hundred gallons shall be constructed in or upon any building without first submitting for the approval of the Commissioner of Buildings a complete set of plans, showing the construction in detail of the supports and foundations of such tank. If such plans shall be satisfactory to the Commissioner of Buildings, they shall be approved by him. The owner or his agent or the contractor erecting such tank shall, before proceeding with the erection of such tank, procure from the Department of Buildings a permit for the sub-structure work, for which permit a fee of five dollars shall be charged.

158. Door and Window Openings, When Protected in Buildings of Classes I, II, IV, V, VII and VIII—Iron Doors—Wired Glass Set in Metal Frames.

(See illustration, Section 258b.)

(a) Where the distance from door to window openings in buildings of Classes I, II, IV, V, VII and VIII is less than thirty (30) feet from the opposite side of the established alley line and where the windows and doors of two or more areas of the same building which is required to be separated by dividing walls by this chapter, are on a court, every such window and door, distant less than thirty feet from another window or door of another such area and where also the doors and window openings are within fifteen (15) feet of an inside lot line, such openings shall be provided with windows and doors constructed of wire glass set in metal frames and sash; provided, further, that doors may be automatic rolling steel shutters or steel plate doors or metal-clad wood doors, and further provided that at least one of the first or ground floor doors must be a swinging door.

(b) Where iron doors are used to fulfill the requirements of this section they shall be made of sheet iron or steel, of not less than No. 14 U. S. gauge metal, and shall lap

the wall at least one-half inch all around the opening, and the bottom shall fit the sill closely where it is not practicable to lap it. The frames and crossbars shall be made of one and one-half by one and one-half by one-fourth inch angles and in no case shall there be less than two crossbars, and where the doors are over six feet high, such crossbars shall be spaced not more than two feet apart. Lever bars shall be made of one and one-half by three-eighths inch iron, extending at least one-third of the distance across the opposite leaf. The number and spacing of such lever bars shall be the same as the crossbars. Where hinges are used they shall be made of two by one-fourth inch iron, extending at least three-fourths of the way across the door. The number and spacing of such hinges shall be the same as is required for the crossbars. Pin bolt or eyes shall be one-half inch round and shall be securely fastened to the building.

(c) Where metal frames, metal sash and wired glass are used to fulfill the requirements of this section, the glazed portion of the frames and sash shall be set with fire-resisting glass such as is elsewhere herein defined. The glass must be supported by frames and sash and shall be retained by the structural part of the frame or sash independently of the material used for water-proofing purposes. Non-inflammable material only shall be employed for the structural members used for retaining glass in the sash. Frames and sash shall be made of sheet metal or of rolled steel sections. Frames shall be of such form as to be retained in the wall opening either with flanges of at least one and one-half inches in width or by fixed anchors of proper length spaced not exceeding twenty-four inches securely set into the wall. Sheet metal frames and sash shall be made of galvanized iron of not less than No. 24 gauge and of a quality soft enough to permit of necessary bending without breaking, or of not less than 20-ounce copper, or other metal of equal strength and durability and which will not melt at a lower temperature than copper. All joints shall be made with interlocking seams, securely riveted together, and in no case shall solder be used for other than weather-proofing purposes. The head of the frame shall be closed at the top and the piece forming this closure shall be securely fastened to each side at all points. The sill shall be filled with concrete or other incombustible material. Movable or sliding sheet metal sash shall have stiles and rails of thickness and of width at least one and three-quarter inches respectively, and shall be securely fastened together at each corner and so constructed that they will correspond with the construction of the frames at every place of contact. Where frames are made of solid rolled steel sections the metal shall be not less than one-eighth inch in thickness securely riveted or locked together at all corners and junctions so as to possess sufficient strength and rigidity to withstand shipment, handling and installation without distortion. Where sash are made of solid rolled steel sections the metal shall not be less than one-eighth inch in thickness excepting the removable members for retaining the glass and the weathering strips which shall not be less than one-sixteenth inch in thickness. The sash members shall be securely riveted or locked together at all corners and junctions so as to possess sufficient strength and rigidity to safely withstand the stresses occasioned by handling, installation, operation and by wind pressure. Frames and sash in the construction of which solid rolled steel section members are used shall have all their parts protected from the effects of rust and corrosion by a covering of durable enamel or by the application of two coats of approved mineral paint. All glazing of frames or sash shall be with wired glass at least one-quarter inch in

thickness. The exposed area of any single pane or light of glass, measured on the inner side of the window shall not exceed seven hundred and twenty (720) square inches nor shall the width or length of any pane or light of glass exceed forty-eight (48) inches. Glass shall be held in position by a metal ledge on each side of same. Ledges on the back or inner side of the glass shall be at least three-quarter inches high for lights where the unsupported glass area is seven hundred and twenty (720) square inches and for glass of an unsupported area of less than seven hundred and twenty (720) square inches a reduction in height of the inside ledges may be made at the rate of one-sixteenth inch for each one hundred (100) square inches reduction of unsupported glass area, but in no case shall the height of the inside ledges be less than one-half inch. The ledges on the outer or weather side of the glass shall not be less than one-half inch in height for unsupported glass areas in excess of three hundred and fifty (350) square inches. For unsupported glass areas less than three hundred and fifty (350) square inches, the weather side ledge may be one-half the height of the inside ledge but in no case shall it be less than one-quarter inch high. Clearance between the edge of the glass and the bottom of the groove formed by the ledges shall not exceed one-eighth inch and all glass shall be set in suitable putty. Movable sash shall have stiles and rails to constructed that they will properly engage with the frame members at all points of contact, afford ample weatherproof qualities and not warp or bulge materially under heat or rapid cooling.

(d) Lifting or sliding sash shall be counter-weighted so as to balance and if doubling the sash weights shall be separated by parting strips in the weight boxes and the weights shall be accessible through the boxes. Such sash shall be provided with metallic sash chain, cord or tape, and smooth running sash pulleys securely riveted or bolted in place. The sash chain, cord or tape shall be of sufficient strength to withstand severe heat without parting and be thoroughly protected against moisture or corrosion. Sash shall be fitted into frame with suitable stops and parting beads of metal or their equivalent. Sash shall be removable. Meeting rails of the sashes shall be so constructed as to prevent the passage of heat and flame and shall be equipped with one or more substantial sash locks securely riveted or bolted in place.

(e) Horizontally pivoted sash and movable sash shall be provided with steel pivots at least three-eighths inches in diameter securely attached above the middle. Pivots shall work in substantial iron or steel eye plates bushed with brass and securely attached in place. Sheet metal frames shall be reinforced where the pivots enter by riveting on one-eighth inch iron strips so drilled as to receive the pivots. Such sash must be provided with suitable stops and an effective attachment for holding them open or closed and with such substantial gravity locks or ledges that will be positive in action and hold the sashes tightly closed when exposed to heat. Where either sash is stationary or where two pivoted sash are used the transom bar dividing such sash shall be so constructed that it will not warp or bulge materially under heat or rapid cooling. Rails or transom bars where used shall be made so as not to be easily affected by rust and to afford ample weatherproof qualities.

(f) Vertically pivoted sash shall comply generally with the requirements for horizontally pivoted sash and movable sash. They must be constructed in such a manner as to afford proper stiffness and in such manner as to prevent material warping or bulging under heat or rapid cooling.

(g) Hinged sash or casement windows must be hinged with substantial iron or steel

hinges securely bolted or riveted in place, and provided with substantial iron or steel latches or locks securely fastened in place. Such sash shall be constructed so as to fit the frame closely and afford ample weatherproof qualities at all points. They shall be provided with stops and fastenings that will prevent material warping or bulging under heat or rapid cooling.

(h) Where the area of wall openings is in excess of 5 by 9 feet, the metal frames containing the sash or glass must be reinforced at every point of division by not less than five-inch "I" beams securely fastened into the brickwork, proper allowance being made for expansion of the beams when heated. "I" beams shall be protected on the flanges with at least two inches of tile, concrete, or other material approved by the Commissioner of Buildings, and next to the web with at least two and one-half inches of such material, which thickness shall be increased on large beams. Metal frames shall be securely attached to the reinforcing members.

(i) Electro-glazed prism glass may be used in lieu of wired glass, when approved by the Commissioner of Buildings as to material and construction of same, providing the frames and sash of same comply with the requirements of this section for wired glass window frames and sash.

(j) In cases in which it is claimed that equally good or more desirable mode or manner of constructing and installing metal frames, metal sash and fire-resisting glass, other than specified in this chapter, can be used in the erection or alteration of buildings, the Commissioner of Buildings upon written application to him for a permit to use the same, shall cause a test to be made of such construction in a laboratory of recognized standing, and may appoint an architect or a fire prevention engineer to represent the City at such test. A requirement of testing said frame and sash shall be that it will be capable of withstanding exposure to fire on the weather side for one hour with temperatures rising gradually to at least fifteen hundred (1500) degrees Fahr. without loss of glass or material passage of flame, and immediately after exposure to before-described fire conditions it shall be required to withstand application to the weather side of a stream of water at least seven-eighths inches in diameter applied from a distance of twenty feet at sixty (60) pounds pressure. The results of the test shall show also that the proposed material and construction will be equal or better in fire-resisting and structural qualities to a frame and sash of dimensions not greater than five feet by nine feet built as per requirements of this section. All expenses of this test shall be borne entirely by the before-mentioned applicant for a permit. In the event of such examination and test being satisfactory to the Commissioner of Buildings he shall authorize the use of such frames and sash as in compliance with this section.

(k) This section shall not apply to frame buildings nor to buildings outside the fire limits twenty-eight hundred square feet or less in area, nor to buildings of Class I, one story in height, nor to buildings of Class II not more than two stories in height, nor to store windows in the first story, where the same are located on an alley and not more than sixteen feet from the street.

559. Dividing Walls and Iron Doors—Openings Inserted. (a) Wherever openings are to be inserted in dividing walls in buildings, where such dividing walls are required by reason of the large area of such building, or in dividing walls between two or more connected or attached buildings, they shall be provided with incombustible doors as follows:

(b) Such doors may be either sliding doors or swinging doors, and shall be so constructed, installed and maintained that they can be easily opened or closed from either side at all times by any person; provided, however, rolling steel shutters may be used when such openings are not used as exits.




Fig. 28.

DIVIDING WALLS AND IRON DOORS OPENINGS INSERTED.

Section 559c, f.

(A) Distance to ceiling.
If A is less than 3' 0" fusible link at ceiling may be omitted.

(B) Steel plate, No. 12 U. S. gauge or greater.

(C) Continuous 2" x 2" x 3/8" Ls.

(D) 2 x 2 x 3/8" Ls forming panels. Angles not less than 2' 0" apart.

(E) Rivets spaced from 4" to 6" o. c.

(F) Door frames 3 x 4 x 3/8" Ls or alternate as by ordinance.

(G) 3/4" bolts, not more than 2' 0" o. c. fastening frame to wall.

(H) 1/4" iron or steel sill required.

(I) Sill fastened to frame by 1 1/2 x 1 1/2 x 1/4" Ls on inner side of frame. (Sec. 559f).

Exception: Sill plates may be omitted where floors are of concrete construction.

(c) Every such door shall be equipped with a device containing a fusible link or other releasing arrangement of equal efficiency, approved by the Commissioner of Buildings. There shall be one of these immediately above the door opening and one above the opening near the ceiling. Where the ceiling is less than three feet above the door opening, the last mentioned fusible link or releasing device may be omitted, if the doors are so arranged that the operation of any one of the thermostats, or other releasing devices, will result in the closing of the doors on both sides of the walls. Fusible links, or other approved substitute, shall be made so that they will fuse or operate when subjected to a heat of 160 to 165 degrees Fahrenheit. If said doors are of steel plate, the plate or plates shall be of No. 12 U. S. gauge or greater thickness, with a continuous two by two by three-eighths inch angle iron frame extending all around the same and two by two by three-eighths inch panel bars not exceeding twenty-four inches apart, riveted to the plate of the door with not less than three-eighths inch rivets spaced four inches

to six inches between centers. Pairs of swinging doors shall be so constructed that when the doors are closed, they will be of strength equal to that of a single door, and shall be so arranged that they will operate automatically. All doors shall be hung on wall frames of four by three by three-eighths inch angle iron or of four by three-eighths inch bar iron stiffened by one and one-half by one and one-half by one-fourth inch angles riveted on the back and fitting snugly to the wall. The frame shall be fastened together by three-fourths inch bolts extending through the wall, such bolts being not more than two feet apart. All doors to be made to fit closely to the wall frame on all sides. Lintels of door openings shall be made of brick, iron or concrete.

(d) Swinging iron doors shall swing on three wrought iron hinges made of two by three-eighths inch bar iron and shall be secured by at least three lever bars of one and one-half by three-eighths inch iron, working together and so arranged as to be operated on either side of the door.

(e) Sliding iron doors shall slide in channels at the top and bottom; bottom channels shall be formed by two angles two and one-half by three-eighths inch and one and one-half by one-fourth inch; top channels to be formed by two angles two by three-eighths inch and one and one-half by one-fourth inch; channels shall be securely riveted or bolted through the wall frame and where they extend beyond the wall frame shall be firmly bolted to the wall by expansion bolts. Track shall be without incline, of one-half by one-half inch iron securely riveted on the upper side of the angle iron channel. Hangers shall be of the anti-friction pattern and securely fastened to the door plate by at least four one-half inch bolts. Wheels shall be of cast iron three-fourths by four and one-half inches.

(f) Sills between iron doors shall be of one-fourth inch iron or steel with edges securely fastened to one and one-half by one and one-half by one-fourth inch angle iron or heavier, on the inner side of the wall frame. Where adjoining floors are of concrete construction, sill plates may be omitted.

(g) When tin-clad doors are used they shall be made of three thicknesses of thirteen-sixteenths inch seasoned, non-resinous wood, of good sound quality, free from sap and large or loose knots, tongued and grooved, dressed on both sides and not exceeding eight inches in width. The outside layers shall be vertical, the inside layer shall be horizontal; layers shall be securely fastened together by wrought iron clinch nails driven in flush and clinched so as to leave smooth surfaces. The woodwork shall be thoroughly covered with terne plate tin of size fourteen by twenty inches, weighing not less than one hundred and thirteen pounds per box of one hundred and twelve sheets; all joints shall be locked one-half inch and nailed under seams, except on edges of door; vertical joints shall be double locked, horizontal joints single locked. Nails used to fasten tin shall be No. 13 gauge, flat head, full barbed wire, two inches long.

(h) Swinging tin-clad doors shall have three-eighths by two and one-half inch wrought iron hinges bolted to doors with four three-eighths inch bolts. Doors in excess of seven feet in height shall be provided with three hinges and have wrought iron wall eyes built in wall, or riveted to wall frame, or bolted through wall with three-fourth inch bolts. They shall have at least three level bars of one and one-half by three-eighths inch iron, working together; the latch shall be placed so it can be operated from either side of the door and pro-

vided with proper keepers bolted through the door, with the spring to insure latching; catches shall be made of one-half inch wrought iron securely bolted to wall or wall frame.




Fig. 29.



Fig. 30.



Fig. 31.

DIVIDING WALLS AND IRON DOORS—OPENINGS INSERTED—(Continued).

Section 559g.

Fig. 29. Tin-clad Doors.

(A) Three thicknesses of 13/16" required.

(B) Boards not wider than 8". Outside layers vertical and inside layer horizontal laid.

(C) Nails clinched as (C).

Fig. 30. Single locked tin plate seam.

Fig. 31. Double locked tin plate seam.


(i) Sliding tin-clad doors shall have tracks inclined three-fourths inch to the foot, made of three and one-half by three-eighths inch rolled steel, or round bars, or round pipes of equal strength, securely bolted through wall with three-fourths inch bolts. Hangers shall be made of three-eighths by three and one-half inch wrought iron attached by not less than one-inch bolts. Wheels shall be of malleable or wrought iron with not less than one and one-half inches bearing on axle. Doors over six feet wide shall have three hangers and shall be provided with necessary binders, chafing strips, bumpers and bumper shoes.

(j) Sills between tin-clad doors shall be of one-fourth inch iron or steel riveted to a three and one-half by five by three-eighths inch angle iron on each side of the wall; angle irons to be fastened together through the wall by three-fourths inch bolts spaced not to exceed eighteen inches apart; provided, that where adjoining floors are of concrete construction, sill plates may be omitted.

(k) Rolling steel doors used as dividing wall doors shall be made either of wooden slats covered with steel or bronze, or of number 20 U. S. gauge painted steel, or of number 24 U. S. gauge galvanized steel. The edges of such doors shall run in steel channels not less than one and one-half inches deep, and three-sixteenths of an inch in thickness.

(l) Such doors shall be hung on winding shafts and helical springs of sufficient

strength to counterbalance the door at any position, and shall be equipped with a device to hold the doors in a closed position if the spring is destroyed. The head of the door opening shall have baffle plates of



SECTION




Fig. 32.

Section 559j.

Fig. 32. (H) 1/4 inch iron or steel sill.

(F) 3" x 5" x 3/8" L riveted to iron sill.

(G) 3/4 inch bolt 18" o. c.

Exception: Sill plates may be omitted where floors are of concrete construction.

number 12 U. S. gauge steel, which shall be reinforced around the edges by one and one-half inch angles, to act as fire and smoke stops. The openings for such doors shall have steel frames and sills as herein required for steel swinging doors.

(m) Wherever incombustible doors are to be used in openings to vertical shafts for stairways, passenger and freight elevators, pipes, conduits, and in corridor and room partitions, they may be made of two thicknesses of wood and covered with tin as described in paragraph (g) of this section, or of No. 20 U. S. gauge steel with stiles and rails not less than one and three-fourths inch and panels one-quarter inch thick, and the interior of said doors shall be filled with asbestos or non-resinous wood; provided further, that in fireproof buildings of Classes IIa, IIb, III, except when used in part as a stable and garage, IV, VI, and VIII, and in fireproof buildings of Class I, when equipped with an automatic sprinkler system, and when the occupancy does not constitute a special fire hazard in the opinion of the Chief of Fire Prevention and Public Safety, these openings, with the exception of openings to freight elevators, may be provided with incombustible doors consisting of a structure

of heavy, non-resinous wood not less than one and five-eighths inch thick assembled in the form of a long fibre asbestos fabric, weighing one and twenty-eight one-hundredths ounces per square foot, or other protective coating equally as incombustible and mechanically bonded therewith and veneered, or consisting of a structure of clear, non-resinous wood with panels not less than three-quarters inch thick and stiles and rails not less than one and five-eighths inch thick assembled in the form of a core and covered on all surfaces with an asbestos fabric and sheet steel, copper or bronze; provided, further, that nothing contained in this paragraph shall be construed as prohibiting the use of such incombustible doors as are described in paragraphs (c), (g) and (k) of this section and paragraph (b) of Section 558. The frames and trim shall be of materials as herein described.

(n) No glass panels shall be permitted in incombustible doors, except that in fireproof buildings of Classes I, IIa, IIb, III except when used in part as a stable or garage, IV, VI and VIII, doors to passenger elevators, stairs, halls, courts, fire escapes, corridor and room partitions, wired glass panels may be used not exceeding one thousand four hundred forty square inches in total area, no division of which shall exceed 720 square inches in area and no dimension of which shall exceed forty-eight inches in extent. Where an elevator or stairway is enclosed with incombustible partitions and doors for the purpose of obtaining credit for additional exits, no glass of any kind shall be permitted in these partitions or doors.

The penalty prescribed in Section 697 of The Chicago Code of 1911 for violation of the provisions of said Section 559, shall apply with equal force to the additional paragraphs set forth herein to be known as paragraphs (m) and (n) of said Section 559.

559. Metal or Reinforced Concrete Chimneys in Fireproof Buildings—Air Space.)

(a) Internal chimneys of rolled steel or iron may be built in buildings of fireproof construction, provided that the rolled steel shall be not less than three-eighths inch in thickness, except that the upper fifty feet of such chimney may be one-quarter of an inch in thickness, riveted in every joint, or of cast iron, providing same shall not be less than three-fourths inch in thickness and jointed by bell and spigot joints or flanged bolted joints. All joints in cast iron work shall be filled and pointed with fire clay. Such metal internal chimneys shall be securely and firmly anchored to the framing of such fireproof building at each floor line and at the roof. The lower part of each such chimney shall be lined with insulating lining for a height herein required for the respective area by Section 631 of this Chapter. The insulating lining shall be one of the linings described in Section 566 of this Chapter.

(b) Reinforced concrete not less than four inches in thickness may be used on the interior of fireproof buildings, provided the requirements for reinforced concrete and for reinforced concrete stacks elsewhere required by this Chapter shall be complied with.

(c) Internal metal or re-inforced concrete stacks on fireproof buildings shall be surrounded by continuous air space from the lowest story through the roof not less than four inches across at any point, and said air space shall be surrounded by brick, hollow tile, or reinforced concrete. No structural metal in such air space shall be without such fireproof covering.

561. Reinforced Concrete Chimneys—How Built.) Reinforced concrete chimneys in which the temperature of the gases is intended to exceed 750 degrees Fahrenheit, shall be lined with fire brick or magnesia

or asbestos insulating lining for the height and in the manner elsewhere required by this Chapter. If the insulating is stopped anywhere below the top of a reinforced concrete chimney or if the cross section of such a chimney is changed, then the reinforcing shall be increased at such points sufficiently to prevent the formation of temperature cracks.

562. Tenement and Apartment House Boiler Chimneys.) Chimneys for the heating apparatus of tenement and apartment houses shall not be considered as flues used for domestic purposes.

563. Height of Chimneys Above Roof.) (a) The height of all chimneys and flues of stoves used for domestic purposes or open fireplaces shall be not less than five feet higher than the highest point of the roof of the building of which they are a part.

(b) The height of all chimneys and flues above the highest portion of the roof of which they are a part, where such chimneys or flues are used for other than domestic purposes or for open fireplaces, shall be determined by dividing the greatest diameter in inches by four, and the quotient thereby obtained in terms of feet, with five feet added, shall be the minimum height from the tops of such chimneys and flues above the highest portion of roof of the building. In no case shall the height of any chimney or flue be less than five feet above the roof of the building of which it is a part.

(c) The sum of the horizontal distance of any wood tank, pent house or roof house, on the same building of which any chimney shall be a part, and the vertical distance of top of such wood tank, pent house, or roof house, on the same building to a horizontal plane passed through the top of the chimney shall not be less than one and one-half times the required height of the top of the chimney above the roof. The tops of chimneys within a radius of twenty-five feet of any wood tank, pent house, or roof house, on the same building of which such chimney shall be a part shall be at least as high as the top of said wood tank, pent house, or roof house. The tops of chimneys on ridge roofs shall be not less than three feet above the ridge.

564. Insulating Cavities—Where Required.) All flues having a greater area than four hundred square inches shall be lined on the inside with an insulating material, which lining shall start at least two feet below the smoke inlet and shall extend upwards for at least ten times the diameter of the flue, or if said flue is not circular or square in cross section for ten times the average diameter, when the flues are of brick, stone or concrete, said insulating lining shall be fire clay brick or fire clay blocks, and if such bricks or blocks are four inches or more in thickness, they may be considered as a portion of the thickness required for the surrounding walls. The walls surrounding chimneys having an area greater than four hundred square inches shall have an insulating cavity not less than three inches wide surrounding the inner four inches of fire brick or fire clay blocks, for not less than the height required above for insulating lining and said inner core shall be built independent of the surrounding brick work and shall be free to expand or contract.

565. Metal Chimneys in Buildings of Ordinary Slow-Burning or Mill Construction.) Interior stacks or smoke flues of metal shall not be used in buildings of ordinary or slow burning or mill construction, unless they are surrounded by self-supporting brick or re-inforced concrete walls of the thickness herein required for flues of the respective area; provided, however, that if




Fig. 33.

Fig. 34.




Fig. 35.




Fig. 36.




Fig. 37.

CHIMNEYS—INSULATING CAVITIES WHERE REQUIRED.

Section 564.

Figs. 33, 34 (A) Area of flue.

(E) Insulating lining.

(F) Insulating cavity.

Explanation: If A is more than 400 sq. in. an insulating lining (E) is required—(see Sec. 564 for further details). If A is more than 400 sq. in. the walls surrounding shall have an insulating cavity F not less than 3" wide.

If E in Fig. 34 is of fire brick of 4" or more in thickness it may be considered as a portion of thickness required for walls surrounding.

Section 567. Framing Around Chimneys.

Fig. 35. (C) Is distance joists or timbers are to be kept away from walls of chimneys = 2".

(D) Is distance to be kept away from inside of flue lining = 7".

Section 570. Walls Forming Smoke Flues.

Fig. 36. Shows chimney without flue lining.

If A = 144 or less, B = 8".

If A = more, than 144 and not more than 600, B = 12".

If A = more than 600, B = 16".

For exceptions see ordinance, Sec. 570.

Fig. 37. Shows Chimney with flue lining, not less than 3/4" thickness.

If A is 144 sq. in. or less, walls surrounding may be (B) or 4".

If A is more than 144 sq. in. and not more than 300 sq. in. B = 9".

If A is more than 300 and not more than 600, B = 12".

If A is greater than 600, B = 16" (exceptions and reductions being stated in Sec. 570).

an interior smoke pipe of steel of not less than three-eighths inch in thickness riveted in every joint, or an interior smoke pipe of cast iron not less than five-eighths inch in thickness is used, then the brick work required inside of the insulating cavity of a stack may be omitted, but such metal linings shall be lined with such insulating material for the height herein elsewhere required for stacks. If a chimney or stack is not a part of the walls of such a building, it shall be designed as an isolated chimney as required by Section 569 of this Chapter.

566. **Insulating Material for Metal Chimneys and Metal Stacks.** (a) Fire clay brick or fire clay blocks may be used for the insulating lining of metal chimneys and stacks but not of a lesser thickness than two inches. The material shall be increased in thickness or supported on structural steel ledges and the material shall be stressed not to exceed the safe limits of stress elsewhere herein fixed for the material, or metal chimneys and metal stacks may be lined with blocks of magnesia insulation or with fused asbestos board insulation, or metal stacks or chimneys may be lined with any other insulating material tested and approved by the Commissioner of Buildings.

(b) Magnesia block insulation shall contain not less than 45 per cent of magnesia and 50 per cent asbestos fibre formed into blocks not less than 1 1/2 inches in thickness by hydraulic pressure. After said magnesia blocks have been set, they and all metal bands and ties exposed with the flue shall be plastered with cement not less than one-half inch in thickness on one and one-half inch blocks, and one-fourth inch in thickness on one and three-fourths inch and thicker blocks.

(c) Fused asbestos board shall be made of alternate flat and corrugated sheets of asbestos board, cemented together and fused under a heat of not less than 1,000 degrees Fahrenheit to a minimum thickness of 1 1/4 inches. After said fused asbestos boards have been set into the flues, they and all exposed metal bands or ties shall be pointed with cement.

(d) Such magnesia blocks, fused asbestos boards, pointing cement and any other insulating material approved by the Commissioner of Buildings shall resist the disintegrating, dissolving, or diminishing action of moist steam and the acid and gaseous fumes present in the flue at any degree of heat obtainable by the combustion of the fuel used.

567. **Chimneys — Interior — Framing Around.** In case of chimneys which are enclosed, or form part of the interior of any building, no joists or girders shall rest or be supported on the walls of such chimney, and the framing around chimneys of all kinds shall be so constructed that in no case will any joists or timbers be placed nearer than two inches from the outside face of walls of flues, and in no case shall the distance from the inside of any flue to any joists or timbers be less than seven inches.

568. **Chimneys—External Location of.)** (a) Chimneys built outside of the walls of buildings shall not encroach upon any street or alley, and shall be built as follows:

(b) If at least one side of such chimney abuts entirely upon the wall of an existing building and the chimney is throughout its entire length securely and firmly anchored to the walls of such existing building, the wall of such chimney may be built of hollow tiles, in which case, however, it shall have a cast iron base, lined with fire brick, extending to a height of at least ten feet above the street or alley grade.

569. **Chimneys—Isolated—Walls Surrounding Smoke Flues.)** Isolated chimneys shall be so designed and constructed that the stress in every part thereof, due to the weight of the stack itself and from wind pressure, shall not exceed the safe limits as provided in this Chapter for the material used.

570. **Walls Forming Smoke Flues.)** The walls forming smoke flues of one hundred and forty-four square inches area or less shall be of brick, concrete, stone, or of any one of these and burnt fire-clay flue tile lining, and such flue linings shall extend from

The lowest opening to a distance of at least two feet above the roof joints. If only one of the above materials is used it shall not be less than eight inches in thickness. Provided, however, that such flues having walls at least three inches in thickness of continuous concrete or interlocking or rabbited joint concrete sectional flues may be used without burnt fire-clay flue tile linings. If any one of the above materials is used in combination with burnt fire-clay tile flue lining it shall be not less than four inches in thickness, and the burnt fire-clay flue lining shall be not less than three-fourths inches in thickness, and built as herein described. The walls forming smoke flues of more than one hundred and forty-four square inches area and not more than three hundred square inches area shall be of brick, concrete, stone, or any one of these and burnt fire-clay flue tile lining. If any of the above materials is used alone, it shall be not less than thirteen inches in thickness. If any one is used in combination with burnt clay flue tile lining, it shall be not less than nine inches in thickness and the fire-clay flue tile lining shall be not less than three-fourths inch in thickness and built as herein required. The walls forming flues having an area greater than three hundred square inches and less than six hundred square inches shall be built of one of the materials described above not less than twelve inches in thickness, and flues having an area greater than six hundred square inches shall have walls of one of the materials described above not less than sixteen inches in thickness, and these walls may be reduced to twelve inches in thickness at a point not less than fifty feet above the top of the breeching; provided, however, that the material of which all chimneys are constructed shall be so proportioned that it will not be subjected to a greater stress than elsewhere herein fixed as the maximum safe stress for such material.


571. Ventilating Ducts—Chutes—Walls Forming.) Walls forming ventilating ducts and rubbish and ash chutes shall be constructed in accordance with the regulations governing the construction of smoke flues elsewhere herein contained. Walls forming ventilating ducts shall not be less than four inches thick, and when the ventilating duct is larger than two hundred and sixty square inches the walls shall be not less than eight inches thick.

572. Smoke Pipes Passing Through Partitions.) In buildings hereafter erected it shall be unlawful to allow smoke pipes of greater diameter than six inches to pass through a combustible partition. Where a smoke pipe of six inches or less passes through a combustible partition it shall be surrounded by a ventilated thimble of incombustible material or by incombustible material with a diameter at least eight inches greater than the diameter of the pipe.

573. Boilers—Location of—Permit for.) In all cases, boilers shall be so placed as to give ample room between any ceiling, wall or partition to connect or operate any valves or pipes or other connections used on such steam boilers. The size, number and location of boilers to be installed in any building shall be marked on the plans and, except in buildings of Class III, approved by the Department of Smoke Inspection of Steam Boilers and Steam Plants, and by the Department of Smoke Inspection, before a permit is issued by the Department of Buildings for the erection of such building.

574. Foundry Cupolas—Construction of Charging Floors and Roofs—Height Above Roof.) There shall be no combustible material used in the construction of a charging floor or a roof within thirty-six inches of the foundry cupola. Where the charging

be used in the construction of such charging floor. Foundry cupolas shall extend twenty-five feet above the highest point of any roof within a radius of forty feet from such cupola, unless such roof is of metal or fireproof construction.



SECTION

Fig. 38.

SMOKE PIPES PASSING THROUGH PARTITIONS AND WOOD WORK AROUND.

Section 572.

- (A) Diameter of smoke pipe, 6" or less.
- (B) Diameter of thimble required 8" greater than diameter of smoke pipe.
- (C) Ventilation holes required.

floor is less than eight feet above the dump floor no combustible material whatever shall

575. Cornices — Eaves — Gutters — Pipes from Roofs.) (a) No wood shall be used for any purpose in connection with cornices, eaves and external gutters on any building more than fifty feet in height. The entire exterior covering of cornices and eaves of buildings hereafter to be erected within the fire limits shall be of incombustible material.

(b) Wherever sheet metal cornices or eaves or external gutters are used, their entire exterior covering shall be of metal or other incombustible material approved by the Commissioner of Buildings. Bracket supports for same shall be firmly secured to the wall at least every four feet, and the walls shall be carried full height under and behind same throughout their entire length.

(c) The water from all roofs shall be carried to the sewer in metal conductor pipes. Every such conductor shall be continually maintained in good condition, and if such conductors are within the exterior walls, they shall be of screwed-joint iron or steel pipe, or of cast iron pipe with caulked joints.

576. Towers, Domes and Spires—Construction of.) Towers, domes and spires may be built on top of the roofs of buildings, but shall not occupy more than one-quarter of the street frontage of any building. Such towers, domes, or spires, if any part thereof is built to a height of more than fifty feet and less than ninety feet, shall be of slow-burning construction, and, if of a greater height than ninety feet above the sidewalk, shall be of fireproof

construction; and, in all cases where the area of such tower, dome, or spire exceeds one hundred square feet, its supports shall be carried down to the ground, and shall be, if the structure supported is more than fifty feet and less than ninety feet high, of slow-burning construction, and, if more than ninety feet high, of fireproof construction. No tower, dome, or spire shall exceed thirty-six hundred (3,600) square feet in area, and in no case shall the area exceed fifteen per cent of the total area of the building on which it is erected, nor shall the height of any tower, dome or spire exceed four hundred feet measured from the established inside grade.

577. Structures—Construction and Limitations of.) All structures built within the City other than those otherwise specifically provided for herein shall be designed and constructed according to established engineering practice, and shall comply with the provisions of this section. No structure of frame or mill construction within the fire limits shall exceed 35 feet in height from the ground to the highest point thereof. No structure of mill or frame construction outside the fire limits shall exceed the height of 45 feet from the ground to the highest point thereof.

All structures over thirty-five feet in height within the fire limits, and all structures over forty-five feet in height outside the fire limits shall be built of structural steel, concrete or masonry; provided, however, that viaducts or runways to be used for the purpose of transferring livestock from one building or place to another may be built of wood not to exceed eighty feet in height either within or without the fire limits.

If it is desired to enclose any structure, such structure shall be enclosed with concrete or masonry walls, or incombustible material of such construction as shall be approved by the Commissioner of Buildings; provided that structures outside the fire limits not exceeding 2,800 square feet in area, or 45 feet in height, may be enclosed with combustible material.

In every structure contemplated by this section safe and adequate means of ingress and egress shall be provided for persons employed in and about the same.

All structures whose height exceeds twice their least dimensions at their base shall be so designed as to safely resist a wind pressure of 30 pounds per square foot of surface exposed to the action of the wind.

578. Skylights—Construction of—Glass in.) (a) Any skylight on the roof of any building less than ninety feet in height, other than a frame building, shall have the sides, sashes and frames constructed of metal, or of wood, metal clad on all exterior surfaces. Any skylight on a building more than ninety feet in height shall be entirely of incombustible material.

(b) Every skylight shall be provided with ventilation opening of an area of at least three per cent of the base area of the skylight.

(c) The glass in all such skylights, except in buildings in Classes III and VI, not exceeding three stories in height, shall have at least six inches over same a strong wire netting with wire not lighter than number twelve gauge, galvanized after weaving, and mesh not coarser than one by one inch, unless the glass contains a wire netting within itself. Supports for screen shall not be less in size than the bars supported and of the same material.

579. Enclosure Upon Roofs.) It shall be permitted to erect on the roofs of all buildings more than fifty feet and less than ninety feet high, skylights, inclosures for

water tanks and inclosures for elevator machinery, the construction of all of which inclosures shall be entirely of incombustible material; provided, however, that the roofs of same may be built of mill or slow-burning construction.

580. Roof—Construction of—Pitch of.) Buildings, other than frame buildings when permitted by this Chapter, less than fifty feet in height with roofs which have a slope of more than three inches per horizontal foot, shall have the roofs covered with incombustible material. Buildings more than fifty feet and less than ninety feet in height with roofs which have a slope greater than three inches per horizontal foot and which are of timber construction, shall have such roofs covered with an incombustible covering upon the roof boards, which shall be made either of mortar or porous terra cotta or plaster boards or other incombustible material, which shall be at least two inches thick. Where this covering is placed upon the roof boards wooden strips shall be inserted, which shall be securely fastened to the wooden structure at regular intervals between the incombustible covering and a weatherproof covering of incombustible material.

581. Roofs—Shingle or Gravel.) (a) The use of shingles or other forms of combustible roof covering erected or altered, otherwise than provided in Section 643, within the fire limits, is prohibited, except as hereinafter provided. In existing frame buildings not more than three stories high, the shingle roofs may be repaired with shingles or other materials.

(b) Roofs, the slope of which is not more than three inches per foot horizontal, and the covering of which is made of a composition of felt and gravel, shall be considered incombustible under the provisions of this Chapter, and may be used upon buildings of all classes. Other forms of composition roof shall be permitted if expressly approved as an incombustible roof by the Commissioner of Buildings.

582. Window and Door Sills—Columns and Lintels Supporting Store Fronts—Incombustible.) (a) For buildings other than frame buildings window and door sills shall be made of incombustible material. Oak timber used for door sills and not less than eight inches thick by the full width of the wall in which such sills occur, shall, for the purpose of this Chapter, be counted incombustible.

(b) In buildings other than frame and excepting buildings of Classes III and VI, lintels shall be of incombustible material; provided that in one-story store front buildings columns and lintels may be of combustible material.

583. Buildings—Height of—Parapet Walls—Roof Houses—Housing Tanks—Skylights and Scuttles.) (a) The limits of heights of buildings heretofore given for non-fireproof buildings shall be the perpendicular distance from the inside sidewalk grade of the street nearest the building to the highest point of the roof thereof. Where such street grade varies, the mean or average grade thereof opposite the building shall be the data from which such height is measured.

(b) The height of a fireproof building shall be the perpendicular distance from the inside sidewalk grade of the street nearest the building to the highest point of the external bearing walls. Where such street grade varies, the mean or average grade thereof opposite the building shall be the data from which such height is measured.

(c) No building shall be erected in the City of greater height than two hundred sixty feet. The erection of parapet walls or of balustrades constructed entirely of incombustible material shall be permitted

above the roof level of buildings of all classes, in addition to the height fixed herein for the same.

(d) Roof houses for elevators, tanks, skylights, stairs or scuttles may be built above the height of the main roof.

584. Basement—Defined.) The upper surface of the floor of the first story of buildings of every class excepting Classes VI and VIII shall be not more than ten feet three inches above the inside sidewalk grade of the street nearest the building and that portion of the building below said floor shall be designated as the basement of the building of which it is a part.

Notes: See Section 419 (b).

585. Sub-basements and Cellars—Construction of.) (a) No building shall have more than one basement or cellar of ordinary or slow-burning or mill construction; all additional basements or cellars shall be of fireproof construction as described in this Chapter, the elevator enclosures shall be of brick from the lowest basement floor level to the first story floor, and the stairways shall be inclosed in fireproof partitions from the lowest basement floor level to the first story floor level with automatic closing standard iron doors, opening outwards.

(b) In cases where a pipe, conduit, dumb-waiter, cable, wire, conveyor or belt, or any combination thereof, passes through a floor from one basement to another, the opening in the floor shall be inclosed as specified in this Chapter.

(c) The number and width of stairs from the lowest basement floor to the first story shall be the same as required for the four highest stories of a building of the same area.

586. Concrete Floors in Basements—Requirements.) Wherever concrete floors are laid in basements of buildings now in existence or buildings hereafter to be erected, the concrete of such floors shall be at least three (3) inches in thickness and such floors shall be laid on a sand or cinder foundation not less than six (6) inches in thickness.

NOTE: Section 585½ was passed March 28, 1917, and by error was given the number "600 1/2."

586. Canopy—Plans Must be Approved by Commissioner of Buildings Before Permit Issued by Department of Public Works.—Fee for Permit—No Advertising Matter or Obstructions Permitted.) It shall be unlawful for any person, firm or corporation to erect or construct any canopy attached to a building or structure under any general or special ordinance now in force or which shall or may hereafter be adopted by the City Council of the City of Chicago, without first submitting the plans of such canopy, and also of the part of the building or other structure to which it is to be attached, to the Commissioner of Buildings for his approval. No permit shall be issued by the Department of Public Works unless the plans of such canopy shall be approved by the Department of Buildings and a permit to attach said canopy to the building from which it is intended to project shall be obtained from the Commissioner of Buildings. The owner or agent shall pay to the Department of Buildings a fee of ten dollars for said permit. No canopy that has been or may hereafter be authorized by any general or special ordinance, which projects over any street or other public place shall at any time be enclosed by canvas or other cloth or material in whole or in part so as to obstruct free passage underneath same, nor shall any such canopy be equipped with or have attached thereto any illuminated or other signs, transparencies, placards, streamers or other advertising devices of any kind; and in case any such canopy shall at any time contain such advertising matter or device it shall be the duty of the owner, lessee

or person in charge or control of such canopy, upon notice from the Mayor, to forthwith remove such advertising matter or device.

586a. Canopies and Marquees—Annual Inspection Fee.) The Commissioner of Buildings shall make an annual inspection of canopies and marquees attached to buildings or other structures which shall extend into or over any street, alley or any public place, and for such inspection shall make the following charge:

Where the horizontal projection of the canopy or marquee does not exceed 200 square feet in area the annual inspection fee shall be five dollars; and where the horizontal projection of the canopy or marquee exceeds 200 square feet in area the fee shall be five dollars for the first 200 square feet and one dollar additional for each additional 50 square feet in the area of such canopy or marquee.

587. Courts and Light Shafts in Buildings.) (a) Every court or light shaft of every building shall be open and unobstructed from the bottom of such court to the sky, with the exception that fire escapes may be built therein, and such courts shall have walls constructed in the same manner as is required for the exterior walls of such buildings; provided, that no walls inclosing such courts are required on street or alley lot lines.

(b) All windows, doors or other openings in court walls, except as otherwise provided in this Chapter, shall have metal frames, metal sashes and metal doors, with the glazed portions thereof of wired glass.

588. Bay Windows—Light Courts—Shafts—Construction of.) (a) The walls of every bay window and every court in every masonry constructed building, except buildings of Class III, shall be built of brick or other fireproof construction throughout as required for exterior walls.

(b) The walls of every vent shaft of every masonry constructed building, except buildings of Class III, shall be built of masonry or a fireproof material not less than four inches in thickness supported by steel or iron.

(c) Every court, light shaft, or vent shaft in every building shall be open and unobstructed from the bottom of such court to the sky with the exception that fire escapes may be built in courts or light shafts, subject to all the provisions of this Chapter.

(d) All windows, doors, or other openings in court walls, except as otherwise provided in this Chapter, shall have metal frames, metal sashes and metal doors with the glazed portion thereof of wired glass.

589. Windows, Cleaning of—Safety Devices.) The owner or agent of every building in the city shall equip each and every window in any such building above the first story thereof with a suitable device or devices which will permit the cleaning of the exterior of each and every window in such building above the first story without danger to the person cleaning such windows, and such devices shall be of such pattern and construction as will reasonably and safely answer the purposes for which they are intended; provided, however, that if windows are of such construction that they may be easily cleaned from the inside they need not be equipped with such devices.

(See Illustration, Sec. 258b.)

590. (a) Wood Lathing and Plastering—Wallboard and Plasterboard—When Permitted as a Substitute.) In all buildings of frame or of ordinary construction, where the use of wood lath and plaster is permitted under the provisions of this chapter, such wood lath and plaster shall be done in accordance with these specifications:

Wood lath shall not be over one and one-half inches wide, and shall be nailed to each stud, joist or bearing with not less than a three-penny fine 16 gauge nail; lath to have joints broken with not over seven lath to a break; lath to be spaced not less than one-fourth of an inch apart. All wood lath must be covered with at least two coats of plaster; such lath and plaster to finish to a total thickness of at least seven-eighths of an inch; no dirty or loamy sand to be used in the mortar or plaster.

(b) In every building of frame or of ordinary construction which contains one or more rooms used for habitation or living purposes, the walls and ceilings of all rooms, including stores (except basement and attic

with at least one coat of plaster on wood lath; wood lath to be not over one and one-half inches wide, and shall be nailed to each stud, joist or bearing with not less than a three-penny fine 16 gauge nail; lath to have joints broken with not over seven lath to a break; lath to be spaced not less than three-eighths of an inch apart. All wood lath to be covered with a heavy coat of mortar; such lath and plaster to finish to a total thickness of three-quarters of an inch in thickness. Before applying such metal ceilings, a wood strip not less than seven-eighths of an inch by one and one-quarter inch wide shall be used under every lap bead, or nailing flange at the intersection of all plates. Strips to be not more




Fig. 39.

WOOD LATH AND PLASTERING.

Section 590.

- (A) Lath to be $1\frac{1}{2}$ " wide.
- (B) Break joints of lath every seventh lath.
- (C) Spacing of lath not to be less than $\frac{1}{4}$ " apart.

(Exception Class I— $\frac{3}{8}$ " spacing allowed—see Sec. 590b).

(D) Plaster coating to finish $\frac{7}{8}$ " thick.

(Exception Class I— $\frac{3}{4}$ " thick finish—see Sec. 590b).

rooms, not used for habitation or living purposes), throughout the building shall be covered with not less than two coats of plaster of the thickness and quality hereinbefore in this section prescribed.

Provided, however, that where such building does not exceed one story and basement in height and contains a room or rooms used for the purposes of Class I as defined in this ordinance, a metal ceiling may be installed in the room used for the purpose of Class I; and provided further, that where such building of frame or of ordinary construction and containing one or more living rooms is more than one story and basement in height and contains a room or rooms used for the purposes of Class I as defined in this ordinance, a metal ceiling may be installed in such room used for the purpose of Class I according to the following provisions:

The ceiling of the room or rooms used for the purpose of Class I shall be plastered

than two feet on centers in the direction of length of rooms with a cross strip every four feet on centers. A wire nail not less than three inches long shall be used in every strip at every joist in the surface to be covered. Metal plates to be not lighter than 29 gauge in thickness and nailed to every six inches on the lap.

(c) Where said metal-plates are applied on walls of buildings of frame or of ordinary construction containing one or more rooms used for habitation or living purposes, plastering upon walls must conform with the requirements of this ordinance for plastered walls. A strip three-eighths of an inch in thickness may be used upon which to apply the metal, same to be nailed to every stud with a nail not less than two and three-quarter inches long; steel plates used on walls to be not lighter than 29 gauge and applied same manner as herein provided for ceilings.

(d) Wallboard or plasterboard of gypsum, asbestos, or other approved incombustible material, containing not more than four per cent (4%) by volume of paper or other combustible fabric reinforcement may be used as a substitute for wood lath where the use of wood lath is permitted by the provisions of this chapter in buildings of frame or of ordinary construction. When such wallboard or plasterboard is attached to metal studding or metal furring and is used as a base for two coats of plaster or mortar, the wallboard or plasterboard and plastering finishing to not less than seven-eighths of an inch in thickness in ceilings and in hollow partitions and not less than two inches in thickness in solid partitions, it may be used in this manner in such buildings and under such conditions as follows:

In buildings of slow burning and mill construction for partitions other than corridor partitions and other than enclosing partitions around stairways, elevators, shafts or other floor openings.

In buildings of fireproof construction of Class II, Class III and Class VI for suspended or false ceilings below a fireproof floor system or roof system built in accordance with the provisions of this chapter and for partitions other than corridor partitions and other than enclosing partitions around stairways, elevators, shafts or other floor openings. The ingredients and the proportions thereof for mortar and plaster and the manner of mixing and preparing same for plastering, as used in accordance with the requirements of this section, shall be subject to the approval of the Commissioner of Buildings.

591. Scaffolds—Protection During Building Operations—Temporary Floors.) (a) All scaffolds erected in this city for use in the erection, repair, alteration, or removal of buildings, shall be well and safely supported, and of sufficient width, and properly secured, so as to insure the safety of persons working thereon or passing under or by the same; and to prevent the falling thereof, or of any material that may be used, placed or deposited thereon.

(b) It shall be the duty of every owner, person or corporation who shall have the supervision or control of the construction or of remodeling of any building having more than three framed floors, whether some or all of such floors are above the established street grade, to provide and lay upon the upper side of the joists or girders, or both, of the first floor below the riveters and structural steel setters, a plank floor, which shall be laid to form a good and substantial temporary floor for the protection of the employes and all persons engaged above or below or on such temporary floor in such building.

(c) Provided, however, that where the permanent floor is in place on the floor herein required to be planked, a temporary protective floor shall not be required.

(d) A good and substantial temporary floor shall be laid on the joists or girders of the next lower floor where the temporary or permanent floor of the second story or the floor or floors above the second story or roof is being placed previous to the placing of the permanent floor or floors immediately below the floor which is being arched or planked. The lowest framed floor in a building shall be considered the first floor.

(e) In buildings more than three stories high where persons are working on a scaffold or scaffolds on the outside of such building such persons shall be protected by well secured planking, set over the heads of such persons for the full width of the scaffolding on which they are working if another story or other stories are being raised above such persons during the time

they are working on such outside scaffold or scaffolding.

(f) It shall be the duty of all owners, contractors, builders or persons having the control or supervision of all buildings in course of erection which shall be more than thirty feet high, to see that all stairways, elevator openings, flues and all other openings in the floors shall be covered or properly protected, and it shall be their further duty to comply with an act of the State Legislature providing for the protection and safety of persons in or about the construction, repairing, alteration or removal of buildings, bridges, viaducts and other structures, approved June 3, 1907, and in force July 1, 1907.

(g) Any person, firm or corporation violating any of the provisions of this section shall be fined not less than one hundred dollars nor more than two hundred dollars for each offense, and any permit granted for the construction of such building may be revoked in the discretion of the Commissioner of Buildings where such violation occurs.

592. Sidewalk and Street—Occupation of—Limitations.) (a) The extent of occupation of sidewalk and street to be covered by the terms of a permit for street obstruction or building, shall be as follows:

(b) Such permit shall not authorize the occupation of any sidewalk or street or part thereof other than that immediately in front of the lot or lots upon which any building is in process of erection and in relation to which such permit is issued.

(c) During the progress of building operations, a sidewalk not less than six feet in width shall be at all times kept open and unobstructed for the purpose of passage in front of such lot or lots. Such sidewalk shall, if there are excavations on either side of the same, be protected by substantial railings which shall be built and maintained thereon so long as excavations continue to exist. It is not intended hereby to prohibit the maintenance of a driveway for the delivery of material across such sidewalk from the curb line to the building site.

593. Sidewalks—Delivery of Material—Elevated Sidewalks.) It shall be permitted for the purposes of delivering material to the basements of buildings in process of erection to erect elevated temporary sidewalks to a height of not exceeding four feet above the curb level of the street, and in case a sidewalk is so elevated it shall be provided with good, substantial steps or easy inclines on both ends of the same and shall have railings on both sides thereof.

594. Temporary Roof Over Sidewalk—Time Maintained.) When buildings are erected of a height greater than four stories and such buildings are near the street line, there shall be built over the adjoining sidewalk a roof having a framework composed of supports and stringers of three by twelve timbers not more than four feet from center to center, covered by two layers of two-inch plank. When additional stories are added to an existing building and such building is located near the street line, there shall be built over the sidewalk, at the point where the new stories commence, a scaffold not less than six feet wide, which shall form a covering over the sidewalk composed of a framework of stringers and supports, covered by two layers of two-inch planks. Such framework and covering shall be of such construction and design as shall be satisfactory to the Commissioner of Buildings. Such roof shall be maintained as long as material is being used or handled on such street front above the level of the sidewalk. Temporary sidewalks, their railings, approaches and roofs over same, shall be made with regard to ease of approach.

strength, and safety, to the satisfaction of the Commissioner of Buildings.

595. Storage of Building Materials—Limitations.) The occupation of the street for the storage of building material for any one building or for temporary sidewalks, shall never exceed one-third of the width of the roadway of the same, and in no event shall any material be stored or placed within four feet of any steam or street railway track, and in all cases where such obstruction of the street is made there shall be a clear space of not less than one foot between such obstruction and the curb line. Provided, that the Commissioner of Buildings and the Commissioner of Public Works, or either of them, may limit, or entirely restrict, the storage of material on any street or alley where a tunnel, conduit, or any underground passageway or subway is located.

596. Sidewalks and Street—Excavated Material and Rubbish On—How Cared for.) Earth, other than sand to be used in the construction of the building, taken from excavations, and rubbish taken from buildings shall not be stored either upon the sidewalks or roadways of streets, and shall be removed therefrom from day to day as rapidly as produced. When dry rubbish is being handled, it shall be kept wetted down so as to prevent its being blown about by the wind.

597. Use of Derricks.) For all buildings more than four stories in height the use of derricks set upon the sidewalk or street is prohibited. In no case shall the guy lines be less than fifteen feet above the roadbed.

598. Frontage Adjacent—How Occupied for Building Purposes.) If the written consent of and a waiver of claims for damages against the city by the owners of properties adjoining the site of any proposed building is first obtained and filed with the Commissioner of Public Works, the permission to occupy the roadway and the sidewalk may be extended beyond the limits of such building in front of the property for which the consent of the owner or lessee thereof has been secured upon the same terms and conditions as those herein fixed for the occupation of sidewalk and street in front of the building site.

599. Street—Use of for Building Purposes—When Terminated—Red Lights.) (a) The permission to occupy streets and sidewalks for the purposes of building is intended only for use in connection with the actual erection, repair, alteration or removal of buildings, and shall terminate with the completion of such operation. It shall be unlawful to occupy any sidewalk or street after the completion of the operation for which a permit has been issued by the Department of Buildings. It shall also be unlawful to occupy a sidewalk or street, under authority of such permit, for the storage of articles not intended for immediate use in connection with the operations for which such permit has been issued.

(b) Red lanterns shall be displayed and maintained during the whole of every night at each end of every pile of material in any street or alley and at each end of every excavation.

600. Street Obstructions—Permits—Bonds—Fees.) (a) Permits for the obstruction of streets shall be issued by the Commissioner of Public Works and shall be paid in proportion to the street frontage occupied at the rate of five dollars per month for every twenty-five feet or fractional part thereof, of frontage so occupied, and before any permit shall be granted to any person, firm or corporation for the obstruction of any street or streets or sidewalk, an estimate of the cost of restoring said street and sidewalk to a condition equally as good

as before it shall have been obstructed, with a fair additional margin for contingent damages, shall be made by the Commissioner of Public Works, which in no case shall be less than two dollars per foot, or fractional part thereof, frontage of the portion of the street to be obstructed, and a deposit shall be required of the person, firm or corporation desiring to obstruct said street or sidewalk. Such deposit, less the charge of five dollars per month for each twenty-five feet of frontage used, shall be returned upon the restoration of the said street and sidewalk to a condition equally as good as before it was obstructed. When the Commissioner of Public Works shall receive satisfactory proof that said street and sidewalk have been restored to a condition equally as good as before it was obstructed, he shall issue a certificate to the Comptroller, certifying to said fact, and the comptroller shall thereupon forthwith issue a warrant on the City Treasurer for the amount of money thus deposited less the deduction herein provided for. But if the person, firm or corporation thus obstructing said street or sidewalk shall fail to restore the same to a condition equally as good as before it was obstructed within three days from and after the completion of the building or structure for which said deposit was required, then the city shall have the right to use such portion of said deposit as may be necessary to remove the obstructions and to restore the said street and sidewalk to a condition equally as good as it was before it was obstructed, and the amount thus expended shall be deducted from the amount of said deposit; provided, however, that nothing herein contained shall preclude the city from maintaining any action against the person, firm or corporation to recover for damage done to any street or sidewalk. No permit shall be issued until the applicant therefor shall have executed and filed with the Commissioner of Public Works a bond, with sureties to be approved by said Commissioner, and in an amount to be designated by him, in no case to be less than ten thousand dollars, conditioned to indemnify, save and keep harmless the city from any and all loss, cost, expense or liability of any kind whatsoever which it, the city, may suffer or be put to, or which may be recovered from it from or by reason of the issuance of such permit, or by reason of any act or thing done or neglected to be done under or by virtue of the authority given in such permit and the requirements of the city ordinances.

(b) Any permit issued pursuant to the terms of this ordinance may be revoked by the Commissioner of Public Works at any time.

601. Stables and Barns—Regulations.) (a) It shall be unlawful for any person, firm or corporation to convert any building for the use of or to construct or maintain any stable or barn for the housing or keeping of more than two horses or other animals on any lot abutting on a street or alley in which a public sewer is constructed without providing such stable or barn with an impervious floor properly drained to such sewer.

(b) It shall be unlawful for any person, firm or corporation to construct, locate, conduct or maintain any boarding, sales or private stable or barn for stabling or keeping of horses on the front two-thirds of any lot on any street where one-half of the buildings on both sides of the street between the next nearest intersecting streets are used exclusively for residence purposes without the written consent of a majority of the property owners according to frontage on both sides of the streets. Such written consent shall be obtained and filed with the Commissioner of Buildings before a permit

is issued for the construction or alteration of any building or place for such purpose. Provided that in determining whether one-half of the buildings on both sides of the street are used exclusively for residence purposes any building fronting upon another street and located upon a corner lot shall not be considered.

(c) It shall hereafter be unlawful for any person, firm or corporation to locate, build, construct or maintain any building or structure for stabling or keeping of ten or more horses within a distance of four hundred feet from any school, church, hospital, public park or public playground.

(d) Any person, firm or corporation violating any of the provisions of this section shall be fined not less than twenty-five dollars (\$25.00) nor more than two hundred dollars (\$200.00) for each offense and each and every day on which such person shall conduct or maintain a stable or barn in violation of the provisions of this section, shall constitute a separate and distinct offense.

602. Tannery Not to Be Placed Within 600 Feet of Any Church, Public or Private School.) It shall be unlawful for any person, firm or corporation to build, construct, locate or maintain any building used, or to be used, for a tannery within six hundred feet measured from the nearest point of the tannery to the nearest point of any building used for a church or for a public or private school.

603. Gas Reservoir Not to Be Placed Within 500 Feet of any Public School.) It shall be unlawful for any person, firm or corporation to build, construct, locate or maintain any tank used or to be used for a gas reservoir within 500 feet of any public school. Said distance to be measured from the nearest point of the building or structure used for a gas reservoir to the nearest point of any building used for a public school.

604. Architect—Must Certify That Plans Comply With Building Ordinances.) It shall be unlawful for any architect or other person permitted under the state law to prepare plans to prepare and submit to the Commissioner of Buildings for his approval any final plans for any building or structure which do not comply with structural requirements of this Chapter. It shall be the duty of the Commissioner of Buildings to require that all final plans submitted to him for approval of any building or structure shall be accompanied by a certificate of such architect or such other person preparing plans that the plans and specifications submitted comply with the structural requirements of this Chapter.

NOTE: See also Section 232.

ARTICLE XIII.

Fireproof Construction.

605. Fireproof Construction—Definition of.) The term "fireproof construction" shall apply to all buildings in which all parts that carry weights or resist strains and also all exterior walls and all interior walls and all interior partitions and all stairways and all elevator inclosures are made entirely of incombustible material, and in which all metallic structural members are protected against the effects of fire by coverings of a material which shall be entirely incombustible, and a slow heat conductor, and herein-after termed "fireproof material." Reinforced concrete as defined in this ordinance shall be considered fireproof construction, when built as required by Section 550.

606. Fireproof Material—Definition of.) The materials which shall be considered as filling the conditions of fireproof covering are: first, burnt brick; second, tiles of

burnt clay; third, approved cement concrete; fourth, terra cotta.

607. Fireproof Construction—Tests For.) (a) In cases in which it is claimed that any equally good or more desirable mode or manner of construction, or material, or device for fireproofing, other than specified in this Chapter, can be used in the erection or alteration of buildings, the Commissioner of Buildings, upon written application to him for a permit to use the same, shall have power to appoint a Board of Examiners, consisting of not less than three nor more than five members, each of whom shall have at least ten years' experience as an architect, engineer or builder, who shall take the usual oath of office. Said oath of office shall be administered by the Commissioner of Buildings. The said examiners shall adopt rules and specifications for examining and testing such mode or manner of construction or material, or device for fireproofing, and furnish a copy of the same to the applicant. And such specifications shall provide that the material to be tested shall withstand successfully a fire of two hours' duration, rising to 1,700 degrees temperature, Fahrenheit, in the first thirty minutes and remaining at that temperature for the following ninety minutes. At the end of the two hours the material shall be quenched with at least a 1½-inch stream of water for five minutes, at a nozzle pressure of fifty pounds per square inch. The said examiners shall notify such applicant to submit the proposed material for such examination and test; and such tests shall be made in the presence of the said examiners, or a majority thereof, according to such rules and specifications. All expenses of such examiners and such examinations and tests, shall be paid by the applicant, and said examiners may require security therefor.

(b) The said examiners shall within 30 days after such examination and tests, certify the results of such test, and their decision on the said application to the Commissioner of Buildings, who shall in the event of the examination and tests being satisfactory, authorize the use of such material or construction as fireproof material.

(c) A complete record of the proceedings and all acts and decisions of the said Board of Examiners shall be kept by the Commissioner of Buildings in his office.

(d) The Commissioner of Buildings shall have the power to pass upon any question relative to the mode or manner of construction or materials to be used for fireproofing in the erection or alteration of any building or structure to make the same conform to the true intent and meaning of the several provisions of this Chapter.

608. Incombustible Material.) The following materials shall be considered as incombustible material: A metal or fire-resisting glass not less than one-quarter of an inch in thickness, metal, plastering on metal lath and metal-studding, plaster blocks, stone, granite, marble, approved cinder concrete, or one of the fireproof materials described in this chapter.

609. Walls—Enclosing in Buildings of Steel Skeleton Construction.) If buildings are made of fireproof construction, and have skeleton construction so designed that their enclosing walls do not carry the weight of floors or roof, then their walls shall not be less than twelve inches in thickness; provided, such walls shall be thoroughly anchored to the iron skeleton, and whenever the weight of such walls rests upon beams or columns, such beams or columns shall be made strong enough in each story to carry the weight of wall resting upon them without reliance upon the walls below them. All walls shall be of fireproof or incombustible material.

610. **Columns—Exterior.)** (a) All iron or steel used as vertical supporting member of the external construction of any building exceeding fifty feet in height shall be protected against the effects of external change of temperature, and of fire by a covering of fireproof material consisting of at least four inches of brick, hollow terra cotta concrete, burnt clay tiles, or of a combination of any two of these materials, provided that their combined thickness is not less than four inches. The distance of the extreme projection of the metal, where such metal projects beyond the face of the column, shall be not less than two inches from the face of the fireproofing; provided, that the inner side of exterior columns shall be fireproofed as hereafter required for interior columns.

(b) Where stone or other incombustible material not of the type defined in this ordinance as fireproof material is used for the exterior facing of a building, the distance between the back of the facing and extreme projection of the metal of the column proper shall be at least two inches, and the intervening space shall be filled with one of the fireproof materials.

(c) In all cases, the brick, burnt clay, tile or terra cotta, if used as a fireproof covering, shall be bedded in cement mortar close up to the iron or steel members, and all joints shall be made full and solid.

(Exterior and Interior Illustrations on the next page.)

611. **Columns—Interior.)** (a) Covering of interior columns shall consist of one or more of the fireproof materials herein described.

(b) If such covering is of brick it shall be not less than four inches thick; if of concrete, not less than three inches thick; if of burnt clay tile, such covering shall be in two consecutive layers, each not less than two inches thick, each having one air space of not less than one-half inch, and in no such burnt clay tile shall the burnt clay be less than five-eighths of an inch thick; or if of porous clay solid tiles, it shall consist of at least two consecutive layers, each not less than two inches thick; or if constituted of a combination of any two of these materials, one-half of the total thickness required for each of the materials shall be applied, provided that if concrete is used for such layer it shall not be less than two inches thick.

(c) In the case of columns having an "H" shaped cross section or of columns having any other cross section with channels or chases open from base plates to cap plates on one or more sides of the columns, then the thickness of the fireproof covering may be reduced to two-and-one-half inches, measuring in the direction in which the flange or flanges project, and provided that the thin edge in the projecting flange or arms of the cross sections does not exceed three-quarters of an inch in thickness. The thickness of the fireproof covering on all surfaces measuring more than three-quarters of an inch wide and measuring in a direction perpendicular to such surfaces shall be not less than that specified for interior columns in the beginning of this section, and all spaces, including channels or chases between the fireproof covering and the metal of the columns, shall be filled solid with fireproof material. Lattice or other open columns shall be completely filled with approved cement concrete.

612. **Columns—Wiring Clay Tile On.)** (a) Burnt clay tile column covering shall be secured by winding wire around the columns after the tile has all been set around such columns. The wire shall be securely wound around tile in such manner that every tile is crossed at least once by

a wire. If iron or steel wire is used it shall be galvanized and no wire used shall be less than number twelve gauge.

(b) In places where there is trucking or wheeling, or handling of packages of any kind, the lower five feet of every column with hollow tile shall be incased in a protective covering of No. 16 U. S. gauge steel embedded in concrete.

613. **Concrete—Approved Cement—When Fireproof.)** (a) All approved cement concrete shall consist of a standard Portland cement, torpedo sand, and crushed stone or gravel, or crushed blast furnace slag, or crushed burnt clay, the volumetric quantity of any one of these materials in addition to the torpedo sand shall not exceed eight times the volume of the Portland cement. All of the ingredients of cement concrete shall be thoroughly worked and wet so as to cover each piece of stone or gravel or slag or burnt clay with moistened cement; and the cement and sand shall fill the voids between the coarse material of the cement concrete.

(b) Cement concrete to be considered a fireproof material shall comply with the provisions of Section 550 and shall be cast and worked in an unset condition against the metal. In all cases where cinder concrete is used, the metal shall be protected as required by Section 554 of this Chapter.

614. **Concrete Ingredients.)** (a) The separate ingredients of concrete shall be measured for each batch, and shall be thoroughly mixed and must be uniform in color, appearance and consistency before placing. The concrete shall be worked continuously with suitable tools, as it is put in place, filling the forms completely.

(b) The sand to be used for concrete shall be clean coarse sand, free from loam or dirt. If crushed stone grit is used it shall be clean, gritty, and free from dust.

(c) The stone to be used in concrete shall be clean crushed hard stone, or clean crushed blast furnace slag, or gravel, and of a size to pass through a 1½-inch square mesh. If limestone or slag is used, it shall be screened to remove all dust; if gravel is used, it shall be thoroughly washed. Stone shall be drenched immediately before using.

(d) In all cases, the brick or hollow tile, solid or terra cotta shall be bedded in cement mortar close up to the iron or steel member and all joints shall be made full and solid.

615. **Pipes Enclosed by Covering.)** (a) Pipes shall not be enclosed in the fireproofing of columns or in the fireproofing of other structural members of any fireproof building; provided, however, gas or electric light conduits not exceeding one inch diameter may be inserted in the outer three-fourths inch of the fireproofing of such structural member, where such fireproofing is entirely composed of concrete.

(b) Pipes or conduits may rest upon the tops of the steel floor beams or girders, provided they are imbedded in cinder concrete to which slaked lime equal to five per cent of the volume of concrete has been added before mixing or their being imbedded in stone concrete.

616. **Shafts—Doors—Frames—Enclosure.)** (a) In cases where a pipe, conduit, dumb waiter, cable wire, conveyor, belt, or any combination thereof, passes from one story to another story through an open hatch or floor opening, a shaft or enclosure of fireproof material shall be built from floor to floor around such hatch or floor opening in each story above and below such hatch or floor opening in the same manner as described for fireproof partitions in this chapter, and no wood shall be used in the construction, support or fittings of such shaft.

The area of space thus enclosed shall not exceed the area of the floor opening by more than one hundred per centum.

(b) All burnt clay or terra cotta partitions or walls around such shafts shall be plastered on the outside and plastered or pointed on the inside.

(c) All doors, frames, sashes, casings and windows in partitions or walls around such floor openings, shall be built of incombustible material. The supports of such doors, frames, sashes, casings and windows shall also be of incombustible material. In

the case of doors, such supports shall be of rolled structural metal extending from floor to ceiling and secured to both. Where there are brick walls of twelve inches or more in thickness, the supports need not extend to ceiling as above specified. All glass used in connection with such partitions or walls shall be wired glass.

(d) Such fireproof enclosures may be omitted if all of the space in each floor opening not occupied by pipes, conduits, cables, wires, or any combination thereof, are filled in solid fireproof material not less than eight inches thick.

Fig. 40.




Fig. 41.




Fig. 42.






Fig. 43.



PLAN

Fig. 44.

PROTECTION OF EXTERIOR COLUMNS.

Section 610.

Figs. 40, 41, 42. Requirement for protection of columns of building exceeding 50 ft. height from external change of temperature and fire.

Fig. 40. (A) 4" concrete required.

(B) 4" brick required.

Fig. 41. (A) 4" solid porous tile required.

(B) 4" hollow tile required.

Fig. 42. (A) If stone or other incombustible material is used for exterior facing then (A) can equal 2".

(B) (C) Combination of materials in fire-proofing, etc., is allowed as at (B plus C), providing their combined thickness is not less than 4 inches.

PROTECTION OF INTERIOR COLUMNS.

Section 611. Requirements for Interior Columns.

Fig. 40. (A') Concrete 2" (shown dotted).

(B) Brick 4".

Fig. 41. (A) Solid porous tile, two layers of 2" each tile.

(B) Hollow tile, 2 layers of 2" each.

For hollow tile (C) is to equal 1 1/2" air space, and (D) not less than 3/4".

Fig. 42. (B plus C). Each equal 1/2" thickness required if used singly, provided if concrete (B) is used it should not be less than 2".

Section 611c.

Fig. 43. In case of H shaped cross section of columns, etc., fire-proof covering may be reduced to 2 1/2" (A) providing (B) flange projection is 3/4" or less.

If (B) is more than 3/4" as at (B') then A must be as before specified for interior columns as at (A').

Section 612b.

Fig. 44. Drawing showing protective casing for lower part columns. (A) = 5' 0".

617. **Spandrel Beams, Girders, Lintel.)**

The metal of the exterior side of the spandrel beams or spandrel girders of exterior walls, or lintels of exterior walls, which support a part of exterior walls, shall be covered in the same manner, and with the same material as specified for the exterior columns in this chapter; provided, however, that shelf angles connected to girders by brackets or projections of girder flanges not figured as part of the flange section, may come within two inches of the face of the brick or other covering of such spandrel beams, girders or lintels. The covering thickness shall be measured from the extreme projection of the metal in every case.

(Illustrations of beams on next page.)

618. **Beams, Girders and Trusses—Coverings of.)** (a) The metal beams, girders and trusses of the interior structural parts of a building shall be covered by one of the fireproof materials hereinbefore specified so applied as to be supported entirely by the

hollow tiles or if of solid porous tiles, or if of terra cotta, such tiles shall be not less than two inches thick, applied to the metal in a bed of cement mortar; hollow tiles shall be constructed in such a manner that there shall be one air space of at least three-fourths of an inch by the width of the metal surface to be covered within such clay coverings, the minimum thickness of concrete on the bottom and sides of metal shall be two inches.

(c) The top of all beams, girders, and trusses, shall be protected with not less than two inches of concrete or one inch of burnt clay bedded solid on the metal in cement mortar.

(d) In all cases of beams, girders or trusses, in roofs or floors, the protection of the bottom flanges of the beams and girders and so much of the web of the same as is not covered by the arches shall be made as hereinbefore specified for the covering of beams and girders. In every case the thick-




Fig. 45.




Fig. 46.




Fig. 47.

PROTECTION OF BEAMS. Section 617, 618.

(A) Fire-proof covering for beams, girders, etc., for exterior structural parts, Sec. 617. See provision for columns (Sec. 610) for A.

Fig. 45. (B) Allowable covering for shelf angles, etc., not figured part of flange section to be 2".

Figs. 45, 46, 47. Necessary fire-proof covering for beams, girders, etc., for interior structural parts (Sec. 618).

Fig. 46. (A) 4" for brick (Sec. 618b).

Fig. 47. (B) 2" for hollow tile or solid tile (Sec. 618b).

(A) 2" for concrete (Sec. 618b).

(C) 3/4" air space by width of metal surface to be covered as required (Sec. 618b).

(D) Concrete covering for tops of beams, girders, etc., to be 2" (Sec. 618c).




Fig. 48.




Fig. 49.

Where lintels are fireproofed previously and independently, the Commissioner of Buildings has ruled that the application of the architectural facing may be supported as shown (Fig. 48, 49).

beam or girder protected, and shall be held in place by the support of the flanges of such beams or girders and by the cement mortar used in setting.

(b) If the covering is of brick, it shall be not less than four inches thick; if of

ness of the covering shall be measured from the extreme projection of the metal, and the entire space or spaces between the covering and the metal shall be filled solid with one of the fireproof materials, excepting the air spaces in hollow tile.

The fireproofing herein required for metal structural roof members may be omitted in buildings used exclusively for purposes of Class IV and of Class V, when such structural roof members support only roof loads and ceiling construction over interior open spaces under the following conditions. A continuous ceiling of incombustible material shall be suspended below the roof from the structural roof members. There shall be no openings in ceilings other than those required for ventilation. Where the plane of the ceiling is twenty feet or more above the floor of the open space, all structural members or parts thereof projecting below said ceiling shall be fireproofed as required by the provisions of this Chapter. The fireproofing to extend upward two inches above the ceiling level. Where the plane of the ceiling is nearer than twenty feet to the floor of the open space all structural members above or below such ceiling to the height of twenty feet above the highest

ment of the floor of the open space shall be fireproofed as required by the provisions of this Chapter. Openings in ceilings for ventilation shall be connected by a conduit or duct to the outside of the building. Ducts shall be of metal or other incombustible material and if of metal where such ducts have an area greater than 400 square inches same shall be constructed double with an intervening air space.

(e) Provided, however, that all girders or trusses when supporting loads from more than one story shall be fireproofed with two thicknesses of fireproof material or a combination of two fireproof materials as required for exterior columns in Section 611 of this chapter, and each covering of fireproof material shall be bedded solid in cement mortar.

619. Fireproofing of Exterior Sides of Mullions.) In buildings required by this chapter to be of fireproof construction on exposures where metal frames, doors, sash and wired glass are not required, all vertical door or window mullions over eight inches wide shall be faced with incombustible material, and horizontal transom bars over six inches wide shall be faced with a fireproof or with an incombustible material.

620. Fireproof Covering, Independent.) The fireproof covering of brick, concrete, burnt clay tiles, hollow terra cotta or of a combination of any two of these materials shall be applied to all of the structural members of the exterior of a fireproof building previous to and independent of the application of the architectural facing of such fireproof building with an incombustible or fireproof material.

621. Walls, Support and Fireproofing of.) Where skeleton construction is used for the whole or part of a building the enveloping material and the walls shall be independently supported on the skeleton frame for each individual story.

622. Iron or Steel Plates for Support of Wall.) Where iron or steel plates or angles are used in each story for the support of the facings of the walls of such story, such plates or angles shall be of sufficient strength to carry the weight within the limits of fibre stress for iron and steel elsewhere specified in this chapter of the enveloping material for such story, and such plates or angles may extend to within two inches of the exterior of such covering.

623. Cut-out Boxes, Chases, Etc.—Fireproof Covering.) No electric service cut-out box, switch box, cabinet, chase or any other recess, shall encroach on the minimum thickness required for any fireproof covering on structural metal, except as provided in this chapter. If the depth of any cut-out box, switch box, cabinet, or chase, or if any other recess is to be concealed, or partially concealed, then the thickness of the fireproof covering shall be increased correspondingly.

624. Segmental and Flat Arches.) Segmental arches shall have a rise of at least one inch for each foot of span of arch.

(b) The least thickness of a hollow tile or porous terra cotta segmental arch shall be one-half of an inch per foot of span, but no such hollow tile or terra cotta arch shall be of a thickness less than five inches.

(c) Both flat and segmental arches shall be so constructed that the joints of the same radiate from a common center and there shall be a cross rib for every four inches, or fractional part thereof, in height in each tile block. The skewback of the arches supporting them, and in addition to the cross ribs, there shall be additional diagonal re-enforcing ribs in the skewback. Such arches, whether flat or curved, shall have their beds well bedded with cement mortar, and the

centers shall not be struck until the mortar has set.

(d) Burnt clay skewbacks shall be molded in such a manner as to support the burnt clay covering on the under sides of beams or girders.

625. Fireproof Floor and Roof Construction.) Brick, hollow tile, porous terra cotta, or approved cement concrete, or approved cinder concrete, shall be used for the construction of floor and roofs of fireproof buildings. Flat arch hollow tile, or flat arch porous clay tile floor arches shall have a height of at least one and one-half inches for each foot of span.

626. Wood Flooring and Nailing Strips.) (a) Wood flooring and wooden nailing strips for such flooring may be used in fireproof buildings.

(b) Where such flooring is used in a fireproof building, the space immediately under the flooring, and between the nailing strips and under such nailing strips, shall be filled with a cement or a cinder concrete tamped into place in an unset state, or with such other incombustible material as shall be approved by the Commissioner of Buildings.

627. Partitions in Fireproof Buildings.) (a) Where stairs, shafts and elevators are enclosed they shall be enclosed in fireproof partitions, as described in Section 628 of this chapter; all other partitions, shall be incombustible partitions. Where blocks are used for building partitions or as enclosing walls, the joints shall be well filled with mortar.

(b) The partitions shall be wedged tight between floor and ceilings with incombustible wedges.

628. Partitions — Fireproof — Incombustible.) (a) Only fireproof material shall be used for fireproof partitions; if of brick, they shall be not less than four inches thick, and if of partition blocks, not less than three inches thick. If fireproof partitions are of reinforced concrete they shall be not less than three inches thick.

(b) All fireproof partitions required by this ordinance shall be supported directly on the steel construction, or on the fireproof floor arches, or on concrete, or on brick.

(c) Only fireproof or incombustible material shall be used in the construction of partitions not required to be fireproof, excepting that frames, casings, doors, sash and the rough carpenter work required for the proper fastenings of such frames, casings, doors or sash, may be of wood, and that ordinary glass may be used in doors and partition windows.

(d) All corridor partitions of incombustible or fireproof material in fireproof buildings, shall be supported directly on the steel construction, on the fireproof floor arches, on concrete or on brick.

629. Stairs—Landings.) (a) Stairs in fireproof buildings shall be built of approved cement concrete, reinforced concrete, stone or metal, or a combination of one or more of such materials.

(b) The handrails of such stairways may be of wood.

(c) If stairs are constructed of solid stone or plain concrete, having the tread and riser in one piece, then there shall be not less than sixty square inches of stone or concrete in the cross section of such combined tread and riser.

(d) If stone treads have less than sixty inches of cross section and platforms less than seven inches in thickness are used, they shall have a metal sub-tread and sub-platform three thirty seconds of an inch thick.




Fig. 50.

Section 629c.

Fig. 50. Area of cross section A B C D E shall not be less than 60 sq. inches.

Section 629d.

Fig. 51. If area of cross section (A B C D) is less than 60 sq. inches or (E) (thickness of platform) less than 7 in., then metal sub-tread F and sub-platform P' ($\approx 3/32$ in. thickness) is required. Section 629e gives exception to above.

Fig. 51.

(e) If platforms have a floor arch sub-construction as described in Section 624 and 625 of this chapter, then the metal sub-platform may be omitted.

630. Roofs—Rise of Roof Above Limit of Height.) In the case of buildings which are fireproof in their construction, the roof may rise above the limit of height of wall fixed by this chapter for such buildings at a slope not to exceed thirty degrees with the horizon, and to a height not exceeding twenty feet above such limitation of the height of the wall. The space enclosed by such roof above the limitation of the height of such wall may be used as an inclosure for pipes, ventilating or elevator machinery or for ventilating ducts, but it shall not be lawful to use such space for purposes of storage, business or residence.

631. Sheet Metal Work—Support Of.) Wood shall not be used as the support of any sheet metal work or of any gutter or cornice of a building more than ninety feet in height.

ARTICLE XIV.

Slow Burning Construction.

632. Slow-Burning Construction Defined.) The term "Slow-Burning Construction" shall apply to all buildings in which the structural members, other than walls elsewhere required to be of masonry, which carry the loads and strains which come upon the floor and roofs thereof are made wholly or in part of combustible material, but throughout which the structural metallic members, if used are fireproofed as required for fireproof construction. Where metallic lintels are used to cover wall openings the fireproofing on the underside may be omitted where such lintels are fireproofed on the other three sides and all voids in them are filled solid with fireproof material. The lower five feet of metal columns shall be protected as required in Section 620 of this Chapter. Underside of joists shall be protected by a covering of three coats of plaster laid on metal lath; and a layer of mortar or other incombustible material at least one and one-half inches thick shall be applied on all floors and roof surfaces above the joists of same.

The fireproofing herein required for metal structural roof members may be omitted in any building of slow-burning construction used exclusively for purposes of Class IV of seating capacity less than one thousand persons or in any building of slow-burning construction used for purposes of Class IV in combination with any other Class where such part of such building as is used for purposes of Class IV has a seating capacity of less than one thousand persons and is separated from all other parts of such building by brick walls of thickness required in this Chapter and also by floors of fireproof construction, when such structural roof

members support only roof loads and ceiling construction over interior open spaces under the following conditions. A continuous ceiling of incombustible material shall be suspended below the roof from the structural roof members. There shall be no openings in ceiling other than those required for ventilation. Where the plane of the ceiling is thirty feet or more above the floor of the open space all structural members or parts thereof projecting below said ceiling shall be fireproofed as required by the provisions of this Chapter, the fireproofing to extend upward two inches above the ceiling level. Where the plane of the ceiling is nearer than thirty feet to the floor of the open space all structural members above or below such ceiling to the height of thirty feet above the highest point of the floor of the open space shall be fireproofed as required by the provisions of this Chapter. Openings in ceiling for ventilation shall be connected by a conduit or duct to the outside of the buildings. Ducts shall be of metal or other incombustible material, and if of metal where such ducts have an area greater than 400 square inches same shall be constructed double with an intervening air space. The floor levels of balconies and galleries having a gross area of less than fifteen per cent (15%) of the gross area of the floor of such open space shall not be used as a basis for calculating the height of such fireproofing.

633. Posts, Girders and Partitions.) Wood posts, if used, shall be of not less than one hundred square inches sectional area. Wood girders, if used, shall be of not less than seventy-two square inches sectional area. All partitions in buildings of this type shall be made entirely of incombustible material. Wood furring, wood studs and wood lath shall not be permitted in buildings of this type.

634. Stairs, Construction of.) Where buildings are required to be of "slow burning" construction, all stairs in such building shall be of incombustible material, except as hereinafter provided. Said stairs may be of ordinary construction, if said building is equipped with an automatic sprinkler system, and stairs are enclosed in a fireproof wall.

ARTICLE XV.

Mill Construction.

635. Definition—Mill Construction Requirements.) The term "Mill Construction" shall apply to all buildings in which wooden posts, if used, have a sectional area of not less than one hundred square inches, and wooden girders and joists a sectional area of not less than seventy-two square inches, and roofs, if of wood, a thickness of not less than two and five-eighths inches in a single layer, except where the building is equipped throughout with a sprinkler system, subject to the approval of the Chief of Fire Prevention and Public Safety, when such layer may be not less than one and five-eighths inches thick, and floors, if of wood, a thickness of not less than three and one-half inches in not more than two layers, the lower one of which shall be not less than two and five-eighths inches in thickness, and in which all structural metallic members, if used, are fireproofed as required for fireproof construction. Where metallic lintels are used to cover wall openings the fireproofing on the underside may be omitted where such lintels are fireproofed on the other three sides and all voids in them are filled solid with fireproof material. All floors and roofs not constructed as above shall be of fireproof construction as elsewhere required for fireproof construction in this ordinance.

636. Fireproofing.) (a) Partitions in buildings of mill construction shall be made entirely of incombustible material. If iron columns, girders, or beams are used in

buildings of this type they shall be protected as specified in this Chapter; but the wooden posts, girders and joists need not be protected by fireproof covering. Wood furring, wood studs and wood lath shall not be permitted in buildings of this type.

(b) If reinforced cinder concrete construction is used in the structural parts of a building which is required to be of slow-burning or mill construction by this chapter, then all partitions shall be of incombustible material and all parts other than structural parts and partitions of the building shall be as required for slow-burning or mill construction buildings by this chapter.

637. Stair Construction Where Automatic Sprinkler System is Installed.) In buildings required to be of "mill construction," all stairs in such buildings shall be of "incombustible" material, except as hereinafter provided. Said stairs may be of wood construction if said building is equipped with an automatic sprinkler system and stairs are enclosed in a fireproof wall.

ARTICLE XVI.

Ordinary Construction.

638. Ordinary Construction Defined.) The term "ordinary construction" as used in this chapter, means the ordinary system of construction in which timber and iron structural parts are not protected with fire-resisting coverings and in which the walls are of masonry built as required by this chapter.

ARTICLE XVII.

Frame Buildings.

639. Repairing of Frame Buildings Within Fire Limits.) Frame buildings within the fire limits which have been damaged by fire, decay or otherwise, to an extent not greater than fifty per cent of their value may be repaired, provided there is no increase in size of such buildings over their original dimensions, and, provided that incombustible roof covering required by Section 581 is used. And, provided, further, that where any frame building is raised for the purpose of erecting a basement story under the same, the walls enclosing such basement shall be of masonry.

640. Frame Building within Fire Limits Prohibited—Exceptions—Brick Veneer.) (a) Hereafter no frame building shall be erected, nor any frame addition made to any existing frame building within the fire limits of the city, except where express provision is made in this chapter therefor.

(b) Outside the fire limits it shall be lawful to erect frame buildings not exceeding forty feet in height from the sidewalk to the highest point of roof. If such frame buildings have a basement story of masonry, their height above the sidewalk may be made not to exceed forty-five feet. Provided, however, that in no case shall any portion of any frame building above the second floor be used as a separate living apartment.

(c) It shall be lawful to surround frame buildings with a veneer of brick not less than four inches in thickness, provided the said brick is not carried higher than the second story, or twenty-two feet above the basement ceiling; and provided further that the said veneer is anchored to the studding or other frame construction in a manner satisfactory to the Commissioner of Buildings. Such brick veneer is not to be placed on gables or any other parts of frame buildings above the height herein specified. All frame buildings which it is desired to surround with brick veneer must have their basement walls and foundations of solid

masonry, as provided in Section 644 of The Chicago Code of 1911.

641. Frame Buildings Within the Fire Limits Changed Into Flat Buildings—Fire Walls.) Whenever any frame building within the fire limits shall be remodeled, altered or charged for the purpose of using the same for flats or apartments, or whenever such frame building shall be occupied for flat or apartment purposes, each suite of apartments in such building shall be separated from every other suite of apartments in such building by a wall of incombustible material, of such dimensions and thickness as required by this chapter.

642. Frame Buildings—Raising—Requirements—Changing Gable or Hip Roofs to Flat Roofs.) Permission may be granted by the Commissioner of Buildings for the raising of existing frame buildings, whether within or without the fire limits, to the limits of height hereinbefore fixed for new frame buildings, and no more, and inside the fire limits for the purpose of putting a masonry basement thereunder. The Commissioner of Buildings is also authorized to issue permits for changing gable or hip roofs of existing frame buildings to flat roofs, and for the raising of walls incident to such change. But if such hip or gable roof is changed to a flat roof and the walls raised in connection with such change, the total cubic contents included by the walls so raised and the roofs so altered shall not exceed the cubic contents originally included in such gable or hip roof, and in no case shall a two-story and attic building be converted into a three-story building thereby.

643. Frame Buildings Carried to a Uniform Height.) Where the different parts of a frame building inside the fire limits are of different heights a one-story portion may be raised to the height of two stories, provided the greatest height thereof does not exceed the limits of height prescribed in this chapter for frame buildings and provided, that no room in the existing building or in the addition thereto shall violate the requirements of this chapter for habitable rooms.

644. Basement or Story Placed Beneath Frame Buildings.) A frame building may be raised for the purpose of erecting a basement or story, or both, thereunder, but the principal floor of such frame building shall not be raised to a higher level than 16 feet above the grade of the sidewalk upon which such premises abut. Where a building so raised one story in height only and the same is raised so as to permit a basement under the same not to exceed six feet six inches in height from the basement floor to the ceiling of said basement, the said house may be placed upon cedar posts. In all other cases the walls enclosing such basement or story shall be of masonry and not less than 12 inches thick except where a one-story frame building is raised and has a basement only built thereunder, the masonry walls of such basement may be eight inches thick above grade and 12 inches thick below. The foundation of such wall shall be constructed as provided in this chapter; provided, however, that no frame building shall be raised for the purpose of constructing a basement or story, or both, under the same to a greater height to the top of its roof than that elsewhere herein given as the maximum height above grade for frame buildings. The thickness of walls hereinbefore required shall also apply to brick walls in new frame buildings.

645. Chimneys in Frame Buildings—Chimney Flues Through Partitions.) Chimneys in frame buildings shall be built as required by Section 570 of this chapter. The wood framing of frame buildings shall be trimmed around chimneys in such a manner as not to come within two inches of same.

646. **Lot Lines—Requirements as to—Number—Dimensions.)** Frame buildings, excepting sheds not exceeding three hundred square feet in area shall not be built nearer than one foot to any line of the lot upon which they are built, street and alley lines excepted, except as hereinafter provided. It shall not be lawful to erect a frame building wider than forty feet nor deeper than seventy feet, unless such building be divided by a fire wall or fire walls, built of incombustible material and of a thickness of not less than four inches and of construction to be approved by the Commissioner of Buildings, so that no more than two thousand eight hundred square feet of superficial area shall be contained in any section or part of such building, uninclosed by such fire walls, and if openings are inserted in such fire walls, then such walls shall be built of brick not less than eight inches thick, and such openings shall have doors as described in Section 559. Each section of such buildings shall be regarded as a separate building for the purpose of determining the number and construction of its stairways and means of egress. If more than one frame building is built in the direction of the depth of any one lot, such buildings shall not be built with a less distance than ten feet between them except where both buildings are used for living purposes, and in that case the distance shall be governed by Sections 426 and 427 of this chapter.

647. **Sheds—Open Shelter—Height of Walls and Foundations—Enclosed.)** (a) Except as hereinafter provided, open shelter sheds not exceeding eight hundred square feet in area not exceeding fourteen feet in height from the ground may be erected within the fire limits, provided they have roofing of incombustible material and the highest point is not over fifteen feet above the ground, and provided that the roofs be supported on sufficient posts or piers; provided, however, that such sheds may be built with an area not to exceed sixteen hundred square feet, if they are kept at least twenty-five feet from any lot line and any other building or structure. Such sheds shall have no combustible enclosing walls or wooden floors, except that a floor of two-inch planking laid directly upon the ground may be used. Such sheds shall only be erected upon the rear of the lot, and not more than one such shelter shed or any other shed shall be erected on any lot of twenty-five feet in width.

(b) If it is desired to enclose an open shelter shed, the enclosing walls shall be made of brick, hollow tile, or other incombustible material, and such walls shall have foundations extending to solid ground and at least four feet below the surface of the ground.

(c) Open shelter sheds may be erected outside the fire limits not to exceed twenty-eight hundred square feet in area and subject to the approval of the Commissioner of Buildings; provided, however, that shelter sheds which comply in other respects with the requirements of this section, may be built not to exceed nine thousand square feet in area where such sheds are located at least twenty feet distant from any other structure and from any lot line.

(d) Sheds not exceeding fourteen feet in height from the ground to the highest point thereof, and not exceeding three hundred square feet in area, with an incombustible roof, may be constructed of wood within the fire limits. Such sheds shall not be located on the front part of any lot, nor shall they be used as a dwelling or as an addition to a dwelling house, or for any business purpose whatever, nor shall more than one shed be erected on any one building lot of twenty-five feet in width.

648. **Sheds—Coal, Brick, Stone, Cement and Salt Sheds and Sheds for Icing Cars Along Railroad Tracks and Navigable Streams.)** Open shelter sheds to be used for the storage or handling of coal, brick, stone, cement, salt or such commodities which are incombustible, or for the icing of cars, may be erected within or without the fire limits upon, along or adjacent to steam railroad tracks, or along or adjacent to navigable waters; provided, such sheds shall have incombustible roofing and shall not exceed 35 feet in height from the ground to the highest point of the roof; provided, further, that said sheds shall be located at least 25 feet distant from any other structure and from any side lot line. If it is desired or intended to enclose any such sheds, the enclosing walls shall be of incombustible material. No such shed shall be built upon any lot or parcel of ground fronting upon any street within 200 feet of any building used exclusively for residence purposes, unless the consent of the owners of the majority of the frontage on both sides of such street between the two nearest intersecting cross streets shall first have been obtained by the person, firm or corporation desiring to erect and maintain such shed, and said written consents shall be filed with the Commissioner of Buildings before a permit shall be issued for such shed.

649. **Ice Houses.)** (a) Houses within the fire limits to be used exclusively for the storage of ice, not exceeding forty-five feet in height, and of a floor area not exceeding 9,000 square feet, may be constructed of wood with incombustible roofing, the walls to be enclosed with an envelope of incombustible material; eight-inch walls of brick or tile or approved cement concrete with proper foundations of masonry shall be used for such envelopes.

(b) Houses to be used exclusively for the storage of ice, located outside of the fire limits and contiguous to any lake and six hundred feet from any other building, except buildings used in connection with the conduct of said business, may be constructed of frame with incombustible roofing, and the floor area of any such building shall not exceed eighty thousand square feet, unless the building is divided by a solid wall of masonry for each additional 80,000 square feet of floor area, or fractional part thereof; and shall extend at each end not less than one foot beyond the enclosure of said building and such wall shall be subject to the approval of the Commissioner of Buildings.

(c) Houses to be used exclusively for the storage of ice, located outside of the fire limits, and contiguous to railroad tracks and not within one hundred feet of any other building, may be constructed of frame with incombustible roofing, and the floor area of any such building shall not exceed 20,000 square feet unless the building is divided by a solid wall of masonry for each additional 20,000 square feet of floor area or fractional part thereof; said wall shall extend at least one foot beyond the enclosure of said building on each end and shall be approved by the Department of Buildings.

(d) All dividing walls must extend through and above the roof of any building in which they are built to a distance of three feet and must be covered with incombustible coping. No dividing wall shall be of less thickness than twelve inches at any point thereof.

ARTICLE XVIII.

Stairways.

650. **Stairways, Number—Location—Construction.)** (a) Fireproof office buildings existing at the time of the passage of this ordinance which are equipped either with one stairway and two or more stairway

fire escapes or with two stairways and one or more stairway fire escapes, shall not be required to have additional stairways or stairway fire escapes.

(b) Except as otherwise expressly provided in this Article, it shall be unlawful to construct or maintain any building or structure of Classes I, II and VII unless its stairway or stairways comply with the following provisions:

(c) In every existing building of ordinary construction having an area greater than 9,000 square feet or of mill or slow-burning construction greater than 12,000 square feet, there shall be not less than three stairways. The width of stairs shall be at least eighty per cent of the width of stairs as computed by the formulae given herein and in no case less than twelve feet.

(d) Every building shall have at least one stairway from the ground to the top floor and one stairway from the lowest basement or cellar to the street grade, and no stairway shall be less than three feet in width.

(e) The width of stairs required for a building shall be constructed as the total width of all stairways required on the building. Stairs shall be measured between the wall and handrail for a single stair and between handrails where two or more handrails are required by this chapter.

(f) In buildings of Class I and Class IIa the width of stairs and fire escapes required for a building shall be determined by the floor area measured on the third floor of the building and such area shall not include walls, columns, stairs, elevator shafts, well holes, chimneys and corridors. In all cases where the building is less than three stories in height the width of stairs shall be determined by the floor area of the second floor as hereinafter specified.

(g) Where the enclosed space between a ceiling and the roof of a building of any Class is of greater average height than two feet in the clear, access shall be provided by means of at least one stairway not less than three feet wide leading from a public hallway or corridor.

(See Illustration, Sec. 398).

651. Stairs—Number and Width of in Classes I, II and VII. (a) In buildings of Class IIb, Class IIc and Class VII the number and width of the stairs and fire escapes shall be determined by the area of that portion of the third floor not occupied by walls, columns, stairs, elevator shafts and well-holes.

In buildings of Class I, II and VII the number and width of stairs required shall be as follows:

(b) IN ORDINARY CONSTRUCTION.

With floor area of 5,000 square feet or less, two stairways;

With floor area of 5,000 to 9,000 square feet, three stairways.

Provided, however, that in buildings of ordinary construction, existing prior to December 5, 1910, with floor area of 5,000 square feet or less, one stairway only shall be required where the building is also equipped with an outside stairway fire escape, and in all such buildings with floor area of from 5,000 to 9,000 square feet, two stairways only shall be required; provided such building is also equipped with an outside stairway fire escape.

(c) The width of stairs required in buildings of ordinary construction shall be computed as follows:

The width of stairs in inches shall be equal to the result obtained by deducting 2,000 from the floor area of the building in square feet and multiplying the remainder

by twelve and dividing the product by 1,000 and adding 72 inches to the quotient, expressed in the formula as follows:

$$\frac{72 \text{ inches plus } (\text{area}-3000) \text{ times } 12}{1,000}$$

(d) IN MILL OR SLOW-BURNING CONSTRUCTION.

With floor area of 6,000 square feet or less, two stairways.

With floor area of 6,000 to 12,000 square feet, three stairways.

(e) The width of stairs required in buildings of mill or slow-burning construction shall be computed as follows:

The width of stairs in inches shall be equal to the result obtained by deducting 3,000 from the floor area of the building in feet and multiplying the remainder by eight and dividing the product by 1,000, and adding 72 inches to the quotient; expressed in the formula as follows:

$$\frac{72 \text{ inches plus } (\text{area}-3,000) \text{ times } 8}{1,000}$$

(f) IN FIREPROOF CONSTRUCTION.

With floor area of 7,000 square feet or less, two stairways.

With floor area of 7,000 to 15,000 square feet, three stairways.

With floor area of 15,000 to 21,000 square feet, four stairways.

With floor area of 21,000 square feet and over, five stairways.

(g) Provided, however, that in fireproof buildings having an area of 21,000 square feet or more only four stairways shall be required if such building is completely equipped with an approved automatic sprinkler system.

(h) The width of stairs required in buildings of fireproof construction shall be computed as follows:

The width of stairs in inches shall be equal to the result obtained by deducting 3,000 from the floor area of the building in feet and multiplying the remainder by six and dividing the product by 1,000, and adding 72 inches to the quotient; expressed in the formula as follows:

$$\frac{72 \text{ inches plus } (\text{area}-3,000) \text{ times } 6}{1,000}$$

(i) Provided, however, that where buildings of Class I are of fireproof construction and are used solely for storage warehouse purposes and the number of persons employed on any one floor does not exceed the number specified hereafter in this section they shall comply as to number of stairways as follows:

With floor area less than 8,000 square feet where not more than ten persons are employed on a floor, two stairways.

With floor area greater than 8,000 square feet and less than 15,000 square feet where not more than fifteen persons are employed on a floor, three stairways.

With floor area greater than 15,000 square feet where not more than twenty persons are employed on a floor, four stairways.

(j) The width of stairs shall be computed as follows:

The width of stairs in inches shall be equal to the result obtained by deducting 2,000 from the floor area of the building in feet and multiplying the remainder by four and dividing the product by 1,000, and adding 72 inches to the quotient; expressed in the formula as follows:

$$\frac{72 \text{ inches plus } (\text{area}-2,000) \text{ times } 4}{1,000}$$

(k) Provided, however, where buildings of Class I are used solely for storage or warehouse purposes and the number of persons regularly employed above the floor nearest the street level does not exceed ten persons or where the number of persons occasionally employed above the floor nearest the street level does not exceed twenty persons, the floor area of such building may be increased fifty per cent (50%) in excess of the area limits as provided in this Section for buildings of Class I of ordinary, slow-burning mill or fireproof construction for the given number of stairways. The width of such stairways shall be as determined by use of formula given for each separate type of construction, by using two-thirds of the actual floor area of such building as a basis for the calculation, and by substituting the words and figures, "64 inches," for the words and figures, "72 inches," where they occur in said formula. There shall be not less than two stairways, or one stairway and a stairway fire escape directly accessible from each area of such building, and the location of all stairways and fire escapes shall be subject to the approval of the Commissioner of Buildings. The minimum width of any stairway in such buildings now in existence shall be not less than thirty inches (30"), the minimum width of any stairway in such buildings hereafter erected or hereafter converted to such use shall be not less than thirty-six inches (36"), and the minimum width of any fire escapes shall be not less than twenty-four inches (24").

652. Stairs—Other Requirements.) (a) The width of stairway fire escapes and three-quarters of the width of sliding fire escapes required by this chapter may be deducted from the width of stairs required.

(b) Stairways shall be located as far from each other as practicable. The bottom of each stairway shall be in the immediate vicinity of the top of the stairs leading to the next lower story and the line of travel from stairway to stairway shall be direct and easily accessible each to the other. At least one stairway shall extend to the roof of every building. In Classes I, II and VII, the whole number of stairways required for each building shall be complete in every respect from the first to the topmost story.

(c) Every story below the street grade shall have not less than two stairways to the first story and each such stairway shall be not less than three feet wide, but where a basement or cellar is used for the retail sale of goods the stairway from such basement or cellar shall in number and aggregate width comply with the requirement of this section for the first four stories above sidewalk grade.

(d) Where two areas of the same building adjoin and are separated by fireproof dividing walls they may have a stairway in common, provided such stairway is not less than five feet wide and is inclosed in all stories of the building by fireproof walls in non-fireproof buildings and by fireproof partitions in fireproof buildings; and where the stairways and landings are built as required by this chapter for buildings of fireproof construction, and where the doors, frames, sashes and casings, and the glazed portion thereof are built as described in Sections 558 and 559 then in such case such stairway may be considered as equivalent to one open stairway from each such area, and where such stairway provides exit from only one floor area such stairway may be considered as equivalent to two open stairways but in no case shall there be less than two stairways in any such building except as otherwise provided in this chapter.

(e) Where adjoining buildings or buildings on opposite sides of an alley or other open space, and of the same class, used

by the same person, firm or corporation, are connected by fireproof bridges or passageways with fireproof doors at each end, or by fireproof doors on each floor built and equipped as required by this chapter for dividing wall doors if such bridge or passageway or fireproof door is located as far as practicable from the stairways in both said buildings, then said bridge or passageway or fireproof door may be considered to be equivalent to a stairway for each of the two areas.

(f) In buildings of Classes I, II and VII, where an interior stairway is inclosed in a tower and built as required by the provisions of Section 653 paragraph (n) of this Chapter, then such stairway shall be considered the equivalent of two stairways, or a stairway and a fire escape; provided, however, that if such stairway is considered the equivalent of two stairways the building must be equipped with a stairway fire escape, or fire escapes, as is required by this Chapter.

(g) Exterior stairways in buildings of Class I, II and VII built entirely of steel and iron, having ice-proof treads not less than ten inches wide from nosing to riser and a riser of eight inches or less for each riser, and otherwise made as required for stairway fire escapes in this chapter and where such stairway fire escape extends from the inside grade to the top floor of the building or is supplied from the second floor to the ground with a counterbalanced section and has a steel ladder from the top landing to the roof, then such stairway may be considered the equivalent of one interior stairway and one stairway fire escape if the width of such stairway and that of the one or more stairways in the building equals the width of stairs required by this chapter; provided, that in such case the respective floors, door sills, and stairway platforms are flush, and that the doors do not obstruct the stairs or platforms and that the doors are each at least 90 per cent of the width of said stairway and that the windows, doors and frames passed by such stairway and platforms are built of incombustible material and wired glass.

(h) In buildings of Class I not more than three stories in height, a stairway fire escape not less than three feet wide located and built as required by this chapter for such fire escape and placed as far as practicable from the stairway, may be considered as a stairway and may be deducted from the "width of stairs" required for the building.

(i) The width of different stairways need not be alike, and for each four stories or fractional number of stories of the building above the first four stories each stairway may be reduced six inches, but no stair in a Class VII building shall be less than three feet in width.

(j) Stairways which are less than three feet three inches wide shall have not less than one hand rail and stairways which are more than three feet three inches wide shall have not less than two handrails. Stairways which are over eight feet wide shall have double intermediate handrails with end newel posts at least five and one-half feet high at all stair landings.

(k) Stairways hereafter erected shall not be spiral stairways or have any winders. Provided, however, that circular or elliptical stairways may be used if the width of treads one foot from the center of the handrail next to the well-hole is nine and one-half inches, including nosings.

(l) Stairways shall not have risers more than eight inches high nor treads less than ten inches wide, inclusive of nosings.

(m) The bottom of any counter-balance stairway or ladder fire escape hereafter

erected on any public thoroughfare when raised shall be not less than fourteen feet above the pavement or surface of the street or alley.

(n) The location of every stairway required by this article shall be subject to the approval of the Commissioner of Buildings.

(See III and IV, Sec. 238.)

ARTICLE XIX.

Fire Escapes.

Fire Escapes—Number and Location. (a) It shall be unlawful for any person, firm or corporation to construct or maintain any building of Classes I, II, III, VI, and VII within the city, unless the same shall be equipped with fire escapes as follows:

(b) Every building four or more stories in height, except such as is used exclusively for a residence for one family shall have one or more incombustible sliding or stairway fire escapes, as required by this chapter, except as otherwise herein provided.

(c) There shall be at least one stairway fire escape constructed as required by the provisions of this chapter for each 250 persons, or fractional part thereof, who occupy any floor of any building habitually and daily or for whom working, sleeping or living accommodations are provided on any one floor above the third floor of any building or structure.

(d) BUILDINGS OF ORDINARY CONSTRUCTION SHALL BE EQUIPPED WITH FIRE ESCAPES AS FOLLOWS:

With floor area of 6,500 square feet or less, one 24-inch stairway fire escape.

With floor area of 6,500 square feet to 9,000 square feet, two 24-inch stairway fire escapes.

(e) BUILDINGS OF MILL OR SLOW-BURNING CONSTRUCTION SHALL BE EQUIPPED WITH FIRE ESCAPES AS FOLLOWS:

With floor area of 8,000 square feet or less, one 24-inch stairway fire escape.

With floor area of 8,000 square feet to 12,000 square feet, two 24-inch stairway fire escapes.

(f) BUILDINGS OF FIREPROOF CONSTRUCTION SHALL BE EQUIPPED WITH FIRE ESCAPES AS FOLLOWS:

With floor area of 10,000 square feet or less, one 24-inch stairway fire escape.

With floor area of 10,000 to 20,000 square feet, two 24-inch stairway fire escapes.

With floor area of more than 20,000 square feet, three 24-inch stairway fire escapes.

(g) FIREPROOF WAREHOUSE BUILDINGS SHALL BE EQUIPPED WITH FIRE ESCAPES AS FOLLOWS:

With floor area of 12,000 square feet or less, one 24-inch stairway fire escape.

With floor area exceeding 12,000 square feet, two 24-inch stairway fire escapes.

(h) A fireproof bridge built as described in Section 652 and connecting each floor of two neighboring buildings occupied by the same person, firm or corporation, shall be considered the equivalent of a fire escape, or of an interior stairway, but not the equivalent of both.

(i) In buildings of Class II there shall be a stairway or a fire escape as near as practicable to the end of each corridor, and where a corridor is endless the stairs and the fire escapes shall be located around and connected to said hall, or corridor at distances approximately equal to each other.

(j) The openings leading to fire escapes on hospitals shall be flush with the floor leading to the fire escape which may be

inclined not more than 2½ inches vertical to 12 inches of horizontal measurement, and shall be constructed and maintained with no obstructions thereon.

(k) In buildings hereafter erected wherever stairway fire escapes are considered the equivalent of an interior stairway or as taking the place of any of the "Width of Stairs" required by this chapter, there shall be a door or casement window leading to such fire escape from each floor. Windows and doors to such fire escapes shall not be less than 24 inches in width and not less than 72 inches in height. The sill of such windows or doors shall not be more than 24 inches above the floor, unless a stair is built leading to the same.

(l) Where a building is divided into separate areas, each such area shall be considered as a separate building and shall be equipped with stairs and fire escapes as is required for buildings by this chapter, unless otherwise herein provided.

(m) Exterior stairway fire escapes built as required by this chapter and having treads not less than 10 inches wide from nosing to riser and risers not more than 8 inches in height and having stairways extending from the inside grade to the top floor of the building or having a counter-balance section from the first story to the ground and a steel ladder from the top landing to the roof, shall be considered the equivalent of one interior stairway and one stairway fire escape, if the width of such stairway fire escapes with that of one or more stairways in the building equals the "Width of Stairs" required for the area of the respective buildings by this chapter.

(n) Where a Fire Shield Stairway is constructed according to the following provisions and requirements, such Fire Shield Stairway shall be considered the equivalent of a stairway or stairways or a fire escape and stairway or stairways combined, as per the provisions of Paragraph "f" of this section.

The Fire Shield Stairway shall be divided or separated from the building by, and completely enclosed with, brick walls or walls of fireproof material not less than twelve inches thick, or by a wall of reinforced concrete and tile in combination not less than ten inches thick subject to the approval of the Commissioner of Buildings. The walls of said Fire Shield Stairway are to be built from the lowest floor level to and at least thirty-six inches above the roof, except as otherwise herein provided. The roof of said Fire Shield Stairway shall be built of fireproof construction. The stairs of said Fire Shield Stairway shall be of fireproof construction, and all door openings must be provided with fireproof thresholds, metal frames and approved incombustible doors. The risers of all stairs shall be not more than eight inches and the tread not less than nine inches, and winders in stairs shall not be permitted. The nearest riser of the stair in a downward direction must be remote from the entrance to the Fire Shield Stairway a distance not less than the width of the stairs. The entrance to the Fire Shield Stairway shall be by a fireproof vestibule or by an outside balcony. Said balcony shall be constructed on private property and shall not encroach on or overhang a public street or alley. Said vestibule or balcony shall be not less than five feet wide and the floors, ceiling and sides thereof shall be of fireproof material. One side of said Fire Shield Stairway shall face a street or alley or an open space leading directly to and connecting with a public street or alley. The side of said vestibule facing the street, alley or other open space, shall be open for the full width thereof from a point four feet above the floor to the underside of ceiling in each story.

The open space above said wall may be enclosed by a fire shield in the following manner only:

A metal frame constructed of steel of commercial shape, or a sheet metal frame filled with concrete, with a horizontal cross piece midway between the top and bottom of said frame, may be fitted in the opening flush with the inside face of the wall. This frame may be hung with two sashes, sash to be of metal and glazed with fire-resisting glass, hinged at the bottom and arranged to open out from the top, and restrained by angle iron or chain attached to the inner part of jambs of the opening, so as to allow sash to rest on same in an open position, in such a manner that the top edge of sash will be flush with the outer face of the wall. The mason work at the head of the wall opening shall be beveled off at an angle of forty-five degrees. The opening and closing of these sashes are to be controlled by a mechanical device to be approved by the Commissioner of Buildings.

Where sash exceed five feet in width, intermediate piers of masonry sixteen inches wide by the breadth of wall in thickness may be built, and the resulting openings shall be each treated as hereinbefore stated.

All metal sash and fire-resisting glass installed shall be subject to specifications and requirements elsewhere contained in this ordinance.

The entrance from the building into the Fire Shield Stairway shall be through the vestibule or by means of the balcony only. All openings from the building to the balcony or vestibule and from the balcony or vestibule to the Fire Shield Stairway shall be not less than six feet nor more than seven feet in height and not less than four feet in width, and shall be provided with approved incombustible doors hung in metal frames and may be glazed with fire-resisting glass. In all cases, the floor of the vestibule or balcony, or floor landing of stairs, and the floor of the building containing Fire Shield Stairway shall be at the same level.

Where balconies are used as a means of access from the building to the Fire Shield Stairway, the floors of same shall be solid and built of fireproof material, and shall be of sufficient strength to sustain a load of one hundred pounds per square foot within the safe limits of stress for materials, as elsewhere specified in this chapter. Said balcony on each story shall be provided on the open side with an incombustible enclosure four feet high. There shall be a sufficient number of windows in the wall between the vestibule and stairway, or the doors to stairway shall be fitted with fire-resisting glass of sufficient area to properly light the said Fire Shield Stairway. All said window openings to be equipped with metal frames and sash and fire-resisting glass. The entire stairway, vestibule and balconies on all floors shall be provided with adequate means of illumination by gas or electricity on a separate circuit, and shall be lighted during all the time any part of the building in which they are located is being used after sunset or whenever lighting shall be required. The Fire Shield Stairway shall terminate at a landing on a level with, or not to exceed six inches above the street, alley or other open space on which said Fire Shield Stairway faces; and access from said landing to said street, alley or other open space, shall be direct by means of an incombustible door or doors equipped with a metal frame and fire-resisting glass, not less than six feet nor more than seven feet in height, and not less than four feet in width. Connection to said Fire Shield Stairway from first floor will not be required if first floor has sufficient exits properly located. All doors to Fire Shield Stairway shall be of the style known as "double acting doors." In buildings other than skeleton construction a slip joint must be pro-

vided in the masonry walls between the tower and any wall connecting or abutting thereto, subject to the approval of the Commissioner of Buildings.

Plans in detail, showing the construction and equipment and all other features of a Fire Shield Stairway shall be submitted in addition to the general plan showing the proposed location of same. Such details shall be drawn to an enlarged scale, and shall consist of a typical floor plan, a typical elevation and cross section of one or more stories and other stories which deviate from typical plan, and shall be approved by the Commissioner of Buildings before a permit for construction of same is issued.

(o) In buildings not more than two stories in height one stairway may be omitted if the building is equipped with a three-foot stairway fire escape built as required for fire escapes in this section with counter-balance drop and placed as far as practicable from the remaining stairway.

(p) Where fireproof buildings have a frontage upon public alleys or have courts of an area of not less than 320 square feet, and where such courts lead directly to a public thoroughfare, fire escapes may be permitted to be erected on such courts or such alleys and shall not be required to be erected upon the street fronts of such buildings. Such fire escapes shall be located as far as possible from stairways in the buildings, and where it is possible to erect the fire escapes on an alley or in a court they may be thus erected subject to the approval of the Commissioner of Buildings.

(q) In fireproof buildings of Class IIa, fire escapes may be located in light courts of fifty feet in the least dimension, having no opening onto a street or alley, but such fire escape must be connected with a stairway of the building at a level no higher than twenty-five feet above finished grade at the building, said stairway to terminate at the first floor level in a public corridor, giving direct egress from the building.

(r) Such fire escapes shall not be considered as part of the width of stairs as defined in Section 650 of this chapter for such buildings unless that portion of the stairway used in connection with the fire escape is increased by the width of the fire escape, from their junction to the ground.

Hospitals two or more stories in height shall be provided with one or more stairway fire escapes not less than 40 inches between handrails. Sliding fire escapes shall have a radius or width of not less than 42 inches. Sliding fire escapes shall not be built on public thoroughfares and shall deposit the person from same not more than twenty-four inches from the surrounding ground, and sliding fire escapes on Class VIII buildings shall be constructed, located and maintained in accordance with the provisions relating to Class VIII.

Wherever stairway fire escapes are considered by this chapter to be the equivalent of an interior stairway or as taking the place of any of the width of stairs, there shall be a door leading to said fire escape from each floor. Such door shall not be less than 24 inches in width and not less than 72 inches in height. The sill of such door shall not be more than 24 inches above the floor and the door shall be as wide as the stairway required on the fire escape. Where the sill is more than 24 inches from the floor, a small stairway shall be built from the floor to the window sill with treads not less than 10 inches wide and risers not more than 9 inches in height.

(s) A stairway fire escape placed on an exterior wall adjacent to a dividing or party wall shall be considered as a stairway fire escape for each building area to which it

is adjacent. In such cases there shall be at least one door or window from each building area leading to the fire escape platform, and the width of each such fire escape shall not be less than 36 inches.

(t) All fire escapes shall be located and constructed to conform to the building for which they are respectively intended.

(u) If any building used wholly or in part for the purposes of Class VII be equipped with automatic sprinklers, and be connected with another building similarly used, and distant not less than twenty-five feet and used by the same occupant, by a fireproof bridge or passageway similarly equipped, then each such tier of bridges or passageways shall be held to be equivalent to and take the place of one outside stairway fire escape on each of the buildings so connected.

(See Special Ruling VI, Page 301.)

654. Stairway Fire Escapes—Fees—Erection of—Location—Painting—Component Parts. (a) The Commissioner of Buildings and his assistants shall determine upon the location of all stairway fire escapes before erection of same is commenced.

(b) Before the work is commenced a permit shall be obtained from the Commissioner of Buildings for which a fee of \$2.00 shall be exacted.

(c) No permit for a stairway fire escape more than twenty-four inches in width shall be granted unless a detailed plan for the fire escape, approved by a licensed architect or a structural engineer, is submitted to the Commissioner of Buildings, and a copy of such plans shall be left on file with said Commissioner.

(d) All anchors for stairway fire escapes shall, wherever possible, pass through the wall of building and be secured on inside of same. Where it is possible to anchor through walls, anchors shall be put in wall not less than fifteen inches at an angle of thirty-five degrees. On buildings of steel construction, where walls are less than twenty inches in thickness there shall be steel channels at least four inches wide set on inside of building from column to column and bolted or riveted to columns, and anchors shall be bolted on inside of channels.

(e) Anchors for a platform four feet two inches or less in width shall be made of one inch square iron; over four feet two inches and not over six feet, shall be one and one-fourth inch square iron with brace; over six feet shall be one and one-half inch square iron with brace. All anchors shall be turned up not less than eight inches at the outside of the platform on which to bolt the post.

(f) Braces shall be the same thickness as the anchors. The spread of the braces shall be the width of the platform. Where the platforms are over five feet in width, anchors shall have double braces, one to the outside and one to the center of the platform.

(g) Platforms shall be not less than fifty inches wide at ends; passageways shall be not less than twenty-four inches between buildings and railings. Platforms shall be not less than five feet in length. The frames and crossbars shall be made as provided in this chapter. Platforms shall have clips at each end bolted to anchors. No door or window or shutter shall open so as to obstruct in any way the free passage on or along a platform or a stairway fire escape.

(h) All stairway fire escapes for apartment buildings, hotels, boarding houses, factories and office buildings, where there are less than 100 people on any one floor, shall be not less than two feet wide between hand

rails. Stringers for a 24-inch stairway fire escape shall be not less than 2 inches by $\frac{3}{4}$ inch set $1\frac{1}{2}$ inches apart. Where stairway fire escapes and their balconies and supports are designed and constructed in accordance with the provisions of this chapter relating to materials permitted for such stairway fire escapes, balconies and supports, so as to sustain a load of 100 pounds per square foot, they may be built of steel channels, angles, or I-beams, but when so constructed, they shall comply with the provisions of this chapter in all other respects. All stairway fire escapes for halls, churches, theaters, hospitals, schools, department stores and buildings where large numbers of people congregate shall not be less than three feet wide in the clear, and all passageways shall not be less than three feet wide in the clear. Stringers for a 36-inch stairway fire escape shall be made of two bars, 3 inches by $\frac{1}{2}$ inch, about one inch apart, or $4\frac{1}{2}$ inches by $\frac{3}{4}$ inch flat iron, or of steel channels, angles or I-beams; where over 12 feet in length, they shall have anchor and brace in the center. The tread shall be made of one-half inch square steel or iron, corner upwards, not to exceed $1\frac{1}{2}$ inches center, riveted at ends to 2 by $\frac{1}{2}$ inch flat iron or steel. There shall be not less than four bars to a tread where treads are less than twenty-seven inches in length; where treads are over twenty-seven inches in length there shall be not less than six bars to a tread; there shall be a truss supporting treads made of bar iron 2 inches by $\frac{3}{8}$ of an inch in thickness riveted to bars of treads in center, supported by not less than two inches by seven-sixteenths of an inch rods bolted at each end of treads. All stairs shall have an incline of about forty-five degrees. The rise shall be not more than nine inches and the tread not less than nine inches.

(i) All stairs shall have three bar railings made of one-inch bar iron for top rail, and three-fourths inch bar iron for lower rail, and when such stairs are more than three inches from the wall of the building, there shall be one or more hand rails on the wall side of such stairs.

(j) All posts used for stair fire escapes shall be made of one and one-half inch angle or channel iron not less than three feet six inches high, measured at right angles with the treads of such fire escapes, and shall have braces on the outside turned upwards and fastened to the frame of the balcony or stairs, which shall be not less than half way up the posts; all stair fire escapes shall extend to the ground either by counterbalance drop or stairs. All ladder fire escapes shall have either extension ladder or counterbalance drop from the first story of said building to the ground or sidewalk. All fire escapes if not continued to the roof shall be equipped with a ladder built in conformity with the specifications for ladder fire escapes contained herein from top story or attic platform to the roof. Their location, material and construction shall be subject to the approval of the Commissioner of Buildings. When cables are used for counterbalance stairs they shall not be less than three-quarters of an inch in size and shall be well oiled or greased when hung up and shall be oiled or greased at least twice a year. All pulleys and cables holding counterbalance drop shall be covered at bracket so as to be protected from snow or ice.

(k) Wherever a stairway fire escape passes a window or door on buildings hereafter erected, the windows or doors shall be of wired glass and shall have metal frames and sash, and whenever such a fire escape passes above a window, door or other opening not fitted with wired glass and metal frames the said fire escape shall be protected on the under side by sheet metal of not less than No. 20 United States gauge

opposite such opening and for a distance of three feet on each side thereof. The use of intermediate platforms shall be permitted on all buildings now built or hereafter constructed whenever it is possible by their use to avoid the necessity of stairway fire escapes passing windows. All fire escapes shall be painted with two coats of mineral paint when erected, one at the shop and one upon completion at the building, and they shall be painted at least once every year thereafter.

(l) Wherever it is impossible to erect stairway fire escapes according to the provisions of this chapter, plans shall be submitted to the Commissioner of Buildings showing the location, material and construction of such stairway fire escapes as are proposed to be built before a permit is issued for the same, and if it is found to be impracticable to locate and construct fire escapes in accordance with the provisions of this chapter and that fire escapes built according to the plan presented would afford safe and practical means of exit from the building on which they are to be placed, then the Commissioner of Buildings may in his discretion approve the same. All such fire escapes shall be inspected by the Commissioner of Buildings on their completion and if found to be safe, satisfactory and in compliance with said approved plans, a certificate shall be issued to such effect upon the payment of \$2.00 to the City Collector. All fire escapes other than such as it is impossible or impracticable to build in accordance with the provisions of this chapter shall be inspected by the Commissioner of Buildings on their completion, and if found to be in compliance with the provisions of this chapter a certificate shall be issued by the Commissioner of Buildings upon the payment of a fee of \$2.00 to the City Collector.

(m) It shall be unlawful for any person, firm or corporation to use any building until the provisions of this article shall have been complied with.

655. Ladder Fire Escapes—When Permitted.) Where a building of Class III or VI, not more than four stories in height has two flights of stairs leading from the ground to the top floor of the building and where also each occupant shall have access to at least two separate and distinct stairways located as required by the provision of this chapter from the top floor to the ground, a ladder fire escape may be used in lieu of the stairway fire escape required herein, where a counter balance drop is placed from the ladder fire escape to the ground.

656. Specifications for Ladder Fire Escapes.) (a) All single and double ladder fire escapes hereafter erected shall be in strict accordance with the following provisions:

(b) There shall be not less than three one-inch square wrought iron anchors to every five-foot balcony and not less than six for a twelve-foot balcony. Such anchors shall pass through the wall of the building and be bolted on the inside with a three-fourths by two-inch nut and three and one-half inch iron washer back of the nut, where the wall is not over twenty inches thick; but where the wall is over twenty inches thick anchors shall be inserted at least eight inches into the wall at an angle of thirty-five degrees.

(c) Where a ladder fire escape is permitted by this chapter, the side guards shall be two by three-eighths inch flat iron. All ladder fire escapes shall be seventeen inches or more in width in the clear. No pipe nor rusted or defective material shall be used in the construction of ladder fire escapes. Rungs of ladders shall be of not less than

one-half inch square iron with corners upward, so as to give a safe footing. Rungs shall be riveted and shall be constructed with fourteen-inch centers.

(d) The brace for the anchors shall be at least twenty inches spread and shall extend into the wall four inches; no other form of anchor shall be allowed except by special permit from the Commissioner of Buildings.

657. Balconies—Construction of.) All balconies hereafter erected shall be either steel or wrought iron and capable of sustaining a weight of one hundred pounds to the square foot. The balcony frame shall be made of not less than two-inch by two-inch by one-fourth inch angle iron which shall be securely riveted together with cross-bars every two feet. Such bars shall be punched one-half inch square close to the top of the bar on two inch centers and one-half inch square iron bars shall be forced through the same. The crossbars shall be securely riveted to the angle iron frame. The crossbars for a balcony twenty-eight inches wide shall be two inch by three-eighths inch. Balcony frames over twenty-eight inches wide shall be made of not less than two by three-eighths inch iron and made to conform with the increased dimensions of iron in crossbars; for thirty-six inch balcony or more they shall be two and one-half inch by three-eighths inch. All balconies over this width shall have a two-inch "T" iron through the center of the balcony for the bars to rest upon; provided that such balconies and platforms of buildings of Class IIc may be built as described in Section 270 of this chapter. Such balconies shall have a substantial cast or wrought iron post every three feet bolted to the balcony. No balcony shall have less than three guard rails which shall be of wrought iron or new iron pipe not less than three-fourths inch in diameter and the ends shall be securely anchored to the wall of the building and shall be not less than ten inches on an angle of thirty-five degrees. Where stairway fire escapes and their balconies are designed and constructed in accordance with the provisions of this chapter to sustain a load of one hundred pounds per square foot, they may be built of steel channel angles or I-beams, but in such cases they shall comply with the requirements of this chapter in all other respects.

658. Stairs and Fire Escapes—Change in Construction.) No change in the position or construction of any stairway or of any fire escape shall be made, unless the permission of the Commissioner of Buildings shall first have been obtained.

ARTICLE XX.

Ventilation.

659. Ventilation in Buildings of Classes IV, V, VII and VIII—Charges for Approval of Mechanical Ventilation Plans.) (a) The air in any room used as an auditorium in buildings of Class IV and V, hereafter erected and the air in any room used as a classroom or assembly hall in buildings of Class VIII, hereafter erected, shall be changed, so as to provide each person for whom seating accommodation is provided in such auditorium, classroom or assembly hall with at least 1,500 cubic feet of air per hour.

(b) In buildings of Class VII, hereafter erected, on floors frequented by the public the air in such rooms shall be supplied at the following rates:

For each person in basement, 2,000 cubic feet per hour.

For each person in 1st to 3rd stories, both inclusive, 1,500 cubic feet per hour.

For each person in 4th story and above, except as hereinafter provided, 1,300 cubic feet per hour.

For each person in grocery departments and restaurants, 1,500 cubic feet per hour.

(c) For the purpose of determining the number of people on any floor in buildings of Class VII, in calculating the means of ventilation, the following floor area per person per floor shall be taken as the basis:

Basement, per person, 20 square feet of floor area exclusive of walls, stairs and elevators.

First story, per person, 20 square feet of floor area, exclusive of walls, stairs, elevators, and enclosed show windows.

Second story, per person, 50 square feet of floor area, exclusive of walls, stairs, elevators, and enclosed show windows.

Third story, per person, 60 square feet of floor area, exclusive of walls, stairs and elevators.

Fourth story and above, per person, 80 square feet of floor area, exclusive of walls, stairs and elevators, except as hereinafter provided.

(d) Grocery departments and restaurants, per person, 40 square feet of floor area, exclusive of walls, stairs and elevators.

(e) The amount of carbon dioxide in the air of any such auditorium, classroom or assembly hall or space frequented by the public in Class VII buildings shall not be permitted to rise above 10 parts of carbon dioxide per 10,000 parts of the air, measurements being taken at levels from two and one-half feet to eight feet above the floor, generally distributed, and the temperature in such spaces when artificially heated shall not exceed 68 degrees Fahrenheit. Relative humidity shall not be less than 45 degrees nor more than 80 degrees.

(f) The air in any room used as an auditorium in buildings of Classes IV and V, constructed prior to the passage of this ordinance, and the air in any room used as a classroom, or assembly hall in buildings of Class VIII, constructed prior to the passage of this ordinance, shall be changed, so as to provide each person for whom seating accommodation is provided in such auditorium, classroom or assembly hall with at least 1,200 cubic feet of air per hour.

(g) The air in any rooms and floors in buildings of Class VII, erected prior to the passage of this ordinance, shall be supplied, by mechanical or other means, at the following rates:

For each person in basement, 1,600 cubic feet per hour.

For each person in 1st to 3rd stories, both inclusive, 1,200 cubic feet per hour.

For each person in 4th story and above, except as hereinafter provided, 1,040 cubic feet per hour.

For each person in grocery departments and restaurants, 1,200 cubic feet per hour.

(h) For the purpose of determining the number of people on any floor in buildings of Class VII, in calculating the means of ventilation, the following floor area per person per floor shall be taken as the basis:

Basement, per person, 20 square feet of floor area exclusive of walls, stairs and elevators.

First story, per person, 20 square feet of floor area exclusive of walls, stairs, elevators and enclosed show windows.

Second story, per person, 50 square feet of floor area exclusive of walls, stairs, elevators and enclosed show windows.

Third story, per person, 60 square feet of floor area exclusive of walls, stairs and elevators.

Fourth story and above, per person, 80 square feet of floor area exclusive of walls, stairs and elevators, except as hereinafter provided.

Grocery departments and restaurants, per person, 40 square feet of floor area exclusive of walls, stairs and elevators.

(i) The amount of carbon dioxide in the air of any such auditorium, classroom or assembly hall or space frequented by the public in Class VII buildings shall not be permitted to rise above 12 parts of carbon dioxide per 10,000 parts of air, measurements being taken at levels from two and one-half feet to eight feet above the floor generally distributed; and the temperature in such spaces when artificially heated shall not exceed 70 degrees Fahrenheit. The relative humidity shall not be less than 40 degrees nor more than 85 degrees.

(j) The word "auditorium" as used in this section in connection with buildings of Classes IV and V shall be construed as including the main floor, balcony and galleries.

(k) In buildings hereafter erected for or converted to the use of a factory, mill or workshop, the air shall be changed, except as hereinafter provided, so as to provide each person for whom working accommodations are provided therein with at least 1,500 cubic feet of air per hour.

(l) In buildings used for the purposes of a factory, mill or workshop at the time of the passage of this ordinance, the air shall be changed, except as hereinafter provided, so as to provide each person for whom working accommodations are provided therein with at least 1,200 cubic feet of air per hour.

(m) In any building or room hereafter erected for or converted to the use of a factory, mill or workshop the amount of carbon dioxide in the air, except as hereinafter provided, shall not be permitted to rise above ten parts of carbon dioxide per 10,000 parts of air.

(n) In buildings or rooms used for the purpose of a factory, mill or workshop at the time of the passage of this ordinance, the amount of carbon dioxide in the air, except as hereinafter provided, shall not be permitted to rise above twelve parts of carbon dioxide per 10,000 parts of air. The measurements in each case above enumerated in this paragraph shall be taken at levels from two and one-half feet to eight feet above the floor, distributed generally; and the temperature in such spaces, when artificially heated, shall not exceed 68 degrees Fahrenheit, except as hereinafter provided; the relative humidity shall not be less than 40 degrees nor more than 85 degrees.

(o) The above provisions and standards as to ventilation shall not apply to storage rooms or vaults or any place where the manufacturing processes therein conducted would be materially interfered with, or where manufacturing processes therein conducted would produce considerable quantities of free carbon dioxide, except that the air in such rooms or vaults or in any places of manufacture shall not be permitted to become detrimental to the health of those who enter or work therein.

(p) No part of the fresh air supplied in compliance with the requirements of this section shall be taken from any cellar or basement.

(q) No person, firm or corporation, either as owner, proprietor, lessee, manager or superintendent of any factory, mill, workshop or any other building where one or more persons are employed, shall cause, permit or allow the same or any portion or apartment of any room in such factory, mill or workshop, to be overcrowded or to have

inadequate, faulty or insufficient light or ventilation.

(r) No person shall be exposed to any direct draft from any air inlet, nor to any draft having a temperature of less than sixty degrees.

(s) All poisonous or noxious fumes or gases arising from any process, and all dust of a character injurious to the health of the persons employed, which is created in the course of a manufacturing process, within such factory, mill, workshop or laundry, shall be removed, as far as practicable, by either ventilating or exhaust devices.

(t) The commissioner of health is hereby authorized and directed to make the following charges for the approval of plans for mechanical ventilation equipment and for the inspection and testing of the same:

Five dollars (\$5.00) for an equipment handling 5,000 cubic feet of air per minute, or less, and one dollar (\$1.00) for each additional capacity of 1,000 cubic feet per minute.

The owner or contractor shall be granted a certificate of inspection when the final inspection and test is made and the fee paid.

No fee for minor alterations shall be charged unless the alterations include changes in the method of ventilating or in the total capacity of the equipment, in which case the charge will be one dollar (\$1.00) for every 1,000 cubic feet of air, per minute, additional capacity.

An annual inspection of all mechanical ventilation equipment in public and semi-public buildings and places of employment shall be made by the Commissioner of Health to see that the same is in proper operating condition. The fee for the annual inspection shall be fifty cents (50c) per 1,000 cubic feet, or fraction thereof, of air handled per minute. Such annual inspection fee shall be paid in advance to the City Collector on the first day of March of each year.

ARTICLE XXI.

Elevators and Their Enclosing Walls.

660. Elevator—Passenger and Freight—Permit for Construction—Fee—Penalty.)

(a) Before proceeding with the construction or alteration of any passenger or freight elevator, except such as are hereinafter specially exempted from the provisions of this chapter, a permit for such construction or alteration shall be obtained from the Commissioner of Buildings either by the owner or agent of the building in which such elevator is to be constructed or in which such alterations are to be made, or by the contractor who is about to construct or alter such elevator.

(b) It shall be unlawful for any such owner, agent, or contractor to permit or allow the construction of any such elevator or the making of such alterations, or to proceed with or in or about any of the work of construction or alteration of any such elevator until such permit shall first have been obtained. Such permit shall be issued by the Commissioner of Buildings after application shall have been made to him therefor by any such owner, agent or contractor, specifying the number and kind of elevators which it is desired to construct, or the nature of the alterations to be made and the location of the building or structure in which the same is or are to be placed or made. Such application shall be accompanied with such plans and specifications as shall be necessary to advise and inform said Commissioner of the plan of construction, type of elevator, kind of alterations and the location thereof. If such plans and specifications shall show that such elevator or elevators is or are to be constructed or erected or altered in conformity with the

provisions of this chapter, the Commissioner shall approve the same and shall issue a permit to such applicant upon the payment of such applicant of a fee of two dollars for each elevator to be constructed, erected or altered, and such fee shall be known as a permit fee and shall not be held to cover the cost of any inspection which shall at any time thereafter be made of such elevator or elevators when constructed, or of any alterations made.

(c) All contractors or persons, firms, or corporations, engaged in the manufacture and work of installing iron doors on passenger or freight elevators, or of installing wire work enclosures around elevators, shall secure a permit from the Commissioner of Buildings for the work on each such elevator, the fee for which shall be two dollars for each elevator in buildings of four stories or less in height, and for more than four stories in height fifty cents additional shall be charged on each elevator for every additional floor in excess of four stories in height.

(d) It shall be unlawful for any person, firm or corporation either as owner, lessee, contractor or agent of any building or structure in which any elevator or elevators are to be constructed or altered to proceed with said work without securing a permit as herein required for such construction or alteration, and no such permit shall be issued until such person, firm or corporation, lessee, contractor or agent shall have complied with all the requirements of this chapter.

661. **Enclosure of Elevator Shafts in Non-Fireproof Buildings.)** In all non-fireproof buildings hereafter erected all passenger elevators and all freight elevators, except such as are expressly excepted by this chapter, shall be inclosed in a wall of brick, tile or such incombustible material as may, from time to time, be approved by the Commissioner of Buildings as proper and suitable for the purpose; such inclosure shall extend from the foundation to the roof of such building, and shall be supported independently of the floor construction; provided, further, however, that the provisions of this section shall not apply to any non-fireproof building which is equipped throughout on every floor and in every room thereof and in all stairways, platforms, elevator shafts, elevator hoistways and well holes with an automatic sprinkler system approved by the Fire Marshal.

662. **Enclosure of Pits and Shafts in Basements.)** In all buildings heretofore or hereafter erected, whenever any elevator shaft extends down into a basement or sub-basement, that portion thereof extending below the street level shall be inclosed in walls of brick, tile or other fireproof material, and the door openings in such inclosure shall be protected by incombustible doors. Where such elevator shafts do not extend down into the basement they shall be provided with fireproof pits at the lowermost floor level above which they serve, and such pits shall have no openings except for cables or other elevator equipment.

663. **Enclosure of Dumb Waiter Shafts—Materials.)** In all non-fireproof buildings hereafter erected, the dumb waiter shafts shall be inclosed with brick, tile, reinforced concrete, or cement plaster not less than two inches thick or metal studs and lath.

664. **Doors—On Elevators.)** In all elevator shafts which are herein required to be enclosed with fireproof walls, the door openings shall be equipped with doors of incombustible material, which shall be made to open from the outside by means of a key or other device satisfactory to the Commissioner of Buildings.

665. **Hatch Doors—Freight Elevators.)** Elevators, used exclusively as freight ele-

vators constructed and in operation at the time of the passage of this ordinance need not have enclosing walls, but in all such cases there shall be at every floor through which such freight elevators pass automatic hatch closers or automatic doors, made in such manner that they will fully close each well hole when the temperature in such well hole exceeds 140 degrees Fahrenheit; and it shall be the duty of the owner, agent or person in possession, charge or control of a building in which such elevator is maintained to keep such hatch closers or doors at all times in good working order. Such automatic hatch closers shall be examined by the Commissioner of Buildings and the Fire Marshal and if said officials shall find that such doors will automatically close when the temperature at or near such doors exceeds 140 degrees Fahrenheit, and that the conditions of construction and operation of such doors or hatch closers are such that there is no reasonable probability of their getting out of order and failing to operate when required, and that in their construction or operation there is nothing that is likely to cause accidents to or interference with the elevator service in such hatch holes which they were intended to close, and that the building in which such freight elevator is in use is equipped with stairways, fire escapes and passenger elevators sufficient to offer ample means of escape from such building in case of fire, for all persons employed or for all persons in such building, then, and in such case only, shall the use of such hatch doors or closers be permitted. All freight elevators in non-fireproof buildings shall comply with the preceding requirements of this section, or shall have inclosing walls of incombustible or fireproof construction. Such elevators are to be inspected semi-annually and oftener when, in the opinion of the Commissioner of Buildings, such inspection is necessary and such fees shall be paid for said inspection as otherwise provided in said chapter.

666. Safety Device.) (a) Every passenger and freight elevator now in operation or hereafter installed, except such as are hereinafter exempted from the provisions of this chapter, shall be provided with a speed governor and such other efficient device to secure the safe operation of such passenger or freight elevator, and to prevent the cab or car of such elevator from falling, and to secure the safety of the cab or car and its load in case it does fail, as may be required by the Commissioner of Buildings. Such speed governor and other devices shall be subjected to such a practical test as may be determined by the Commissioner of Buildings for the purpose of ascertaining the efficiency of such safety device.

(b) It shall be the duty of the Commissioner of Buildings to make such test of each and every device upon all elevators, and no elevator shall be permitted to be run until such test has been made.

(c) That whenever any accident shall occur causing injury to any person affecting life or limb, in or about an elevator, or while getting on or off an elevator, or in any way impairing the safety of the elevator, the same shall be reported at once by the owner, superintendent, lessee or manager of the building, or the operator of the elevator, to the Commissioner of Buildings. No broken or damaged part of such elevator shall be moved or displaced, or repairs made thereon, nor shall said elevator be operated until an investigation into such accident has been made by the Commissioner of Buildings or his duly authorized agent. A full report in writing of the result of each investigation shall be filed in the Department of Buildings, and the Commissioner of Buildings shall keep a complete

record of all such accidents and reports thereon.

(d) It shall be unlawful for any operator of any elevator in the City of Chicago wherein passengers are conveyed to start such elevator until all doors of such elevator and leading into such elevator shall be closed. It shall be unlawful for any such operator to open the doors of such elevator until said elevator has come to a full stop.

(e) Any person violating any of the provisions of this section shall be fined not less than twenty-five dollars nor more than two hundred dollars for each offense.

667. Safeguards for Elevators.) (a) Where the counterweights travel in the same hatchway with an elevator car, the portion of the car contiguous to the weights shall be protected from the top to the bottom of the car by a suitable guard.

(b) All freight elevators shall be provided with a guard at least six feet high. All elevator cabs or cars, whether used for freight or passengers, shall be provided with some device whereby the car or cab may be held in the event of accident to the shipper rope or hoisting machinery or controlling apparatus.

(c) No passenger elevator hereafter erected shall be installed with a freight compartment either below or above the car.

(d) All hoistways, hatchways, elevator wells and wheel holes in any building, whether occupied or vacant, shall be securely fenced, inclosed or otherwise safely protected, and it shall be the duty of the owner, occupant or agent of any such building to keep all such means of protection closed at all times, except when it is necessary to have the same open, in order that the said hatchways, elevators or hoisting apparatus may be used.

(e) It shall be unlawful to erect or maintain an elevator where such elevator or its counterweight descends into any passageway or thoroughfare.

(f) There shall be directly under the sheaves at the top of every elevator hatchway, a grating of steel or heavy wire mesh properly supported by steel or iron and capable of sustaining a load of not less than 500 pounds.

(g) All counterweights hereafter installed shall have their component parts so fastened together as to prevent any piece or pieces from becoming detached from the guides should the counterweights be accidentally drawn to the top of the hatchway.

(h) Where drum counterweight cables run through or pass by the car counterweights to weights underneath, they shall be provided with a suitable covering to prevent their chafing and wearing on the counterweights.

(i) Where elevators other than hand-boosts and sidewalk elevators are not inclosed with fireproof or incombustible material, as is elsewhere herein specified in this Article, the well-hole of such elevator shall be enclosed with a wire guard not less than six feet high. The counterweights and the immediate space through which they travel must be protected from the floor to the ceiling with a wire guard or with other incombustible material. There must be on all elevators hereafter constructed a clear space of not less than two feet between the bottom of the hatchway and the level of the lower floor landing when the car is at its lowest position, and there must be a clearance of at least four feet from the top of the crossbeam of the car to the lower side of the grating under the overhead sheaves. Whenever there is conflict in regard to the manner of enclosing any elevator shaft or portion thereof between this section and Sections 661, 662 and 663, the provisions of the latter sections shall prevail.

(j) All passenger and freight elevators hereafter installed, except sidewalk or hand elevators, shall have an artificial traveling gas or electric light attached to the car and maintained in good working condition.

(k) All power driven elevators hereafter constructed or installed shall have at least two hoisting cables for the cage and two cables for each counterweight. The lifting and counterweight cables shall have at least one full turn of the cable on the drum when the car has run its limit.

(l) It shall be unlawful to change a hand-hoist to a power-driven elevator without first making application to the Commissioner of Buildings for a permit for such change, and it shall be unlawful to connect an electric motor or any other appliance to the hand elevator machinery without the approval of the Commissioner of Buildings.

(m) All elevators, except hand elevators operated by a pulley rope and sidewalk ram or chain hoist elevators, and elevators used in tunnels for freight service only, shall be equipped with a safety speed governor.

(n) Where ropes or cables are used to operate safety devices, a weight shall be properly attached to the same in such a manner as to insure the necessary tension on such rope or cables for proper performance of the safety devices.

(o) All elevators propelled by electricity shall be provided with an additional device not operated by a link belt or sprocket chain which will automatically stop the elevator machinery when the car has reached its limit of travel. It shall be unlawful to construct or maintain any elevator equipped with a sprocket chain or link belt device or devices connecting the operating device and controller.

(p) An emergency switch which will disconnect the current shall be provided in all passenger elevators hereafter installed which are operated by an electric controller switch, and such cars shall be so constructed that they will automatically stop when the current is disconnected.

(q) The underside of the floors or other parts of a building which project into passenger elevator shafts shall be equipped with a smooth steel guard curved and sloped from the enclosure of said elevator to the edge of such projection for the width of the door to such elevator car and the slope of the guard plate shall not be less than sixty degrees with the horizon.

(r) The provisions of this section requiring the equipment of elevators with safety devices shall not apply to any hand hoists, elevator or hoist used solely for hoisting materials or tools in any building in course of construction, but the Commissioner of Buildings shall make such reasonable requirements as he may deem necessary for public safety in the operation of such hand hoists, elevators or hoists used solely for hoisting materials or tools in such buildings while under construction.

668. Inspection—Test—Certificate to Be Posted.) (a) Every elevator now in operation or which may be hereafter installed, together with the hoistway and all equipment thereof, shall be inspected under and by the authority of the Commissioner of Buildings at least once every six months, and in no case shall any new elevator be placed in operation until an inspection of the same has been made.

(b) It shall be the duty of every owner or agent, lessee or occupant of any building wherein any elevator is installed and the person in charge or control of any elevator to permit the making of a test and inspection of such elevator or elevators and all devices used in connection therewith upon demand being made by the Commissioner of Buildings or by a duly authorized Eleva-

tor Inspector within five days after such demand has been made.

(c) Whenever any such elevator has been inspected and the tests herein required shall have been made of all safety devices with which such elevator is required to be equipped and the result of such inspection and tests shows such elevator to be in good condition, satisfactory to the Commissioner of Buildings, and that such safety devices have been provided in accordance with the requirements of this chapter and are in good working condition and in good repair, it shall be the duty of the Commissioner of Buildings to issue or cause to be issued a certificate setting forth the result of such inspection and tests and containing the date of inspection, the weight which the elevator will safely carry and a statement to the effect that the shaft doors, hoistway and all equipment, including safety devices, are constructed in accordance with the provisions of this chapter, upon the payment of the inspection fee required by this chapter.

(d) It shall be the joint duty of the owner, agent, lessee or occupant of the building in which such elevator is located and of each person in charge or control of such elevator to frame the certificate and place same in a conspicuous place in each elevator.

(e) The words "safe condition" in this section shall mean that it is safe for any load up to the amount of weight named in such certificate.

(f) Where the result of such inspection or tests shall show such elevator to be in an unsafe condition or in bad repair, or shall show that the safety devices, or any of them, which are required by this chapter, have not been installed, or if installed, are not in good working order or not in good repair, such certificate shall not be issued until such elevator, its hoistway and its equipment or such device or devices shall have been put in good working order, satisfactory to the Commissioner of Buildings. The inspection fees herein required shall be paid either at the time application is made for inspection or upon the completion of such inspection and tests.

669. Power of Commissioner to Stop Operation of Elevators.) (a) Whenever any building or elevator inspector finds any passenger or freight elevator or any of its running parts or automatic devices or other equipment out of order, or in an unsafe condition, he shall immediately report the same to the Commissioner of Buildings, together with a statement of all the facts relating to the condition of such elevator or elevators.

(b) It shall be the duty of the Commissioner of Buildings upon receiving from any inspector a report of the unsafe condition of any elevator, to order and cause such elevator not to be used until the same shall have been placed in a safe condition, and it shall be unlawful for any owner, agent, lessee, or occupant of any building, wherein any such passenger or freight elevator is located within the city, to permit or allow any such elevator to be used after the receipt of a notice in writing from the Commissioner of Buildings that any such elevator is out of order or is in an unsafe condition and until said elevator has been put in a safe and proper condition as required by the provisions of this chapter.

ARTICLE XXIII.

Billboards, Signboards, Signs, and Fences.

670. Billboards and Signboards on Buildings—Construction—Height.) No billboard or signboard shall be erected or placed upon or above the roof of any building or structure within the limits of the City of Chi-

cago; and it shall be unlawful for any person, firm or corporation to attach any billboard or signboard to the front, sides, or rear walls of any building, unless the same shall be placed flat against the surface of the building and safely and securely anchored or fastened thereto in a manner satisfactory to the Commissioner of Buildings.

671. Size and Construction of Billboards and Signboards Erected Within Fire Limits Otherwise Than on Buildings.) The face of billboards or signboards erected within the fire limits as now defined or as they may hereafter be defined by ordinances of the City of Chicago other than signboards and billboards referred to in Section 673 hereof, shall not exceed twelve feet in height, and the same shall be constructed of galvanized iron or some other equally incombustible material, except that the stringers, uprights and braces thereof may be of wood. All such billboards or signboards shall be securely anchored or fastened so as to be safe and substantial.

672. Height and Distance From the Ground of Billboards and Signboards Erected Within the Fire Limits.) It shall be unlawful for any person, firm or corporation to construct or erect any billboard or signboard, except those specified in Section 673 hereof, within the fire limits of the City of Chicago at a greater height than fifteen feet six inches above the level of the adjoining street. Where the grade of the adjoining street or streets has not been established, no billboard or signboard shall be constructed or erected at a greater height than fifteen feet six inches above the level of the ground upon which such billboard or signboard is erected. The face of every billboard or signboard within the fire limits shall be of incombustible material, but the supports and framework of the same shall be of wood. The base of the billboard or signboard shall, in all cases, be at least three feet six inches above the level of the adjoining street. If, however, the level of the ground where the billboard or signboard is to be erected is above the level of the street, then the bottom of the face of the billboard or signboard must be at least three feet six inches above the level of the ground at the point where the board is to be erected. Every said billboard or signboard must be constructed and located in accordance with the provisions of this Article and shall be subject to the approval of the Commissioner of Buildings.

673. Wooden Billboards or Signboards—Construction—Size—Exceptions.) Billboards or signboards not exceeding twenty-four (24) square feet in area when attached to the front, sides, or rear walls of any building, so that the flat surface of same is against the building, or when erected on the ground, if not erected nearer than ten feet to any building, structure, other signboard or public sidewalk, which are used to advertise the sale or lease of the property upon which they shall be erected, may be built of wood or other combustible material, and such billboards or signboards shall be exempt from the provisions of this article, except that they shall be safely and securely anchored or fastened and shall be so constructed, anchored and fastened that they will withstand the wind pressure specified in Section 678 of this Article. It shall be unlawful to erect any such billboard or signboard exceeding twenty-four (24) square feet in area before a permit therefor has been procured from the Commissioner of Buildings, the application for which must include the plans and specifications of such board and its supports and fastenings.

674. Billboards and Signboards Erected Outside the Fire Limits—Construction—Size.) It shall be unlawful for any person, firm or corporation to construct, erect

or locate any billboard or signboard, except those specified in Section 673 hereof, outside the fire limits of Chicago at a greater height than fifteen feet six inches above the level of the adjoining street. Where the grade of the adjoining street has not been established, no billboard or signboard shall be constructed or erected at a greater height than fifteen feet six inches above the level of the ground upon which such billboard or signboard is erected. The base of the billboard or signboard shall, in all cases, be at least three feet six inches above the level of the adjoining street. If, however, the level of the ground where the billboard is to be erected is above the level of the street, then the bottom of the face of the billboard or signboard must be at least three feet six inches above the level of the ground at the point where the board is to be erected. The braces, supports and face of the billboard or signboard outside the fire limits may be made of wood, unless the billboard or signboard shall be erected or located so that any part of the face of said board is nearer than ten feet to any building or structure in which case the face of the same shall be constructed with incombustible material. Every such billboard or signboard shall be safely and securely constructed, anchored, fastened and located in accordance with the provisions of this article and shall be subject to the approval of the Commissioner of Buildings.

675. Provisions of This Article Shall Apply to Other Similar Structures.) The provisions of this article shall apply to other similar structures of like size and construction without regard to their use whether erected on or near the surface of the ground or anchored to, or fastened to any building or structure.

676. No Billboard or Signboard Shall be Erected Without Permit.) No billboard or signboard or other similar structure such as is described in this article shall be erected or maintained within the city unless a permit shall first have been secured by the person, firm or corporation desiring to erect or maintain such billboard or signboard from the Commissioner of Buildings to whom application for such permit shall be made; and such application shall be accompanied by such plans and specifications of the proposed billboard or signboard and location of same as are necessary to fully advise and acquaint the said Commissioner with the construction of such proposed billboard or signboard. If the plans and specifications accompanying such application shall be in accordance with the provisions of this article, said Commissioner shall thereupon issue a permit for the erection of such billboard or signboard upon the payment by the applicant of a fee as hereinafter fixed.

677. Alteration and Repair of Billboards and Signboards.) No material alteration of any billboard or signboard nor removal from one location to another shall be made except upon a written permit issued by the Commissioner of Buildings authorizing such alteration or removal; and such permit shall be issued upon application in writing made to such Commissioner by the owner of such billboard or signboard or by the person in charge, possession or control thereof, accompanied by a plan of the proposed alterations or repairs to be made and a written statement covering the proposed removal from one location to another and its reconstruction in the new location, which said alteration and repairs or removal shall be made in accordance with the provisions of this article and the ordinances of the City of Chicago. Where such plans, specifications and location are in compliance with the requirements of this article and are satisfactory to and approved by the Commissioner of Build-

ings, such Commissioner shall issue a permit upon the payment of a fee therefor as hereinafter fixed; but such alteration shall not be construed to apply to the changing of any advertising matter of any billboard or signboard, nor the refacing of the framework supporting same.

678. Wind Pressure—Strength—Billboards Now Existing or Hereafter Constructed.) All billboards and signboards now in existence, or hereafter to be constructed, erected or maintained, shall be made, constructed, erected and maintained of sufficient strength to withstand a wind pressure of twenty-five pounds per square foot of surface without stressing the material beyond the safe limit of stress given elsewhere in this chapter.

679. Changes in Existing Billboards and Signboards.) No surface billboard or signboard constructed or erected prior to the passage of this ordinance shall be maintained after six months from and after the passage of this ordinance where the height of such billboard or signboard exceeds seventeen feet, nor shall such billboard or signboard be maintained after such date, unless there is a clear space of at least three feet six inches above the level of the adjoining street. If, however, the level of the ground where the billboard or signboard is erected or maintained is above the level of the street then there must be a clear space of at least three feet between the bottom or face of the billboard or signboard and the level of the ground at the point where the billboard or signboard is erected or maintained.

680. Duty of Commissioner—Owner's Name to Be Placed on Top of Billboard or Signboard—Annual Inspection.) It shall be the duty of the Commissioner of Buildings to inspect all plans and specifications submitted in connection with the erection or construction or the alteration or repair of any billboard or signboard and to approve same if the method of construction and provisions made for fastening, securing, anchoring and maintaining such billboard or signboards are such as will serve to protect the public and to render such billboards safe and substantial. It is further made the duty of the Commissioner of Buildings to exercise supervision over all billboards and signboards erected or being maintained under the provisions of this article; and to cause inspection by inspectors in his department of all such billboards and signboards to be made once each year and oftener where the condition of such boards so require; and whenever it shall appear to said Commissioner that any such billboard or signboard has been erected in violation of this ordinance or is in an unsafe condition or has become unstable or insecure or is in such a condition as to be a menace to the safety or health of the public, he shall thereupon issue or cause to be issued a notice in writing to the owner of such billboard or signboard or person in charge, possession or control thereof, if the whereabouts of such person is known, informing such person, firm or corporation of the violation of this ordinance and the dangerous condition of such billboard or signboard and directing him to make such alterations or repairs thereto, or to do such acts or things, as are necessary or advisable to place such billboard or signboard in a safe, substantial and secure condition and to make the same comply with the requirements of this ordinance within such reasonable time as may be stated in said notice. If the owner or person in charge, possession or control of any billboard or signboard when so notified shall refuse, fail, or neglect to comply with and conform to the requirements of such notice, said Commissioner shall, upon the expiration of the time therein mentioned, alter, change, tear down or cause to be torn down such part of such billboard or signboard as


is constructed and maintained in violation of this ordinance, and shall charge the expense to the owner or person in possession, charge or control of such billboard or signboard which shall be recovered from them by appropriate legal proceedings. If the owner of such billboard or signboard or the person in charge, possession or control thereof cannot be found, or his or their whereabouts cannot be ascertained, the Commissioner shall attach or cause to be attached to said billboard or signboard, a notice of the same import as that required to be sent to the owner or person in charge, possession or control thereof, where the owner is known; and if such billboard or signboard shall not have been made to conform to this ordinance and be placed in a secure, safe and substantial condition, in accordance with the requirements of such notice, within thirty days after such notice shall have been attached to such billboard or signboard, it shall be the duty of the Commissioner of Buildings to thereupon cause such billboard or signboard or such portion thereof as is constructed and maintained in violation of this ordinance to be torn down; provided that nothing herein contained shall prevent the Commissioner of Buildings from adopting such precautionary measure as may be necessary or advisable in case of imminent danger in order to place such billboard or signboard in a safe condition, the expense of which shall be charged to and recovered from the owner of such billboard or signboard or person in charge, possession or control thereof in any appropriate proceedings therefor. No permit shall be issued to any applicant for permission to erect a billboard or signboard unless such applicant shall agree to place and maintain on the top of such billboard or signboard the name of the person or corporation owning same or who is in charge, possession or control thereof. It shall be the duty of the Commissioner of Buildings to require that the name of the person or corporation owning or in possession, charge or control of such billboard or signboard is placed upon such billboard or signboard forthwith upon the erection thereof and is kept thereon at all times such billboard or signboard is maintained; and in case the owner of such billboard or signboard or the person in charge, possession or control thereof shall fail or refuse to place and maintain such name on the same, they shall be subject to the penalty hereinafter provided for. Every person, firm or corporation engaged in the business of erecting billboards or signboards for the purpose of display advertising shall file with the Commissioner of Buildings within ninety days after the passage of this ordinance a full and complete report of the location and size of all existing billboards or signboards.

681. Fees and Permits and Annual Inspection—Indemnifying Bond.) (a) The fee to be charged for permits issued for the erection or construction of billboards or signboards or for the alteration thereof shall be five dollars for each twenty-five lineal feet of billboard or signboard erected or altered. An annual fee shall be charged every person, firm or corporation as owner, or in possession, charge or control of any billboard or signboard for inspection of such billboards or signboards which shall be one dollar for each twenty-five lineal feet of billboard or signboard, or fractional part thereof; Provided, however, that where such signboard does not exceed sixty-five square feet in area and is attached to the surface of a permanent building in accordance with the provisions of Section 670 and is designed to give publicity to the business carried on within such building, and no part of said sign is more than eighteen feet above the average inside grade at the front of the building, no fees for erection or inspection shall be charged; but not more than one sign of

Put the **INFALLIBLE SHUR-LOC** in charge of your elevators

THE ONLY
INTERLOCK
THAT
DOUBLE
LOCKS
THE
SHAFTWAY
DOOR

100% SAFETY



THE ONLY
INTERLOCK
WHICH
PRE-LOCKS
THE CONTROL
LEVER
BEFORE
THE
SHAFTWAY
DOOR
IS OPENED

100% SAFETY

SHUR-LOC COMPANY *of* ILLINOIS

Phone
Wabash 530

208 South La Salle Street

Chicago

Field Museum of Natural History

Graham, Anderson, Probst and White, Architects, Chicago



Casement windows in this building made waterproof with
SAGER METAL WEATHERSTRIP
A Modern and Better Strip

LET US DEMONSTRATE THE SUPERIOR FEATURES OF OUR STRIP

GEORGE F. WOLFF & COMPANY, Licensee

Telephone Dearborn 1776

190 N. STATE ST., CHICAGO, ILL.

sixty-five square feet shall be allowed for each twenty-five lineal feet of frontage, unless the fees for erection and inspection are paid as herein provided for.

(b) Every person, firm or corporation engaged in the business of constructing and erecting billboards or signboards shall file with the City Clerk a penal bond, with sureties to be approved by the Commissioner of Buildings, in the sum of twenty-five thousand (\$25,000.00) dollars, conditioned that such person, firm or corporation shall faithfully comply with all the provisions and requirements of this ordinance with respect to the construction, alteration, location and safety of billboards or signboards and for the payment of the inspection fees required by said ordinance; and conditioned, further, to indemnify, save and keep harmless said City of Chicago and its officials from any and all claims, damages, liabilities, losses, actions, suits or judgments which may be presented, sustained, brought or secured against the City of Chicago or any of its officials on account of the construction, maintenance, alteration or removal of any of said billboards or signboards, or by reason of any accidents caused by or resulting therefrom.

682. Frontage Consents Required.) It shall be unlawful for any person, firm or corporation to erect or construct any billboard or signboard in any block on any public street in which one-half of the buildings on both sides of the street are used exclusively for residence purposes without first obtaining the consent in writing of the owners or duly authorized agents of said owners owning a majority of the frontage of the property on both sides of the street in the block in which such billboard or signboard is to be erected, constructed or located. Such written consents shall be filed with the Commissioner of Buildings before a permit shall be issued for the erection, construction or location of such billboard or signboard.

683. Penalty.) Any person, firm or corporation owning, operating, maintaining or in charge, possession or control of any billboard or signboard within the city, who shall neglect or refuse to comply with the provisions of this article, or who erects, constructs or maintains any billboard or signboard that does not comply with the provisions of this article shall be fined not less than twenty-five (\$25.00) dollars nor more than two hundred (\$200.00) dollars for each offense; and each day on which any such person shall permit or allow any billboard or signboard owned, operated, maintained or controlled by him to be erected, constructed or maintained in violation of any of the provisions of this article shall constitute a separate and distinct offense.

684. Fence: Construction—Fee for Permit.) It shall be unlawful for any person, firm or corporation to erect or construct any fence within the city limits of the City of Chicago without first obtaining a permit from the Commissioner of Buildings. No wooden fence shall be constructed of greater height than eight feet above the sidewalk grade or eight feet above the surface of the ground where no grade is established. The fee to be charged for permits for the erection or construction of fences shall be one dollar for each one hundred lineal feet of fence.

(See Special Ruling VII, Page 301.)

685. Illuminated and Other Roof Signs of Steel Skeleton Construction—Definition—General Requirements—Fees.) (a) Illuminated and other roof signs regulated by this section shall be defined as signs constructed, erected and maintained upon or over the roof of any building which have all or any part of its letters of which said signs may be constructed either in an outline of incandescent lamps or which have painted.

flush or raised letters where the face of the sign presents a surface to be affected by wind pressure not in excess of the requirements hereinafter contained; or signs having a border of incandescent lights attached thereto and reflecting light thereon; or transparent glass signs where they are lighted by electricity or other illuminant. Every such sign as hereinabove described shall be constructed with steel skeleton construction so as to present a surface to be affected by wind pressure which shall not exceed fifty per cent. of the face of the sign. No illuminated roof sign shall be erected or maintained upon or over the roof of any building unless the framework thereof shall be entirely of metal or some other equally incombustible material, and no material, except such material as is used for insulating wires and conductors, which is less combustible than metal, shall be used in, on or about, or comprise a part of any illuminated roof sign, except that the material to which the framework of any such sign shall be anchored, may be substantial beams anchored or securely fastened to the roof or walls of the buildings upon or over which any such sign is erected.

(b) The distance between the roof of said building or structure and the lower edge of such sign shall not be less than five (5) feet. The height of any such sign from the roof of the building or structure to which the same is anchored or attached shall not exceed sixty (60) feet. No such sign, hereafter erected, shall be constructed closer than six (6) feet from the edge of the roof of the building or structure upon which same is erected. No such illuminated roof sign shall be constructed on any building or structure which is over eight stories in height. Any illuminated roof sign, less than twelve (12) feet in height, shall be exempt from the provisions of this section and shall be held to be governed by the ordinances of the City of Chicago relating to billboards and signboards. No illuminated roof sign, such as is described in this section, shall be constructed, erected, maintained or put in place until the person, firm or corporation desiring to construct, erect, maintain or put in place such sign shall have made application in writing to the Commissioner of Buildings for permission so to do, submitting with such application plans and specifications showing the size, nature and construction of the sign proposed to be erected, and shall present to the City Electrician plans showing the insulation, location and construction of the electrical part of such sign. If the Commissioner of Buildings shall be of the opinion that such sign, if erected, constructed and maintained in accordance with the plans and specifications so submitted, shall be safe and secure, he shall approve the application so submitted, providing the plans bear the approval of the City Electrician, and the Commissioner of Buildings shall note his approval upon such plans and specifications and keep a copy thereof at all times on file in his office. All signs shall be constructed, erected and maintained of sufficient strength to withstand a wind pressure of not less than thirty pounds per square foot of surface without stressing the material beyond the safe limits of stress given elsewhere in this chapter. It shall be the duty of the Commissioner of Buildings to cause his building inspector or inspectors to make an inspection annually of each illuminated roof sign erected or constructed or being maintained under the provisions of this ordinance for the purpose of ascertaining whether such sign is safely and securely constructed and so anchored and fastened to the building or structure; provided, however, that the provisions of this section shall not apply to the erection, construction and maintenance of signboards and billboards as

***NU-TILE* ASPHALT SHINGLES**

Fire destroyed three houses covered with wooden shingles; Nu-Tile Asphalt Shingles saved one and gave the architect and contractor who were responsible for the roof a big boost—a big boost that has resulted in several other houses being protected now by Nu-Tile Asphalt Shingles.

For your benefit as well as that of your customers recommend Nu-Tile Asphalt Shingles—attractive, red, moss green and white water-proof, fire-resisting, and lasting.

Address nearest office and ask for Nu-Tile Catalog.

AMALGAMATED ROOFING CO.


431 South Dearborn Street

CHICAGO

Eastern Office: Fulton Bldg., Pittsburgh, Pa. Southern Office: 18 S. 27th St., Birmingham, Ala.

Brasco COPPER STORE FRONTS

The Best Copper Store-front Construction Made



BRASCO MANUFACTURING COMPANY

5025-35 S. WABASH AVENUE, CHICAGO

regulated by the ordinances of the City of Chicago.

(c) Any person, firm or corporation desiring to erect or maintain an illuminated roof sign, as described in this ordinance, shall pay to the city, to cover the cost of inspection and approval by the Commissioner of Buildings of the plans and specifications of such sign, when erected, a fee of fifty dollars for the first five hundred square feet of superficial area of such sign or fractional part thereof, and for each additional square foot five cents. For each annual inspection by the Commissioner of Buildings, subsequent to the first inspection, there shall be paid a fee of fifty dollars for the first five hundred square feet or fractional part; five cents additional for each additional square foot area over five hundred square feet for each illuminated roof sign. In addition to the fees herein required by the Commissioner of Buildings, to be paid for inspection, there shall be paid by the owner or person having charge or control of any illuminated roof sign, as herein described, an annual inspection fee to cover the cost of such inspection, which shall be made by the city electrician, and such fee shall be at the rate provided by the ordinances of the city.

(d) Every illuminated roof sign erected, constructed or maintained under the provisions of this ordinance shall have the name of the owner thereof placed thereon in a legible and conspicuous manner. No person, firm or corporation shall be permitted to erect or maintain an illuminated roof sign unless he shall execute and file with the City Clerk of Chicago, with sureties to be approved by the Commissioner of Buildings, a bond to the City of Chicago in the penal sum of fifteen thousand dollars (\$15,000.00), conditioned to indemnify, save and keep harmless the City of Chicago, and its officers and agents, from any damage which it, the said city, or any of said officers, may suffer, or from any costs, liability or expense of any kind whatsoever which it, the said city, or any of its officers, may be put to or which may be recovered against the said city, or any of its officers, from or by reason of the construction, erection and maintenance of such sign, and conditional further to faithfully observe and perform all the provisions and conditions of this ordinance and of any ordinance now in force or which may hereafter be passed by the City Council of the City of Chicago, relating to or governing the erection, maintenance, use or inspection of illuminated roof signs.

(e) The permission and authority granted by this ordinance shall cease at any time hereafter at the discretion of the Mayor. In case of the termination of the privileges herein granted by the exercise of the Mayor's discretion as aforesaid, all such electrical signs erected by virtue of the authority conferred by this ordinance, shall be removed at the expense of the owner or owners of the building or the person, firm, corporation or individual who are then maintaining same without any cost or expense of any kind whatsoever to the City of Chicago, provided that in the event of the failure, neglect or refusal on the part of the owner of the building or structure upon which said illuminated electric sign is constructed or the person, firm, corporation or individual operating and maintaining said electric sign to remove said electric sign upon the revocation of the permit by the Mayor as herein provided, the Commissioner of Buildings may proceed to remove same and charge the expense thereof to the owner of the building or structure upon which said illuminated electric sign is constructed or the person, firm, corporation or individual operating or maintaining same.

(f) Any person, firm or corporation who shall erect, construct or maintain an illuminated roof sign in violation of any of the provisions of this section shall be fined not

less than fifty dollars (\$50.00) nor more than two hundred dollars (\$200.00) for each offense.

ARTICLE XXIV. Frontage Consents.




Fig. 52.

686. **Definition of Word "Block" as Used in This Chapter.)** Whenever a provision is made in this chapter that frontage consents shall be obtained for the erection, construction, alteration, enlargement or maintenance of any building or structure in any block, the word "block," so used, shall not be held to mean a square, but shall be held to embrace only that part of a street bounding the square which lies between the two nearest intersecting streets, one on either side of the point at which such building or structure is to be erected, constructed, altered, enlarged or maintained, unless it shall be otherwise specifically provided.

687. **Frontage Consents—Where Required—Uses of Property for Which Frontage Consents are Required—Consent Required in Writing.)** It shall be unlawful for any person, firm or corporation to locate, build, construct or maintain on any lot fronting on any street or alley in the City in any block in which one-half of the buildings on both sides of the street are used exclusively for residence purposes, or within fifty feet of any such street, any building, structure or place used for a gas reservoir, gas manufacture, stock yards, slaughter house, packing house, smoke house or place where fish or meats are smoked or cured, soap factory, glue factory, size or gelatine manufactory, rendering plant, fertilizer manufactory, tannery, storing or scraping of raw hides or skins, lime kiln, cement or plaster of Paris manufactory, oil cloth or linoleum manufactory, rubber manufactory from the crude material, saw or planing mill, wood working establishment, starch factory, glucose or dextrine manufactory, textile factory or manufactory, laundry to be run by machinery, factory combined with a foundry, iron or steel works, brass or copper works, sheet metal works, blacksmithing or horseshoeing shop, boiler making, foundry, smelter, metal refinery, machine shop, stone or monumental works run by machinery, asphalt manufactory or refining, paint or varnish manufactory, oil or turpentine manufactory, printing ink manufactory, tar distillation or manufactory, tar roofing or tar paper or tarred fabric manufactory, ammonia or chlorine or bleaching powder manufactory, celluloid manufactory, place for the distillation of wood or bones, lamp black manufactory, sulphurous acid, sulphuric acid, nitric or hydrochloric acid manufactory, storing or baling of junk or scrap paper or rags, shoddy manufactory or wool scouring, second-hand store or yard, incineration or reduction of garbage or offal or dead animals or refuse, stable for more than five horses, medical dispensary, livery stable, sale stable, boarding stable, without the written consent of a majority of the property owners according to frontage on both sides of such street or alley. Such written consent shall be obtained and filed with the Commissioner of Buildings before a permit is issued for the construction or alteration of any building, structure or place for any of the above purposes; provided, that in determining whether one-half of the buildings on both sides of the street



Lounge Room, Drake Hotel, Chicago

Marshall and Fox Architects

F. O. BAUMANN MFG. CO.

**Contractors for Fine Interior Cabinet Work for Residences,
Public Buildings, Banks and Offices**

Telephone Lincoln 602

Blackhawk St. and Smith Ave., Chicago, Ill.

Rolling Wood Partitions
Folding (Sectionfold) Partitions
Rolling Steel Shutters
Blinds—Adjustable Louvre Slats
Wardrobes—Rolling, also Folding Fronts



H. B. DODGE & COMPANY

332 South Michigan Avenue

CHICAGO, ILL.

are used exclusively for residence purposes any building fronting upon another street and located upon a corner lot shall not be considered.

688. Frontage Consents—For What Required.) It shall be unlawful for any person, firm or corporation to locate, build or construct any store for the sale at retail of goods, wares and merchandise, on any street in any block in which all the buildings are used exclusively for residence purposes, without first securing and filing with the Commissioner of Buildings the written consent of a majority of the property owners according to frontage on both sides of the street in the block in which the building to be thus used is located; provided, in determining whether all the buildings in the said block are used exclusively for residence purposes, any building fronting upon another street and located upon a corner lot shall not be considered.

689. Reformatories—Sheltering Institutions.) (a) It shall be unlawful for any person, firm or corporation to build, construct, maintain, conduct or manage any reformatory, rescue or sheltering institution in any block or square in which one-half of the buildings on both sides of the street or streets on which the proposed reformatory, rescue or sheltering institution may front, are used exclusively for residence purposes without the written consent of a majority of the property owners, according to frontage on both sides of the streets bounding such block. Such written consent shall be obtained and filed with the Commissioner of Buildings before a permit is issued for the construction, alteration, or maintenance of such building.

(b) Provided, that in determining whether one-half of the buildings on both sides of the street are used exclusively for residence purposes, any building fronting upon another street and located upon a corner lot shall not be considered.

690. Frame Building—Permit to Move—Fee—Frontage Consents Required.) (a) No person, firm or corporation shall be permitted to move any building which has been damaged to an extent greater than 50 per cent of its value by fire, decay or otherwise; nor shall be permitted to move any frame building of such a character as is prohibited to be constructed within the fire limits from any point outside the fire limits to any point within the fire limits; nor shall be permitted to move any building to a location at which the uses for which such building is designed are prohibited by ordinance. Permits for the moving of frame buildings other than those the moving of which is herein prohibited, shall be granted upon the payment of a fee of ten cents for each one thousand cubic feet of volume or fractional part thereof of such building, and securing and filing the written consent of two-thirds of the property owners according to frontage on both sides of the street in the block in which such building is to be moved. No permit shall be issued to move any building used or designed to be used for purposes for which frontage consents are required until frontage consents in the block to which such building is to be moved have also been secured and filed, as required by the ordinances relating to such use.

(b) No building used for residence or tenement house purposes shall be moved from one lot to another or from one location to another upon the same lot unless the space to be occupied on such lot shall comply with the provisions of Section 427 of this chapter.

(c) No frontage consent shall be required of any person, firm or corporation for removing a building upon his own premises and not going upon the premises of any other person, or upon any street, alley or other public place, in making such removal.

691. Amusements—Frontage Consents Required.) It shall be unlawful for any person, firm or corporation to construct or erect any building designed or intended to be used for the purpose of presenting or carrying on therein any entertainment for which a license is required by the ordinances of the City of Chicago without first obtaining the written consent of the property owners as required by the City ordinances.

692. Buildings for the Storage of Shavings, Sawdust and Excelsior—Frontage Consents.) It shall be unlawful for any person, firm or corporation to construct or erect any building designed or intended to be used for the purpose of storing shavings, sawdust or excelsior therein within the city without first obtaining the written consent of the property owners as required by the City ordinances.

693. Frontage Consents—Business of Selling Meats, Etc.) It shall be unlawful for any person, firm or corporation to carry on the business of selling meats, poultry, fish, butter, cheese, lard, vegetables or any other provisions from any place of business located in any block in which all the other buildings are used exclusively for residence purposes, without first securing and filing with the City Collector of the City of Chicago the written consent of three-fourths of the property owners according to frontage on both sides of the street in the block in which the building to be thus used is located, provided in determining whether all the buildings in said block are used exclusively for residence purposes, any building fronting on another street and located upon a corner shall not be considered.

694. Business of a Store in Restricted District—Permit Required to Build, Etc.) No permit shall be issued for the erection or remodeling of any building in any block in which the use of buildings is restricted or regulated by ordinance if such building is designed to be used for conducting therein any business or store, without first requiring the applicant for such permit to file with the Commissioner of Buildings a plat showing the use to which all the property in such block is devoted.

ARTICLE XXV.

Fire Limits.

Note: See No. 713, which embraces ordinances excluding temporarily certain territory within the fire limits.

695. Fire Limits—Provisional Fire Limits.) (a) The fire limits of the City of Chicago, within which wooden buildings shall not be erected, shall be and they are hereby defined, as follows: All that part of the City of Chicago bounded by the following limits: Commencing at the intersection of the shore of Lake Michigan and the center line of Rogers avenue, thence southwesterly along the center line of Rogers avenue to the east line of the right of way of the Chicago and Northwestern Railway Company, thence south along the east line of said right of way of the Chicago and Northwestern Railway Company to a line 125 feet north of the north line of Foster avenue, thence west along said line 125 feet north of the north line of Foster avenue to the center line of the North Shore channel, thence southeasterly along the center line of said North Shore channel to the center line of the north branch of the Chicago river, thence northwesterly and westerly along the center line of said north branch of the Chicago river to a line 125 feet west of the west line of North Kedzie avenue, thence south along said line 125 feet west of the west line of North Kedzie avenue to a line 125 feet south of the south line of Irving Park boulevard, thence east along said line 125 feet south of the south line of Irving Park boulevard to the center line of the north branch of the Chicago river, thence northerly along the center line of the north

We weather strip and caulk metal or wood windows and doors. Originators of metal weather strip. Successful more than 26 years. Complete guarantee.

Member of
Associated Builders of Chicago
Chicago Assn. of Commerce
Cook County Real Estate Board

Chamberlin Metal Weather Strips

Save 20% to 40% in Fuel Keep Out Dirt, Dust and Cold

THE STANDARD BY WHICH ALL WEATHER
STRIPS ARE JUDGED

Phone for Estimate
and Expert Advice Harrison 4561

Office and Showrooms:
626 S. Dearborn Street

Sherman & Ellis Service

for CONTRACTORS
ARCHITECTS

Workmen's Compensation Insurance }
Public Liability Insurance } AT NET COST
All Forms of Contingent Insurance }

Through INTER INSURANCE — the LOGICAL MODERN SOLUTION of the Insurance Problem

Your Inquiry Solicited

SHERMAN & ELLIS, Inc.

Home Office — CHICAGO, ILLINOIS — 11 So. La Salle St.

Kansas City, Mo. Overland Bldg.
St. Joseph, Mo. County Finance Bldg.
Milwaukee, Wis. Ry. Exchange Bldg.
Indianapolis, Ind. Merc. Bank Bldg.
Cincinnati, Ohio. Harding Bldg.
New York, N.Y. Citizens Bank Bldg.
St. Louis, Mo. Atlantic Bldg.
Grand Rapids, Mich. Atlantic Bldg.

Toledo, Mo. Mercers Bank Bldg.
Moorhead, Minn. Peoples Bank Bldg.
Baltimore, Md. Calvert Bldg.
Nashville, Tenn. Stadium Bldg.
Topeka, Kan. New La. Bldg.
Wichita, Kans. Beacon Bldg.
Oklahoma City, Okla. Am. Bank Bldg.

Tulsa, Okla. World Bldg.
Houston, Tex. Chronicle Bldg.
Louisville, Ky. Lincoln Bank Bldg.
Birmingham, Ala. Am. Trust Bldg.
Shreveport, La. 222g Edwards St.
New Orleans, La. Whitney Bldg.
Fort Worth, Tex. 1st Natl. Bank Bldg.
Wichita Falls, Tex. City Natl. Bank Bldg.

SAFETY

SERVICE

SAVING

branch of the Chicago river to a line 125 feet south of the south line of Montrose avenue, thence east along said line 125 feet south of the south line of Montrose avenue to a line 125 feet west of the west line of North Western avenue, thence south along said line 125 feet west of the west line of North Western avenue to the center line of Addison street, thence east along the center line of Addison street to the center line of North Western avenue, thence south along the center line of North Western avenue to the center line of Belmont avenue, thence east along the center line of Belmont avenue to the center line of Southport avenue, thence south along the center line of Southport avenue to the center line of Fullerton avenue, thence west along the center line of Fullerton avenue to the center line of the north branch of the Chicago river, thence northwesterly along the center line of the north branch of the Chicago river to a line 125 feet north of the north line of Belmont avenue, thence west along said line 125 feet north of the north line of Belmont avenue to a line 125 feet west of the west line of North Kostner avenue, thence south along said line 125 feet west of the west line of North Kostner avenue to a line 125 feet north of the north line of Diversey avenue, thence west along said line 125 feet north of the north line of Diversey avenue to a line 125 feet west of the west line of North Cicero avenue, thence south along said line 125 feet west of the west line of North Cicero avenue to a line 125 feet north of the north line of Armitage avenue, thence west along said line 125 feet north of the north line of Armitage avenue to a line 125 feet northeasterly of the northeasterly line of West Grand avenue, thence northwesterly along said line 125 feet northeasterly of the northeasterly line of West Grand avenue to a line 125 feet north of the north line of Fullerton avenue, thence west along said line 125 feet north of the north line of Fullerton avenue to a line 125 feet northeasterly of the northeasterly line of West Grand avenue, thence northwesterly along said line 125 feet northeasterly of the northeasterly line of West Grand avenue to the center line of Harlem avenue, thence south along the center line of Harlem avenue to a line 125 feet southwesterly of the southwesterly line of West Grand avenue, thence southeasterly along said line 125 feet southwesterly of the southwesterly line of West Grand avenue to a line 125 feet south of the south line of Fullerton avenue, thence east along the said line 125 feet south of the south line of Fullerton avenue to a line 125 feet southwesterly of the southwesterly line of West Grand avenue, thence southeasterly along said line 125 feet southwesterly of the southwesterly line of West Grand avenue to the southerly line of the right of way of the Chicago, Milwaukee and St. Paul Railway Company, thence northwesterly and westerly along the southerly line of said right of way of the Chicago, Milwaukee and St. Paul Railway Company to the center line of Narragansett avenue, thence south along the center line of Narragansett avenue to the center line of West North avenue, thence east along the center line of West North avenue to the center line of North Central avenue, thence south along the center line of North Central avenue to the center line of Le Moyne street, thence west along the center line of Le Moyne street to the center line of North Menard avenue, thence south along the center line of North Menard avenue to the center line of Hirsch street, thence east along the center line of Hirsch street to the center line of Leclaire avenue, thence north along the center line of Leclaire avenue to the center line of West North avenue, thence east along the center line of West North avenue to a line 125 feet west of the west line of North Cicero avenue, thence south along said line 125 feet west of the west line of North Cicero avenue to a line 125 feet north of the north line of West Division street, thence

west along said line 125 feet north of the north line of West Division street to the center line of North Austin avenue, thence south along the center line of North Austin avenue to a line 125 feet south of the south line of West Division street, thence east along said line 125 feet south of the south line of West Division street to the center line of North Laramie avenue, thence south along the center line of North Laramie avenue to the center line of West Chicago avenue, thence west along the center line of West Chicago avenue to the center line of North Austin avenue, thence south along the center line of North Austin avenue and South Austin avenue to the center line of West 12th street, thence east along the center line of West 12th street to the center line of South Kenton avenue, produced north, thence south along the center line of South Kenton avenue, produced north, to the center line of West 39th street, produced west, thence east along the center line of West 39th street, produced west, to the center line of the Illinois and Michigan Canal, thence north-easterly along the center line of the Illinois and Michigan Canal to the center line of South Western Avenue boulevard, thence south along the center line of South Western Avenue boulevard to the center line of West 39th street, thence east along the center line of West 39th street to the center line of South Robey street, thence south along the center line of South Robey street to the center line of West 43rd street, thence east along the center line of West 43rd street to a line 125 feet west of the west line of South Ashland avenue, thence north along said line 125 feet west of the west line of South Ashland avenue to the center line of West 41st street, thence east along the center line of West 41st street to the center line of South Ashland avenue, thence north along the center line of South Ashland avenue to the center line of West 40th street, thence east along the center line of West 40th street to a line 125 feet east of the east line of South Ashland avenue, thence south along said line 125 feet east of the east line of South Ashland avenue to the center line of West 43rd street, thence west along the center line of West 43rd street to the center line of South Ashland avenue, thence south along the center line of South Ashland avenue to the center line of West 47th street, thence east along the center line of West 47th street to a line 125 feet west of the west line of South Halsted street, thence south along said line 125 feet west of the west line of South Halsted street to the center line of West 51st street, thence west along the center line of West 51st street to the center line of South Racine avenue, thence south along the center line of South Racine avenue to a line 125 feet north of the north line of West 63rd street, thence west along said line 125 feet north of the north line of West 63rd street to the center line of South Western avenue, thence north along the center line of South Western avenue to the center line of West 51st street, thence west along the center line of West 51st street to the center line of South Rockwell street, thence south along the center line of South Rockwell street to the center line of West 59th street, thence west along the center line of West 59th street to the center line of South Kedzie avenue, thence south along the center line of South Kedzie avenue to a line 125 feet south of the south line of West 67th street, thence east along said line 125 feet south of the south line of West 67th street to the center line of South Richmond street, thence north along the center line of South Richmond street to a line one hundred and twenty-five feet south of the south line of West 63rd street, thence east along said line one hundred and twenty-five feet south of the south line of West 63rd street to the center of South Rockwell street and thence south along the center line of South Rockwell street to the center line of West 66th



We guarantee satisfaction
to the user

**SIMPLEX IRONERS, WASHERS
WRINGERS AND
EXTRACTORS**


**American
Ironing Machine Co.**

168 North Michigan Avenue
CHICAGO, ILL.

Phone Randolph 1064

**We Specialize on
Laundering Machines
and Equipment**

especially adapted to the need of
the smaller Hotels, Hospitals, Insti-
tutions, Apartment Houses and
Residences, and
are prepared to
assist the Archi-
tect and Builder
with plans and
suggestions.



**Dumb Waiters
Refrigerators**

OF EVERY DESCRIPTION

**Cooling Rooms
Cold Storage Doors
Portable
Cold Storage Houses**

PROMPT SERVICE

QUICK ESTIMATES

D. A. MATOT

MANUFACTURER

Main Office and Factory

Phones, Lincoln 2-3

1538-1546 Montana St., CHICAGO

street, thence east along the center line of West 66th street to the center line of South Western avenue, thence north along the center line of South Western avenue to a line 125 feet south of the south line of West 63rd street, thence east along said line 125 feet south of the south line of West 63rd street to the center line of South Racine avenue, thence south along the center line of South Racine avenue to the center line of West 75th street, thence west along the center line of West 75th street to a line 125 feet east of the east line of South Ashland avenue, thence north along said line 125 feet east of the east line of South Ashland avenue to the center line of West 71st street, thence west along the center line of West 71st street to a line 125 feet west of the west line of South Ashland avenue, thence south along said line 125 feet west of the west line of South Ashland avenue to the center line of West 75th street, thence west along the center line of West 75th street to the center line of South Cicero avenue, thence south along the center line of South Cicero avenue to the center line of West 87th street, thence east along the center line of West 87th street to the center line of South Western avenue, thence south along the center line of South Western avenue to the center line of West 99th street, thence west along the center line of West 99th street to the center line of South California avenue, thence south along the center line of South California avenue to the center line of West 115th street, thence east along the center line of West 115th street to the center line of South Western avenue, thence south along the center line of South Western avenue to the center line of West 119th street, thence east along the center line of West 119th street to the center line of Vincennes avenue, thence northeasterly along the center line of Vincennes avenue to a line 125 feet north of the north line of West 95th street, thence east along said line 125 feet north of the north line of West 95th street to the center line of South Halsted street, thence south along the center line of South Halsted street to the center line of West 103rd street, thence west along the center line of West 103rd street to the center line of Beverly avenue, thence northwesterly along the center line of Beverly avenue to West 87th street, thence northwesterly and northerly along the east line of the right of way of the P., C. C. & St. L. Railway to a line 125 feet south of the south line of West 83rd street, thence east along said line 125 feet south of the south line of West 83rd street to the center line of South Winchester avenue, thence south and southeasterly along the center line of South Winchester avenue to the northwestern boundary line of the right-of-way of the Chicago, Rock Island & Pacific Railway Co., in South Hermitage avenue, thence southwesterly in South Hermitage avenue along said northwestern boundary line of the right-of-way of the Chicago, Rock Island & Pacific Railway Co., to the center line of West 91st street, thence east along the center line of West 91st street to a line 125 feet west of the west line of South Ashland avenue, thence south along said line 125 feet west of the west line of South Ashland avenue to a line 125 feet south of the south line of West 95th street, thence east along said line 125 feet south of the south line of West 95th street to a line 125 feet east of the east line of Vincennes avenue, thence northeasterly along said line 125 feet east of the east line of Vincennes avenue to a line 125 feet north of the north line of West 90th street, thence west along said line 125 feet north of the north line of West 90th street to the center line of South Racine avenue, thence north along the center line of South Racine avenue to a line 125 feet south of the south line of West 83rd street, thence east along said line 125 feet

south of the south line of West and East 83rd street to a line 125 feet west of the west line of South Park avenue, thence south along said line 125 feet west of the west line of South Park avenue to a line 125 feet north of the north line of East 95th street, thence west along said line 125 feet north of the north line of East and West 95th street to a line 125 feet west of the west line of South State street, thence south along said line 125 feet west of the west line of South State street to a line 125 feet south of the south line of West 99th street, thence east along said line 125 feet south of the south line of West 99th street and East 99th street to a line 125 feet west of the west line of South Michigan avenue, thence south along said line 125 feet west of the west line of South Michigan avenue to a line 125 feet north of the north line of East 119th street, thence west along said line 125 feet north of the north line of East and West 119th street to a line 125 feet west of the west line of South Morgan street, thence south along said line 125 feet west of the west line of South Morgan street to a line 125 feet south of the south line of West 119th street, thence east along said line 125 feet south of the south line of West and East 119th street to a line 125 feet east of the east line of South Michigan avenue, thence north along said line of 125 feet east of the east line of South Michigan avenue to a line 125 feet south of the south line of East 99th street, thence east along said line 125 feet south of the south line of East 99th street to a line 125 feet west of the west line of South Park avenue, thence south along said line 125 feet west of the west line of South Park avenue to the center line of East 115th street, thence east along the center line of East 115th street to the northeasterly line of the right of way of the Michigan Central Railroad Company, thence south and southeasterly along said northeasterly line of the right of way of the Michigan Central Railroad Company to the center line of East 127th street, thence east along the center line of East 127th street to the shore line of Lake Calumet, thence northwesterly and northeasterly along the shore line of said Lake Calumet to a line 125 feet east of the east line of Stony Island avenue, thence north along said line 125 feet east of the east line of Stony Island avenue to a line 125 feet north of the north line of East 95th street, thence west along said line 125 feet north of the north line of East 95th street to a line 125 feet east of the east line of the right of way of the Illinois Central Railroad Company, thence northeasterly along said line 125 feet east of the east line of the right of way of the Illinois Central Railroad Company to a line 125 feet south of the south line of East 79th street, thence east along said line 125 feet south of the south line of East 79th street to the center line of Brandon avenue, thence south along the center line of Brandon avenue to the center line of East 83rd street, thence east along the center line of East 83rd street to the center line of Burley avenue, thence south along the center line of Burley avenue to the center line of East 89th street, thence west along the center line of East 89th street to a line 125 feet west of the west line of Manistee avenue, thence south along said line 125 feet west of the west line of Manistee avenue to the northeasterly line of the right of way of the Lake Shore and Michigan Southern Railroad Company, thence southeasterly along said northeasterly line of the right of way of the Lake Shore and Michigan Southern Railroad Company to the easterly and southeasterly line of the South Chicago branch of the Pittsburgh, Fort Wayne and Chicago Railroad Company, thence southwesterly along said easterly and southeasterly line of the South Chicago branch of the Pittsburgh, Fort Wayne and Chicago Railroad Company to the center line of East 106th street, thence

TELEPHONE, WARASH 79

HAGGARTY FIRE PROTECTION CO.



Contractors for AUTOMATIC
SPRINKLER EQUIPMENTS

Approved U. S. Automatic Sprinkler

327 SOUTH LA SALLE STREET

CHICAGO, ILLINOIS



William Penn Hotel, Pittsburgh, Pa.



Ford Motor Car Company Assembling Plant,
Kansas City, Mo.

These buildings are roofed with
AMERICAN TARRED FELT and
A. T. P. OLD STYLE ROOFING
PITCH which are recommended
by the leading architects, engi-
neers and contractors through-
out the country.

SEND FOR SPECIFICATIONS

AMERICAN TAR PRODUCTS COMPANY, Inc.

208 South La Salle Street

CHICAGO, ILLINOIS

east along the center line of East 106th street to a line 200 feet east of the east bank of the Calumet river, thence north along said line 200 feet east of the east bank of the Calumet river to the center line of East 95th street, thence east along the center line of East 95th street to the shore of Lake Michigan, thence northerly and northwesterly along the shore of Lake Michigan to the place of beginning.

(b) Also, commencing at the intersection of the center line of Addison street and the center line of the north branch of the Chicago river, thence west along the center line of Addison street to the center line of North Whipple street, thence south along the center line of North Whipple street to the center line of Elston avenue, thence southeasterly along the center line of Elston avenue to the center line of Roscoe street, thence east along the center line of Roscoe street to the center line of the north branch of the Chicago river, thence north along the center line of the north branch of the Chicago river to the place of beginning.

(b1) Also, commencing at the intersection of the center line of South Western avenue boulevard and the center line of West 45th street, thence west along the center line of West 45th street to the center line of South Cicero avenue, thence south along the center line of South Cicero avenue to the center line of West 51st street, thence west along the center line of West 51st street to the southerly line of the right of way of the Chicago & Alton Railroad, thence southwesterly along said southerly line of the right of way of the Chicago & Alton Railroad to the center line of South Harlem avenue, thence south along the center line of South Harlem avenue to the center line of West 59th street, thence east along the center line of West 59th street to the center line of South Narragansett avenue, thence south along the center line of South Narragansett avenue and Narragansett avenue produced south to the center line of West 65th street, produced west, thence east along the center line of West 65th street produced west and West 65th street to the center line of South Cicero avenue, thence south along the center line of South Cicero avenue to the center line of West 69th street produced west, thence east along the center line of West 69th street produced west and West 69th street to the center line of South Western avenue, thence north along the center line of South Western avenue to the center line of West 66th street, thence west along the center line of West 66th street to the center line of South Rockwell street, thence north along the center line of South Rockwell street to a line 125 feet south of the south line of West 63rd street, thence west along said line 125 feet south of the south line of West 63rd street to the center line of South Richmond street, thence south along the center line of South Richmond street to a line 125 feet south of the south line of West 67th street, thence west along said line 125 feet south of the south line of West 67th street to the center line of South Kedzie avenue, thence north along the center line of South Kedzie avenue to a line 125 feet south of the south line of West 59th street, thence west along said line 125 feet south of the south line of West 59th street to a line 125 feet west of the west line of South Kedzie avenue, thence north along said line 125 feet west of the west line of South Kedzie avenue to a line 125 feet north of the north line of West 53rd street, thence east along said line 125 feet north of the north line of West 53rd street to a line 125 feet east of the east line of South Whipple street, thence south along said line 125 feet east of the east line of South Whipple street to a line 125 feet south of the south line of West 57th street, thence east along said line 125 feet


south of the south line of West 57th street to the center line of South Rockwell street, thence north along the center line of South Rockwell street to the center line of West 51st street, thence east along the center line of West 51st street to the center line of South Western avenue boulevard, thence north along the center line of South Western avenue boulevard to the place of beginning.

Also all of that territory bounded on the west by Stony Island avenue, thence along a line one hundred and twenty-five feet south of East 83rd street on the south, east to the center line of Yates avenue, thence north to a line one hundred and twenty-five feet south of East 79th street on the north, thence west to Stony Island avenue.

Also commencing at the intersection of a line 125 feet north of the north line of West 59th street and 125 feet east of the east line of Rockwell street, thence west along said line 125 feet south of the south line of West 59th street to a line 125 feet west of the west line of South Kedzie avenue, thence north along said line 125 feet west of the west line of South Kedzie avenue to a line 125 feet north of the north line of West 53rd street, thence east along said line 125 feet north of the north line of West 53rd street to a line 125 feet east of the east line of Whipple street, thence south along said line 125 feet east of the east line of Whipple street to a line 125 feet north of the north line of West 57th street, thence east along said line 125 feet north of the north line of West 57th street to a line 125 feet south of the east line of Rockwell street, thence east along said line 125 feet east of the east line of Rockwell street to the place of beginning. Also commencing at the intersection of a line 125 feet south of the south line of East 83rd street, and 125 feet west of the west line of South Park avenue, thence south along the said line 125 feet west of the west line of South Park avenue to a line 125 feet north of the north line of 95th street, thence west along said line 125 feet north of the north line of 95th street to a line 125 feet east of the east line of Stewart avenue, thence north along said line 125 feet east of the east line of Stewart avenue to a line 125 feet south of the south line of East 83rd street, thence west along said line 125 feet south of the south line of East 83rd street to the center line of Eggleston avenue; thence south on the center line of Eggleston avenue to a line 125 feet south of the south line of West 95th street; thence west on the line 125 feet south of the south line of West 95th street to a line 125 feet east of Vincennes avenue; thence along the line 125 feet east of Vincennes avenue to a line 125 feet north of West 90th street; thence west along the line 125 feet north of West 90th street to the center line of South Racine avenue; thence north along the center line of South Racine avenue to a line 125 feet south of the south line of 83rd street; thence east along said line 125 feet south of the south line of 83rd street to the place of beginning.

Also commencing at the intersection of a line 125 feet south of the south line of East 83rd street and 125 feet west of the west line of Yates avenue, thence south along said line 125 feet west of the west line of Yates avenue to the right of way of the Lake Shore & Michigan Southern Railroad, thence northwest along said right of way of the Lake Shore & Michigan Southern Railroad to a line 125 feet south of the south line of East 83rd street, thence east along said line 125 feet south of the south line of East 83rd street to the place of beginning.

All that part of the City of Chicago bounded by the following limits is hereby included within the fire limits of the City of Chicago: Commencing at the intersection of the center line of Berteau avenue and



PHONES: RAND. 3374. 4719

THE SCHARMER CONSTRUCTION CO.
CARPENTERS AND GENERAL
CONTRACTORS

1913 City Hall Square Bldg.

139 N. Clark St., Chicago

RALPH SOLLITT & SONS
CONSTRUCTION CO.

GENERAL CONTRACTORS
AND BUILDERS

30 N. La Salle Street

CHICAGO

Telephone Main 2383
 2382

Western avenue, thence north along the center line of Western avenue to its intersection with the center line of Montrose avenue, thence west along the center line of Montrose avenue to the east line of the Chicago River, thence southeast and south along the east line of the Chicago River to the center line of Berteau avenue, thence east along the center line of Berteau avenue to the place of beginning.

All that part of the City of Chicago bounded by the following limits is hereby included within the fire limits of the City of Chicago: Commencing at the intersection of the center line of West Grand avenue and La Crosse avenue, thence north along the center line of La Crosse avenue to its intersection with the center line of Armitage avenue, thence west along the center line of Armitage avenue to its intersection with the center line of Laporte avenue, thence south along the center line of Laporte avenue to its intersection with the center line of West Grand avenue, thence southeasterly and south along the center line of West Grand avenue to the place of beginning.

All that part of the City of Chicago bounded by the following limits is hereby included within the fire limits of the City of Chicago: Commencing at the intersection of the center line of West Chicago avenue and North Central avenue, thence north along the center line of North Central avenue to its intersection with the center line of West Division street, thence west along the center line of West Division street to its intersection with the center line of North Austin avenue, thence south along the center line of North Austin avenue to its intersection with the center line of West Chicago avenue, thence east along the center line of West Chicago avenue to its intersection with the center line of North Central avenue.

All that part of the City of Chicago bounded by the following limits is hereby included within the fire limits of the City of Chicago: Commencing at the intersection of the center line of West Division street and North Cicero avenue, thence north along the center line of North Cicero avenue to its intersection with the center line of West North avenue, thence west along the center line of West North avenue to its intersection with the center line of North Austin avenue, thence south along the center line of North Austin avenue to its intersection with the center line of West Division street, thence east along the center line of West Division street to the place of beginning.

All that part of the City of Chicago bounded by the following limits is hereby included within the fire limits of the City of Chicago: Commencing at the intersection of the center line of East 83rd street and Jeffery avenue, thence south along the center line of Jeffery avenue to its intersection with the center line of East 87th street, thence west along the center line of East 87th street to the east line of the right of way of the New York, Chicago and St. Louis Railroad, thence northwest and north along the said east line of the right of way of the New York, Chicago and St. Louis Railroad to the center line of East 83rd street, thence east along the center line of East 83rd street to the place of beginning.

(c) Excepting, the district bounded as follows: Commencing at the intersection of a line 125 feet south of the south line of Foster avenue and the center line of North Leavitt street, thence west along said line 125 feet south of the south line of Foster avenue to a line 125 feet east of the east line of North Western avenue, thence south along said line 125 feet east of the east line of North Western avenue to a line 125 feet east of the east line of Lincoln avenue, thence southeasterly along said line 125 feet east of the east line of Lincoln avenue to a line 125 feet north of the north line of Lawrence avenue, thence east along said line 125 feet north of the north line of Lawrence avenue to the center line of North Leavitt

street, thence north along the center line of North Leavitt street to the place of beginning.

(d) Excepting, also, the district bounded as follows: Commencing at the intersection of a line 125 feet south of the south line of Belmont avenue and the center line of North Kedzie avenue, thence west along said line 125 feet south of the south line of Belmont avenue to the center line of North Crawford avenue, thence south along the center line of North Crawford avenue to the center line of Fullerton avenue, thence east along the center line of Fullerton avenue to the center line of North Central Park avenue, thence north along the center line of North Central Park avenue to the center line of Diversey avenue, thence east along the center line of Diversey avenue to the center line of North Kedzie avenue, thence north along the center line of North Kedzie avenue to the place of beginning.

(e) Excepting, also, the district bounded as follows: Commencing at the intersection of a line 125 feet south of the south line of Armitage avenue and a line 125 feet west of the west line of North Cicero avenue, thence west along said line 125 feet south of the south line of Armitage avenue to a line 125 feet northeasterly of the northeasterly line of West Grand avenue, thence southeasterly along said line 125 feet northeasterly of the northeasterly line of West Grand avenue to a line 125 feet west of the west line of North Cicero avenue, thence north along said line 125 feet west of the west line of North Cicero avenue to the place of beginning.

(f) Excepting, also, the district bounded as follows: Commencing at the intersection of the center line of West 40th street and the center line of Normal avenue, thence west along the center line of West 40th street to the center line of Wallace street, thence south along the center line of Wallace street to the center line of West 43rd street, thence west along the center line of West 43rd street to a line 125 feet east of the east line of South Halsted street, thence south along said line 125 feet east of the east line of South Halsted street to the center line of West 51st street, thence east along the center line of West 51st street to the center line of South Union avenue, thence south along the center line of South Union avenue to the center line of West Garfield boulevard, thence east along the center line of West Garfield boulevard to a line 125 feet west of the west line of Wentworth avenue, thence north along said line 125 feet west of the west line of Wentworth avenue to the center line of West 43rd street, thence west along the center line of West 43rd street to the center line of Normal avenue, thence north along the center line of Normal avenue to the place of beginning.

(g) Excepting, also, the district bounded as follows: Commencing at the center line of West 43rd street and a line 125 feet west of the west line of South State street, thence west along the center line of West 43rd street to a line 125 feet east of the east line of Wentworth avenue, thence south along said line 125 feet east of the east line of Wentworth avenue to the center line of West Garfield boulevard, thence east along the center line of West Garfield boulevard to a line 125 feet west of the west line of South State street, thence north along said line 125 feet west of the west line of South State street to the place of beginning.

(h) Excepting, also, the district bounded as follows: Commencing at the intersection of the center line of West 52nd street and the center line of South Peoria street, thence west along the center line of West 52nd street to the center line of South Morgan street, thence south along the center line of South Morgan street to the center line of West 53rd street, thence east along the center line of West 53rd street to the center line of South Peoria street, thence north

Douglas 944



Fugard & Knapp and Ralph C. Harris, Associated Architects
220 East Walton Place

McLennan Construction Company

HUGH McLENNAN, President

*Building
Construction*

McLENNAN BUILDING
31st and Calumet Avenue
CHICAGO

PHONES: MAIN 487 AND 488

James Shedden & Co.

Building Contractors

Masonry

Reinforced Concrete

Carpentry

FACTORIES, WAREHOUSES, MERCANTILE AND
INDUSTRIAL BUILDINGS. MILL, STEEL
AND REINFORCED CONCRETE CONSTRUCTION

106 NORTH LA SALLE ST.

CHICAGO

along the center line of South Peoria street to the place of beginning.

(i) Excepting, also, the following territory, which shall be known as a provisional fire limit district: Commencing at the intersection of the shore of Lake Michigan and the center line of Rogers avenue, thence southwesterly along the center line of Rogers avenue to the east line of the right of way of the Chicago & Northwestern Railway Company, thence south along the east line of the right of way of the Chicago & Northwestern Railway Company to the center line of Devon avenue, thence east along the center line of Devon avenue to the shore of Lake Michigan, thence northwesterly along the shore of Lake Michigan to the place of beginning.

(j) Excepting, also, the following territory, which shall be known as a provisional fire limit district: Commencing at the intersection of the shore line of Lake Michigan and the center line of East 67th street, thence west along the center line of East 67th street to the center line of Cottage Grove avenue, thence north along the center line of Cottage Grove avenue to the center line of East 63rd street, thence west along the center line of East 63rd street to the center line of South Park avenue, thence south along the center line of South Park avenue to the center line of East 67th street, thence west along the center line of East 67th street to the northeasterly line of the right of way of the Lake Shore & Michigan Southern Railroad Company, thence northwesterly along the northeasterly line of the right of way of the Lake Shore & Michigan Southern Railroad Company to the center line of South State street, thence south along the center line of South State street to the center line of East 75th street, thence east along the center line of East 75th street to the center line of Cottage Grove avenue, thence south along the center line of Cottage Grove avenue to a line 125 feet south of the south line of East 79th street, thence east along said line 125 feet south of the south line of East 79th street to the shore of Lake Michigan, thence northwesterly along the shore of Lake Michigan to the place of beginning.

(k) Excepting, also, the following territory, which shall be known as a provisional fire limit district: Commencing at the center line of East 87th street and a line 125 feet east of the east line of the right of way of the Illinois Central Railroad Company, thence west along the center line of East 87th street to a line 125 feet west of the west line of South Park avenue, thence south along said line 125 feet west of the west line of South Park avenue to the center line of East 95th street, thence east along the center line of East 95th street to a line 125 feet east of the east line of the right of way of the Illinois Central Railroad Company, thence northeasterly along said line 125 feet east of the east line of the right of way of the Illinois Central Railroad Company to the place of beginning.

(l) The following described territory outside the above described fire limits is hereby established as a provisional fire limits district: Commencing at the intersection of the southwesterly line of the right of way of the Pittsburgh, Ft. Wayne and Chicago Railroad and a line 125 feet easterly of the easterly line of the right of way of the Illinois Central Railroad, thence southwesterly along said line 125 feet easterly of the easterly line of the right of way of the Illinois Central Railroad to the center line of East 83rd street, thence east along the center line of East 83rd street to the center line of Stony Island avenue, thence north along the center line of Stony Island avenue to the southwesterly line of the right of way of the Pittsburgh, Ft. Wayne and Chicago Railroad, thence northwesterly along the southwesterly line of the right of way of the Pittsburgh, Ft. Wayne and Chicago Railroad

to the said line 125 feet easterly of the easterly line of the right of way of the Illinois Central Railroad, the place of beginning.

(m) Any person desiring to erect a frame or wooden building to be used for residence or mercantile purposes within the provisional fire limits above described shall have a right to do so, upon presenting a petition to the Commissioner of Buildings together with a plat, plans and specifications showing the place where such building is to be erected. Such petition shall be verified by the affidavit of the applicant and shall contain the written consent of the owners of a majority of the frontage upon both sides of the streets surrounding the square in which the building is to be erected.

(n) No frame or wooden residence or mercantile building shall be erected within the said provisional fire limits exceeding forty feet in height.

696. **Nuisance.)** (a) Every building or structure constructed or maintained in violation of this chapter, or which is in an unsanitary condition, or in an unsafe or dangerous condition or which in any manner endangers the health or safety of any person or persons, is hereby declared to be a public nuisance.

(b) Every building or part thereof which is in an unsanitary condition by reason of the basement or cellar being damp or wet, or by reason of the floor of such basement or cellar being covered with stagnant water, or by reason of the presence of sewer gas, or by reason of any portion of a building being infected with disease or being unfit for human habitation or which by reason of any other unsanitary condition, is a source of sickness, or which endangers the public health, is hereby declared to be a public nuisance.

697. **Penalty.)** Any person, or corporation who violates, neglects or refuses to comply with, or who resists or opposes the enforcement of any of the provisions of this chapter, shall be fined not less than twenty-five nor more than two hundred dollars for each offense, and every such person or corporation shall be deemed guilty of a separate offense for every day on which such violation, neglect or refusal shall continue; and any builder or contractor who shall construct any building in violation of any of the provisions of this chapter, and any architect designed, drawing plans for or having charge of such building or who shall permit it to be constructed, shall be liable to the penalties provided and imposed by this section.

698. **No Amusement License to Issue Without Certificate from City Officials.)** No license shall be issued to any person, firm or corporation to produce, present, conduct, operate or offer for gain or profit, any theatricals, shows or amusements until the Commissioner of Buildings, the Commissioner of Health, the Fire Marshal and the City Electrician shall have certified in writing that the room or place where it is proposed to produce, present, conduct, operate or offer such theatricals, shows or amusements complies in every respect with the ordinances of the City of Chicago.

ORDINANCES

Pertaining to building operations, and given numbers (arbitrarily) following the numbers of sections of the Building Ordinance, for convenience in indexing.

No. 699

DRY-CLEANING PLANTS: ORDINANCE PERTAINING TO.

Be it ordained by the City Council of the City of Chicago:

Section 1. That the ordinance creating the Bureau of Fire Prevention and Public

Joseph H. Buttas



John W. Buttas

The Studio Building, S. W. Cor. Cass and Superior Sts.
Walter W. Ahlschlager, Architect

B-W Construction Company

(Not Inc.)

BUTTAS BROS.

Telephones:
Franklin 5298 and 851

General Contractors

10 South LaSalle St.
CHICAGO

TELEPHONE, HARRISON 3676

O.W. Rosenthal-Cornell Co.

BUILDERS

RAILWAY EXCHANGE
CHICAGO

“Building Buildings Better—The ‘R-C’ Business-Getter”

Safety passed July 22, 1912, and appearing on pages 1543 to 1620 inclusive, of the Journal of the Proceedings of the City Council of that date, as subsequently amended, be and the same is hereby further amended so that Section 164, Article XI of said ordinance shall read as follows:

Section 164. Frontage Consents.—Building Requirements.—Ventilation.—Fire Prevention Equipment.—Lighting.—Water Trough.—Asbestos Blanket.)

(a) Whenever application is made for a permit to build or license to use or occupy any building for the purpose of conducting or carrying on the business of dry cleaning or drying, as defined in this ordinance, in any block or square in which two-thirds of the improved property, according to frontage on both sides of the streets surrounding such block or square, is used exclusively for residence purposes, such application shall be accompanied by the written consent of a majority of all the property owners according to frontage on both sides of the streets surrounding such block or square before a permit or license may be issued; and such building or buildings shall be constructed and equipped according to the following specifications:

(b) Every such building shall be built of brick, stone or concrete, with no basement, and shall not exceed two stories in height; provided, however, that the use of any building not exceeding three stories in height in which a dry cleaning business was carried on prior to July 22, 1912, may be continued if such building complies in all other respects with the provisions of this ordinance. The first floor of such building shall be higher than the surface of the ground surrounding such building and shall be so laid that there shall be no space underneath the same. The floor or floors of both dry cleaning room and drying room, and the ceiling or roof of dry cleaning room shall be of fireproof construction, and the roof on the drying room, if of combustible material, shall be without concealed spaces.

There shall be no openings through the floors, excepting in two-story buildings, in which a stairway leading from the second floor to the first floor may be permitted, if properly enclosed with walls of incombustible material. Such stairways shall lead to the outside of the building without any doors or openings leading into the dry cleaning room.

Every such building shall be detached and at least fifty (50) feet from any other building or structure or to line of adjoining property which may be built upon; provided, however, that the use of any building in which a dry cleaning business was carried on prior to the passage of said ordinance on July 22, 1912, may be continued where such building is separated from all other buildings by a fire wall, with no openings into any adjoining building; and further provided, that any building previously used for dry cleaning but not so occupied or used for such purpose for a period of three (3) consecutive months immediately prior to the passage of this amendatory ordinance, shall not again be used for the business of dry cleaning unless all requirements governing new buildings or dry cleaning plants have been complied with.

A building used for dry cleaning or drying shall not be occupied for any purpose other than the conduct of a dry cleaning and dry room plant. The walls of such building shall be not less than twelve inches thick and shall have vent holes at the floor line not less than sixteen (16) square inches in area when ventilation by means of exhaust fan or fans is employed, and not less than thirty-two (32) square inches in area when ventilation by means of paddle-wheel type fan or fans is employed; such vent holes shall be not more than six (6) feet apart, measured from center to center, and shall be protected by screens of thirty (30)

mesh brass wire on the inside of such walls and by iron bars or screens of large mesh on the outside of such walls.

(c) Such building, unless divided into compartments, as hereinafter described, shall be further ventilated by means of an exhaust fan or fans of sufficient capacity to change the air in the building every three minutes and shall be kept in operation at all times during the use of such building. Such exhaust fan shall be located in an air conduit whose inlet openings shall be at or near the floor level in the wall farthest away from any other building or structure, and the discharge end of such conduit shall be carried above the roof of such building. If such building be divided into fireproof compartments, by partitions of six-inch hollow tile, or equivalent, extending from floor to ceiling, each such compartment having a capacity of not to exceed twenty-five hundred (2,500) cubic feet, the exhaust fan or fans and air conduit before mentioned may be omitted from each of such compartments, and in lieu thereof there shall be a paddle-wheel type fan attached to the line shafting in each compartment, of sufficient size to displace an amount of air equal to the cubical contents of the compartment at least once each minute. All doors in any such building shall be constructed of incombustible materials and shall open outward. All window openings of such building shall be protected by fire-resisting glass with metal sash and frames, or by outside iron shutters.

(d) Every such building two stories high shall be provided with two stairways leading from the second to the first floor, at least one of which must be placed on the outside and be constructed of iron or steel.

(e) Every such dry cleaning plant shall be equipped with a high pressure steam boiler of a capacity equivalent to one (1) horse power for each one hundred (100) cubic feet contents of the dry cleaning or benzene room to admit of flooding the dry cleaning and dry rooms with steam in case of fire. A steam pressure of at least thirty (30) pounds must be maintained in said boiler at all times while plant is in operation. Each room of such building shall be equipped with a line of one and one-fourth (1¼) inch pipe connected with a one and one-fourth (1¼) inch supply line leading from such high pressure boiler and having down spouts of at least two (2) inches in length and not less than ten (10) feet apart distributed over washers and extractors.

The valves operating such lines of pipe shall in every case be placed outside of such building; provided, however, that every such dry cleaning plant, constructed and maintained prior to the passage of said ordinance on July 22, 1912, may in place of such high-pressure boiler be equipped with such adequate and practical fire extinguishing system as may be approved by the Chief of Fire Prevention and Public Safety.

(f) Whenever steam power shall be used for the operation of any machinery contained in any such dry cleaning establishment, the boiler generating such power shall be located in a separate building and so situated that the line of travel for gases from the boiler and the nearest opening into the cleaning or drying room shall be not less than twenty (20) feet, and whenever electrical power is used, the electric motor furnishing such power shall be similarly located; provided, however, that such boiler and electric motor may be located in the same building where such building was used for dry cleaning purposes prior to the time of passage of said ordinance on July 22, 1912, if such boiler or electric motor is separated from the dry-cleaning or drying room by fire walls having no openings into such dry cleaning or drying room, except such openings as may be required for shafts in operating the machinery contained therein.



Union Petroleum Bldg., Argyle E. Robinson, Architect

H. B. BARNARD

BUILDING CONTRACTOR

1004-05, 140 So. Dearborn Street

Marquette Building

Phone Central 2804

CHICAGO



Midway Masonic Temple, Chicago, Ill.

Robert Hyde and Arthur Verne Brown, Architects, Chicago, Ill.

PETER OLSON COMPANY

GENERAL CONTRACTORS

Phone, Central 1920

19 S. La Salle St., **CHICAGO**

(g) Every such building shall be lighted by incandescent electric lamps having keyless sockets, protected by vapor-tight outer globes, and controlled by outside switches. No open light or flame of any kind whatsoever shall be allowed or used therein.

(h) Every such establishment shall be provided with an open tank not less than four (4) feet long, two (2) feet wide and three (3) feet deep, which shall be placed near the entrance to the dry-cleaning room and shall be kept filled with water.

(i) Every such establishment shall be equipped with an asbestos blanket of a size not less than six (6) feet by nine (9) feet; said blanket to be placed inside of the dry cleaning or benzine room near the door thereof and in such a position that it shall be easily accessible for use in case of fire.

Section 2. This ordinance shall take effect and be in force from and after its passage, approval and publication.

Passed June 25, 1917.

No. 700

ORDINANCE CONCERNING GARAGES.

AN ORDINANCE

Amending an Ordinance passed on July 17, 1911, as published in the left hand column on page 962 of the Journal for the years 1911 and 1912, in regard to the location of garages.

Be it ordained by the City Council of the City of Chicago:

Section 1. That Section 1 of an ordinance relating to garages, passed by the City Council on July 17, 1911, as published in the left hand column on page 962 of the Journal of the proceedings of the City Council of the City of Chicago for the years 1911 and 1912, as such ordinance is amended by an ordinance passed on December 7, 1914, and published on page 2393 of the Journal of the proceedings of said City Council for the years 1914 and 1915, be and the same is hereby further amended so as to read as follows:

Section 1. It shall be unlawful for any person, firm or corporation to locate, build, construct or maintain any garage within the territory bounded by the Chicago River and the south branch thereof on the north and west, by Lake Michigan on the east and by Van Buren Street on the south, any part of which is within eighty feet, or the entrance or exit to or from which, for the use of automobiles, is either within one hundred and sixty feet, of any portion of the street front of any building used as and for a hospital, church or public or parochial school, or upon a street containing street car tracks, and within one (1) block of the entrance of a street railway tunnel, or which shall house within said distance of one hundred and sixty feet of such street front, more than seventy-five cars. It shall be unlawful to locate, build, construct or maintain any garage within two hundred feet of any building used as and for a hospital, church or public or parochial school, or the ground thereof, in any portion of the City of Chicago outside of the territory above named, and it shall be unlawful for any person, firm or corporation to locate, build, construct or maintain any garage in the city on any lot in any block in which two-thirds of the buildings on both sides of the street are used exclusively for residence purposes, or within one hundred feet of any such street in any such block, without securing the written consent of a majority of the property owners according to frontage on both sides of the street as provided by

the ordinances of the City of Chicago; provided, that all lots which abut only on a public alley or court shall be considered as fronting on the street to which such alley of court leads.

Such written consent shall be obtained and filed with the Commissioner of Buildings before a permit is issued for the construction of any such building; provided, that in determining whether two-thirds of the buildings on both sides of such street are used exclusively for residence purposes, any building fronting upon another street and located upon a corner lot shall not be considered; only that part of the street in question which lies between the two nearest intersecting streets.

Secs. 2 to 7 pertain to licensing, etc.

Passed July 17, 1911.

Section 1 amended December 7, 1914.

Section 1 further amended June 29, 1917.

No. 701

AN ORDINANCE

Declaring theatres located above the first floor of buildings a nuisance: **Exception.**

Be it ordained by the City Council of the City of Chicago:

Section 1. That it shall be and it is hereby declared to be a nuisance to conduct a public theatre in a room located on any floor above the first floor level of a building of other than fireproof construction or a building which did not comply with the ordinances of the City of Chicago with reference to fireproof construction in force at the time such building was built, and that all such public theatres now being conducted in rooms on any floor above the first floor level of a building of other than fireproof construction or a building which did not comply with the ordinances of the City of Chicago with reference to fireproof construction in force at the time such building was built, with a seating capacity of more than three hundred, shall be and they are hereby declared to be nuisances; and it shall be unlawful to continue to use such rooms for public theatrical purposes whether the same are equipped with a stage and scenery or are used for moving picture shows only.

The provisions of the foregoing paragraph shall not apply where the theatre is altered so as to bring the main audience room on the first floor level and slow-burning construction is used in the reconstruction work and in making such alterations and all requirements of the ordinances of the City applying to Class IVb are complied with, nor shall said provisions apply where the following conditions are fully complied with:

(a) The building shall be used for theatre purposes only.

(b) The seating capacity shall not exceed the seating capacity at the time of passage of this ordinance.

(c) Metal scenery only shall be used; provided, however, one proscenium drop, one back drop and three borders may be used provided they are of asbestos cloth subject to the approval of the Fire Marshal.

(d) All seats shall be at least eighteen inches wide and spaced thirty-two inches from back to back.

(e) There shall be no boxes, stalls or loges.

(f) No stove or furnace heating shall be allowed.

(g) All lighting shall be by electricity; provided, however, that gas may be used in connection with exit lights.



A. & E. Anderson Company

Building Contractors

Telephones:
Randolph 3896 and 1640

927-19 S. La Salle St.
CHICAGO

Webster Apartment Hotel, Webster Avenue and Lincoln Park, Chicago
Fridstein & Co., Engineers

C. A. MOSES, Pres.

O. O. CARPENTER, Vice-Pres.

G. D. MILLER, Sec'y

C. A. Moses Construction Co.


GENERAL CONTRACTORS

1304 Chamber of Commerce Building, Chicago

Reinforced Concrete

Phone Main 3316

Industrial Buildings



Centennial Memorial Building, Springfield, Ill.

Edgar Martin, Supervising Architect

Richard E. Schmidt, Garden & Martin, Asso. Archts.

(h) At least sixty inches of exit space shall be provided for every one hundred seats.

(i) The stage shall not be more than twenty-two feet from front to rear.

(j) The audience room shall be surrounded by brick walls.

(k) In all cases where dressing rooms are placed back of the stage the brick wall shall extend between the stage and such dressing rooms, but the stage wall may contain a door leading to such dressing room located behind said wall.

(l) All dressing rooms shall have incombustible partitions and all existing wooden partitions, wherever located, shall be removed.

(m) There shall be an open space on at least three sides of the building containing such theatre, except as otherwise herein provided, which space shall be open from the floor level of the auditorium to the sky.

(n) One of such open spaces must be a public street and the others public or private alleys or open spaces leading directly to a street or public or private alley, and in all cases where such open space is private ground, it must be at least five feet wide where the seating capacity does not exceed six hundred, and six inches additional width must be provided for each one hundred seats installed in such theatre in excess of six hundred; provided, however, that in all cases where a sprinkler system is installed over the stage, together with an approved power pump and pressure tank subject to the approval of the Fire Marshal, it shall be sufficient if there are open spaces as above required on two sides of the building in which such theatre is located.

(o) Wherever the side of an audience room adjoins an open space, as hereinabove required, which open space is on private ground or is a private or public alley, there shall be a five-foot open iron platform extending the entire length of the audience room, with an open iron stairway leading to the ground from said platform at each end thereof, and in all such cases there shall be a stairway fire escape leading from the gallery of the theatre, if there is a gallery, to such platform.

(p) Where the only open space adjoining the side of the audience room is a public street, there shall be a five-foot stairway, enclosed by walls of incombustible material, leading from the middle of the audience room on the side contiguous to such street to the first floor, at the bottom of which stairway there shall be an exit opening directly to the street, and in such cases there shall be a three-foot stairway leading from the gallery, if there is a gallery, to the main floor of the auditorium, the bottom of which shall be within ten feet of the stairway leading from such main floor to the ground floor.

(q) There shall be an exit at least five feet wide on each side of the stage, which exit shall lead through a passageway constructed entirely of incombustible material to a stairway which shall be completely enclosed with incombustible material. Said stairway shall lead to the ground level and communicate through a passageway of incombustible material directly with a public street or alley or a private alley which leads directly to a public street or alley.

(r) An exit shall be provided on each side of the balcony or gallery at the end nearest the stage by means of a stairway

of incombustible material leading to the main floor of the audience room.

(s) The exits at the front of the theatre shall communicate with stairways of incombustible material leading directly to the ground level and either opening directly out upon the street or communicating with the street through fireproof passageways, and in no case shall any stairway leading from the main audience floor to the ground level communicate or connect with any other such stairway.

(t) All doors leading through the proscenium wall or from the stage to the dressing rooms shall be of incombustible material.

(u) All alterations made in buildings containing such theatres shall be of slow-burning construction, except as herein otherwise provided.

Section 2. Any person, firm or corporation that shall violate any of the provisions of this ordinance shall be fined not less than twenty-five (\$25.00) dollars nor more than two hundred (\$200.00) dollars for each offense, and each day's operation contrary to this ordinance shall be considered a distinct and separate offense.

Section 3. This ordinance shall take effect and be in force from and after its passage and due publication.

Passed July 22, 1912.

No. 702

ORDINANCE LIMITING LOCATION OF HOSPITALS.

Be it ordained by the City Council of the City of Chicago:

Section 1. That Section 1220 of The Chicago Code of 1911 be and the same is hereby amended so as to read as follows:

1220. (Location of Hospital near School or Playground.) No hospital of any kind or description shall hereafter be erected or established within four hundred feet of any property used for public or parochial school purposes or as a public playground.

Section 2. This ordinance shall take effect and be in force on and after its passage and due publication.

Passed April 29, 1912.

No. 703

Buildings, Etc., in Streets.

Be it ordained by the City Council of the City of Chicago:

Section 1. That The Chicago Code of 1911 be and the same is hereby amended by inserting after Section 2444 thereof three (3) sections numbered respectively 2444a, 2444b and 2444c, to read as follows:

2444a. **Erection of Building or Other Structure in Street Forbidden.** No person or corporation shall erect or place any building or other structure, in whole or in part, upon any street, alley, sidewalk or other public ground within the city, and every person or corporation that violates or fails to comply with any of the provisions of this section shall be fined not less than twenty-five dollars nor more than two hundred dollars.

2444b. **Obstruction Upon Streets—New Street.** The owner of any building, structure, fence, porch, steps, gallery or other obstruction now standing or which may



E. L. ARCHIBALD CO.

General Contractors

Tel. Franklin 274; Main 4920

111 W. Washington St., CHICAGO
63 Davies Bldg. DAYTON, O.


McKEOWN TRUSSES

Built of wood in spans from 3' to 13'. Afford clear floor space at lowest cost.



The McKeown "Lattis-Truss"

The standard truss of this type since 1925. Built on the job and erected by us.



The McKeown "Bowstring Truss"

Built on the job and erected by us. Or shipped in knock down ready for assembling and erecting. Estimates and advice upon request. Architects who specify McKeown Trusses assure their clients safe and satisfactory construction with no delay or risk.

McKEOWN BROTHERS COMPANY

Contractors and Engineers

Phone, Central 7950

112 West Adams St., CHICAGO

hereafter be erected or placed upon any street, alley, sidewalk or public ground within this city, or which may be left standing upon any new street that has been opened, or may hereafter be opened, shall remove the same within such reasonable time, not exceeding thirty days, as may be fixed by the Commissioner of Public Works in a written notice to be served as hereinafter provided for, but the time fixed therein shall not be less than five days after such service. Such written notice may be served upon the owner or upon the person or corporation in possession or occupancy of the premises, or by posting the written notice upon such building, structure, fence, porch, steps, gallery or other obstruction.

Any person or corporation violating any of the provisions of this section shall be fined not less than twenty-five dollars nor more than two hundred dollars, and shall be fined a further sum of ten dollars for each and every day such building, structure, fence, porch, steps, gallery or other obstruction shall remain after the expiration of the time fixed for the removal of same in the written notice given as in this section provided.

2444c. Refusal to Remove—Nuisance.) Whenever the owner of any building, structure, fence, porch, steps, gallery or other obstruction upon any street, alley, sidewalk or public ground in this city, shall refuse or neglect to remove the same, after notice served as prescribed in the preceding section, the same shall be deemed a nuisance, and the Commissioner of Public Works shall cause the same to be removed or taken down, and the expense of such removal or taking down shall be recoverable from the owner in an action of assumpsit, and every person who shall forcibly and unlawfully resist the execution of any order of the Commissioner of Public Works in the premises shall be deemed guilty of disorderly conduct and shall be subject to a penalty of not less than five dollars nor more than two hundred dollars.

Section 2. That an ordinance amending The Chicago Code of 1911 by inserting after Section 2444 three sections numbered 2444a, 2444b and 2444c, passed by the City Council of the City of Chicago on March 9, 1914, and appearing on pages 4355 and 4356 of the Journal of the Proceedings of the City Council of that date be and the same is hereby repealed.

Section 3. This ordinance shall take effect and be in force from and after its passage, approval and publication.

Ordinance passed April 27, 1914.

No. 704 AN ORDINANCE

To provide for the licensing and regulation of mason contractors and employing masons.

Be it ordained by the City Council of the City of Chicago:

Section 1. Any person, firm or corporation engaged in or desiring to engage in or work at the business of masonry or mason work, either as contractor, sub-contractor or employing mason, in the City of Chicago, shall submit to an examination and shall obtain a license as a mason contractor or employing mason in the manner hereinafter provided for; provided, that whenever a firm or corporation consists of more than one master or employing mason, it shall not be necessary for more than one member of said firm or one officer of said corporation to

undergo such examination in order to obtain a license for such firm or corporation. The words "masonry" or "mason work" as herein used shall include all work in brick, stone, concrete, terracotta, tile and fireproofing, or any combination of these materials, as used in and about the construction of buildings or structures above or below the surface of the ground, with the exception of laying brick or concrete sidewalks and brick or concrete paving.

Section 2. There is hereby created a board of examiners of mason contractors, consisting of three members, all of whom shall be practical masons, and who shall be appointed by the Mayor, by and with the advice and consent of the City Council, and their term of office shall extend until the first day of May following their appointment, and their successors shall be appointed in like manner for the term of one year annually before the first day of May. Said board shall select its own chairman. Each member of said board so appointed shall, before entering upon the duties of his office, execute a bond to the city in the sum of Five Thousand Dollars (\$5,000), with sureties to be approved by the City Council, conditioned for the faithful performance of the duties of the office to which he has been appointed. Each of the members of the said board of examiners of mason contractors shall receive such salary as may be provided therefor in the annual appropriation bill.

Section 3. The secretary to the Board of Examiners of Plumbers shall act as secretary to the said board of examiners of mason contractors. It shall be his duty to preserve and keep all of the records, books and papers, which are required by law to be kept by or filed with the said board of examiners of mason contractors, and to do and perform such other service as may be from time to time required of him by said board.

Section 4. Any person, firm or corporation desiring to procure a license as a mason contractor or employing mason shall make application to the board of examiners of mason contractors and shall, at such time and place as said board may designate, undergo such examination as to qualifications and competency to engage in any or all of the recognized branches of such business as the said board of examiners may direct. Said examination shall be made in whole or in part in writing and shall be of a practical and elementary character, sufficiently strict, to test the qualifications of the applicant. Where the applicant is a firm or corporation such applicant shall state in writing the name or names of the person or persons connected therewith who will submit to such examination as to qualifications, and in case such firm or corporation receives a license and thereafter severs its connection with such person or persons, so that no member of said firm or officer of said corporation has qualified as a mason contractor or employing mason as required by this ordinance, the license granted to such firm or corporation shall no longer be in force, and such firm or corporation shall be required to make a new application for a license in the same manner as before.

Section 5. Said board of examiners of mason contractors shall examine such applicants as to their practical knowledge of any or all of the recognized branches of masonry and mason work and of matters pertaining to mason construction and, if satisfied of the competency of any such applicant, shall thereupon issue a license to such applicant, authorizing him to engage in the business of mason contracting or employing mason in any or in all of its recognized branches, as the case may be. The fee for such examination, including the first year's license fee, shall be fifty dollars, and thereafter the annual license fee for such mason contractor or employing mason shall be twenty-five dol-



First Cavalry Armory, I. N. G.—Held and Roche, Architects

HANSON BROTHERS COMPANY

GENERAL CONTRACTORS

Telephone Central 6824

127 North Dearborn Street, Chicago



Vesta Battery Corp., Chicago

Puckey and Jenkins, Architects

S. N. NIELSEN & COMPANY

MASONRY
CARPENTRY
REINFORCED
CONCRETE

GENERAL
CONTRACTORS

Established 1893
Telephone, Nevada 323

CHICAGO

INDUSTRIAL
RESIDENTIAL
PUBLIC WORK

lars; said license shall be valid and have force for a period of one year from the date vided, and may be renewed upon its expiration by paying in advance the annual renewal fee. All fees received for said examinations and licenses shall be paid into the city treasury.

of publication, except as herein otherwise pro-

Section 6. All masonry or mason work placed in or upon or in connection with any building or structure in the City of Chicago shall be done in accordance with the ordinances regulating materials, construction, alteration and inspection of such work now or hereafter in force in the City of Chicago, and no masonry or mason work shall be done or placed in or upon or in connection with any building or structure in the city without a permit being first issued therefor by the department charged with the enforcement of the ordinances pertaining thereto; Provided, however, that nothing herein contained shall apply to any mason work being done by the City of Chicago by day labor.

In every case where any masonry or mason work forms a part of the work to be done in or upon or in connection with the construction of a building or structure for which a permit is required under the ordinances of the city, such permit shall only be issued upon the application of a person, firm or corporation licensed as a mason contractor or employing mason as provided in this ordinance, or upon an application containing a statement that all mason work on such building or structure will be performed by a properly licensed mason contractor or employing mason; and in case any mason work or any such building or structure shall be performed by any contractor or employing mason not licensed as herein provided, such permit shall be revoked, and the masonry work on such building or structure shall be stopped by order of the chief of the department charged with the enforcement of the ordinances pertaining thereto, and the person or persons performing such work and the person or persons having such work done shall be subject to the penalty herein prescribed.

Section 7. Any person, firm or corporation engaged in the business of contracting for masonry or mason work that shall fail to procure a license as herein provided for, or any person, firm or corporation that shall violate any of the provisions of this ordinance, shall be fined not less than five dollars nor more than fifty dollars for each offense, and in addition to such penalty the license of any person, firm or corporation licensed hereunder may be revoked for cause in the discretion of the Mayor.

Section 8. This ordinance shall take effect and be in force from and after its passage and due publication.

Ordinance passed January 16, 1914.

Amended November 1, 1915, and March 26, 1918.

No. 705

AN ORDINANCE

Restricting the noise of building operations at night in residential districts.

Section 1. It shall be unlawful for any person, firm or corporation, in conducting any building operations between the hours of ten o'clock in the evening and four o'clock in the morning, to operate or use any pile drivers, steam shovels, pneumatic hammers, derricks, steam or electric hoists or other apparatus, the use of which is attended with loud or unusual noise in any block in which more than half of the buildings on either side of the street are used exclusively for residence purposes.

Section 2. Any person, firm or corporation violating any of the provisions of Section 1 hereof shall be fined not less than five dollars, nor more than one hundred dollars for each offense, and each day's violation of same shall be considered a separate offense.

Section 3. This ordinance shall take effect and be in force from and after its passage and due publication.

Ordinance passed November 13, 1911.

No. 706

Contractors for Buildings—Requiring Registration with Commissioner of Buildings.

Section 1. That every person, firm, company or corporation engaged in the business of constructing or repairing the whole or any part of buildings or the appurtenances thereto in the City of Chicago, shall before undertaking the erection, enlargement, alteration, repair or removal of any building, for which permits are required by the ordinances of the City, register the name and address of such person, firm, company or corporation in a book kept by the Commissioner of Buildings and used for this purpose.

No permit shall be granted to any person, firm, company or corporation for the erection, enlargement, alteration, repair or removal of any building in the City for which a permit is required unless the name and address of the person, firm, company or corporation undertaking the work of construction involved in the erection, enlargement, alteration, repair or removal of such building is contained in the registration book kept by the Commissioner of Buildings.

When application is made for a permit and the work of construction involves masonry construction only the above provisions shall not apply to any person, firm or corporation licensed as a mason contractor or employing mason as provided in and by an ordinance passed by the City Council on January 16, 1914, as amended on March 9, 1914. Where the work of construction for which a permit is sought involves construction other than masonry construction, any mason contractor or employing mason, licensed as aforesaid, engaged in or undertaking the work of such other construction than masonry construction must register his, their or its name or names and comply with the other requirements of this ordinance as herein provided before a permit as required by the ordinances of the City for such work is issued.

Section 2. If any person, firm, company or corporation whose name is registered in the registration book kept by the Commissioner of Buildings, shall fail in the execution of any work for which a permit was issued as aforesaid to comply with the ordinances of the City relative to the erection, enlargement, alteration, repair or removal of any building, either the Commissioner of Buildings or the Commissioner of Health may, according to the ordinances of the City of Chicago, bring suit and prosecute said person, firm, company or corporation for such failure or violation, and if such person, firm, company or corporation is convicted of any violation of the said ordinances of the City of Chicago, his, their or its name or names shall be stricken from the registration book kept by the Commissioner of Buildings and shall not be re-entered or reinstated during such time as any violation exists or any judgment remains unsatisfied with regard to said conviction.

Section 3. Any person, firm, company or corporation that may have been convicted of violating any of the ordinances relating to the erection, enlargement, alteration, re-



Lafayette Memorial Hospital, Hall & Keller, Inc. Hartman & Steinbach, Architects

HENRY MENKE

R. W. MENKE

HENRY MENKE CO. GENERAL CONTRACTORS

Masonry

Carpentry

Concrete Work

Office, 2nd Floor, 2028-31 W. Lake St.

CHICAGO

Phone West 55-7



Continental Tire Co., 7574 Cottage Grove St. Lazard & Knapp, Architects

MASONRY
CONCRETE

PHONE STITE 6797

CARPENTRY
Building Alterations

ARDMORE CONSTRUCTION CO.

A. FREMONT OLSEN, PRES.

CONTRACTORS

Room 607, 186 N. LaSalle St.

CHICAGO, ILL.

pair or removal of any building that may have had his, their, or its name or names stricken from the registration book kept by the Commissioner of Buildings as aforesaid, may have his, their or its name or names re-entered in said registration book for the purpose of obtaining building permits, on filing with the Commissioner of Buildings certificates from the City Prosecutor, the Commissioner of Buildings and the Commissioner of Health to the effect that all violations upon the premises with reference to which conviction was secured, have been corrected and are non-existent and that all claims and judgments with regard to such conviction have been paid.

Section 4. This ordinance shall be in full force and effect from and after its passage and due publication.

No. 707

AN ORDINANCE.

Section 1. That Chapter XXVI of The Chicago Code of 1911 be and the same is hereby amended by adding thereto a section which shall be known as Section 1450½ in the words and figures following:

Workmen's Temporary Closets.) It shall be unlawful for the owner of any building or any person, firm or corporation employing or in charge of any men to begin the construction, alteration or repair of any building, or the construction of any public or private works without having provided proper and sufficient toilet facilities, viz, water-closets, chemical closets, privies, or incinerators of a type approved by the Commissioner of Health for the use of all employees engaged in the construction, alteration or repair such building, or the construction of any public or private works.

There shall be at least one such water-closet, chemical closet, privy or incinerator for every thirty (30) employees or a fraction thereof. Such toilet facilities in due proportion shall be provided on at least every fifth floor of a building.

It shall be unlawful to install such water closets, chemical closets, privies or incinerators without having first applied for and obtained a permit issued by the Commissioner of Health, and they shall be installed and maintained in accordance with the provisions of such permit.

A chemical closet shall be construed to be any closet or privy in which human excreta and urine are deposited in a receptacle containing a solution of caustic hydrates. The receptacle in such a closet shall be water tight. The capacity of such receptacles shall be as follows:

	Gallons
For 10 persons or less.....	60
For 20 persons or less.....	100
For 40 persons or less.....	300

"A solution containing at least 16.42 per cent crude caustic hydrates (12-3 lbs. to 1 gallon of water) shall be used in such receptacles, and such chemical closets charged with such a solution.

The contents of such chemical closets shall be removed and disposed of by a regularly licensed night soil scavenger, in compliance with the requirements of Sections 1444, 1445, 1446 and 1450 to 1455 of The Chicago Code of 1911 and as amended. Every such closet shall be cleaned before being removed from one premises to another and as often otherwise as may be deemed necessary by the Commissioner of Health.

Penalty.) Any person, firm or corporation violating any of the provisions of this sec-

tion shall be fined not less than Ten Dollars (\$10.00) nor more than One Hundred Dollars (\$100.00) for each offense."

Section 2. This ordinance shall be in full force and effect from and after its due passage, approval and publication.

Passed July 10, 1916.

No. 708

Ice-Making or Cooling Plants: Location Restricted.

AN ORDINANCE

Amending Article II of Chapter LXXI of The Chicago Code of 1911.

Be It Ordained by the City Council of the City of Chicago:

Section 1. That Article II of Chapter LXXI of The Chicago Code of 1911 be, and the same is hereby, amended by inserting therein a new section to be known as "2414½," after Section 2414 and before Section 2415, as follows:

"**2414½. Location of Ice-Making Houses and Cooling Plants.)** It shall be unlawful for any person, firm or corporation to locate, establish, conduct or maintain any ice-making house or cooling plant within four hundred (400) feet of any church, hospital, public or parochial school, said distance to be measured by the shortest straight line between the ice-making house or cooling plant sought to be so located, established, conducted or maintained, and any such building used for the purpose of a church, hospital, public or parochial school."

Section 2. This ordinance shall take effect and be in force from and after its passage and due publication.

Passed December 30, 1912.

No. 709

Ice-Making or Cooling Plants: Frontage Consent Requirement.

Be It Ordained by the City Council of the City of Chicago:

Section 1. It shall be unlawful for any person, firm or corporation to locate, establish, conduct or maintain any ice-making house or cooling plant in any block in which two-thirds of the buildings fronting on both sides of the street on which the proposed plant shall be located are devoted exclusively to residence purposes unless the owners of the majority of the frontage in said block on both sides of the street on which said plant is located shall consent in writing to the location, establishment, conducting or maintenance of such plant in such block. Such written consents of the majority of said property owners shall be filed with the Commissioner of Buildings before a permit shall be granted for the building or constructing of any such ice-making house or cooling plant.

Section 2. Any person, firm or corporation violating any of the provisions of this article, or refusing, failing or neglecting to comply with any of the said provisions, shall be fined not less than \$5.00 nor more than \$100.00 for each offense, and a separate offense shall be regarded as having been committed for each day during which such violation shall continue.

Section 3. This ordinance shall take effect and be in force from and after its passage and due publication.

Passed January 8, 1913.

Telephone Main 4266

A. J. Samuelson

*General Contractor
and Builder*

189 West Madison St.

CHICAGO, ILLINOIS

CENTRAL 8345



HENRY ERICSSON COMPANY

GENERAL CONTRACTORS

CITY HALL SQUARE BLDG.

CHICAGO

No. 710**Restriction on the Location of Foundries, Machine Shops and Factories Wherein Pneumatic Hammers and Similar Devices are Used.**

Be It Ordained by the City Council of the City of Chicago:

Section 1. It shall be unlawful for any person, firm or corporation to locate, build, construct, or maintain a foundry, machine shop or factory wherein pneumatic hammers or other apparatus, the use of which is attended with loud or unusual noises, are used within two hundred (200) feet of any residence.

Section 2. Any person, firm or corporation violating any of the provisions of Section 1 hereof shall be fined not less than \$25.00 nor more than \$100.00 for each offense, and each day's violation shall be considered a separate offense.

Section 3. This ordinance shall take effect from and after its passage and due publication.

Passed December 8, 1919.

No. 711**AN ORDINANCE**

Providing that no Plans be Approved and that no Permit be Issued by the Commissioner of Buildings for the Construction, Enlargement, Etc., of any Building on any Tract, Lot or Parcel of Land, Unless Same Shall be Provided with Adequate Drains.

Be It Ordained by the City Council of the City of Chicago:

Section 1. No plans shall be approved and no permit shall hereafter be issued by the Commissioner of Buildings for the construction, enlargement, altering, repair or removal of any building on any tract, lot or parcel of land, unless such tract, lot or parcel of land shall be provided with adequate drains connecting with or emptying into a public drain or sewer in accordance with the general ordinances of the City or unless proceedings shall have been instituted to provide such drain or sewer.

Section 2. This ordinance shall be in force from and after its passage.

Passed June 11, 1917.

No. 712**AN ORDINANCE**

Creating a Zoning Commission and Defining Its Powers and Duties.

Be It Ordained by the City Council of the City of Chicago:

Section 1. That there be, and there is hereby, created a Commission consisting of twenty-two members, to be known as the Zoning Commission. The said Commission shall consist of the Commissioner of Buildings, the President of the Board of Local Improvements, the Commissioner of Health, the Corporation Counsel, the Chairman of the Chicago Plan Commission, the Chairman of the Committee on Buildings and City Hall of the City Council, the Chairman of the Committee on Local Industries of the City Council, six Aldermen in addition to the chairmen of said committees to be named by the Mayor and nine additional members holding no other office or employment in the City government to be appointed by the Mayor with the approval of the City Council. The Mayor shall appoint a member of such Commission as the chairman thereof. The powers and duties of such Commission shall cease upon the adoption by the City Council of the final

report of such Commission hereinafter provided for.

The officers of the City, who are hereby made ex-officio members of said Commission, shall receive no extra compensation for their services as such, and the other member shall serve without compensation.

Section 2. The said Zoning Commission shall have the following powers:

1. To employ a competent zoning expert or experts and an adequate staff, and such other employes as may be essential for the purpose of making all surveys, investigations, computations, maps, the compiling of statistics and collection of data and information necessary or expedient for the preparation of the reports hereinafter provided for and of an ordinance or ordinances in pursuance of powers granted to the City Council in an Act of the General Assembly of the State of Illinois passed June 28, 1919, in force July 1, 1919, entitled, "An Act to confer certain additional powers upon city councils in cities and presidents and boards of trustees in villages concerning buildings, the intensity of use of lot areas, the classification of buildings, trades and industries with respect to location and regulation, the creation of residential, industrial, commercial and other districts, and the exclusion from and regulation within such districts of classes of buildings, trades and industries," and amendments thereof, or substitutes therefor.

2. To arrange for, conduct and hold preliminary public hearings upon the subject matter of proposed districting for the purpose of informing and aiding said Commission in the preparation of its surveys, reports and maps, as herein provided for. Notice of such preliminary public hearing or hearings may be given by publication or otherwise, in such manner as said Commission may determine, and the same, together with the times and places of holding the same, and the procedure therefor, shall be determined by regulations to be adopted by said Commission.

3. To cause to be published from time to time whenever the Commission deems proper such maps, books, pamphlets, circulars, papers, or other matters as will inform the City Council and the other officers of the City and the general public of the progress made in the work of districting the City in accordance with the provisions of this ordinance.

4. To make and publish a tentative report, with proposed ordinance or ordinances and maps, to the City Council, covering the zoning of the entire city, which, after consideration by the City Council, shall be returned to such Commission with its suggestions and recommendations. The Commission shall then proceed to formulate and publish a final report with ordinance or ordinances and maps covering the zoning of the entire City, which shall be returned to the City Council, all in accordance with the spirit and intent of said statute, to the end that wide publicity may be given before the enactment of any ordinance creating such districts.

5. To prepare and submit with said final report to the City Council an ordinance or ordinances to carry into effect the said final report, making classifications of districts for purposes of regulation, limitation and restriction of buildings and uses of same therein, describing fully each kind of district and defining the terms used with reference to same, and establishing within the City districts of one or more of the various classes so specified, and defining the limits of each of such districts; also to include in such ordinance or ordinances any special regulations that the said Commission may deem necessary or desirable in any particular district or case.



Russell Bldg., Chicago

Chatten & Hammond, Archts., Chicago

Phone: State 6330

E. P. Strandberg Co. Builders

1809 Conway Building

CHICAGO



Surf Apartment
Hotel

Pine Grove Ave.
and Surf St.
Chicago

H. R. Wilson
& Co., Archts.

John A. Armstrong
Successor
Chicago



E.V. Johnson Co.

Fireproof Building Construction, Reinforced
Concrete and Hollow Tile Structures

20 West Jackson Boulevard
Phone, Harrison 5320

CHICAGO, ILL.

Section 3. In addition to performing the functions necessary to carry into effect the powers enumerated in Section 2 hereof, the said Zoning Commission shall have the following duties:

1. To provide for a public hearing and speedy consideration of any such ordinance coming within the provisions of the statute hereinbefore mentioned, which the City Council directs the Commission to consider; and the President of the Board of Local Improvements is hereby designated as the member of said Commission and officer who shall cause the publication to be made and the notices to be given and posted, concerning such public hearing or hearings as provided for in said statute hereinbefore mentioned.

2. To hear and consider the objections, if any, to any such formally proposed ordinance or ordinances, and to make a report and recommendation concerning such ordinance or ordinances as promptly as the circumstances will permit.

3. To perform all other functions in and about the preparation and submission of districting ordinances, the filing and consideration of objections thereto, the alteration of same, or any other proceeding in relation thereto prescribed by statute which is not by law reserved to the City Council itself.

Section 4. Whenever the said Zoning Commission shall report to the City Council a proposed ordinance which has been considered at a formal public hearing or hearings held pursuant to publication and notice of the time and place of such hearing or hearings, as provided by the statute hereinbefore mentioned, establishing within the City any district or districts as herein provided, within a recommendation that such ordinance should be enacted into law, in case there is any written objection filed thereto within the time and in the manner prescribed by statute, the said ordinance and the objection thereto shall forthwith be returned to said Commission for such further action as may be required by law; but in case no such objection is so filed within the time limited by statute, the said ordinance may be taken up for final passage by the City Council, provided, that in case such ordinance is amended by the City Council it shall again be referred to said Commission to take such action thereon as may be required by law.

Section 5. This ordinance shall take effect and be in force from and after its passage and approval.

Passed February 18, 1920.

Note:—See ordinance directing the withholding of building permits in certain restricted districts pending the passage of a zoning ordinance (passed July 21, 1919, amended Sept. 9, 1919), page 279.

Fire-limit Areas: Temporary Exclusion of the Territory Bounded by W. 45th St., S. Western Avenue Boul. W. 55th St., S. Central Park Av., W. 65th St. and the City Limits.

Be it ordained by the City Council of the City of Chicago:

Section 1. That Section 695 of The Chicago Code of 1911, as amended, be and the same is hereby further amended by adding thereto the following paragraph:

"That the territory described as follows: Commencing at the intersection of the center line of 45th street with the western city limits of the City of Chicago, thence east along the center line of 45th street and 45th street extended to the intersection of the center line of 45th street with the center line of South Western Avenue boulevard, thence south along the center line of South Western Avenue boulevard to a point in Gage Park, where the center line of South

Western boulevard extended intersects with the center line of 55th street extended, thence west to the center line of South Central Park avenue, thence south along the center line of South Central Park avenue to the center line of 65th street, thence west along the center line of 65th street and 65th street to the Western City Limits of the City of Chicago, thence along said City Limits to the place of beginning, shall be, and the same is hereby excluded from the fire limits of the City of Chicago, as hereinbefore set forth, for a period of one year from and after July 1, 1921, provided, however, that during such period it shall be unlawful to erect within said territory any buildings costing less than twenty-five hundred dollars (\$2500.00), except garages built on the rear of the lots of such territory."

Section 2. This ordinance shall be in full force and effect from and after its passage and due publication.

Passed June 28, 1921.

Fire-limit Areas: Temporary Exclusion of the Territory Bounded by E. 95th St., S. State St., B. & O. R. R. and C. & W. I. R. R.

Be it ordained by the City Council of the City of Chicago:

Section 1. That Section 695 of The Chicago Code of 1911, as amended, be and the same is hereby further amended by adding thereto the following paragraph:

"The territory bounded on the south by East 95th street, on the east by South State street, on the north by the right of way of the Baltimore and Ohio Railroad Company, and on the west by the right of way of the Chicago and Western Indiana Railroad Company, shall be, and the same is hereby excluded from the fire limits of the City of Chicago, as hereinbefore set forth, for a period of one year from and after July 1st, 1921; provided, however, that, during such period it shall be unlawful to erect within said territory any buildings costing less than twenty-five hundred dollars (\$2500.00), except garages built on the rear of the lots of such territory."

Section 2. This ordinance shall be in full force and effect from and after its passage and due publication.

Passed June 28, 1921.


Be it ordained by the City Council of the City of Chicago:

Section 1. That Section 695 of The Chicago Code of 1911, as amended, be and the same is hereby further amended by adding thereto the following paragraph:

"The territory bounded on the south by West 115th street, on the east by South Western avenue, on the north by West 99th street, and on the west by South California avenue, also the territory bounded on the south by West 95th street, on the east by Stewart avenue, on the north by West 90th place, and on the west by the right of way of the Chicago, Rock Island and Pacific Railroad Company; also the territory bounded on the south by West 87th street, on the east by South Western avenue, on the north by West 83rd street, and on the west by South Albany avenue, shall be, and the same are hereby excluded from the fire limits of the City of Chicago, as hereinbefore set forth, for a period of one year from and after August 1, 1921; provided, however, that, during such period it shall be unlawful to erect within said territories any buildings costing less than twenty-five hundred (\$2,500.00) dollars, except garages built on the rear of the lots of said territories."

Section 2. This ordinance shall be in full force and effect from and after its passage and due publication.

Passed July 22, 1921.



Jos. T. Ryerson & Son's Bldg.

Holabird & Roche Architects

GEORGE THOMSON & SON CO. BUILDING CONSTRUCTION

34 North La Salle Street

Tel. Franklin 4316

CHICAGO

HENRY L. APPEL

PRES. AND MGR.

A. W. APPEL

VICE PRES.

HENRY T. HESS

SECV.

HENRY L. APPEL CO. GENERAL CONTRACTORS

Telephone Diversey 1620

931 W. North Avenue

CHICAGO

Special Rulings of the Building Department of the City of Chicago

These rulings are not a part of the Code of the City of Chicago; but are requirements of the Building Department.

BRACING OF TRUSSES, COLUMNS, WALLS, ETC., IN STEEL SKELETON CONSTRUCTION.

I

In regard to Section 555 of the Revised Building Ordinances, the Commissioner has ruled that the following interpretation shall be placed upon the section concerning bracing:

(a) All skeleton buildings, trusses, and structures shall be securely braced during erection by guys, cables or such other temporary supports as may be necessary to provide for stresses due to erection.

(b) Special wind bracing shall be provided in steel skeleton buildings over one hundred (100) feet in height or higher than twice the least width. Whenever it is impossible to avoid rivets being in tension to resist such wind stresses, the same shall be assumed at three-fourths ($\frac{3}{4}$) the resisting value of the rivet in single shear.

(c) For permanent construction bracing shall be of the same material as the structure itself and it shall be so designed that the skeleton will be self-supporting and safe against lateral and buckling or crippling forces before any of the inclosing walls or roofs are built in place.

(d) In cases where wind forces are nominal and to prevent buckling or crippling, the minimum amount of bracing required shall be $\frac{3}{4}$ " rod for steel tension members or equivalent in other material. Compression members shall be limited in length to one hundred and fifty (150) times the least radius of gyration or otherwise as specified in the Ordinances.

(e) Trusses shall be properly anchored to the walls at the point of bearing in such a way as not to strain the masonry on account of the temperature stresses in the truss.

(f) In general, all eccentric loading on the foundations shall be avoided and where not possible to do so, proper bracing between opposite walls shall be provided, sufficient to offset the bending moment due to eccentricity.

NOTES ON REINFORCED CONCRETE DESIGN.

II

(a) In regard to Section 537, as applying to a combination of tile and concrete construction, the Commissioner has ruled that the width of flange of the concrete joists may be assumed as the full distance c. to c. of ribs but not exceeding eight (8) times the thickness of the concrete on top of tile fillers, plus the average width of rib.

(b) In computing the shear at supports, the average width of the concrete rib plus the thickness of the tile on one side of the rib may be figured as the effective width of joist, provided that joints in tile are properly staggered.

(c) When steel or plaster fillers are used between concrete joists, the width of flange shall be limited to three-fourths ($\frac{3}{4}$) of the distance center to center of ribs as per Section 537.

In regard to Section 534 (c)

(a) When compression is applied to a surface of concrete of at least twice the loaded area, a stress of thirty (30) per cent of the ultimate may be allowed, and

(b) In continuous beams and girders the compressive stress in extreme fibre at the support may be fifteen (15) per cent greater than at the center of span.

In regard to Section 536 (1)

The total amount of steel required for square slabs with two-way reinforcement may be reduced twenty (20) per cent by gradually increasing the rod spacing from the third point to the edge of the slab.

THE DESIGN OF FLAT SLABS SHALL BE IN ACCORDANCE WITH THE FOLLOWING RULING.

III

Definitions.

(1) Flat slabs as understood by this ruling are reinforced concrete slabs, supported directly on reinforced columns with or without plates or capitals at the top, the whole construction being hingeless and monolithic without any visible beams or girders. The construction may be such as to admit the use of hollow panels in the ceiling or smooth ceiling with depressed panels in the floor.

(2) The column capital shall be defined as the gradual flaring out of the top of the column without any marked offset.

(3) The drop panel shall be defined as a square or rectangular depression around the column capital extending below the slab adjacent to it.

(4) The panel length shall be defined as the distance center to center of columns of the side of a square panel, or the average distance center to center of columns of the long and short sides of a rectangular panel.

Columns.

(5) The least dimension of any concrete column shall be not less than one-twelfth ($\frac{1}{12}$) the panel length, nor one-twelfth ($\frac{1}{12}$) the clear height of the column.

Slab Thickness.

(6) The minimum total thickness of the slab in inches shall be determined by the

$$\text{formula: } t = \frac{W \frac{1}{2}}{44} = \text{square root of } W \text{ di-}$$

vided by forty-four, where t = total thickness of slab in inches, W = total live and dead load in pounds on the panel, measured center to center of columns.

(7) In no case shall the thickness be less than one thirty-second of the panel length ($L/32$) for floors, nor one-fortieth of the panel length ($L/40$) for roofs, (L being the distance center to center of columns).

(8) In no case shall the thickness of slab be less than six inches (6") for floors or roofs.



C. RASMUSSEN BUILDING CONSTRUCTION

154 W. RANDOLPH ST.

Phone Franklin 4695

CHICAGO



Versailes Apartment Hotel, Chicago. E. E. Hall, Architect

Telephone, State 5577

Mark Salomon, Pres.

C. Waterton, Sec'y and Treas.

Salomon- Waterton Co.

GENERAL CONTRACTORS

35 South Dearborn Street
CHICAGO

Column Capital.

(9) When used the diameter of the column capital shall be measured where its vertical thickness is at least one and one-half inches ($1\frac{1}{2}$ "), and shall be at least two hundred and twenty-five thousandths (.225) of the panel length.

The slope of the column capital shall nowhere make an angle with the vertical of more than forty-five degrees. Special attention shall be given to the design of the column capital in considering eccentric loads, and the effect of wind upon the structure.

Drop Panel.

(10) When used, the drop panel shall be square or circular for square panels and rectangular or elliptical for oblong panels.

(11) The length of the drop shall not be less than one-third of the panel length ($L/3$) if square, and not less than one-third of the long or short side of the panel respectively, if rectangular.

(12) The depth of the drop panel shall be determined by computing it as a beam, using the negative moment over the column capital specified elsewhere in this ruling.

(13) In no case, however, shall the dimensions of the drop panel be less than required for punching shear along its perimeter, using the allowable unit shearing stresses specified below.

Shearing Stresses.

(14) The allowable unit punching shear on the perimeter of the column capital shall be three-fiftieths ($3/50$) of the ultimate compressive strength of the concrete as given in section 533 of the building ordinance. The allowable unit shear on the perimeter of the drop panel shall be three one-hundredths ($3/100$) of the ultimate compressive strength of the concrete. In computing shearing stress for the purpose of determining the resistance to diagonal tension the method specified by the ordinance shall be used.

Panel Strips.

(15) For the purpose of establishing the bending moments and the resisting moments of a square panel, the panel shall be divided into strips known as strip A and strip B. Strip A shall include the reinforcement and slab in a width extending from the center line of the columns for a distance each side of this center line equal to one-quarter ($\frac{1}{4}$) of the panel length. Strip B shall include the reinforcement and slab in the half width remaining in the center of the panel. At right angles to these strips, the panel shall be divided into similar strips A and B, having the same widths and relations to the center line of the columns as the above strips. These strips shall be for designing purposes only, and are not intended as the boundary lines of any bands of steel used.

(16) These strips shall apply to the system of reinforcement in which the reinforcing bars are placed parallel and at right angles to the center line of the columns, hereinafter known as the two-way system, and also to the system of reinforcement in which the reinforcing bars are placed parallel, at right angles to and diagonal to the center line of the columns hereinafter known as the four-way system.

(17) Any other system of reinforcement in which the reinforcing bars are placed in circular, concentric rings and radial bars, or systems with steel rods arranged in any manner, whatsoever, shall comply with the requirements of either the two-way or the four-way system herein specified.

Bending Moment Coefficients, Interior Panel, Two-way System.

(18) In panels where standard drops and column capitals are used as above specified, the negative bending moment taken at a cross-section of each strip A at the edge of the column capital or over it, shall be taken

$$\text{as } \frac{WL}{30}$$

(19) The positive bending moment taken at a cross-section of each strip A midway between column centers, shall be taken as

$$\frac{WL}{60}$$

(20) The positive bending moment taken at a cross-section of each strip B in the

$$\text{middle of the panel shall be taken as } \frac{WL}{120}$$

(21) The negative bending moment taken at a cross-section of each strip B on the center line of the columns shall be taken as

$$\frac{WL}{120}$$

(22) In the formulas hereinabove given

"W" = total live and dead load on the whole panel in pounds,

"L" = panel length, center to center of columns.

Bending Moment Coefficients, Interior Panel, Four-way System.

(23) In panels where standard drops and column capitals are used as above specified, the negative bending moment taken at a cross-section of each strip A at the edge of column capital or over it, shall be taken as

$$\frac{WL}{30}$$

(24) The positive bending moment taken at a cross-section of each strip A, midway between column centers shall be taken as

$$\frac{WL}{80}$$

(25) The positive bending moment taken at a cross-section of each strip, B, taken in the middle of the panel shall be taken as

$$\frac{WL}{120}$$

(26) The negative bending moment taken at a cross-section of each strip B on the center line of the columns shall be taken as

$$\frac{WL}{120}$$

Bending Moment Coefficients, Wall Panels.

(27) Where wall panels with standard drops and capitals are carried by columns and girders built in walls, as in skeleton construction, the same coefficients shall be used as for an interior panel, except as follows: The positive bending moments on strips A and B midway between wall and first line of columns shall be increased twenty-five (25%) per cent.

(28) Where wall panels are carried on new brick walls, these shall be laid in Port-



Hyatt Office Building, Detroit, Mich., 60x95 ft. reinforced concrete building moved a distance of 450 feet. One of the recent operations of

L. P. FRIESTEDT CO.

BUILDING ENGINEERS

RAISING MOVING SHORING

Contracts Taken Anywhere in the United States. *Work Guaranteed.*

General Offices: 1638 TRIBUNE BLDG. Tel. Randolph 296-297

New York, N. Y.

CHICAGO, ILLINOIS

Detroit, Mich.

QUANTITY

QUALITY

SERVICE

AMERICAN SAND & GRAVEL COMPANY

YEARLY OUTPUT

TWO MILLION YARDS

22 City Delivery Yards—Five Docks

CAR, BOAT and TRUCK DELIVERY

GENERAL OFFICES

905-909 Chamber of Commerce Bldg.
Chicago, Illinois

PHONE FRANKLIN 366

Private Exchange
All Departments

land cement mortar and shall be stiffened with pilasters as follows. If a sixteen-inch wall is used, it shall have a four-inch pilaster. If a twelve-inch wall is used, it shall have an eight-inch pilaster. The length of pilasters shall be not less than the diameter of the column, nor less than one-eighth ($\frac{1}{8}$) of the distance between pilasters. The pilasters shall be located opposite the columns as nearly as practicable, and shall be corbeled out four inches at the top, starting at the level of the base of the column capital. Not less than eight (8") inches bearing shall be provided for the slab, the full length of wall.

The coefficients of bending moments required for these panels shall be the same as those for the interior panels except as provided herewith: The positive bending moments on strips A and B midway between the wall and first line of columns shall be increased fifty (50%) per cent.

(29) Where wall panels are supported on old brick walls, there shall be columns with standard drops and capitals built against the wall which shall be tied to the same in an approved manner, and at least an eight-inch bearing provided for the slab, the full length. Where this is impracticable, there shall be built a beam on the underside of slab adjacent to the wall between columns, strong enough to carry twenty-five (25%) per cent. of the panel load.

The coefficients of bending moments for the two cases of slab support herein described shall be the same as those specified in Sec. 27 and Sec. 28 for skeleton and wall bearing condition respectively.

(30) Nothing specified above shall be construed as applying to a case of slabs merely resting on walls or ledges, without any condition of restraint. These shall be figured as in ordinary beam and girder construction specified in the Ordinances.

Bending Moment Coefficients, Wall and Interior Columns.

(31) Wall columns in skeleton construction shall be designed to resist a bending mo-

ment of $\frac{WL}{60}$ at floors and $\frac{WL}{30}$ at roof. The

amount of steel required for this moment shall be independent of that required to carry the direct load. It shall be placed as near the surface of the column as practicable on the tension sides, and the rods shall be continuous in crossing from one side to another. The length of rods below the base of the capital and above the floor line shall be sufficient to develop their strength through bond, but not less than forty (40) diameters, nor less than one-third ($\frac{1}{3}$) the clear height between the floor line and the base of the column capital.

(32) The interior columns must be analyzed for the worst condition of unbalanced loading. It is the intention of this ruling to cover ordinary cases of eccentric loads on the columns by the requirement of Sec. 5. Where the minimum size of column therein specified is found insufficient, however, the effect of the resulting bending moment shall be properly divided between the adjoining slab and the columns above and below according to best principles of mechanics and the columns enlarged sufficiently to carry the load safely.

Bending Moment Coefficients, Panels Without Drops, or Capitals, or Both.

(33) In square panels where no column capital or no depressions are used, the sum total of positive and negative bending mo-

ments shall be equal to that computed by the following formula:

$$B.M. = \frac{WL}{8} (1.53 - 4k + 4.18k^2)$$

where B.M. = numerical sum of positive and negative bending moments, regardless of algebraic signs.

W = total live and dead load on the whole panel.

L = length of side of a square panel, c. to c. of columns.

K = ratio of the radius of the column or column capital to panel length, L.

This total bending moment shall be divided between the positive and the negative moments in the same proportion as in the typical square panels for two-way or four-way systems specified above for interior and wall panels respectively.

Points of Inflection.

(34) For the purpose of making the calculations of the bending moment at the sections away from the column capitals, the point of inflection shall be considered as being one-quarter ($\frac{1}{4}$) the distance center to center of columns, both cross-wise and diagonally, from the center of the column.

Tensile Stress in Steel and Compressive Stress in Concrete.

(35) The tensile stress in steel and the compressive stress in the concrete to resist the bending moment shall be calculated on the basis of the reinforcement and slab in the width included in a given strip, and according to the assumption and requirements given in sections 532 to 535 inclusive of the building ordinance.

The steel shall be considered as being concentrated at the center of gravity of all the bands of steel in a given strip.

(36) For the four-way system of reinforcement the amount of steel to resist the negative bending moment over the support in each strip A shall be taken as the sum of the areas of steel in one cross band and one diagonal band. The amount of steel to resist the positive bending moment of each strip B shall be considered as the area of the steel in a diagonal band. The amount of steel to resist the positive bending moment in each strip A shall be considered as the area of the steel in a cross-band, and the amount of steel to resist the negative moment in each strip B shall be the steel included in the width of strip B.

(37) For the two-way system of reinforcement the amount of steel to resist the bending moment in any strip shall be considered as the area of steel included in the width of the strip.

(38) In both systems of reinforcement the compressive stress in the concrete in any strip shall be calculated by taking the area of steel considered for each strip, and applying it in a beam formula based on the principles of section 535 of the building ordinance.

(39) Where drop panels are used, the width of beam assumed to resist the compressive stresses over the column capital shall be the width of the drop.

(40) The width of beam where no drop panels are used, shall be the width of steel bands. Where this is found insufficient, the area shall be increased by introducing compression steel in the bottom of slab.

WILLIAM MAVOR COMPANY

CONTRACTORS AND BUILDERS

7 SOUTH DEARBORN ST.

CHICAGO

JOHN MAVOR, PRES.
MORTON R. MAVOR, SEC'Y
HUGH N. MAVOR, TREAS.

TELEPHONE
CENTRAL 2435

A. C. THIELBERG

HENRY SCHAEPPI

A. C. THIELBERG

GENERAL
CONTRACTOR

154 W. RANDOLPH ST., CHICAGO

PHONE MAIN 3849

ROOM 592

B. J. REGNELL, Pres. and Treas.

J. A. REGNELL, Vice-Pres.

A. V. REGNELL, Secy.

B. J. REGNELL CO.

Carpenters and General
Contractors

Telephones—Offices: Randolph 480 and State 7990

19 SOUTH LA SALLE STREET, CHICAGO

Phone Randolph 5920

AUSTIN J. LYNCH CO.

BUILDERS

622 HARRIS TRUST BUILDING, CHICAGO

Rectangular Panels.

(41) When the length of panel in either two-way or four-way system does not exceed the breadth by more than five (5%) per cent, all computations shall be based on a square panel whose side equals the mean of the length and breadth, and the steel equally distributed among the strips according to the coefficients above specified.

(42) In no rectangular panel shall the length exceed the breadth by more than one-third ($1/3$) of the latter.

Rectangular Panels, Four-Way System.

(43) In the four-way system of reinforcement where length exceeds breadth by more than five (5%) per cent, the amount of steel required in strip A, long direction, both positive and negative, shall be the same as that required for the same strip in a square whose length is equal to the long side of the rectangular panel.

(44) The amount of steel, strip A, short direction, positive and negative, shall be the same as that required for the same strip in a square panel, whose length is equal to the short side of the rectangular panel.

(45) The amount of steel in strip B, positive and negative, shall be the same as that required for similar strip in a square panel whose length is equal to the mean of the long and the short side of the rectangular panel.

(46) In no case shall the amount of steel in the short side be less than two-thirds ($2/3$) of that required for the long side.

Rectangular Panels, Two-way System.

(47) In the two-way system of reinforcement the amount of steel required for the positive and the negative moment of each strip A shall be determined in the same manner as indicated for the four-way system above.

(48) The amount of steel in strip B, positive and negative, running in short direction, shall be equal to that required for the same strip in a square panel whose length equals the long side of the rectangular panel.

(49) The amount of steel in strip B, long direction, positive and negative, shall be equal to that required for the same strip in a square panel, whose length equals the short side of the rectangular panel.

(50) In no case shall the amount of steel in strip B, long direction, be less than two-thirds ($2/3$) of that in the short direction.

Walls and Openings.

(51) Girders and beams shall be constructed under walls, around openings and to carry concentrated loads.

Spandrel Beams.

(52) The spandrel beams or girders shall, in addition to their own weight and the weight of the spandrel wall, be assumed to carry twenty (20%) per cent of the wall panel load uniformly distributed upon them.

Placing of Steel.

(53) In order that the slab bars shall be maintained in the position shown in the design during the work of pouring the slab, spacers and supports shall be provided satisfactory to the Commissioner of Buildings. All bars shall be secured in place at intersections by wire or other metal fastenings. In no case shall the spacing of the bars exceed nine inches (9"). The steel to resist

the negative moment in each strip B shall extend one-quarter ($1/4$) of the panel length beyond the center line of the columns in both directions.

(54) Splices in bars may be made wherever convenient, but preferably at points of minimum stress. The length of splice beyond the center point, in each direction, shall not be less than forty diameters (40d) of the bars, nor less than two feet (2'0"). The splicing of adjacent bars shall be avoided as far as possible.

(55) Slab bars which are lapped over the column, the sectional area of both being included in the calculations for negative moment, shall extend not less than twenty-five one-hundredths (.25) of the panel length for cross-bands, and thirty-five one-hundredths (.35) of the panel length for diagonal bands, beyond the column center.

Computations.

(56) Complete computations of interior and wall panels and such other portions of the building as may be required by the Commissioner of Buildings shall be left in the office of the Commissioner of Buildings when plans are presented for approval.

Test of Workmanship.

(57) The Commissioner of Buildings or his representative may choose any two adjacent panels in the building for the purpose of ascertaining the character of workmanship. The test shall not be made sooner than the time required for the cement to set thoroughly, nor less than six weeks after the concrete has been poured.

(58) All deflections under test load shall be taken at the center of the slab, and shall be measured from the normal unloaded position of the slab. The two panels selected shall be uniformly loaded over their entire area with a load equal to the dead load plus twice the live load, thus obtaining twice the total design load. The load shall remain in place not less than twenty-four (24) hours. If the total deflection in the center of the panel under the test load does not exceed one eight-hundredth ($1/800$) of the panel length, the slab may be placarded to carry the full design live load. If it exceeds this amount of deflection, and recovers not less than eighty per cent (80%) of the total deflection within seven days after the load is removed, the slab may be placarded to carry the full design live load. If the deflection exceeds the allowable amount above specified, and the recovery is less than eighty per cent (80%) in seven days after the removal of the test load, other tests shall be made on the same or other panels, the results of which will determine the amount of live load the slabs will be permitted to carry.

General.

(59) The design and the execution of the work shall conform to the general provisions and the spirit of the Chicago Building Ordinances in points not covered by this Ruling, and to the best engineering practice in general.

Enforcement.

(60) This ruling shall be in effect on and after March first, Nineteen Hundred and Eighteen (March 1st, 1918), and shall supersede all previous rulings on flat slabs.

Signed: CHAS. BOSTROM,
Commissioner of Buildings.
(Continued on page 301)

CADENHEAD CO.

8 EAST HURON STREET



TELEPHONE SUPERIOR 1474

CHICAGO

SUMNER SOLLITT COMPANY BUILDERS

MASSASOIT BUILDING
225 North Michigan Boulevard
CHICAGO

TELEPHONE
STATE 4460

TELEPHONE SUPERIOR 1474-1475

EDWARD A. ANDERSON COMPANY

Mason and General Contractors
8 East Huron Street
CHICAGO

Phone Seeley 5586

JONES CONSTRUCTION CO. GENERAL CONTRACTORS

BRICK, CONCRETE AND TILE WORK
CARPENTER WORK - ALTERATIONS

We Make a Specialty of Very Fine Interior Trim and Paneling

1748 W. Madison Street

CHICAGO






FIG 1



Section a-a.
Showing Location of Bending Moment Steel with Reference to Column Surfaces.

Telephone Randolph 2576

GERHARDT F. MEYNE

BUILDING, CONTRACTING
REMODELING

127 North Dearborn Street, Chicago

Phone Main 613

Yard } 2729 W. Congress St.
 } 2728-30 W. Harrison St.

Wm. Morrice Co.

BUILDING CONTRACTORS

17 N. La Salle Street
Room 850

CHICAGO

Telephones West 5516
 West 5517



Office and Warehouse
2532-34 Warren Ave.

Mutual Construction Company

ALTERATION SPECIALISTS
CHICAGO

Barrett Construction Co.

GENERAL CONTRACTORS

-- East Washington Street
Room 1530

Telephone Central 8656

CHICAGO

FIREPROOFING OF REINFORCED CONCRETE COLUMNS.

IV

In reference to Section 536-j and Section 550 of the Chicago Building Ordinance, the Commissioner has ruled that in buildings classed as ordinary construction the full section of the column may be calculated in columns reinforced with vertical rods only. In buildings classed as slow burning or mill construction, the outside one and one-half inches shall not be figured in columns reinforced with vertical rods only, and in buildings classed as fireproof construction the outside two inches shall not be figured in the strength of columns with vertical rods only. When spiral reinforcement is used, only the area within the core shall be figured in accordance with Section 538-b.

CAISSONS.

V

Ruling.—The Commissioner has ruled that in determining the area required for concrete caissons, the load on the caissons shall be the load for which the basement column was designed, and the allowable stress on the concrete shall be as given in Section 520 (a). The allowable stress used shall be the stress at the top of the caisson.

A RULING ON COUNTERBALANCE OF STAIRWAY FIRE ESCAPES.

VI

The Commissioner of Buildings has made a ruling in regard to the construction of the movable part of stairway fire escapes as follows:

All counterbalance stairway fire escapes hereafter constructed shall conform to the following requirements in addition to those specified in the Building Ordinance for fixed stairway fire escapes, Section 654.

(a) The stringer carrying the counterweight may be built of steel channels, angles or "I" beams or any combination thereof, not less than eight inches deep and $\frac{3}{8}$ " metal, but it shall be so designed that the maximum fibre stress over the support shall not exceed 8,000 pounds per square inch and the moment of inertia about the vertical axis parallel to the web of the stringer shall not be less than 33% of the moment of inertia about the horizontal axis perpendicular to the web and passing through the center, which shall be accomplished by riveting an angle or angles onto the channel or "I" beam stringer.

(b) The same section of stringer shall be continued for equal distances on either side of the support and the reinforcement shall be extended as close to the counterweight as practicable.

(c) The truss rod from the counterweight to the opposite end of the stringer shall always be used either as an independent brace or in connection with the railing to prevent any sag of the stringer and shall be at least $\frac{3}{4}$ " in diameter firmly connected, the strength of connection to be sufficient to develop the strength of the rod, but in figuring stresses, the stringer must be assumed to carry the total dead and live load as required by the ordinance.

(d) The connection between the stringer and the supporting rod must be designed to stiffen the stringer securely against horizontal or twisting motion by means of a steel casting or forging riveted to the stringer both through the web and the flange.

(e) In order to secure good bearing against the wall under the bracket supporting the platform, the square bracket rods shall be turned up about two inches to a flat bearing before entering the wall, the said two

inches to bear snugly against the wall.

(f) All shutters of any description must be removed from all windows and exits to fire escapes hereafter erected.

ILLUMINATED AND OTHER ROOF SIGNS OF STEEL SKELETON CONSTRUCTION.

VII

In regard to Section 685, of revised Building Ordinances, the Commissioner has ruled that all illuminated roof signs of steel construction shall conform to the following specific requirements:

(a) All compression members shall be proportioned by the usual formula, $16,000-70I$ except that the length of the main or principal members R may be increased to one hundred and seventy-five (175) times the least radius of gyration, and the length of all secondary or sub-members may be increased to two hundred (200) times the same.

(b) The anchorage of every roof sign shall be designed with a factor of safety not less than two (2), i. e., there shall be at least twice as much weight of masonry or concrete resisting the pull on the anchors as figured from the overturning effect of wind.

(c) The thickness of all structural steel members shall not be less than one-fourth ($\frac{1}{4}$) of an inch.

(d) Where a sign structure is so designed as to allow free access to the roof from all sides of the building and where the minimum clearance between roof and the lower edge of the sign is five (5) feet the sign may be erected directly over and flush with the face of the wall on the street or alley side of the building, provided that no part projects over the coping or the lot line, and the lower edge of the sign is at least five (5) feet above the top of the wall.

Chicago, March 15th, 1916.

With reference to Section 517 (h) of the Revised Building Ordinances, the Commissioner has ruled that,

(a) Whenever two or more rows of piles are required, the distance between the center lines shall not be less than the largest diameter of the piles.

(b) When a single staggered row of piles is used, the distance between the center lines shall not be less than one-half the largest diameter of the piles, except that in one-story buildings or walls less than twenty feet high a single row without any staggering may be used.

(c) The piles shall be driven so that the distance between centers shall not be less than twice the largest diameter nor two feet six inches minimum.

RULING GOVERNING THE MINIMUM THICKNESS OF METALS.

VIII.

In steel construction exposed to the weather, no metal in principal members shall be less than 5-16 inch thick. For secondary members, no metal shall be less than 1-4 inch thick, except that webs of channels or "I" beams used as secondary members may be 3-16 inch thick, but not less. This ruling is not to apply to electric signs or fire escapes or canopies.

In steel construction protected by buildings no metal in a principal member shall be less than 1-4 inch thick, except that closed sections filled with concrete and the webs of channels and "I" beams may be 3-16 inch thick, but not less. For secondary members metal may be 3-16 inch, but not less.

The above rulings to take effect August 28 1916.

PHONES: Monroe 3232

Lumber Yard: Austin 300

W. J. NEWMAN CO.
Contractors
Wrecking, Excavating and Caisson Work
21 NORTH CURTIS STREET
CHICAGO

Telephone Central 4223

Chicago Foundation Company
Excavating Work by Steam Shovels a Specialty
Suite 600 -- 76 WEST MONROE STREET, CHICAGO

C. H. HOULTON, *President*

W. L. HOULTON, *Vice-President*

J. C. De WITT, *Sec'y-Treasurer*

LAKE SUPERIOR PILING COMPANY
MANUFACTURERS AND DEALERS IN
WOOD PILING OF ALL KINDS

We are Headquarters for Bridge, Dock and Foundation Piles

BRANCHES:

NEW ORLEANS, LA.
UNEEDUS, LA.

Main Office and Yard:
22d and Morgan Streets CHICAGO, ILL.
Telephone Canal 861

Greenebaum Sons
Bank and Trust Company

A Commercial Bank for You

Aggregate Capital, Surplus and Undivided Profits, Over \$4,500,000

Checking Accounts Invited
3% Interest Allowed on Savings

Greenebaum Sons
Investment Company

Safe Investments Since 1855

First Mortgages and Real Estate Bonds
for Banks, Estates and Individuals

S. E. Corner LaSalle and Madison Streets

OLDEST BANKING HOUSE IN CHICAGO

RULING ON REINFORCED CONCRETE FLOORS.

IX.

In regard to Sec. 550 referring to fireproofing concrete floors, the Commissioner has ruled that the following interpretation shall apply to concrete joist and floor tile construction:

(a) Whenever a combination of reinforced concrete joists and hollow burned clay tile fillers is used, the same shall be assumed same as solid concrete slabs as far as fireproofing of steel rods is concerned.

(b) Whenever a system of concrete joists and steel or plaster domes instead of clay tiles is used, whether same is left in place or withdrawn afterwards, the combination shall be assumed and be subject to same requirements as reinforced concrete beams and girders, with the exception that steel reinforcement in the top of the joists may be considered as in solid slab construction.

(c) Whenever cement plaster ceiling on metal lath is used in connection with the latter type of construction, one-half inch may be deducted from the required amount of fireproofing at the bottom and the sides of joists, provided that cement plaster not less than three-fourths inches thick be applied directly to the under side of joists.

RULING GOVERNING STAR-SHAPED COMPRESSION MEMBERS.

X.

In regard to columns or struts built of two angles placed back to back in star-shape

the Commissioner has ruled that the same should comply with the following specifications:

1. Star-shaped compression members shall be tied together by pairs of batten plates or pairs of angle lugs in opposite directions spaced not more than three (3) times the width of main member center to center of each successive pair.

2. Each batten plate or angle lug shall have enough rivets connecting it to each angle of the column or strut to be able to transfer fifteen (15%) per cent of total stress in the member from one angle to the other through the rivets when these are figured in single shear.

3. Minimum size of rivets shall be as follows:

$\frac{7}{8}$ " diameter for 8" angles.

$\frac{3}{4}$ " diameter for 6", 5" and 4" angles.

$\frac{5}{8}$ " diameter for 3" and 2 $\frac{1}{2}$ " angles.

4. Minimum spacing of rivets shall be three (3) inches for single row and two and one-half (2 $\frac{1}{2}$) inches for double row, staggered, measured parallel to the gage lines. When two gage lines are used, rivets must be staggered.

5. Minimum thickness of strut angles or batten plates shall be one-fourth of an inch ($\frac{1}{4}$) when exposed to weather, and three-sixteenth (3-16) inches when protected within a building, but batten plates or angle lugs shall not be less than two-thirds (2-3) the thickness of the main compression members.

STATE ZONING LAW

Senate Bill 125

(See city ordinance passed July 21-1919 Page 245)

For an Act to confer certain additional powers upon city councils in cities and presidents and boards of trustees in villages and incorporated towns concerning buildings and structures, the intensity of use of lot areas, the classification of trades, industries, buildings, and structures, with respect to the location and regulation, the creation of districts of different classes, and the establishment of regulations and restrictions applicable thereto.

Section 1. Be it enacted by the People of the State of Illinois, represented in the General Assembly: In addition to existing powers, and to the end that adequate light, pure air and safety from fire and other dangers may be secured, that the taxable value of land and buildings throughout the city, village or incorporated town, may be conserved, that congestion in the public streets may be lessened or avoided, and that the public health, safety, comfort morals and welfare may otherwise be promoted, the city council in each city, and the president and board of trustees in each village and incorporated town shall have the following powers:

To regulate and limit the height and bulk of buildings hereafter to be erected; to regulate and limit the intensity of the use of lot areas, and to regulate and determine the area of open spaces, within and surrounding such buildings; to classify, regulate and restrict the location of trades and industries and the location of buildings designed for specified industrial business, residential and other uses; to divide the entire city, village or incorporated town into districts of such number, shape, area and of such different classes (according to use of land and buildings, height and bulk of buildings, intensity of the use of lot

areas, area of open spaces, or other classification) as may be deemed best suited to carry out the purposes of this Act; to fix standards to which buildings or structures shall conform therein; to prohibit uses, buildings or structures incompatible with the character of such districts respectively; and to prevent additions to and alteration or remodeling of existing buildings or structures in such a way as to avoid the restrictions and limitations lawfully imposed hereunder. In all ordinances passed under the authority of this Act, due allowance shall be made for existing conditions, the conservation of property values, the direction of building development to the best advantage of the entire city, village or incorporated town, and the uses to which property is devoted at the time of the enactment of any such ordinance. The powers by this Act given shall not be exercised so as to deprive the owner of any existing property of its use or maintenance for the purpose to which it is then lawfully devoted.

Section 2. The city council in cities and the president and board of trustees in villages and incorporated towns, which desire to exercise the powers conferred by this Act, shall provide for a zoning commission whose duty it shall be to recommend the boundaries of districts and appropriate regulations to be enforced therein, such commission to be appointed by the mayor or president of the board of trustees, subject to confirmation by the council or board of trustees. Such commission shall prepare a tentative report and a proposed zoning ordinance for the entire city, village or incorporated town. After the preparation of such tentative report and ordinance, the commission shall hold a hearing there-

Morris L. Greeley, Pres.

L. E. Alswede, V. P.

Sylvester N. Howard, Sec.

Fred Norlin, Treas.

ESTABLISHED IN 1854

GREELEY-HOWARD-NORLIN CO.

Surveyors and Engineers

Suite 531, 127 N. Dearborn St.

Telephone: Dearborn 1870

CHICAGO

A. I. SILANDER

Phone Franklin 2716

SILANDER SURVEYOR

OFFICE: 30 NORTH LA SALLE STREET, CHICAGO
S. W. Corner Washington Street

WM. KRAMER SURVEYOR

8 S. DEARBORN STREET
1203 HARTFORD BLDG.

Telephones—Central 3871
Dearborn 5513
Residence Tel. Rogers Park 1192

CHICAGO

W. D. JONES SURVEYOR AND CIVIL ENGINEER ESTABLISHED 1888

Special facilities for accurate and prompt surveys in Chicago,
& Cook County, Ill. and in Lake County, Ind.

8 S. DEARBORN ST.

Office Tel. CENTRAL 3871
And RANDOLPH 5513

Residence Tel. KEDZIE 7406

on and shall afford persons interested an opportunity to be heard. Notice of such hearing shall be published at least fifteen (15) days in advance thereof in a newspaper of general circulation in such city, village or incorporated town; or, if there is no such newspaper, such notice shall be posted at least fifteen (15) days in advance thereof in four conspicuous places within the city, village or incorporated town. Such notice shall state the time and place of the hearing and the place where copies of the proposed ordinance will be accessible for examination by interested parties. Such hearing may be adjourned from time to time.

Within thirty (30) days after the final adjournment of such hearing the commission shall make the final report and submit a proposed ordinance for the entire city, village or incorporated town to the city council or board of trustees, as the case may be. The city council or board of trustees may enact the ordinance with or without change, or may refer it back to the commission for further consideration. The zoning commission shall cease to exist upon the adoption of a zoning ordinance for the entire city, village or incorporated town.

Section 3. All ordinances passed under the terms of this Act shall be enforced by such officer of the city, village or incorporated town as may be assigned by ordinance. Each city, village or incorporated town exercising the powers conferred by this Act shall provide by ordinance for the creation of a board of appeals of not less than three members nor more than five members to be appointed in the same manner as the zoning commission. Such board of appeals shall have power: (a) Upon application to review the actions of the enforcing officer of the city, village or incorporated town in order to determine whether they are in accordance with the terms of ordinances enacted under the terms of this Act; (b) to recommend to the city council or board of trustees such ordinances or amendments as it may deem necessary or desirable, including power in specific cases of particular hardship to recommend variations of the original ordinance or amendments thereto. Variations from or amendments to ordinances enacted under the terms of this Act shall in all cases be made by ordinance.

Section 4. The regulations imposed and the districts created under the authority of this Act may be varied or amended from time to time by ordinance after the ordinance establishing same has gone into effect, but no such variations or amendments shall be made without a hearing before the board of appeals, provided for by Section 3 hereof. Such board shall give notice and proceed in the same manner as is provided by Section 2 with respect to the zoning commission. Upon its report the city council or board of trustees may adopt the proposed variation or amendment, with or without change, or may refer it back to the board for further consideration. Any proposed variation or amendment which fails to receive the approval of the board of appeals shall not be passed except by the favorable vote of two-thirds of all the members of the city council in cities or of the members of the board of trustees in villages or incorporated towns. In case of written protest against any proposed variation or amendment, signed by the owners of twenty per cent of the front-

age proposed to be altered, or by the owners of twenty per cent of the frontage immediately adjoining or across an alley therefrom, or by the owners of twenty per cent of the frontage directly opposite the frontage, proposed to be altered as to such regulations or district, filed with the said board of appeals, or with the city council or board of trustees, such variation or amendment shall not be passed except by the favorable vote of two-thirds of all the members of the city council in cities or of the members of the board of trustees in villages or incorporated towns.

Section 5. "An Act to confer certain additional powers upon city councils in cities and presidents and boards of trustees in villages concerning buildings, the intensity of use of lot areas, the classification of buildings, trades and industries with respect to location and regulation, the creation of residential, industrial, commercial and other districts, and the exclusion from and regulation within such districts of classes of buildings, trades and industries," approved June 28, 1919, in force July 1, 1919, is repealed. This repeal shall in no way affect the validity of steps taken or acts done under the Act so repealed. No acts done in compliance or supposed or attempted compliance with the Act so repealed shall be rendered void or of no effects because of omissions, defects or irregularities, if such acts are in compliance with the requirements of this Act.

RESIDENCE DISTRICTS: TEMPORARY WITH-HOLDING OF BUILDING PERMITS.

Be it ordained by the City Council of the City of Chicago:

Passed July 21, 1919.

Amended September 9, 1919.

Section 1. That in all cases where an application for a permit is made for the erection of a new building in any block in which a majority of the buildings are used exclusively for residence purposes, or in a block on the opposite side of the block so used for residential purposes, if there shall be filed with the Commissioner of Buildings a protest signed by not less than ten owners of property in such block so used for residential purposes, or in case the majority of the frontage is owned by less than twenty persons then by a majority of the owners according to frontage, the Commissioner of Buildings shall withhold the issuance of a building permit until the City Council shall have ordered a public hearing in accordance with an act of the General Assembly entitled "An Act to confer certain additional powers upon city councils in cities and Presidents and boards of trustees in villages concerning buildings, the intensity of use of lot areas, the classification of buildings, trades and industries with respect to location and regulation, the creation of residential, industrial, commercial and other districts, and the exclusion from and regulation within such districts of classes of buildings, trades and industries," in force July 1, 1919. For the purposes of this ordinance a block shall be understood to be a plot of ground containing city lots surrounded by public streets, railway rights-of-way, natural boundaries or public places or thoroughfares.

Section 2. This ordinance shall take effect and be in force from and after its passage and approval.

Victor S. Pearlman & Co.

Maintain an exclusive Lighting Fixture Studio where examples of all descriptions may be seen for various projects which will interest Architects



SOME RECENT INSTALLATIONS:

Tivoli Theatre.....	Chicago, Ill.
Chicago Theatre.....	Chicago, Ill.
Parthenon Theatre.....	Hammond, Ind.
Newman Theatre.....	Kansas City, Mo.
Royal Theatre.....	Kansas City, Mo.
Rialto Theatre.....	Omaha, Nebr.
Drake Hotel (main portions).....	Chicago, Ill.
Quigley Seminary (Archbishop Quigley Memorial)	
.....	Chicago, Ill.
St. Mary's Academy (Cathedral).....	Leavenworth, Kas.
St. Edmund's Church.....	Oak Park, Ill.
First Church of Christ, Scientist.....	Springfield, Mass.
13th Church of Christ, Scientist.....	Chicago, Ill.
Second Church of Christ, Scientist.....	Peoria, Ill.
Second Church of Christ, Scientist.....	Chicago, Ill.
Douglas County Court House.....	Omaha, Nebr.
Noel State Bank.....	Chicago, Ill.
Continental & Commercial National Bank and Subsidiary Banks	Chicago, Ill.
Union National Bank.....	Muskegon, Mich.
Guarantee Trust Co.....	Butler, Pa.
First Central National Bank.....	Madison, Wis.
Farmers Trust Co.....	Maryville, Mo.
National Bank of Commerce.....	San Antonio, Tex.
R. Q. Astin Residence.....	Bryan, Tex.
Frank Cullinan Residence.....	Dallas, Tex.
C. A. Braley Residence.....	Kansas City, Mo.
E. J. Curtis Residence.....	Clinton, Ia.

Our Service Is Complete and Prompt

We cordially invite you to visit our Galleries and Workshops which are in the same building

Victor S. Pearlman & Co.

Creators of Exclusive Lighting Fixtures

533-535 S. Wabash Ave.

Telephone, Harrison 2707-8-9

Chicago, Illinois

DEPARTMENT OF ELECTRICITY, CITY OF CHICAGO

Particular attention is called to the various important requirements of the Ordinances printed herein.

Permits will be issued only to licensed electricians.

A licensed electrician can do work only in the class for which he is licensed. Application should not be made to do work in any other class.

Licenses may be transferred from one class to another by paying the difference between the original license fees and the difference between the renewal fees for the unexpired portion of the license period. The supervising electrician must submit himself to an examination in the new class to which transfer is desired.

Licenses which are allowed to lapse will, on renewal, be dated back to the date of expiration of the previous license, but no license will be renewed after one year from date of expired license.

Bonds must be furnished before the issuance of all classes of licenses except maintenance licenses. The term of the bond must correspond with the period of the license to be issued. Bond must be properly executed and forwarded to the Electrical Inspection Bureau, together with the renewal fee. No license will be issued until the required bond is furnished and where such bond is not supplied permits will not be issued to the licensee.

Inspection fees must accompany applications, otherwise permits cannot be issued.

Applications for permits must be correctly and completely filled out and must be signed by the Supervising Electrician, otherwise application must be returned and work delayed.

In all cases the location must be completely and correctly stated. If in an office building or other building having a number of floors, the floor or room number must be given. Where necessary the prefix East, West, North or South must be given. Failure to comply with this requirement confuses the records of the office and results in inconvenience and delays to the contractor and the public.

Application must be made only for the work contracted for and installed by the licensee. The obtaining of permits for work done by others will be considered cause for revocation of license.

Where apparatus is installed in addition to that originally applied for, full fee will be charged for such apparatus.

Permits must be obtained **before** any work is started. Violation will be considered as sufficient cause for revocation of license.

The wiring contractor must connect up all switches and receptacles installed by him. He must also pole up all wires at fixture outlets and must solder and tape all such wires except those to which a fixture is to be attached.

The use of electric current is prohibited previous to the issuance of a current permit or certificate.

Temporary work must be inspected and approved before current is used on the same. Alterations to existing wiring must not be made without obtaining a permit.

Violation of the ordinance constitutes a misdemeanor and is punishable by a fine of from \$50.00 to \$100.00, also by the cutting off and stopping the use of current.

WILLIAM G. KEITH,

Commissioner of Gas and Electricity.

SPECIAL SUGGESTIONS TO ARCHITECTS.

The Department of Electricity will **not allow more than sixteen (16) sockets to be attached to one circuit.**

Architects are urged to make definite specifications for electrical work, for the benefit of both the electrical contractor and the fixture contractor, specifying the number of outlets in each job for the electrical contractor to follow, and the exact number of 40 watt or equivalent.

Frequently the fixture contractor installs more than sixteen lights on a circuit, which is in violation of the city ordinances, and causes the consumer very much annoyance in getting electric current to his premises.

It is also suggested that the architects demand of the electrical contractor that he make up all connections and combinations relative to switches, complicated outlets, etc., leaving only two wires for the fixture hanger to make his fixture connections.

GENERAL SUGGESTIONS.

In all electric work conductors, however well insulated, should always be treated as bare, to the end that under no conditions, existing or likely to exist, can a grounding or short circuit occur, and so that all leakage from conductor to conductor, or between inductor and ground, may be reduced to the minimum.

In all wiring special attention must be paid to the mechanical execution of the work. Careful and neat running, connecting, soldering, taping of conductors and securing and attaching of fittings, are especially conducive to security and efficiency, and will be strongly insisted on.

In laying out an installation, except for instant current systems, every reasonable effort should be made to secure distribution centers located in easily accessible places, which points the cutouts and switches

controlling the several branch circuits can be grouped for convenience and safety of operation. The load should be divided as evenly as possible among the branches, and all complicated and unnecessary wiring avoided.

SPECIAL NOTICE.

Service switches, cutouts and meters must, when practicable, be placed in basements or other public portions of the building. Exception will be made for cutouts in the case of apartment buildings having 4 circuits or more per apartment or where the building is four stories or more in height. Where cutouts are located in apartments or on the various floors of residences, etc., they must never be located in clothes closets or any other location where combustible material is stored.

Service switches, cutouts and meters should not be installed above or in close proximity to laundry tubs, sinks, gas meters or plumbing fixtures.

Meter outlet fittings must be of approved construction.

A separate fitting is required for each meter.

Meter fittings are required on all installations where the mains are of No. 2 B. & S. gauge or smaller. This includes both power and light.

On mains larger than No. 2 B. & S. gauge, conduit fittings, where wires leave the conduit system through separate insulated openings, must be used.

The meter fitting must be placed so that the opening for the wires is at the top of the fitting, except where the fitting is so constructed that the wires to meter leave at the side.

All wires from fitting to meters where liable to come in contact with wires or other materials must be protected by flexible tubing.



R. L. M. Domes
Reflector Socket



Glass and Vapor-Proof Fixture



Industrial Signal




Bowl Shade
Holder Reflector



Elliptical Angle
Reflector



"Benco"
Weather-proof
Socket



Dead Front
Panel Board

REFLECTOR SOCKETS.—Benjamin Reflector Sockets are seamless, made of one piece of steel and will successfully resist the influences of corrosion. Furnished in R. L. M., Bowl, Shallow Bowl and Flat cone shapes, to meet all lighting requirements. Porcelain enameled, green outside, white inside.

SHADE HOLDER REFLECTORS.—Intended for use principally where sockets are already installed. Fit any standard porcelain or brass shell socket, 2 1/4-inch shade holder, or the "Benco" threaded socket. R. L. M., Bowl, Shallow Bowl, or Symmetrical Angle shapes. Porcelain enameled, green outside, white inside.

ELLIPTICAL ANGLE REFLECTORS AND PARABOLITES—Elliptical Angle Reflector is used where a vertical surface must be lighted or where overhead mounting is not possible. Parabolite is used to light narrow aisles, corridors, areas adjacent to fences etc. Sockets included. Porcelain enameled, black outside, white inside.

"BENCO" WEATHER-PROOF SOCKETS.—"Benco" Weather proof Sockets are highly insulated metal cased sockets for indoor and outdoor service. Keyless or pull chain types. Fit Type "S" shade holder reflectors. Finished in frosted aluminum, brushed brass, natural copper, or green to match reflector.

GAS AND VAPOR-PROOF FIXTURES.—Benjamin protective lighting units. For use in powder, benzol and paint plants, garages, gasoline filling stations, etc. Flat Cone or Shallow Bowl reflector and without reflector. Metal parts galvanized, reflector white porcelain enameled inside and out.

INDUSTRIAL SIGNALS.—Benjamin Industrial Signals have a peculiar, penetrating tone pitch, which makes them more effective as audible signals than gongs or bells. A special adjusting means governs volume and tone pitch. A large number of devices—one for every industrial application.

BENJAMIN-STARRETT PANEL BOARDS.—Built upon approved composition bases, with concealed bus bars. Stronger, smaller, lighter—quickly procured, easily installed. Open and Dead Front Standardized Panel Boards from 4 to 30 circuits, Open and Dead Front Residence Panel Boards from 2 to 10 circuits.

Address Chicago Office

BENJAMIN ELECTRIC MFG. CO.

CHICAGO

NEW YORK

SAN FRANCISCO

BENJAMIN ELECTRIC MFG. CO. of Canada, Ltd.
Toronto, Canada

THE BENJAMIN ELECTRIC, Ltd.
London, England

SECTIONS OF THE CHICAGO CODE OF 1911 OF THE CITY OF CHICAGO GOVERNING ELECTRICAL INSPECTIONS

Passed March 13, 1911.

Amended December 30, 1912; July 7, 1913; July 21, 1913; November 3, 1913; July 21, 1919; July 22, 1921.

CHAPTER XXIV. ELECTRICITY — ARTICLE 1. DEPARTMENT OF GAS AND ELECTRICITY.

"830. **Electric Current.**) No electric current shall be used for lighting, heating or power purposes except as hereinafter provided.

"831. **Applications — Contents — Permit.**) All persons or corporations desiring to install wires or other apparatus for the use of electrical currents for any of the purposes mentioned in the foregoing section, shall, before commencing or doing any electrical construction work of any kind whatever, either installing new electrical apparatus or repairing apparatus already in use, file an application for a permit therefore in the office of the Commissioner of Gas and Electricity, which application shall describe in detail such material and apparatus as it is desired to use, with a full description of the same, giving the locality by street and number, such application to be countersigned by the person under whose supervision the work is to be done; and upon the filing of said application, if found proper, such permit shall be given, and no work shall be started until such permit has been obtained. No work shall be done unless under the supervision of a duly qualified person as provided in Section 832.

"832. **Requirements for License—Classification—Suspension and Revocation of License.**) Any person or corporation making application for permits must first file with the Commissioner of Gas and Electricity an application containing an affidavit stating that the work to be done under such permits will be under the supervision of a person who is not less than twenty-one (21) years of age, who has a thorough knowledge of electrical construction and who has had not less than four (4) years of practical experience in installing or maintaining electrical wires and apparatus in the class mentioned in the application for license and provided for in the classification of licenses as given below, and who shall have regularly passed the examination as provided for hereinafter. Such application shall be made upon a form prepared and approved by the Board of Examiners to be appointed by the Mayor for the purpose of inquiring into and ascertaining the qualifications of such applicant and of the Supervising Electrician, as provided herein. Such application shall contain the name and signature of the person under whose supervision the work is to be done, together with two indorsements from responsible citizens, made under oath, that such person possesses the qualifications above designated. Upon filing such application in proper form and upon the deposit of an amount equal to the

license fee for the class of license being applied for, with the said Examining Board, and upon the Supervising Electrician successfully passing the examination hereinafter provided for, the said Examining Board shall cause to be transferred to the City Collector the deposit made by such applicant, which deposit the said City Collector shall receive as the license fee for the said applicant, and the Commissioner of Gas and Electricity shall issue, or cause to be issued, the license applied for, which license shall entitle the licensee to obtain permits to do such work as shall be within the classification covered by such license. The license fee for the first year for a General Electrical Contractor shall be two hundred dollars (\$200.00) with a renewal fee of fifty dollars (\$50.00) for each year. The license fee for the first year for Electrical Construction shall be one hundred dollars (\$100.00) with a renewal fee of twenty-five dollars (\$25.00) for each year. The license fee for the first year for a fixture license, including such persons or corporations doing fixture work only, shall be one hundred dollars (\$100.00) with a renewal fee of twenty-five dollars (\$25.00) for each year. The license fee for the first year for a sign license, including such persons or corporations doing sign work only, shall be twenty-five dollars (\$25.00) with a renewal fee of ten dollars (\$10.00) for each year. The license fee for the first year for a maintenance license, including such persons or corporations doing maintenance work in buildings owned or controlled by such persons or corporations, shall be twenty-five dollars (\$25.00) with a renewal fee of ten dollars (\$10.00) for each year. The above classification of licenses and the fees pertaining thereto shall not immediately apply to those certificates of registration in existence at the time of passage of this ordinance but shall apply to such certificates of registration at the expiration of the period for which they are issued at which time a renewal fee in accordance with the above classification must be paid before such renewal is made.

Prior to the issuance of a license for General Electrical Contractor, Electrical Construction, Fixture License and Sign License, the applicant shall file with the City Collector of the City of Chicago, an indemnifying bond with good and sufficient sureties in the penal sum of five thousand dollars (\$5,000.00), and bond being payable to the Commissioner of Gas and Electricity of the City of Chicago, for the use of any persons or corporations with whom such applicant shall thereafter contract to do work, to indemnify any such persons or corporations for damages sustained on account of the failure of such applicant to perform the work so contracted for,

ECONOMY

renewable FUSES



Knife Blade Type Fuse
Disassembled



Cartridge

"Drop-Out"
Renewal
Link and
Winged
Washer
Economy



Ferrule Type
Fuse & "Drop-
Out" Renewal
Link

ECONOMY FUSES are made in three general types (ferrule, plug, and knife blade) with a full line of capacity ranges for all commercial voltages. This was the first line of fuses approved in all capacities by the Underwriters' Laboratories, Inc., established and maintained by the National Board of Fire Underwriters, employing an inexpensive bare link for restoring a blown fuse to its original efficiency.

The fusible elements are of the "Drop Out" renewal link type, accurately rated and of definite design. Every part of an Economy fuse is built on the "safety first" principle, which means that the design is right from an electrical standpoint, and that material entering into the construction of the completed fuse is the best that money can buy.

The use of Economy Fuses in establishments where the fire hazard is great (powder factories, arms and munition plants, chemical works, flour mills, submarines, battleships, etc.) and where "safety first" is the highest consideration (department stores, hospitals, schools, hotels, theaters, institutions, ships, railway cars, etc.) is the proof of their safety in use.

Write "Economy or Equal" Into All Your Specifications for Electrical Fusing.

Hang the Fixture Like a Picture

The Economy Fuse & Manufacturing Company is now actively producing and marketing, through its own sales organization, ECONOMY RECEPTACLES and PLUGS for Elexits, under license from the Electric Outlet Company, Incorporated, under patents of April 14th, 1914, December 7th, 1920, etc. The service and co-operation of our large sales organization is offered to the fixture manufacturer and dealer and the electrical trade in order to develop the universal standardization and use of this modern method of installation of electric fixtures.

ECONOMY FUSE & MFG. CO.

2711 Greenview Avenue - Chicago, Illinois

Atlanta, Ga.
Baltimore, Md.
Boston, Mass.

Buffalo, N. Y.
Cleveland, Ohio
Cincinnati, Ohio
San Francisco, Cal.

Detroit, Mich.
Denver, Colo.
Kansas City, Mo.
Seattle, Wash.

Los Angeles, Cal.
Milwaukee, Wis.
Minneapolis, Minn.
St. Louis, Mo.

New York, N. Y.
Philadelphia, Pa.
Pittsburgh, Pa.

Economy Fuse & Mfg. Co. of Canada, Ltd., Montreal, Canada

Complete Stocks Carried by All Leading Jobbers

in accordance with the provisions and requirements of the City of Chicago, relating to the installing, operating and maintaining of electrical wires or apparatus. The filing of the above mentioned bond shall be required previous to the issuance of any original license or the renewal of any certificate of registration in existence at the time of passage of this ordinance.

For the purpose of ascertaining the qualifications of the applicant and of the Supervising Electrician, the Mayor shall appoint an Examining Board of five (5) members to consist of the following: Commissioner of Gas and Electricity, chairman, one member to be selected from the Board of Underwriters of the City of Chicago, one member to be a General Electrical Contractor, regularly engaged in the contracting business in the City of Chicago, one member to be a journeyman fixture hanger, who has had at least five (5) years of practical experience in general fixture work, and one member shall be a journeyman electrician who has had at least five (5) years of practical experience in general electrical work. Each member of said Examining Board, with the exception of the Commissioner of Gas and Electricity, shall receive as his compensation as such, the sum of ten dollars (\$10.00) per day for each day, not to exceed thirty (30) days per year, that he shall be actively engaged in the business of the Examining Board, and such compensation shall be paid out of the corporate funds. Such members shall hold office for a period of one year or until their successors are duly appointed. Provided, further; a clerk shall be assigned by the Commissioner of Gas and Electricity to assist the said Examining Board in its work and such clerk shall be a Civil Service employee. Provided, further, that the said Examining Board shall have power to adopt the necessary rules and regulations for the licensing of electricians and for the examination of Supervising Electricians and such examination shall be conducted by the said Board by the oral and written method and the judgment of the said Board as to whether or not an applicant or Supervising Electrician is qualified and has sufficient experience and knowledge for the particular class of license applied for shall be final.

Licenses shall be classified as follows: General Electrical Contractor, Electrical Construction, Fixture License, Sign License and Maintenance License. Under the classification of General Electrical Contractor shall be included persons or corporations doing all classes of electrical work in which shall be included general electrical contracting, electrical construction, fixture, sign and maintenance work. Under the classification of Electrical construction, fixture, sign and maintenance work. Under the classification of Electrical work excepting electrical fixtures and electrical signs. Under the classification of Fixture License shall be included persons or corporations doing electrical fixture work only. Under the classification of Sign License shall be included persons or corporations doing illuminated sign work only. Under the classification of Maintenance License shall be included persons or corporations doing maintenance work only in buildings owned or controlled by such persons or corporations.

Where a Certificate of Registration is in existence at the time of passage of this ordinance a renewal of such Certificate shall only be made within the classification previously placed on such Certificate by the Commissioner of Gas and Electricity, and for the purpose of transferring to or renewing a Certificate of Registration in any other class, as provided for herein, the Supervising Electrician must submit to, and properly pass, an examination such as will determine his experience and qualifications to act as Supervising Electrician in the particular class of business to which he desires to transfer.

Where a license is permitted to lapse by failure on the part of the licensee to renew same on or before the date of expiration the renewal of same will date back to the date of expiration of the expired license, and no license shall be renewed after a period of one year from date of expiration.

All licenses issued under the provisions of this ordinance shall be transferable. All such transfers shall be registered with the Examining Board and with the Commissioner of Gas and Electricity. Such transfers, however, shall not be made until such time as transferee has complied with all the terms of the ordinances of the City of Chicago. The Supervising Electrician may be replaced at any time with any other Supervising Electrician who shall comply with the terms of this ordinance and no fee shall be charged for such transfer.


For the purpose of conducting examinations and for the transaction of business, the Board of Examiners shall hold its meetings when it shall deem necessary. All applications for license shall be submitted by the applicants to the Board and placed on file at least fifteen days (15) days before the time set for holding the examination and such applications shall be acted upon by the Board within forty-five (45) days from date of filing.

The Board of Examiners, upon complaint being made to it by the Commissioner of Gas and Electricity respecting the character of the work done by any licensee, shall have the power, and it shall be its duty, to cause such licensee or his Supervising Electrician to appear before the said Board for the purpose of examination. If such Board shall find the licensee or Supervising Electrician is not qualified to do the work for which he has been licensed or that such licensee or Supervising Electrician has not complied with the ordinances of the City of Chicago, or with the rules and regulations of the Department of Gas and Electricity, in the performance of his work, it shall be the duty of the said Board to certify such facts to the Commissioner of Gas and Electricity with a recommendation for the suspension or revocation of the license as the Board shall in its judgment deem advisable.

The Commissioner of Gas and Electricity may, for any violation of the provisions of this article, or of any rule or regulation of the Department of Gas and Electricity of which the licensee has received notice, suspend the license of such licensee for a period not to exceed thirty (30) days. The Mayor may revoke the license of any licensee for violation of any ordinance of the City of Chicago relative to the installation, operation or maintenance of electrical wires or apparatus, or if in his discretion the holder of such license is incompetent or unfit.

"833. Duties of Commissioner of Gas and Electricity Thereon.) The said Commissioner of Gas and Electricity, or his assistants, shall have power, and it shall be their duty, when deemed necessary by the Commissioner of Gas and Electricity, to carefully inspect any such installation previous to and after its completion, and they shall have the right to enter any building when by them deemed necessary, to inspect any such installation, and it shall be competent for them to remove any existing obstructions which may prevent a perfect inspection of the current-carrying conductors, such as laths, plastering, boarding or partitions; and it shall be unlawful for any person to interfere with them in the performance of their duties; and if such installation shall prove to have been constructed in a safe and secure manner, after the payment of a fee, as hereinafter provided, the Commissioner of Gas and Electricity shall issue a certificate of such inspection, which shall contain a general description of the installation and the date of such inspection. Any owner installing or causing

“U N I O N”



RENEWABLE FUSES

enable the user to make a greater saving in the cost of fuse maintenance, on circuits subject to fluctuation of current causing frequent replacements, than may be obtained with any other fuse on the market.

That is a strong statement, but you will find it is true upon considering:

- 1st—That in addition to being accurately rated and approved by the Underwriters Laboratories, Inc. thereby giving the necessary protection, they are
- 2nd—stronger and more ruggedly constructed and will therefore last longer, and
- 3rd—simpler in their design and can therefore be renewed more easily and quickly than other fuses.

If you want to make a saving, naturally you would like to save all you can. This you can do by using Union. Send for our booklet and let us explain further. For sale by all leading electrical Jobbers and Dealers.

CHICAGO FUSE MFG. COMPANY

CHICAGO

Manufacturers of



Renewable Fuses

NEW YORK

to be installed any electric wires to be hidden from view shall, prior to such installation, give said Commissioner of Gas and Electricity a reasonable notice in order to give ample time for inspection. The use of electric current is hereby declared to be unlawful previous to the issuance of such certificate; provided, however, the Commissioner of Gas and Electricity may issue a temporary permit for the use of electrical current during the course of construction or alteration of buildings, which permit shall expire when the electrical apparatus for such building is fully installed. The Commissioner of Gas and Electricity may, in his discretion, receive a single deposit from one or a number of different persons, firms or corporations to guarantee the payment of inspection fees as imposed by the ordinance of the City of Chicago, and in such case shall, at the time of receiving such deposit, enter into an agreement with the persons, firms or corporations, on behalf of whom said deposit is made, wherein among other conditions shall be stated the purpose for which said deposit is made and on whose behalf, and such agreement shall provide that in case said deposit is in anywise depleted to the extent of twenty-five per cent (25%), the persons, firms or corporations on whose behalf said deposit is made shall, within three days after notice of such depletion given by the head of such department to any one of such persons, firms or corporations on whose behalf said deposit is made, deposit a sufficient sum to replenish said fund so that the amount shall be equal to that originally deposited; and provided, whenever any notice to replenish a deposit shall have been given as herein provided, and said deposit shall not be replenished as herein provided, no permit shall thereafter issue to any of the persons, firms or corporations on whose behalf said deposit was made, unless such person, firm or corporation shall first deposit a sum as provided by the ordinances pursuant to which such permit is issued.

§34. Power of Commissioner of Gas and Electricity—Inspections and Re-Inspections.) The said Commissioner of Gas and Electricity is hereby empowered to inspect or re-inspect all overhead, underground and interior wires, and apparatus conducting electric current for light, heat, or power, and when said conductors or apparatus are found to be unsafe to life or property, he shall notify the person or corporation owning, using or operating them to place the same in a safe and secure condition within forty-eight hours. Any person or corporation failing or refusing to repair, change or remove the same within forty-eight hours or within such further time as the Commissioner of Gas and Electricity shall determine is necessary, after the receipt of such notice, shall be subject to the penalty hereinafter provided.

Whenever it shall be necessary in the opinion of the Commissioner of Gas and Electricity to call upon the department of police for aid or assistance in carrying out or enforcing any of the provisions of the City of Chicago governing electrical inspections, he shall have authority to do so, and it shall be the duty of the department of police or any member of said department, when called upon by said Commissioner of Gas and Electricity, to act according to the instructions of and to perform such duties as may be required by said Commissioner of Gas and Electricity in order to enforce or put into effect the provisions of these rules and regulations.

§35. Poles—Covers — Wires — Electric Service Entrances—Switches.) All poles now standing or hereafter erected, and all covers for manholes now in service, or hereafter placed in service for the use of electric conductors, shall be branded or stamped with the name of the person or corporation owning the same; all electric service entrances shall

have attached to the conductor or conductors, in a conspicuous place, a substantial tag designating the owner, and giving such a full description of the conductors as shall meet with the approval of said Commissioner of Gas and Electricity; and all of said electric service entrances shall be properly equipped with approved cutout service switches. Each building into which electric current shall hereafter be introduced shall have independent service from the street or alley, entering at right angles with the street curb, except where the service wires are placed in conduits; and no wires hereafter put up shall pass from one building to another through any party wall or along any building wall or over any roof or under any sidewalk, except where such conduits are used.

“§36. Fees.) (See Tables of Fees, Pages 266 to 269.) There shall be paid by the registered electrician and collected by the City Collector prior to the issuance of any permit to do electrical work, inspection fees in accordance with the following classification:


Wiring Only for Lighting Circuits. (Not including Fixtures, Sockets or Receptacles.) For the inspection of each complete branch lighting circuit of 1,000 watts or less; one dollar and fifty cents for one circuit, one dollar and twenty cents for each of the next four circuits, one dollar for each of the next five circuits, eighty-five cents for each of the next five circuits, seventy-five cents for each of the next five circuits, sixty-five cents for each of the next five circuits and sixty cents for each succeeding circuit. (Effective September 1, 1921.)

For the inspection of each complete branch lighting circuit of larger capacity than 1,000 watts the charge shall be in proportion to the wattage of such circuit. (Effective September 1, 1921.)

For the inspection of additional outlets on existing circuits; ten cents for each outlet on which a socket, receptacle or fixture will be attached. (Effective September 1, 1921.)

Electrical Fixtures, Sockets and Receptacles. (Not including the circuit feeding same.) For the inspection of fixtures, sockets or receptacles for lamps of nominal fifty watts capacity; one to fifteen lamps, fifty cents; sixteen to twenty lamps, seventy-five cents; twenty-one to twenty-five lamps, one dollar; twenty-six to thirty lamps, one dollar and twenty-five cents; thirty-one to forty lamps, one dollar and fifty cents; forty-one to fifty lamps, one dollar and seventy-five cents; fifty-one to sixty lamps, two dollars; sixty-one to seventy lamps, two dollars and twenty-five cents; seventy-one to eighty lamps, two dollars and fifty cents; eighty-one to ninety lamps, two dollars and seventy-five cents; ninety-one to one hundred lamps, three dollars; one hundred and one to one hundred and ten lamps, three dollars and twenty cents; one hundred and eleven to one hundred and twenty lamps, three dollars and forty cents; one hundred and twenty-one to one hundred thirty lamps, three dollars and sixty cents; one hundred and thirty-one to one hundred and forty lamps, three dollars and eighty cents; one hundred and forty-one to one hundred and fifty lamps, four dollars; one hundred and fifty-one to one hundred and sixty lamps, four dollars and twenty cents; one hundred and sixty-one to one hundred and seventy lamps, four dollars and forty cents; one hundred and seventy-one to one hundred and eighty lamps, four dollars and sixty cents; one hundred and eighty-one to one hundred and ninety lamps, four dollars and eighty cents; one hundred and ninety-one to two hundred lamps, five dollars; above two hundred lamps, twenty-five cents for each group of twenty-five lamps or less. For lamps of larger or smaller capacity the charge shall be in proportion to the wattage of the lamp.

Wiring and Fixtures. For the inspection of both circuit wiring and fixtures, sockets



TRACTION TYPE

Simplicity Itself

HOW DO YOU LIKE IT?

Any LOAD — Any SPEED — Any CONTROL

Montgomery Elevator Co.

FACTORY
Moline, Illinois

CHICAGO OFFICE
122 S. Michigan Ave.
Telephone Wabash 6789

JOIN OUR 1,000 SATISFIED USERS

or receptacles: The aggregate sum of the fees as shown above for wiring and for electrical fixtures.

Motors and Other Forms of Power. For the inspection of each electrical horsepower of seven hundred and forty-six watts used for mechanical or other purposes than above mentioned, the sum of one dollar for each horsepower from one to five horsepower, inclusive; for each of the next succeeding five horsepower, seventy-five cents; for each of the next succeeding five horsepower, sixty-five cents; for each of the next succeeding ten horsepower, fifty-five cents; for each of the next succeeding twenty-five horsepower, fifty cents; for each of the next succeeding two hundred horsepower, twenty-five cents; for each of the next succeeding two hundred and fifty horsepower, ten cents; and for each additional horsepower, five cents.

Temporary Work, Outside Work, Etc. Inspections of electric lights, other than electric signs as herein defined, placed on a public street or alley for the purpose of illuminating the same, temporary installations for show window exhibitions, conventions and the like, underground or overhead wires and apparatus, and all other inspections not specifically provided for herein, shall be charged for according to the time required for such inspection at the rate of one dollar per hour.

Note: The ordinance requires the payment of the inspection fee previous to the issuance of the permit. In the case of "time" charges the amount of the fees cannot be determined until after the inspection has been completed. In such cases a uniform fee of \$1.50 should accompany the application for permit and a bill will be mailed for the balance of the fee after the final inspection has been made.

Re-Inspections. Each re-inspection of any overhead, underground or interior wires or apparatus shall be charged for according to the time required for such re-inspection at the rate of one dollar per hour.

Note: The inspection charge of \$1.00 per hour for time will only be applied on the inspection of incandescent and arc lamps in the following instances:

a. Re-inspection on alterations and repairs where the location of the lamps is not changed or where new lamps are not added. By "alterations and repairs" is meant only such minor changes as may be necessary to place an existing installation in safe condition. It does not include either extensive or complete rewiring.

b. Replacing of fixtures where the circuit wiring is not changed or where the number of lamps, or the total connected wattage of the lamps is not increased over the original installation.

c. Commercial street lighting.
d. Temporary installations for show window exhibitions, conventions, and the like.

All inspections other than those noted above will be charged on the basis of the number of lamps wired for and at the full rate as specified for new work. In no case will credit be allowed for lamps replaced except in the case of replacing fixtures as specified above.

Extra Inspections. Where extra inspections are made on account of any of the following reasons a charge of one dollar shall be made for each such inspection; inaccurate or incorrect information, failure to make necessary repairs, faulty construction.

Minimum Fee. No inspection shall be made for a less amount than one dollar.

On each installation where a permit has been issued and work not sufficiently completed within three months for wiring only certificate to be issued, and where inspection has been made on such work, a portion of the regular fee must be charged to cover the cost of such inspection, which will be credited on the final certificate.

The Commissioner of Gas and Electricity shall make a fee bill, in duplicate, on a form to be approved by the City Comptroller, and shall forward the same to the Comptroller to be recorded and rendered. The person, or corporation, receiving the fee bill shall pay the amount thereof to the City Collector, who shall endorse payment thereon and enter the fee bill and payment in a book in his office, to be provided for that purpose, and thereupon the City Collector shall deliver the paid fee bill to the person or corporation paying the same. The Commissioner of Gas and Electricity shall thereafter issue the certificate as provided for in Section 833.

"837. **Alterations.**) No alterations shall be made in any electrical installation without first notifying the said Commissioner of Gas and Electricity and submitting the same for inspection in the same manner as provided for new work.

* * * * *

"848. **Penalty.**) Any person or corporation who shall violate any of the provisions of this article or who shall furnish or use any electrical current or install any electrical wires or apparatus within the city in violation of any of the provisions of this article, shall be fined not less than fifty dollars nor more than one hundred dollars for each offense, and each day's use thereof contrary to the provisions of this Article shall constitute and be a separate and distinct offense. Said Commissioner of Gas and Electricity may, for any violation of the provisions of this Article, also order and compel the cutting off and stopping of such current until the provisions of this Article are fully complied with.

ARTICLE II. ILLUMINATED SIGNS.

"850. **General Requirements—Definition.**) It shall be unlawful for any person or corporation to erect or maintain over any sidewalk, street, avenue, alley or public way in the city, any illuminated signs, except in accordance with the ordinances of the City of Chicago.

For the purpose of this Article illuminated signs shall be declared to be signs constructed as follows: Signs, all or any part of the letters of which are made in an outline of incandescent lamps; signs with painted, flush or raised letters, lighted by an electric lamp or lamps attached thereto; signs having a border of incandescent lamps attached thereto and reflecting light thereon; and transparent glass signs whether lighted by electricity or other illuminant.

"851. **Inspection Fees.**) (See Table of Fees. Page 269.) The owner or person having charge or control of any sign authorized by this Article shall pay for the use of the city an annual inspection fee to cover the expense of inspection of such sign, the amount of such fee to be computed according to the following classification and schedule:

Projecting Signs.

The fee for all signs projecting at right angles or obliquely from the building against which same are placed, whether such signs are vertical or horizontal, and not being flat signs as hereinafter described, shall be computed at the rate of fifteen cents per annum per square foot of sign surface on each illuminated side of such signs.

Flat Signs.

The fee for all signs placed against a building and running parallel thereto and not projecting obliquely or at right angles therefrom shall be computed at the following rates:

For the inspection of lamps of nominal fifty watts capacity as follows: For each of the first twenty-five incandescent lamps, ten

BEARDSLEE CHANDELIER MFG. CO.

216 South Jefferson Street

DENZAR

CHICAGO, ILLINOIS



Manufacturers of a complete line of chandeliers and bronzes, including the now famous Denzar, the most efficient and highly satisfactory lighting unit for stores, offices, schools, banks, dance halls, places of amusement, hotels and municipal buildings.

Denzar—The Unit of Day Brightness

Denzar was designed especially to utilize the full illuminating value of the high power and economical Mazda "C" Lamp. It does away entirely with the blinding glare which must be softened and diffused in order to make the "C" lamp usable. No portion in the lamp filament is visible from any angle. The lower part of the bowl, of white enamel glass, softens and diffuses the rays and floods the space to be illuminated with a soft clear radiance resembling soft sunlight. The upper part of the bowl is of clear glass, allowing the upper rays to be deflected by the reflecting dome, which distributes them on the working plane.

There are no bright spots or distracting shadows when Denzars are used. For stores, offices, schools, banks, dance halls, places of amusement, hotels and municipal buildings, Denzar is the most efficient and economical lighting unit, not only because it provides better illumination with less current, but also because the lamp is entirely closed and protected from dust, dirt and insects which gather rapidly in units having open bowls.

Denzar is made in a variety of types and sizes to fit every lighting requirement and to harmonize with any style of architectural and decorative treatment. It is furnished with plain or ornamental bowls, or with decorated bowls in artistic designs. Its compact well-balanced design and pleasing lines make it appropriate for use in any commercial or public surroundings.

Artistic Lighting Equipment and Designing Service


A staff of illuminating engineers, designers and metal workers is employed to plan and suggest suitable lighting equipment to harmonize with any architectural detail and decoration. The designers and metal workers are exceptionally skillful in producing replicas of period designs and creating lighting forms to harmonize with architectural and decorative features. The services of this exceptional staff is extended to every critical architect.



*Pendant Type Denzar
De Luxe*



*Compact Ceiling Type Denzar
with Ornamental Bowl*



*Flexible Ceiling Type Denzar
with Plain Bowl*

cents; for each of the next twenty-five lamps, nine cents; for each of the next twenty-five lamps, eight cents; for each of the next twenty-five lamps, seven cents; for each of the next one hundred lamps, six cents; for each of the next one hundred lamps, five cents; for each additional lamp above three hundred, four cents. For lamps of larger or smaller capacity the charge shall be in proportion to the wattage of the lamp.

Temporary Signs.

The fee for illuminated signs installed for temporary use for special occasions not to exceed thirty days shall be computed at one-fourth of the annual rate fixed for the particular type or style of sign, whether projecting or flat.

"852. **Application—Permit.**) Any person or corporation desiring to erect and maintain an illuminated sign over any sidewalk, street, alley or public way in the city shall make application to the Commissioner of Gas and Electricity for that purpose on a printed form to be furnished therefor by the Department of Gas and Electricity, setting forth in such printed form such information as is required by said department. Such application when made shall be submitted by the Commissioner of Gas and Electricity to the Commissioner of Public Works for his approval as to the location of such sign, and when the approval of the Commissioner of Public Works shall be placed upon such application as to the location thereof the Commissioner of Gas and Electricity shall issue to such applicant, upon the payment by such applicant to the City Collector of the inspection or permit fee as herein fixed, a permit in writing, authorizing such applicant to erect a sign at the location designated in such application and of the style or design described therein. Upon the completion of the work of erecting such sign under such permit the applicant shall forthwith notify the Commissioner of Gas and Electricity, who shall thereupon cause an inspection of such sign to be made; and if he shall find that such sign has been constructed and erected in accordance with the ordinances of the City of Chicago, he shall thereupon issue to such applicant a permit in writing authorizing such applicant to operate and maintain the sign so erected for the period of one year from the date of the issuance thereof; such permit to be issued without further cost or expense to the applicant other than the fees hereinbefore provided.

The use of electrical current or of any other illuminant, by such applicant in connection with such sign previous to the issuance of the permit last described, is prohibited and no electrical current, or other illuminant, shall be turned on, or into, such sign, previous to the issuance of such permit, except by order of the Commissioner of Gas and Electricity, for the purpose of testing the same to see whether it is constructed in accordance with, and pursuant to, the provisions of this chapter.

No alteration shall be made on any sign erected or maintained under the authority of this Article unless all the provisions hereof are fully complied with and unless a permit expressly issued for the purpose of allowing such alterations be first secured from the Commissioner of Gas and Electricity.

"853. **Location—Time of Illumination.**) Every sign erected under and pursuant to the provisions of this Article shall be placed at

least nine feet above the surface of that part of the public way which any such sign overhangs, and the portion of any such sign nearest to the building against which it is placed shall not be a greater distance than two feet from such building.

No illuminated sign shall be permitted to project beyond the curb line.

All sides of every such sign designed to be illuminated shall be illuminated each and every night for a no less period of time than from dusk until the hour of 9:30 p. m.

The authority granted for the erection of any such sign may be revoked at any time by order of the Mayor or of the City Council, and any inspection to permit fees paid to the city for such sign shall not be refunded in case of any such revocation.

"854. **Compliance with Rules.**) Every sign erected and maintained under and pursuant to the provisions of this Article shall comply with the provisions of this Article, and be installed in a safe and secure manner.

"855. **Penalty.**) Any person or corporation who shall erect or maintain an illuminated sign, or use any electric current or other illuminant in any sign in violation of any of the provisions of this Article shall be fined not less than fifty dollars, nor more than one hundred dollars for each offense, and shall be fined a further sum of ten dollars for each and every day on which he or it shall permit or cause any such sign to be erected or maintained or any electric current or other illuminant to be used therein in violation of any of the provisions of this Article; and in addition to such penalties the Commissioner of Gas and Electricity shall for any violation of any of the provisions of this Article compel the cutting off and stopping of electric current or other illuminant supplied to any such sign, and if deemed necessary or advisable by him he shall order such sign removed.

"710. **Illuminated Roof Signs.**) (Permit to be obtained from Building Department. Fee for electrical inspection same as for Flat Signs, Section 851. To be reinspected annually.)

ENCLOSING LIVE PARTS

All exposed live parts of apparatus must be guarded against accidental contact either by the provision of suitable enclosures or by so locating the apparatus that only electricians duly qualified to handle the same can come in contact with it.

All apparatus, with exposed live contacts which in their ordinary operation produce arcs, must be provided with suitable enclosures or so located that nothing of a combustible nature will be in close proximity to the same.

These rules shall not apply to trolley wires or other exposed live parts which from the nature of their use cannot be enclosed.

It is the intent of this rule to require such protection of live parts of electrical apparatus as will eliminate, as far as possible: (1) Accidents from contact with live parts. (2) Fires which may result from sparks or flames produced in the operation of electrical apparatus.

The protection of live parts against accidental contact will be required on all apparatus where a person not familiar with the

BRASCOLITE

The Ideal Light for Every Purpose



Type W. G.

Architecturally correct details and proven efficiency are combined in all BRASCOLITES.

BRASCOLITE is the fundamentally correct lighting fixture, in which the component parts not only produce the highest quality of illumination, but when assembled produce a structure of harmonious beauty. The principle of Brascolite efficiency can be built into units (single or multiple) of any size and to harmonize with any architectural treatment—a distinct advantage—giving a range of adaptability without limit.

Write us for a copy of catalog No. 8, also Architectural series of bulletins.

LUMINOUS UNIT COMPANY

ST. LOUIS, U. S. A.

Division of the St. Louis Brass Mfg. Company

BRANCH OFFICES

New York	Philadelphia
Cincinnati	Minneapolis
Los Angeles	Seattle
Atlanta	New Orleans
Chicago	Denver
Oklahoma City	Kansas City
Detroit	Boston

NORTHERN ELEC. CO., LTD., Montreal, Que.,
Canadian Distributors.

electrical apparatus may accidentally come in contact with such live parts.

The protection of arcing contacts will be required on all apparatus so situated that such arcing contacts might produce fires.

Protection of live parts may be obtained by so locating apparatus that the live parts are not easily accessible. This may be accomplished by elevating the apparatus eight feet or more above the floor; by locating the apparatus in an engine room or other location where accessible only to authorized electricians.

Protection of arcing contacts may be obtained by locating such arcing contacts in fireproof locations where there is no liability of combustible material being placed near them.

Where there are live parts which can not be protected by location as described above then such live parts must be provided with such enclosures as will afford the protection required above.

It is intended that the enclosure referred to will be provided in the design of the apparatus and will be supplied by the manufacturer.

The effect of the rule on various classes of apparatus where such apparatus cannot be protected by its particular location as described above, is herewith given:

TERMINALS OF APPARATUS.

Exposed binding posts must not be used unless all live parts of both binding post and connections to the same are so insulated that contact cannot be accidentally made with the live parts.

For portable apparatus using flexible cord connections the conductors may enter the apparatus and be connected directly to the interior conductors if provided with a means of strain relief; or a separable plug may be used with the connecting cord terminating in the separable part. Separable plugs should be so connected that there will be no exposed live parts when the plug is disconnected.

For non-portable apparatus, the design should be such as to allow the direct entrance of conduit to the interior of the apparatus and the connection of the conductors to the interior binding posts or conductors, or a junction box may be attached to the apparatus frame and connections made within it.

For motors, or other apparatus, so installed that a small adjustment of position can be made for belt tension, or similar purpose, a short length of flexible steel conduit or of steel armored cable must be used to allow for the adjustment, and care shall be taken that the fastenings shall be secure and permanent.

MOTORS.

Commutators must be protected against accidental contact. This may be accom-

plished by guards so designed that accidental contact cannot be made with live parts, or by a special design of the motor itself. Where protection of arcing contacts is required the commutator must be so enclosed that sparks from the commutator cannot get outside the enclosure. If doors or covers are used as guards they must be attached to the motor by hinges.

For protection against contact, openings in guards must not exceed one-half inch in any dimension except when the distance of the live parts from the guard is more than four inches, openings may be not to exceed three-fourths inch. For protection against fire, opening in guards must not exceed one-tenth inch in any dimension. (This protection is not to be considered as affording a means to prevent explosions.) Opening of dimensions exceeding those given above may, where they afford equivalent protection, be accepted by the department.

This ruling applies to motors of all sizes including the smaller types of motors used on electric fans, vacuum cleaners and the various motor-operated household and other appliances.

CONTROLLERS.

Manually operated starting boxes, speed controllers and the like must have enclosures of such design that all live parts are completely enclosed and must be so arranged that the device can be operated from the outside of the enclosure. This protection must be obtained by the design of the device. The placing of a manually operated starting box inside a metal cabinet, where it is necessary to open the door of the cabinet to operate the device, is not acceptable.

Automatic starting boxes and similar electrically controlled devices must be placed in standard cabinets provided with hinged doors.

AUTOMATIC CONTROL BOARDS.

Including automatic elevator controllers and similar devices, unless placed in fireproof locations and guarded (by screens or location) so that unauthorized persons cannot make contact with same, must be placed in metal enclosures.

For elevators located in fireproof rooms the room must be used only for the enclosure of the elevator machinery and the electrical control apparatus. The entire room, including floor, must be of fireproof construction. For the fireproofing of the floor concrete, tile or sheet metal must be used. Concrete must be at least three inches thick and when placed over wood floors all openings through such floors must have the exposed ends of boards covered by sheet metal. Sheet metal used as a floor covering must be not less than No. 14 U. S. S. gage. Ceilings if of wood may be covered by metal lath and plaster or by transite board not less than one-fourth inch thick. All doors to the room must be kept locked.

REFLECTOLYTE

Lighting Fixture

Specifications



SUPREME

"Supreme" REFLECTOLYTE Lighting Fixtures


shall be the one piece-glass, wholly-enclosing type, consisting of a bell-shaped metal body or holder within which there shall be a vitreous porcelain enameled steel reflector detachably held in position by three spring fingers. This reflector shall be positioned so that the lower edge of the body and reflector and the lamp filament, shall lie within a horizontal plane. Enclosing these elements, and securely supported by the metal body or holder, there shall be an acorn-shaped ornamental Urn, blown of translucent glass of low absorption and high diffusing power.



STANDARD

"Standard" REFLECTOLYTE Lighting Fixtures

shall be the two-piece open type, consisting of a drawn steel upper member provided with angularly disposed, oppositely inclined reflecting surfaces, which shall be vitreous porcelain enameled and not less in cross-section than 94% of the extreme outside diameter,—and a diffusing bowl blown of special white glass of low absorption and high diffusing and reflecting power, which shall be suspended below the reflecting member by means of flexible supports, each consisting of an eye and link—the eye securely attached to the reflector, and the link of such length as to correctly position the bowl beneath the reflecting member.



JUNIOR

"Junior" REFLECTOLYTE Lighting Fixtures

shall be the open two-piece-glass type, consisting of a metal holder with a double set of perforation for adjustment, a dense depolished opal glass reflector with angularly disposed, oppositely inclined reflecting surfaces—and a hemispherical diffusing bowl blown of special translucent glass of low absorption and high diffusing and reflecting power. These glass members must be adjustably supported by three rods, the ends of which are formed to hook into the slotted perforations in metal holder.



The REFLECTOLYTES specified and illustrated are "close" or "ceiling" types; suspended types are also made—in a variety of styles and sizes—single, multiple and candle units, with brackets to match, embracing simple and inexpensive as well as highly ornate types, suitable for illuminating Public and Office Buildings, Banks, Department and Retail Stores, Churches, Schools, Hospitals, etc. See SWEET'S Catalogue.

List of satisfied users of REFLECTOLYTES and catalog sent on request.

The Reflectolyte Company

Lighting Specialists

914-V Pine Street

St. Louis, Mo., U. S. A.

AUTO STARTERS, COMPENSATORS, ETC.

Where there are no exposed live parts no special protection is required. Where no-voltage or overload coils having exposed contacts are used such contacts must be enclosed.

RESISTANCE GRIDS.

All types of resistance grids must be protected against accidental contact either by location or by suitable ventilated enclosures. It is intended that the protective enclosure for grids shall be furnished by the manufacturers as a part of the device.

CIRCUIT BREAKERS.

Circuit breakers must be enclosed in metal cabinets and, if used in place of a switch, must be operable from the outside of the enclosure.

SPECIAL PANEL BOARDS

Such as dental boards and similar apparatus must have live parts protected.

ELECTRICAL HEATERS.

Electric heaters of all types must have no exposed live binding posts or contacts. This does not apply to the heating element.

RECEPTACLES NEAR FLOOR.

Receptacles located within thirty inches of the floor must be of the protected contact type. Receptacles of a type having Edison bases, and receptacles having bare contacts when the attachment plug is removed, will not be approved unless located more than thirty inches from the floor.

KNIFE SWITCHES.

Rule 24b, 2nd paragraph, reads as follows: Knife switches, except on panel boards, switchboards, and distributing centers, must be of the safety enclosed type. Safety enclosed switches must be of an approved design and arranged to be operated from the outside of the enclosure. They shall be so marked as to indicate, without opening the enclosure, whether the switch is in the 'on' or 'off' position. They shall be so constructed and installed that the fuses, if fuses are used, will be dead when the switch is in the open position; and, except in the case of double-throw and alternating current motor starting switches, designed for 'starting' and 'running' positions, must be so constructed and installed that the blades of the switch will be dead when the switch is in the open position. If, in order to comply with the above, the incoming wires must be connected to certain terminals, such terminals must be marked 'line.'

Note. "Panelboard" means a single panel or assembly of panels containing busses, fuses and in some cases switches, to control lights, fan motors, and similar devices of small individual as well as small aggregate capacity, placed in or against a wall or partition and accessible only from the front.

"Switchboard" means a large single panel, frame or assembly of panels on which are

mounted (on the face or back or both) switches, fuses, busses, and usually instruments.

"Distributing center" means a single panel or assembly of panels containing busses, fuses and in some cases switches to control lights, motors and similar devices of large individual as well as large aggregate capacity, placed in or against a wall or partition and accessible only from the front.

In the case of apartment buildings with one circuit to an apartment a safety switch may be used for each apartment up to and including three switches and such switches will be accepted as service switches. Where there are more than three circuits a main line service switch of the safety type must be provided with a separate cabinet for the fuses.

This rule applies to all knife switches manually operated. Automatic switches may be enclosed in standard cabinets, with hinged doors.

EDISON PLUG CUTOUTS.

After January 1, 1922, Edison plug cutouts, except those used in connection with safety switches, must be of the dead front or safety type. Where such cutouts are used in apartment buildings the enclosing covers should be provided with a means of designating the location of the circuit.

STRIP FUSES.

Strip and link fuses will not be accepted. All fuses must be of the plug or cartridge type.

CABINETS.

Where devices are placed in metal cabinets, such cabinets must comply with the specifications on cut-out cabinets and boxes.

ENFORCEMENT OF RULES.

It is the intent of these rules to ultimately obtain from the manufacturer a class of apparatus which in its inherent design will provide the protection sought. In most cases this very desirable protection from both accident and fire can be obtained without any material increase in the cost of production. The department will, in obtaining a strict compliance with the provisions of the rule, extend every warranted concession, but it requests and expects the active co-operation of all concerned.

The rules will be enforced on all new installations and applied to all apparatus, except as noted below, whether the apparatus being installed is new or used. Where apparatus is moved from one location to another within the same building and for the same owner, or where a concern moves from one location to another, this rule shall not apply provided the apparatus has been previously approved by the department and is in good condition. On new installations, used apparatus, other than that exempted above, must be remodeled to comply, as far as practicable, with these rules before being again placed in use.



Office buildings, factories and stores find Central Station Service cleanly, dependable and economical. Many of Chicago's largest buildings are using EDISON SERVICE entirely; have used it from the start. Many building owners and managers have found it profitable to discard their private generating plants and adopt EDISON SERVICE—a very important factor to consider for your next building.

The true beauty of a home is greatly enhanced by electric light. During the day, the uses of electricity in the homes are manifold; electric irons, toasters, vacuum cleaners, dish washers, electric washing and ironing machines and numerous other appliances help the housewife to conserve time, labor and money.

Phone, Randolph 1280—Contract Department
Commonwealth Edison Company
Edison Building, 72 West Adams St.
CHICAGO

RULES AND INFORMATION PERTAINING TO ELECTRIC SERVICE, METERS AND WIRING OF COMMONWEALTH EDISON CO.

SPECIAL NOTICE.

The following Rules and Information of the Commonwealth Edison Company, pertaining to electric service, meters, wiring and motors are an EXCERPT from a revision and addition to those Rules and Information published by this Company in 1915. These revised rules have, however, up to date not been published in book form by this Company. The publication in book form will be issued on or before January 1st, 1921.

These Rules and Information are subject to change from time to time and this fact should be borne in mind by those consulting this publication.

SERVICES.

The Company will not be responsible for mistakes of any nature whatever, resulting from information relative to the character of its service or location of its mains, given verbally or over the telephone, unless such information is confirmed, in writing, by the Company.

Standard Forms of Service.

The Company's standard service for light and power is available in different forms, the kind of service available, depending upon the locality and the amount of energy required, as follows:

Direct current, three-wire, low tension Edison Service, at approximately 115-230 volts, available for light and power only within the district boundaries described as follows:

North Side.

South of Menominee Street, east of Halsted Street and the Chicago River.

West Side.

West of the Chicago River to Racine Avenue, between Kinzie Street and 16th Street (except on West Madison Street, where it extends to Ashland Avenue), and from Sangamon Street to the river from 16th to 22nd Streets.

South Side.

From the Chicago River to 31st Street, between Stewart Avenue and Cottage Grove Avenue. From 31st Street to 37th Street, between the New York Central Railroad and Cottage Grove Avenue, also from 37th to 39th Streets, between the New York Central Railroad and Rhodes Avenue.

The above described boundary lines of the direct current districts are approximate and inquiry should be made at the office of the Distribution Division, Engineering Department, to ascertain what kind of service is available at particular locations near these boundary lines. These boundaries are subject to changes from time to time and the direct and alternating current lines overlap in some places.

Overhead.

The Company will provide, at its own expense, for any customer, one overhead service connection not exceeding 115 feet in length. Where the length of a service exceeds 115 feet, a pole or other suitable support with necessary fixtures for the attachment of wires must be provided for each 110 feet, or fraction thereof, of such excess length. The cost of the poles, fixtures and wire in excess of that required for a service 115 feet in length must be borne by the customer.

Not more than one service will be installed for lighting or for the same class of power in the same building except at the customer's expense.

Service outlets should never be more than thirty (30) feet nor less than twelve (12)

feet from the ground. For buildings of two or more stories in height, the outlet should be brought out at the ceiling of the second floor.

Where a service outlet is terminated on a post supporting a porch or on a horizontal timber attached to the post, galvanized steel braces of the dimensions given in the following sketches must be securely lagged to two sides of the post or timber by $\frac{1}{4}$ "x2 $\frac{1}{2}$ " lag screws in such a manner that the post or timber will be securely held in place.

The service outlet must be so located that there will be at least 24 inches clearance between it and any telephone or signal wires where attached to the building, and at least 36 inches clearance between the service drops of both systems in an open span, in accordance with the rules of the Department of Gas and Electricity of Chicago.

Where the position of a building is such that the service outlet cannot be located at a point which may be reached by a single span from the pole line, or where the outlets of a low building must be brought out less than 12 feet above the ground, some form of intermediate support of suitable strength and height must be provided by the customer.

When the intermediate support is a pole placed in the ground, it must be of cedar, 6 inches in diameter at the top and not less than 16 feet long, 3 feet of which is to be set in the ground. This pole must be painted with waterproof paint.

When the support consists of a riser attached to the building to which electricity is to be furnished, the riser must be of clear, sound, straight-grained fir, pine, or cypress, at least 4 inches by 4 inches and secured to the building by bolts which pass through the brick work or timbers. This riser must be painted with waterproof paint.

Where the close proximity of the pole to the building prevents the installing of a service drop in the usual manner, the service outlet must be brought to a point opposite the pole. The Company will then run the service drop down the pole and connect.

Underground.

Where the space beneath the sidewalk is excavated, the service cables will be terminated at a point about three feet inside the curb wall, and the wiring installed by the customer must be brought to the nearest service entrance, if there be one within 50 feet of his premises.

Where there is no sidewalk excavation and where there is a basement at the property line, the service cables will be terminated at a point about 3 feet inside of such basement wall.

Where no basement is available at the property line, the service will be extended underground from the property line to any point designated at the customer's expense, but in no case will the service be terminated in any place which is liable to be used for coal storage.

On account of the obstacles met with in the installing of an underground service lateral, it is impossible for the Company to determine in advance the exact location where the service cables will enter the building. Because of this uncertainty the service cabinet should not be installed until after the Company has completed the laying of the duct or pipe into the building.

Where the service cables installed by the Company are to supply more than one building, the Company will install a junction cabinet at the point of entrance of the service stub, enclosing the service cables.


HENRY NEWGARD & Co.

Established 1882

Electrical Contractors, Manufacturers and Engineers

WE INSTALL

Power and Light Plants, Generators and Motors, Electric Light and Power Wiring for Factories, Churches, Schools, Colleges, Theatres, Offices, Stores and Residences. Estimates cheerfully furnished for this class of work in any part of the United States.



Corn Products Refining Co. Plant, No. Kansas City, Mo.

WE MANUFACTURE

Switchboards, Panelboards, Steel Cutout Cabinets, Junction Boxes, Service Switch Boxes, Theatre Stage Plugs, Experimental Switchboards and appliances for High Schools and Colleges.

Newgard Receptacles and other electrical specialties.
Dynamos and Motors Repaired.

Telephone Haymarket 991 All Departments

947-955 Washington Boulevard

CHICAGO, ILL.

Branch, MILWAUKEE, WIS., Tel. Grand 613

The customer's service conduit should be terminated at, and locked into the junction cabinet. A sufficient length of wire must be left to permit the Company to make the connection to the service cables.

Where the service cables are to supply the building into which they enter only, the service switch must be installed by the customer and located at the service stub in such a manner that the cables will be entirely enclosed. If this is not practicable, a junction cabinet may be installed by the customer, and conduit be provided connecting the junction cabinet with the service switch cabinet; this conduit to be of sufficient size to contain the lead covered cables.

In case the customer does not wish to bear the expense of an underground service across his property, the underground service will be brought up on a pole at the lot line. The pole and overhead service to the building will be installed at the customer's expense, unless the customer is willing to permit the Company to use the pole to supply other customers.

C. E. Co. Metering Panels.

In any building where the service is supplied through the Company's standard service and meter panel equipment, the contractor must secure from the Inspection Bureau a service location.

The contractor in such cases will not be required to install the usual service switch and cutout, but will extend the conduit to the service location secured from the Inspection Bureau, terminating the same with a piece of flexible metal conduit of sufficient length to reach to the bottom of the panel, this conduit to be fitted with locknut and bushing on the end and not less than one foot of wires projecting from the end of such flexible conduit.

The additional meterboard will be installed, and the connection of the customer's mains thereto will be made by this Company at the time the meter is installed.

No person other than an authorized representative of the Company will be permitted to make any alterations of the metering panel or other distribution facilities. No conduit, cutout cabinet, or other device will be permitted to be attached to or mounted on such metering panel other than that installed by the Company.

Where a metering panel is provided, the contractor must not locate or make provision for meters to be located at any place other than on the metering panel. If wiring is being installed for both light and power in any part of the building, it will be necessary to run both lines to the metering panel. Exceptions to this rule will be permitted in the case of building risers serving several customers.

Transformer Vaults.

Where a separate transformer installation is necessary, and local conditions are such that the transformers cannot be installed in the usual manner on poles, the installation will be made within the building in a suitable vault, constructed at the expense of the customer, in accordance with the following specifications:

1. GENERAL.

The vault, or rooms, should be located in an accessible part of the building, in space free from pipes or other facilities, which may require attention periodically, and must be constructed of fireproof materials and in accordance with Rules 14 and 45 of the Electrical Code of the Department of Gas and Electricity of the City of Chicago. The room must be provided with a door of standard height not less than 36 inches wide, and in case the transformer units are larger than 50 K. W. the door should be 48 inches wide. The door must be hinged and provided with a hasp suitable for a standard padlock, which will be provided by the Company. The location of the door must be such as to permit ready handling of the transformers in and out of the room.

In case the room is above the ground floor, unless there is adequate elevator service available, permanent facilities must be provided by which transformers weighing 5,000 lbs. each can be handled to and from the transformer room. The entrance to such rooms must be readily accessible if above the floor level.

Suitable lighting should be provided within the vault.

2. 4,000 VOLT SYSTEM.

(a) Floor Space: The vault should be rectangular in form if possible, the width to be not less than 6 feet in installations made up of transformers of less than 50 K. W. and not less than 10 feet in larger installations. The floor area must be not less than the amounts following:

Single Transformers.

Up to and including 25 K. W. 36 sq. ft.
26 to 100 K. W., inclusive..... 50 sq. ft.

Two Transformers.

Up to and including 50 K. W., total capacity 40 sq. ft.
51 to 150 K. W. 60 sq. ft.

Three or Four Transformers.

Up to and including 60 K. W. 150 sq. ft.
61 to 200 K. W. 225 sq. ft.
201 to 500 K. W. 300 sq. ft.

The space for larger installations varies largely with local conditions and must be determined after consultation with the Distribution Division of the Company.

(b) Head Room.

The vault must have a clear height of at least 8 feet from floor to ceiling.

(c) Ventilation.

To protect transformers from overheating, air inlets and outlets of ample dimensions must be provided. The inlets must be placed not more than one foot from the floor of the room and must be arranged to take in air from outside the building. There should be an inlet opposite each transformer in the larger installations.

The air outlets must be not less than 1 foot below the ceiling and should be terminated outside the building in suitable ventilation outlet.

Where openings are made direct to the outside air, they must be provided with suitable louvers to protect the openings from the entrance of rain and snow, and if accessible to persons, the openings must also be protected by suitable wire screens.

The inlets and outlets must each be not less than the following areas:

Up to and including 25 K. W. 1 sq. ft.

For larger installations, the area must be not less than 3 sq. in. per K. W. of transformer capacity.

(d) Wiring.

The meter and secondary service switch must be placed outside the transformer room, in an approved location. The connections from the secondary service switch to the vault must be provided by the customer.

The work of installing the primary cables, transformers, and secondary wiring within the vault, will be performed by the Company at the expense of the customer, provided, however, that the Company will furnish and retain ownership of the transformers and primary fuses, and provided further that the amount paid by the customer shall be the estimated cost of making the transformer vault installation less the estimated cost of making an equivalent transformer installation on poles.

3. TRANSMISSION SYSTEM.

Transformers supplied from the transmission system at voltages above 7,500, require greater floor space and head room. Vaults for such must be constructed in accordance with the specifications on file in the Engineering Department of the Company, copies of which will be furnished upon request.

WIRING.

Meter Connections.

Wiring must be so arranged that a separate meter may be installed for each class

WHITE CITY ELECTRIC CO.

Electrical Contractors and Engineers

COMPLETE ELECTRICAL INSTALLATIONS

LIGHT

POWER

TELEPHONES

Telephone, Main 803

CHICAGO

14 North Franklin Street

A PARTIAL LIST OF BUILDINGS THAT HAVE BEEN DONE
THE WHITE CITY WAY WHICH REPRESENTS
EFFICIENCY AND SERVICE

Installation	Architect
Butler Bros. Bldg.	Graham, Anderson, Probst & White
Tribune Bldg.	Jarvis Hunt
Chicago Beach Hotel.	Geo. C. Nimmons
Excelsior Motor Mfg. & Supply Co.	Walter Ahlschlager
Gulbrandsen-Dickinson Co.	A. S. Alschuler
Dickinson Seed Co.	Martin C. Schwab
Madison & Kedzie Bank.	Cady & Crosby
Hummer Engine Works, Springfield.	Lockwood, Greene Co. (Engrs.)
Morrison Hotel Bldg.	Marshall & Fox
Camp Knox, Louisville.	E. H. Bennett
Unity Bldg.	Rapp & Rapp
Covent Garden Theater.	Davidson & Weiss
Rand McNally Bldg.	Holabird & Roche
Seattle Terminal Bldg., Seattle.	Geo. C. Nimmons
Midway Gardens.	Frank Lloyd Wright
Chicago Art Institute.	Shepley, Ruttan & Coolidge
Presbyterian Hospital.	Berlin, Swern & Randall
Delaware Apartments.	John Nyden
Swedish Covenant Hospital.	Edw. Benson
Oscar Mayer & Co.	Woltersdorf & Bernhard
Winnebago County Courthouse.	J. W. Royer
Second Regiment Armory.	Jas. B. Dibelka
Chateau Theater.	August Wilmanns
Hurley Machine Co.	The Arnold Co. (Engineers)

of service supplied under the Company's schedule of rates, as follows:

Rate A.

Available for any customer using the Company's standard service for lighting purposes, or for both lighting and power purposes, provided that electricity will not be furnished hereunder for welding machines, wireless telegraph apparatus or other power apparatus in which the use of electricity is intermittent or subject to violent fluctuation and the operation of which may interfere with lighting service.

1. Where the rated capacity of the customer's installation is $1\frac{1}{2}$ K. W. or less, the maximum demand is determined in accordance with a table set out in the rate schedule which provides for different values of demand for commercial and residence lighting. The arrangement of meter connections of such installations must be in accordance with the following regulations:

(a) The wiring of residence and commercial installations must be arranged for separate watt-hour meters.

(b) The lighting of halls, entrances and basements of apartment buildings will be considered as commercial lighting, provided that where the hall, entrance and basement lighting installation has a rated capacity of 200 watts or less and where the owner occupies one of the apartments in the building as his place of residence, such installation will be considered as residence lighting during the period of such occupancy, and may be connected to the meter for the owner's apartment lighting, if desired.

(c) Where apartments and stores or shops are in the same building the apartment lighting will be considered as residence lighting and the store or shop lighting will be considered as commercial lighting, and the wiring should accordingly be arranged for separate meters; provided, however, that if the customer desires, both installations may be combined on one meter, and the combined installation will be considered as commercial lighting. (For combined installations exceeding $1\frac{1}{2}$ K. W., see 2-b below.)

(d) Where a portion of a store or shop is used as living quarters, and the wiring is arranged for a single meter for both the store or shop and the living quarters, the installation will be considered as a commercial lighting installation.

2. (a) Where the rated capacity of a customer's installation is more than $1\frac{1}{2}$ K. W. the wiring must be arranged for the installation of demand meters.

(b) In case the residence and commercial lighting installations of a customer have an aggregate rated capacity of over $1\frac{1}{2}$ K. W. and are in the same building, both installations may, if desired, be arranged to be connected to one watt-hour meter with demand meters.

Rate B.

Power service is supplied under this rate, and is defined as "electric service used for any purpose other than lighting." Service for photographic printing, bath cabinets and other kinds of equipment which are not used for general illumination, will be considered as power service and may be served under Rate B, if desired.

In the case of direct current installations having a rated capacity of more than $1\frac{1}{2}$ K. W., the maximum demand is measured, and provision must be made for setting demand meter.

In the case of alternating current installations having a rated capacity of 10 H. P. or more, provision must likewise be made for setting a demand meter.

Rate C.

The lighting and power service of large users may be combined under Rate C. However, on the alternating current system a separate service and meter may, at the option of the Company, be provided for the lighting service, and in such cases the wiring must be arranged for meters accordingly.

Residence and Apartment Loads.

Every residence and apartment lighting installation which does not exceed 2640 watts must have a 2-wire service main and 2-wire meter loops, as such an installation will be connected to the Company's system by two service wires at 115 volts. Where the installation exceeds 2640 watts it must be wired for a 3-wire service and meter.

Commercial Loads.

Every business lighting installation of over 1500 watts must have a 3-wire service main and 3-wire meter loops. If the installation is 1500 watts or less, it must be wired with a 2-wire service main and 2-wire meter loops. Motors operating on 115 volts and heating appliances on the lighting service will not be considered in determining two or three wire installations where the rated capacity of such equipment does not exceed twenty-five per cent of the lighting load.

Mixed Loads.

On installations where there are stores and apartments in the same building the rule governing the service and meter installations is as follows:

To the total connected wattage of the stores add $\frac{1}{4}$ of the connected wattage of the apartments, and if the total is 1500 watts or less, the service mains and meter loops must be two wire. If this wattage, however, is in excess of 1500 watts, the service mains must be three-wire, but the meter loops will be governed according to the rules above on residence and commercial lighting.

Switchboards.

Specifications and blueprints for service and meter switchboard installations must be submitted to the Distribution Division of the Company for approval before construction on the switchboard is begun.

Fuses must be so arranged that they will be readily accessible for the purpose of replacement, and to this end, it is recommended that no more than three rows of switches be placed on a switchboard.

To prevent overheating of fuses and cables, it is recommended that all the lugs have a conductivity not less than 60% of that of pure copper and that their cross sectional area be such that they will not be required to carry more than 600 amperes per square inch continuously. They should have a bolting contact surface of not less than 1 square inch for each 150 amperes of current.

The general arrangement of the connections on the back of the board must be such as to make it possible to make repairs or alterations with a reasonable degree of facility and safety while the board is in service.

The bus bars must be rigidly supported so as to prevent any sag and the arrangement of the feeder cables between the terminal of the conduit system and the back of the switchboard must be made in a systematic and orderly manner and the cables must be segregated as far as possible with a view to minimizing the possibility of serious interruption to the service. For details concerning the installation of meter test links and other matter pertaining to switchboard meters, see "Switchboard Meters."

APPLIANCES.

Welders and Furnaces.

A separate service outlet should be installed for welders and furnaces when the connected load exceeds 40 K. W. Separate meter loops must be installed for all electric welders and similar apparatus where the use of electricity is intermittent and subject to violent fluctuations, and where the rated capacity of such equipment is more than 25 per cent of the aggregate rated capacity in horsepower of the motors and other non-intermittent power using equipment installed in the premises.

X-Ray and Wireless Telegraph Coils.

A separate outlet must be provided for X-Ray apparatus, wireless telegraph coils and similar devices. The cost of the serv-

EFFECTIVE SERVICE

Delivered in Times of Stress

Enables us to with confidence submit to the Public the following list of industries and enterprises, for whom we installed the electrical lighting and power equipment during the recent industrially active period.

HOTELS:

Parkway Hotel
Parkway Addition
W. W. Ahlschlager, Architect
Webster Hotel
Fridstein & Co., Engineers
Somerset Hotel
S. N. Crowen, Architect
Rogers Park Apmt. Hotel
B. Leo Steif & Co., Architects

THEATRES:

New Majestic Theatre, Dallas, Tex.
Indiana Theatre, Terre Haute, Ind.
John Elbersson, Architect

PRINTING AND ADVERTISING:

Reuben H. Donnelley Corporation
Chas. G. Atkins, Engineer
Buckley Dement & Co.
Robt. S. Smith, Architect

PACKING INDUSTRY:

John Agar Packing Co.
Illinois Packing Co.
David Levi & Co.
Brennan Packing Co.
Henschien & McLaren, Archts.
Miller & Hart

FOOD PRODUCTS AND REFRIGERATING:

Beatrice Creamery
W. W. Ahlschlager, Architect
Bunte Brothers
R. E. Schmidt, Garden & Martin, Archts.
American Coconut Butter Co.
Francisco & Jacobus, Archts. & Engrs.
McNeill & Higgins Co.
W. L. Fergus, Engineer
Reid Murdoch Co., Hammond, Ind.
Thos. W. McNeill, Engineer

John Sexton & Co.
A. S. Alschuler, Architect

FOUNDRIES AND MECHANICAL

General Motors Corp., Central Foundry and Jackson Church Wilcox Plant in Saginaw, Mich.
Cribben & Sexton Munitions Plant
Frank D. Chase, Inc., Ind. Engrs.
Dallas Brass & Copper Co.
W. G. Uffendell, Architect
Stewart Mfg. Co.
Chicago Flexible Shaft Co.
S. N. Crowen, Architect
Gartland McCarthy Co.
Austin Co., Engineers

TANNERIES:

Griess-Pfleger Tanning Co., Waukegan
Gutmann & Co.
Chas. G. Atkins, Engineer

BAKERIES:

Gordon Baking Co.
Arthur Woltersdorf, Archt.
Piper Baking Co.
W. W. Ahlschlager, Architect

MISCELLANEOUS INDUSTRIES:

Edison Electric Appliance Co.
W. G. Uffendell, Architect
General Electric Co., Engrs.
Northwest Street Lighting Substation
City of Chicago
Economy Fuse & Mfg. Co.
W. G. Uffendell, Architect
Rothacker Film Mfg. Co.
W. W. Ahlschlager, Archt.
Saginaw Table & Cabinet Co.
Saginaw, Mich.
Heppes Nelson Roofing Co.
Austin Co., Engr.

J. N. PIERCE

S. N. TIDEMAN

R. A. MORRISON

PAUL PIERCE

Pierce Electric Company

Not Incorporated

Contracting Engineers

215 West Randolph St.

TELEPHONE
MAIN 3401

Chicago, Illinois

ice connection for wireless telegraph and X-Ray apparatus will be charged to the customer, except X-Ray machines requiring not more than 2 K.W., which may be connected to the lighting service and meter.

Where X-Ray and wireless telegraph apparatus require more than 2,000 watts, the coils must be operated at 230 volts.

In connection with wireless telegraph equipment, a suitable condenser and spark gap must be installed by the customer. No ground will be permitted in connection with the equipment except that on the side of the oscillation transformer to which the antennae are connected. This rule may be waived when a motor generator set is employed to convert the electricity received from the Company's service into another form. All high tension wiring used in connection with the apparatus must be kept away from the meter and wiring of the building.

Electric Ranges, Ovens and Heating Appliances.

Electric ranges and other heating appliances in which the aggregate rating of the heating units is not more than 2,000 watts, will be connected for 115 volt, 2-wire service. Where the aggregate rating of the heating units exceed 2,000 watts they must be so arranged that they may be connected to a 3-wire 115-230 volt circuit, and the units must be balanced as nearly as possible on each side of the circuit.

Electric ranges and heating appliances for family use must be connected to the lighting service, if one is installed.

Electric ranges and ovens installed in places of business must be wired to the power service, if one is installed.

Nameplates.

All electrical equipment such as motors, welders, furnaces, X-Ray and wireless coils, heating utensils and the like, must be provided with nameplates showing the rating of the apparatus in kilowatts, horsepower, kiloamperes or amperes, volts, cycles, phase, and where necessary character of current required for its operation.

MOTORS.

Direct Current.

Direct current motors of 1½ H.P. and smaller may be operated at either 115 or 230 volts. Motors larger than 1½ H.P. must operate on 230 volts.

A starting resistance is recommended in connection with all direct current motors, but motors not larger than ½ H.P. of the shunt type, ¾ H.P. compound and 2 H.P. series wound, not requiring a starting current in excess of the values given in the starting current tables, be installed without starting resistance.

Direct current motors of 10 H.P. and smaller must generally be wired so that they may be connected to the lighting meter.

Alternating Current.

All alternating current motors, which start frequently, such as those operating coffee mills, meat grinders, shoe repairing machines, electric pianos, pumps, carbonators, etc., must be wound for and connected for operation on the Company's 230 volt service, except that the repulsion induction type of motors of less than ¾ H.P. may be operated on 115 volt service.

Split phase motors which are not intermittent in character of ¼ H.P. and smaller, be operated on 115 volts where the starting current does not exceed 15 amperes.

The wiring must be so arranged that all motors of the repulsion induction type of 1 H.P. and less, or of the split phase type of ½ H.P. and less, may be connected to the lighting service and meter. Either type of motors above these sizes must be wired for separate service and meter. Where the aggregate rating of two or more motors of the above sizes installed does not exceed 2 H.P., they must be wired to the lighting service. This will require three-wire service and

three-wire meter loops where 230 volt motors are installed. Where larger motors are installed, or where the aggregate is more than 2 H.P., the wiring must be so arranged that all motors can be connected to a separate service and meter.

No motors larger than 5 H.P. will be supplied on the single phase system, except by special permission given in each case by the Distribution Division of the Company.

Motors of 5 H.P. or more are supplied from the three-phase system in a large part of the alternating current territory, but inquiry should be made of the Distribution Division of the Company as to the proximity of three-phase lines to any particular location where such power may be desired.

Three-phase service will not be provided for installations aggregating less than 5 H.P., unless the customer deposits with the Company a sum equivalent to the excess cost to the Company of installing a three-phase service and meter over and above the cost of installing a single phase service and meter. In case the customer's power installation shall subsequently be increased to a total rated capacity of 5 H.P. or more, the Company will return the amount of the deposit to the customer.

Motors of 50 H.P. and larger rated capacity, if operated at variable speeds, or if normally started frequently, must be of the round rotor or slip ring type. Such motors, when used at constant speed and not started frequently, may be of the squirrel cage type.

Motors of 100 H.P. or larger rated capacity must preferably be of the synchronous type, where it is practicable to use a synchronous motor for the work to be performed.

All motors of 7½ H.P. rating, and above, must be equipped with starting apparatus.

Motor starting devices must be equipped with a no-voltage release which will cause it to be thrown to the starting position or the circuit opened entirely in case of an interruption to the power supply. For motors of large capacity which are difficult to start, the no-voltage release must have a time element relay, which will prevent the opening of the circuit in the event of momentary voltage fluctuation.

In the case of the star delta starting method, the starting switch must be so arranged, so that it cannot be thrown into the starting position.

Reverse phase relays or hatch limit switches must be installed on all three phase elevator, crane and similar installations, as required by the Department of Gas and Electricity of Chicago.

Starting Current.

The instantaneous current drawn from the line by a motor of any given rated horsepower, with the starting device (if any be required) in the starting position, must not exceed the value for such rated horsepower as shown in the following tables under the heading "Amperes":

Single Phase—60 Cycle.

Horsepower	Volts	Amperes
½ H.P. and below.....	220	15
¾ H.P. and 1 H.P.	220	20
		Amperes per H.P.
1¼ H.P. up to and including		
5 H.P.	220	15
6 H.P. and above.....	220	11


Three Phase—60 Cycle.

Horsepower	Volts	Amperes per phase per H.P.
5 H.P. and below.....	220	13
6 H.P. up to and including	30	
¾ H.P.	220	9
31 H.P. and above.....	220	6

Current values in the above tables are those indicated by a suitable well damped ammeter in the motor circuit on the line side of the compensator, and are 75% of the permissible locked rotor values.



The Electric Ventilating Co.
Alfred S. Alschuler, Archt.



Archdiocesan Seminary Power House
Jos. W. McCarthy, Archt.

Complete Electrical Installations Is Our Business—Light, Power, Telephones,
Electrical Systems and Apparatus of Every Description

—for—



Quigley Memorial Seminary
Z. T. Davis, Archt.

Light and Power Plants,
Schools and Colleges,
Churches and
Seminaries

Office and Factory Builders,
Stores and Theatres,
Residences, Hos-
pitals and
Hotels



McKinlock Office Bldg.
C. S. Frost, Archt.

E. D. FUCHS ELECTRIC COMPANY


ELECTRICAL CONTRACTORS

Telephones, Randolph 4746-5062

129 S. La Salle St., CHICAGO



Evansston Hospital
Schmidt, Garden & Martin, Archts.



Philipsborn Catalogue House
Alfred S. Alschuler, Archt.

DIRECT CURRENT.

	Amperes	Volts	per H. P.
Horsepower			
3 H. P. and below	230	12	
Above 3 H. P.	230	9	

Current values in the above tables are those indicated by a suitable well damped ammeter on the line side of the starting resistance.

FIRE PUMPS.

Fire pump motor installations must be made in accordance with the rules of the authorities having jurisdiction over such installations. The Department of Gas and Electricity of Chicago has issued special instructions for the installation of this class of motors, which are shown on page 231 of the Electrical Code.

Meters shall be of the shunt type for direct current system and of the current transformer type for alternating current systems. A meter cabinet of shape and dimensions as shown on the drawings must be provided and installed by the electrical contractor. This cabinet must be provided with a door which is arranged to be locked with a padlock, which lock will be furnished by the Company. The cabinet may be located at any point in the service run, provided it is readily accessible and not subject to moisture or vibration. Conduits carrying service mains must enter cabinet in a standard manner, and the cables must be long enough to connect with lugs on shunts or current transformers. The lugs for shunts or current transformers will be furnished by the Company and installed by the contractor. A $\frac{1}{4}$ " slate base for the mounting of the meter and other equipment, standard cartridge fuses and cutout blocks of capacity shown must be furnished by the contractor and installed in the locations shown on the drawings.

It is suggested that fire pump switching connections be so arranged that a fire pump may be periodically tested while connected to the regular power supply. If this testing is done at times when the regular power is not in use, the demand charge will be reduced by the amount due to the demand of the fire pump.

Diagrams showing how such connections may be arranged will be furnished by the Company on application to the Inspection Bureau.

METERS. Location.

All meters must be installed in a suitable location as near as practicable to the point where the service enters the building. The wires should be enclosed in a continuous metal conduit from the service to the meter. In office buildings, special meter closets of ample size must be provided on each floor; in apartment buildings, all meters should preferably be installed in the basement, and the separate circuits to each apartment must be carefully labeled. In residences, meters should be installed in the basement or a rear hall, rather than in the attic.

The requirements of a suitable meter location are as follows:

(a) Meters must be accessible to the company's employees at all reasonable times, and must be so located that they may be easily read, inspected, and tested, with a minimum of annoyance to the tenants. Small capacity meters must be so installed that the bottom of the meter is not more than seven feet from the floor, and meters of a capacity of 100 amperes and above, not more than 5 feet from the floor to the bottom of the meter. Meters must not be placed in bedrooms, closets, bath or toilet rooms or in any room commonly kept locked, or near coal bins, in elevator or ventilator shafts, near stoves, radiators, sinks, wash tubs, gas or steam piping, steam heaters or boilers.

(b) The location selected must be free from moisture. A watthour meter must never be placed under a water pipe, from

which, as a result of sweating, water may drip. When a damp location is unavoidable, a moisture-proof cabinet must be provided by the customer to contain the meter.

(c) The location must be free from vibration. Where traffic is heavy, or cars are passing, meters should be placed upon a wall at the building line, rather than upon the front curb wall, and must never be placed under the sidewalk, except by special permission from the Inspection Bureau. They must not be placed on any insecure partition, over a doorway, or in a stairway.

(d) Meters must be located, if possible, so that they will not be exposed to mechanical injury. If this is unavoidable, a suitable cabinet must be provided by the customer to contain the meter, and to thoroughly protect it from possible damage.

(e) The meter location must be as free as possible from magnetic disturbance. Meters must not be installed in close proximity to motors or generators. Cabinets, for direct current meters, must be of asbestos board or non-magnetic metal.

Meter cabinets must be of ample size to permit the safe handling of wires when connecting, disconnecting or testing the meters, to motors or generators. Cabinets, when the conditions require the installation of a metal cabinet, the inside must be lined with suitable insulating material.

Meter Loops.

Where meter fittings are installed, they must have on the cover a holder for the insertion of a customer's identification card, $2\frac{1}{2} \times 3\frac{1}{2}$ " in size. The contractor should place a paper in the holder of all fittings, indicating the address and location of the apartment.

Where meter loops are provided for meters smaller than 200 amperes in size, a free end of at least 24 inches must be left to give ample wire for connection to the watthour meter, or if the wires are left in the form of a loop, each loop must contain at least 48" of wire. For larger meters greater lengths are required and the Inspection Bureau must be consulted as to the length required.

Meter loops and fittings must be so arranged that the meters can be placed at least six inches away from iron cabinets and cut-out boxes so as to permit the safe handling of wires during tests.

The distance between centers must not be less than 12 inches for A. C. and 15 inches for D. C. meters. Meters of a capacity in excess of 50 amperes must have a distance between centers of not less than 24 inches, and the leads of one meter must not run within 12 inches of another meter.

Service and house leads for type C.S.2 and type C.S.3 Thompson direct current meters, which are the types generally installed in sizes of 200 amperes and larger, must be carried in a metal trough from the cabinet to a point directly beneath the meter, and brought outside the trough through bushings spaced far enough apart that the loops may be run in a direct vertical line to the meter terminals. They must be so anchored that the weight of the cables will not rest on the meter terminals.

Where external resistances, current on potential transformers are used in connection with either house or switchboard type meters, they must be located where they are accessible for inspection, and can be removed without danger of making a short circuit.

Contact making clocks for operating type P demand meters must not be installed within a loop formed by the cable leads or close to conductors carrying heavy currents, as the magnetic field may affect their accuracy, neither should they be installed in any place subject to extreme changes in temperature.

When meters are to be installed for construction work, cabinets of weather-proof construction must be provided by the customer to protect them against injury. The

TELEPHONES, FRANKLIN 2354-2355

J.B.HEWITT & COMPANY

ELECTRICAL

CONTRACTORS and ENGINEERS

10 S. LA SALLE ST.

CHICAGO

Some of Our Installations

Ajax Forge Company plants at Chicago
and Superior

American Can Company, Factories at
Chicago, Joliet, Maywood, Ill., and
St. Paul, Minn.

American Forge Company

Benjamin Electric Company, Desplaines

Dryden Rubber Company, Chicago

Ford Service Stations at Omaha and
Oklahoma City

Hydrox Company, Chicago

Morris & Co., Chicago

Packard Motor Car Company, Chicago

Sinclair Refining Company

LIGHT POWER HEAT

final connections between the customer's wiring and the Company's mains, will, in every instance, be made by the Company. When it is possible, a location should be selected for a meter at the outset, which can be used throughout the construction period.

For the following 2-wire installations one side of the line is to be brought to the meter with a potential tap from the other side.

2-wire 115 volt D. C. meters.

2-wire 115 volt A. C. meters.

2-wire 230 volt D. C. meters.

2-wire 230 volt A. C. meters larger than 150 amperes.

In case of 115 volt meters the potential tap must be from the neutral wire.

Both outside wires must be carried to the meter for all 2-wire 230 volt A. C. meters of 150 amperes and smaller; also for all 3-wire, 230 volt meters. For D. C. meters a potential tap from the neutral wire must be provided except for installations of larger capacity using type C.S.2 and C.S.3 Thompson meters.

For three-phase motors two-phase wires and a potential tap from the third phase must be brought to the meter, and where current transformers are used in connection with the meter, three potential wires are required, one for every phase.

Potential taps for all meters must be so made that they cannot become disconnected. The connecting wire should be as short as possible, and must be soldered to the return or neutral circuit without a fuse. When a number of meters are installed in one location, a separate potential tap must be provided for each meter.

Meter Fuse Protection.

All meters must be protected by suitable fuses of approved capacity. Meters must never be placed between the service and the service switch.

Where more than one meter is dependent on the service switch, fuses must be provided in such manner as to protect the meter where the meter is supplied by mains larger than No. 10 B. & S. gauge. These fuses must be installed between the service switch and the meter loops.

Meter Board.

A suitable meter board of cedar, pine, or other soft wood not less than $\frac{3}{8}$ " thick, must be provided by the customer and rigidly secured to the wall or other support. Where it is mounted on metal, lath or other metal part of the building, all supporting screws or bolts must be counter sunk. Specification of the Department of Gas and Electricity of Chicago covering the dimensions of these boards and location on same of meter fittings of 100 ampere capacity and less.

Types and Dimensions.

Standard front connected meters are provided for all alternating current installations. Current transformers are used in connection with alternating current meters of a capacity in excess of 150 amperes. Current and potential transformers are required on all motor installations on primary lines. For the different types of alternating current meters and wiring, see pages.

Standard front connected types of direct current meters are used up to a capacity of 60 amperes, 230 volts, 3-wire, and 600 amperes, 230 volts, 2-wire. Larger capacity meters will be furnished either of the front connected or of the back connected switchboard type.

Switchboard Meters.

Switchboard meters and their necessary equipment will be furnished by the Company or large installations if the customer makes arrangements with the Company in advance and provides for the necessary drilling and connections for both meters and equipment. Demand meters, printometers, contact making clocks and relay switches are part of the meter equipment. Proper templates and wiring diagrams will be furnished by the Company.

Test links must be installed with all switchboard meters. For 2-wire meters, two test links are required, one on the service lead to the meter, and one on the load lead from the meter. For the 3-wire meters, four test links are required, one in each of the service leads to the meter, and one in each of the load leads from the meter. Test links should be located on the front of the switchboard. The test terminals, studs and links of the approved type only will be furnished by the Company and are to be installed at the expense of the customer.

In all cases test links must be readily accessible and must be placed at a distance of not less than 2 inches from any switches, bus-bars, switchboard frame or frame bolts, so as to eliminate, as far as possible, danger from short circuits while making connections for tests.

Various details, such as the method of metering, the type and capacity of watt-hour meters and maximum indicators, and the size of test links, must be determined by the Company for each switchboard installation. These details should be taken up with the Distribution Division of the Company by the customer or his representative before the board is designed, and sufficiently in advance of its construction to give the Company time to obtain the special equipment. Blueprints or sketches showing the proposed location and connections of meters and equipment on switchboards must also be submitted to the Distribution Division for approval, before the switchboard is constructed. See "Switchboards."

INSPECTION.

All wiring which is to be connected with the Company's service must be inspected and approved by the Department of Gas and Electricity of the City of Chicago, and must conform to the rules and regulations established by the Company from time to time.

A temporary current permit, or final certificate of inspection issued by the Department of Gas and Electricity of the City of Chicago must be presented at the office of the Inspection Bureau of the Company before the electricity can be turned on. This applies to additional wiring which may be connected at any time, as well as to original installations. The Company reserves the right to make final connection of all wiring to its mains and in case any damage results from unauthorized connections the customer will be held responsible for such damage.

The Company furthermore reserves the right to discontinue service to the customer in case the Company deems the condition of the customer's wiring either hazardous or not in compliance with the Company's wiring rules. The Company also reserves the right to discontinue the customer's service on orders from the Department of Gas and Electricity of the City of Chicago when such a step is deemed necessary by that Department in order to secure compliance with the Electrical Code of Chicago.

INSPECTION OF NEW PIPING.

One inspection will be made, namely, after the piping has been installed, and before the building has been lathed and plastered.

In order that certificates may be issued as soon as possible after the piping is installed, Gas Fitters must adhere strictly to rules as to sizes, etc., and are requested to notify the Peoples Gas Light and Coke Company, Application Department (Wabash 6000) immediately after piping has been completed, so as to allow sufficient time for inspection before piping has been concealed.

Manhattan Electrical Supply Co.

INCORPORATED

114 So. Wells Street, Chicago

NEW YORK

ST. LOUIS

SAN FRANCISCO

MAKERS OF

Flush and Surface Switches of Dependable Quality

and

"Something Electrical for Everybody"


THE MAXOLITE DIFFUSER FOR INDUSTRIAL LIGHTING

No
Glare

Dust
Proof

No
Shadows

Moisture
Proof



Write for Bulletin No. 75 on the Maxolite Diffuser
and R. L. M. Maxolite

Central Electric Company
FOUNDED 1887
The House of Service
316-326 South Wells Street
CHICAGO



PROPER LIGHTING FIXTURES AND THEIR RELATION TO THE HOME BEAUTIFUL

By C. G. EVERSON, President Lighting Fixture Council

Most everyone, whether interested in the subject of lighting and lighting fixtures, or not, must have observed in the last few years the radical advanced steps taken in the matter of illumination and fixture designs.

This article will but touch on the illumination aspects, for this subject, while having been greatly advanced in the industrial and commercial field, reaching a high point of perfection therein, is comparatively new in Home Lighting—and this article deals mostly with Home Lighting.

To the writer's mind, too, the need of illuminating engineering skill in the home with the same objects as sought in the industrial and commercial field, is not so vital. Rather, common sense treatment of home illumination could be the rule—by which I mean simply to avoid glare and distribute enough light to relieve eye strain in the use of light for general purposes. The use of color in illumination, now being experimented with, will be a fine idea for decorative purposes in those homes which want it, but the 99 out of 100 homes will not require and will not want decorative color. Good illumination is needed. The number of foot candles per square foot while important in industry, requiring continued, concentrated eye action, is superfluous in the home. Here, four hours out of each twenty-four is the average spent under artificial lighting, and then with variations of occupations. In other words, you sit around a living room in converse. Glareless, shaded light is needed. For concentrated occupation, increased brilliancy—the light from portable floor or table lamps is required. Hence, the lighting of a living room of average size to be satisfactory should consist of a center fixture, affording an abundance of soft light when needed—wall brackets to distribute and localize the illumination, and portable lamps to provide localized illumination. Certain translucent bowls, if used as a center fixture, deliver wonderfully good light for reading. Likewise, a "direct" reflected light when used close to the ceiling and the light source properly shielded becomes a satisfactory reading light. I use the word "reading," for it implies the need for just about the best form of illumination.

The candelabrum so much in vogue today is primarily a decorative fixture, and with it should be used a shade or shield over the bulb. Used thus, this style of fixture is perfectly all right where the soft illumination from it can be supplemented by additional reading light.

In the dining room a center fixture is most necessary, but here plenty of light

on the table is always desirable. However, the avoidance of glare from the light source is highly necessary, and several new ideas for concealing the light source, but obtaining the intensity of a direct reflected light, are displayed by Chicago fixture manufacturers. Candle types of fixtures are likewise used in this room, but here again they must be used at the cost of strong illumination. They can, though, be used in combination with the translucent bowl, and thus obtain both decorative and good illumination. Wall lighting in the dining room is most essential, for two reasons at least. As in the living room, it distributes the light more evenly through the room, and may be most effective in a decorative way. Also, in this room, portable lamps, candlesticks excepted, are out of place; hence, sole reliance is on the center and side wall light sources.


The reception room dependent on size, should likewise have the ceiling light either supplemented by wall brackets or possibly floor torcheres. The ceiling light would be best when the light source is enclosed or shielded.

Thus, from an illumination standpoint, we see that the tendency is for an abundance of outlets and plenty of lights, all shielded. It is a commonsense, practical method, and our lesson is taken from the illuminating engineer who says avoid eye strain.

With the illumination needs of the home covered briefly by the foregoing, we come to what, in the writer's mind, is a more deplorable condition. It is "fixture design", or rather, an utter lack of it. And the fault is not all with the manufacturers.

In many homes today lighting equipment is selected and purchased with little thought or consideration given to its proportions or symmetry. And furthermore, they are purchased with but little or no knowledge of what constitutes a fixture of good quality, aside from its design. In the majority of fixture sales by the manufacturer, the chief consideration has been price—although, most happily, and for the prime interest of the user, a strong tendency to buy better fixtures is now most apparent.

This price consideration generally restricts the user to fixtures of cheaper design and cheaper construction than nine out of ten are able and willing to pay for. They buy, and take great pride in the possession of their furniture and rugs, and in the decorative pictures, etc., in their home. These things are purchased by them entirely to their taste, governed of course, by their pocketbook. But their fixtures, as a



C. G. Everson & Co.
Lighting Fixtures.
 70, West Lake St., Chicago
 Phones—Central, 6737, -38, -39.

Telephones { Main 4665
 Main 4666

L. H. Lamont & Company
Electrical Contracting Engineers

9 South Clinton Street, CHICAGO

L. K. COMSTOCK & COMPANY, Inc.
 CONSTRUCTING ENGINEERS

COMPLETE ELECTRICAL AND
 MECHANICAL INSTALLATIONS



79 W. MONROE STREET
 CHICAGO, ILL.
 TEL., RANDOLPH 6660

PHONES CENTRAL 8533-8673

Dearborn Electrical Construction Co.

INCORPORATED

Contracting Engineers

Power

Light

Telephone

27 WEST KINZIE STREET

CHICAGO

rule, in a new building, are computed to cost a certain percentage of the cost of the building, a percentage usually much too low to provide the style and quality of fixture this client is **able** and **willing** to buy, and should buy to conform to his other furnishings. The client has much to learn about design and quality, and his purchase coming within or around the amount allowed by the architect lacks much to be desired in these qualities.

Lighting Equipment has a decorative value in the home, absolutely on a par with every furnishing in the rooms. In the home and in the apartment its value should be thus considered by the architect and a sufficient allowance for this made, in addition to its value only as a lighting medium, and to cover the outlets provided.

Inquiries made among a number of architects revealed the fact that they allowed all the way from $\frac{1}{2}$ of 1% to 5% for lighting equipment, and some allowed merely a given amount, without regard to the building cost and with no knowledge whether their clients obtained satisfactory fixtures within their allowances or not. The 5% man was one specializing in residences, and usually worked with his clients very closely on most of the decorations.

So, with fixtures so much an intimate part of the home furnishing, it might be questioned why the architect has anything to do with the lighting equipment. Why not allow the owner to purchase them as he purchases his furniture, or be guided by the decorator?

The fact is, there is now a growing movement on foot—the “hang your fixture like a picture” idea. This means wiring the house or apartment to a standard “plug in” outlet, to which may be attached without mechanical skill or expert assistance, fixtures provided with standard plugs to fit these outlets. Thus, the owner of these fixtures carries them along from one home or apartment to another, just as he now takes his furniture. While there is a great impetus to this idea, I will speak later of the reason it will probably not prevail.

The actuality and growth of the idea however, is the strongest proof that users are not satisfied with the fixtures they find when moving from house to house, or apartment to apartment.

It is up to the architect to realize the value of better fixtures in the homes, and it should be his duty and to his interest, to pass on to his client this belief that more care than has usually heretofore been given should now be given in their selection. And in spite of the “hang your fixture like a picture” idea and its attendant assumption that the owner will buy his fixtures and take them around with him when he moves, the cost of fixtures will remain within the province of the architect. The “portable fixture” plan, while having many advantages, has some drawbacks—chief among these is the fact that the number of ceiling and wall outlets in one house or apartment rarely correspond exactly with the number and location in another. Hence, fixtures will continue to be a part of the cost schedule of the building and within the architect's jurisdiction. But the architect must take more interest in lighting to give the satisfaction to his client, and home and apartment owners, which, they as a rule, have heretofore not had, but for which there is a growing insistence.

Even in buildings constructed for speculation, the question of suitable fixtures should receive the most careful consideration. The builder finds in good fixtures one of the strongest talking points he can

bring to bear, whether to sell or rent his property. They are one of the most prominent features of each and every room. They are the visible evidence of good or bad taste, and may be the reason for judging of unseen or uncomprehended parts of the building. The tenant may be so attracted to them that they swing his decision to rent or buy. And the architect profits by all of this kind of satisfaction. While the fixtures can be made the instrument of such unbounded good will, they should be selected with utmost care.

With the possibility of fixtures becoming so much a part of “home furnishing” that the matter of personal choice is a difficult or undesirable one for the architect to mix in with, I would answer in two ways.

First, if he is inclined to aid his client in his selection, it is not a difficult task. There are only four types of fixtures.

The Total Indirect.

The Semi-indirect or Translucent Bowl.

The Direct Reflected.

The Candelabrum.

Then various combinations of these types, then various styles of these types. By elimination one can quickly resolve the matter down, to the types, then to a few considered styles which are just right for the place and purpose, from which a final choice is easily made.

The difficulty comes, when for a given kind of home, a selection is attempted to cost much too little for that home. Usually, because the architect has placed too little stress on lighting, and allowed the owner to assume he could get what he should have for too little.

So the architect's second choice, if unable or unwilling to aid personally in the selection of lighting equipment, is to allow a sufficient amount in his cost schedule that will enable his client to go to some reliable firm and purchase fixtures with real merit.

So, since the placement of outlets and the consequent fixture requirements remain under the architect's supervision, it behooves the forward looking architect to become more interested and to keep himself fully informed on new fixtures and devices for increasing the efficiency of lighting equipment.

For instance, with architects specializing in hotel apartments, there has been a great need for a suitable fixture for the small breakfast room. A simple little device recently gotten out made it possible to design a very practical and beautiful fixture for this room. It enables the user to obtain light, a receptacle for toaster, coffee percolator or other electrical utensil, all separately controlled, and precludes the need for wall switch or baseboard outlet.

Things of this kind are being developed constantly, by the various fixture manufacturers through their associations. These associations, organized in all the larger cities and collaborating with the National Council of Fixture Manufacturers are doing a great work in aiding the movement for better lighting. And through their united efforts, the move for better illumination and better design is receiving great impetus and wonderful commendation from architects throughout the country. The field is large, and it is the architect's place to share in it.


Gas Piping Is Essential

IN EVERY BUILDING
FACTORY OR RESIDENCE

Service - Economy - Dependability

Gas for Manufacturing

Even heat under instant control.
Gives uniform production. Saves
loss from spoilage. No dust, dirt
handling cost or storage space.



GAS
100% FUEL

Expert Engineering Advice on all ques-
tions of heat applications furnished free

The Peoples Gas Light & Coke Co.

Factory Appliance Dept.—Phone Wabash 6000
Michigan Avenue at Adams Street

GAS FITTERS' RULES

Of the Peoples Gas, Light and Coke Company

OFFICE BUILDINGS, DWELLING HOUSES AND FLATS
MANUFACTURED GAS FOR LIGHT

INDEX TO RULES

	RULES		RULES
Air compressed	12	Piping, for fuel only.....	17
Alterations in house piping, etc.....	75	" for laundry.....	35
Appliances, connecting	14	" how to avoid trapping.....	9
" domestic and industrial, feet of pipe		" inspection of	1
allowed	26	" imbedded in concrete or cement.....	8
Automatic water heater, feet of pipe allowed.....	27	" obstruction in	2
Building Service, bringing to street service.....	72	" on outside wall.....	6
" feet of pipe allowed.....	29	" on masonry wall.....	7
" finished rooms in basement.....	57	" office building, schools, hospitals, residences	
" header	63	and flats.....	22
" only, installing	50	" rooms in rear of store.....	25
" in flat or residence.....	51	" stores and factories.....	23
" in store	52	Pipe, single pipe system.....	16
" in unheated basement.....	55	" size required and equivalents.....	19
" laid through a masonry wall.....	60	Riser, distance below ceiling.....	43
" location of	58	" for theatre.....	34
" opening in	61	" height of	42
" solid wall porch.....	56	" in rear of a basement.....	58
" test pipe on.....	62	" in other apartments.....	39
" terminating	73	" in laundry, etc.....	33
" underground	53	" in cold basement.....	36
" wrapping	59	" in front hall.....	41
Branch lights, feet of pipe allowed.....	24	" location for.....	32
Branch lines, drops from.....	11	" near a vestibule partition.....	37
Breaking sizes of pipe	10	" near an electric cut-off box.....	38
Compressed air	12	" prohibited location for.....	40
Defective material	3	" size of for combined line.....	21
Drops from branch lines.....	11	Rules, understanding.....	18
" distance below ceiling.....	48	Sizes, breaking	10
Electric cut-off box.....	38	Single pipe system.....	16
Equivalents, table.....	19	Services, disconnecting and reconnecting.....	75
Exit lights	44	" for apartment buildings.....	65
Gas engines, feet of pipe allowed.....	28	" for building in rear of corner lot.....	68
Light for public hall 3 flat building or over.....	45	" for corner buildings.....	67
" " 2 flat building	46	" for court buildings.....	66
Meter, location of.....	31	" building in rear of lot.....	69
" changing location of.....	75	" for stores	64
Material, defective	3	" opening in wall for.....	70
" not allowed	4	" opening in floor for.....	71
Masonry Walls, piping on.....	7	" two in one trench.....	54
Openings, size of, how to determine.....	20	" charge for inside property line.....	76
Outlets, for mantel or fireplace.....	49	Testing of piping.....	1
" for fuel, height of	47	Typesetting machines.....	15
" capping of	5	Water heater, automatic, feet of pipe allowed.....	27
" for fuel	17	Window lights, feet of pipe allowed.....	24
Outside wall, piping on.....	6	Work charged for by company.....	75
		" not allowed.....	13
		" reserved by company.....	74

The following rules governing the piping of buildings for the distribution of gas for light and fuel have been adopted by The Peoples Gas Light and Coke Company.

General Instructions.

1. Inspection of New Piping. One inspection will be made, namely, after the piping has been installed, and before the building has been lathed and plastered.

In order that certificates may be issued as soon as possible after the piping is installed, Gas Fitters must adhere strictly to rules as to sizes, etc., and are requested to notify the Peoples Gas Light & Coke Company, Application Department (Wabash 6000) immediately after piping has been completed, so as to allow sufficient time for inspection before piping has been concealed.

After fixtures are installed, piping must stand a pressure of one inch on a column

of mercury without showing any drop for the same period of time.

2. Obstructions in Pipe. All piping must be free from burrs and other obstructions.

3. Defective Material. Split pipe or fittings repaired with cement or lead must not be used. Caulked fittings must not be used.

4. Material Not Allowed. Unions or bushings must not be used in work that is to be concealed, and cast iron fittings are prohibited in either exposed or concealed work.

5. Capping Outlets. All outlets must be securely closed with iron caps until fixtures or appliances are installed.

6. Piping on Outside Wall. When it is absolutely necessary to run pipe on an outside wall a furring strip must be placed between the pipe and the wall.



Walls finished with Cabot's Old Virginia White,
Roof finished with Cabot's Creosote Stain.
J. W. O'Connor, Architect, N. Y.

Cabot's Building Specialties

Creosote Stains for Shingles, Siding, Clapboards, Trimmings, Boards and all other Exterior Woodwork.

Waterproof Stucco and Brick Stains for waterproofing and artistically coloring cement and brick buildings.

"Quilt" for lining houses to keep out cold or heat, for sound deadening in floors and partitions, and for insulating cold storage and refrigerators.

Old Virginia White for the clean, brilliant "whitewash-white" effect on shingles and other woodwork.

Conserve Wood Preservative for preserving Posts, Planks, Sills and all other exposed timbers.

Mortar Colors, Protective Paints for Metals, Waterproofing Compounds, etc.

SAMUEL CABOT, Inc., Manfg. Chemists

24 W. Kinzie Street, CHICAGO

Telephone Central No. 1

TELEPHONE CENTRAL 903

ESTABLISHED 1847

M. W. POWELL COMPANY


ROOFERS

MARQUETTE BUILDING

CHICAGO

Our Engineering department is at your service to help solve your Roofing problems

WINTHROP
TAPERED



ASPHALT
SHINGLES

BECKMAN-DAWSON ROOFING COMPANY

Telephone, Central 4479

19 S. La Salle St., CHICAGO



Peterson Nursery

Established 1856

Trees

Perennials

Shrubs

Landscape Plans Prepared

Estimates Given

Send for New Catalogue

30 North La Salle Street

Telephone Main 3613

Chicago

7. Piping on Masonry Walls. All piping run on masonry walls must be securely fastened thereto by strapping it to wooden plugs driven into the wall.

8. Imbedding in Concrete or Cement. When pipe is to be imbedded in concrete or cement, it must be covered with tar paper or other suitable covering, or laid in a conduit pipe.

9. Trapping Pipe. To avoid trapping pipe gas fitters must grade it to riser or to drops, except as provided in rule No. 66.

10. Breaking Sizes. In every case where an extension is to be made, pipe must be broken at a point where the full size can be maintained.

No extension must be made from a pipe of a smaller size.

11. Drops from Branch Lines. Drops on branch lines should have a set of 4 inches and they must be dropped square. Outlets for side brackets may be either square bends or long drop ells. The use of nipples is prohibited.

12. Compressed Air. Compressed air must not be used for industrial appliances.

13. Work Not Allowed. Gas fitters must not do any underground piping outside of a building.

14. Connecting Appliances. Fitters are particularly requested to see that all gas burning appliances are connected solid with iron pipe. Under no circumstances will this Company approve of the use of lead pipe or rubber tubing.

15. Typesetting Machines. A linotype or monotype machine must be supplied by a separate fuel run.

Rules and Tables for Piping.

16. Single Pipe System. The following tables and rules provide for a single pipe system in either new or old buildings. However, should it be more economical to install a double pipe system, such may be installed, and outlets computed on the same basis as that for a single pipe system.

17. Fuel Only. When piping is installed for illumination in either a new or old building, an outlet must be left for fuel.

If gas for light is not desired, a building may be piped for fuel only.

18. Understanding Rules. If, in any instance, the rules governing the sizes of pipe to be installed are not clearly understood, or if unusual conditions not covered by the rules are met with, the Gas Company should be consulted.

19. Size of Pipe Required and Equivalents. The amount of gas passing through a $\frac{3}{8}$ -inch pipe under normal pressure is approximately 10 cubic feet of gas an hour. The capacity of a $\frac{3}{8}$ -inch outlet has therefore been called an equivalent, and the table of pipe sizes below has been figured out on that capacity and is to be used in estimating the size of the pipe necessary to give an adequate supply of gas to an appliance.

For example, a range for a flat or residence requires five times the quantity of gas supplied by a $\frac{3}{8}$ -inch pipe, or five equivalents.

Range for flat or residence....5 equivalents
Grate or log.....3 "
Laundry appliance.....3 "
Water Heater4 "
Arc Lamp2 "

The number of $\frac{3}{8}$ -inch equivalents for any appliance not mentioned in the above table may be determined by dividing the total consumption per hour of that appliance by ten.

Consumption of gas-fired steam boilers may be obtained by assuming 80 cubic feet of gas per hour for each horsepower.

20. Size of Opening. To determine the size of the opening required when risers are connected at the meter end, the combined loads of the risers must be added together. (See table in Rule 22.)

21. Size of Riser for Combined Lines. When two or more lines of pipe are connected in order to be supplied by one riser, the riser must be of sufficient size to supply the combined load of all the lines. (See Rule 22.)

22. Office Buildings, Schools, Hospitals, Residences and Flats, Under Single Pipe System.

Size of Pipe in Inches	Feet of Pipe Allowed	Number of $\frac{3}{8}$ -inch Equivalents allowed
$\frac{3}{8}$	30	2
$\frac{1}{2}$	40	4
$\frac{3}{4}$	60	10
1	70	15
$1\frac{1}{4}$	100	30
$1\frac{1}{2}$	150	60
2	200	100
$2\frac{1}{2}$	250	200
3	300	300
4	450	500

Notes: Any ceiling 20 feet high or over must have $\frac{1}{2}$ -inch drops.

In a residence or a flat building, a $\frac{3}{4}$ -inch outlet for a range in a kitchen may be used to supply two appliances, such as a range with a $\frac{3}{4}$ -inch outlet extended full size, and a water heater or a laundry appliance with a $\frac{1}{2}$ -inch extension.

23. Stores and Factories.

Size of Pipe Inches	Feet of Pipe Allowed	Number of $\frac{1}{2}$ -inch Outlets allowed
$\frac{1}{2}$	30	1
$\frac{3}{4}$	60	8
1	70	12
$1\frac{1}{4}$	100	20
$1\frac{1}{2}$	150	35
2	200	50

Notes: For stores the running line must not be less than $\frac{3}{4}$ -inch to the last outlet.

Drop outlets for stores must be $\frac{1}{2}$ -inch in size.

24. Bracket and Window Lights. Thirty feet of $\frac{3}{8}$ -inch pipe will be allowed for bracket lights. The same length of $\frac{1}{2}$ -inch pipe will be allowed for window lights.

25. Piping Rooms in Rear of Store. When a store building with living rooms in the rear is supplied by one riser, the running line must be $\frac{3}{4}$ -inch to the outlet for fuel.

26. Domestic and Industrial Appliances. Gas to be used at one point.

Size of Pipe in Inches	Feet of Pipe Allowed	Number of $\frac{3}{8}$ -inch Equivalents allowed
$\frac{3}{8}$	80	4
$\frac{1}{2}$	90	10
1	100	20
$1\frac{1}{4}$	150	30
$1\frac{1}{2}$	200	40
2	250	60

27. Automatic Water Heaters. An automatic water heater must be supplied with a separate pipe. For sizes and lengths allowed see table under this rule.

ASBESTOS
ROOFING AND SIDING

ASBESTOS
BOILER AND PIPE COVERING

H. F. WATSON CO.

ASPHALTED FELTS
FOR DAMP PROOFING, TILE
—AND SLATE LININGS—

COMFORT BRAND DEADENING FELT

ESTIMATES FURNISHED
TELEPHONE MAIN 4405-6

319 NORTH WELLS STREET

HENRY W. GREBE, Pres.

HENRY F. GRIER, Vice-Pres.

ERNEST BUEHLER, Secy. and Treas.

Central Asbestos & Magnesia Co.

CONTRACTORS FOR

*Pipe and Boiler Coverings
Smoke Stack and Breeching Linings
Asbestos and Magnesia Products
Hair Felt, Packings, Etc.*

Telephone Superior 4830

214 & 216 W. Grand Ave., Chicago

Asbestos and 85% Magnesia Pipe and Boiler Coverings

Cork Insulation and Brine Pipe Coverings

Smoke - Stack and Breeching Linings

PAUL J. KREZ CO.

Heat and Cold Insulation Contractors

Distributors of

Asbestos "Century" Shingles—Asbestos Building Lumber

Telephones { Franklin 1337
Franklin 1667

442-444 No. La Salle Street

Members of Building Construction Employers' Association of Chicago

Telephones { Monroe 6147
Monroe 2011

Standard Asbestos Mfg. Co.

Manufacturers and Contractors for

STEAM PIPE AND BOILER COVERINGS
ASBESTOS PRODUCTS—ROOFING

816-18-20-22 West Lake St.

CHICAGO

Automatic Water Heaters.

Automatic Storage Heaters.

28. **Gas Engine** The gas supply for a

Size of Pine	Feet of Pine
1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10
11	11
12	12
13	13
14	14
15	15
16	16
17	17
18	18
19	19
20	20
21	21
22	22
23	23
24	24
25	25
26	26
27	27
28	28
29	29
30	30
31	31
32	32
33	33
34	34
35	35
36	36
37	37
38	38
39	39
40	40
41	41
42	42
43	43
44	44
45	45
46	46
47	47
48	48
49	49
50	50
51	51
52	52
53	53
54	54
55	55
56	56
57	57
58	58
59	59
60	60
61	61
62	62
63	63
64	64
65	65
66	66
67	67
68	68
69	69
70	70
71	71
72	72
73	73
74	74
75	75
76	76
77	77
78	78
79	79
80	80
81	81
82	82
83	83
84	84
85	85
86	86
87	87
88	88
89	89
90	90
91	91
92	92
93	93
94	94
95	95
96	96
97	97
98	98
99	99
100	100

Note: If the length of pipe required exceeds

Size of Pipe in Inches	Feet of Pipe Allowed	Number of $\frac{3}{4}$ -inch Equivalents allowed
1	70	16
1 $\frac{1}{4}$	100	40
1 $\frac{1}{2}$	150	80
2	200	120
2 $\frac{1}{2}$	250	200
3	300	300
4	450	500

32 Plan of Joint and Separate Sessions

In determining sizes of piping for a build-

Plan No. 1. **Devildown**

RESIDENCE



TELEPHONE DIVERSEY 2440

The Nollau & Wolff Mfg. Company

MANUFACTURERS OF

GENERAL MILLWORK-INTERIOR FINISH CABINET WORK

OFFICE AND FACTORY
1705 TO 19 FULLERTON AVENUE


CHICAGO




HARTMANN - SANDERS CO.

Sole Manufacturers

Koll's Lock-Joint Patent Wood Columns



Pergolas,
Garden Accessories



ASK FOR CAT. NO. 47

SPECIAL MILL WORK

Factory and Main Office:
2155-87 Elston Avenue, CHICAGO, ILL.

Telephone Monroe 4868

New York City Office: 6 E. 39th Street

Troy Laundry Machinery Co.

(Limited)

We are prepared to furnish estimates for Laundry Equipment for any sized plant from the small hand to the largest steam laundry.

Our complete line of up-to-the-minute machinery and our long experience in all branches of the business enable us to guarantee absolute satisfaction.

WE INVITE CORRESPONDENCE

La Salle and 23d Sts. TELEPHONE 2600 VICTORY

Chicago.

LAUNDRY MACHINERY

for

HOTELS, HOSPITALS, INSTITUTIONS
or SPECIAL PURPOSES


Our Engineering Department is at Your Service

THE AMERICAN LAUNDRY MACHINERY CO.

208 W. Monroe St.

CHICAGO, ILL.

SAMPLE PIPING PLAN STORE WITH LIVING ROOMS IN REAR



Plan No. 2. Store with Living Room in Rear.

Line	Number of 3/8-inch Equivalents supplied by line	Length	Size
K to J	5	12' 6"	3/4"
K to J	6	12' 6"	3/4"
10 to J	1	8'	3/8"
J to I	7	5'	3/8"
9 to I	1	8'	3/8"
I to H	8	8'	3/8"
8 to H	1	2' 6"	3/8"
H to G	9	7'	3/8"
2 to A	2	14' 6"	1/2"
1 to A	2	9' 6"	1/2"
A to B	4	6'	3/8"
3 to B	1	2'	3/8"
C to B	5	6'	3/8"
4 to C	1	2' 6"	3/8"
C to D	6	12'	3/8"
5 to D	1	2' 6"	3/8"
D to E	7	12'	3/8"
6 to E	1	2' 6"	3/8"
E to F	8	6'	3/8"
7 to F	1	17'	3/8"
G to F	12	6'	3/8"
G meter	21	20'	1 1/4"

METER AND RISERS AND THEIR LOCATION.

31. Location for Meter. The Company reserves the right to determine in all cases the location for the meter.

32. Location for Risers. All risers must be placed in public basements, provided the latter are dry and warm and not less than 6 feet in height. The Gas Company positively will not set a meter in a basement that is less than this height.

If no public basement or meter room is provided, the riser for each floor should be placed either in the toilet, pantry or kitchen of that floor.

33. Risers in Laundries, etc. Risers may be run to laundries, furnace or boiler rooms, provided the risers are not placed closer than 10 feet to any appliance and in no case directly in front of a boiler or a furnace.

34. Riser for Theatre. A meter to supply a theatre may be set in a public meter room with other meters and may be supplied by the service supplying these meters.

35. Piping for Laundry Room. In a flat building where appliances, such as laundry

stoves, driers, etc., are installed for the joint use of tenants, a pipe from each tenant's meter must be run to the laundry room and a header provided on the wall adjacent to the appliance. Each riser must be equipped with a lock-cock.

A meter tag with the flat number plainly marked thereon must be securely fastened to each cock.

One outlet for a light in the laundry may be taken from the end of the laundry header.

36. Riser in Cold Basement. A riser in an unheated basement should be located 4 feet from an outside wall. If, however, the owner desires the meter set on the outside wall, this will be permissible, provided a false partition of wood is built and an air space of 2 inches is left between the partition and the wall.

37. Vestibule Partition. A riser must not be run closer than one foot to a vestibule partition.

38. Electric Cut-off Box. A riser must never be brought to a point nearer than 5 feet from an electric cut-off box.

39. Riser in Other Apartment. A riser for one apartment must not end in another apartment, except as provided for in Rule No. 46.

40. Prohibited Locations for Risers. A riser must not end in any place where the Gas Company's meter will be exposed to frost or dampness, or liable to injury from any cause.

LOCATIONS SPECIFICALLY PROHIBITED.

Under a bulkhead or show-window.

Horse stall or any place in a barn where it would be at all liable to be disturbed by horses.

Sleeping apartment.

Stairway closet.

Bedroom closet.

Under a sink or washstand

Over a toilet stool.

In the way of a flush tank.

Over a gas or an electric light.

In a closet that is not properly ventilated by means of either a register or an opening close to the ceiling.

In a room where a moving picture machine is to be operated.

Chicago's Finest Apartments



The Harbor Apartments
3400 Sheridan Road

P. J. WEBER, Architect

ARE installing the **Stevens System** of Sound Deadening as evidenced by the illustration herewith of one of Chicago's latest and most luxurious apartment houses.

This equipment was selected for this magnificent edifice after a thorough investigation of its merits and installations, which proved beyond doubt that it has proceeded to a point beyond the experimental stage.

Sound Deadening is not only desirable, but is an essential feature of present day construction.

The installation of the **Stevens System** in the accompanying building involved 94,128 square feet of wood floors. No wet, slow drying cinder concrete fill; hence no warping or buckling of floors. It saves time and money.

STEVENS PARTITION AND FLOOR DEADENER COMPANY

501, 175 W. Washington St. CHICAGO

Telephone, Main 3154 and Main 1272

SAUMS PRESERVATIVE

"The Floor Everlasting"

For Wood Floors

Penetrates entirely thru 1" flooring.
Cannot be worn or scrubbed off.
Waterproof and acid-resisting.
Uniform appearance.
No bare spots at doorways.
Prevents warping and swelling.
Prevents splintering and dusting.
Prevents dry rot.
Is non-inflammable.
Eliminates upkeep expense.

For Concrete and Composition Floors

Penetrates from 1/4" to 1/2" into floor.
Seals voids in surface.
Is **not** a chemical hardener.
Waterproof and acid-resisting.
Prevents dusting.
Prevents disintegration.
Cleans easily.
Makes uniform wearing surface.
Even appearance.
Eliminates upkeep expense.

Twenty Years of uniformly successful use on the largest and finest buildings in United States and Canada.

Furnished and Applied by

SCOFIELD, EVANS & COMPANY

Tel. Harrison 1188

508 SO. DEARBORN ST., CHICAGO

"SECO SERVICE FIRST WILL ALWAYS LAST"

41. Riser in Front Hall. If the riser in an old building must end in the front hall, the pipe must not be run to a point nearer than 4 feet from the outside wall.

42. Height of Risers. A riser must be placed at a height of not less than:

4 feet from the floor for openings up to 60 in number.

5 feet from the floor for 60 to 100 openings.

6 feet from the floor for any number over 100 openings.

No riser must be placed higher than 9 feet from the floor.

43. Distance Below Ceiling. A riser must extend not less than 1½ inches below a finished ceiling, or 2 inches below an unfinished one.

44. Exit Lights. When running pipe for exit lights in theatres, schools, amusement or assembly halls, the city building ordinance should be referred to.

45. Public Lights—3-Flat Building. In a three-flat building or over, outlets for vestibule, public hall and basement lights must be taken from an independent pipe, and an opening left on the building service so that a separate meter can be set for these lights. If so desired, the riser may be connected with a union, or a right and left coupling to the meter of the applicant who may wish to pay for the gas.

46. Public Lights—2-Flat Building. In a two-flat building the outlets for the vestibule and basement lights must be taken from a separate riser, the end of which must be located near the first floor riser so that these outlets can be connected. A separate outlet in the building service for the vestibule and basement lights will not be required.

OUTLETS.

47. Outlet for Fuel. If the pipe has been run under the floor, the outlet for fuel in a kitchen must be left 3 inches above the floor and 2 inches clear of the baseboard. If the pipe has been run overhead and down, the outlet must be left 3 feet from the floor and 2 inches clear of the finished wall.

48. Drops. Drop outlets in a residence must be produced 1½ inches below an unfinished ceiling, or ¾ inch below a finished one. In a store the drop outlets must be produced 2½ inches below an unfinished ceiling, and 1½ inches below a finished one.

49. Mantel or Fireplace. An outlet for mantel or fireplace must be produced ½ inch above the finished bottom of the fireplace, 6 inches from the left hand side and 6 inches from the back.

BUILDING SERVICES.

50. Building Service Only. If it is desired to install a building service only in any building, instructions for size of pipe and openings to be left must be obtained from the General Office of the Gas Company.

The size of the building service must in every case be determined by the size and number of openings.

51. Building Service in Flat or Residence. A building service for a flat building, or a residence must be run overhead, and brought down in an inside partition, not less than 4 feet from an outside wall.

No building service must be run under a basement floor or under a first floor where there is no basement.

52. Building Service in Store. A building service in a store may be run overhead the entire horizontal run of pipe can be added to the street service. If not, it must run under the floor.

When a building service is run overhead it must be brought down at least 4 feet from the front wall of the building.

53. Building Service Underground. When it is necessary to extend a building service underground from the front to the rear of a store or factory building, it must be encased in tile pipe with cemented joints.

54. Running Two Services in One Trench. When two services are to be installed from a main in a paved or unpaved street to supply two (2) buildings under the same or different ownership, if these buildings are not more than fifteen feet (15') apart, such services may be run in one trench to a point inside the lot line and then branched, one to the right and the other to the left, to the respective buildings, being sure that each service is laid in its respective lot.

In all services run in the above manner, fitter will bring building service and house riser to side of building where service is to enter.

55. Building Service in Unheated Basement. A building service in an unheated basement must be graded to the street, and the tee left turned up so that any condensation forming in the pipe will run to the street and not to the meter.

56. Solid Wall Porch. In a building with a solid wall porch, the building service must be run to the front and then to the side wall inside basement.

57. Service Beyond Front Wall of Building. When there are one or more finished rooms in the front part of a basement and the owner does not wish to have the building service appear in these rooms, it may be terminated outside of them, but as close to the front of the building as the finished portion of the basement will permit.

No service pipe will be laid in a space covered or to be covered with cement.

58. Location of Building Service. When risers are located in the rear of a basement or in a room provided for that purpose, or on the various floors, the building service must be brought to within 18 inches of the wall through which the street service will be produced.

59. Wrapping Building Service. A building service run under an open porch and connecting the front and rear sections of a building, must be covered with mineral wool or steam pipe covering and boxed in.

60. Encasing Building Service. A building service laid through a masonry wall must be encased and the pipe left resting on the bottom of the casing with a 1½-inch clearance on top.

61. Opening in Building Service. The opening in a building service should always be on the left hand side of the riser which it is to supply, and 15 inches from it.

62. Test-pipe to Prove Work. Every building service must have a ¾-inch test-pipe to which a gauge can be attached.

63. Building Service Header. When it is necessary to set more than two meters together, a building service header must be supplied with an opening for each meter.

64. Street Services for Stores. A building containing stores must have a separate service for each store, unless a public meter room or other public place on the floor or below that where the gas is to be used is provided.

65. Street Services for Apartment Buildings. In apartment buildings of 12 flats and under, only one street service will be required. This will make it necessary to connect the various building services supplying the groups of risers regardless of firewalls, and extend one building service to the point where the street service will come in.

Bell



System

Of Interest to Architects and Builders

It is desirable that provision be made in the original plans for office and apartment buildings for carrying large systems of interior wiring necessary for furnishing telephone service.

Foresight in this detail will remove possibilities of extensive and costly alterations, for the purpose of concealing the wires, after buildings have been completed.

One of the functions of the Plant Engineering Department of the Illinois Bell Telephone Company is to make complete studies of plans for the accommodation of interior telephone wiring. It offers to architects and builders the benefit of its experience, and will consult without charge as to the system best adapted to each large building project.

Call Official 300

M. H. Riley, Division Plant Engineer

ILLINOIS BELL TELEPHONE COMPANY

In apartment buildings containing more than 12 flats, two or more street services will be allowed.

66. Street Services for Court Buildings. In a building which faces on a park-way or has a park-way or court in the center, one street service will be run in the court or park-way and branched therefrom to supply the various building services.

The gas fitter may run building services through fire walls and connect them, but these must be extended as close to the front of the building as possible.

Any building service in a court building must not be terminated in a finished room.

67. Locating Service to Corner Building. To avoid complications when working on a corner building, the gas fitter should obtain from the Gas Company a written notice giving the exact location where the street service will enter the building.

68. Building in Rear of Corner Lot. A building on the rear of a corner lot must be supplied from the side street if a gas main is on that street. If not, it may be supplied either from the front building or directly from the main, whichever is the more practicable.

69. Building in Rear of Lot. When a building in the rear of a lot is to be supplied, a separate service should be used, wherever possible. If, however, an independent supply is not practicable, the building service for the front building, if there is one, must be extended to the rear of the building, and of a size not less than 1½ inches so the rear building can be supplied from it also.

In all cases where a supply to a rear building is desired the Gas Company must be consulted.

70. Opening in Wall for Street Service. In a new building, an opening should be provided in the wall for street service. The most preferable way is to build a sleeve of wood, rectangular in shape, 12 inches by 6 inches, with an inside partition about 6 inches from the street end of the sleeve.

Application should be made to the General Office of the Gas Company to locate the wall and the point in the wall wherein the sleeve should be built, so that when the service pipe is run, it will pass through the opening, provided therefor. In this way

the damaging of foundation walls will be avoided.

71. Opening in Floor for Stand Pipe. When a stand pipe connection may have to be made above the floor level, an opening must be left in the floor so that the stand pipe can be introduced without disturbing anything. The Building Inspection department will, on notification, instruct the gas fitter where to leave this opening.

72. Bringing Building Service to Street Service. When the street service is into a building before the house-piping is completed, the building service must be brought directly over the street service, except where the street service comes through the bay, then the building service must be brought to the nearest corner of the bay.

73. Terminating Building Service. A building service must not be terminated in a coal hole or in any other place where it will not be easily accessible.

WORK DONE BY THE GAS COMPANY.

74. Work Reserved. This Company does not permit anyone but its own authorized employees to place any piping or connections on any part of either the outlet or inlet meter connections, turn on the gas, disconnect, move, or interfere in any way with its piping, meters or connections.

75. Alterations in Building or House Pipes. When a customer desires to have any work done or alterations made on his premises which necessitate the disconnecting, or reconnecting, or alteration of the service or meter installation the Gas Company may undertake to do the work and charge the customer the actual cost.

If the customer's pipe fitter does the interior piping the Gas Company will reconnect service and reset meter and charge the actual cost to the customer.

76. Charge for Service Pipe Inside Property Line. In accordance with an order of the State Public Utilities Commission service pipes shall hereafter be laid within the property line at the sole cost of the applicant.

Where a service is to be laid in a paved street, under Street Railway tracks or on streets controlled by Park Boards, the applicant shall deposit with the Company in advance of laying the service a sum sufficient to cover the cost of repaving.

SUGGESTIONS FOR THE PROVISIONS OF WIRING AND CABLING OF BUILDINGS FOR SERVICE OF ILLINOIS BELL TELEPHONE CO.

The extensive use of the telephone in office buildings, hotels and large apartment buildings renders it essential that a provision be made in all modern buildings of these types, in advance of their completion, for carrying the requisite number of wires necessary for furnishing telephone service.

Where a private branch exchange switchboard or a building basement terminal is stalled it is necessary to carry at least 50 wires from each telephone to the central distributing point in the building. Where these buildings are furnished telephone service by means of cable it is generally necessary to extend a building cable and establish one or more branch terminals, from which the distributing wires are taken. Hence, the importance of making adequate provision in advance for such building cabling and wiring.

It is advisable to have such provision included in the building plans. Otherwise the walls may be disfigured by unsightly open runs, or it will be necessary to make openings through the walls, floors and partitions after the completion of the building. The Telephone Company will be pleased to furnish the owner or architect with all

necessary information as to size, type and location of conduits. Building wiring may be logically divided as follows:

(1) APARTMENT BUILDINGS.

The term apartment buildings as used herein means buildings larger than single houses or stores and smaller than office buildings. Such buildings may contain living and office apartments, also stores, generally on the ground floor.

In an apartment building the maximum number of telephones in any one apartment, or on any floor, is quite definitely fixed, generally one per apartment.

Vertical building conduit, with an outlet at each floor, should be installed in each tier of apartments in an apartment building.

(2) OFFICE BUILDINGS.

The wiring of an office building presents a difficult problem for the following reasons:

The number of telephones will depend largely upon the character of the business and district. The number of telephones on any floor of these buildings will depend upon the requirements of the individual tenants



At present, particularly, it is important for you to know that no other plastering base for exterior and interior, is so economical as **E-Cod Fabric**. Lower than any other durable base in first cost and available for immediate shipment, it saves in every plastering operation. **E-Cod Fabric** saves from 40% to 60% of the scratch coat required on any ordinary open mesh lath to form the key. Plaster can be applied faster, saving heavily in expensive labor—time. For real economy in building specify **E-Cod Fabric**. Full particulars and samples on application.

MacADAMS & CALL
Conway Building CHICAGO

Vitrifyx Floor Preservation Service

Prevents Concrete Floor Disintegration



Vitrifyx is a clear, colorless, liquid chemical, which when applied to concrete floors, penetrates every pore. Vitrifyx welds the cement particles into a solid flint-like impervious mass.

Permanently Preserves New Wood Floors

And Restores Old Ones



Vitrifyl is employed for treating wood floors. It is a liquid compound of oils, gums and resins. It penetrates the entire flooring and gives many years of additional wear, toughness and freedom from warping, dusting, rotting, slivering and cracking.

Hydrolithic—"The Heart of Concrete"



Hydrolithic is a liquid chemical concentrate applied integrally by adding to the gauging water of the concrete mix. For a quarter of a century it has been successfully used in the world's finest structures. Send for complete literature, reference and specifications.

THE VITRIFYX COMPANY

2526 West Congress St.

CHICAGO, ILL.

This is not constant for any extended period, as tenants may from time to time be replaced by others using more or less service.

In office buildings where the floor is likely to be divided into a large number of rooms or offices the distributing wires from the floor terminals to telephones can be run in moulding. The floor terminals should be located near the ceiling. A suitable moulding should be provided in the halls for carrying the wires from the terminal boxes to the various rooms. A smaller moulding should also be provided in the individual rooms, or suites of rooms, for carrying the wires to the proper location desired.

At certain intervals, depending upon the arrangement of the building in question, it will be desirable to have a piece of conduit extend across the ceiling of the hall in order to distribute from the floor terminal on one side of the hall to the rooms on the other side of the hall, in case there is no terminal on the other side.

With the system above described, the wiring is practically concealed and the system is flexible enough to allow proper distribution of facilities among the various rooms on the floor.

In large office buildings it is necessary to have a cross connecting rack—to afford means for getting connections between different floors. In the case of very large buildings a small room should be designed for this in the basement.

Cable.	Conduit		Conduit		Conduit Run Less than 75'. One 90° Bend.	Conduit Run More than 75'. One 90° Bend.	Outside Diam. of Cable.	Size of Pull Boxes.
	Twisted Pairs.	Straight Run Less than 75'.	Straight Run More than 75'.					
	2	½"	½"		½"	¾"		4"x4" 2" deep
	4	¾"	¾"		¾"	¾"		6"x18" 4" deep
25-pr.		1"	1"		1"	1¼"	23/32"	6"x20" 4" deep
50-pr.		1¼"	1½"		1½"	1½"	29/32"	6"x20" 4" deep
100-pr.		1½"	2"		2"	2"	1 3/16"	8"x24" 6" deep
200-pr.		2½"	2½"		2½"	2½"	1¾"	10"x30" 8" deep
300-pr.		3"	3"		3"	3"	2 1/16"	12"x32" 8" deep
400-pr.		3"	3"		3"	3"	2¾"	12"x32" 8" deep
600-pr.		3½"	3½"		3½"	3½"	2¾"	12"x36" 10" deep

Conduits smaller than 1" are objectionable for lead covered cable because they are frequently deformed during construction of building.

All runs exceeding 100 feet in length
All runs having more than two 90° bends
All runs having bends sharper than 90° } should be provided with pull boxes

When an entire office building, or several floors of a large building, is devoted exclusively to the purposes of one firm, some floors are generally not subdivided into small rooms, yet it is necessary to supply telephone service to many desks in the large rooms, and it is desirable to have the telephone wiring concealed.

If the room has columns and the desks can be grouped along the walls and about the columns, outlet boxes can be placed adjacent to these groups of desks and these outlets connected to distributing centers by run conduits, as described under "Hotel" wiring.

Where a very large use of telephones is contemplated, outlets may be placed in the rooms on approximately five-foot centers, which outlets are connected to distributing centers by a lateral system of ducts or iron conduits.

(3) HOTELS.

Depending upon the size and location, type and kind of building and character of service contracted for, a hotel may be included

in either the office building class or the apartment building class or a part of both.

Where a very large use of telephones is contemplated, outlets may be placed in the floors on approximately five-foot centers, which outlets are connected to distributing centers by a lateral system of ducts or iron conduits.


The telephone system installed in hotel buildings consists of a telephone switchboard located at some convenient point, usually on the ground floor, in, or near the office. Telephones are placed in each room or suite and wired to the switchboard, which is connected by one or more trunk lines with the nearest exchange of the Telephone Company. The wiring problem is, therefore, comparatively simple, involving the running of a pair of wires from some definite point in each room or suite to a common center near the switchboard location. Provision should also be made so that the Telephone Company can run its trunk wires from the switchboard to the point at which the telephone cable enters the building from the street, usually in the basement. A two (2) inch conduit is frequently sufficient for this purpose.

The method of getting wires from the common point (switchboard) up through and to the various floors, also the provision for terminating service cables, is the same as above described for cabling of office buildings.

From the floor terminal a conduit one-half (½) inch inside diameter is run to a designated location in the wall of each room in

which a telephone is to be placed. The height of the outlets in each room should be about five (5) feet from the finished floors; this will depend largely upon the desire of the hotel architect or owner. A one-half (½) inch (inside diameter) conduit should not be over fifty (50) feet in length, nor have more than three bends with a minimum radius of five (5) inches. Any conduit one hundred (100) feet in length should not be less than one (1) inch inside diameter. One-half (½) inch (inside diameter) conduit should be provided for a maximum of two pairs of wires; three-quarters (¾) inch (inside diameter) conduit for five pairs; and one (1) inch (inside diameter) conduit for nine pairs. In extending conduit from terminal boxes to rooms it is possible in many cases to use one run of larger conduit to supply three or four rooms, rather than run smaller conduit to each individual room. When the floor area and the number of rooms are large it may be found economical to have more than one terminal box on a floor

Kno-Burn METAL LATH



“The Steel Heart of Plaster”


VERY impressive indeed would be a list of the “million dollar” theatres, residences, churches, schools, apartment buildings, libraries, etc, for which KNO-BURN Metal Lath has been specified.

But more important perhaps is the growing number of *moderate priced residences*, made more permanent and fire resistive by the use of this economical, small diamond meshed plastering base.

May we send you, without cost, a book describing its special advantages for stuccoing, interior plastering, fire-proofing and rat proofing, also samples and recommended specifications?

NORTH WESTERN
EXPANDED METAL CO.

928 Old Colony Building
CHICAGO



SPECIFICATIONS FOR ERECTING METAL LATH

Recommended by the Associated Metal Lath Manufacturers.

(Approved by Executive Committee, July 1, 1920.)

GENERAL.

Metal Lath for inside walls and partitions and for fire-proofing columns, brackets, ducts and vertical furring where tied to steel shall weigh not less than 2.5 pounds per square yard; where attached to wood shall weigh not less than 2.3 pounds.

For Ceilings Metal Lath shall weigh not less than 3.0 pounds per square yard tied to steel or 2½ pounds if attached to wood with supports spaced not greater than 16 inches center to center.

For exterior stucco work Metal Lath shall weigh not less than 3.4 pounds per square yard.

Ribbed Metal Lath shall not weigh less than the minimums above, but the spacing of supports shall be in accordance with the published recommended practice of the manufacturers thereof.

Sheet Metal Lath shall weigh not less than 4½ pounds per square yard with supports for non-bearing partitions and ceilings not more than 24 inches on centers, or for bearing partitions not greater than 16 inches on centers.

Staples shall be 1¼" by 14 gauge smooth wire, driven to a penetration of at least ⅞ inch.

Nails shall be not less than 4d, for flat metal lath and where ribbed lath or furring is used, 6d nails shall be used. They shall be driven to at least ⅞" penetration and shall be bent up to engage at least one strand without breaking.

Tie Wire shall be not less than No. 18 gauge black annealed lather's wire.

Furring for wood frame buildings shall be at least ½" by 22 gauge crimped steel or 16" pencil rods, or self-furring lath.

Furring for suspended ceilings shall be ½" cold or hot rolled channels.

Runner Bars for suspended ceilings shall be not less than 1½" cold or hot rolled channels, or 1½"x1½"x¼" angles, or 2¼" by 16" flats.

Hangers for suspended ceilings shall be 3" rods, or No. 8 galv. steel wire fastened by twisting, or 1" by ⅝" flats.

WOOD FRAME BUILDINGS.

Where furring is used it is to be fastened to studs and joists by nailing or stapling every 12 inches.

The metal lath is placed with the long dimension (8 feet) across supports and fastened by nailing or stapling every 6 inches. Staples are placed astride the furring, nails are bent over the furring. The sheets are lapped not less than ½" on the sides and ed once with wire between supports. Endsapped not less than 1" over supports.

The lath is first applied to ceilings and carried down 6 inches onto all walls and partitions.

All lath shall be started one stud away from a corner and be bent into the corner to avoid a lap there.

On walls and partitions the lathing is started at top and carried down, the lower sheets lapping over the upper sheets. (The lap being not less than ½".)

Diamond Lath, sheet lath or ribbed lath on exterior work should be fully imbedded in cement by back-plastering where wood sheathing is eliminated, furring with ½" crimped pencil bars (or self-furring lath). For overcoating, or where sheathing is required, at least ⅜" space shall be provided behind the lath and must be filled by cement plaster.

SUSPENDED CEILINGS.

Hangers are placed 4 feet center to center in both directions. Where suspended below concrete construction, hangers are placed before pouring concrete; below flat arch hollow tile, hangers are fastened to toggle bolts inserted after tile are placed, or by hangers extending completely through the block. Where steel beams or purling are not more than 4 feet center to center, hangers may be attached directly to them.

Runner bars placed 4 feet on centers are bolted to hangers, or suspended by securely twisted loops formed in the lower ends of the hangers.

Channels are placed not more than 3¼" on centers across the runner bars and clipped securely to them. Where integral lath or ribbed lath is used, the channels may be spaced on centers in accordance with the standards as published and recommended by the manufacturers.

The metal lath is then wired to the channels, the long dimension (8 feet) of the sheet being across the channels. The ties are placed 6" apart, sheets are lapped not less than ½" on sides and not less than 1" on ends and tied once between supports.

SOLID PLASTER PARTITIONS.

Studding used for solid partitions shall be ¾" cold or hot channels 15¼" center to center for partitions not to exceed 16 feet in height and 1" channels for greater height properly braced during plastering. Where ribbed lath is used, the partition shall be erected in accordance with the standards as published recommended practice of the manufacturers.

The channels are held in place by springing into holes drilled in floor and ceiling. On wood floors, channels are bent to an angle and spiked, or set in shoes.

The metal lath is fastened to the channels, with the long dimension of the sheet across the channels, by wiring every 6 inches.

Sheets are lapped not less than ½" on sides and wired once between supports and lapped not less than 1" at ends over supports.

All lath shall be started one spud away from a corner and be bent into the corner to avoid a lap there.

The work is started at the top of the partition and carried down so that the lower sheets lap over those above.

AMERICAN BRIDGE COMPANY

EASTERN DIVISION

30 CHURCH STREET, NEW YORK, N. Y.

PITTSBURG DIVISION

FRICK BUILDING, PITTSBURG, PA.

WESTERN DIVISION

208 S. LA SALLE STREET, CHICAGO, ILL.

MANUFACTURERS *of*

STEEL BRIDGES

STEEL BUILDINGS

AND ALL CLASSES OF

STEEL STRUCTURES

INCLUDING

Barges, Hulls *and* Transmission Towers

Heroult Electric Furnaces

—

FORGINGS

and

HEAT TREATMENT

STRUCTURAL BUILDING STEEL

By Frank J. Llewellyn, Member American Society of Civil Engineers

This article is republished by request as many Architects and Engineers have been added to our mailing list this year. The article has been revised and brought up to date.

Last year I was entrusted with a discussion of the subject of STRUCTURAL BUILDING STEEL, with special relation, as suggested by the editors, to its "manufacture"; its "cost as compared with pre-war conditions"; its "comparison with concrete construction"; and finally, to "such surrounding special or general features as might be of interest to architects, engineers, contractors or builders."

Since the appearance of this article, which is now largely reproduced below, Structural Building Steel has made only slight history. Its employment has for the time being dropped to possibly one-fifth of the normal consumption. Under these circumstances, the Stabilizing Process which had been arbitrarily and unselfishly accomplished by leading mills during the long period in which demand had greatly exceeded supply has been swept from existence.

By successive and rapid stages the sensational prices of those who had been operating at the higher levels dropped to the rational and moderate basis which had been adopted by leading mills as the result of the conferences held with the Government at the beginning of the year 1919.

But they did not stop at this point: the Stabilization, so grateful in a market whose trend had been violently upward, was no longer welcome under the reversal which had taken place in the relation between supply and demand; prices dropped lower and still lower, until now both rolling mill and fabricator are operating at a level which is effecting a serious drain upon their resources.

Thus has Steel fallen from its high estate, and from Prince, almost at a single bound has become Pauper. Under conditions such as these, little place has for the moment been found for activities not centering in what has come to be the one vital question of the day: How To Keep Going? The hour now striking has perforce been given over to Commissions of Inquiry, to Investigations, and to Indictments, in the effort to discover "What Is the Matter?" and to bring Costs into proper relation to Selling Prices.


During, then, this period of struggle for very existence, one can well understand that the lines of progress with relation to improved practice in the design and employment of Structural Building Steel may easily have come almost to a standstill. Nevertheless, time has been found for further study of the design of rolled material as applied to both beam, girder and column sections, the results of which are appearing from time to time in the announcements and Handbooks of the Steel Makers.

The subject of electric welding, too, has undoubtedly moved forward, and there is even tentative promise of a built-up steel column in which the spot weld will replace the rivet. Such practice, however, is still regarded as a far cry as related to the employment of steel in important structures.

Otherwise, there is little change in the general status of the subjects discussed in last year's Handbook. The Price Table has been corrected and brought closely down to date. It will at once be noted that from the high point—\$122.60 per net ton in 1920—to the low point—\$65.00 per net ton to August 31st, 1921, a fall in price had occurred on Steel Skeletons delivered at Chicago of \$57.60 per ton. With the added fact that the freight rate from Pittsburgh to Chicago on Structural Steel is only \$7.60 per ton, is it not possible to get a sounder, a more intelligible view of the much exploited question of the "Pittsburgh Basing Point"? It would seem to be a self-evident fact that the Chicago rolling mills may be depended upon not to submit to the dictation of Pittsburgh mills whereby they would add to their quotations freights or other figures which would interfere with their sales, and which would at the same time permit the Pittsburgh sellers to capture the business. Prices cannot be fixed, or if fixed, cannot be maintained either as the result of gentlemen's agreements or of delightful foregatherings around the dinner table. On the contrary, they are dependent upon a much more direct and simple law, whose operation is governed by the relation existing between supply and demand. A year ago steel requirements were greatly in excess of the maximum possible production—price result \$122.60 per ton. Today the steel making capacity is certainly four times greater than the demand—price result already \$65.00 per ton; while the "Pittsburgh Basing Point" remains now, as always, merely a basis of Price Comparison.

The setting which suggested and possibly made appropriate the concluding paragraph or the former article has now become considerably modified. Some of the forecasts are already well on their way towards fulfillment. Matters, however, are as yet by no means entirely rectified, so that with this added introduction the original article now follows:

At the outset we will rely not upon the text-book, but upon the "note-book" and upon the recollection of the "oldest settler": delightful sources of information, through which, by way of introduction, we may venture as far back as to the great Chicago Fire in 1871, when "iron" construction as employed in buildings was an infant in



Rolled from new billet stock only

Include in Your Specifications

reinforcing bars that will add the greatest strength and stability to the structure.

Kalman Grip Bars

insure these features of permanency of construction.

Round and square sections rolled to identical weight of plain bars.

Shop Bending
Spirals



Concrete
Accessories

PAUL J. KALMAN CO., INC.

Executive Offices
22 West Monroe Street
CHICAGO, ILL.

District Offices

ST. PAUL, MINN.
Merchants Nat'l Bank Bldg.


MILWAUKEE, WIS.
First National Bank Bldg.

MINNEAPOLIS, MINN.
Builders Exchange Bldg.

KANSAS CITY, MO.
Security Bldg.

WAREHOUSES
CHICAGO—ST. PAUL—MINNEAPOLIS

Catalogue on Request



Rolled from new billet stock only

arms, but tough and tractable withal. The "standard of practice" then in vogue involved the employment of cast iron columns and rolled iron floor beams, as exemplified in

The **Post-Office** at Dearborn and Monroe Streets, in which the conflagration just referred to resulted in a heat so great that the columns gave way and everything fell into the basement:

The **Tribune Building** at Madison and Dearborn Streets, which seemed to be passing through the fire fairly well until a twelve-inch cast iron shell filled with black powder, a souvenir of the Civil War, and which had its place in one of the editorial rooms, exploded and tore out part of the Madison Street front, bringing down the floors above:

The **First National Bank Building** at Washington and State Streets, where the iron construction gave a very good account of itself; and

A building which was in course of construction at the corner of Monroe and La Salle Streets, on a portion of the site which is now occupied by the New York Life Insurance Building, in which the floor beams were so little damaged that the building was finished in accordance with the original plans and using actually the original material in the iron floor construction.

Followed a period of extreme activity in all building lines, as illustrated by the fact that two architects practicing at that time were each reported as having the equivalent of "five miles" of building frontage on their boards during the year 1872. However, the Palmer House was the only building of importance at that immediate period which went forward with iron construction.

There was no essential change in the practice for some years; and as late as 1884 and 1885 the Home Insurance Building and the Rookery Building were being constructed with cast iron columns and iron floor beams. The Chicago Auditorium, 1887, is one of the earliest buildings in which steel beams were employed, although to a very limited extent only, the main construction still consisting of cast iron columns and iron beams. The earlier instances of built up riveted columns are to be found in the Masonic Temple, 1891, and in the Ashland Block and the Chicago Athletic Club. Those in the Temple, however, were still of iron, but those in the Athletic Club were of steel; and from that time forward riveted steel columns rapidly monopolized the building field.

At this point we may quote not only the broadening use of steel, but also its greatly broadened characteristics, as compared with a largely opposite condition as to wrought iron. In earlier days the matter was delightfully simple. Popularly and paradoxically, any wrought iron that could be tempered was "steel"; if it could not be tempered then, of a truth, it was iron. Today the

term "wrought iron" is applied almost exclusively to the product of the hand puddling furnace, or to the material produced by building up fagots of scrap, heating them to welding temperature and hammering them into billets for reheating and rolling to the desired shapes. The term "steel," however, covers such a multitude of products that the name itself gives little clue to the varied results which are obtained. This is exemplified in the practice of the American Society for Testing Materials, who have produced separate specifications characterizing the various steels most suitable for

Bridges, Buildings, Structural Parts of Locomotives, Steel Cars, Steel Ship Frames and Plates, Rivet Steel for Ships, Boilers and Fire Boxes, Boiler Rivet Steel and Steel Concrete Reinforcing Bars.

And this introduces us at once to the subject of **Alloy Steel**: a well established innovation which, as touching our subject, has so far only found its way into bridge design and construction. Perhaps the most comprehensive definition of this material is that given by the International Association for Testing Materials, as follows:

"Alloy steel is steel which owes its distinctive properties chiefly to some element or elements other than carbon, or jointly to such other elements and carbon. Some of the alloy steels necessarily contain an important percentage of carbon, even as much as 1.25 per cent. There is no agreement as to where the line between alloy steel and carbon steel shall be drawn."

More in detail, Henry D. Hibbard of the Bureau of Mines gives the following classification:

"Simple steel (often called carbon steel or plain steel) consists chiefly of iron, carbon and manganese. Other elements are always present, but are not essential to the formation of the steel, and the content of carbon or manganese, or both, may be very small."

"Alloy steel (sometimes called special steel) is steel that contains one or more elements other than carbon in sufficient proportion to modify or improve substantially and positively some of its useful properties."

"Alloy-treated steel is simple steel to which one or more alloying elements have been added for curative purposes, but in which the excess of the element or elements is not enough to make it an alloy steel."

As shown by the foregoing classification, the introduction of the various alloys into the manufacture of steel is for the purpose of increasing its efficiency; and the economic use of such material as applied either to bridges, buildings or other structures will depend upon the ratio of the increased efficiency to the increased cost of production. Bridge design and construction has already been greatly advantaged along these lines:



SPECIFY "PresTeel" STAIRWAYS

MADE to suit any building or condition. We furnish these stairs to correspond with any architectural design, plain or ornamental balusters with newel posts to match.

Manufactured by

Woodbridge Ornamental Iron Co.

1519 Altgeld Street


CHICAGO

ILLINOIS

Write for Our Stair Catalog

We are specialists in the manufacture and erection of Presteel Stairways.

Our engineering department is at your service, and is ready to assist you in planning stairways that will give the maximum of service at a reasonable cost.



first, by the introduction of nickel steel eye bars, and subsequently by the employment of an alloy steel in other main members. This, by the reduction in the dead load, has resulted in increasing the permissible length of what is known as the simple span (as distinct from the cantilever, arch or suspension type):

See, for example, the **Municipal Bridge at St. Louis, Missouri**, consisting of three double deck pin connected railroad and highway through truss spans, each 668' center to center of end pins; in which the main sections of the truss members, including eye bars, pins, turnbuckles, pin plates and splice plates are of nickel steel; the floor system, the bracing and all miscellaneous members and minor details of the truss members being of carbon steel, with a corresponding division of field and shop rivets; and

The **Bridge over the Ohio River at Metropolis**, a double track structure which, in addition to four 550' through pin spans, one 304' through pin span and one 247' deck pin span, included one through pin span 720' in length; in which all the main members of the trusses are of silicon steel; the eye bars and pins of nickel steel, and the remaining material of medium structural steel.

The advantage to other types of spans is equally great, of which the most recent distinguishing example is the new **St. Lawrence River Bridge at Quebec**, in which nickel steel was used practically throughout, except in the floor system, which was of carbon steel.

Essential to the fullest employment of alloy steel is the practice of **Heat Treatment**, concerning which it is perhaps sufficient to say that this high-sounding title merely describes the modern refinement of the old method of tempering which is familiar to all. But while this general statement is true, it should be said that up to the present time probably no alloy steel used in bridge construction has also been heat treated, such heat treatment having been confined almost exclusively to eye bars manufactured of steel carrying a high carbon content.

An important phase of this particular subject is that which is embraced in the practice of the addition of a small percentage of copper to sheet material, both flat and corrugated, plain and galvanized, which greatly reduces the tendency to rust.

A further noteworthy advance is found in the improvement which has been effected in the outlines of the rolled sections now current. Appreciation of the intricacies of this problem will be heightened by consideration of the fact that rolled sections are subject to three distinct sets of strains: first, those incident to the process of rolling the ingot to the finished shape; second, those incident to the cooling of the finished sections after they have left the rolls; and third, those to which the finished material is subjected under load in the completed building. Exhaustive tests and experiments have been conducted covering all the phases of this sub-


ject; there has been consultation and co-operation amongst metallurgists, engineers and manufacturers to produce the present standard shapes which, when modified in accordance with the most recent recommendations, will undoubtedly furnish as great a degree of strength per dollar's worth of finished material as so far it seems possible to attain. The modifications now being considered, and which have already been accepted in part, involve the adoption of British standard sections as to ship channels and shipbuilding bulb angles, which appear to be better adapted to economical manufacture than the American standard for these sections; and in the adoption of a new line of beam sections to take the place of the present American standards which were established in 1896. These sections will have wider flanges, and are believed to be more nearly in accord with the most recent developments in the fabrication of bridges and buildings.

Practically all of the American manufacturers of structural shapes own their ore, coal and stone lands, and many of them also own their transportation facilities from the mines to the works for all of these materials.

Having come thus far along introductory lines, it will, at this particularly critical period of our national and industrial life, be appropriate that we proceed to the consideration of economies, of reduction in costs, which may be open to us as touching the use of steel in building construction. Two definite suggestions might at once be considered:

First: The employment of a low priced alloy steel; concerning which, however, it must be said that the immediate moment would present some difficulties. Congestion upon the railroads and amongst the furnaces and mills is already very great, and the application of new or special specifications to current structural steel manufacture would undoubtedly increase costs and limit production to a degree which would be highly undesirable, if not prohibitory. Such suitable low priced alloy steel, however, is already an accomplished fact, and with the return of normal industrial conditions can readily be made available; which would result in greatly increased working values and in materially reduced costs. It must, however, be borne in mind that the employment here suggested would, in any event, be applicable only in connection with the larger and heavier construction and where a reduction in the dead weight constitutes an important item. In small buildings and where only inconsiderable tonnages are involved, such employment would offer no advantages.

Second: Special co-operation amongst engineers and architects has been in existence for some time, resulting in a most earnest effort to bring about certain revisions in the City of Chicago ordinances with reference to building materials. The Illinois Chapter of the American Institute of Architects, the Western Society of Engineers, the Illinois



Johnson - Meier Company

Designers and  *Manufacturers*

Artistic Wrought Iron, Doors
Grills, Lighting Fixtures
Wall Brackets

Console Tables, Spark Screens
Table and Floor Lamps
Andirons and Bronzes

REPRODUCTIONS OF ANTIQUES

*Special attention given to Architectural Designs and the development
of work that requires artistic ability and study*

Telephone, Superior 5205

CHICAGO, ILL.

155 Wendell St.

Society of Architects and the Structural Engineers' Association of Illinois have each appointed five members who have formed a Joint Professional Committee on Materials and Methods, and this Committee has done splendid work in collecting data and drawing up specifications for the most important building materials. It is hoped that when these specifications, prepared by the Joint Committee, shall have been examined and recommended by the parent Societies enumerated above, the City Council will promptly adopt them; the result of which certainly will be to bring about additional safety to the public and at the same time to effect large savings in building costs; and it is a wider and more vigorous co-operation amongst all architects and engineers, and others directly interested in the subject, to bring about this desired result at the earliest possible moment that is suggested as the second of these two definite lines of effort.

A somewhat more remote, although by no means impossible field of economy may be found in the electrical welding of structural steel; in connection with which much is already promised, both as to cost and efficiency, by engineers who have made a careful study of this subject. It is confidently asserted that a considerable saving, as compared with the standard practice of riveting or bolting, can thus be secured. The three fundamental types of welds—namely, the fillet weld, the butt weld and the rivet weld—seem to compass all the practical conditions; and we have seen roof trusses in which the joints are thus welded together, and columns electrically welded to their bearing plates, which indicates a large amount of success already achieved. The evidence, however, upon this subject is not yet all in. Indeed, the present attitude seems to be that "Building departments and other inspection and control organizations have refused to allow the use of welding in building construction on account of the fact that they did not feel sure of a welded joint"; and, further, that "Welding depends for its quality and strength largely upon the skill and integrity of the workmen who perform it, and building inspectors have assumed that it was impossible to judge the quality of a weld once it was made, and for this reason they have not been convinced by the various tests that have been exhibited for their benefit, although such tests have demonstrated that welds can be made with 100% joints."

Whatever, therefore, may be hoped for in this direction is for the future to demonstrate, the present development of the art not yet being such as to widely and certainly justify its employment.

Along more general lines, it may be suggested that the attitude of the engineer of today towards the whole subject of working unit stresses will probably be found to result in final economies. The willingness to substitute factors based upon absolute tests

of material, both as to plain rolled sections and also as to fabricated columns and girders, in place of purely theoretical formulae, must certainly be reassuring to the consumer in relieving him of all uncertainty as to the waste which otherwise is not infrequently experienced.

Reinforced concrete construction, in comparison with the more standard steel frame and tile or other fireproof filling, has already been abundantly tried and proved; and notwithstanding the occasional accidents which are encountered, some of which have been extremely serious, this method may undoubtedly be regarded as both sane and safe, and for the past few years it has been widely practiced. The relative costs will, of course, vary from time to time; and with the wide fluctuations of the last several years it would be of little value to hazard any conjecture with reference thereto; whereas the answer to the question of relative desirability will probably always reflect primarily the personal preference and particular training and experience of the architect. It may be said, as to all steel construction, that one is dealing with a material the quality of which, from the manufacturer's standpoint, is insured by the fidelity of the blast furnace and open hearth foremen, who, highly trained in their vocation, are also personally interested in maintaining the quality of the material which they produce; a factor, indeed, which is also essential to the permanence of their employment and to the special remuneration which is based upon it. Strengthening this feature is the fact also that the inspector's representatives are constantly in the mills, observing and testing the processes of operation and the results which are secured. This inspection is continued in the fabricating shops to insure equally high workmanship during the later stages of manufacture. The factors, however, entering into the construction of concrete steel buildings are in many respects necessarily less positive; the quality of the material used is not so readily controlled, and the man at the mixer has a much less definite task to perform. The question, then, is always pertinent as to whether the chances of poor concrete are greater or less than the chances of poor steel. Determination of design and of comparative value as an investment by the owner must, of course, rest with the architect and his engineer, and will be answered in accordance with their skill in analyzing each particular case. In connection with such determination, however, there will always be taken into account the fact that the all steel construction affords greater latitude in the matter of interior arrangement as applied to large office buildings, railway stations, buildings for manufacturing purposes, theatres or other large structures. For example: long clear spans may be used without materially adding to costs and without resulting in heavy or unsightly architectural lines; while in the case of very tall buildings the all steel column results in a


Babcock Brothers Co.

(INC.)

Underwriters Approved

FIRE DOORS

Ornamental Iron



All types furnished and erected

OFFICE:

533-4 Marquette Building

PHONES:

State 1572

Randolph 1371

State 4573

FACTORY:

4235 West Kinzie Street

PHONE:

Kedzie 5862

CHICAGO, ILLINOIS

greatly reduced diameter as compared with reinforced concrete construction, thus permitting the most economic use of the available space and tending to an increased rental value.

Upon the subject of the costs entering into the production of steel, it is important to note that approximately 80% is for the account of labor, the balance of 20% covering overhead and distributive charges; so that the cost, and equally the selling price, will always follow the swing of general prosperity. Pig iron has for long been regarded as the barometer of business; today, however, the price of steel billets might be a better indicator. The following table, compiled from data published in the Iron Age, shows the high and the low prices for the various years of both Bessemer pig and Bessemer billets; and paralleling the same is given similar information compiled from personal data as to steel skeletons for fire-

further reduction which followed various conferences held between the Industrial Board and the steel makers, which went into effect March 21st, 1919. The sum of these two reductions approximated \$10.00 to \$12.00 per ton; and this left the base price on standard structural material at \$2.45 per hundred pounds f.o.b. cars Pittsburgh; which base has prevailed ever since, and on the part of the largest of our steel makers has probably not been exceeded. This means that building construction generally has not been subjected to any handicap resulting from inflated prices as applied to the rolled material itself. In other directions, however, variations in the prices of steel have been extreme; and the trade journals, in their weekly reviews, have taken cognizance of this fact, dividing the steel makers into two classes: on the one hand, those maintaining this established price; and on the other hand, those quoting much

YEAR	PIG IRON No. 2 FOUNDRY Price per gross ton—delivered Chicago		BESSEMER BILLETS Price per gross ton—delivered Chicago		STEEL SKELETONS Price per net ton—delivered Chicago		40 STOCKS	
	High	Low	High	Low	High	Low	High	Low
1900.....	\$23.85	\$14.70	\$38.00	\$19.50				
1901.....	16.00	14.50	30.50	22.70				
1902.....	23.55	16.00	35.50	30.50	\$64.20	48.60		
1903.....	23.45	14.50	33.50	26.00	52.40	42.20		
1904.....	17.70	13.50	26.00	22.50	51.80	42.20	\$ 85.00	\$58.00
1905.....	19.60	16.50	29.00	25.00	58.70	54.00	100.00	79.00
1906.....	25.85	18.50	32.50	29.00	54.00	44.00	114.00	99.00
1907.....	26.85	18.40	33.30	31.00	56.60	53.60	111.00	67.00
1908.....	18.75	17.05	31.00	28.00	71.00	45.60	91.00	68.00
1909.....	19.30	16.70	30.50	26.00	54.80	40.00	106.00	88.00
1910.....	19.30	15.80	30.50	26.00	52.00	44.00	104.00	78.00
1911.....	15.80	14.30	26.00	22.20	44.00	39.40	95.00	82.00
1912.....	18.30	14.30	30.00	22.75	49.60	36.40	102.00	89.00
1913.....	18.50	14.20	31.50	23.00	61.20	46.60	94.00	77.00
1914.....	14.75	13.00	24.00	22.16	48.60	37.26	88.00	68.00
1915.....	19.00	13.30	34.16	22.16	59.00	34.10	102.00	72.00
1916.....	30.50	18.50	63.16	35.16	94.00	63.80	109.00	92.00
1917.....	55.50	30.50	103.16	50.66	105.00	95.00	102.00	68.00
1918.....	34.50	31.50	52.00	48.00	119.00	91.00	91.00	70.00
1919.....	40.50	27.25	52.40	43.00	110.00	79.00	100.00	80.00
1920.....	46.70	33.70	69.30	49.52	122.60	92.00	111.00	58.00
1921*.....	32.70	18.95	49.52	35.02	83.60	65.00	75.00	47.00

* To August 31st



proof buildings. There are also shown the prices of forty standard stocks, based upon figures published by Lee, Higginson & Company:

Of course, figures such as these require careful analysis and exact application in order to arrive at their true significance. It is quite possible that differences in the character of the work itself might be sufficient to account for the rather extreme fluctuations entering into the steel frame figures quoted for 1918, '19 and '20; or emergency conditions may have entered into particular cases, involving the use of stock material or of other special service, such as would account for the highest of the figures given. It is pretty generally understood that the base price of structural steel which has prevailed since the beginning of the year 1919 was the result of an initial reduction from the war-time base made by the steel makers as of January 1st of that year; and of a

higher prices such as the unusual conditions made it possible for them to exact; the difference in the two scales ranging as high as \$30.00 per ton. In addition, large quantities of material have been marketed, by those not observing the established base, for employment along special lines at prices which have given them a premium ranging anywhere from \$25.00 to \$100.00 per ton.

Outside of the differences in the character of the work, and outside of the special conditions and service entering into the various structures, there has been, as is well known, a steady advance in the rates paid for labor of all classes; so that while the price of rolled structural material, due to the causes referred to above, has remained stationary, the fabricating costs have constantly increased, until a point has now been reached at which many building operations have been greatly slowed down, while others have entirely ceased.

*View before attaching
Ceiling Lath and
Gypsum Plaster*



Cuts the Dead Weight of Fireproof Floors in Half

COMPARED with other types of fireproof floor construction, those built with National Steel Lumber Joists eliminate 50 per cent of the dead weight. This means half the amount of floor material to buy, ship, handle and erect.

National Steel Lumber joist sections are fabricated and marketed with complete engineering service by structural steel companies. With this material is built the modern fire-proof floor that does away with excessive weights, wood forming and other expensive items usually associated with high-grade permanent construction.

Telephone or write for a copy of the 1921 handbook giving complete details, tables, etc.



National Steel Lumber Fire-Safe First Floors for Homes Prevent the Spread of Basement Fires. Write us.

The NATIONAL PRESSED STEEL CO.

General Office and Mills: Massillon, Ohio

The remedy for such conditions is not easy to find, and when once found will involve many difficulties of application. To my mind one thing is entirely certain: The principle, the spirit of the Open Shop, must be universally adopted. I am not in the least thinking, on the one hand, of the Open Shop, as such, as being a thing apart, and necessarily antagonistic to the Labor Union, as such, on the other hand. I am thinking only of the principle itself, which does, as a matter of fact, accord with the practice of the Open Shop, which permits a man to work when and where he pleases, on terms mutually agreed upon, and whether he does or does not belong to a Labor Union. So fair, so right, so patriotic is this principle that on many hands it is now being termed "**The American Plan.**" This plan contemplates no combat with Labor Unions as such, but it insists that such organizations, in common with all other organizations, should be subject to the control and regulation of the Government, and that no illegal interference of any kind on the part of the Labor Unions be permitted, either with the business of the employers or with the men who desire and who elect to work for them.

I am not unmindful of the fact that this article is to be published in a Handbook whose life runs for an entire year, and that suggestions of today as touching the general situation may become entirely obsolete within a few weeks even. Nevertheless, we cannot too strongly keep before us the lines along which our tremendous industrial problems must be solved.

Advances in the sciences and in the arts; in design and in methods of construction; the effecting of improvements and economies in shop practice and in field operations, all seem to have a way of taking care of themselves. These subjects are never permitted to lie dormant. Some ingenious mind is always carrying them a step forward. These advancements, readily recognized, are quickly adopted, and Progress continues to keep step with Time.

But to these other great questions of policy in trade and in commerce; of regulation and control; of the relationship between capital and labor, there is no such easy answer. I suppose it to be a fact that each day there is wasted millions of money, resulting from disagreements and from the lack of sound policy and practice in our national; in our state; in our municipal and in our industrial life. The offset to such losses that can be secured through improved manufacturing processes is infinitesimally small.

It is because of this that I am availing myself of the latitude which the letter of invitation permits to suggest that when, by some stupendous miracle, the virtue of sane, of practical and of proper unselfishness shall have been thrust upon us, and upon every

one of us, then, and then only perhaps, will there be possibility of adjustments that are orderly, effective and permanent. In the meantime, those who by their knowledge and experience are best entitled to an opinion seem generally to agree:

That although the times are critical they are not out of hand, not beyond control, and that all claim of panic is merely idle talk; because panic only comes when the end of credit resource is reached—a point with us certainly not within measurable distance:

That the vital necessity is a steady increase in **Production**:

That expansion and expense have proceeded at so high a speed as to necessitate the utmost care to avoid the wreck which would surely result from a too sudden application of the brakes:

That production, labor, credit and transportation—the factors upon which alone our economic equilibrium depends—must be co-ordinated and required to co-operate, instead of being exploited and set by the ears by self-seeking politicians or professional fomenters of disputes:

That labor, whether physical or professional, must once more come to take an honest pride in its work, with the determination that the service performed shall not fall short in value of the wage received:

That misunderstandings between employer and workman can and must be seriously approached and broadly and generously adjusted:

That viciousness manifested either by the one or the other must be promptly repudiated through the overwhelming weight of public disapproval:

That personal expense and scale of living must be regulated in accordance with sound and normal judgment, instead of being expanded to the full limits of a pay envelope the proportions of which are as unexampled as they are fleeting.

With all this will come the necessary fall in commodity and goods prices; the liquidation of speculative holdings of commodities and goods; the adjustment of wages to a basis which will admit of reasonable profit in the production and sale of commodities and goods at normal prices; the curtailment of bank loans and the replenishment of bank reserves; the reduction of interest rates to a level which will enable the typical borrower to make a reasonable net profit through the use of borrowed funds; and a general quickening of the mental attitude which will permit both prices and wages to respond to the law of supply and demand, instead of reflecting, as is now and as for some time past has been the case, conditions which are so thoroughly abnormal and extravagant as to be highly dangerous.



Chicago Factory and Warehouse

BARTON SPIDER-WEB SYSTEM

3426 S. Kedzie Ave. Chicago, Ill.

Telephone: LaFayette 3894

Eng. Service for Any
Type of Structures


Reinforcing Steel
Spirals Inserts

SERVICE AND ACCURACY OUR MOTTO

Architects Licensed to Use the Combination 2-way and 4-way System of
Flat Slab Construction

American Steel & Wire Company

208 S. La Salle Street
CHICAGO



TRIANGLE-MESH CONCRETE REINFORCEMENT

For Highways, Buildings, Levees, Canal Locks,
Chimneys, Sewer-pipe, Retaining Walls, Floor
Slabs, Wall Slabs.

AMERICAN WIRE ROPE


For Elevators, Dredges, Lumbering, Oil-well Drilling,
Stump Pulling, Cranes, Derricks, Ships' Rigging and
every other form of wire rope use.

COMPLETE CATALOGUES FURNISHED



STEEL LUMBER CONSTRUCTION

by STANLEY MACOMBER, Assoc. M. Am. Soc. C. E.



Steel Lumber is the name applied to light weight structural sections used as joists and studs in floor and partition construction. To complete the floors steel lath is applied on the top and bottom of the joists. A thin concrete slab is spread over the floor lath and the ceiling lath is plastered. Figure 1.

Steel Lumber joists are used for the purpose of carrying the lighter loads in a building until the accumulated load is large enough to be more economically carried by structural steel sections.

The production of steel joists involves the rolling of a strip from 100' to 125' long. This strip is then rolled cold into a channel section. Two channel sections are placed back to back and securely spot-welded together. The result is a section giving the greatest depth for weight of material consistent with lateral stiffness and web crippling requirements.

The first known use of a steel joist floor construction was by James Renwick an architect in the Bank of State of New York building, New York City. This building was built in 1855, and the steel joists sections were designed as shown in figure 2, detail of floor construction being very similar to present day practice. This building was demolished in 1906, at which time all the sections were in absolutely perfect condition.

In 1901, Mr. Timothy O'Shea, of Chicago, designed and patented a steel joist as shown in figure 3. The O'Shea floor design was quite unlike the present day construction but involved a similar principle. The joists were formed of two light gage angles bolted

back to back with a one inch angle bolted along web for stiffening. The usual spacing of joists was 16 inches on center. Corrugated sheets were fastened on top of joists by means of nails driven into web, furring strips were placed top of joists with a concrete fill between strips and wooden finish floor nailed to strips. A metal ceiling to carry the plaster was hung from the floor joists. This construction was used between 1900 and 1905 in various buildings, in Chicago, the principal ones of which are Firminich Bldg., 184 W. Washington; Royal Insurance Bldg., 160 W. Jackson Blvd., (now wrecked) Lehmann Flats.

In later years different types of floors involving the use of structural shapes were tried out but did not develop the desired practicability. In 1915 the Berger Mfg. Company of Canton, Ohio, started manufacturing a joist, figure 4, which was made up on brakes. A few years later the Truscon Steel Company of Youngstown, Ohio, started marketing a symmetrical section, figure 5, and in a very short time were rolling this section instead of using brakes.

Steel lath was fastened to the top of the joists by nailing through the lath and between the two channel sections, using a big headed roofing nail. The ceiling lath was secured by means of prongs which were punched from the bottom flange of the joists. The prongs were a nuisance in shipping and made the application of ceiling lath more difficult. This method of ceiling lath attachment was common practice until 1919.

Prior to 1915 all Steel Lumber sections were made from sheet steel. The two chan-



Fig. 3.



Fig. 4



Fig. 5.

THE SUPER



Reinforcement

EXPANDED METAL

Flat Sheets — Lengths up to 16'

Your files are not complete without our new
"STEELCRETE HAND-BOOK"

The Consolidated Expanded Metal Co's

OF ILLINOIS


Office and Warehouse: 560-62 W. Monroe Street, CHICAGO

PHONE FRANKLIN 125
PHILADELPHIA

NEW YORK

PITTSBURG

"UNIVERSAL" Spacers and Supports



For Reinforcing Steel in
Concrete Slabs, Beams, Girders, Joists

UNIVERSAL FORM CLAMP CO.

Telephone Monroe 3138

14 NORTH MAY ST.

CHICAGO, U. S. A.


SCULLY WROUGHT STEEL FLOOR PLATES

DIAMOND AND RIBBED PATTERN

Made of Open Hearth Steel of high tensile strength.

Diamonds raised giving rugged and firm foothold.

In stock for immediate shipment.



For Floor, Stairs, Platforms, Thresholds, Fire Escapes, Approaches, Sidewalk doors, Gutter covers, Trench covers, etc.


Write for catalog, also our Stock List and Reference Book.

WE ALSO CARRY A COMPLETE STOCK OF STRUCTURAL STEEL, REINFORCING BARS AND STEEL FOR BUILDING PURPOSES

SCULLY STEEL & IRON CO., CHICAGO, ILL.

Phone Canal 2500

P. O. Box 814



Trade Mark



Approved by Underwriters Laboratories, Inc.

Castle Die Pressed Steel Stair Treads. Sub-Treads for Concrete Filling. Castle "Star" Steel Post-Caps and Caps made to Your Order.

Post-bases—Wall-boxes—Wall plates, Hangers, Stirrups, Anchors, etc. Also Pressed Steel Stringers.

BUILDING SPECIALTIES DEPT.

A. M. CASTLE & Co.

715 NORTH MORGAN ST.

CHICAGO, ILLINOIS




Fig. 6

also reduces the cost of applying lath. The steel joist today as compared with that of a few years ago has the proper proportion of thickness of material to the depth of the section; has the channel section spotwelded together instead of riveted, and has no splices. The material is now on a definite commodity basis.

The principle of steel joist construction has been demonstrated as correct and practical. The distribution of the section through the structural steel industry assures its rapidly becoming a common type of construction, and any further development in production methods tending to reduce costs and increase efficiency will further increase the already wide field for the use of this light weight fire-safe steel construction.

Steel construction, i. e., structural steel skeleton frames supporting steel joist floors, offers several very desirable features in building operations. The construction is rapid in erection, is clean and positive. Every operation is that much definitely accomplished. As compared with other equally good fire-safe designs it will save from 25 to 30% in time of erection of a building. From a structural viewpoint the strength of the building is established with certainty. The proper inspection of the material requires comparatively little time. After the completion of the structure those qualities which are more important to the owner, such as sound-proofness, low depreciation,* durability and fire-safety, are emphasized as years go by.

The soundproof qualities of any structure are more or less relative and difficult to determine in advance. The design of the building has such an effect upon the soundproof qualities that the material used is not a deciding factor. Buildings incorporating the use of any modern type of fire-safe design may be found which give apparently good results in soundproofness, while others similarly constructed are quite the opposite. The

determination then of the soundproof qualities of steel construction is a matter of comparison of actual installations. This comparison shows a very satisfactory condition existing. Some structures where poor workmanship has permitted continuous air spaces in hollow tile walls connecting with the space between joists give a slight transmission of sound through partitions. These exceptional installations which may be classed as not entirely satisfactory probably occur in a smaller percentage of cases than in any other type of construction, at least not any oftener. Steel joists with the ends butting against I-beams or buried in solid brick walls provide soundproof floors. The high degree of their efficiency is because of the several different materials through which the sound vibration has to travel and the wide variation in the density of these materials. In any floor construction where the sound has only one continuous material to traverse the opportunity for molecular vibration is much greater. Therefore the floor construction although it is light in weight does give practically soundproof results as demonstrated in hundreds of buildings, such as hospitals, where this particular feature is of great importance.

Due to the fact that there is no shrinkage in the materials used, and that the ceiling and floors are reinforced with a steel mesh, there are practically no cracks in the ceiling or floors of steel lumber constructed buildings. This remarkably low rate of depreciation becomes apparent after ten or fifteen years service—the condition of the structure being practically the same after years of occupancy as it is when first finished.

The durability of the construction is sometimes questioned on account of the possibility of corrosion. Theoretical analysis of the factors applying and the actual demonstration of installations prove conclusively that the only opportunity for corrosion on steel joists in a building is limited to those places where moisture is directly applied, as

UNION FOUNDRY WORKS

General Office
1427 First National
Bank Building

Works
76th St. and
Greenwood Ave.

Structural and Ornamental **IRON WORK**

A Large Stock of Structural
Steel Shapes on Hand

Office Phone, Randolph 3663
Works Phone, Hyde Park 277

JNO. J. DUFFIN,
PRES & TREAS
JAS. J. DUFFIN,
VICE-PRES
M. E. DUFFIN & CO. L.L.C.
SECRY

Duffin Iron Company
STRUCTURAL STEEL & ORNAMENTAL IRON

4837-55 S. KEDZIE AVE.

PHONE LAFAYETTE 732-733

Chicago, Ill.

Sales Office

Room 619, Fisher Building

Telephone Harrison 8609

343 S. Dearborn Street

from a leaky water pipe, soil pipe or steam pipe. In such cases the presence of this moisture is always evidenced by stained ceiling plaster long before any corrosion takes place on the joists. It is doubtful whether such a condition could ever continue to exist to a point where the joists would be corroded to failure, as the ceiling lath would probably fall long before that condition could exist. Such local application of moisture will corrode steel whether it be an I-beam, steel joist or reinforcing bar. Of all the structural parts of a building the least importance could be attached to the corrosion of the joists, as in no instance could a failure of the slab be anticipated. The worst development being a comparatively small expense to replace those sections corroded. Such would not be the case however in columns or main bearing beams. The development of this condition from the local application of moisture is a very infrequent happening. The possibility of such condition being allowed to continue a sufficient length of time, which would mean several years, is very remote. It would seem that there is nothing much to fear in this regard.

As to the probability of corrosion due to atmospheric moisture there is no opportunity for this to occur. To secure this corrosion the atmospheric moisture must be condensed upon the steel, and in order to secure this condensation there must be a difference in temperature between the steel and the atmosphere. Examination of the floor construction, whether it be placed in roof, floor or partition, indicates the impossibility of securing a difference in temperature between the joists and the air space between the joists. Consequently the impossibility of condensation of atmospheric moisture on a section. As long as the joists are in a building their appearance remains the same as when they were installed.

In steel joist floor construction the use of combustible materials is eliminated. The concrete slab above the joists provides a fire block to prevent the passage of fire between the joists. The ceiling plaster on metal lath provides protection to the joists, and the efficiency of the whole construction depends upon the ability of the joists to stand in place under the conditions to which they will be subjected. It is common knowledge that temperatures have a decided effect upon the strength of steel. It is interesting to note just what this effect is. Reference to the temperature strength curve, Figure 6, shows that low carbon steels develop their maximum strength at a temperature approximately 600 to 700 degrees F. The structural steel section is subject to twisting and distorting at comparatively low temperatures, i. e., around 700-800 degrees F., and for this reason such sections must be protected with a type of fireproofing which will hold the temperature of the section at not much over 500 degrees. The common practice calls for the equivalent of 2" of reinforced concrete

to give this protection. If steel joists acted in the same manner then they would require the same protection. However, such is not the case.

A cast iron column does not twist and distort under high temperatures, although the material used is the same as that used in an I-beam excepting for the refinement resulting from extra heating and working. A cast iron section is produced by pouring molten metal into a mould. The metal cools off without being further worked. This gradual cooling off of the metal is more or less of an annealing process, and there are no internal stresses developed in the section excepting inconsequential ones due to possible uneven cooling. In the production of the I beam, although the shape itself will be produced at a high temperature, the forming of the section introduces stresses, particularly around the fillet, which causes the shape to be crooked as it comes from the final pass. This shape is then run through straightening rolls, which operation is ordinarily done after the temperature has been reduced below the lower recolescence point. The straightening process is merely the bending of the section into true alignment but the operation develops internal stresses. Later as temperatures are applied to the section these internal stresses are released by the twisting or distortion of the beam. Direct connection with the straightening temperature and the shape of the section before straightening is indicated by the fact that this twisting and distortion occurs at approximately that point and the sections take approximately their original shape before being straightened. The fact that all structural shapes, although of the same material produced in the same manner, do not twist and distort at the same temperatures or to the same degree, further indicates that this particular quality is dependent on the production process, which would naturally not be uniform in practice. The production of the steel joist because of the long length of strip required and the very rapid radiation of heat, necessitates great rapidity in operation. The process of production must be completed before the steel has reached the lower recolescence point. Any working of the material at these high speeds when the temperature has decreased below 1300 degrees results in extremely high rate of depreciation on equipment, and a very high percentage of rejected material. The strip is a rectangular section rolled evenly throughout its width and finished above the lower recolescence point. There are no internal stresses introduced. The result is that a steel joist will not twist and distort under high temperatures—regardless of how high the temperature or prolonged the application. The heat may soften the steel so that the joist may deflect but there will be no twisting and distortion.

The result is that the steel joists do not have to be protected against temperatures

O. H. HILL COMPANY

FIRE DOORS *and* SHUTTERS

Underwriters' Labeled MEAKER Elevator Doors
SIDEWALK DOORS

2253-2259 ST. PAUL AVENUE
PHONE HUMBOLDT 5412 CHICAGO



*Drake
Hotel
Chicago*

*Marshall
and Fox
Architects*

Telephone
West
1018

STANDARD FIRE ESCAPE CO.

MANUFACTURERS OF
STANDARDIZED FIRE ESCAPES

23-25 South Western Ave.

CHICAGO, ILL.

around 700 to 800 degrees, but should be protected against temperatures exceeding 1,200 degrees in order to maintain sufficient strength to carry the loads super-imposed on the floor. Fire tests of the standard floor construction have developed the fact that very rarely does the temperature between the joists exceed 550 degrees during the application of 1,700 degrees F. for four hours underneath the slab. A $\frac{3}{8}$ " thickness of cement plaster has proven amply sufficient. Other types of plaster will give equally as good results and are more economical in construction, but cement plaster is used as a basis of comparison. A steel joist floor develops its greatest strength at temperatures around 600 to 700 degrees. The efficiency of steel construction when the columns and beams are protected with 2" of cement plaster on steel lath, leaving an air space around the sections, and where steel joists are protected with $\frac{3}{8}$ " of cement plastered ceiling, has been proven by fire tests applied to this type of construction.

The economy of steel construction is not dependent upon the low cost of materials involved. It results from the efficient use of each material in such a manner as to secure the benefit of its greatest merits. Concrete has no particular structural strength excepting in compression. It is, however, an efficient fire retardant. The 2" concrete slab above the joist utilizes this principal merit of concrete to its full advantage. The compressive strength of the material is taken advantage of in carrying loads from joist to joist, and for that purpose the concrete is reinforced with expanded steel mesh which mesh also acts as a form for supporting the concrete when first applied. The shape of the steel joist is such as to develop the greatest strength from a minimum of weight. The method of production permits of the utilization of the full strength of the section available at all temperatures. The ceiling plaster reinforced and mechanically bonded with steel lath provides a valuable protection to the joists and serves architecturally as the finished ceiling. The weight of the completed floor will not exceed 35 to

40 pounds to the square foot. This low dead weight reflects in reduced load on supporting beams, reduces the load applying on columns and footings, and for that reason materially affects the cost of the skeleton frame.

This reduction in dead weight on an average office building, 120' long x 80' wide and 8 stories high, will amount to a total difference of 2500 tons or more in comparison with other equally efficient fire-safe types of construction. Two thousand five hundred tons of material which does not require transportation, cartage, hoisting and handling. The economy of the construction is a direct result of the more efficient application of the materials involved. The efficiency of the construction is due to the recognition of the merit of the various materials and the strengthening of their weaknesses.

The limits of the use of steel construction are economic. Because of the light weight of the floor and its resulting lack of inertia, it is not a proper design to use for heavy vibratory loads. For heavy warehouse construction involving live loads of 250 pounds per square foot and up, it is apparent that a floor weighing not over 40 pounds per square foot will not meet this condition economically, except in rare instances. It is not a question of strength, as that is only a matter of design, but for such loads on comparatively long spans the spacing of the joists would be so close that the cost of the construction would exceed the cost of other equally good designs. The particular field for all steel construction (structural steel skeleton frames supporting steel joist floors) are those types of buildings involving floor spans not exceeding 25',—the maximum economy being developed in spans under 20' and live loads under 125 pounds.

With in this range are included office Bldgs., Hotels, Stores, Apartments, Schools, Dormitories, Hospitals, Residences, Theaters, and the like.

The efficiency of steel construction has been proven by the test of time. Its economy in this particular field is a matter of comparison.



Established 1863

Incorporated 1914

HOLMES, PYOTT & CO.

STRUCTURAL STEEL AND
ARCHITECTURAL IRON WORK
IRON FOUNDERS

Private Exchange, All Departments, Franklin 1385-1386-1387

Office and Works: 159 No. Jefferson St.

Yards, Campbell Ave.
and Pan Handle R. R.

CHICAGO

PAUL WILLIS, PRES. & TREAS.

A. J. T. BENNETT, SECY. & ENGR.

KENWOOD BRIDGE CO.

ENGINEERS AND BUILDERS OF
STRUCTURAL STEEL WORK

Office: 1413-15-16 First National Bank Bldg., Chicago. Works: Grand Crossing, Ill.

TELEPHONE RANDOLPH 1488

ROOFS, BRIDGES, COLUMNS AND GIRDERS, STEEL MILL BUILDINGS A
SPECIALTY. WATER TOWERS. DESIGNS AND ESTIMATES FURNISHED

MORAVA CONSTRUCTION CO.

MANUFACTURERS OF

Structural Steel

General Office:

BRIDGE AND STRUCTURAL STEEL WORKS

8301 to 8457 Stewart Avenue

Telephone Stewart 870

City Office:

Suite 419 Peoples Gas Building

122 Michigan Boulevard

Chicago, Ill.

Telephone Harrison 21

Established 1856

Incorporated 1898

A. BOLTER'S SONS

MANUFACTURERS AND BUILDERS OF

STEEL AND IRON STRUCTURES

Iron Founders

Ornamental Iron Work

Main Office and Works: Ward St., Belden Ave., Fullerton Ave. and C. M. & St. P. Ry.

Telephone Lincoln 155

Contracting Office: 53 West Jackson Blvd.

Telephone: Wabash 125

CHICAGO

STANDARD SPECIFICATIONS FOR BILLET-STEEL CONCRETE REINFORCEMENT BARS

Serial Designation: A 15—14.

The specifications for this material are issued under the fixed designation A 15; the final number indicates the year of original issue, or in the case of revision, the year of last revision.

Adopted, 1911; Revised, 1912, 1913, 1914.

(1) (a) These specifications cover three classes of billet-steel concrete reinforcement bars, namely: plain, deformed, and cold-twisted.

(b) Plain and deformed bars are of three grades, namely: structural-steel, intermediate and hard.

2. (a) The structural-steel grade shall be used unless otherwise specified.

(b) If desired, cold-twisted bars may be purchased on the basis of tests of the hot-rolled bars before twisting, in which case such tests shall govern and shall conform to the requirements specified for plain bars of structural-steel grade.

I. Manufacture.

3. (a) The steel may be made by the Bessemer or the open-hearth process.

(b) The bars shall be rolled from new billets. No rerolled material will be accepted.

4. Cold-twisted bars shall be twisted cold with one complete twist in a length not over 12 times the thickness of the bar.

II. Chemical Properties and Tests.

5. The steel shall conform to the following requirements as to chemical composition:

Phosphorus
Bessemer.....not over 0.10 per cent
Open-hearth.... " " 0.05 "

6. An analysis to determine the percentages of carbon, manganese, phosphorus and sulfur, shall be made by the manufacturer from a test ingot taken during the pouring of each melt, a copy of which shall be given to the purchaser or his representative. This analysis shall conform to the requirements specified in Section 5.

7. Analysis may be made by the purchaser from finished bars representing each melt of open-hearth steel, and each melt, or lot of ten tons, of Bessemer steel, in which case an excess of 25 per cent above the requirements specified in Section 5 shall be allowed.

III. Physical Properties and Tests.

8. (a) The bars shall conform to the following requirements as to tensile properties:

Tensile Properties.

Properties Considered.	Plain Bars.			Deformed Bars.			
	Structural Steel Grade.	Intermediate Grade.	Hard Grade.	Structural Steel Grade.	Intermediate Grade.	Hard Grade.	Cold-twisted Bars.
Tensile strength, lb. per sq. in....	55,000 to 70,000	70,000 to 85,000	80,000 min.	55,000 to 70,000	70,000 to 85,000	80,000 min.	Recorded only.
Yield point, min., lb. per sq. in....	33,000	40,000	50,000	33,000	40,000	50,000	55,000
Elongation in 8 in. min., per cent....	1,400,000*	1,300,000*	1,200,000*	1,250,000*	1,125,000*	1,000,000*	5
	Tens. str.	Tens. str.	Tens. str.	Tens. str.	Tens. str.	Tens. str.	

(b) The yield point shall be determined by the drop of the beam of the testing machine.

9. (a) For plain and deformed bars over $\frac{1}{4}$ in. in thickness or diameter, a deduction of 1 from the percentages of elongation specified in Section 8 (a) shall be made for each increase of $\frac{1}{8}$ in. in thickness or diameter above $\frac{1}{4}$ in.

(b) For plain and deformed bars under $\frac{7}{16}$ in. in thickness or diameter, a deduction of 1 from the percentages of elongation specified in Section 8 (a) shall be made for each decrease of $\frac{1}{16}$ in. in thickness or diameter below $\frac{7}{16}$ in.

10. The test specimen shall bend cold around a pin without cracking on the outside of the bent portion, as follows:

Bend-Test Requirements.

Thickness or Diameter of Bar.	Plain Bars.			Deformed Bars.			Cold-twisted Bars.
	Structural Steel Grade.	Intermediate Grade.	Hard Grade.	Structural Steel Grade.	Intermediate Grade.	Hard Grade.	
Under $\frac{3}{4}$ in....	180 deg. d=t	180 deg. d=2t	180 deg. d=3t	180 deg. d=t	180 deg. d=3t	180 deg. d=4t	180 deg. d=2t
$\frac{3}{4}$ in. or over...	180 deg. d=t	90 deg. d=2t	90 deg. d=3t	90 deg. d=2t	90 deg. d=3t	90 deg. d=4t	180 deg. d=3t

Explanatory Note: d=the diameter of pin about which the specimen is bent;
t=the thickness or diameter of the specimen.

11. (a) Tension and bend test specimens for plain and deformed bars shall be taken from the finished bars, and shall be of the full thickness or diameter of bars as rolled; except that the specimens for deformed bars may be machined for a length of at least 9 in., if deemed necessary by the manufacturer to obtain uniform cross-section.

(b) Tension and bend test specimens for cold-twisted bars shall be taken from the

finished bars, without further treatment; except as specified in Section 2 (b).

12. (a) One tension and one bend test shall be made from each melt of open-hearth steel, and from each melt, or lot of ten tons, of Bessemer steel; except that if material from one melt differs $\frac{1}{8}$ in. or more in thickness or diameter, one tension and one bend test shall be made from both the thickest and the thinnest material rolled.

*See Section 9.



STEEL BARS FOR Reinforcing Concrete

PLAIN AND
DEFORMED
ROUNDS AND
SQUARES

Shipments
from Stock
and Mill
Rolling

OUR
SERVICE

ESTIMATING

SETTING AND
BENDING DETAILS

BENDING

CALUMET STEEL COMPANY

CONTINENTAL AND COMMERCIAL BANK BUILDING

CHICAGO

(b) If any test specimen shows defective machining or develops flaws, it may be discarded and another specimen substituted.

(c) If the percentage of elongation of any tension test specimen is less than that specified in Section 8 (a) and any part of the fracture is outside the middle third of the gage length, as indicated by scribe scratches marked on the specimen before testing, a retest shall be allowed.

IV. Permissible Variations in Weight.

13. The weight of any lot of bars shall not vary more than 5 per cent from the theoretical weight of that lot.

V. Finish.

14. The finished bars shall be free from injurious defects and shall have a workman-like finish.

VI. Inspection and Rejection.

15. The inspector representing the purchaser shall have free entry, at all times while work on the contract of the purchaser is being performed, to all parts of the manufacturer's works which concern the manu-

facture of the bars ordered. The manufacturer shall afford the inspector, free of cost, all reasonable facilities to satisfy him that the bars are being furnished in accordance with these specifications. All tests (except check analyses) and inspection shall be made at the place of manufacture prior to shipment, unless otherwise specified, and shall be so conducted as not to interfere unnecessarily with the operation of the works.

16. (a) Unless otherwise specified, any rejection based on tests made in accordance with Section 7 shall be reported within five working days from the receipt of samples.

(b) Bars which show injurious defects subsequent to their acceptance at the manufacturer's works will be rejected, and the manufacturer shall be notified.

17. Samples tested in accordance with Section 7, which represent rejected bars, shall be preserved for two weeks from the date of the test report. In case of dissatisfaction with the results of the tests, the manufacturer may make claim for a rehearing within that time.

STANDARD SPECIFICATIONS FOR RAIL STEEL CONCRETE REINFORCEMENT BARS

As Adopted by American Society for Testing Materials. Philadelphia, Pa., U. S. A., 1913.

Classes.

1. These specifications cover three classes of rail-steel concrete reinforcement bars, namely: plain, deformed, and hot-twisted.

I. MANUFACTURE. Process.

2. The bars shall be rolled from standard section Tee rails.

Hot-twisted Bars.

3. Hot-twisted bars shall have one complete twist in a length not over 12 times the thickness of the bar.

II. PHYSICAL PROPERTIES AND TESTS.

4. (a) The bars shall conform to the following minimum requirements as to tensile properties:

Properties Considered.	Plain Bars.	Deformed and Hot-twisted bars.
Tensile strength, lb. per sq. in....	80,000	80,000
Yield point, lb. per sq. in.....	50,000	50,000
Elongation in 8 in., per cent*.....	1,200,000 Tens. str.	1,000,000 Tens. str.

* See Section 5.

(b) The yield point shall be determined by the drop of the beam of the testing machine.

Modification in Elongation.

5. (a) For bars over ¾ in. in thickness or diameter, a deduction of 1 from the percentages of elongation specified in Section 4 (a) shall be made for each increase of ¼ in. in thickness or diameter above ¾ in.

(b) for bars under 7-16 in. in thickness or diameter, a deduction of 1 from the percentages of elongation specified in Section 4 (a) shall be made for each decrease of 1-16 in. in thickness or diameter below 7-16 in.

Bend Tests.

6. The test specimen shall bend cold around a pin without cracking on the outside of the bent portion, as follows:

Bend Test Requirements.

Thickness or Diameter of Bar.	Plain Bars.	Deformed and Hot-twisted bars.
Under ¾ in.....	180 deg. d = 3 t	180 deg. d = 4 t
¾ in. or over.....	90 deg. d = 3 t	90 deg. d = 4 t

Explanatory Note: d = the diameter of pin about which the specimen is bent; t = the thickness or diameter of the specimen.

Test Specimens.

7. (a) Tension and bend test specimens for plain and deformed bars shall be taken from the finished bars, and shall be of the full thickness or diameter of bars as rolled, except that the specimens for deformed bars may be machined for a length of at least 9 in., if deemed necessary by the manufacturer to obtain uniform cross-section.

(b) Tension and bend test specimens for hot-twisted bars shall be taken from the finished bars, without further treatment.

Number of Tests.

8. (a) One tension and one bend test shall be made from each lot of ten tons or less of each size of bar rolled from rails varying not more than 10 lb. per yd. in nominal weight.

(b) If any test specimen shows defective machining or develops flaws, or if a tension test specimen breaks outside the middle third of the gage length, it may be discarded and another specimen substituted.

III. PERMISSIBLE VARIATIONS IN WEIGHT.

Permissible Variations.

9. The weight of any lot of bars shall not vary more than 5 per cent from the theoretical weight of that lot.



Architectural Iron Work

JOSEPH HALSTED CO.

RANDOLPH AND ELIZABETH STS.

CHICAGO

TELEPHONE MONROE 4410

ORNAMENTAL IRON WORK

IRON STAIRS

ELEVATOR DOORS AND ENCLOSURES

IRON STORE FRONTS

IRON FENCES AND GRILLES

STEEL BEAMS AND COLUMNS

FIRE ESCAPES

CAST IRON FENCE AND RAILING POSTS
FOR BUILDINGS A SPECIALTY

Reder Foundry Co.

Iron Foundry

ARCHITECTURAL MACHINERY AND
STOVE PLATE CASTINGS

Telephone LaFayette 3706

Oakley Ave. & 35th Place

One Block East of Western Blvd.



Ornamental and Miscellaneous IRON

Incorporated 1910

CAPITAL \$500,000.00

HANKE IRON & WIRE WORKS

ALBANY, GRAND and CHICAGO AVES.

Telephone Garfield 970

Representative Work:

"Burlington Bldg."
"Pennsylvania Station"
"Continental & Commercial
National Bank Bldg."
"Carter H. Harrison High
School"
"Borland Bldg."
"Chicago Telephone Com-
pany Bldg."
"Mallers Bldg."

References:

Schmidt, Garden & Martin
Graham, Anderson, Probst
& White
Holabird & Roche
University of Chicago
Geo. A. Fuller Company
Marshall & Fox
Bulley & Andrews
Western Electric Company

OFFICE: MAIN 2722

WORKS: B. ULEVARD 2120

FEDERAL-IRON-WORKS

STRUCTURAL AND ARCHITECTURAL IRON
807 STOCK EXCHANGE. 30 N. LA SALLE
WORKS: 3545-55 SHIELDS AVE., CHICAGO

RULES OF MEASUREMENT FOR EXAVACATION AND CONCRETE WORK

The following rules have been carefully studied and analyzed by a joint committee consisting of five (5) members of the Chicago Architects Business Association, five (5) members of the Western Society of Engineers, and five (5) members of the Contractors' and Masons' Association of Chicago.

If any new rules or new applications of old rules should be found in the following, we can only say for their recommendation that we have carefully considered them in all their bearings, endeavoring to secure equal justice to owner as well as contractor, and that they will form the standard for deductions as well as for compensation for extra work.

EXCAVATION OF CELLARS AND BASEMENTS.

1. Excavation to be measured and computed by the actual amount of material displaced. If unit price is based upon loose measurement add forty (40%) per cent to actual bank measurement, except if consisting of sand and gravel, when only twenty (20%) per cent will be added. If rehandling becomes necessary, same to be done at a special price agreed upon in addition to the above.

EXCAVATION OF TRENCHES AND PITS.

2. Excavation of trenches, pier holes, or pits when more than 3' wide to be computed on actual contents when less than five (5') ft. deep.

When less than three feet wide excavation of trenches, pier holes, or pits to be computed on actual contents if less than two (2') feet deep.

If more than two feet (2') deep compute contents of trench on base of three foot (3') width, even though same is narrower.

If less than two (2') feet in depth estimate actual width.

For pits or pier holes more than two (2') feet deep and less than twelve (12) square feet in area estimate area of same on base of twelve (12) square feet multiplied by depth of same down to five (5') foot, and if more than five (5') feet deep estimate on same basis as given below for additional depth of trenches, with the same percentages of increases added.

Add 75% to actual contents of excavation of trenches, pier holes, or pits for depth between five (5') ft. to ten (10') ft.

Add 150% to actual contents of excavation of trenches, pier-holes, or pits, for depth between ten (10') ft. and fifteen (15') feet.

Add 225% to actual contents of excavation of trenches, pier holes, or pits for depth between fifteen (15') feet and twenty (20') feet.

Add 300% to actual contents of excavation of trenches, pier holes, or pits for depth between twenty (20') feet and twenty-five (25') feet.

Add 375% to actual contents of excavation of trenches, pier holes, or pits between twenty-five (25') feet and thirty (30') feet in depth.

Add 450% to actual contents of excavation of trenches, pier holes, or pits between thirty (30') feet and thirty-five (35') feet in depth, and so on, adding 75% accumulative for every five (5') feet additional depth.

BACK FILLING AND GRADING.

3. Soil required for back filling or grading to be measured by computing from cross-sectioning cubic contents of area to be filled or graded.

SHEET PILING.

4. Sheet piling and lagging to be estimated per thousand feet of lumber required. Kind of lumber to be specified.

SHORING OF EARTH BANKS.

5. Shoring of earth banks to be done at unit price, per square foot of shored surface of bank.

DRAINING.

6. Pumping or bailing when required to be done at special price, in addition to excavation unit price, as the excavation rules are based on dry work; this, however, does not apply to rain or storm water.

CONCRETE FOUNDATIONS.

7. Foundations for walls to be measured actual contents when made with square and level off-sets.

Footings with sloping or beveled off-sets less than 30% from the horizontal multiply area of base by greatest height of footing. This applies to piers also, except when courses in pier foundations are less than twelve (12') feet in area, when one (1) cubic foot will be added for each corner for every foot in height of such course.

8. Foundations for all projections such as chimney breasts, pilasters, buttresses, or flues connected with walls to be measured actual contents contained therein, and one cubic foot added thereto for each corner for every foot in height.

9. Recesses and slots in foundations to be measured solid and in addition thereto allow two (2) cubic feet for every foot in height or length.

Eugene J. Sullivan, President

John E. Redmond, Secretary

SULLIVAN-KORBER COMPANY

HIGH GRADE ORNAMENTAL IRON AND BRONZE

2437-2441 WEST TWENTY-FIRST PLACE
CHICAGO

Phones: Canal 1999, Roosevelt 3026

GUARANTY IRON AND STEEL CO.

Ornamental
Iron Stairs
Elevator Enclosures
Elevator Cabs
Balcony Railings
Wire Enclosures
Hammered
Grille Work

FIRE DOORS

APPROVED ELEVATOR DOOR AND
WIRE WORK

TELEPHONES { GARFIELD 7259
KEDZIE 1579

Window Guards
Brass Railings
Steel Doors
Fire Escapes
Counterbalanced
Stairways
Stand Pipes
Stable Fixtures

2847-49-51 WEST LAKE STREET :: :: CHICAGO


Bronze Memorial Tablets,
Signs and Name Plates

MANTON & SMITH COMPANY

ORNAMENTAL AND ARCHITECTURAL IRON AND BRONZE

1709 WEST AUSTIN AVENUE
CHICAGO

Phone Haymarket 6145



The Arrow System— means perfection in the latest types of lightning protection. Specified by U. S. Government and architects and engineers of the largest cities in the United States and Canada, including Chicago and New York.

Recommended, labeled and approved by National Board of Fire Underwriters, Factory Insurance Ass'n, etc.

Write for copy of Standard specifications as approved by the National Board of Fire Underwriters.

Chimneys Banded and Repaired with Improved Scaffolding

THE ARROW - CONDUCTOR CO.
1536 West Adams St., CHICAGO

10. Arches in foundation. Multiply length of chord at spring of arch by height from chord to extrados by thickness of arch, and add to the wall measurement. Height of arching equal to thickness of wall.

CIRCULAR OR POLYGON FOUNDATIONS.

11. Circular or polygon foundations to be figured at double actual contents.

EXTERNAL, DIVISION AND INTERIOR CONCRETE WALLS.

12. For walls fourteen (14) feet or less in height, twenty-four (24) inches or more in thickness, use the actual thickness as basis in computing the volume. For walls less than twenty-four (24) inches in thickness, add one-half the difference between the actual thickness and twenty-four (24) inches in computing the volume. If walls are more than fourteen (14) feet in height between floors add to cubic contents fifteen (15) per cent for every additional four (4) feet in height, on accumulative scale, as given for trench excavation.

CIRCULAR WALLS.

13. For circular walls of radius sufficiently large to obviate the necessity of using specially prepared lumber for forms, add one-fifth (1-5) of length to girth of wall, and figure cubic contents on the same basis as prescribed for External and Division Walls, Paragraph 12.

BATTERED WALLS.

14. For battered, or sloping walls estimate contents on same basis as for external and division walls, and add one-half ($\frac{1}{2}$) of contents of wedge, or batter to same when narrower on top than twenty-four (24") inches. See Paragraphs 12 and 17.

INTERSECTION OF WALLS.

Intersection of division walls twenty-four (24) inches thick or less (bonded together in any manner not abutting) to be measured as slot or recess. When thicker add (1) one foot to length of wall for every intersection when measuring.

RETAINING WALLS.

15. In retaining walls reinforced with beams, columns, or girders figure concrete casing a minimum thickness of twelve (12") inches from outside edge of steel on side next to earth bank and six (6") inches from outside edge of steel on opposite side—i. e. compute wall one foot, six inches (1'-6") thicker than width of steel.

For all other retaining walls compute on same basis as for external or internal walls, paragraphs twelve (12) and seventeen (17.)

No deduction in cubic contents of concrete to be made for metal imbedded in same.

HOLLOW WALLS.

16. Hollow walls to be at special rates.

CORNERS.

17. For each corner of wall more or less than ninety (90) degrees add one foot, six inches (1'-6") to girth length of walls in measuring.

The term corner is used for salient angles of walls, and angle for re-entering angles.

PILASTERS, ETC.

18. All plain projections, such as chimney breasts, piers connected with walls and pilasters to be measured actual contents contained therein, and one (1) cubic foot added for each corner for every foot in height.

PIERS.

19. Independent plain square piers to be measured by the same rule, i. e. add one cubic foot for each corner for every foot in height. For plain polygon or round piers, add four (4) cubic feet for each foot in height.

RECESSES.

20. Recesses and slots to be measured solid and in addition thereto allow two (2) cubic feet for every foot in height or length.

ARCHES.

21. In Vaults: multiply length of chord at spring of arch by height from chord to extrados by thickness of arch.

In walls: find contents of arch by same rule and add same to wall measurement, as called for in paragraph ten (10).

In sewers and tunnel arches: multiply length of extrados by thickness of arch.

OPENINGS WITH FRAMES BUILT IN.

22. Deduct contents of windows, doors and other openings, measuring from jamb to jamb and from top of sill to spring of arch, and add two (2) feet of wall for each jamb for every foot in height of opening when plank frames are used; if box frames are used add four (4) feet of wall for each jamb for every foot in height.

OPENINGS WITHOUT FRAMES.

23. Deduct contents of openings, same to be measured from top of sill to spring of arch and shortest distance between concrete jambs for width, and add for each jamb two (2) feet of wall for every foot in height of opening.

Circular, oval or other special shaped openings to be figured at special price.

CHIMNEY BREASTS, FLUES AND PILASTERS.

24. All flues and hollows in chimneys or walls less than two (2) feet in area, figure solid and add two (2) cubic feet for every foot in height. All flues and hollows in chimneys or walls from two (2) feet to four (4) feet in area to be measured solid. When larger, deduct one-half ($\frac{1}{2}$) of contents of flue.

Detached portions of chimneys in buildings and plain chimney tops above roof to be measured solid, and one (1) cubic foot to be added for each corner for every foot in height.

DETACHED STACKS.

25. Detached chimney stacks to be figured at special rates.

TRIMMINGS.

26. No deductions allowed for omissions of concrete for cut-stone, terra cotta or other trimmings, bond blocks, timber, joists or lintels.

All ornamental or moulded work in cornices, gutters, belt or sill courses, etc., to be figured at special rates.

CUTTING AND PATCHING.

27. Cutting and patching of joists, girders, or other holes, slots, panels, recesses, etc., to be paid for on basis of time and material required.

TOOTHING.

28. When ordered by the Owner, Architect, Engineer, or the Superintendent in charge of the work, to rack or block in consequence of delay of delivery of iron, steel, stone, terra cotta, or other material, that concrete work may connect with such rack-

Phones: Yards 1265-1285

Butler Street Foundry & Iron Company

ESTABLISHED 1891

Structural and Architectural Steel and Iron Work
Large Stock of Structural Steel on Hand
All kinds of Boiler and General Castings

Office and Foundry, 3422-32 Normal Avenue
Steel Plant, 3423-43 Parnell Avenue

CHICAGO

Vierling Steel Works

Manufacturers of

Structural and Ornamental
Iron and Steel

Office and Works: 23rd St. & Stewart Ave.

Telephone Victory 1900

Chicago

Louis Vierling, Pres. and Treas.


C. J. Vierling, Vice-Pres.

Norman Speight, Secy.

ESTABLISHED 1884

F. P. SMITH WIRE AND IRON WORKS

Telephone
Lincoln 7000



Branch Office: 175 No. Dearborn St.
Phone Central 439

GENERAL OFFICES AND SHOPS
CLYBOURN & FULLERTON AVES., CHICAGO
ORNAMENTAL IRON and BRONZE

Art Metal Work, Iron Fences, Stairs, Stable
Fixtures, Jail Cells, Guards, Fire
Escapes, Wire Cloth

Wire Fencing, Iron and Wire Window Guards,
Grilles, Wickets, Brass Railings, Etc.

SEND FOR CATALOGUE

Sole Agents for Solar Hollow Steel Doors, Trim and Metal Partitions Sole Agents for Reliance Ball Bearing Elevator Door Hangers

REUTER BROTHERS

Structural Steel

Ornamental and Miscellaneous Iron Work

Works: 58th, Wood and Honore Sts.

Office: 5814 Wood Street Telephone: Prospect 4069

ing or blocking shall be measured as extra work, as follows: Increase girt length of such line by one-half ($\frac{1}{2}$) and multiply by thickness of wall.

CONCRETE FLOORS ON SOIL AND TILE ARCHES.

29. Floors to be measured by the superficial surface between outside walls of building. No deduction to be made for floor sleepers, conduits, pipes, drains, division or partition walls. No deduction to be made for any piers, columns, chimney breasts, pilasters or other projections of walls of ten (10') feet or less in area.

CAISSONS.

30. Owing to grillage in caissons being left at different heights in same building, unit price for caissons will be computed on excavated contents, including necessary wood-lagging and rings for same. Cubic contents of excavation of caissons to be computed from top of first set of lagging to bottom of caissons and from outside to outside of lagging. If steel or other special casing is required same to be paid for additional, at special unit price per pound.

BELLS.

31. Area of bottom of bell to be multiplied by height of bell to neck for cubic contents.

32. For Caissons 7' 0" or more in diameter estimate actual contents from outside to outside of lagging.

For Caissons from seven to six ft. six inches inclusive add 5% to actual contents.

For Caissons under six feet six inches to six feet inclusive, add 15% to actual contents.

For Caissons under six feet to five feet six inches inclusive, add 25% to actual contents.

For Caissons under five feet six inches to five feet inclusive, add 35% to actual contents.

For Caissons under five feet add fifty per cent (50%) to actual contents.

33a. If compressed air is required, same to be paid for in addition to the above.

33. If rings are ordered left in caissons, same to be paid for additional at unit price per pound.

34. Pumping and bulkheading to be paid for at additional price.

35. No deduction to be made for cubic contents of metal imbedded in concrete.

CONCRETE FILLING IN CAISSONS.

36. Concrete for filling of caissons to be computed on actual contents per cubic foot of concrete, but no deduction to be made for any metal imbedded in same.

REINFORCED CONCRETE WORK.

37. Reinforced Walls:

Compute concrete on same basis as specified in Sections 12 and 17, for external and division walls, and add to same cost of reinforcing metal put in place. If through changes or revisions cutting of reinforcing metal delivered or ordered becomes necessary, estimate the full length of such bars or metal fabric, and add to same cost of cutting and fitting required. Reinforcing metal to be computed on unit price per pound or square foot. No deductions to be made in estimating cubic contents of concrete for any metal imbedded in same, such as wire netting, expanded metal, bars, beams, columns, etc.

COLUMNS.

38. Measuring of plain uniform size columns to be covered by the foregoing paragraph 19 relating to piers.

39. Capitals, caps, brackets, panels, mouldings or other ornamental or moulded work to be figured special rate.

GIRDERS, FLOOR BEAMS OR OTHER DROP PROJECTIONS BELOW FLOOR SLAB.

40. For projections named in this paragraph add for each corner and angle to cubic contents one (1) cubic foot for each foot in length. For each chamfered or rounded corner or angle add one-half ($\frac{1}{2}$) cubic foot for each foot in length in addition to the above.

FLOOR SLABS.

41. Floor and roof slabs to be estimated on same basis as called for in paragraph 29 for floors on soil, and at a minimum thickness of six (6) inches. Less than six (6) inches in thickness will be computed as six (6) inches.

OPENINGS.

42. No deductions to be made in floor area for openings of less than twenty (20) square feet. For larger openings after deducting full area of opening, add one (1) superficial foot to floor area for each foot in length of girt of opening, and one (1) CUBIC FOOT extra for each corner or angle.

DEPRESSIONS.

43. For pits, baskets or other depressions in floor, add on superficial foot to the area of walls and floor of same for each foot in length of each corner and angle.

SETTING OF FACIAS, FRAMES, PIPES, SLEEVES, BOLTS, RODS, CLAMPS, ETC.

44. Setting of facias, frames, pipes, sleeves, bolts, rods, clamps, etc., imbedded in concrete to be paid for additional at special price.

FLOOR BASE AND COVES.

45. Floor base and coves to be estimated at special price per lineal ft. with one foot added to length of same for each corner and angle. For base or cove around round columns estimate three (3) times girt of column and for square or polygon columns add one foot for each corner to girt of same.

46. Concrete stairs to be estimated square foot area of face of treads and risers. Stair-landings and platforms between floors to be same unit price per foot as stairs.

47. Curbs and roofs or skylights to be estimated on same basis as called for in sections 40 and 41 except that quantities for same shall be doubled.

48. Sidewalks laid on soil or tile and brick arches, to be estimated as floor-slab section 29 with special unit price.

Sidewalks reinforced to be estimated same as called for in sections 40 and 41 with special unit price.

Curbs to be estimated per lineal foot at special unit price.

Driveways to be estimated square foot area at special unit price. (Signed)

H. B. Wheelock,	W. S. Shields,
Thomas H. Mullay,	B. E. Grant,
Joseph C. Lewellyn,	A. Lanquist,
L. G. Hallberg,	Addison E. Wells,
Arthur Woltersdorf,	E. F. Pierce,
Joachim G. Glaver,	Henry Ericsson,
Louis E. Ritter	J. W. Snyder.
Alexander C. Warren,	


Used but Not Consumed

THERE is an old saying that you cannot eat your cake and have it too. Practically all commodities are consumed in use. Food is consumed. Clothing is consumed. But there is a product used but not consumed. Cement is used in making concrete, and concrete is permanent. It cannot rust, rot, decay or burn. It endures.

Concrete highways connect city and country. Concrete forms the base of well-paved streets and alleys. Concrete sidewalks make walking easy. Railroads are large users of concrete. Modern buildings are of reinforced concrete. Almost every thing from chicken coops to skyscrapers rests on a concrete foundation.

Practically all the Universal cement that has been shipped still serves a useful purpose. It has not been consumed but has been transformed into valuable improvements that form additions to the permanent, taxable wealth of the country as well as tools for production of additional wealth.

Universal cement is used but not consumed.



Shipments of UNIVERSAL cement have grown from a few thousand sacks to more than 45 million sacks a year

Universal Portland Cement Co.

Chicago • Pittsburgh • Minneapolis • Duluth • Cleveland • New York

Concrete for Permanence

REVISED SPECIFICATIONS FOR PLAIN CONCRETE FLOORS

WM M. KINNEY, M. E.

That preference for concrete as a building material is on the increase is evident even to the casual observer as well as to architect and engineer. The Any material pson according to recognized best practice in construction for which it is adapted, will give the maximum efficiency capable with that material. On the other hand, no material used contrary to best practice can be expected to give satisfactory results. Take, for instance, the subject of concrete floors. That this question is of more than passing interest is evidenced in the following editorial, which appeared in Engineering Record for November 14, 1914:

"Why is it that in two concrete buildings apparently constructed under identical conditions, built by contractors of equal intelligence and integrity, from concrete composed of similar aggregates and the same brand of Portland cement, the floors in one will turn out hard, firm and resistant to abrasion, while in the other ordinary usage will result in dusting sufficient to make necessary some remedial measures?"

"The fact that numerous dustless concrete floors have been laid seems to indicate that the trouble must lie in the selection, proportioning, mixing, placing or finishing of the material. The procedure and proportions described below have given excellent results, though undoubtedly different mixes have also been used with satisfaction."

"Special precautions should be taken to insure first-class work. A rich mixture is desirable, say, a 1:1:1 mix, in which the aggregate consists of granite, or other hard stone, screenings graded from $\frac{1}{4}$ in. in size down to the finest, and crushed stone of equal quality passing a $\frac{1}{2}$ -in. ring and retained on a screen having a $\frac{1}{4}$ -in. mesh. All troweling and finishing of the floor surface should be completed within $2\frac{1}{2}$ hours from the time the materials leave the mixer. This necessitates mixing the material for the wearing course to such consistency that the mortar has to be scraped from the wheelbarrows and will hardly flatten out when dumped upon the floor, yet wet enough so that it can be 'struck off' with little difficulty when spread out with shovels. The floor usually is in a condition to be troweled for the last time within an hour and a half or two hours after the wearing course has been mixed. When sufficiently hardened to prevent pitting the floor should be sprinkled with water until 2 inches of sawdust can be thrown on the surface without injury. The sawdust should be thoroughly wet down and kept moist by sprinkling for a period of two weeks."

"Numerous experiments in curing concrete have demonstrated conclusively the superior quality of specimens which are properly cured by being kept moist for a period of two weeks or more. Wetting is quite common with other types of concrete work and can be relied upon to give as satisfactory results with floors."

"There are so-called hardeners on the market intended to be used with the finishing coat. In using these preparations careful supervision of the work from the time the concrete is mixed to the time that traffic is allowed on the floor is made a prime requisite for success. In all probability if the same care and attention are given to the workmanship and curing of floors in which no integral preparation is used, an excellent surface will result."

Extensive investigation has disclosed the fact that although several factors may be the determining ones in the dusting of concrete floors, none of these is other than a departure from good practice in any kind of

concrete construction. Dusting may result from too fine, dirty, or otherwise unsuitable sand; too little cement in the mixture; too much time allowed to elapse between mixing and finishing; troweling at several intervals after hardening has commenced and thus disturbing the process of crystallization of the cement in hardening; the use of dryers; and, finally, permitting the mortar to dry out too rapidly after placing."

The following specifications apply to plain concrete floors that are to be subjected to considerable wear and cover the preparation of the sub-base and the laying, finishing and curing of the floor. These are based on recommendations made after careful study of the subject by the American Concrete Institute. If the method of construction outlined in these specifications is followed, a concrete floor free from dusting, hence one that will give the maximum efficiency capable with the material—will result.

SUGGESTED SPECIFICATIONS FOR CONCRETE FLOORS.

GENERAL REQUIREMENTS.

I. Materials.

1. Cement: The cement shall meet the requirements of the current Standard Specifications for Portland Cement adopted by the American Society for Testing Materials.

2. Aggregates: Before delivery on the job, the contractor shall submit to the architect or engineer a fifty (50) pound sample of each of the aggregates proposed for use. These samples shall be tested, and if found to pass the requirements of the specifications, similar material shall be considered as acceptable for the work. In no case shall aggregates containing frost or lumps of frozen material be used.

(a) **Fine Aggregate:** Fine aggregate shall consist of natural sand or screenings from hard, tough, crushed rock or gravel, consisting of quartzitic grains or other equally hard material graded from fine to coarse, with the coarse particles predominating. Fine aggregate, when dry, shall pass a screen having four (4) meshes to the linear inch; not more than twenty-five (25) per cent shall pass a sieve having fifty (50) meshes per linear inch; and not more than five (5) per cent shall pass a sieve having one hundred (100) meshes per linear inch. Fine aggregate shall not contain vegetable or other organic matter nor more than three (3) per cent by weight of clay or loam. Field tests may be made by the architect or engineer on fine aggregate as delivered at any time during progress of the work. If there is more than seven (7) per cent of clay or loam by volume in one (1) hour's settlement after shaking in an excess of water, the material represented by the sample shall be rejected.

Fine aggregate shall be of such quality that mortar composed of one (1) part Portland cement and three (3) parts fine aggregate, by weight, when made into briquets, shall show a tensile strength at seven (7) and twenty-eight (28) days at least equal to the strength of briquets composed of one (1) part of the same cement and three (3) parts Standard Ottawa sand, by weight. The percentage of water used in making the briquets of cement and fine aggregate shall be such as to produce a mortar of the same consistency as that of the Ottawa sand briquets of Standard consistency. In other respects all briquets shall be made in accordance with the methods of testing cement recommended by the American Society for Test-

Olney J. Dean & Company

ENGINEERS AND MANUFACTURERS

Steel Bars for Reinforcing Concrete

179 W. Washington Street

Phone State 5940-5986

CHICAGO

CONCRETE INSERTS

of malleable iron correctly designed will develop the full strength of bolt when set in concrete

"CHICAGO" SCUPPERS

To secure maximum protection against fire and water loss at lowest insurance rates

VARIETY FIRE DOOR COMPANY

Formerly

VARIETY MANUFACTURING COMPANY

Steel Fire Doors, Art Metal Doors

Rolling Steel Shutters, Tin Clad Fire Doors

Cross Horizontal Folding Doors


Freight Elevator Doors, Saino Doors

Underwriters Labelled Doors

Carroll and Sacramento Aves.

Phone Kedzie 3434

CHICAGO, ILLINOIS



K I N N E A R

STEEL AND WOOD ROLLING
DOORS AND SHUTTERS
UNDERWRITERS APPROVED

The Kinnear Mfg. Co.

1860 Continental and Commercial Bank Bldg.

Phone Wabash 6474

CHICAGO, ILL.

FREDERICK VOSS

Manufactures of

**Fire Proof Wire Lathing and
Wire Cloth and Metal
Furring for all
purposes**

TELEPHONE MAIN 5333

552-554 W. Monroe St., Chicago

ARCHITECTS

will serve the best interests of their clients by specifying Voss Wire Lath for plastering—either plain, painted or galvanized. We recommend 18 gauge.

Always Specify

No. 18 Washburn & Moen Gauge .0475
3/8" Mesh Wire Lath. In calling for
Voss Lath you get this gauge and mesh.

ing Materials. (See Cement Specifications A. S. T. M.)

(b) **Coarse Aggregate:** Coarse aggregate shall consist of clean, hard, tough, crushed rock or pebbles graded in size, free from vegetable or other organic matter, and shall contain no soft, flat or elongated particles. The size of the coarse aggregate shall range from one and one-half ($1\frac{1}{2}$) inches down, not more than five (5) per cent passing a screen having four (4) meshes per linear inch, and no intermediate sizes shall be removed.

(c) **No. 1 Aggregate for Wearing Course:** No. 1 aggregate for the wearing course shall consist of clean, hard, tough, crushed rock or pebbles, free from vegetable or other organic matter, and shall contain no soft, flat or elongated particles. It shall pass when dry a screen having one-half ($\frac{1}{2}$) inch openings and not more than ten (10) per cent shall pass a screen having four (4) meshes per linear inch.

3. Mixed Aggregates: Crusher-run stone, bank-run gravel or mixtures of fine and coarse aggregate prepared before delivery on the work shall not be used.

4. Subbase: Only clean, hard material, such as coarse gravel or steam-boiler cinders, free from ash or particles of unburned coal, shall be used in the subbase. (Note: Eliminate this clause when subbase is not required.)

5. Water: Water shall be clean, free from oil, acid, alkali or vegetable matter.

6. Color: If artificial coloring matter is required, only those mineral colors shall be used which, in the amount hereinafter specified, will not appreciably impair the strength of the cement.

7. Reinforcement: The reinforcing metal shall meet the requirements of the current Standard Specifications for Steel Reinforcement of the American Society for Testing Materials. It shall be free from excessive rust, scale, paint or coatings of any character which will tend to reduce or destroy the bond.

8. Joint Filler: The joint filler shall be a suitable compound that will not become soft and run out in hot weather, nor hard and brittle and chip out in cold weather; or, prepared strips of fibre matrix and bitumen as approved by the architect or engineer. The strips shall be one-half ($\frac{1}{2}$) inch in thickness and their width shall at least equal the full thickness of the slab.

II. Subgrade.

9. Preparation: All soft and spongy places shall be removed and all depressions filled with suitable material which shall be thoroughly compacted in layers not exceeding six (6) inches in thickness. The subgrade shall be thoroughly tamped until it is brought to a firm, unyielding surface.

10. Deep Fills: All fills shall be made in a manner satisfactory to the architect or engineer. The use of muck, quick-sand, soft clay, spongy or perishable material is prohibited.

11. Drainage: When required, a suitable drainage system shall be installed and connected with sewers or other drains indicated by the engineer.

12. Depth: The subgrade shall be not less than.....(00) inches below the finished surface of the floor.

Note: Subgrade to be five (5) inches below the finished surface of the floor when subbase is not required, and at least eleven (11) inches below when subbase is required.

III. Subbase.

(Omit these sections when subbase is not required.)

13. Thickness: On the subgrade shall

be spread a material as hereinbefore specified, which shall be thoroughly rolled or tamped to a surface at least(00) inches below the finished grade of the floor. On fills, the subbase shall extend the full width of the fill.

14. Wetting: While compacting the subbase, the material shall be kept thoroughly wet, and shall be in that condition when the concrete is deposited.

IV. Forms.

15. Materials: Forms shall be free from warp and of sufficient strength to resist springing out of shape.

16. Setting: The forms shall be well staked or otherwise held to the established lines and grades and their upper edges shall conform to the established grade of the floor.

17. Treatment: All wood forms shall be thoroughly wetted and metal forms oiled or coated with soft soap or whitewash before depositing any material against them. All mortar and dirt shall be removed from forms that have been previously used.

V. Construction.

18. Size of Slabs: The slabs or independently-divided blocks when not reinforced shall have an area of not more than one hundred (100) square feet, and shall not have dimensions greater than ten (10) feet. Larger slabs shall be reinforced as herein-after specified.

19. Thickness of Floor: The thickness of the floor shall be not less than five (5) inches.

20. Width and Location of Joints: When required by the architect or engineer in charge, a one-half ($\frac{1}{2}$) inch space or joint shall be left between the floor and the walls and columns of the building, to be filled with the material before specified under "Joint Filler."

21. Protection of Edges: Where required by the architect or engineer in charge, the edges of the slabs at the joints shall be protected by metal. Unless protected by metal, the upper edges of the slabs shall be rounded to a radius of one-half ($\frac{1}{2}$) inch.

VI. Measuring and Mixing.

22. Measuring: The method of measuring the materials for the concrete or mortar, including water, shall be one which will insure separate uniform proportions at all times. A bag of Portland cement (94 pounds net) shall be considered one (1) cubic foot.


23. Machine Mixing: When mixing by machine, a batch mixer of an approved type shall be used. The ingredients of the concrete or mortar shall be mixed to the specified consistency, and the mixing shall continue until the cement is uniformly distributed and the mass is uniform in color. Raw materials shall not be permitted to enter the drum until all the material of the preceding batch has been discharged.

24. Hand Mixing: When it is necessary to mix by hand, the materials shall be mixed dry on a water-tight platform until the mixture is of uniform color, the required amount of water added, and the mixing continued until the mass is homogeneous and of uniform consistency.

25. Retempering: Retempering, that is, remixing with additional water or materials, mortar or concrete that has partly hardened, will not be permitted.

VII. Concrete Base.

26. Proportions: The concrete shall be mixed in the proportions, by volume, of one (1) sack Portland cement, two and one-half ($2\frac{1}{2}$) cubic feet fine aggregate and five (5) cubic feet coarse aggregate.



ARCHITECTURAL BRASS, BRONZE AND IRON WORKS

Bank Installations
Tubular Railings
Bank Grilles

Signs and Tablets
Cafeteria Fixtures
Theatre Frames

Ask for a copy of our catalog for your files

THE NEWMAN MANUFACTURING CO.

68 West Washington St., CHICAGO, ILL. 717 Sycamore St., CINCINNATI, O.

Badger Wire & Iron Works

Ornamental and Miscellaneous
IRON and WIRE WORK

Cleveland and 24th Aves.

MILWAUKEE, WIS.

J. E. ULRICH, Pres. & Gen. Mgr.

Phone, Ravenswood 298

W. E. BORG, Secy. & Treas.

WESTERN IRON CONSTRUCTION CO.

— INCORPORATED —

ENGINEERS AND CONTRACTORS
MANUFACTURERS OF
STRUCTURAL STEEL ORNAMENTAL IRON

Roof Trusses, Plate Girders and Building Iron of Every Description, Iron Stairs, Window Guards,
Side Walk Doors and Store Front Alterations a Specialty

We carry the largest stock of structural steel on the North side—cut to lengths on short notice

Office and Works: 4906-4908 N. Clark St., CHICAGO

Something New for the Architect, Builder and Consumer

“AJAX SERVICE”

Ajax Tanks and Towers for Sprinkler Systems

also

**WOOD TANKS, VATS AND TUBS OF ALL SIZES, KINDS AND
DESCRIPTION. STEEL OR MASONRY SUPPORTS FOR TANKS**

Repairing a specialty with us. We solicit all your inquiries, large or small

LAFAYETTE
5666

AJAX TANK & TOWER CO., 1407 W. 37th St.

27. Consistency: The materials shall be mixed wet enough to produce a concrete of a consistency that will flush readily under slight tamping, but which can be handled without causing a separation of the coarse aggregate from the mortar.

28. Placing: After mixing, the concrete shall be handled rapidly and the successive batches deposited in a continuous operation completing individual sections to the required depth and width. Under no circumstances shall concrete that has partly hardened be used. The forms shall be filled and the concrete struck off and tamped to a surface the thickness of the wearing course below the established grade of the floor. The method of placing the various sections shall be such as to produce a straight, clean-cut joint between them so as to make each section an independent unit.

29. Reinforcement: Slabs having an area of more than one hundred (100) square feet, or having any dimension greater than ten (10) feet, shall be reinforced with wire fabric, or with plain or deformed bars. The cross-sectional area of metal shall amount to at least 0.041 square inches per linear foot transversely and parallel to center line of floor. The reinforcement shall be placed upon and slightly pressed into the concrete base immediately after the base is placed and shall not cross joints and shall be lapped sufficiently to develop the full strength of the metal.

VIII. Wearing Course.

30. Proportions: The mortar shall be mixed in the proportions of one (1) sack of Portland cement, one (1) cubic foot of fine aggregate and one (1) cubic foot of aggregate for wearing course.

31. Consistency: The mortar shall be of the dryest consistency possible to work with a sawing motion of the strikeboard.

32. Thickness: The wearing course of the floor shall have a minimum thickness of three-quarter (¾) inch.

33. Placing: The wearing course shall be placed immediately after mixing. It shall be deposited on the fresh concrete of the base before the latter has appreciably hardened, and brought to the established grade with a strikeboard.

34. Finishing: After the wearing course has been brought to the established grade by means of a strikeboard, it shall be worked with a wood float in a manner which will thoroughly compact it and provide an even surface. When required, the surface shall be steel troweled, but excessive working shall be avoided.

35. Coloring: If artificial coloring is used, it must be incorporated with the entire wearing course, and shall be mixed dry with the cement and aggregate until the mixture is of a uniform color. In no case shall the amount of coloring exceed five (5) per cent of the weight of the cement.

IX. Protection.

36. Treatment: As soon as the finished floor has hardened sufficiently to prevent damage thereby, the floor shall be covered with at least one (1) inch of wet sand, or two (2) inches of wet sawdust, which shall be kept wet by sprinkling with water for at least ten (10) days. The freshly finished floor shall be protected from hot sun and drying winds until it can be sprinkled and covered as above specified.

37. Temperature Below 35 Degrees Fahrenheit: If at any time during the progress of the work the temperature is, or in the opinion of the architect or engineer will within twenty-four (24) hours drop to 35 degrees Fahrenheit, the water and aggregates shall be heated and precautions taken to protect the work from freezing for at least five (5) days. In no case shall concrete be deposited upon a frozen base.

These specifications plainly direct or imply the following fundamentals:

Clean, hard, well graded aggregates.
Clean water.
Proper consistency of concrete.
Proper curing.

The wearing course should be placed immediately after depositing the base so that a perfect bond will obtain between the two courses and the consistency of the wearing course should be such, when deposited, as will permit finishing to final surface in one operation within, say, 20 minutes after placing.

Too much water in the top course invariably compels several trowelings to secure the surface finish desired and frequent troweling after hardening of the cement has commenced breaks up the attendant processes of crystallization, thus affecting the ultimate wearing quality of the surface. Besides, over-troweling brings a film of cement and fine material to the surface which sets too quickly to attain proper strength, thus resulting in a surface devoid of wearing quality.

Proper curing of the floor. This perhaps does more to eliminate subsequent dusting than does minute observation of some of the other requirements, although none should be slighted.

Moisture is a necessary element for the hardening of concrete. Just as soon as possible after having finished the top course to the desired surface, the floor should be covered with a layer of protective material consisting of two inches or more of wet sand or sawdust, this covering to be kept wet by frequent sprinkling for from ten days to two weeks to prevent rapid drying out of the concrete.

Remedial treatments of several kinds may be used with from fair to indifferent success in temporarily allaying dusting of old concrete floors, but from the very nature of these treatments, which are essentially surface applications, renewal is required from time to time. Turpentine and boiled linseed oil combined in such proportions as to be readily absorbed by the floor surface form a mixture that will temporarily allay dusting. It is suited, however, only to old or thoroughly cured concrete and will somewhat darken the color of the floor.

If the wearing course of an old floor has separated from the base, or from whatever cause disintegrated so that resurfacing is necessary, a new wearing course that will be dustless may be applied by following the essentials of the foregoing specifications, if the old base is in good condition. First, however, all loose particles, preferably all of the old top course, must be removed, so as to expose the base, which must then be thoroughly cleansed by brushing and washing, followed by an application of a solution of 1 part hydrochloric acid to 3 or 4 parts of water, this being applied by a brush containing no metal. After having been allowed to remain from 10 to 15 minutes the acid wash must be thoroughly removed with clean water applied by a hose. An acid treatment such as described will expose the surface of aggregates in the base so that new concrete will more readily bond. Before placing the new top course, a grout of neat cement and water mixed to the consistency of thick cream should be applied to the cleansed surface of the base. Only a small area should be treated with grout at one time so that concrete for the new wearing course may be applied before the grout paint has commenced to harden. If the requirements of consistency, floating or troweling, and protection to insure proper curing, are observed, the refinished floor will be dustless.

Chester N. Marthens Marble Co.

Marble Workers and Contractors

53RD AND WALLACE STREETS
CHICAGO

FOREIGN *and* DOMESTIC
MARBLE *for* BUILDING
INTERIORS

TELEPHONE
BOULEVARD 1166

BRICK

• CHIMNEYS •

CONCRETE

THE HEINE CHIMNEY CO.

123 W. MADISON ST.

CHICAGO, ILLINOIS

TANKS

CONCRETE
RESERVOIRS

TOWERS

Telephone Franklin 2591-2595

AMERICAN CHIMNEY CONSTRUCTION CO.

RADIAL AND COMMON BRICK CHIMNEYS

SUITE 407-408
OXFORD BUILDING

CHICAGO, ILL.

Western Brick Company

DANVILLE, ILL.

FACING BRICK IN ALL SHADES AND TEXTURES

EXCLUSIVE MANUFACTURERS OF

"Doric" and "Gothic" Shades STIPPLED BRICK

Shale Common Brick and Hollow Building Tile

Capacity 100,000,000 Annually

STANDARD SPECIFICATIONS FOR SOUTHERN YELLOW PINE TIMBERS

As Recommended by The Illinois Society of Architects

DEFINITION FOR SOUTHERN YELLOW PINE.

(Authorized reprint from the copyrighted Standards of The American Society for Testing Materials, Philadelphia, Pa.)

Southern Yellow Pine.—This term includes the species of yellow pine growing in the Southern States from Virginia to Texas, that is, the pines hitherto known as long leaf pine (*Pinus palustris*), short leaf pine (*Pinus echinata*), loblolly pine (*Pinus taeda*), Cuban pine (*Pinus heterophylla*) and pond pine (*Pinus serotina*).

Under this heading two classes of timber are designated: (A) dense Southern yellow pine and (B) sound Southern yellow pine. It is understood that these two terms are descriptive of quality rather than of botanical species.

(a) **Dense Southern Yellow Pine** shall show on either end an average of at least six annual rings per inch and at least one-third summer wood, or else the greater number of the rings shall show at least one-third summer wood, all as measured over the third, fourth, and fifth inches of a radial line from the pith. Wide-ringed material excluded by this rule will be acceptable, provided that the amount of summer wood as above measured shall be at least one-half.

The contrast in color between summer wood and spring wood shall be sharp and the summer wood shall be dark in color, except in pieces having considerably above the minimum requirement for summer wood.

In cases where timbers do not contain the pith, and it is impossible to locate it with any degree of accuracy, the same inspection shall be made over 3" on an approximate radial line beginning at the edge nearest the pith in timbers over 3" in thickness and on the second inch (on the piece) nearest to the pith in timbers 3" or less in thickness.

In dimension material containing the pith but not a 5" radial line, which is less than 2x8" in section or less than 8" in width, that does not show over 16 sq. in. on the cross-section, the inspection shall apply to the second inch from the pith. In larger material that does not show a 5" radial line the inspection shall apply to the three inches farthest from the pith.

The radial line chosen shall be representative. In case of disagreement between purchaser and seller the average summer wood and number of rings shall be the average of the two radial lines chosen.

(b) **Sound Southern Yellow Pine** shall include pieces of Southern pine without any ring or summer wood requirement.

GENERAL TIMBER SPECIFICATIONS.

All timber except No. 1 Common must be free from defects such as injurious ring or round shakes, and through shakes that extend to the surface; unsound and loose knots, and knots in groups that will materially impair the strength. Seasoning checks and discolored sap shall not be considered defects in any grade.

KNOTS.

(Adopted by the American Society for Testing Materials, August 21 1915.)

Knots shall be classified as round and spike in form and for quality as sound, encased, loose and unsound.

A **round knot** is one which is oval or circular in form.

A **spike knot** is one sawn in a lengthwise direction; the mean or average width shall be considered in measuring these knots.

A **sound knot** is one which is solid across its face and which is as hard as the wood surrounding it; it may be either red or black, and is so fixed by growth or position that it will retain its place in the piece.

An **encased knot** is one whose growth rings are not intergrown and homogeneous with the growth rings of the piece it is in. The encasement may be partial or complete; if intergrown partially or so fixed by growth or position that it will retain its place in the piece, it shall be considered a sound knot; if completely intergrown on one face, it is a watertight knot.

A **loose knot** is one not firmly held in place by growth or position.

A **rotten knot** is one not as hard as the wood it is in.

WANE.

Wane is bark, or the lack of wood from any cause, on edges of timbers.

SHAKES.

Shakes are splits or checks in timbers which usually cause a separation of the wood between annual rings.

Ring shake: An opening between the annual rings.

Through shake: A shake which extends between two faces of a timber.

Shakes not hereinbefore described unless known to have extensive penetration shall not be considered a defect under this classification.

SIZES.

All rough timber, except No. 1 Common, must be full size when green. One-quarter inch shall be allowed for each side surfaced.

LENGTHS.

Standard lengths are multiples of two feet, eight to twenty feet, inclusive, extra lengths are multiples of two feet, twenty-two feet and longer. When lineal average is specified, standard of lengths shall be multiples of one foot.

BUILDING MATERIALS OF ALL KINDS



STONEKOTE EXTERIOR

White, Testing, Torpedo,
Bank and Moulding

S A N D

FIRE, Paving and Pressed

**BRICK
PAINT**

TOCH BROS. R. I. W.

Medusa White, Atlas White, LaFarge Non-
Staining, Best Bros.' and Victoria Keene's

CEMENT

The Garden City Sand Co., 708-711 Chamber of Commerce Bldg., CHICAGO
All Telephones Main 4827

Telephone Franklin 1523

Works { Mecca, Indiana
Newport, Indiana
Cayuga, Indiana
Oak Hill, Ohio

WM. E. DEE COMPANY
SEWER PIPE, FLUE LINING, WALL COPING
DRAIN TILE

Fire Brick and Clay, Building Material, Etc.
Manhole and Catch Basin Covers, Sanitary Castings

Main Office

30 North La Salle Street

CHICAGO

Brownell Improvement Company

MANUFACTURERS OF

CRUSHED STONE AND CRUSHED STONE SCREENINGS

*Crushed Stone and Screenings for Concrete Construction Work,
all Recrushed from Clean Screened Stone*

Rail Connections

C. & E. I. R. R., B. & O. C. T. R. R., C. T. H. & S. E. R. R., I. C. R. R., Wabash

General Offices: Chamber of Commerce Bldg.

Telephone Main 44

Quarries: Thornton, Ill.

CHICAGO

Franklin 970



W. H. McCARTHY

FACTORY SALES AGENT

Fire Brick, Metal Lath, Corner Beads,
Partition and Book Tile, Kellastone,
Stucco, Building Specialties

405 Chamber of Commerce Bldg.,
CHICAGO, ILL.

GRADES OF TIMBERS.

HEART TIMBERS.

All timber specifications, except "Merchantable" specifying heart requirements, shall be considered as a special contract, and shall specify whether the heart requirements refer to cubical contents or surface measurements in each piece.

NO. 1 COMMON TIMBERS.

May be either Dense or Sound Pine. Common timbers rough 4x4 and larger shall be not more than $\frac{1}{4}$ " scant at any point when green, and be well manufactured and may have $1\frac{1}{2}$ " wane on one corner one-third the length of the piece, or its equivalent on two or more corners; the wane measured on its face.

Timbers 10x10 in size may have 2" wane as above; the larger sizes may have wane as above in proportion to sizes.

The diameter of any one knot shall not exceed 2" in 4x4 to 6x6; $2\frac{1}{2}$ " in 6x8 to 8x10; 3" in 10x10 to 10x12; $3\frac{1}{2}$ " in 12x12 to 12x14; 4" in 14x14 to 14x16; $4\frac{1}{2}$ " in 16x16 to 16x18. In sizes not mentioned the diameter of knots admissible will increase or decrease in proportion to the size of the timbers on same basis as above specified.

In determining the size of knots, mean or average diameter shall be taken, or the equivalent of the above in grouped knots at any one point. Shakes one-sixth the length of the piece, small unsound knots and a limited number of pin worm holes, well scattered, are inadmissible.

SQUARE EDGE AND SOUND TIMBERS.

May be either Dense or Sound Pine. Square edge and sound timbers shall be well manufactured and conform to the General Timber Specifications, admitting sound knots, and shall be free from wane.

MERCHANTABLE TIMBERS.

May be either Dense or Sound Pine. All merchantable timbers shall be well manufactured and conform to the General Timber Specifications.

Sizes under 9" on the largest dimension, shall show two-thirds or more heart surface on one of the wide faces; sizes 9" and over on the largest dimension shall show two-thirds or more heart on both of the wide faces. When sticks are square the face showing the most heart shall govern the inspection on sizes under 9", and the two faces showing the most heart shall govern the inspection when 9" and over. Heart showing the full length, even if not two-thirds of the area as above, shall meet the requirements of this quality.

Wane not exceeding one-eighth of the dimension of the face and one-quarter of the length of the piece on one corner, or the equivalent on two or more corners on not to exceed ten per cent of the pieces, shall be admitted.

SELECT STRUCTURAL MATERIAL.

(A rule incorporating suggestions by the United States Forest Service.)

REQUIREMENTS FOR DENSITY AND RATE OF GROWTH.

1. Shall contain only sound wood and be well manufactured.

2. Shall conform to the definition of Dense Southern Pine as adopted by the American Society for Testing Materials, August 21st, 1915, shown on page 6.

For the purpose of determining whether any given piece meets the requirements for density and rate of growth, the following rule, suggested by the United States Forest Service, shall be applied. It will be sufficient if either end passes the inspection.

(1) Pith Present or Accurately Located.

- (A) Radial line of 5" present.
 - (a) Apply inspection over third, fourth and fifth inches.
- (B) Radial line of 5" not present.
 - (a) Apply inspection to the second inch on 2x3, 2x4, 2x6, 3x3, 3x4, 4x4, or any other dimension material that has less than 16 square inches on the cross section.
 - (b) In the larger material apply inspection to the 3 inches farthest from the pith.

(2) Pith Not Present or Cannot be Accurately Located.

- (A) Material over 3" thick apply inspection to three inches nearest the pith.
- (B) Dimension material 3" or less in thickness apply inspection to second inch of the piece nearest the pith.

(3) The Radial Line Chosen Shall Show a Representative Number of Annual Rings of Growth and Per Cent of Summer Wood.

Restrictions on Knots in Beams.

3. Shall not have in Volume 1 sound knots greater in diameter than one-fourth the width of the face on which they appear—maximum knot $1\frac{1}{2}$ ". Shall not have in Volume 2 sound knots greater in diameter than one-half the width of the face on which they appear—maximum knot 3 inches.

The aggregate diameter of all knots within the center half of the length of any face shall not exceed the width of that face.

The diameter of a knot on the narrow or horizontal face of a beam is to be taken as its projection on a line perpendicular to the edge of the timber. On the width or vertical face, the smallest dimension of a knot is to be taken as its diameter.

Restrictions on Knots in Columns.

4. Shall not have sound knots greater in diameter than one-third the least width of the column—maximum knots 4 inches.

Restrictions on Shakes and Checks in Beams.

5. Round or ring shakes shall not occupy, at either end of a timber, more than one-fourth the width of green material, nor more than one-third the width of seasoned material.

Any combination of checks and shakes which would reduce the strength to a greater extent than the allowable round-shakes will not be permitted. Shakes shall not show on the faces of either green or seasoned timber.

Restrictions on Cross Grain in Beams.

6. Shall not have diagonal grain with slope greater than one in twenty in Volume 1.

ABBREVIATIONS OF TIMBER GRADES.

For the purpose of branding timbers with the names of the grades it is recommended that the following abbreviations be used:

SQ EDG-SD —Square Edge and Sound.
NO 1 COM —No. 1 Common.
MERCH —Merchantable.
SEL STRUC—Select Structural.

INTERIOR TILING COMPANY

CONTRACTORS FOR

WALL, FLOOR AND FIREPLACE TILING

Ceramic Mosaic, Vitreous, Flint, and Quarry Tile Floors.

Glazed and Faience Tile Wainscotings.

OFFICE AND SHOWROOMS, 5TH FLOOR ISABELLA BUILDING

21 E. VAN BUREN STREET, CHICAGO

Phone Main 3965

WILLIAMS-WENDT CO. **Flooring Contractors**

"Korkstone" Composition, "Mas-Oleum" Mastic, Tiles and Mosaics,
Cork Tile, Etc.

Samples, Estimates and General Information on All Flooring
Problems Furnished

118 N. La Salle Street, CHICAGO

WEARY *and* BECK

CONTRACTORS FOR

*Wall, Floor and Fireplace Tiling, Ceramics,
Quarries, Rookwood and Grueby Faience Tiles*

Office and Showroom

1732 S. Michigan Ave., Chicago, Ill.

Telephone Calumet 4570

MAGNETILE **FLOORS**

SANITARY BASE—WAINSCOT—STAIR TREADS and RISERS

Manufactured and Installed by

THE CRAIG COMPANY

Phone Central 8950

30 North Michigan Avenue, CHICAGO

ARCHITECTS SPECIFICATIONS FOR SOUTHERN YELLOW PINE STRUCTURAL TIMBERS.

(1) When Both Maximum Durability and Strength Are Required.

Longleaf southern yellow pine of "select structural material grade" in accordance with the definition of "Dense Southern Yellow Pine" as adopted by the American Society for Testing Materials (August, 1915), and the Southern Pine Association ("Density Rule" book, March 15, 1916). To be dressed to standard sizes conforming to the rules of the Southern Pine Association and branded in accordance with the official requirements of that Association.

(2) When Strength Is Required Without Special Reference to Durability.

Southern yellow pine of "select structural material grade" as defined in Section (1) above. To be dressed to standard sizes conforming to the rules of the Southern Pine Association and branded in accordance with the official requirements of that Association.

(3) When Used Without Reference to Durability or Maximum Strength.

No. 1 Common southern yellow pine timbers of "dense" grade as defined in the "Timber Rule" book of the Southern Pine Association (March 15, 1916). To be dressed to standard sizes conforming to the rules of the Southern Pine Association.

(4) When Used for Joists, Studs, etc., in Ordinary or Minor Structures Without Reference to Durability or Maximum Strength.

No. 1 Common southern yellow pine, as defined in the "Timber Rule" book of the Southern Pine Association, March 15, 1916. To be dressed to standard sizes conforming to the rules of that Association.

FOR SOUTHERN YELLOW PINE HEAVY FACTORY AND LAMINATED FLOORING.

(5) When Durability and Maximum Strength Are Required.

"Dense" southern yellow pine of "merchantable grade" as defined in the "Timber Rule" book of the Southern Pine Association (March 15, 1916). To be dressed to standard sizes conforming to the rules of that Association and branded in accordance with the official requirements of that Association.

(6) When Strength Is Required Without Reference to Durability.

Southern yellow pine of "No. 1 Common Timbers" as defined in the "Timber Rule" book of the Southern Pine Association (March 15, 1916). To be dressed to standard sizes conforming to the rules of that Association.

Note.

In lieu of the branding of timber above specified, the contractor may at his option arrange to have all material furnished under this specification inspected by the Inspection Department of the Southern Pine Association, in which event the contractor shall furnish and deliver to the architect a certificate showing that all material delivered complies with the architect's specifications. The entire expense of said inspection must be paid by the contractor.

Reinspection.

Should the architect demand that any material delivered be reinspected the said inspection shall be made by the official inspectors of the Inspection Bureau of the

Southern Pine Association or Lumbermen's Association of Chicago. Should ninety-five per cent (95%) or more of the material inspected be approved as complying with the grade specified, the inspection fee shall be paid by the owner. Should five per cent (5%) or more of the material inspected be rejected by the said Inspector as not complying with said grading rules, all inspection fees shall be paid by the contractor.

STANDARD SPECIFICATIONS FOR GRADES OF SOUTHERN YELLOW PINE FLOORING MARCH 15, 1916.

No. 1 COMMON FLOORING is the combined grade of C and D Flooring, and will admit all pieces that will not grade "B," and are better than No. 2 Common.

No. 2 COMMON FLOORING admits all pieces that will not grade as good as "D" flooring that can be used for cheap floors without a waste of more than one-fourth the length of any one piece. (See Sec. 26.)

No. 1 COMMON FACTORY FLOORING will admit of sound knots not over one-half the cross-section of the piece at any point throughout the length; pitch pockets, sap stain, shakes that do not go through, firm red heart, seasoning checks which do not show an opening through the piece, wane one-fourth inch deep on the face, a limited number of pin worm holes well scattered, loosened or heavy torn grain or other machine defects which will lay without waste, and pith knots which will not cause a leakage of grain. (See Secs. 35 and 123.)

"A" FLAT FLOORING must be practically free from defects on the face side and well manufactured.

"B" FLAT FLOORING will admit any two of the following or their equivalent of combined defects: 15 per cent. sap stain, 15 per cent. firm red heart, three pin knots, one standard knot, three small pitch pockets, one standard pitch pocket, one standard pitch streak, slight torn grain, small seasoning checks, six pin worm holes.

"C" FLAT FLOORING will admit any two of the following defects or their equivalent of combined defects: 25 per cent. of sap stain, 25 per cent. of firm red heart, two standard pitch streaks; medium torn grain, or other machine defects that will lay without waste; slight shake that does not go through, or seasoning checks that do not show an opening through, two standard pitch pockets, six small pitch pockets, two standard knots or six pin knots, twelve pin worm holes.

EDGE GRAIN FLOORING shall take the same inspection as Flat Grain, except as to the angle of the grain. (See Sec. 23.)

HEART FACE EDGE GRAIN shall be free from sap on face side.

"D" FLAT FLOORING will admit the following defects or their equivalent of combined defects: Sound knots not over one-half the cross section of the piece in the rough at any one point throughout its length; three pith knots, pitch, pitch pockets, sap stain, firm red heart, seasoning checks that do not show an opening through, shake that does not go through, a limited number of pin worm holes well scattered, loosened or heavy torn grain, or other machine defects that will lay without waste.

Pieces otherwise as good as "B" Flooring may have one defect (like a knot hole) that can be cut out by wasting 1½ inches of the length of the piece, provided both pieces are 16 inches or over in length after cutting out such defects.

HOLLOW TILE

Structural *and* Partition

Our works at Roanoke, Ill., is one of the most efficiently equipped in the country with a capacity of 2,000 cars annually. We manufacture **MASTER TILE** and will be pleased to furnish samples and price lists on request.

BARRON BRICK COMPANY
Tribune Building CHICAGO, ILL.

SPECIFICATIONS RECOMMENDED FOR HOLLOW TILE FIREPROOFING

(1) In General:

The contractor for the fireproofing shall furnish all the Hollow Tile material required for the floor and roof construction, including the fireproofing of all structural steel work, beams, girders, lintels, columns, etc., excepting where steel is indicated as being encased in the wall or other masonry, or specifically referred to as being left exposed (such as roof trusses, elevator sheave beams, etc.), also the Hollow Tile for partitions, furring and such other work as indicated on the drawings.

This contractor shall furnish all labor, transportation, tools and equipment and all other materials required to erect the Hollow Tile fireproofing and other construction in accordance with the drawings and as herein-after specified, all conforming to the best and latest practice and to the satisfaction of the architect; only skilled tile setters to be employed for the setting.

Contractors shall carefully examine the steel framing, drawings and structural details and provide for the complete and proper fireproofing of the structural frame.

(2) Material:

All Hollow Tile fireproofing shall be of hard burned (dense) or (semi-porous) ware that will develop a crushing strength of at least 1525 pounds per square inch of net sectional area of the tile when tested on end, and stamped with the Manufacturer's name or that of his association. No badly split, cracked, warped or underburnt tile shall be used.

Book tile roofing, solid beam and girder covering (nailing tile) and such other items as are specifically so noted shall be hard burned, full-porous ware.

All Hollow Tile fireproofing shall be capable of withstanding the tests prescribed by the "National Board of Fire Underwriters" standards for fire resistive floor, wall and partition construction.

(3) Size and Dimensions of Tile:

All Hollow Tile arching shall be of the shape required to carry and transmit the loads with an ample factor of safety.

Floor arch tile shall have the outside shells not less than $\frac{3}{4}$ " in thickness and the webs not less than $\frac{5}{8}$ " in thickness, excepting that the shells and webs of keys and skewbacks, or other shapes that must resist both compression and shearing stress, shall be thicker when required. Skewbacks shall be designed to resist the combined shear and thrust from arch and be formed to fit and protect the various steel sections on which they are set.

Partition tile shall have shells not less than $\frac{5}{8}$ " and webs equal in thickness, number and arrangement to Hollow Building Tile Association Standard.

Cross webs in all arch and fireproofing shall be spaced not over 4" on centers and all blocks 8" or more in thickness shall have at least one mid-web.

The faces of all tile that are to receive plastering or mortar shall have the standard scoring. The thickness of the shells of side construction arches shall be made sufficient to resist the combined compression and shearing stresses, with ample fillets at all intersections of webs and shells.

Beam, girder and lintel fireproofing shapes when hollow shall have shells at least $\frac{5}{8}$ " in

thickness, or if solid, be of porous or semi-porous ware and at least $1\frac{1}{2}$ " thick at extreme edge of metal.

(4) Fireproofing Steel:

The thickness of fireproofing around steel members shall in no case be less than the following (and thicker where necessary to conform to existing State or Municipal ordinances or by-laws):

Soffit coverings on lower flange of beams supporting flat arches shall be $1\frac{1}{2}$ " thick if of solid material and 2" thick if made hollow.

Covering on beams and girders extending below the soffit of arches: at least 2" thick for plain rolled sections, plate girders, trusses, etc. Web covering shall be built out solidly to the thickness required in all cases.

Solid Tile column fireproofing for round or other special columns shall be at least $2\frac{1}{2}$ " in thickness of porous or semi-porous ware.

(5) Detail Drawings:

This contractor shall submit to the architects for approval any required detail drawings, showing the form, section and method of applying the fireproofing to the steel work, etc., before starting the manufacture of material. Details to be full size where any special shapes are required.

Stock shapes may be used throughout for the fireproofing of beams and girders, columns, etc., where they conform to the requirements of this specification and fit the contour of the steel sections. Elsewhere the contracts shall furnish, without extra cost, all other shapes required to properly fit and encase the steel work.

(6) Scaffolding and Centers:

Contractor shall provide his own hoisting rig and all scaffolding, centers and forms required for the setting of his work. Scaffolding and centers to be provided in sufficient quantity to insure the rate of progress outlined in contract.

This contractor shall also furnish the proper protection for his men and for those working under him, as required by the City and State laws.

(7) Mortar and Laying:

All arches, fireproofing, partitions, furring, etc., shall be set in cement mortar composed by volume of one part (approved brand) Portland cement to three parts clean sharp sand. Not over 15% of the cement by volume of hydrated lime may be added.

Cements, sand, etc., shall conform to the requirements elsewhere specified under the heading of "Masonry."

All steel work shall be coated with this mortar just ahead of the setting of fireproofing.

All tile shall be laid with full butted end and side joints and shall be shoved to a bearing on a full bed of mortar with as close a joint as possible, pointing up and filling all crevices with mortar.

In warm weather all tile shall be thoroughly wetted before setting. Frost shall be driven from the tile by heating when setting is carried on during cold weather and no fireproofing shall be set when the temperature is below 20 degrees Fahrenheit without the permission of the architect.

Telephone Harrison 459

Standard Shapes
Fireproofing Tile



Flat and Segmental
ARCH TILE

Illinois Fire Proof Construction Co.


*Manufacturing Contractors and
Dispensers of Everything in*

“HOLLOW TILE”

Rookery Building, 209 S. LaSalle St.

R. W. RAFTIS, *President*

CHICAGO



National Fire Proofing Company

MANUFACTURERS OF

*Terra Cotta Hollow Tile
for Building Purposes*

Contractors for construction of Hollow Tile
Fireproofing Buildings.
Reinforced Concrete
Buildings.

OFFICE—2610 Shields Avenue

CHICAGO, ILL.

(8) Flat Arches:

All floors throughout (including the main roof and the roof in light court), except where otherwise noted, shall be constructed of ... deep end construction flat arches having (side construction) skewbacks and keys of the sizes required to fit the several spans without cutting.

Any additional keying or wedging required shall be done with tile slabs or slate.

Solid beam soffit tile shall be separate from the skewbacks and of the proper size, having bevelled sides so as to be securely keyed in place by the skewbacks.

Skewbacks shall be of the size required and be properly formed or coped to fit the various beam sections.

Whenever possible, any openings required in arches for pipes, etc., shall be formed or left at the time of setting so as to avoid later cutting.

(9) Segmental Arches:

All.....shall be 6" (or 8") deep, side construction segmental arches, set on skewbacks of the forms indicated on drawings, properly encasing the lower flange of beams, all segment lengtheners to be uniform size, except where smaller sizes are required for keying up, and shall be set with broken joints in each course, carefully fitting up to and between tie rods by using the required short lengths for starters and closures.

Solid beam soffit tile shall be separate from the skewback and of the proper size, having bevelled sides so as to be securely keyed in place by the skewbacks.

(10) Beam and Girder Covering:

All beams, girders, or other steel members, extending below the soffit of arches, shall be encased in Hollow Tile of the thickness specified, all to be properly fitted and set with well filled mortar joints encasing the entire length of beam and where necessary be securely strapped or clipped in place with 1" by No. 16 gauge band iron or No. 10 gauge galvanized iron wire. Where metal fastening is necessary, as in the case of wide soffits, the soffit tile shall be hollow and the metal clamp be arranged in the hollow space; these soffit tile to be also keyed into place by mortar joints. The fireproofing of main carrying beams and girders shall be independent of the floor arch construction and shall extend up to top flange so that openings for pipes, etc., that may be left or cut will not expose the webs or flanges of any members of the structural frame. All spandrel beams and girders and other lintel members shall be protected with the tile fireproofing where not indicated as being encased in the masonry of walls.

(11) Book Tile Roofing:

The roofs of penthouses and vent shafts, also the backs and ends of saw-tooth skylights and mansard roof and top of cornice and the pitched roofs of tower or dome, shall be constructed of 3" book tile, set on "T" irons which will be provided and erected by the steel contractor.

The floor of bulkheads in show windows shall also be constructed of book tile.

(12) Suspended Ceilings:

The ceiling under roof in (top) story and the ceiling of boiler room (also the soffits of stairs, where so indicated) shall be constructed of 3" book tile ceiling bolcks, set on "T" iron framing provided and erected by the steel contractor.

Book tile for ceilings shall be coped so as to give a level ceiling and before setting the lower flange of "T" irons shall be wrapped with a strip of galvanized light weight diamond mesh expanded metal, or galvanized woven wire mesh.

(13) Column Covering:

All interior columns (and such other columns that are so indicated on the drawings) shall be encased with Hollow Tile as indicated, set 1" free of the steel; all channel spaces in columns shall first be filled in solid with Hollow Tile or a fine stone or gravel concrete, or broken tile and cement mortar.

The steel column shall be plastered with a full $\frac{1}{2}$ " coat of Portland cement mortar just in advance of the setting of the tile covering.

Column covering shall in all cases start on the top of the fireproof floor construction and be carried up to the underside of fireproof ceiling above, each course of tile to be set breaking joint with the one below and be warped once in every course with 10-lb. galvanized iron wire, or be tied together with "U" shaped clips of band iron in each course.

Where so indicated, column covering shall have rounded corners.

No piping shall be enclosed in the column fireproofing, excepting electric conduits, not over $\frac{5}{8}$ " in size, built into the channel space before the column covering is set. These conduits shall be grouted in solid with at least 3" of solid material between conduit and the face of steel. All other piping at columns shall be separately inclosed in ducts as indicated and hereinafter specified.

(14) Wall Furring:

The furring of exterior walls (and the party walls where so shown, including the walls of basement), where free standing, shall be built of 3" (or 4") hollow partition tile, the same as partitions, elsewhere the furring of all exterior and party walls shall consist of 2" split furring tile built against and secured to the brick or other masonry with approved metal wall ties previously built into the masonry, or with galvanized heavy 4" wire nails driven into the joints of same every second course in height and not over 3' 0" apart.

Wall furring, where so indicated, shall be returned into jambs at windows (including the furring down at windows soffit).

(15) Special Furring, Pipe Enclosure, Etc.:

Where indicated on drawings, the walls, columns, piers, etc., shall be furred out to the lines required by the architectural details for the special form and finish of the room, corridors, etc., as indicated, forming all offsets, reveals pilasters, etc., using partition tile of the required size. In general this work shall be done with 3" partition tile with brace or cross walls of same size blocks wherever required. Cross walls shall

Waterproof and Wearproof for Permanence

ADVANCE WATERPROOF CEMENT CO.

MANUFACTURERS OF

Advance Reground Waterproof Portland Cement.

A self contained **waterproof Reground** Portland Cement, ground to a fineness of talcum powder, for the Permanent, Dense, Integral Method of Waterproofing Portland Cement Concrete, Plaster, Stucco and Mortar for all purposes.

Advance Hydro-Corundum Portland Cement

A **Reground** Portland Cement with a floor hardener combined, for a Dense, Waterproof, Dustproof, Wearproof and Permanent Portland Cement Concrete Floor and Stair Finished Topping.

(Mills at Blue Island, Ill.)

15 E. Van Buren St., Chicago, Ill.

Tel. Wabash 2020

Robert W. Hunt

Jno. J. Cone

D. W. McNaugher

Robert W. Hunt & Co., Engineers

Bureau of Inspection :: Tests and Consultation

Inspection and Tests of Structural and Reinforcing Steel and Cement

Testing of Walls, Floors, Columns, Elevators and Power Plant Equipment

Inspection and Supervision of Construction

Cement, Physical and Chemical Laboratories

General Offices: 2200 Insurance Exchange, Chicago

W. G. Bohnsack, Pres.

Telephones: Main 3877; Franklin 2809

Carey Brick Company

Manufacturers

Common and Sewer Brick

Main Office, 422 Chamber of Commerce Building, CHICAGO

Yard Narragansett and Grand Avenues

WM. SCHLAKE, PREST.
G. F. PERKINS, TREAS.

C. B. OBERMEYER, VICE-PREST.
CARL NETTELHORST, SECY

ILLINOIS BRICK COMPANY

1717 CONWAY BUILDING

CHICAGO

TELEPHONE MAIN 15

be anchored or tied into both furring and masonry.

All piping, conduits, etc., where so indicated shall be inclosed with 2" or 3" partition tile; chases in walls to be similarly covered. This work shall be independent of the column fireproofing and be arranged so that the piping is left accessible until after it has been tested.

(16) Partitions:

All partitions and interior division walls shall be built of light weight Hollow Partition Tile of the several thicknesses indicated on drawings. Sizes not marked on plans shall be as follows:

Partitions enclosing elevator and stair walls, pipe shaft, etc., and all partitions over 18' 0" in height to be 6" thick.

Division walls in stores on ground story to be 8".

All main and corridor partitions and all partitions around toilet rooms, etc., also all sub-dividing partitions over 14' 0" in height to be 4" thick.

All other partitions to be 3" thick.

All division walls, main and corridor partitions shall start directly on the arches; but sub-dividing partitions may be built on the floor filling and where so indicated shall be built on the top of finished floor to provide for tenant changes.

All partitions to be carried up to and be wedged tightly against the underside of fireproof ceiling or beams above.

Where there are more than two courses of partition tile the heads of doors or other openings in sub-dividing partitions and over all openings wider than 3' 6" jack arches, light steel lintels or suitable reinforcement or band iron shall be provided and similar lintels shall be provided over all openings in main partition wall furring, etc.

All partitions shall be built true to a line and plumb and at all intersections shall be bonded together or be tied with approved metal ties or with band iron. Provision shall be made for securely anchoring all heavy frames which are not fastened to the steel framing.

All partitions, furring, column casing or other items built with partition or furring tile shall be well bonded by breaking joints at least 3" in each course, all joints to be thoroughly bedded and flushed and pointed up with mortar.

Double partitions shall be bonded together and stiffened with cross walls of the same material, as shown on drawings. All anchors, ties, etc., required for this work to be furnished by this contractor.

(17) Vaults:

The lining of fireproof vaults shall consist of a 4" Hollow Partition Tile built 2" free of and anchored to the vault wall masonry by hollow header brick. The wall of storage vaults on .. stories shall consist of a double 4" partition tile (or a double 4" and 6" partition) breaking joints in each course. Vault doors to be securely anchored at least two courses deep in every second course.

(18) Pent Houses and Other Walls:

The walls of pent houses and vent shafts on roof (also the wall of pipe tunnel back

of cornice) shall be built of 8" exterior wall tile having a deep scoring to receive the cement stucco. All openings in tile at the top of these walls shall be capped with a tile (slab) before the cresting or coping is set.

(19) Bulkheads and Skylight Curbs:

The bulkheads and skylight curbs where indicated as covered with sheet metal shall be built of 3" (or 4") thick Hollow Partition Tile. Elsewhere they shall be built of 6" (or 8") exterior wall tile same as pent houses. The roof of bulkheads (unless otherwise shown) shall be constructed of 3" book tile, set on loose "T" iron which will be furnished by another contractor but be set by this contractor.

(20) Miscellaneous Iron:

All loose light steel sections and miscellaneous ironwork occurring in connection with the Hollow Tile fireproofing work, excepting anchors, ties (reinforcement), band iron, etc., will be furnished by other contractors, but shall be set by this contractor without extra charge.

(21) Raised Floor:

The raised floors in toilet room where indicated shall be constructed of 3x12x18 book tile or heavy section partition tile set on dwarf walls of partition tile and brick. This work shall be so arranged as not to interfere with the installation of the plumbing work. These floors to be closed up only after the pipes have been tested and approved.

(22) Roof Fill and Finish:

Here specify cinder-fill and cinder, slag or sawdust concrete being careful to require protection against corrosion around pipes.

(23) Load Tests:

All Hollow Tile arches shall be capable of sustaining a load of three times the required live load, per square foot, and they shall be tested by the contractor where so directed by the architects.

(24) Cutting and Patching:

This contractor alone shall do all cutting and patching of the arching, beam, girder and column fireproofing that may be required for the roughing in of piping, etc., or the installation of other work, the cost of which (actual labor cost plus 10%) shall be reported to the general contractor (or architect), who will adjust same with the contractors for whom this work is done.

The cutting and patching of partitions and furring, etc., will be paid for by the contractors whose work occasions same.

All other cutting and patching and the repairing of all Hollow Tile work so as to leave the whole work perfect and complete shall be done by this contractor at his own expense.


(25) Removal of Rubbish:

Upon completion of the Hollow Tile fireproofing and whatever else required by the architect's superintendent, this contractor shall clean up and remove from the premises any refuse and surplus material resulting from this work, leaving the premises clear of such rubbish. This contractor, however, may use the broken tile in the floor filling, provided same is broken into small pieces and kept free from plaster, wood chips and other rubbish.

"PIERCE"

MAGAZINE FEED, DOWN DRAFT SMOKELESS BOILER

For Soft or Hard Coal



Long Firing Period, Requires Little Attention

ECONOMICAL, SMOKELESS

ACCEPTABLE IN ALL CITIES THAT HAVE SMOKE ORDINANCES

WRITE FOR GENERAL
CATALOGUE AND
FULL INFORMATION

THE KELLOGG-MACKAY COMPANY

HEATING AND PLUMBING SUPPLIES

CHICAGO

MINNEAPOLIS

DULUTH

KANSAS CITY

ST. PAUL

HEATING AND VENTILATION

Edited by Fred J. Postel, Mech. Engr.

HEATING.

In considering the installation of a heating system, the architect or engineer in almost every instance has his choice of three types, namely, steam, hot water and hot air. Both steam and hot water systems are fundamentally the same in principle regardless of the size of the installation, although, of course, there are modifications and variations in the application, to meet local conditions.

In hot air heating installations the smaller installations are almost always gravity systems, while the larger installations are almost always mechanically operated systems, i. e., the air is moved by means of fans.

As a matter of convenience, we may divide heating systems into two general classes, those using piping and radiating surfaces (steam and hot water systems) and those using ducts (hot air furnaces and hot blast systems).

STEAM VS. HOT WATER:

Before taking up the systems of the first class in detail, it may be well to consider some of the outstanding advantages and disadvantages of each. To simplify the discussion, the simple gravity system of each type is referred to in this comparison. Numerous improvements and modifications have been developed for both steam and hot water systems in order to gain some of the advantages of the other system. These naturally involve the installation of devices more or less automatic, but all requiring a certain amount of attention to keep them in operation. The question of whether the advantage gained warrants the expenditure both in first cost and in operation and maintenance, will depend on local conditions and no general rule will apply.

Generally speaking, the advantage of the steam over hot water is lower first cost, smaller radiators and smaller piping. The principal disadvantage is the fact that the temperature of the radiating surface cannot be regulated to meet the demands of the weather conditions. Again, the system is operative only so long as there is pressure in the mains. If the pressure is allowed to fall to atmosphere, circulation ceases, and the building is, to all intents and purposes, without a heating system, even though there is a smoldering fire in the furnace.

The advantage of the hot water heating system is that the temperature of the water may be varied with the demands of the service. With a properly designed system the water circulates at a very low temperature,

so that a smoldering fire will produce sufficient circulation in mild weather. This feature makes it possible also to continue heating the building after the fires have been banked for the night.

The principal disadvantages of a hot water system are the greater first cost, larger radiators and piping, and the ever present possibility of damage to decorations and furnishings, as a result of a leak in the system.

The "vapor" system of steam heating and the so-called "modulation" system, both provide excellent means of temperature regulation and in this respect approach the advantages of a hot water system.

On the other hand, to overcome the disadvantage of large, ungainly radiators and piping, in hot water systems, various devices have been developed to increase the temperature of the water under conditions of extreme demand. These systems depend on increasing the pressure on the water above atmosphere and are what may be referred to as closed systems, either wholly or in part.

STEAM HEATING.

In designing a system of steam heating, it should first be determined whether the conditions will be best met by a gravity, or a vacuum system.

In a gravity system, the mains and radiating surface are so laid out that all condensation returns to the boiler by gravity and no machinery is required to keep the system in operation. This system is necessarily operated at a pressure above atmosphere so that the pressure in the radiators is sufficient to expel the air from the system.

Practically all the vacuum systems being installed today remove the condensate and the entrained air through the same pipe. Another type of vacuum system in which each heating unit was provided with an air valve and these valves connected to a vacuum pump was in quite general use some years ago but is seldom used now.

The term "vacuum system" as used in this discussion will be taken to mean a system in which each individual heating unit is provided with a thermostatic or float type of trap and the condensate and air removed through a system of piping by means of a vacuum pump. In this connection it may be stated that in the case of large installations in which a group of buildings is sup-

Kewanee, Ill., Chicago, Ill., 328 W. Washington St., Phone Franklin 4189
Branches in principal cities of the United States

BOILERS

Brick-Set Direct Draft Fire-Box

Number of Boiler	1	2	3	4	5	6	8	9	10	11	12	13	14	15	16	17	18	19	20	
Capacity, Steam	sq. ft	1500	1050	1200	1400	1700	2000	2600	3000	3500	4000	4500	5500	6500	7500	8700	10000	11000	12000	14000
Capacity, Water	sq. ft	900	1050	2000	2300	2800	3300	4300	5000	5800	6600	7400	9100	10700	12400	14400	16500	18200	19800	23100
Diameter Boiler	in.	30	30	30	36	36	36	42	42	48	48	48	54	54	60	60	66	72	72	81
Diameter of Stack	in.	12	12	14	14	16	16	18	20	22	22	26	26	30	30	30	30	34	34	34
Minimum Height of Stack	ft.	40	40	40	40	40	45	45	45	45	50	50	50	55	55	60	60	60	60	60

Brick-Set Smokeless Fire-Box

Number of Boiler.....	107	108	109	110	111	112	113	114	115	116	117	118	119	120
Capacity, Steam.....sq. ft.	2660	3100	3600	4000	4700	5500	6500	7500	8500	10000	11500	13000	14000	16000
Capacity, Water.....sq. ft.	4200	5100	5900	6600	7800	9100	10700	12400	14000	16500	19000	21500	23000	26400
Diameter Boiler.....in.	42	42	42	48	48	48	54	54	60	60	66	66	72	72
Diameter Stack.....in.	20	20	22	22	24	24	28	28	32	32	34	34	36	36
Minimum Height of Stack, ft.	50	50	50	50	55	55	60	60	60	60	70	70	70	70

Portable Direct Draft Fire-Box

Number of Boiler.....	407	408	409	410	411	412	413	414	415	416	417	418	419	420
Capacity, Steam.....sq. ft.	2500	2900	3500	4000	4500	5000	5500	6000	7000	8000	9500	11000	13000	15000
Capacity, Water.....sq. ft.	1100	1800	3800	6600	7400	8200	9100	9900	11600	13200	15700	18200	21500	24800
Diameter Boiler.....in.	48	48	48	54	54	54	60	60	60	60	66	66	72	72
Diameter Stack.....in.	20	20	20	22	22	22	24	24	26	26	28	30	32	32
Minimum Height Stack.....ft.	50	50	55	55	55	60	60	60	65	65	65	70	70	70

Portable Smokeless Fire-Box

Number of Boilers.....	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322
Capacity, Steam...sq. ft.	3000	3500	4000	4500	5000	5500	6000	6500	7500	8500	10000	12000	14000	16000	18000	20000
Capacity, Water...sq. ft.	3000	3500	6600	7400	8300	9100	9900	10700	12400	14000	16500	19800	23100	26400	29700	33000
Diameter of Boiler...in.	48	48	48	54	54	54	60	60	60	60	66	66	72	72	78	78
Diameter Stack.....in.	20	20	20	22	22	22	24	24	26	26	28	30	32	32	34	34
Minimum Ht. Stack...ft.	50	55	55	55	55	60	60	60	65	65	65	70	70	70	80	90

Garbage Burners—Hot Water Heaters

Radiation ^{Standard}Types Steel Storage Tanks

plied from a central heating plant, the plan is frequently adopted of laying out the system in each building as a gravity job; providing one large trap for the entire building and discharging this trap into return mains connected to a vacuum pump. In such a system each building rather than each radiator is treated as a unit. Such a system is not, however, what is ordinarily meant by the term "vacuum" system.

In determining whether the expense of a vacuum system is justified by the conditions, the advantages to be obtained by using it must be carefully considered. The two things which make a vacuum system better than a gravity system are, first, circulation at a lower pressure; second, quick circulation when new radiation is turned on. The former is of particular importance in cases where the exhaust steam from engines is used to heat the building. The efficiency of the engine is increased as the back pressure is decreased. Therefore, the use of a vacuum system may be the means of saving considerable coal. On the other hand, the installation of a vacuum system cannot be justified from the standpoint of economy in coal consumption, if the demand for exhaust steam is so heavy that live steam must be used to make up the deficiency, even with the engine running against a back pressure.

Vacuum systems are sometimes installed where there are no engines and where the system might as well operate at 5 lbs. as at $\frac{1}{2}$ lb. back pressure. The net cost of operating such a system is necessarily greater than would be the case in a gravity system and the only advantage is a somewhat freer circulation, and the fact that the radiators will heat up promptly when the inlet valves are opened.

While the cost of thermostatic or float vacuum valves adds materially to the cost of a vacuum system installation, this increased cost is offset, to a certain extent, by the fact that smaller pipes may be used in a vacuum system than in a gravity system.

A well laid out gravity system of ordinary size should circulate freely with one pound pressure under all ordinary conditions and with not to exceed two pounds pressure in extreme cold weather, when the demand for steam and therefore the velocity of the steam in the pipes reaches a maximum. A vacuum system should not require to exceed one-half to one pound pressure under any conditions.

A gravity system may be either a "one-pipe" or a "two-pipe" system and either of these may be an "up-feed" or a "down-feed" system. Except in the case of very high buildings equally good results can be obtained with either up-feed or down-feed, but where the building is very high there is an advantage in having a down-feed system.

A vacuum system may be either up-feed or down-feed, but will always be a two-pipe or a three-pipe system. The wet vacuum system is always necessarily a two-pipe system. The dry vacuum system when used in connection with cast iron radiation is usually a two-pipe system, the vacuum pipe being a very small pipe with probably $\frac{1}{4}$ -inch branches and a main seldom larger than one inch. Where the dry vacuum system is applied to a coil system of heating in which the steam and returns are separate, the vacuum pipe will be required in addition to

the other two, thus making a three-pipe system. As previously stated, the dry vacuum system is now very seldom used.

Inasmuch as the loss of heat from buildings is by radiation and conduction from walls, windows, roof and floor, and by the air which must be replaced by fresh outdoor air for ventilation, heating formulae must necessarily involve the quantities: area of exposed wall, roof and floor, area of glass (including doors) and the cubical contents. Wind exposure and the directions of the compass must also be considered.

Loss of heat through walls, roof, and floor depend upon the construction, the thickness, and the materials used as well as the difference in temperature between outside and inside surfaces.

There are a great number of heating formulae in use and it is seldom that the results figured by these various formulae will agree. The formulae are all empirical formulae and are based on average conditions. If the conditions of any particular case vary considerably from the average, it is quite likely that none of the formulae will give correct results. To illustrate why there is often a wide variation in the amount of radiation calculated as being necessary for a certain installation, let us take the one factor of air changes. Generally speaking, we assume one air change per hour for a room. However, there may be some good reason for assuming that the windows will be open slightly or that for other reasons the room will have two air changes per hour. Obviously the required radiation for the two assumptions will be radically different.

The application of any of the formulae, after all, depends on the architect's or engineer's knowledge of the exact conditions likely to prevail and the factors which should be used for those conditions. In the last analysis, therefore, it is principally a matter of judgment on the part of the designer as to what constants are applicable.

The Chicago Steam Fitters' Association have compiled rules for computing radiating surface, published elsewhere in this volume, which will meet the average conditions quite satisfactorily.

PIPE SIZES:

One of the most common sources of error in designing a heating system is in the selection of proper pipe sizes. The cause is probably the fact that some designers fix the sizes according to tables without regard to local conditions. The size of a steam main is determined by the quantity of steam passing through it, the pressure of the steam, and the permissible friction loss. The length of the main is, of course, a factor in the latter item. Thus, it is permissible and good practice to use higher velocities in short mains than in long mains and likewise where the initial steam pressure is four or five pounds and a friction loss of two or three pounds not objectionable, much higher velocity may be used than in designing a system which is expected to circulate with steam at one pound pressure. The proper method of designing steam mains is to determine the initial pressure and the permissible friction loss and then figure the main to produce this loss at the assumed pressure.

In the design of return mains we have substantially the same conditions as in the design of the steam mains and in addition the item of allowable pitch. Where it is

Plan for Health as Well as Beauty

Incorporate the Kernerator in your plans. It promotes health by eliminating the garbage can and securing clean kitchen and yards. The


KERNERATOR *Built-in-the-Chimney*

REG. U. S. PAT. OFF.

destroys kitchen refuse, wrapping paper, paper boxes, rags, sweepings, faded flowers by burning—the sanitary, economical and labor-saving way. It disposes of tin cans, bottles, and other non-combustibles. Requires no fuel other than the dry waste that is deposited in kitchen hopper.

Built at the base of kitchen or boiler chimney when the apartment house or residence is erected and requires little extra masonry work.

Fully Guaranteed.



Drop all waste here — then forget it

H. W. Ewing, Mgr.

CHICAGO BRANCH
28 East Jackson Blvd.
Phones Wabash 8117-8

**Kerner Incinerator
Company**

OF MILWAUKEE

possible to give return mains considerable pitch they may, of course, be smaller than where they are run more nearly level.

The following table of pipe sizes is based on gravity systems, with short mains, operating at a pressure of from one to three pounds. It is a convenient reference for the conditions on which it is based, but, of course, must not be assumed to fit other conditions.

Radiation up to	One Pipe Work	Two Pipe Work
100 sq. ft.....	1½"	1 "x ¾"
200 sq. ft.....	1½"	1½"x ¾"
400 sq. ft.....	2 "	1½"x1 "
600 sq. ft.....	2½"	2 "x1 "
900 sq. ft.....	3 "	2½"x1½"
1,400 sq. ft.....	3½"	3 "x1½"
2,000 sq. ft.....	4 "	3½"x1½"
3,300 sq. ft.....	5 "	4 "x2 "
4,500 sq. ft.....	6 "	5 "x2 "
7,000 sq. ft.....	7 "	6 "x2½"
9,000 sq. ft.....	8 "	7 "x3 "
11,000 sq. ft.....	9 "	7 "x3 "
15,000 sq. ft.....	10 "	9 "x4 "
24,000 sq. ft.....	12 "	10 "x4 "

For vacuum systems the figures for "Two pipe work" may be reduced one pipe size.

HOT WATER HEATING.

In hot water heating the system may be a one-pipe or two-pipe system, or may be a gravity circulation system or a forced circulation system.

The gravity circulation system is dependent for circulation upon the fact that cold water is heavier than hot water. Therefore, the pitch of supply line should be upward from the boiler (which is the reverse of the requirement in steam heating) and the return should pitch downward toward the boiler as is the case, also, in steam heating.

In forced circulation systems which must usually be used when long horizontal runs are encountered, as is the case in factory heating, where the boiler or source of heat is in a detached power plant, a pump is used.

In one-pipe systems the radiators are connected in shunt with the supply lines, that is, the water to a radiator is taken from supply line, passes through radiator and is returned to supply line at a point further along in the direction of the travel of the water. Special fittings are sometimes employed in the diversion of the water into the radiators, especially in the case of forced circulation systems.

Two-pipe systems, especially in gravity circulation systems, may be considered to have more positive circulation.

Either one-pipe or two-pipe, gravity or forced circulation systems may be closed or open systems, though closed systems are not frequently found except in larger forced circulation systems. In either system an expansion tank must be used because of the expansion of water as its temperature rises.

The formulae which are used in estimating the amount of radiating surface required for steam heating may be used for computing the amount of radiating surface required

for hot water heating, providing a factor dependent upon the difference in temperature of the hot water and of the steam is introduced.

SIZE OF HOT WATER MAINS.

(For gravity circulation and low buildings.)

Size of Main	Area	Direct Radiation	Indirect Radiation
		Will Supply, Feet	Will Supply, Feet
1½ in.	2.03	200	135
2 in.	3.35	325	200
2½ in.	4.78	450	300
3 in.	7.38	700	450
3½ in.	9.82	900	600
4 in.	12.73	1200	800
4½ in.	15.93	1500	1000
5 in.	19.99	2000	1200
6 in.	28.88	3000	2000
7 in.	38.73	4200	2800
8 in.	50.03	5600	3600
9 in.	63.63	7000	4600
10 in.	78.83	8500	5600

In forced circulation systems it is considered good practice to so proportion mains and returns that velocity of water will not exceed 200 feet per minute.

Carpenter gives as a practical rule, applicable when main and supply do not exceed 200 feet in length, "The diameter of main supply or return pipe in a system of direct hot water heating should be one pipe-size greater than the square root of the number of square feet of radiating surface, divided by 9 for the first story, by 10 for the second story and by 11 for the third story of the building. For indirect hot water, multiply above by 1.5".

BOILERS FOR HEATING SYSTEMS.


Boilers sold for heating installations are rated by manufacturers in square feet of radiating surface, which they will supply. Comparison of boilers sold by different manufacturers discloses the fact that boilers of different makes, having the same amount of heating surface have widely different ratings, as given by the manufacturers; the difference being in some cases nearly 100 per cent.

The capacity of a boiler depends on the form and extent of the heating surface, the water and steam space and upon the amount of grate surface.

Another factor to be considered is the question of whether the boiler is to be installed in a large plant with a fireman constantly on duty and firing at regular intervals, or whether the boiler is to be used in a small installation where it is desirable to have a boiler of sufficient size to permit intermittent firing and even banking for periods of several hours while carrying the connected load.

Power boilers are usually rated at from 7½ sq. ft. to 12 sq. ft. per boiler horse power. On account of the difference in the method of firing, a heating boiler should have not less than 15 sq. ft. per rated horse power.

Imperial "Super-Smokeless" Boiler



MANUFACTURED BY

UTICA HEATER COMPANY

UTICA, NEW YORK, and 218-220 West Kinzie Street, CHICAGO, ILL.

Franklin 831-832

*Specified and Recommended by these Architects of Chicago
and Elsewhere in Illinois:*

Alfred S. Alschuler
A. H. Andrews Co.
Albert Anis
Henry J. Apfelbach
Chas. S. Archer
J. A. Armstrong
W. Scott Armstrong
Howard Arney Co.
George Awsunb
F. L. Barrett
Berlin, Swern & Randall
Edward A. Blondin
B. J. Bruns
William G. Carnegie
Frank D. Chase, Inc.
Chatten & Hammond
Childs & Smith
A. S. Coffin
Coolidge & Hodgdon
Harry L. Dalsey
Robt. S. De Golyer
F. O. De Money
N. Max Dunning
Scott C. Dyer
C. A. Eckstorm
S. Milton Eichberg
Foltz & Brand
J. T. Fortin
Arthur Foster
Fox & Fox
Roy F. France
C. E. Frazier
Fugard & Knapp
Wm. Gauger
Herman J. Gaul
Paul Gerhardt
Geo. H. Grussing
Eric E. Hall
L. G. Hallberg & Co.
C. O. Hansen
H. M. Hansen

Ralph C. Harris
C. Hatzfeld
Henschen & McLaren
J. T. Hetherington & Son
J. T. Himelblau
Carl Hoerman
Holabird & Roche
Jarvis Hunt
A. Jacobs
Percy T. Johnstone
William C. Jones
S. Scott Joy
C. W. Kallal
Geo. S. Kingsley
D. S. Klaffter
W. G. Kohfeldt
C. W. Lampe
Alex. L. Levy
Lewis & Dougherty
Sidley Lovell
Lowenberg & Lowenberg
A. G. Lund
Marshall & Fox
H. Clvde Miller
L. M. Mitchell
Moore & Dunford
Mundie & Jensen
Henry L. Newhouse
Edgar M. Newman
E. J. Ohrenstein
Paul F. Olsen
Le Roy Paddock
Wm. Pagels
Roy E. Pingrey
Pond & Pond
Postle & Fisher
Wm. H. Pruyn, Jr.
Puckey & Jenkins
Purcell & Emslie
G. W. & G. L. Rapp
Riddle & Riddle

Rissman & Hirschfeld
E. E. Roberts
David Robertson
Jean B. Rohm & Son
Ronneberg, Pierce & Hauber
L. E. Russell
Ira C. Saxe
Henry J. Schlacks
Hugo Schmidt
R. E. Schmidt, Garden &
Martin
R. G. Schmidt
A. S. Schwartz
S. M. Seator
Shattuck & Laver
Henry Sierks
R. S. Smith
Z. Erol Smith
O. P. Speyer
Maurice Spitzer
I. S. Stern
H. L. Stevens & Co.
John R. Stone
Tallmadge & Watson
A. V. Teisen
W. G. Uffendahl
O. D. Van Gunten
X. Vigeant
Weary & Alford
H. B. Wheelock
W. P. Whitney
Chester Wolcott
Waltersdorf & Bernhard
Robert Work
Worthman & Steinbach
Joseph Zidek
Illinois
Geo. Morris, Elgin
J. F. Richardson, Ottawa
Jas. M. White, Urbana
R. A. Young, Pontiac

Roughly 100 sq. ft. of radiation requires one boiler horse power.

SIZES OF CHIMNEYS:

The size and height of chimneys will depend on the kind and amount of coal burned; the kind of grate; the type of boiler and also on the location of the chimney relative to surrounding buildings. The latter is of great importance. A chimney which would be of sufficient height out in the country, where it extended above all surrounding buildings, might be totally inadequate in a city where it would be "blanketed" by high adjoining buildings.

In general, however, assuming a short straight breeching; a chimney smooth on the inside, reasonably tight and extending above surrounding buildings; and a good grade of bituminous coal used as fuel, the following sizes will be found ample:

Sq. Feet of Direct Steam Radiation	Horse Power	Size of Chimney	Sq. Feet of Direct Water Radiation
250	2.5	8"x 8"x25'	400
500	5.0	8"x12"x30'	850
800	8.0	12"x12"x35'	1350
1400	14.0	12"x16"x40'	2400
2200	22.0	16"x16"x50'	3700
3500	35.0	18"x18"x60'	5900
5500	55.0	20"x20"x70'	9300
8000	80.0	24"x24"x80'	13000

HOT AIR HEATING

In this classification is generally included the hot air furnace, the hot blast system and indirect steam radiation. The direct-indirect radiation might be included either under this head or under piping and radiator systems.

The hot air furnace is the simplest and usually the most effective of all the various heating systems, but its application is limited to buildings which do not require long horizontal ducts. It is well adapted to small one or two-story residences which do not cover much ground area and in which the furnace can be located in the center of the basement. The hot air furnace has the advantage of low first cost; is efficient in operation, and if properly operated provides better ventilation than either a steam or hot water system. The heating system is in operation almost from the moment a fire is started in the furnace. As soon as the air surrounding the fire pot becomes heated it starts to circulate. A hotter fire increases both the temperature and the volume of the circulating air. This system is, therefore, well adapted for wide ranges of outdoor temperature.

The principal disadvantages of the hot air furnace are the dust and dirt which are carried into the rooms, and the difficulty which is frequently found of maintaining a uniform temperature throughout a building, especially on windy days. Hot air furnaces are seldom air tight and as a result the gas from the combustion chamber as well as dust and dirt enter the air space around the fire pot and are carried up into the rooms through the ducts. The difficulty of maintaining uniform temperatures can be greatly reduced if the system is well designed, particularly with reference to exposure and prevailing winds.

A further objection to the hot air furnace is the fact that the air for heating passes over the surfaces which are heated directly by the flames and which at times may become almost red hot. Dust particles carried in the air are burned as they come in contact with the hot iron surfaces. This produces an offensive fine dust ash, which not only is very noticeable by its odor, but which irritates the nasal membranes.

Hot air furnaces should always be provided with a fresh air supply duct leading outdoors and a recirculating air duct leading to a hallway or other part of the building to which the various rooms connect. Both ducts should have control dampers so that the proportion of fresh outside air and of recirculated air may be regulated, as required by the number of occupants in the building.

Furnaces should also be equipped with water pans in the heated air compartment, to maintain proper humidity. These pans are sometimes placed near the bottom of the air chamber and are consequently surrounded by the cold air, making them very much less effective.

Warm Air Furnace Heating Plant Design follows the same rules in the method of computing its requirements as are heretofore set forth in connection with the discussion on steam and hot water heating.

A simple rule for computing sizes of hot air ducts for furnace systems is as follows: Determine the square feet of radiation that would be required if the room were to be heated by direct steam radiation; multiply this figure by the factors E and F determined from the following tables. The result will be the square inches of area of a round duct required to heat the room. This size may have to be increased or decreased slightly for special conditions:


Let **E** equal factors for exposure, the following table gives approximately correct estimates of proper values for **E**:

North exposure	E=1.4
East "	E=1.
N. E. "	E=1.2
South "	E=1.
S. E. "	E=1.
West "	E=1.4
S. W. "	E=1.2
N. W. "	E=1.4

Let **F** equal factor for story location in the case of the gravity system only, then for:


First story	F=1.4
Second "	F=1.2
Third "	F=1.0

Inasmuch as the system is operated by discharging air into a room, it follows that a nearly equal amount of air has to be taken from the room. There will be some leakage, and as the air leaving the room is cooler there will be less cubic feet of air leaving the room than entering. Where it is probable that a room will be closed off most of the time, a return duct should be installed connecting either to the basement or to that part of the building where the recirculating register is located. In short, circulation is essential to satisfactory operation and some provision must be made to secure this circulation.



Heating *and* Ventilation

Save Your Clients Money



Mechanical Hot Blast Heater

First cost is from 50 to 75 per cent lower than any other system of factory heating. Operation and maintenance are proportionately lower. Armour Institute test gives this heater twice the overall efficiency of steam.

File the Gordon Catalog


The new Robert Gordon, Inc., Catalog No 3 should be in your file for ready reference. It is filled with facts and figures pertinent to efficient, money-saving heating and ventilating installations.

A post card brings it.

When the old pocket-book is roaring and your client demands economy, read *Which Heating System and Why*.

Plain facts; plain English. Worth reading. Free to Architects and Engineers.

Write for copy—now!



Gordon Steam Unit Heater

Highest possible radiating efficiency. Occupies but a small space and can be moved anywhere.

ROBERT GORDON, Inc.

620 West Monroe Street

Chicago, Illinois

BLAST SYSTEMS:

Blast systems of heating are essentially the same as simple furnace systems except that the air is moved by a fan. The system is, therefore, much more positive. The air may be heated either directly in a furnace or by being blown or drawn over radiating surfaces heated by steam or hot water. Systems in which the air is heated by radiating surfaces heated by steam are by far the most common.

The size of the ducts is governed by the amount of friction loss permissible and, therefore, by the velocity of the air and the length of duct. Duct velocities vary over a wide range from 300 ft. to 1,500 ft. per minute. Where the power required to operate the fan is of minor importance, as for example, where the fan is driven by an engine which exhausts into the heating coils, high velocities are permissible. These may range from 600 ft. per minute in small ducts to 1,500 ft. per minute in large ducts. On the other hand, where the cost of power to drive the fan is important, it may be more economical to install larger ducts designed for velocities of from 300 ft. in small ducts to 1,000 ft. or 1,200 ft. as a maximum, in large ducts. Register velocities up to 600 ft. per minute are permissible where the register is located near the ceiling. Velocities above 600 ft. are likely to produce objectionable noise. Where the register is located near the floor, velocities as low as 150 ft. to 250 ft. per minute may be necessary in order to avoid objectionable drafts.

The velocity through exhaust registers even though located at the floor, may usually be as high as 400 ft. to 500 ft. per minute, and sometimes, depending on the location, as high as 600 ft. per minute.

The term "indirect heating" is usually applied to the system in which steam or hot water radiation is installed in a compartment or chamber under the floor and outside air permitted to pass over this radiation and into the room to be heated through duct and register. It is, therefore, very similar to the hot air furnace heated by steam or hot water is used instead of radiating surface heated directly by the flames.

The so-called "direct-indirect" system has the radiators in the room to be heated, connected with the outdoor air so that the air passing over the radiator is a mixture of fresh outdoor air and air circulating in the room.

Both of these systems have the advantage that they introduce some fresh air and to that extent are desirable from a ventilation standpoint. However, they meet the situation only part way, because the amount of air supplied to the room is usually determined by the outside temperatures rather than by the ventilation needs of the room.

HEATING BY ELECTRICITY.

Heating by electricity is entirely feasible and practical where the cost of electric cur-

rent is very low. At the ordinary prevailing rates, however, the cost is prohibitive. The reason for this is that where electricity is generated in a steam plant using simple engines, only about 4% of the B. T. U. in the steam is delivered to the switchboard in the form of electrical energy. In stations where the highest type of generating apparatus is used, this percentage may be increased to 20%.

While the large power boiler is more economical in the production of steam than the small heating boiler, the fact that only 4% to 20% of the steam generated by the large power boiler is available as electrical energy makes the cost of this form of heating prohibitive.

TABLE OF EQUIVALENT TEMPERATURE FOR TESTING A HEATING PLANT AT DIFFERENT OUTSIDE TEMPERATURES.

For the purpose of indicating the efficiency of the apparatus for any specified condition, Prof. Carpenter gives the following table, which has been generally accepted as the standard test.

For steam, the radiator temperature in all cases is assumed to be that due to a pressure of 3 pounds at the boiler, or about 220° Fahr.

For water, the radiator temperature is assumed in all cases to be at an average of 160° Fahr.


For a plant proportioned sufficiently to maintain a temperature of 70° when the outside temperature is at zero.

Temperature of Outside Air	Room should be raised to
—10	64.7
0	70.0
10	75.1
20	81.0
30	86.5
40	93.1
50	98.7
60	104.7
70	110.5
80	117.1
90	123.5
100	130.3

See University of Illinois Engineering Experiment Station Bulletin No. 31 for methods and results of tests on house heating apparatus. These tests have been made on different kinds of house heating apparatus with different kinds of fuel. The bulletin embodies the results of about three hundred tests. These bulletins are for free distribution.

VENTILATION.

The term ventilation, when used in the ordinary sense is a purely relative term. Every room or building, unless it is her-



*Adaptable to any
Furnace—Steam,
Hot Water or
Hot Air*

*Protected by
Doble-Detroit Patents*

NOKOL

Automatic Oil Heating for Homes

5,137 Nokol heaters had been installed on September First, 1921. Nokol has been in successful operation for four years, in every type of heating plant. Nokol is a perfected, thoroughly established, trouble-free, automatic mechanism.

Nokol installation requires no alteration in any type of heating plant. The Nokol burner simply takes the place of the grate bars.

Complete combustion takes place in the Nokol burner—the combustion chamber where atomized kerosene or distillate (Nokol fuel) and air are combined at a high temperature until the carbon in the oil and the oxygen in the air combine.

Oil is delivered to the burner by the suction of air blown from the fan. This blower is electrically driven and controlled by the thermostat, which starts the blower when the temperature falls below the desired point and stops it when the temperature rises above that point.

Nokol is safe. There is safety control of both oil and electricity and pilot light. Nokol is approved by the Underwriters' Laboratories of the National Board of Fire Underwriters, and is rated as non-hazardous.

Send for complete data and specifications.

THE STEAM CORPORATION

Division of the Amalgamated Machinery Corporation

215 N. Michigan Ave.

CHICAGO

Nokol is on the Fire Underwriters' List of Approved Appliances

metically sealed is "ventilated" to a certain extent. A room heated with steam or hot water direct radiation and with all the windows and doors closed is ventilated by the amount of air leakage, due to the fact that neither the doors nor windows nor even the walls are air tight and there is a constant tendency for the interchange of air from the outside to the inside of the building. With the indirect system of heating, fresh air from the outside is introduced at a definite point and by means of a system entirely under control at all times.

The ducts supplying the air to the indirect radiation are usually provided with dampers, so that the amount of fresh air can be absolutely regulated. From the standpoint of ventilation, indirect radiation is far superior to direct radiation, but on account of the very much greater cost of operation, the amount of indirect radiation is usually restricted to one or two stacks in the ordinary residence.

In laying out any system of ventilation it is necessary to decide first of all on the standard of purity to be maintained. Pure country air contains about four parts of CO₂ in 10,000. This amount of CO₂ can be increased to 6, 8 and even 10 parts without any bad results to the occupants of the room. Naturally there is no sharp, well defined line above which ventilation is totally bad or below which the ventilation may be referred to as absolutely good. As a general proposition, it may be said, however, that a system of ventilation which permits the CO₂ to rise above 12 parts in 10,000 is not a good modern ventilating system, while on the other hand, for commercial reasons, it is seldom that an attempt to keep the air purer than 6 parts of CO₂ in 10,000 is made.

It should be clearly understood that the mere presence of CO₂ in such quantities as 12 parts in 10,000 is not in itself harmful. An artificial mixture of fresh country air and sufficient CO₂ to bring the total up to 12 parts of CO₂ in 10,000 would not be in the least injurious. On the other hand, when the air in a room is re-breathed until the CO₂ content reaches 12 parts of CO₂ in 10,000 then that air will contain enough harmful impurities thrown off by the lungs to make it offensive and impure.

The CO₂ content then is an indicator of the purity of the air only when this CO₂ has been thrown off in the breath of persons or animals. In that case, however, it indicates not only the relative purity of the air, but also the air movement or air change at that particular point.

In calculating the probable impurities, it may be assumed that the ordinary person in average good health, exhales 0.6 of a cubic foot of CO₂ per hour and a "5-foot" gas burner vitiates about five times as much air as the ordinary person. A gas grate or any open fire-place, on the other hand, has a tendency to improve the ventilation; for while it uses up oxygen, it must be kept in mind that all the gases which pass up the chimney, must in the natural course of events be replaced by fresh air through the doors and windows.

As incandescent electric lights use up no oxygen, they have no effect on the ventilation of a room. In hospitals the amount of fresh air required for occupants is naturally

much greater than in buildings occupied by persons in good health. The amount of fresh air per occupant must be doubled and some times trebled to maintain the required standard of purity.

The Chicago Commission on Ventilation in their report for 1914, says:

"However satisfactory the quantity of air furnished for the ventilation of a room, and however satisfactory may be the means employed for properly distributing it, both of which in the long run are very important, nevertheless the human body makes an immediate demand which may overshadow either or both. IMMEDIATE PHYSICAL COMFORT IS THE STANDARD OF THE HUMAN BODY, whatever the consequences, as exemplified either in the drowsy stupor that descends on one immersed in a hot, stifling atmosphere on a cold wintry night, or in the quiet repose that comes from a balmy summer breeze outdoors. Good ventilation shall produce immediate comfort.

One of the most prominent as well as immediate factors in the production of comfort, is temperature. * * *

The comfort of the human body is largely influenced by the temperature of the surrounding air, and also, and at the same time, by the rate at which perspiration may evaporate into the air from the body. Relative humidity influences the rate at which such evaporation occurs, but it is only in recent years that much consideration has been given to atmospheric humidity in relation to temperature and comfort."

TEMPERATURE AND HUMIDITY IN RELATION TO COMFORT.

"It has become traditional in this country that the best temperature to maintain in a room is 68 to 70 degrees. There are, however, some who urge that these temperatures are too high, and they cite the English practice of 59 to 62 degrees as evidence of their claim. The difficulty with both these positions is that in deciding on the best temperature, proper consideration is not given to relative humidity. Any adult knows that sultry days are much less comfortable than days of even higher temperature when the atmosphere is comparatively dry. This well-known fact of outdoor experience must be taken into account, especially since it is now recognized that in cold weather we need to humidify air indoors. On this point of humidity, it may be said that the human organism seems to be adapted to a large range of relative humidity, but it is not accustomed to abrupt changes such as one might experience on a cold day in passing from the outdoors into a heated room. In a word, it seems important from the standpoint of health and comfort to maintain a fair degree of correspondence between the relative humidity of outdoors and indoors."

"Any system of ventilation to be practicable, must produce a feeling of comfort, and therefore both the temperature and the relative humidity of the air are important in ventilation. Temperature and relative humidity jointly help determine comfort."

"It has generally been considered that a temperature of from 68 to 70 degrees with a relative humidity of 70 percent, is a most desirable condition to obtain (the 70 percent relative humidity also is largely traditional).


The STABILITY of Dunham Standards

The experimenting, which determined the principle of the Dunham Radiator Trap, ended twenty years ago. Refinements in its appearance have, of course, been made since it was placed on the market, but improvements here and there have only accentuated the ideal principle on which it operates.

The basic principle of the Dunham Radiator Trap is one involving the laws of thermodynamics. The permanency of this principle makes unnecessary any juggling with the purely mechanical side of the trap.

Permanency in mechanical construction is vital also. The best proof we know of is that furnished by eighteen-year-old Dunham Traps operating today with promise of keeping at it indefinitely. Much of that can be credited to the honest craftsmanship of eighteen years ago—and to this standard we adhere today, in what is said to be one of the finest industrial plants west of the Mississippi.

In using Dunham Radiator Traps and other Dunham products, you place your confidence in standards that have matured, that will never be sacrificed to commercial expedencies.



The Two Part Dunham Radiator Trap

It is distinctive in the simplicity of its construction. It consists of two major parts, a body, and a cover. In the cover the operating member, the Dunham Thermostatic Disc, is securely placed. It has an exceptionally large valve opening. There are no

loose parts in the path of flow, no sliding contacts, nothing to gum up, and no guide or pin to obstruct the valve opening. The position and design of the valve is such that it is self-cleaning. The action of the disc is positive and the valve seats squarely, like a globe valve, the tightest of all types of valves. All of its working parts are made of non-corrosive material of the best quality.

Dunham Specialties

**Packless Radiator Valves
Radiator Traps
Drip Traps
Blast Traps
Air Line Valves
Vacuum Pump Governors
Reducing Pressure Valves
Oil Separators
Suction Strainers
Air Vents
Return Traps
Check Dampers
Damper Regulators**

***The* DUNHAM**
REG. TRADE-MARK
HEATING SERVICE

Full details of the Dunham Trap, and twelve other Dunham specialties, will be sent on request

C. A. DUNHAM COMPANY, 230 East Ohio Street, CHICAGO

Factories: Marshalltown, Iowa, Toronto, Canada

52 Branch and Local Sales Offices in the United States and Canada

London: 223-A Regent Street, W. 1

Paris: 64 Rue du Rocher

Distributors: Munzing & Co., 47 Rue de la Fontaine-au-Roi

In our tests it was assumed that the best temperature may or may not be 68 to 70 degrees; and also the most satisfactory relative humidity may or may not be 70 percent."

Ventilating systems may be divided into gravity and mechanical systems. Air can be moved into and from a room only by some form of power expenditure. When air is warmed, approximately one-third of the heat imparted to it is expended in work of expanding the air and is, in part at least, available for ventilating purposes.

In a gravity ventilating system, the working pressure is due to the difference in weight between the air inside and the air outside of the building or duct. This working pressure is much smaller than the pressures ordinarily used in a fan or mechanical ventilation system.

If the working pressure in a gravity ventilation system is small, the supply and discharge ducts must be made proportionately larger. The cross sectional area of these ducts is governed by the temperature of the air in the supply ducts and the highest outside temperature for which the vent ducts are provided. The cross sectional areas also are modified by the straightness and smoothness of ducts, the height of ducts and numerous other local conditions.

With indirect systems of heating, fresh air from the outside is introduced at definite points where indirect radiation is installed. The ducts supplying the air to the indirect radiation must be provided with dampers so that the amount of fresh air can be regulated. If they were not provided with dampers, the amount of air supplied in cold weather would be excessive and the cost of heating, therefore, would be too great.

The so-called mechanical ventilation systems are superior to gravity ventilation systems in that they require relatively small space for ducts and in the uniformity of ventilation secured, as they are independent of temperature or weather conditions.

The fan system of heating and ventilating is desirable from the ventilating standpoint to just the extent that fresh air is drawn from the outside. It should be understood that it is possible to operate a fan system, drawing the entire supply from the inside of the building. In this case, even though there is a movement of air, the ventilation is no better than with the ordinary direct radiation system.

Systems have been installed in which all the air is recirculated but passed through an air washer before being again delivered to the rooms. The theory is, that washing the air removes its objectionable qualities. There is a decided difference of opinion as to the

merits of this system. At this time there is insufficient data at hand to either prove or disprove the claims made.

If all the air is taken from the outside, the combined heating and ventilating system will provide the very best of ventilation. In practice, for purposes of economy, fan systems are usually designed to take most of the air from the outside, but a by-pass is provided so that in extreme cold weather, part of the air can be drawn from the inside of the building.

Quite frequently a combination of a direct heating system and a fan ventilation system is used. In such cases the heating system is usually designed to supply the heat lost by radiation through walls, roof, floor and windows. The fan ventilating system is designed to supply sufficient air to maintain a predetermined standard of purity and is then provided with just sufficient radiation to heat this air to the room temperature.

AIR WASHERS:

The use of air washers in connection with fan ventilating systems, is almost always desirable and in most cases absolutely necessary, in order to assure a supply of clean, pure air.

All air washers consist primarily of a spray chamber in which the air is made to pass through a fine spray of water, and an eliminator or separator in which the water is separated from the air.

The movement of air, containing particles of dust and dirt, through a system of ducts is bound to cause a deposit of part of the impurities on the walls of the ducts. As it is next to impossible to clean the average ventilating duct, this, in time, becomes so dirty that no matter how clean the air leaving the fan, some dirt will be carried into the room through the fresh air registers. From this, it is evident that even though air washers do not remove all of the dust in the air, the use of an air washer improves a ventilating system by just the amount of dirt that the washer removes.

It should also be noted that air washers present a convenient means of increasing the humidity of the air.

BOILER AND PIPE COVERINGS.


Experiments under actual steam plant conditions, conducted by Geo. M. Brill (Trans. Am. Soc. Eng. Vol. XVI) show that in ordinary practice the early results and theories, advanced by Sir Isaac Newton and Peclet, are too low. He found that by using an 8 inch bare steam pipe 60 feet long with an average pressure of 110.5 lbs. by gauge, and with air 75.5 degrees Fahrenheit, that 736.546 B. T. U. per square foot of surface per hour, were lost. These results accord so closely

The New York Blower Company

Main Office
CHICAGO, ILL.


Factory
LAPORTE, IND.

Branch Offices
IN PRINCIPAL CITIES




Single Width Seri-Vane Fan

We show on either side our Type "C" SERI-VANE FANS of the reversible type made in all sizes to and including No. 6, wheel diameter 36 inches. Larger sizes are made in any hand and discharge desired. These fans have unusually large capacities and are well known for their quiet running, economy in operation, durability and performance. Write for catalog No. 70 for full description.




Double Width Double Inlet Seri-Vane Fan

Cut on the right pictures our Standard Type "D" PEERLESS AIR WASHER. We make these for all capacities. Standard washers are constructed throughout of high quality galvanized steel sheets, but special washers are commonly furnished of copper, ingot or toncan iron, etc. Washer can be fitted with complete humidity regulation at a small increase in price. Special bulletin describes our washers fully.



Peerless Air Washer

Below is shown our newest mushroom ventilator with the famous friction grip steel stud. Some of the latest ideas are embodied in this ventilator. It has only two parts and no loose bolts or nuts. Simplicity of design and ease of adjustment are two of its attractive features. Get our descriptive circular.



Peerless Blower

Our PEERLESS BLOWER pictured to the left is very useful for pulley driven or direct connected blowers whenever small quantities of air are needed at either low or moderately high pressures. Extensively used for exhausting air from kitchens, die vats, toilet rooms, restaurants and foundries.



Mushroom Ventilator

with the experiments conducted by Prof. R. C. Carpenter of Cornell University, and Prof. M. E. Cooley of the University of Michigan, that it seems fair to use these results as a premise of calculation in practical work. The magnitude of the loss from a bare pipe can be understood possibly more closely by the following calculation:

Adopt from Mr. Brill's results a loss of 736.546 B. T. U. per square foot of surface per hour and, assuming an 8-inch pipe to be 100 feet long, the loss would then be as follows:

736.546 B. T. U. multiplied by 225 square feet (surface of an 8-inch pipe 100 feet

long) equals 165722 B. T. U. lost per hour or, divided by 30,000 B. T. U., heat units in one horse-power at above pressure (assuming 34½ lbs. of water from and at 212 degrees to be a horse-power) equals 5.5 horse-power per hour lost. The method adopted for preventing in a measure this loss is by the application of some non-conducting material to the radiant body, having for its object the protection of the external surfaces from loss of heat and from any injurious action liable to occur in consequence of their exposure. It will therefore be seen that a great economy is effected by the application of pipe covering or boiler lagging.

BOILER EFFICIENCY TABLE

Based on evaporation from and at 212° F.

B. T. U. Per Lb. Coal.	50% Efficiency		55% Efficiency		60% Efficiency		65% Efficiency		70% Efficiency		75% Efficiency		80% Efficiency	
	Evaporation Per Lb. Coal.	Lbs. Coal Per H. P. Hour.	Evaporation Per Lb. Coal.	Lbs. Coal Per H. P. Hour.	Evaporation Per Lb. Coal.	Lbs. Coal Per H. P. Hour.	Evaporation Per Lb. Coal.	Lbs. Coal Per H. P. Hour.	Evaporation Per Lb. Coal.	Lbs. Coal Per H. P. Hour.	Evaporation Per Lb. Coal.	Lbs. Coal Per H. P. Hour.	Evaporation Per Lb. Coal.	Lbs. Coal Per H. P. Hour.
7500	3.8	9.0	4.2	8.2	4.6	7.5	5.0	6.8	5.4	6.4	5.8	6.0	6.2	5.5
8000	4.1	8.4	4.5	7.6	4.9	7.0	5.3	6.5	5.7	6.0	6.2	5.5	6.6	5.2
8500	4.4	7.8	4.8	7.1	5.2	6.6	5.7	6.0	6.1	5.6	6.6	5.2	7.0	4.9
9000	4.6	7.5	5.1	6.7	5.5	6.2	6.1	5.5	6.5	5.3	6.9	5.0	7.4	4.6
9500	4.9	7.0	5.4	6.3	5.9	5.8	6.3	5.4	6.8	5.0	7.3	4.7	7.8	4.4
10000	5.1	6.7	5.6	6.1	6.2	5.5	6.7	5.1	7.2	4.7	7.7	4.4	8.2	4.2
10500	5.4	6.3	5.9	5.8	6.5	5.3	7.1	4.8	7.6	4.5	8.1	4.2	8.6	4.0
11000	5.6	6.1	6.2	5.5	6.8	5.0	7.4	4.6	7.9	4.3	8.5	4.0	9.1	3.7
11500	5.9	5.8	6.5	5.3	7.1	4.8	7.7	4.4	8.3	4.1	8.9	3.8	9.5	3.6
12000	6.2	5.5	6.8	5.0	7.4	4.6	8.0	4.3	8.6	4.0	9.3	3.7	9.9	3.4
12500	6.4	5.3	7.1	4.8	7.7	4.4	8.4	4.1	9.0	3.8	9.7	3.5	10.3	3.3
13000	6.7	5.1	7.4	4.6	8.0	4.3	8.7	3.9	9.4	3.6	10.0	3.4	10.7	3.2
13500	6.9	5.0	7.6	4.5	8.3	4.1	9.0	3.8	9.7	3.5	10.4	3.3	11.1	3.1
14000	7.2	4.7	7.9	4.3	8.6	4.0	9.4	3.6	10.1	3.4	10.8	3.2	11.5	3.0
14500	7.5	4.6	8.2	4.2	9.0	3.8	9.7	3.5	10.5	3.2	11.2	3.0	12.0	2.8



THE DRAKE HOTEL
The Country's Most Luxurious Hostelry

Typical of the class of buildings in the city of Chicago using SIROCCO equipment throughout and a few others that we might mention: The Wrigley Bldg., The Northwestern Depot, Federal Reserve Bank, The Field Museum, Sears-Roebuck Ad. Bldg., The Tivoli Theatre


AMERICAN BLOWER CO., Marquette Bldg., CHICAGO

The PEERLESS single grate smokeless boiler is constructed so that the fire goes toward the crown sheet instead of from it (see cut). All PEERLESS sectional boilers have "S" water tubes in the fire pot.

*Phone Wentworth 1920
for catalog*


Weir & Craig Company
PLUMBING & HEATING SUPPLIES

6316 Wentworth Avenue
CHICAGO, ILLINOIS



TWO-PIPE NON-SHORT CIRCUIT HOT WATER HEATING SYSTEM

HOMER R. LINN, Mechanical Engineer, Member American Society Heating and Ventilating Engineers



Gravity hot water heating systems may be divided into two general heads, viz.: Short circuit systems and non-short circuit systems. These may be subdivided into up feed, feed, down feed, etc.

In the non-short circuit system the flow return mains run parallel, grade up away from the boiler and are of corresponding sizes where any radiator is taken off. The first radiator taken off of the flow main is also the first radiator on the return main. We, therefore, have the greatest push or pressure on the flow main and the greatest pull on the return main at this point. The result is that the tendency of all of the hot water is to go through this radiator, while the one on the farther end of the main has less pressure and therefore is sluggish. Various means are resorted to in overcoming this air, such as putting lead washers in the valve unions, taking flow connection off of the side of the main, etc. Any of these are uncertain and often cause trouble which is hard to locate.

In the non-short circuited system the flow main grades up away from the boiler. Where the connection to the first radiator is taken off of the flow main, the connection from the return of this radiator is brought into the end of the return main. In other words, this is the smallest diameter of the return main. It will be seen that we have here the greatest push on the flow main and the least pull on the return main. At this point both mains should be on the same level, but from here on the return main should grade down one-half inch in ten feet, while the flow main should continue to grade up one-half inch in ten feet. The last radiator taken off of the flow main will be the nearest radiator to the boiler on the return main: Therefore, at this point we have the least push in the flow main but the greatest pull in the return main.

Thus it will be seen we have no short circuits, but a balanced condition throughout. The accompanying sketch illustrates how the proper sizes of valves and pipes may be selected from the table. It also shows the best method of making connections to the flow main and also to the return main.

Unless boilers are furnished with integral metal insulating jackets, they should be well covered with a plastic covering having an air space between the boiler and the covering. All mains, branches and risers should be covered with a good grade of moulded covering. The expansion tank pipe may be taken off from either the flow or the return main, whichever is most convenient.

GRAVITY HOT WATER HEATING.

Sizes of mains for basement two-pipe non-short circuit system where mains are not over 100 feet long.

1 1/4" pipe,	0 sq. ft. to 100 sq. ft.
1 1/2" pipe,	101 sq. ft. to 250 sq. ft.
2" pipe,	251 sq. ft. to 400 sq. ft.
2 1/2" pipe,	401 sq. ft. to 650 sq. ft.
3" pipe,	651 sq. ft. to 1000 sq. ft.
3 1/2" pipe,	1001 sq. ft. to 1900 sq. ft.
4" pipe,	1901 sq. ft. to 2500 sq. ft.
4 1/2" pipe,	2501 sq. ft. to 3100 sq. ft.
5" pipe,	3101 sq. ft. to 4000 sq. ft.
6" pipe,	4001 sq. ft. to 5600 sq. ft.

Sizes of Risers.

3/4" pipe,	0 sq. ft. to 40 sq. ft.
1" pipe,	45 sq. ft. to 65 sq. ft.
1 1/4" pipe,	70 sq. ft. to 100 sq. ft.
1 1/2" pipe,	105 sq. ft. to 175 sq. ft.

Sizes of Valves.

1/2" valve,	0 sq. ft. to 40 sq. ft.
3/4" valve,	45 sq. ft. to 75 sq. ft.
1" valve,	80 sq. ft. to 100 sq. ft.
1 1/4" valve,	105 sq. ft. to 125 sq. ft.
1 1/2" valve,	130 sq. ft. to 175 sq. ft.

Humphrey Heater

Chicago, Ill., June 15, 1921.

Humphrey Company Div., Kalamazoo, Mich.:

Gentlemen: Your inquiry of May 12th with reference to the Humphrey Water Heater which I have in my home has just come to hand again, it having become mislaid on my desk since that time.

As to the part the Humphrey plays in my home, I might in passing state that I am somewhat of a faddist with reference to anything of a mechanical nature which promotes comfort in the home and have, therefore, provided myself with most all the modern equipment, such as washing machines, mangles, Nokoi heating apparatus and many other small conveniences too numerous to mention. However, I would part with one and all of them before I would give up the Humphrey, which I designate as the Janitor of my home, because it is always on the job with hot water any time of the day or night and in any quantity you need. It has stood in my basement for years without any care whatever and is operating just as good today as when I bought it.

Will be glad to co-operate with you in every way possible.

Yours very truly,

C. E. CARQUEVILLE.

When you include the Humphrey Automatic Gas Water Heater in your home plans, you are providing just this sort of Hot Water Service in every instance.


HUMPHREY COMPANY

Div. Ruud Mfg. Co.

KALAMAZOO

MICHIGAN

Chicago Store: 204 S. Wabash Ave.



GENUINE JENKINS VALVES

In a specification, means the highest standard
of valve construction and service


Specifications reading "Jenkins
Disc" Valves may be interpreted
to mean any valve with com-
position disc. All *Genuine*
Jenkins Valves have this
trade-mark



Angle, Male Union
Fig. 168



Jenkins Bros.



Right Hand, with Male
Union, Fig. 180

JENKINS BROS.

646 WASHINGTON BLVD.

CHICAGO, ILL.

CHICAGO MASTER STEAM FITTERS' ASSOCIATION STANDARDS

For Computing Boiler Sizes and Radiation Quantities for Buildings of Average Construction.

RULE FOR COMPUTING RADIATOR QUANTITIES FOR HEATING PLANTS.

The following are rules compiled and recommended by the Chicago Masters Steam Fitters' Association. However, they should not control against the best judgment of the competent designing engineer.

Schedule for computing minimum quantities of steam radiation at 70° F. with outside temperature at minus 10° F.

1 foot of radiation for every 300 cubic feet of contents, plus

1 foot of radiation for every 15 square feet net exposed wall surface, plus

1 foot of radiation for every 2 square feet of single glass surface, plus

1 foot of radiation for every 4 square feet of double skylight.

For all rooms with plastered ceilings and unheated air space between ceiling and the roof, add 1 foot of radiation for every 30 square feet of ceiling area.

For all rooms with ceiling plastered on roof joist add 1 foot of radiation for every 20 square feet of ceiling area.

For all rooms with open joist roof construction add 1 foot of radiation for every 10 square feet of roof.

For all rooms having concrete roof add 1 foot of radiation for every 6 square feet of roof.

For all floors except wood construction having no basement or air space, 1 foot of radiation for every 30 square feet of floor area.

All bath rooms in living abodes to be heated to 80°.

For all rooms with northeast or northwest exposures add 10 per cent additional radiation.

Where radiators are placed under seats or behind grills add 20 per cent additional radiation.

Where radiators are placed in open recesses add 10 per cent additional radiation.

For indirect radiation without fan system add 50 per cent additional radiation.

For direct-indirect without fan system add 25 per cent additional radiation.

Where single pipe coils or single cast-iron wall radiation is placed on side walls 80 per cent of the required amount of standard column radiation may be installed. Size of boiler and piping, however, shall be based on standard column radiation requirements. Ceiling coils to be considered as standard column radiation.

In measuring glass surface the full opening in wall shall be figured. Outside door openings shall be taken as glass.

For computing minimum quantities of hot water radiation at 70° F. with outside temperature at minus 10° F., add 60 per cent to amount necessary for steam.

For computing minimum quantities for vapor systems at 70° F. with outside temperature at minus 10° F., add 20 per cent to amount necessary for steam.

A vapor system is defined as a two-pipe steam system which has the return lines open to atmosphere with no valve at the return connections of heating units which will close against steam.

For heating to temperatures other than minus 10° F. to 70° F. multiply actual amount of radiation required by the following coefficients:

-10° to 80°...1.13	-10° to 55°... .81
-10° to 75°...1.06	-10° to 50°... .75
-10° to 70°... .1	-10° to 45°... .69
-10° to 65°... .94	-10° to 40°... .62
-10° to 60°... .87	

RULE FOR COMPUTING BOILER SIZES FOR DIRECT RADIATION

Schedule for computing minimum sizes of boilers for the average building based on ap-

proved ratings specified in the manufacturer's catalogue.

Steel tubular or steel water tube boilers 100 sq. ft. per horse power (A. S. M. E. code).

In computing boiler sizes for buildings heated to lower than -10° to 70° F. multiply the amount of cast iron column radiation necessary to maintain the required temperature by the following co-efficient before adding the percentage given in rule for computing boiler sizes.

	Steam.	Water.
-10° to 65°.....	1.03	1.05
-10° to 60°.....	1.07	1.09
-10° to 55°.....	1.10	1.13
-10° to 50°.....	1.13	1.18
-10° to 45°.....	1.17	1.24
-10° to 40°.....	1.20	1.27

RULE FOR COMPUTING BOILER SIZE FOR DIRECT-INDIRECT AND INDIRECT RADIATION

For computing boiler size for direct-indirect and indirect radiation, reduce same to basis of direct by adding 25 per cent to direct-indirect and 50 per cent to indirect, then use factor of safety as called for on direct radiation.

RULE FOR COMPUTING BOILER SIZES FOR HOT BLAST COILS

For computing boiler size to be used for Hot Blast Coils use manufacturers' condensation charts, and figure ¼ lb. of condensation per hour as equivalent to 1 square foot of direct radiation and add following factor of safety:

Fire-box, up-draft	10%
Fire-box, down-draft	15%
Portable	15%
Cast-iron, down-draft.....	25%
Magazine	25%
Cast-iron, up-draft	40%

Where coils are to be inserted in boiler or steam coils in hot water tank for heating water for domestic purposes, size of boiler should be increased, figuring each gallon of water tank capacity as equivalent to 2 sq. ft. of radiation. For example, a 160-gallon tank should be figured as equivalent to 320 sq. ft. of radiation plus factor of safety as indicated on boiler chart showing factors of safety.

The above schedules of quantities are commensurate with good heating results for the average building of average construction, but by no means to be construed as guarantees of the proper quantities of radiation or boiler sizes necessary to heat every building, as extraordinary conditions will of course require additional radiation or boiler capacity.

It is recommended in all installations of steam boilers that drain valves be placed on the returns and that the condensation from such returns be discharged into the sewer for a period of from three days to one week after starting fire, thereby clearing system of grease and dirt. At the end of this period boiler should be thoroughly washed and blown out.

EXAMPLE

Find size of steel down-shaft brick set boilers required for the following installation (Key No. 7, Boiler Chart):

- (1) 500 sq. ft. of direct cast iron column radiation in rooms to be heated from -10° to 70°.
- (2) 500 sq. ft. of direct cast iron column radiation in rooms to be heated from -10° to 50°.



Ventilation

FOR OFFICES · STORES ·
 FACTORIES · PUBLIC BUILDINGS
 RESTAURANTS · THEATRES · HOUSES · ETC.



ILG "Self-Cooled Motor" Propeller Fans meet requirements of "state and city codes" for ventilating factories, offices, restaurants, theatres, etc.

ILG Universal Blowers, direct connected or belt drive, meet state and city codes for blast heating and ventilating theatres, schools, halls, factories, etc.

ILG Volume Blowers comply with requirements specified in "state and city codes" for ventilating toilet rooms, chemical laboratories, telephone booths, etc.

ILGAIR Unit Heaters for garages, factories and large open spaces, place heat where it belongs—at the floor.

ILGAIR Humidifiers and Air Washers. Economical in first cost, maintenance and less complicated.

ILG Kitchen Ventilators prevent greasy cooking odors from circulating through living rooms. Send for descriptive literature and blue prints.



ILG ELECTRIC VENTILATING CO.

Telephone, Kildare 1520

2834 N. Crawford Ave., Chicago, Ill.



"MUELLER"

STEAM AND WATER BOILER RATINGS

ARE

Positively Guaranteed

THEY ARE

Quick Heaters, Powerful,
 Durable and Economical

MADE BY

L. J. Mueller Furnace Co.

(Established 1857)

196 Reed Street MILWAUKEE, WIS.

Chicago Office, 60 E. Lake St.

Tel. Central 6545

- (3) 500 sq. ft. of cast iron wall radiation or wall pipe coils (being the equivalent of 625 sq. ft. of cast-iron column radiation) in rooms to be heated from -10° to 50° .
- (4) 500 sq. ft. of indirect radiation.
- (5) 500 sq. ft. of direct-indirect radiation.
- (6) 250 gal. hot water tank. Water to be heated with steam coils.
- (7) 500 sq. ft. of cast iron hot blast radiation, regular sections, 5" centers, 1,000 ft. velocity, air taken from out of doors -10° to F.T. 80. Radiation 3 stacks deep.

ANSWER

(1)	500 sq. ft.	500
(2)	500 sq. ft. + 13%	565
(3)	500 sq. ft. + 25%	+ 13%.....	707
(4)	500 sq. ft. + 50%	750
(5)	500 sq. ft. + 25%	625
(6)	250 gal. \times 2.....	500

3647

Add factor of safety .378%.....1378

5025

(7) $500 \times 1.92 \times 4 + 15\%$4416

Minimum rated capacity of boilers.....9441

SIZES OF LOW PRESSURE STEAM MAINS ONE PIPE CIRCUIT SYSTEM DRIPPED AT END

1" up to 60 sq. ft.	
1½" 60 sq. ft. to 100 sq. ft.	
1½" 100 sq. ft. to 200 sq. ft.	
2" 200 sq. ft. to 400 sq. ft.	
2½" 400 sq. ft. to 600 sq. ft.	
3" 600 sq. ft. to 900 sq. ft.	
3½" 900 sq. ft. to 1,400 sq. ft.	
4" 1,400 sq. ft. to 2,000 sq. ft.	
4½" 2,000 sq. ft. to 2,600 sq. ft.	
5" 2,600 sq. ft. to 3,300 sq. ft.	
6" 3,300 sq. ft. to 4,500 sq. ft.	
7" 4,500 sq. ft. to 7,000 sq. ft.	
8" 7,000 sq. ft. to 9,000 sq. ft.	
9" 9,000 sq. ft. to 11,000 sq. ft.	
10" 11,000 sq. ft. to 15,000 sq. ft.	
12" 15,000 sq. ft. to 24,000 sq. ft.	

On all piping, proper provision shall be made for expansion and contraction.

All piping shall be properly pitched.

All horizontal branches more than 12 feet in length shall be increased 2 sizes.

All horizontal branches more than 16 feet in length shall be properly dripped.

Supply mains shall not be reduced more than one-half the diameter of the largest main.

Dry returns shall be not less than one-half the diameter of the supply.

Wet returns may be one size smaller than one-half the diameter of the supply pipe. By supply pipe is meant the size of the main at the point of leaving boiler.

PIPE SIZES FOR UP-FEED RISERS

1"	25 square feet or under.
1¼"	25 to 60 square feet
1½"	60 to 100 square feet
2"	100 to 200 square feet
2½"	200 to 350 square feet
3"	350 to 900 square feet
3½"	900 to 1,200 square feet
4"	1,200 to 2,000 square feet

RADIATOR CONNECTIONS

Up to and including 25 square feet.....1"
Above 25 and including 60 square feet.....1½"
Above 60 and including 90 square feet.....1½"
Above 90 square feet.....2"

All horizontal connections to radiators shall be increased one size except branches for radiators from 91 to 130 square feet, which may be the same size as radiator connections.

All horizontal connections to risers shall be increased one size.

A New Factor in Building Valuations

It is felt that there is need for a new viewpoint in building valuation. In the past it would seem that too much stress has been placed on age and immediate revenue in building valuation. It would seem that the architect, owing to his peculiar training, is in a position to point out other very important factors entering into value make-up, which have not heretofore been considered in this locality; such as, balance of structural design, adaptability to purposes intended, character of construction as influencing cost of up-keep.

Feeling that the stability of building investment can be better assured by taking the before mentioned factors into consideration, the Illinois Society of Architects has appointed a Building Valuation Committee to furnish the public with competent architectural valuation service. This Committee should form a real asset to the community.

FULL AREA OF TWO-PANE WINDOWS

GIVING THE TOTAL AREA OF TWO-PANE WINDOWS, BRICK OPENING.


Height of Glass Width of Glass	16"	18"	20"	22"	24"	26"	28"	30"	32"	34"	36"	38"	40"
TOTAL AREA IN SQUARE FEET													
12"	5.9	6.4	7.	7.5	8.	8.6	9.2	9.8	10.2	10.9	11.4	12.	12.5
14"	6.5	7.1	7.7	8.3	9.	9.6	10.2	10.8	11.4	12.	12.6	13.2	13.8
16"	7.	7.7	.4	9.1	9.8	10.5	11.2	11.9	12.6	13.3	14.	14.4	15.
18"	7.6	8.4	9.1	9.8	10.5	11.2	12.	12.7	13.	14.1	14.8	15.6	16.3
20"	8.2	9.	9.8	10.5	11.3	12.1	12.9	13.7	14.5	15.2	16.	16.8	17.5
22"	8.8	9.6	10.4	11.2	12.1	13.	13.8	14.6	15.4	16.2	17.	17.8	18.8
24"	9.4	10.3	11.1	12.	12.9	13.8	14.7	15.6	16.5	17.4	18.3	19.2	20.
26"	10.	10.9	11.8	12.7	13.7	14.7	15.6	16.6	17.5	18.5	19.4	20.4	21.3
27½"	10.4	11.4	12.5	13.4	14.3	15.3	16.3	17.3	18.3	19.3	20.3	21.3	22.2
28"	10.5	11.5	12.5	13.5	14.5	15.5	16.5	17.5	18.5	19.5	20.5	21.5	22.5
30"	11.1	12.2	13.2	14.3	15.4	16.4	17.5	18.5	19.6	20.6	21.7	22.7	23.8
32"	11.7	12.8	13.9	15.	16.1	17.2	18.4	19.5	20.9	21.7	22.8	23.9	25.
34"	12.3	13.5	14.6	15.8	17.	18.1	19.3	20.5	21.6	22.9	24.	25.2	26.3
36"	12.9	14.1	15.3	16.5	17.8	19.	20.9	21.4	22.7	23.9	25.1	26.3	27.5
38"	13.5	14.7	16.	17.3	18.6	19.9	21.1	22.4	23.7	25.	26.2	27.5	28.9
40"	14.	15.4	16.7	18.	19.4	20.7	21.6	23.4	24.7	26.	27.4	28.7	30.
44"	15.2	16.7	18.1	19.5	21.	22.4	23.9	25.3	26.8	28.2	29.7	31.1	32.5
48"	16.4	17.9	19.5	21.	22.6	24.2	25.7	27.3	28.8	30.4	31.9	33.5	35.

Sizes not shown, figure brick opening.

IMICO

House Heating Boilers

For Steam and Hot Water



Low Ratings, Perfect Construction, Low Fuel Consumption, Unexcelled Efficiency

Illinois Malleable Iron Co.

1801-1825 Diversey Boulevard

CHICAGO

CHICAGO PUMP CO.

Electric Pumping Machinery

Phone Armitage 1286

2336 Wolfram St., CHICAGO, ILL.

TABLE OF CAPACITIES

Multi-Stage Turbine House Pumps

Type and Size of Pump Inches	Capacity in G. P. M.	Maximum Head in Feet per Stage at 1750 R. P. M.
E	5	15
E 1	10	30
E 1 1/2	15	27
E 1 1/2	25	20
C 1 1/2	35	50
C 1 1/2	50	45
C 2	75	40
H. S. 2	100	135
H. S. 2 1/2	150	135
H. S. 3	200	125
H. S. 3	250	115

Electric Bilge Pumps

Type and Size of discharge	Capacities in G. P. M.
LG No. 1—1 in.	10-15
LG No. 2—1 1/2 in.	25-30
LG No. 3—1 1/2 in.	50-55
LG No. 4—2 in.	70-75
LG No. 5—2 1/2 in.	100
LG No. 6—2 1/2 in.	125
E No. 7—3 in.	150
E No. 8—4 in.	200
E No. 9—4 in.	250
E No. 10—4 in.	300
E No. 11—4 in.	350
E No. 12—4 in.	400

Electric Condensation Pumps and Receivers

No. of Pump	Max. sq. ft. direct radiation	Horse Power motor
1	1500	1/2
1A	2000	1
2	3000	1 1/2
3	6000	2
4	10000	3
5	15000	1
6	25000	2
6A	35000	2

Vacuum Pumps for Heating Systems

No. of Pump	Max. sq. ft. direct radiation	Horse Power motor
1	6000	1 1/2
2	12000	2 1/2
3	20000	3

Type E and LG Sewage Ejector

Type and Size of discharge	Capacity Gal. per min.
LG No. 1—2 in.	50
LG No. 2—2 in.	75
LG No. 3—2 1/2 in.	100
LG No. 4—2 1/2 in.	125
E No. 5—3 in.	150
E No. 6—3 1/2 in.	200
E No. 7—4 in.	250
E No. 8—4 in.	350

SECTIONS OF THE SANITARY CODE OF INTEREST TO ARCHITECTS, WITH INDEX

INDEX

<p>Air—Quantity of for each person..... 447</p> <p>Amendments to Sanitary Code passed Sec. since March 13, 1911, amending Section 2854 4</p> <p>Architects' penalty 1</p> <p>Architects' plans 140</p> <p>Bakery defined 276-448</p> <p>Bath rooms—requirements 1377</p> <p>Distances between buildings on same lot 1377</p> <p>Dry cleaners—Building requirements—Ventilation—Equipment—Lighting—Water trough 2854</p> <p>Frontage consents required, when..... 1219</p> <p>Handling of oils..... 2855</p> <p>Height of ceilings—Windows..... 1379</p> <p>Hospitals defined 1213</p> <p>Living rooms in cellar or basement—When permitted 477-477½</p> <p>Lodginghouse defined 1388</p> <p>Location of hospitals near schools.... 1220</p> <p>Lodginghouses, penalty 1389</p> <p>Lodginghouse—Ventilation 1378</p> <p>Pantries—Requirements 276</p> <p>Pipes through floors— Catch basins — Water closets 472</p> <p>Rooms, habitable — Definition of—Requirements as to size and ventilation 274-448</p>	<p>Rooms—Access to 469</p> <p>Rooms—Change in existing..... 475</p> <p>Seats for females..... 1402</p> <p>Seats for females—Penalty..... 1403</p> <p>Sinks — Requirements..... 471</p> <p>Slaughtering, rendering, packing, etc.. 1330</p> <p>Sleeping stalls in rooms—When allowed 262</p> <p>Stories—Height of 507</p> <p>Tenement and lodging houses conform to requirements 1376</p> <p>Definition of 432</p> <p>Apartments—Yard—Court—Shaft, etc. 432</p> <p>New, when occupied..... 435</p> <p>Rooms in basement..... 449</p> <p>Undertakers; care of dead human bodies; burials 1238</p> <p>Undertaking rooms 1239</p> <p>Ventilation of stores, factories, workshops, etc. 1399</p> <p>Walls—Division and partitions — Fire Stops 261</p> <p>Water closets and urinal stalls — Requirements in relation thereto..... 276</p> <p>Windows, courts and attics..... 476</p> <p>Workshops—Workshops defined 1390</p> <p>Water supply—Cellar floor—Ventilation of halls 1380</p>
--	---

Architect—plans.] Section 1. Be it enacted by the People of the State of Illinois, represented in the General Assembly: That it shall be the duty of any architect or architects, builder or builders of, or other person or persons interested in any projected tenement, lodging house, or other places of habitation, in any incorporated city of fifty thousand inhabitants, to submit plans and specifications of any such building or buildings to the health commissioner or commissioners of such incorporated city; that the said health commissioner or commissioners may examine the said plans and specifications, for his or their approval or rejection, as to the proposed plans for the ventilation of rooms, light and air shafts, windows, ventilation of water closets, drainage and plumbing.

Architect—penalty.] Section 4. If any architect or architects, builder or builders, violate the provisions of this act, he or they shall be fined in a sum not less than one hundred nor more than two hundred dollars for each offense.

BAKERIES.

140. Bakery defined.] Any place used for any process of mixing, compounding or baking, for sale or for purposes of a restaurant, bakery or hotel, any bread, biscuits, pretzels, crackers, buns, rolls, macaroni, cake, pies or any food product of which flour or meal is a principal ingredient, shall be deemed a bakery for the purpose of this chapter; provided, that licensed restaurants in which any of the foregoing food products are mixed and baked for consumption in such restaurant only, on or in ordinary restaurant kitchen stoves or ranges, and kitchens or rooms in dwellings where any of the said food products are mixed and baked in an ordinary kitchen stove or range, shall not be considered bakeries.

145. Sanitary requirements—ventilation.] Every place used as a bakery shall be kept in a clean and sanitary condition as to its floors, side walls, ceilings, woodwork, fixtures, furniture, tools, machinery and utensils. All parts of the bakery shall be adequately lighted at all times and shall be ventilated by means of windows or skylights or air shafts or air ducts or mechanical ap-

EXPERIENCE 42 YEARS

MEHRING & HANSON COMPANY

GENERAL STEAM FITTING

POWER PLANTS--POWER PIPING

HEATING, COOLING AND VENTILATING
SYSTEMS

118-120 NORTH FRANKLIN STREET

TELEPHONES FRANKLIN 2010-2011

CHICAGO

American Heating and Plumbing Corporation

Central 5927-5928

CLARKE BLDG

189 N. Clark Street

CHICAGO, ILLINOIS

CONTRACTING ENGINEERS

for Power Installation, Steam and Hot Water Heating
Ventilation, Sanitary Plumbing, Sewerage Systems

BRANCH OFFICES

3550 North Clark Street
Phone Lake View 459

1615 Benson Avenue, Evanston, Ill.
Phone Evanston 975

OIL BURNERS FOR ALL BOILERS
UNIT HEATERS

ROBERT GORDON, Inc.

Heating and Power Piping Contractors
Ventilating Contractors

Haymarket 3740-3741

622 W. MONROE STREET

HARRY PECKHAM, Jr.

Steam & Hot Water Heating & Steamfitting

2345 West Roosevelt Road

Telephone Seeley 1854

::

CHICAGO

paratus, if necessary, so as to insure a free circulation of fresh air at all times. Such ventilating construction and equipment shall be of such character that a complete change of air in all parts of the bakery may be made at least four times each hour; provided, however, that it shall not be necessary to ventilate at such time or in such manner that the process of mixing or rising of dough shall of necessity be interfered with or prevented.

146. Floor—how constructed.] The floor of every place used as a bakery, if below the street level, shall be constructed of concrete, cement, asphalt or other impervious material, or of tile laid in cement, which floor may, if desired, be covered with a hardwood floor having tight joints; if above the street level, the floor may be of hardwood with tight joints or may be of any impervious material, as above provided. The angles where the floor and wall join shall be made and maintained so as to be rat-proof.

148. Walls and ceilings—woodwork.] The side walls and ceilings shall be well and smoothly plastered, tiled or sheathed with metal or wood sheathing, and shall be kept in good repair. If made of mill construction with smooth surfaces, such walls and ceilings need not be sheathed or plastered. All walls and ceilings shall be kept well painted with oil paint, or lime washed and calcimined, and all woodwork shall be kept well painted with oil paint.

156. New bakeries—requirements.] No new bakery shall be hereafter established in any room, basement or cellar in which the clear height between the finished floor and ceiling is less than eight feet six inches or in any room or place, the floor of which is more than five feet below the street, sidewalk or alley level adjacent to the building, or in any room or place which is not so naturally lighted by means of windows, doors or skylights that on clear days a book or paper printed with double long primer type can be read between the hours of ten o'clock a. m. and two o'clock p. m. in all parts of the bakery which are used in mixing or handling bakery products.

261. Walls—divisions and partitions—fire stops.] (a) In buildings hereafter erected used wholly or in part for the purposes of Class IIb of ordinary slow-burning or mill construction, there shall be for every eight rooms in any one story, dividing walls or partitions of incombustible material separating such eight rooms from the contiguous spaces.

(b) In all buildings hereafter erected to be used wholly or in part for the purposes of Class IIb, all elevators and stairs shall be enclosed in partitions of incombustible or fireproof material, and the partitions on all corridors leading to such elevators and stairs shall be of fireproof or incombustible material. Such partitions shall be carried on self-supporting masonry or a framework of steel or iron. Where glass is used in said partitions, the same shall be wired glass set in metal frames, but such glass shall not exceed sixty per centum of the superficial area of said partitions.

(c) In all non-fireproof buildings of Class IIb there shall be between joists a stop of brick, concrete or tile not less than four inches in thickness, extending the full height of joists and spaced not more than twenty-five feet apart, measured in the direction of the length of the joist.

262. Sleeping stalls in rooms—when allowed.] Sleeping stalls shall not be constructed or used in any room in any building now existing or hereafter erected and devoted, in whole or in part, to the purposes of a lodging or rooming house unless such

room has two or more windows which open directly upon a street, alley, yard or court and which windows have a total area equal to at least one-tenth of the floor area of such room, nor unless the semi-partitions forming such stalls are so constructed that there is a clear and unobstructed interval of at least thirty inches between the top of such semi-partitions and the ceiling of the room, nor unless each such stall shall open directly into an aisle or passageway leading directly to a stairway or stairway fire escape, the location of which is indicated by a red sign and at night by a red light also. Such sleeping stalls shall not be installed in any such room in such numbers that there shall be less than 400 cubic feet of air per person when all stalls are occupied to their full capacity. The semi-partitions forming such stalls hereafter constructed shall be of incombustible material.

274. Habitable rooms—definition of—requirements as to size and ventilation.] (a) For the purposes of this chapter the term "habitable room" shall be held to include every room in every building of Classes III and VI, and every room in buildings of other classes if such rooms are used for the purposes of Classes III and VI, in which a family or the individual members thereof regularly sleep or eat or carry on their usual domestic or social vocations or avocations. Laundries, bath rooms, water closet compartments, serving and storage pantries, storage rooms and closets, boiler and machinery rooms, cellars, corridors, and similar spaces used neither frequently nor during extended periods, shall not be deemed as coming within the scope of this term.

(b) In every building hereafter erected for or converted to the purposes of Class III, every habitable room shall have a window or windows with a total glass area equal to at least one-tenth of its floor area, opening onto a street, alley, or yard, as defined in section 432 of this chapter. None of such required windows shall have a glass area of less than ten square feet; and each such window shall have its top not less than seven feet above the floor and shall be so constructed that at least its upper half may be opened its full width. No such habitable room shall have a floor area of less than eighty square feet, nor a clear height from floor to ceiling of less than eight feet and six inches; provided, that attic rooms need not be eight feet six inches high for more than one-half of their area, and that such attic rooms shall have total cubic contents of not less than seven hundred and fifty cubic feet each.

(c) No living room shall be partitioned off or constructed in any existing building or portion thereof, until plans of such building and room have been filed with, and a permit for such partitioning or constructing obtained from the commissioner of buildings and the commissioner of health; and every room so partitioned off or constructed shall comply with all the requirements for habitable rooms as contained in this section.

276. Pantries, bath rooms, water closet and urinal compartments—requirements in relation thereto.] In every building hereafter erected for or converted to the purposes of Class III, every pantry, bath room, water closet or urinal compartment shall have at least one window with a glass area of at least six square feet and a minimum width of at least one foot opening upon a street, alley, or yard as defined in section 432 of this chapter, or upon a vent shaft not less in area than said window; and no habitable room shall open into or connect with a vent shaft thus used.

***432. Definition of "new tenement house"—"apartment"—"yard"—"court"—"shaft"—**

Established 1877

L. H. PRENTICE COMPANY

LEON H. PRENTICE, Pres.

Engineers and Contractors for Steam and Hot Water
Heating and Ventilating Apparatus, Power Plants and Power Piping
Hot Blast Heating and Mechanical Ventilation
Stationary Vacuum Cleaning Systems

Probably the largest firm of this kind in the world, viz: exclusively steam and hot water heating apparatus THAT HEATS.

328 and 330 Sherman St.
near Board of Trade

Day Telephone Wabash 1188
Night Telephone Austin 1638

CHICAGO

OFFICE AND SHOP
15 W. KINZIE STREET
CENTRAL 2695

KEHM BRO'S COMPANY
CONTRACTORS
POWER PLANTS AND PIPING
STEAM (HEATING APPARATUS) WATER
VENTILATING SYSTEMS

AUG KEHM PRES

CHICAGO

TELEPHONE WELLINGTON 2500

ESTABLISHED 1895

NILSON BROS.
PLUMBING and HEATING

3222-24 N. Halsted Street

CHICAGO

HEATING

VENTILATING

POWER

PHILLIPS, GETSCHOW CO.
ENGINEERS AND CONTRACTORS
INDUSTRIAL PIPING

128-130 W. Kinzie St. Telephone Franklin 678

CHICAGO

"public hall"—"stair hall"—"basement"—"cellar"—"story"—"solid masonry." (a) "New tenement house" shall include every tenement, flat and apartment house hereafter erected and every tenement house which shall be increased or diminished in size or otherwise altered after its erection and every building now or hereafter in existence not now used as a tenement house but hereafter converted or altered to such use.

(b) "Apartment" is a room or suite of two or more rooms occupied or intended or designed to be occupied as a family domicile.

(c) "Yard" is an open unoccupied space on the same lot with a tenement house, separating every part of every building on the lot from the rear line of the lot.

(d) "Court" is an open, unoccupied, unobstructed space, other than a yard, on the same lot with a tenement house; a court entirely surrounded by a tenement house is an "inner court"; a court bounded on one side and both ends by a tenement house, and on the remaining side by a lot line is a "lot line court"; a court extending to a street, alley or yard is an "outer court."

(e) "Shaft" includes exterior and interior shafts, whether for air, light, elevator, dumb waiter or any other purpose; a "vent shaft" is one used solely to ventilate or light a water closet compartment, bathroom, or pantry.

(f) "Public Hall" is a hall, corridor or passageway not within an apartment.

(g) "Stair Hall" includes the stairs, stair landings and those portions of the public halls through which it is necessary to pass in getting from the entrance floor to the top story.

(h) "Basement" is a story partly, but not more than one-half below the level of the inside sidewalk grade of the street nearest the building. If the floor of such basement is less than two feet (2 ft.) below such grade or if the ceiling of such basement is more than seven feet six inches (7 ft. 6 in.) above said grade, said story shall be classed as the first story of the building in which it occurs. Provided, however, that the ceiling height may be raised above the height of seven feet six inches (7 ft. 6 in.) heretofore given, not more than one-third of an inch for every foot of such distance said building is set back from the street line of the street nearest the building, but in no case shall any rise of ceiling be allowed for any distance beyond thirty feet (30 ft.) said building may be set back from the line of the street nearest the building, and in such cases all rises in the basement ceiling shall be computed according to the distance between the street line and the outside wall of the building nearest to said street line. And further provided, that the yard or ground level, or walks, or other improvements thereon for a distance of twelve feet (12 ft.) at every point from all outside walls walls of said building shall not be lower than eight feet three inches (8 ft. 3 in.) below the floor level of the first story of said building.

(i) "Cellar" is a story more than one-half below the level of the inside sidewalk grade of the street nearest the building. Where the grade of a street adjacent to a tenement house varies, the average grade of such street opposite the lot containing the tenement-house shall be regarded as the grade of such street within the meaning of this chapter.

(j) "Story" is that portion of a building between the top of any floor beams and the top of the floor or ceiling beams next above.

435. New tenement house—when to be occupied.] (a) No new tenement house shall be occupied in whole or in part for human habitation until the issuance of a certificate by the commissioner of health that such building conforms to the requirements of this chapter relative to light and ventilation, plumbing and drainage applicable to said buildings, nor until the issuance by the commissioner of buildings of a certificate that the said building conforms to the requirements of this chapter relative to fire escapes and means of egress applicable to new tenement houses. Within five days from date of application for any certificate above mentioned, such certificate shall be issued or the official concerned shall state in writing his reasons for his refusal to issue said certificate.

(b) The certificate above referred to may be issued in the case of a new tenement building comprising more than three apartments so as to allow the occupation of any section of the building extending from cellar to roof in advance of the completion of the other portions of the building.

(c) When the outer walls of a new tenement house have been erected so as to outline the position of the courts and shafts required for the lighting and ventilation of habitable rooms, the owner of the building or his representative shall be entitled, upon application in writing, to an inspection of the same by the commissioner of buildings, and if the work to that point is in compliance with the provisions regarding the size of the shafts and the location of the building, to a certificate setting forth those facts.

(d) When the work of constructing partitions has advanced to a degree on any floor, that the rooms on that floor are determined in their dimensions, the owner or his representative shall be entitled to an inspection from the commissioner of buildings, and if the rooms thus outlined conform in their dimensions to the plans filed and to the requirements of this chapter, to a certificate stating that fact.

(e) If a new tenement house is occupied as a place of habitation in any of its parts in violation of this section, it shall forthwith be subject to notice from the commissioner of buildings and shall be vacated upon such notice and shall not again be occupied until made to conform with the provisions of this chapter nor until after the issuance of the two certificates required in this section.

447. Air—quantity of for each person.] No room in any tenement house shall be occupied so that the allowance of air to each adult person living or sleeping in such room shall at any time be less than four hundred cubic feet or less than two hundred cubic feet for each person under twelve years of age.

448. Habitable rooms—bathrooms—pantries—requirements as to ventilation and lighting.] (a) In every new tenement house every habitable room shall have a window or windows with a total glass area equal to at least one-tenth of its floor area opening onto a street, alley, yard or court. None of such required windows shall have a glass area of less than ten square feet, and each such window shall have its top not less than seven feet above the floor, and shall be so constructed that at least its upper half may be opened its full width.

(b) In every new tenement house every bathroom, water closet, or urinal compartment shall have at least one window with a glass area of at least six square feet and a minimum width of one foot, opening upon a street, alley, yard, court or vent shaft.

* As amended July 2, 1914, and February 8, 1915.

PHONE: SUPERIOR 4285

E. J. CLAFFEY CO.

Engineers—Contractors

**STEAM and HOT WATER HEATING, VENTILATING SYSTEMS
GENERAL STEAM FITTING, POWER PLANTS**


10-12-14 W. Illinois St.

CHICAGO

Phone Central 5679

DWYER & COMPANY

**Plumbing, Heating and
Ventilating Contractors**



31 W. Illinois Street

CHICAGO, ILLINOIS

Telephone Main 4572

GLENNON-BIELKE CO.

Steam

HEATING

Water

Vacuum

Vapor

Power Plants, Ventilation

546 WEST LAKE STREET, CHICAGO

Office Phone: Monroe 2491

J. J. HERLIHY

CONTRACTOR AND ENGINEER

**STEAM, VAPOR, VACUUM AND HOT WATER HEATING, VENTILATING,
POWER PLANTS AND REFRIGERATION,
INSTALLING AND REPAIRING**

751 W. VAN BUREN ST.

CHICAGO

(c) In every new tenement house every party shall have at least one window of not less than six square feet in area, with a width of not less than one foot, opening into a street, alley, yard, court or vent shaft, which vent shaft shall be at least six square feet in area.

***449. New tenements—habitable rooms in basements—prohibited in cellars.]** In no new tenement house shall any room in the cellar be constructed, altered, converted or occupied for living purposes; and no room in the basement of a new tenement house shall be constructed, altered, converted or occupied for living purposes unless such room shall be at least eight feet six inches high in the clear and shall have at least one-half of such height above the finished grade of said premises at the building, and at least four feet three inches of such height above the average street grade at the building. Provided that only one living apartment not exceeding six rooms shall be allowed in the basement of any tenement house hereafter to be constructed.

* As amended February 8, 1915.

469. Access to rooms—otherwise than through bedroom.] In each apartment in every new tenement house, access to every living room and bedroom, and to at least one water closet compartment, shall be had without passing through any bedroom.

471. Sinks—requirements.] In every new tenement house there shall be in each apartment at least one kitchen sink with running water. In every existing tenement if there be not one such sink in each apartment there shall be on every floor at least one kitchen sink with running water, accessible to all the tenants of the floor, without passing through any other apartment. In no tenement house shall there be woodwork inclosing sinks; the space underneath shall be left entirely open.

472. Pipes through floors—catch basins—water closets.] (a) In every new tenement house where plumbing or other pipes pass through floors or partitions, the openings around such pipes shall be sealed tight with plaster or other incombustible material, so as to prevent the passage of air or the spread of fire from one floor to another or from room to room.

(b) In the premises of a tenement house the catchbasin shall, whenever practicable, be placed in a court or yard, and shall be covered with a stone or iron cover, flush with the surface so that access to such basin shall be convenient.

(c) Where it is for any reason impracticable to place a catchbasin in a court or yard, the commissioner of health may authorize the use of an iron catchbasin with air-tight cover, located in the cellar or basement.

***475. Rooms—change in existing.]** No room in any now existing tenement house shall hereafter be constructed, altered, converted or occupied for living purposes, unless it contains a window having a superficial area not less than one-twelfth of the floor area of the room, which window shall open upon a street or alley or upon a yard or court having a superficial area of not less than twenty-five square feet and a minimum width of not less than two feet six inches, or unless such room adjoins another room in the same apartment, which other room shall have such a window opening upon such a street, alley, yard or court, between which two adjoining rooms there shall be an alcove opening equal in extent to at least 20 per cent of the entire wall surface of said room; provided, however, that all of the requirements of sections 439 and 440 of The Chicago Code of 1911 shall be complied with.

* As amended July 8, 1912.

Where a frame tenement house is moved from one lot to another, or from one location to another on the same lot, it shall comply with the provisions of section 452 of this chapter.

476. Windows—courts—attic.] No room in any now existing tenement house, which has no such window as aforesaid, opening upon a street or alley or upon a yard or court having a superficial area of not less than twenty-five square feet, shall hereafter be constructed, altered, converted or occupied for living purposes, unless it contains a floor area of at least sixty square feet and also at least six hundred cubic feet of air space; nor unless every part of the finished ceiling of such room be at least seven feet six inches distant from every part of the finished floor thereof; provided, that an attic room need be seven feet six inches high in but one-half of its area, and provided, further, that such attic room has not less than seven hundred fifty cubic feet of air space therein; and such attic room shall not be used for purposes of human habitation other than as a sleeping room.


***477. Existing tenements—living rooms in cellars or basements—when permitted.]** In every existing tenement house, no room in an existing cellar or basement shall be occupied for living purposes unless such room shall be at least seven feet six inches high in the clear, and have not more than four feet eight inches of such cellar or basement below the finished grade at building; provided, that no such room shall be used for living purposes unless such room shall have a window opening upon a street, alley, yard or court, and, provided, that when the windows of any living room front solely upon a street and the floor of such basement is four feet eight inches below the sidewalk grade, such windows shall be located not less than three feet back of the lot line; provided, however, that in every case where the height of ceiling of any living room is less than eight feet six inches in the clear, the window area of such room shall be at least fifteen per centum of the floor area.

(b) When a brick or frame tenement house is moved from one lot to another, or from one location to another on the same lot, and a basement or story, or both, is constructed under the same, the total height of which is more than six feet six inches from the floor to the ceiling, the walls of such basement shall be constructed of masonry according to the provisions of section 658 of The Chicago Code of 1911, and the habitable rooms therein shall comply with the provisions of section 475 of The Chicago Code of 1911, and the space on the lot shall comply with the provisions of section 430 and section 440 of The Chicago Code of 1911.

* As amended July 8, 1912.

477½. Insanitary condition—nuisance.] A tenement house or part thereof which is in an insanitary condition by reason of the basement or cellar being damp or wet, or by reason of the floor of such basement or cellar being covered with stagnant water or by reason of the presence of sewer gas, or by reason of any portion of such building being infected with disease, or being unfit for human habitation, or which by reason of any other insanitary condition is a source of producing sickness among the inhabitants of this city, or which in any way endangers the public health, is hereby declared to constitute a public nuisance.

507. Stories—height of.] No story above the basement shall be less than twelve feet in height in the clear.



Dole Packless Graduated Valve

DOLE Packless Radiator Valves

A Special Valve for Every System
Positive Satisfaction Guaranteed

THE DOLE VALVE COMPANY
1923-1933 Carroll Ave., CHICAGO

OUR REFERENCES

A list of Owners
and Architects
given on request.

Results Guaranteed

Telephone Haymarket 2310

W. B. Graves Heating Co.

STEAM AND HOT WATER
HEATING AND VENTILATING
POWER PLANTS

162 N. Desplaines St.

INSTALLATION

REMODELING

TELEPHONES MONROE 4000

WILLIAM A. POPE

Heating and Power Plants---Power Plant Piping

26 N. Jefferson Street, Chicago

Phone Main 4636

BEN RIGBY, INC.

STEAM & HOT WATER HEATING

545 WEST LAKE STREET

CHICAGO, ILL.

HOSPITALS.

1213. Hospital defined.] For the purpose of this article a hospital is hereby defined to mean any institution or place used for the reception or care, temporary or continuous, of two or more sick, injured or dependent persons; or used for the treatment of two or more persons suffering from or afflicted with any mental or physical disease or bodily injury, including all hydro-pathic and massage institutions.

For the purposes of this article a maternity hospital is hereby defined to mean any institution or place used for the reception and care, temporary or continuous, of one or more women during pregnancy while awaiting confinement, during confinement, or for one month or less after confinement while recovering therefrom.

Unless otherwise specified, the word "hospital" as used in this article shall be held to include maternity hospital.

1219. Frontage consents required—when.] It shall be unlawful for any person, firm or corporation to build, construct, maintain, conduct or manage in any block, in which two-thirds of the buildings fronting on both sides of the street or streets on which the proposed hospital may front are devoted exclusively to residence purposes, any hospital, unless the owners of a majority of the frontage in such block, and the owners of a majority of the frontage on the opposite side or sides of the street or streets on which said building faces, consent in writing to the building, constructing or maintaining, managing or conducting of any such hospital in such block. Such written consents of the majority of said property owners shall be filed with the commissioner of health before a permit shall be granted for the building or constructing or a license be issued for the maintaining, conducting or managing of any such hospital.

1220. Location of hospitals near school.] No hospital of any kind or description shall hereafter be erected or established within four hundred feet of any property used for public or parochial school purposes.

1230 Method of slaughtering—offensive odors to be destroyed—construction of condensers.] The keeping and slaughtering of live stock and the preparation and keeping of all meat, fish, birds and fowls, and the rendering of all animal matter and the manufacture of glue and all by-products from animal matter shall be conducted in that manner which is, or is generally reputed or known to be, the best adapted to secure and continue their safety and wholesomeness as food, and to avoid all offensiveness of such keeping, slaughtering, rendering and manufacturing. Blood from slaughtered animals shall not be allowed to flow into any sewer or into the Chicago river or any of its branches, but while still fresh shall be treated so as not to become offensive.

All offensive odors arising from the handling of meat or other animal matter, melting or rendering, and the treating of and caring for offal, blood or any other material stored or manufactured, shall be destroyed by combustion, condensation or other means equally effective, and according to the best and most approved means and processes, and shall not be allowed to escape into the out-

side air. In the event that condensation shall be adopted as a method of destroying offensive odors or gases, the method of condensation employed shall be as follows:

Every rendering establishment shall use as condensers, tanks or other suitable airtight condensing appliances, with an overflow connecting with a sewer, and shall have a feed water pipe of sufficient diameter by which a continuous stream of cold water shall pass into the condenser and escape through the aforesaid overflow at or near the top, and all gases generated in the process of boiling shall be carried to and entered into the bottom of and under the body of water contained by said condenser, and such gases as are not condensed in the water shall be carried through another pipe connected with the top of the condenser, to the boilers or other places where heat of not less than six hundred degrees Fahrenheit is maintained, and shall there pass through such fire and be consumed. While the condenser is in use it shall be obligatory on the part of the user to allow sufficient water to flow through the condenser to maintain a temperature not higher than one hundred degrees Fahrenheit.

A condenser of the spray, jet or other suitable pattern shall be connected with all dryers operated, and a fan or pump shall draw the vapors from the dryer and force them through such condenser, the water from which shall pass into the sewer, and a sufficient quantity of water shall be used to thoroughly condense any and all vapors and odors conveyed thereto.

To the end that a proper inspection may be readily made by the authorities of the temperature maintained in such condensers, there shall be attached to each of such condensers an automatic or self-registering thermometer of such a character as will automatically keep a daily record of the temperature maintained in each such condenser at all times during the use thereof.

UNDERTAKERS; CARE OF DEAD HUMAN BODIES; BURIALS.

1238. Frontage consents.] It shall be unlawful for any person to carry on the business of an undertaker, as defined in this article, who, in connection with such business, receives at his place of business the body of any dead person, for embalming or other purposes, where such place of business is located on any street in any block in which two-thirds of the buildings on both sides of the street are used exclusively for residence purposes, without the written consent of a majority of the property owners according to the frontage on both sides of such street in such block; provided, however, that nothing herein contained shall apply to persons licensed as undertakers at the time of the passage of this ordinance.

Such frontage consents shall be obtained and filed with the department of health before a license shall issue for such business.

1239. Undertaking rooms.] No person shall be licensed to carry on the business of undertaking in any establishment, store or place, unless such establishment, store or place shall be provided with a compartment or room completely shut off or capable of being completely shut off from the other



MACHINISTS and PIPING CONTRACTORS

215-219 W. Congress St., CHICAGO

REPAIR DEPARTMENT OPEN
DAY AND NIGHT

Telephones } HARRISON 2896
 } HARRISON 2897

TELEPHONES MAIN 2959-2960

WILLIAM LEES

Contractor for

Steam and Hot Water Heating Apparatus

Ventilating and Steam Power Plants

548 Washington Boulevard

CHICAGO

P. NACEY CO.

Founded 1866

*Automatic Sprinkler, Power, Heating, Refrigerating,
Ventilating, Plumbing and Sewer Contractors*

927 South State Street

Harrison 387

CHICAGO

Harrison 4826

Established 1859

Telephone Main 4732

Baker & Smith Company

Steam and Hot Water
Heating

Our Long Experience and Thorough Organization assure Satisfactory Results

408-410 No. WELLS STREET

parts of such establishment, store or place; such compartment or room shall have free outside ventilation and light, and its floor shall be constructed of or covered with a non-absorbent material and shall be connected with a sewer by an approved sanitary drain.

TENEMENTS AND LODGING HOUSES.

1376. Conform to requirements.] No house or building hereafter erected shall be used as a tenement house or lodging house, and no house or building heretofore erected and not now used for such purposes shall be converted into, used or leased for a tenement or lodging house, unless in addition to the requirements hereinbefore contained in article IX of chapter XVI of this ordinance, it conforms to requirements affecting tenement or lodging houses, or both, as specified in the following sections of this article.

1377. Distances between buildings on same lot.] It shall not be lawful hereafter to erect for or convert to the purpose of a lodging house a building on any lot, other than a corner lot, where there is another building on the same lot, unless there is a clear, open space exclusively belonging thereto, and extending upwards from the ground, of at least ten feet between such buildings, if they are one story high above the level of the ground; if they are two stories high, the distance between them shall not be less than fifteen feet; if they are three stories high, the distance between them shall not be less than twenty feet; and if they are more than three stories high, the distance between them shall be not less than twenty-five feet.

1378. Lodging house—ventilation.] Every house, building or portion thereof in the city, designed to be used, occupied, leased or rented, or which is used, occupied, leased or rented, for a lodging house, shall have in every room which is occupied as a sleeping room and which does not communicate directly with the external air, a ventilating or transom window having an opening or area of three square feet over the door leading into and connected with the adjoining room, if such adjoining room communicates with the external air, and also a ventilating or transom window of the same opening or area communicating with the entry or hall of the house; or where this is from the relative situation of the rooms impracticable, such last mentioned ventilating or transom window shall communicate with an adjoining room that itself communicates with the entry or hall. Every such house or building shall have in the roof at the top of the hall an adequate and proper ventilator. No room in any lodging house shall be so occupied that the allowance of air to each person living or sleeping in such room shall at any time be less than four hundred cubic feet for each such person more than twelve years old and two hundred cubic feet for each such person of the age of twelve years or under.

1379. Height of ceilings—windows.] In every such house hereafter erected or converted, every habitable room except rooms in the attic shall be in every part not less than eight feet in height from the floor to the ceiling; and every habitable room in the attic of any such building shall be at least eight feet in height from the floor to the ceiling throughout not less than one-half

the area of such room. Every room shall have at least one window connecting with the external air, or over the door an adequate ventilator connecting it with a room or hall which has a connection with the external air, and so arranged as to produce a cross current of air. The total area of window or windows in every room communicating with the external air shall be at least one-tenth of the superficial area of every such room; and the top of one at least of such windows shall not be less than seven feet and six inches above the floor, and the upper half at least shall be made so as to open the full width. Every habitable room of a less area than one hundred superficial feet, if it does not communicate directly with the external air, and is without an open fireplace, shall be provided with a special means of ventilation by a separate air shaft extending to the roof, or otherwise, as the commissioner of health may prescribe.

1380. Water supply—cellar floor—ventilation of halls.] Every such house hereafter erected or converted shall have proper conveniences and receptacles for ashes and rubbish; it shall have water furnished at one or more places in such house or in the yard thereof, so that the same may be adequate and reasonably convenient for the use of the occupants thereof; it shall have the floor of the cellar properly cemented so as to be water-tight; the halls of each floor shall open directly to the external air, with suitable windows, and shall have no room or other obstruction at the end, unless sufficient light or ventilation is otherwise provided for said hall in a manner approved by the commissioner of buildings.

1388. Lodging house defined.] A lodging house shall be taken to mean and include any house or building or portion thereof in which persons are harbored or received or lodged for hire for a single night or for less than a week at one time, or any part of which is let for any person to sleep in for any term less than a week.

1389. Penalty.] Any person who shall violate, disobey, neglect or refuse to comply with, or resist, any of the provisions of this article, or who refuses to comply with any of the sanitary regulations of the department of health concerning any of the matters or things mentioned in this article shall be fined not less than ten dollars nor more than two hundred dollars for each offense.

WORKSHOPS.

1390. Workshop defined.] Any place where goods or products are manufactured or repaired, cleaned or assorted, in whole or in part, for sale or for wages, shall be taken and be held to be a workshop; and whenever any house, room or place is used for the purpose of carrying on any process of making, altering, repairing or finishing, for sale or for wages, any coats, vests, trousers, knee pants, overalls, cloaks, shirts, ladies' waists, purses, feathers, artificial flowers, or cigars, or any wearing apparel of any kind whatsoever intended for sale, it shall be deemed a workshop for the purposes of this article.

No one of the articles mentioned in this section shall be made, finished, altered or repaired in any room or apartment used as a living room or a sleeping room; nor shall any workshop be conducted, maintained, op-

GEO. H. KIRK
HEATING ENGINEER AND CONTRACTOR
FOR STEAM AND HOT WATER HEATING APPARATUS
AND POWER PLANTS

6711 WENTWORTH AVENUE, CHICAGO

TELEPHONE WENTWORTH 1185

MEMBER AMERICAN SOCIETY
HEATING AND VENTILATING
ENGINEERS

A. KILANDER & CO.

Contractors

Steam and Hot Water Heating

Complete Power Plant Equipment

Telephone Franklin 855

126 S. Clinton Street, Chicago

Capacity and character of material may be defined in heating specifications, but the success or failure of any plant is really determined by your choice of contractors.

C. W. JOHNSON, INC.

STEAM HEATING AND POWER PLANT CONSTRUCTION

FAN HEATING AND VENTILATING SYSTEMS

644 Washington Blvd.

Phones Monroe { 3574
5708

CHICAGO, ILL.

Phone Edgewater 644

George A. Henrich Co.

*Steam and Water Heating
Power Pipe Fitting*

5650 Broadway

Chicago

erated or carried on in any cellar or basement.

STORES, FACTORIES, WORKSHOPS—MISCELLANEOUS PROVISIONS.

1399. Ventilation of stores, factories, workshops, etc.] No person, being the owner, proprietor, lessee, manager or superintendent of any store, factory, workshop or other structure or place of employment where workmen and workwomen are employed for wages, shall cause, permit or allow the same or any portion or apartment of, or any room in such store, factory, workshop or other structure or place of employment, to be overcrowded or inadequate, faulty or insufficient in respect of light, ventilation, heat and cleanliness; and in every such building or apartment, or room in any such building, where one or more persons are employed as aforesaid, at least five hundred cubic feet of air space shall be allowed to each and every person employed therein, and fresh air supplied by ventilation at the rate of four complete changes of air per hour during the hours of employment. No part of such air supply shall be taken from any cellar or basement.

1402. Seats for female:.] It shall be the duty of all employers of females in any mercantile or manufacturing business or occupation to provide and maintain seats for the use of such female employees, and to permit, to a reasonable extent, the use of such seats by such employees during the hours of their employment, for the preservation of their health. Seats shall be furnished at the ratio of one seat for every four female employees. All mercantile and manufacturing occupations and establishments where females are employed shall be inspected by officers of the health department to ascertain if this section is complied with, and any employer violating any of the provisions of this section shall be subject to a fine of not less than five dollars nor more than one hundred dollars.

1403. Penalty.] Any person violating, disobeying, neglecting or refusing to comply with any of the provisions of this article, where no other penalty has been provided, shall be fined not less than ten nor more than one hundred dollars for each offense.

DRY CLEANERS.

2854. Building requirements—ventilation—equipment—lighting—water trough.] Every building used or intended to be used for the purpose of conducting or carrying on the business of dry cleaning, as defined in this chapter, shall be constructed and equipped according to the following specifications:

Every such building shall be built of brick, stone or concrete, with no basement, and shall not exceed two stories in height; provided, however, that the use of any building not exceeding three stories in height in which a dry cleaning business was carried on prior to the passage of this ordinance may be continued, if such building complies in all other respects with the provisions of this chapter. The first floor of such building shall be higher than the surface of the ground surrounding such building and shall be so laid that there shall be no space un-

derneath the same. The floor or floors and roof shall be of fireproof construction, and such floor or floors shall be covered with a wire carpet. There shall be no openings through the floors, excepting in two-story buildings in which a stairway leading from the second floor to the first floor may be permitted, if properly enclosed with walls of incombustible material. Such stairways shall lead to the outside of the building without any doors or openings leading into the dry cleaning room. Every such building shall be detached from all other buildings, or separated from all other buildings by a fire wall, with no openings to the adjoining building thereto, and shall not be occupied for any purpose other than the conduct of a dry-cleaning and dry-room plant. The walls of such building shall be not less than twelve inches thick and shall have vent holes at the floor line, not less than sixteen square inches in area, not less than six feet apart, measured from center to center, which vent holes shall be protected by screens of thirty mesh brass wire on the inside of such walls, and by iron bars or by screens of large mesh on the outside of such walls.

Such building shall be further ventilated by means of an exhaust fan or fans of sufficient capacity to change the air in the building every three minutes, and shall be kept in operation at all times during the use of such building. Such exhaust fan shall be located in an air conduit whose inlet openings shall be at or near the floor level in the wall farthest away from any other building or structure, and the discharge end of such conduit shall be carried over the roof of such building.

All doors in any such building shall be constructed of incombustible materials and shall open outward. All window openings of such building shall be protected by fire resisting glass with metal sash and frames, or by outside iron shutters.

Every such building, two stories high, shall be provided with two stairways leading from the second to the first floor, at least one of which must be placed on the outside and be constructed of iron or steel.

Every such dry-cleaning plant shall be equipped with a high pressure steam boiler of sufficient capacity to admit of flooding the dry cleaning and drying rooms with steam in case of fire. Each room of such building shall be equipped with a line of one and one-fourth inch pipe connected with a one and one-fourth inch supply line leading from such high-pressure boiler and having down-spouts of at least two inches in length and not less than ten feet apart, distributed over washers and extractors. The valves operating such lines of pipe shall in every case be placed outside of such building; provided, however, that every such dry cleaning plant, constructed and maintained prior to the passage of this ordinance, may, in place of such high-pressure boiler, be equipped with a suitable and adequate tank or tanks containing carbon dioxide. At least one such tank, containing not less than one hundred eighty cubic feet of gas under pressure, shall be provided for each one thousand cubic feet, or fraction thereof, of cubic contents of the room to be protected from fire. The valve or valves operating such tank or tanks shall be located on the outside of such building.

J. E. DOUGHERTY
Tel. Dorchester 9869

N. J. DOUGHERTY
Hyde Park 7295

Schampel & Dougherty

HEATING CONTRACTORS

173-5 W. Washington St.

Phones { **Main 1272**
 Main 3154

CHICAGO

THOS. J. DOUGLASS, President

FRANK J. DOUGLASS, Secretary

Thos. J. Douglass & Co.

ENGINEERS AND CONTRACTORS
VAPOR—STEAM—HOT WATER
HEATING PLANTS

Tel. Central 1156.

441 N. Dearborn St.

SUPERIOR 9868-6730

WM. V. HOIER CO.

(Not. Inc.)

HEATING, VENTILATING, POWER PIPING
REFRIGERATING PLANTS

701 NORTH WELLS STREET

CHICAGO

Telephone Douglas 8500

HANLEY & COMPANY

CONTRACTING ENGINEERS

Plumbing, Heating, Ventilating, Power and Electric Installations

3438-3444 Forest Ave.

CHICAGO

Whenever steam power shall be used for the operation of any machinery contained in any such dry cleaning establishment, the boiler generating such power shall be located in a separate building and so situated that the line of travel for gases, between the boiler and the nearest opening into the cleaning or drying room, shall be not less than twenty feet, and whenever electrical power is used, the electric motor furnishing such power shall be similarly located; provided, however, that such boiler and electric motor may be located in the same building where such building was used for dry cleaning purposes prior to the passage of this ordinance, if such boiler or electric motor are separated from the dry cleaning or drying room by fire walls having no openings into such dry cleaning or drying room, except such openings as may be required for shafts in operating the machinery contained therein.

Every such building shall be lighted by incandescent electric lamps having keyless sockets, protected by vapor-tight outer globes, and controlled by outside switches. No open light or light or flame of any kind whatsoever shall be allowed or used therein.

Every such establishment shall be provided with a tank not less than four feet long, two feet wide and three feet deep, which shall be placed near the entrance to the dry cleaning room and shall be kept filled with water.

2855. Handling of oils.] Tanks for the storage of any one or more of the oils or fluids mentioned in section 2851 of this chapter must be placed outside of the buildings used for such dry cleaning establishment and must comply with the ordinances of the city of Chicago relating to the storage of oils. No such tank shall be built underneath any such building. Pumps or devices for the removal of the contents of such tanks, which are operated by hand power, and which have been approved by the fire marshal of the city of Chicago, may be placed inside of any such building. All gasoline used in any such building shall be conveyed to and from the same through closed metal piping; no open troughs shall be permitted. There shall be no piping or connection whereby any of the oils or fluids mentioned in this chapter may flow from the cleaning room into any public or private sewer, drain, catch basin or pit.

AMENDMENTS TO THE SANITARY CODE PASSED SINCE MARCH 13, 1911.

An Ordinance, Passed November 20, 1911, Amending Section 2854 of The Chicago Code of 1911.

Be it ordained by the City Council of the City of Chicago:

Section 1. That the first three paragraphs of Section 2854 of The Chicago Code of 1911, being all that part of said Section 2854 before the paragraph beginning, "All doors in any such building," be and the same are hereby amended so as to read as follows:

"2854. Building Requirements—Ventilation—Equipment—Lighting—Water Trough.] Every building used or intended to be used for the purpose of conducting or carrying on the business of dry cleaning as defined in this chapter, shall be constructed and equipped according to the following specifications:

Every such building shall be built of brick, stone or concrete, with no basement, and shall not exceed two stories in height; provided, however, that the use of any building not exceeding three stories in height, in which a dry cleaning business was carried on prior to the passage of this ordinance may be continued, if such building complies in all other respects with the provisions of this chapter. The first floor of such building shall be higher than the surface of the ground surrounding such building, and shall be so laid that there shall be no space underneath the same. The floor or floors and roof shall be of fireproof construction. There shall be no openings through the floors, excepting in two-story buildings, in which a stairway leading from the second floor to the first floor may be permitted, if properly enclosed with walls of incombustible material. Such stairways shall lead to the outside of the building without any doors or openings leading into the dry cleaning room. Every such building shall be detached from all other buildings; provided, however, that the use of any building in which a dry cleaning business was carried on prior to the passage of this ordinance may be continued where such building is separated from all other buildings by a fire wall, with no openings into any adjoining building. Such building shall not be occupied for any purpose other than the conduct of a dry cleaning and dry room plant. The walls of such building shall be not less than twelve (12) inches thick and shall have vent holes at the floor line not less than sixteen (16) square inches in area when ventilation by means of exhaust fan or fans is employed, and not less than thirty-two (32) square inches in area when ventilation by means of paddle-wheel type fan or fans is employed; such vent holes shall be not less than six (6) feet apart, measured from center to center, and shall be protected by screens of thirty (30) mesh brass wire on the inside of such walls, and by iron bars or screens of large mesh on the outside of such walls.

Such building, unless divided into compartments, as hereinafter described, shall be further ventilated by means of an exhaust fan or fans of sufficient capacity to change the air in the building every three minutes, and shall be kept in operation at all times during the use of such building. Such exhaust fan shall be located in an air conduit whose inlet openings shall be at or near the floor level in the wall farthest away from any other building or structure, and the discharge end of such conduit shall be carried above the roof of such building. If such building be divided into fireproof compartments, by partitions of six-inch hollow tile, or equivalent, extending from floor to ceiling, each such compartment having a capacity of not to exceed twenty-five hundred (2500) cubic feet, the exhaust fan or fans and air conduit before mentioned may be omitted from each of such compartments, and in lieu thereof there shall be a paddle-wheel type fan attached to the line shafting in each compartment, of sufficient size to displace an amount of air equal to the cubical contents of the compartment at least once each minute."

Section 2. This ordinance shall take effect and be in force from and after its passage and due publication.

ROBINSON FURNACE CO.

Robinson Tubular Furnaces
Steam and Water Heating
Ventilating Systems

Phone Franklin 4400

205 W. LAKE STREET, CHICAGO

HEAT REGULATION

The Johnson Pneumatic System

THE RECOGNIZED STANDARD

Complete Systems for all Methods of Heating


Hot Water Tank Regulators
Reducing Valves for air, water, steam
Control of Humidity

Poised Mixing Dampers for two pipe systems

JOHNSON SERVICE COMPANY

H. J. GILSON, Mgr. Chicago Office, 177 N. DEARBORN ST.

The
DAVIS
Pressure
Regulator



One of the
Davis Steam
Savers

<i>Pressure Regulators—</i>	<i>Balanced Valve—</i>
<i>Back Pressure Valve—</i>	<i>Float Valve—</i>
<i>Exhaust Relief Valves—</i>	<i>Damper Regulator—</i>
<i>Steam Trap—</i>	<i>Pump Governors—</i>
<i>Stop and Check Valves—</i>	<i>Water Relief Valve—</i>
<i>Altitude Valves—</i>	<i>Receiver and Pump</i>
<i>Vacuum Pump Governor</i>	<i>Governor</i>

An
Illinois
Product

DAVIS VALVE
STEAM SAVERS SINCE 1875
SPECIALTIES

For
Illinois
Architects

Write to the G. M. Davis Regulator Co., 428 Milwaukee Ave.,
Chicago, for catalog showing all the Davis Valve Specialties
and explaining their various uses

Recognized as the standard for 33 years on all questions relating to the better utilization
of steam for heating purposes

WARREN WEBSTER & CO.

Main Office and Works, Camden, N. J.

ESTABLISHED 1888

Chicago Office, 715 Monadnock Bldg.

Phone Harrison 8500

Age + experience + organization service + perfect apparatus = Guaranteed Results

Webster Vacuum System of Steam Circulation
Webster Modulation System of Steam Circulation
Webster Feed Water Heaters, Purifiers and Filters

Webster Steam and Oil Separators
Webster Expansion Joints

MEASURING VENTILATION

By E. VERNON HILL, Aerologist.

Division of Ventilation, Department of Health.

The American Society of Heating and Ventilating Engineers recently adopted the Synthetic Air Chart as the standard method for determining the degree of perfection of air conditions in an occupied, enclosed space. The chart (designed by the writer) was offered to the profession some years ago as a means of measuring with a greater degree of accuracy than heretofore the air conditions maintained in any given room. Instead of speaking of the ventilation of a room as good, bad or indifferent, etc., the results of tests are plotted on the chart and the air conditions are recorded as a percentage of perfect. This is done by considering all of the known factors that make up the air conditions. These factors with their proper weights, experimentally determined, are arranged in columns vertically across the chart. The base of each column represents the ideal condition, or 100% perfect. Bordering on either side of the main columns are two narrow columns marked, "+ %" and "- %," the minus percent denoting the penalization to be subtracted from the percentage of perfect column and the plus percent denotes the condition considering only the one particular factor. These various factors are divided into three groups:

First, wet bulb difference, which includes temperature, humidity and air motion. Second, dust, bacteria and odors. Third, carbon dioxide which is considered in relation to the air supply. In addition, columns entitled "Other injurious substances" and "Distribution" are inserted. The upper limit of any of these groups represents the condition where life would cease to exist, hence at this point the "- %" column would indicate 100% penalization. (Since the upper ends of the columns represent conditions that are not found in practice they are not included in the chart.) The lower limit of any of these groups represents ideal or perfect conditions, hence at this point the "+ %" column is indicated by 0.

To illustrate the method of graduating the columns, consider the first, which is headed "Wet Bulb Difference." When at rest with no air motion the ideal wet bulb temperature is 56°. The upper portion of the column represents the unlivable condition, which is approximately 106° with 100% humidity. This gives a wet bulb difference of 50°. Any variation from 56° will, therefore, represent a definite percentage of variation from the ideal, 56° being 100% perfect or 0 in penalization, and 106° being 100% penalization and 0% perfect. The graduations in the other columns were constructed in a like manner.

After the values of all the factors have been determined by test the results are plotted on the chart by a heavy vertical line, preferably in red ink, $\frac{1}{8}$ " wide, and the height of the line will indicate the results obtained in the test. Penalization for all the

factors will then be read directly opposite the top of each line. All the minus percentages are then totaled and the sum subtracted from 100% to determine the percentage of perfect ventilation for the room as a whole. This result is plotted in the last column headed "Percent of Perfect."

The theory of the chart is to take all the known factors into consideration that influence air conditions and to indicate by the plotted lines how far these conditions vary from the ideal. Some may be satisfactory while others may be so far from the ideal as to bring the total percent below desirable. It is, therefore, easy to determine which conditions need correction. The ideal is 100% on the chart, while the unlivable is zero.




Chart of Test in a Tailor Shop.

The chart illustrated herewith is from a test in a tailoring shop in Chicago. The room tested was ventilated by means of windows on opposite sides of the room, north and south. The total window area is 600 square feet and the room is 100 by 80 ft., with an 11-ft. ceiling. Heat is supplied by direct radiation placed beneath the windows. There were 110 persons employed in the room, engaged in the manufacture of clothing. The chart gave a final percentage of nearly 82, which is too low for health and comfort.

The points to be criticized in the air conditions in the room are shown principally in the first and next to the last columns. The first column shows an exceedingly high wet bulb temperature, due to the use of gas heated irons. The next to the last column, namely, the distribution column, is also bad, as is frequently the case where particular attention is not given to this factor.

TELEPHONE MONROE 4714

R. B. HAYWARD COMPANY

Contractors and Engineers

VENTILATING AND EXHAUST SYSTEMS
SHEET METAL WORK — BOILER BREECHINGS

849-853 WEST OHIO STREET, CHICAGO

Phones: West 2470, 2471

Estimates Furnished

Narowetz Heating & Ventilating Company

GENERAL SHEET METAL WORK

*Heating and Ventilating
Apparatus*

*Contractors for Complete Ventilating
Systems*

LITTLE NIAGARA SANITARY AIR WASHER

Louis Narowetz, Pres.
Louis Narowetz, Jr., Sec'y

1711-1717 Park Ave., CHICAGO

Telephone: Seeley { 2765
2766

THE HAINES COMPANY

Blast Heating and Ventilating

CONTRACTING ENGINEERS

1929 to 1937 W. Lake Street

CHICAGO

Phone Belmont 227

Estimates Cheerfully Furnished

K. A. GUSTAFSON

CONTRACTOR

GENERAL SHEET METAL WORK

Hot Air Blast Heating and Ventilating, Sheet Metal Piping, Tanks,
Separators, Ventilators, Blast and Exhaust Equipments

2110-2114 N. Springfield Avenue

CHICAGO

FURNACE DESIGN

with Special Reference to Hand Fired Boilers and Limitations of Each Design

by FRANK A. CHAMBERS of the Smoke Prevention Association of America

The development of industrial centers brings with it the problem of abating the nuisance resulting from the emission of smoke from the chimneys of its power and industrial plants, residences, and apartment houses, and from the stacks or locomotives. Smoke, however, has no defense, its formation being primarily due to incomplete combustion or fuel, resulting from and due to defects in the operation, design or installation. Modern engineering practice has demonstrated that it can be abated.

The City of Chicago first recognized the desirability of legislating against smoke in 1881, when an ordinance prohibiting the emission of dense smoke was passed by the City Council. This ordinance was subsequently amended, until the ordinance as it stands today, was adopted. The ordinance uses the words "dense smoke" and for years the city of Chicago has considered this to mean smoke which cannot be seen through at the point of emission from the chimney. This does not mean that the smoke must be black in color or that it must be so dense that no light pierces through, but it must be so dense that an object placed on the side opposite to the observer cannot be clearly defined through the smoke.

CITY SUPERVISION OF FUEL BURNING EQUIPMENT

The ordinance provides that plans be submitted and permits be secured for new fuel burning plants and for the reconstruction and repair of old ones. This provision of the ordinance of 1907 was a new departure in municipal smoke prevention work and in planning this section the idea was that if any permanent and lasting good was to result, the details of the plant equipment must be carefully studied by competent engineers and every precaution taken to so construct that smoke might be prevented.

In determining whether a proposed furnace will smoke, three factors have to be considered.

First: The kind of fuel to be used.

Second: Attention to be paid to proper firing.

Third: Character of equipment for burning fuel.

The character of equipment is of vital importance in the smokeless operation of any boiler plant. Development of the smoke abatement work has shown that a great deal of Chicago's smoke was due to poor equipment and the successful application of supervision by the City, demonstrated by very pronounced reductions in the average density of smoke throughout the entire city, has proven that this third feature is most important and desirable.

If the elimination of smoke is to be brought about the general standard of equipment must be such as will make up for the natural fuel conditions, and allow for such carelessness in operation as is to be expected.

The requirements of the ordinance as regards equipment, for new and reconstructed plants, are very broad; the code merely stating that plans submitted shall indicate all provisions made for the purpose of securing complete combustion of the fuel used and

for the purpose of preventing smoke. It is left to the judgment of the smoke inspector to determine if these general requirements have been complied with and the standards existing today are the result of the knowledge gained through experience with the actual operating conditions. The three important items entering into this determination are—

First: Sufficient draft to burn the maximum amount of coal to be consumed.

Second: Sufficient space to properly operate and maintain the equipment.

Third: Properly designed furnace to secure complete combustion; all other requirements complied with.

The chimney height is determined by the amount of draft required at its base and this in turn is calculated from the sum total of draft over fire required, plus the losses encountered in boiler, setting and breeching.

Area of Stacks.

Quantity of gas to be handled and its velocity are the two main factors determining the chimney area. Velocities of from 10 to 40 feet per second are met in common practice. In stacks connected to heating boilers an average velocity of 10 feet per second, and in those connected to high pressure boilers, 25 feet per second, are good working averages. The free area of the stack at the smallest cross section should be not less than 1/5 of the area of the total connected grate surface, where the stack is less than 150 feet high. The rule used in determining stack area for Horizontal Return Tubular and Scotch Marine and Fire Box Boilers, is to provide an area equal to 125 per cent of the boiler tube area. A convenient method employed in calculating stack areas is as follows:

$$\text{Area of stack} = \frac{HP \times 55.08}{\sqrt{H}}$$

H = Height of stack.

Space Requirements.

It has often been said that the power or heating plant is the last thing thought of by the architect in designing buildings, and it is true that in most cases the least space possible is allotted for boiler equipment. As a result of this situation, there is seldom space enough for well designed furnaces, the breechings have unnecessary turns, firing space is limited, ventilation poor, and cleaning facilities faulty. In numerous plants in Chicago today which were erected prior to the time the ordinance required city supervision, lack of space is the stumbling block encountered in proper reconstruction and rehabilitation.

Fuel.

The ordinance requires a statement of the kind of fuel proposed to be used. The framers of the ordinance recognized that in certain classes of equipment it is desirable to use anthracite and semi-bituminous coal and agreements are entered into with the plant owners to permit the installation of boilers and furnaces which are limited to the use of smokeless fuels. These are called fuel agreements, and in general are restricted to the use of power boilers containing not

Telephones Main 3677, 3678 and 3679

Mellish-Hayward Company

Contractors and Engineers

213-221 West Austin Avenue

Ventilating, Hot Air and Blast
Heating, Cooling, Drying, Blast
and Exhaust Equipments, Lead Burning

Sheet Metal Piping, Breechings,
Tanks, Separators, Ventilators, etc.,
Air Washers, A. & J. Floor Sleeves

LIGHT OXY-ACETYLENE WELDING AND CUTTING

Phone Diversey 2952

The Monarch Ventilating Co.

Incorporated

SHEET METAL CONTRACTORS

Our Specialty Ventilating Systems for

THEATRES, HOTELS, RESTAURANTS, FACTORIES, ETC.

Boiler Breechings, Ventilating Stacks, Sheet Metal Work in General

1338 Sedgwick Street

CHICAGO

LICENSEE



NEW ERA

Fire Protection Engineers

INCORPORATED

CONTRACTORS

Automatic Fire Sprinkler Systems

716 W. Madison Street

CHICAGO

PHONE MONROE 4880

The Best

ALBERENE STONE

Laundry Tubs — Toilet Partitions

Laboratory Table Tops — Acid Sinks

Nonabsorbent — Positively Sanitary

INVESTIGATE — SEE US

ALBERENE STONE COMPANY

214-224 No. Clinton St.

CHICAGO

more than 250 square feet of heating surface and heating boilers rated at not more than 2,600 square feet of steam radiation and 4,100 feet of water radiation. In special cases, where circumstances warrant it, larger sizes are permitted under fuel agreements.

Stacks.

The chimney has often been called the heart of the plant and certainly plays an important part in its successful operation. The requirements regarding height and area are mentioned above but its location and relation to the boiler are very important, and these features are closely watched in examining boiler plans. In general, the requirements are that it be so located as to permit the installation of a well designed breeching with a minimum number of turns or angles. Attention is paid to the location and size of breeching opening in chimney to avoid downward pitches in breeching as it enters the stack, and to provide an opening approximating a square as nearly as possible.

Head Room.

Provide sufficient head room to allow for generous combustion space and to allow for boilers of ample capacity, breechings of good form, accessibility to manholes and valves, provision for meeting with the requirements of the building code in so far as protection against fire is concerned.

Floor Space.

Provide sufficient floor space for operating the furnaces, renewing the boiler tubes, cleaning the soot from the tube region, allowing for easy access to the furnace inspection doors, and that the location of the coal storage does not interfere with the operation of the furnaces.

Adequate Ventilation.

Plans and specifications shall show that the room or apartment in which such plant shall be located is provided with doors, windows, air-shafts, fans and other means of ventilation sufficient to prevent the temperature of such room, apartment, basement or other portion of such building, wherein such steam plant or apparatus is to be used, from rising to a point higher than 120 degrees Fahrenheit, and sufficient also to provide that the atmosphere of any such apartment, wherein such apparatus may be located, may be entirely changed every ten minutes.

Furnace Equipment.

The general policy first adopted by the smoke department was to determine by inspection of existing plants, whether or not they could be operated within the requirements of the ordinance with average care. By process of elimination certain constructions and types of equipment were eliminated and approval refused on those constructions.

Although this article deals with requirements for hand fired furnaces, certain of these are applicable to all fuel burning equipment. The department requires that mechanical stokers be used where new equipment is being installed in connection with all boiler units exceeding 250 boiler horse power, except as the nature of the fuel or other conditions exclude the use of mechanical stokers. For wood and refuse burning furnaces, hand fired equipment is acceptable. The department advocates and urges the use of auto-

matic stokers wherever conditions make them desirable.


Space and time do not permit a paper covering all types of hand fired furnaces with the numerous types of boilers in use in Chicago today. I will try to deal only with hand fired furnaces in connection with horizontal return tubular and horizontal water tube boiler, the latter being horizontally baffled. This embraces equipment as is used with such boilers as the Heine, Kroeschell, B. & W., EdgeMoor, Lyons, Casey-Hedges, Springfield, Keeler, and Oil City. The first item considered is the setting height. For best results from a smoke elimination standpoint, the heating surface should be set as near the fire as possible and still provide ample room for combustion. The result is better heat absorption and better combustion, with less smoke, due to lower initial furnace temperature with a resulting less violent distillation of the volatile matter in the coal. The space required between grate and heating surface should be such that there is no restriction to the expansion of gases in this region and no interference with the mixture of air and the combustible gases. The gases rise from the fuel bed in a vertical direction until the force of draft bends them toward the rear. They seldom impinge against the heating surface forming the roof of the furnace. The chilling from the adjacent heating surface has no material effect on combustion as there is a strata or film covering the shell that moves at a comparatively less velocity and is usually impeded by the roughness of the furnace roof. The setting heights are based on a requirement of 25 percent opening over the bridge wall and where this is an unrestricted opening, the height of boiler setting is equal to 25 percent of the grate length, plus the height of the bridge wall, less the pitch of grates. Bridge wall heights of not less than 18 inches are recommended and a grate pitch of not more than one inch to one foot of length are approved.

It has been found desirable, after experimenting with different setting heights, to reduce the distances between the grate and shell of the boiler to the standards that are being followed at the present time. This change proved desirable not only on account of smoke elimination but from a fuel-saving standpoint as well.

In the 1911 report of the Smoke Department are illustrated seven types of furnaces known as the Department No. 1, No. 2, No. 3, No. 4, No. 5, No. 6, and No. 7. It is interesting to note that development of smokeless furnace designs has eliminated all but one of these types, (No. 6) from common use. A new design, patented by H. Misostow, has been added to the list of departmental furnaces, and is known as the No. 8. Since its adoption, approximately 85 percent of the hand fired furnaces of the types being considered in this paper, have been of this design or a modification of it. The No. 8 construction consists of an arrangement of fire brick piers built in the combustion chamber.

The No. 6 which is popularly known as the Double Arch Bridge Wall Furnace, is an arrangement of brick arches forming retorts over the bridge wall and a deflection arch or diaphragm placed in the rear of the bridge wall. This type of construction has been in very common use in connection with high pressure boilers, and with reasonable care has been successful in smoke elimination.

American Outside Center
Packed Plunger
Boiler Feed Pump



One of our many patterns.
We make pumps for all kinds of service.

AMERICAN - MARSH


Steam and Power Pumps
Air Compressors
Centrifugal Pumps

AMERICAN STEAM PUMP CO.,

J. M. STANNARD, Mgr.

CHICAGO

1220-21 Monadnock Tel. Harr. 2300



Ric-Wil Underground Steam Pipe Conduit and Improved Drain Base


For the proper insulating of steam and hot water underground lines. Highest efficiency, shipped complete, and easy to install. Insulating material is moulded into the vitrified salt glazed tile. Send for complete catalogs.

Stannard Power Equipment Co.

CHICAGO

1220-21-22 MONADNOCK BLK.

Tel. Harrison 2300



Jennings Turbine Vacuum and Low Pressure Boiler Feed Pumps

ELECTRICALLY OPERATED.

MANUFACTURED BY

NASH ENGINEERING CO.

VERY SIMPLE and DURABLE

Especially Adapted for Vacuum Heating Systems

SALES REPRESENTATIVE

Stannard Power Equipment Co., Chicago

1220-21-22 Monadnock Bldg.

Tel. Harr. 2300

Yeomans Centrifugal Sewage Ejectors

Bilge Pumps, House Pumps, Condensation Pumps, Etc.


SHONE PNEUMATIC SEWAGE EJECTORS

STANDARD THE WORLD OVER


YEOMANS BROTHERS COMPANY

Phone Diversey 5600


1432 Dayton St., Chicago



LONGITUDINAL SECTION THROUGH "D-D"



PLAN SECTION THROUGH "C-C"



SECTION THROUGH A-A

SECTION THROUGH B-B

SECTION THROUGH A-A

DISPOSITION SHEET FOR DEPARTMENT NO. 6 FURNACE

A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23
24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46
47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69
70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92
93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115
116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138
139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161
162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184
185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207
208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230
231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253
254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276
277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299
300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322
323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345
346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368
369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391
392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414
415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437
438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460
461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483
484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506
507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	524	525	526	527	528	529
530	531	532	533	534	535	536	537	538	539	540	541	542	543	544	545	546	547	548	549	550	551	552
553	554	555	556	557	558	559	560	561	562	563	564	565	566	567	568	569	570	571	572	573	574	575
576	577	578	579	580	581	582	583	584	585	586	587	588	589	590	591	592	593	594	595	596	597	598
599	600	601	602	603	604	605	606	607	608	609	610	611	612	613	614	615	616	617	618	619	620	621
622	623	624	625	626	627	628	629	630	631	632	633	634	635	636	637	638	639	640	641	642	643	644
645	646	647	648	649	650	651	652	653	654	655	656	657	658	659	660	661	662	663	664	665	666	667
668	669	670	671	672	673	674	675	676	677	678	679	680	681	682	683	684	685	686	687	688	689	690
691	692	693	694	695	696	697	698	699	700	701	702	703	704	705	706	707	708	709	710	711	712	713
714	715	716	717	718	719	720	721	722	723	724	725	726	727	728	729	730	731	732	733	734	735	736
737	738	739	740	741	742	743	744	745	746	747	748	749	750	751	752	753	754	755	756	757	758	759
760	761	762	763	764	765	766	767	768	769	770	771	772	773	774	775	776	777	778	779	780	781	782
783	784	785	786	787	788	789	790	791	792	793	794	795	796	797	798	799	800	801	802	803	804	805
806	807	808	809	810	811	812	813	814	815	816	817	818	819	820	821	822	823	824	825	826	827	828
829	830	831	832	833	834	835	836	837	838	839	840	841	842	843	844	845	846	847	848	849	850	851
852	853	854	855	856	857	858	859	860	861	862	863	864	865	866	867	868	869	870	871	872	873	874
875	876	877	878	879	880	881	882	883	884	885	886	887	888	889	890	891	892	893	894	895	896	897
898	899	900	901	902	903	904	905	906	907	908	909	910	911	912	913	914	915	916	917	918	919	920
921	922	923	924	925	926	927	928	929	930	931	932	933	934	935	936	937	938	939	940	941	942	943
944	945	946	947	948	949	950	951	952	953	954	955	956	957	958	959	960	961	962	963	964	965	966
967	968	969	970	971	972	973	974	975	976	977	978	979	980	981	982	983	984	985	986	987	988	989
990	991	992	993	994	995	996	997	998	999	1000	1001	1002	1003	1004	1005	1006	1007	1008	1009	1010	1011	1012

A modification of this furnace for low pressure work, known as the Department No. 7, is also used to a considerable extent. The change from the No. 6 consists in building a drop arch over the grates at a point above $\frac{1}{4}$ of the grate length in front of the bridge wall. This permits of firing by the coking method, green coal being fired in large charges in front of the coking or ignition arch, and pushed back when thoroughly coked, before the next charge of coal is fired.

Other types of hand fired furnaces, which are patented and controlled by furnace contractors, are the Twin Fire Furnace, Down Draft Furnace, Foltz Smokeless Furnace, Chicago Tile Arch Furnace and others of special construction. In general, the requirements for these are similar to the department furnaces and the area of gas passages and provision for mixing gases conform to the rules laid down for the others.

Air Admission.

The basis of efficiency in combustion is a correct mixture of air with the combustible. This item, which has an important bearing on smokeless combustion is a matter given special attention by the department. Provision must be made for the admission of air over the fire and although there are a number of arrangements for pre-heating the air supply, and discharging it at various points in the furnace, a common practice is to cut a panel opening in the fire doors having an aggregate of four square inches per square foot of grate surface. These panels are usually fitted with a ratchet arrangement so as to allow the desired amount of air to enter over the fire.

Steam Jets.

Steam jets entering the furnace front above the firing doors and so installed as to syphon air into the firebox, are required on all types of hand fired furnaces where such mechanical mixers are necessary. When properly applied and operated, they assist in reducing the smoke to satisfy the requirements of the ordinance and should be so adjusted that the center line of the steam pipe, if extended, will strike the bridge wall


at a point six inches above the intersection of the grate and bridge wall. An automatic steam jet that operates in conjunction with the opening of the fire door is desirable, although not required.

The best combination of this kind is the one that adequately delivers the necessary air with the least possible amount of steam and so adjusted as to at least open automatically (for instance in conjunction with the fire door) and patented devices offer no advantage over that which any competent engineer is capable of installing.

By reason of the low cost of steam jets, they are very widely used to regulate smoke, but not without objection thereto. The steam jets are to be so directed that the center line projected immediately over the highest part of the fire will strike the bridge wall as near the rear end of the grate as is possible.

The so-called "smoke devices" of which there are a large number appearing on the market, and which must be held distinctly apart from construction of recognized merit, are not unqualifiedly approved by the department unless as much provision for smoke prevention is made as is incorporated in those furnaces above mentioned. These devices usually consist of special means for the admission of air and steam above the fire to create a condition where complete combustion may be obtained. The policy of the department has been that these devices do not in themselves meet the department requirements, although in conjunction with well designed furnaces they aid very materially, and their use is recommended.

The popular conception of a smoke consumer is a device that can be attached to a boiler or furnace and with its adoption will eliminate smoke. However, as all well informed engineers know, there is no device or apparatus or construction that is a cure-all for all smoke troubles, and their indiscriminate use is a serious mistake and leads to trouble. The best furnace is the one that meets the conditions to be encountered in any given case and supplies all the requisites for the proper functioning of this particular installation.



WOLFF Quality

PLUMBING

To the Architect, Wolff fixtures supply all the requisites a specification should include:

- 1—The perfected product that inevitably results from 65 years' continuous leadership in the field.
- 2—The sum of all manufacturing advantages and economies which are made possible by thorough standardization of design, together with large volume.
- 3—The solid *quality* which assures long life and low maintenance.
- 4—The unqualified approval of users everywhere.

Architects may always rely upon our assistance in working out any problem of plumbing specifications. Our catalogs and bulletins will be supplied freely on request, for your files.

**Wolff Sanitary
Enamelware—
Wolff Range Boilers**



**Wolff Potteryware—
Wolff Brass Goods—
Wolff Marble**

Established 1855
CHICAGO DENVER DALLAS OMAHA ST. LOUIS HAMMOND CINCINNATI

MODERN SANITATION OF BUILDINGS

By LEO H. PLEINS, Architect and Sanitary Engineer

The primary object of this article is to present to Architects in as brief a form as possible, data, which the writer trusts may be of service in their office practice in the preparation of plans and specifications covering plumbing work.

The great importance of sanitary plumbing work is daily becoming more and more recognized and hence if the Architect is to give his client full service, plumbing must be given the same careful consideration as the other structural parts of the building.

For convenience of reference the article is arranged under four headings—"Drainage of Building";—"The Water Supply";—"Arrangement of Toilet and Bath Rooms"; and "Plumbing Fixtures". Space does not permit of covering all that may be said under each heading, but endeavor has been made to mention characteristic features of importance, that should be given consideration in the proper analysis of each particular problem.

DRAINAGE OF BUILDINGS.

I. Proper Fall to Main Sewer. When a survey is made the location and size of main sewer should be indicated thereon. If stubs to curb are in place their location, size and grade should be shown. The basement floor grade should always be given and also grade of main sewer at curb or street. The desirable grade for house sewer connections is $\frac{1}{4}$ " to one foot. If this cannot be obtained, the grade may be reduced but in this case the size of the tile pipe must be increased according to the length of the connection from building to main sewer.

See Table I for carrying capacity of tile pipe at varying grades. Discharge is given in cubic feet per second. Convert this into gallons by multiplying by 7.50

FLOW OF WATER IN CIRCULAR PIPES, SEWERS ETC., FLOWING

FULL. BASED ON KUTTER'S FORMULA, WITH $n = .013$

Discharge in Cubic Feet per Second.

Diameter	Slope or Head Divided by Length of Pipe							
	1 in 40	1 in 70	1 in 100	1 in 200	1 in 300	1 in 400	1 in 500	1 in 600
5 in.	.456	.344	.288	.204	.166	.144	.137	.118
6 "	.762	.576	.482	.341	.278	.241	.230	.197
8 "	1.70	1.29	1.08	.765	.624	.54	.516	.441
9 "	2.37	1.79	1.50	1.06	.868	.75	.717	.613
Slope	1 in 60	1 in 80	1 in 100	1 in 200	1 in 300	1 in 400	1 in 500	1 in 600
10 in	2.59	2.24	2.01	1.42	1.16	1.00	.90	.82
12 "	4.52	3.74	3.35	2.37	1.93	1.67	1.5	1.37
Slope	1 in 100	1 in 200	1 in 300	1 in 400	1 in 500	1 in 600	1 in 700	1 in 800
15 in.	6.18	4.37	3.57	3.09	2.77	2.52	2.34	2.19

II. When Main Sewer is Above Level of Basement Floor Grade: In this case all drainage from floor drains or fixtures in basement must be run to a sump basin and elevated by means of a pump. If no water closets or urinals are to be installed in basement the pump will be described as a **bilge** pump. If water closets and urinals are to be provided in basement, the pump will be described as a **sewage ejector**.

Obviously all waste and soil lines that may be drained by gravity, such as all drainage from floors above the basement shall be run into a horizontal line and this carried under ceiling of basement and thence through the wall connecting to the main sewer at such

distance below grade as necessary to properly drain the system. The discharge from Bilge Pump or Sewage Ejector shall be connected into the horizontal line under ceiling of basement at such point inside of building as may be convenient.

If a Bilge Pump is installed—the basin for a single pump should be as follows: For pump from 10 to 30 gallons per minute, basin to be 30" diameter; for a pump from 50 to 100 gallons per minute, basin to be 36" diameter and for a pump from 125 to 200 gallons per minute, basin to be 42" diameter. For two or duplex pumps—basin to be 48" diameter for pumps from 100 to 125 gallons per minute and 60" in diameter for pumps of 150 to 200 gallons per minute capacity. All basins should be 36" deeper than lowest inlet entering the same.

If a Sewage Ejector is installed, the basin for a single ejector shall be as follows: For an ejector from 50 to 75 gallons per minute—basin to be 36" in diameter; for an ejector of from 100 to 200 gallons per minute, the basin should be 42" diameter and for an ejector of 250 to 350 gallons per minute, the basin should be 48" in diameter. For two or duplex ejectors, the basin to be 48" in diameter for ejectors of from 50 to 100 gallons per minute and 60" in diameter for ejectors of from 125 to 350 gallons per minute. All basins should be 48" deeper than the lowest inlet entering the same.

The best motive power for Bilge pumps or Sewage ejectors is a direct connected vertical type electric motor—the operation of which is automatically controlled by means of a float switch.

Wherever possible, both Bilge pumps and Sewage ejectors should be installed in duplicate sets. With duplex pumps the automatic control is arranged so that the same will start one pump when the water level has raised, holding the second pump in reserve, and starting the second pump when the first is not capable of handling all the water. Both pumps will then operate until normal condition has been restored. The automatic control should be provided with a four-pole transfer switch so connected up that by throwing over switch, each pump will operate at alternate periods, holding the other as reserve and in this way, equalize the wear on the pumps.

Always ascertain and specify the correct electric current and provide for service wires to within 5 feet of pump to be furnished by contractor for Electrical Work. If current is Direct give the voltage and if current is Alternating give voltage cycles and phase.

The motors for pumps are usually mounted on a cast iron or steel cover which forms a support for motors, contact apparatus etc. The basins may be of cast iron, steel, brick or concrete. If of the latter materials basins must be thoroughly waterproofed.

A swinging check valve, cast iron body, brass mounted must be placed in the horizontal discharge pipe between pump and sewer.

Blow-off drainage from boilers cannot be run directly into bilge pump or sewage ejector basins—but must always discharge into a cast iron or steel blow-off basin or muffler tank. From this basin the drainage may then be run to bilge or sewage ejector basins, if it is impossible to drain the same by gravity.

CLOW PLUMBING FIXTURES

ARE DESIGNED PARTICULARLY
FOR
SCHOOLS



MOZART SCHOOL, Chicago, Illinois
A. F. Hussander, Architect, Chicago



GROVER CLEVELAND HIGH SCHOOL,
St. Louis
Wm. B. Ittner, Architect, St. Louis

INDUSTRIAL PLANTS



TYPICAL TOILET ROOM. ARMOUR & CO., UNION STOCK YARDS, CHICAGO
Photo taken before closet partitions were placed
R. C. Clark, Architect, Chicago

HOSPITALS



OREGON STATE INSANE HOSPITAL
Salem, Oregon
Lazarus, Whitehouse & Foulhous, Architects



U. S. NAVAL TRAINING STATION
HOSPITAL, North Chicago
Jarvis Hunt, Architect

They Save 50% of Water Bills and Repair Bills
Let Us Send You a Catalogue

JAMES B. CLOW & SONS

534-546 So. Franklin Street

CHICAGO, ILL.

Boiler Blow-Off Basins:

These are usually included under the heading of "Heating Work." The contractor for this work makes all connections between same, boiler blow-offs, drips, etc. When directly connected to the house sewage line the plumbing contractor makes such connection as also the venting of blow-off basins through roof. Attention in this connection is called to the requirements of the Chicago Ordinance prohibiting the discharge from basins being made into tile sewers within any building, furthermore, that the water discharged into a sewer shall not exceed 120° "F." It is necessary therefore to use cast iron pipe and in order to prevent leaks of joints, therefore cast iron hub and spigot pipe should be made with iron cement instead of lead—or flanged pipe used with asbestos graphite gaskets.

The following Table (II) may be of service to determine the proper size of basin to be provided:

Table II.

- For Boiler of 25 to 75 H. P. use Basin 42" diameter by 60" deep.
- For Boiler of 100 to 200 H. P. use Basin 48" diameter by 72" deep.
- For Boiler of 250 to 400 H. P. use Basin 60" diameter by 72" deep.

For more than 400 H. P. use two or more basins—using the above as multiples according to horse power of boiler.

Downspouts and Downspout Drains:

In many localities the drainage from downspouts must be connected into a "Storm Water Sewer"—and not to the "Sanitary or house sewer." In either case arrangement of downspouts and drainage from same may be the same.

The best material to use for vertical inside downspouts is extra heavy cast iron pipe and fittings of proper size. All outside sheet metal downspouts should be connected into cast iron pipe and fittings above grade and cast iron pipe be run to proper depth below grade and connected to tile pipe by means of a cast iron quarter-bend.

Before making connection to roof—downspouts should be increased one size and the roof connection should be made to allow for expansion and contraction by means of a copper or lead sleeve. Roof fittings and strainers should be of cast iron and well flashed with copper or lead.

To determine the proper size for downspouts the following may be of service.

A rainfall of 1-inch in depth on an area of 100 square feet will give a run off of 62 gallons.

Downspouts proportioned as follows have been found in practice to give satisfactory results. For small roofs, 1 sq. inch in sectional area of the leader for each 150 sq. ft. of roof surface. For medium sized roofs 1 sq. in. in sectional area of the leader for each 200 sq. ft. of roof surface. For large roofs, 1 sq. inch in sectional area of the leader for each 250 sq. ft. of roof surface.

Judgment must be used in arranging downspouts so as to equalize the square feet of drainage as nearly as possible.

Outside downspouts should be avoided, especially in cold climates, as they are constantly giving trouble on account of freezing and therefore cause damage to roofs and walls.

Where roofs are covered with gravel or in localities where high winds are likely to cover roof with debris, etc., the downspouts should be provided with cast iron gravel basins or running traps with cleanouts. Gravel basins or traps must always be used when connecting downspout drains to sanitary sewers, where ordinances do not require such downspout drains to be run into outside catch basin as required by the Chicago ordinance.

Size of Main House Drain:

The size of the main house drain when serving as a combination drain (sanitary and rain water) may for all practical purposes be determined by the total surface area covered by the building or buildings and paved surfaces to be drained, by the following table, which is based on cast iron pipe. If vitrified tile sewer pipe is used the diameter of pipe as given must be increased one size for same area of drainage.

Square Feet of Drainage Area.

Diameter	Fall ¼ in. per foot	Fall ½ in. per foot	Fall ¾ in. per foot
4 inch	1,500	1,800	2,500
6 "	3,000	5,000	7,500
8 "	6,000	9,100	13,600
10 "	9,000	14,000	20,000

Back Water Valves:


Whenever the grade or size of sewer in street is such that there is a possibility of the same backing up—the house sewer must be provided with a cast iron back water valve of approved type and this valve should be placed in a manhole or otherwise located so as to be accessible for inspection or repair. It is desirable to use a back water valve having a flushing connection so that the line may be flushed.

Flush Tanks:

Whenever the sewer in street to which connection must be made forms what is known as a "dead end" it is desirable to provide a flush tank which when filled to a proper height with clean water, will automatically discharge the contents into the sewer and thereby keep the sewer free and prevent obstructions that might otherwise occur. These flush tanks may be of two types—as illustrated herewith. Type A being suitable for flushing more than one dead end; Type B may be used if the "dead end" will be continued at some later time—in which case the flush tank may be converted into a standard manhole by taking off the cap at end of siphon and removing the latter.

Soil Pipe System:

Cast iron extra heavy soil pipe and fittings is the most permanent and best system for this work and should be used wherever possible. It may safely be used for all buildings up to ten stories in height and while the regulations of some of the large cities required wrought iron screwed pipe and fittings to be used for buildings over seven stories in height—it is the opinion of the writer that it would be better to use screwed cast iron pipe and fittings for stacks and cast iron calked joint pipe and fittings for laterals in all buildings regardless of the height. If wrought iron pipe is used not less than 10 feet of cast iron pipe should be used for all vent extensions up through roof.



SECTION OF FLUSH TANK TYPE "A".



"Standard" Plumbing Fixtures

Standard Sanitary Mfg. Co.



Largest Manufacturers of Plumbing Fixtures in the World

**MAIN OFFICE & SHOWROOM: 14 N. PEORIA ST. (HALF BLOCK NORTH OF MADISON ST.)
CHICAGO, ILL. TELEPHONE MONROE 6400**

CHICAGO BRANCH STORES:

**NORTH WEST SIDE: 2337 N. CRAWFORD AVE.
OAK PARK: 260 W. MADISON ST.**

**SOUTH SIDE: 7234-38 STONY ISLAND AVE.
NORTH SIDE: 516-28 KEENEY ST., EVANSTON**



SECTION C PLAN OF FLOOR-TANK TYPE "B"

Simplicity in arrangement of soil, waste and vent stacks is desirable and it is extremely desirable to make diagrams of the system that will be of aid to the plumbing contractor as well as of being of service to the other contractors on the work. In order to be of service these diagrams must be accurately drawn and amplified by details where necessary.

The importance of a plumbing plan carefully laid out has unfortunately not been properly recognized. At the present time the cost of material is such that the Architect who is going to give his client the service for which he is paid—must more than ever consider every item that will form a part of the work.

The structural parts of a building are carefully analyzed, weights of steel columns, girders, etc., proportioned to the loads they must carry, and all this work carefully detailed—and still the plumbing work is very rarely even laid out beyond a mere indication of the main run of soil or sewer lines—on the basement or foundation plan.

Specifications very often contain a clause requiring the successful bidder to submit a piping plan for the Architect's approval before commencing work. They might just as properly contain clauses asking the successful bidders to submit details for the elevations of the buildings, etc., etc. It is the Architect's duty to secure the best proposition possible for his client and therefore the plumbing work should be drawn—detailed and specified in such a manner that all bidders on the work may estimate on the same fixed basis and not permit them to submit figures based upon their ideas and conception of what may be required for the work. Such methods are very unsatisfactory and can only result in misunderstanding and most frequently in absolute failure at the expense of the client.

Whenever wrought iron pipe and cast iron drainage fittings are used, either asphalted in and out or galvanized—the stacks should be placed in pipe shafts so that the piping may be inspected and sections replaced when necessary without disturbing walls and partitions. All vents through roof should be of extra heavy cast iron soil pipe for a distance of not less than 10 feet below. Never place wrought iron pipe under basement floors. All such drainage pipe must be of extra heavy cast iron soil pipe and fittings.

When the building covers considerable area—it is desirable to use cast iron or waterproof concrete catch basins on the main lines and at intersections so as to permit of rodding the lines. In place of catch basins—large cleanouts may be used—which must always be the same size of pipe up to 6". Such cleanouts should be placed in manholes with cast iron covers large enough so that the lines can be rodded properly. Cleanouts must be placed at the foot of all stacks and

wherever a change in direction of a horizontal line occurs. Cleanouts for best work should be of the heavy brass bell ferrule type with brass trap screw. With ferrules of iron the brass trap screw rusts in so that it is difficult to remove the same.

Changes in direction of horizontal lines should always be made on as full a sweep as possible, using Y-branches and 45° bends.

Connection between vertical stacks and horizontal drains in basement must always be made by means of Y-branches and 45° bends. Connection between horizontal lines on upper floors may be made by means of sanitary tees—although Y-branches are better.

All horizontal soil and waste lines should have a fall of $\frac{1}{4}$ " to the foot toward outlets where possible.

All horizontal vent lines must be pitched so that water of condensation will drain freely into soil and waste lines or stacks, and foot of all vent stacks must be connected into a main soil or waste line or stack.

Reventing of each plumbing fixture is generally required. The Chicago ordinance prescribes this; other localities permit circuit venting and hence, the Architect must necessarily familiarize himself with the requirements of ordinances that may be in force in the locality in which his building is to be erected.

All main vent stacks must be extended up through roof. On pitched roofs, the vents may extend above roof 6 to 12 inches, on flat roofs 18 inches to 2 feet will be better in order to be safe in case of heavy fall of snow and to avoid dirt entering same.

In the Eastern, Central and North Western States it is necessary to increase all vent stacks at least one size up to 6 inch before passing through roof. The minimum size vent through roof should be 4 inch. All extensions through roof must be cast iron. Increasing stacks makes it possible to turn down lead or copper flashing into the pipe and leaves the extension free to provide for expansion and contraction. While caps or vent cowls should never be placed on top of vent stacks, it is desirable to use a strainer of cast iron of a removable type. Galvanized wire strainers are worthless. See Drawing.

Lead wastes are infrequently used in modern practice so we will only briefly mention them. When lead waste piping is used—it should be of a weight known as "medium" and when connected to wrought iron piping the connection must be made by means of extra heavy brass soldering nipples and a good heavy wiped joint. When connected to cast iron pipe—extra heavy brass bell ferrules must be used, wiped to the lead pipe and caked into the cast iron pipe.

Joining of pipe must be carefully done. For cast iron soil pipe—the following is a good method:

1828 MOTT PLUMBING 1921



For almost a century the name of Mott
has been synonymous with the best in
plumbing fixtures

THE J. L. MOTT IRON WORKS

NEW YORK


CHICAGO

AND ALL PRINCIPAL CITIES



Office and Warehouse on trackage, Chicago, Ontario Street, West of
Orleans. Showroom, Monroe Building, 104 South Michigan Avenue

General Offices and Plant, Trenton, N. J.


The following illustrations show several methods for reventing plumbing fixtures in accordance with the Chicago practice and also by what is known as the "Circuit Venting" system.



All joints of cast iron soil pipe shall be made with oakum and pure pig lead, bedded with hammer and calking iron. A gasket of well packed oakum shall be placed at the bottom of the hub extending above the rim of the spigot to prevent the escape of lead. The hub to be filled at one pouring and the lead calked with such force as to make the joint absolutely water tight under a pressure of at least 10 lbs. per square inch. All



SINK STACK, USING F.W.
CAST IRON FITTINGS.



W.I. PIPE & DRAINAGE FITTINGS.


joints shall be filled at one pouring; if it fails to run full, it shall be dug out and re-poured. Lead shall not be covered with paint, putty or otherwise.

Twelve ounces of lead should be allowed for each inch of diameter of pipe or fitting on which joint is made.


Joints between lead and cast iron pipe to be made by means of brass ferrules wiped to the lead pipe and calked into hub of cast iron fittings. Joints between lead and wrought iron pipe to be made by means of soldering nipples with hexagon nuts. Joints between wrought iron pipe and fittings to be screwed home into couplings or fittings without the use of any red lead or other compound.

No steam or cast bushed fittings to be used on any drainage or vent work.

Joints of tile pipe shall be made with neat Portland cement. A cleaner to be run through every length of pipe as it is laid so that no mortar used in jointing will adhere to the interior of the pipe. The connection between cast iron and tile pipe shall be made with a collar of concrete 6 inches thick and extending not less than 8 inches on each side of joint. See illustration.



METHOD FOR JOINTING C.I. to TILE Pipe



In best work the pipe should always be of genuine wrought iron. Where cost is an item to be considered—steel pipe may be used—both kinds should be galvanized and fittings should be galvanized malleable iron—beaded. Plain fittings must never be used.


All soil, waste and vent piping shall be tested. Ordinances usually prescribe the manner of testing which may be by means of water, air, peppermint or smoke on new work.

WATROUS
PATENT
PLUMBING
FIXTURES
AND
DUOJET
WATER CLOSET

Cut Down Water Bills


Did you ever stop to figure out the daily waste of water from a single water closet? That is, if you are now depending on closets operating on the ordinary syphon jet principle, all of which require from 5 to 7 gallons of water for flush and refill, and even then, with uncertain results.

Multiply the waste from one closet by the number installed, and you will readily appreciate why the Watrous Duojet Closet is being substituted for syphon jet closets by so many progressive architects and builders.



Watrous Duojet Floor Closet. Note the two convergent jets and straight outlet passage.

The Watrous Duojet, using about half the amount of water that ordinary closets require—Flushes instantaneously—Uses every drop of water to clean; wastes none in building up a flush for a weak final action—Saves users the cost of thousands of gallons annually for each closet in operation—Conserves coal at pumping stations—Will not foul nor clog.



Watrous Duojet Wall Closet. Sectional view showing method of support.

The Watrous Line:—Duojet Closets, Flushing Valves, Urinals, Self-Closing Cocks, Drinking Fountains, Liquid Soap Fixtures, etc.—has become famous as the first radical improvement for years in this branch of sanitary science. Most efficient, economical and easy to install.

A request on your letterhead will bring the New Watrous Catalog giving complete data, roughing-in dimensions, etc.

Manufactured and Sold Exclusively by

The Imperial Brass Mfg. Co.

1200 West Harrison Street, Chicago

For good work both water and peppermint tests should be made and if it is desired to be absolutely certain that integrant traps of water closets, etc., are perfect a smoke test may be made after fixtures are set.

In alteration work a peppermint test must always be made.

THE WATER SUPPLY

There are so many failures in the water supply system of buildings that it is evident that little study is given the problem which is one of most vital importance.

In order to provide an adequate supply of water for the particular building it is necessary to analyze the actual requirements based on a per capita consumption per day—and another factor that enters into the problem is the pressure under which the water will be delivered.

Per capita requirements may be determined by the following tables, which are the minimum:

Schools (not boarding) 50 gallons per capita per day.

Industrial Plants & Factory Buildings—50 gallons per capita per day.

This does not include water that may be required directly in connection with plant operation in various manufacturing processes.

Hotels, Hospitals, Asylums, Sanitariums—150 to 200 gallons per capita per day.

Homes for the Aged, Orphan Asylums, Boarding Schools—Dormitories—100 gallons per capita per day.

To the above must be added water for sprinkling lawns, etc., which must be based on the flow in gallons per minute of each ¾" lawn sprinkler installed—allowing for a period of 3 to 4 hours for each sprinkler as a fair average.

Having determined the total quantity re-

quired for 24 hours—the next thing to determine is the proper pressure required for the work and in working this out the following must be considered:

If the average pressure is not sufficient to deliver water on the top floor of the building under at least 20 lbs. maintained pressure, it is advisable to provide a pumping system to increase the pressure so as to maintain an average of at least 20 lbs., on the top floor.

It is always advisable to install pumps in duplicate sets in larger installations.

Where city pressure is not constant and less than 20 lbs., it is advisable to install a surge tank from which the pump is supplied. The tank should contain not less than 10 times the water of the pump capacity per minute. Supply to tank should not be less than 2" and supply controlled by a float valve.

All pipe up to 2½" should be provided with unions with brass seats—for best work and for over 2½" flange unions should be used. Gaskets should be of "Rainbow" packing or better.

All fittings over 2½" should be flanged.

Valves should be heavy type brass double gate valves up to 2½" and iron body bronze mounted flanged end for larger sizes. Valves should be of the "rising stem" type for the reason that with this type it can be quickly observed if the valve is "open" or "closed".

For service pipe to building—extra strong lead pipe may be used for sizes up to 2½". For larger sizes cast iron hub and spigot water pipe of proper weight should be used. When cast iron pipe is brought into the building and up through floor the same should terminate in a flanged end fitting about 12" above floor.

The following tables may be used to advantage in determining the sizes of main and branch supplies for buildings:

Equalizing Table of Areas of Taps

PIPE SIZES, INCHES	1/2	3/4	1	1 1/4	1 1/2	2	2 1/2	3	4	5
1/2	1	1.7	2.8	4.9	6.6	11	15.6	24	32	65
3/4		1.	1.6	2.6	3.8	6.2	8.9	13.8	23	37.
1			1	1.7	2.3	3.8	5.5	8.5	14	23
1 1/4				1.	1.3	2.2	3.1	4.9	8	13.
1 1/2					1	1.6	2.3	3.6	6.2	9.7
2						1.	1.4	2.2	3.8	5.3
2 1/2							1	1.3	2.6	4.1
3								1.	1.7	2.7
4									1	1.6
5										1

Equalizing Table of Delivering Capacities of Pipes

DIAMETER, INCHES	1/2	1	1 1/4	1 1/2	2	2 1/2	3	4	5	6
1/2	2.27	4.88	8.49	15.8	31.7	52.9	96.9	205.	377.	630.
3/4		2.05	3.43	6.97	14.0	23.4	42.5	90.4	160.	273.
1			1.62	3.15	6.82	11.4	20.9	44.1	81.1	133.
1 1/4				1.69	2.67	5.91	11.6	23.7	47.4	78.5
1 1/2					1.26	2.31	6.13	13.0	25.8	39.2
2						1.67	3.06	6.47	11.9	19.6
2 1/2							1.83	3.57	7.12	11.7
3								2.12	3.53	6.35
4									1.81	3.02
5										1.65

Gallons per Minute Delivered From Circular Openings at Mains Under Various Net Pressures


HEAD IN FEET	Pounds-Pressure	1/4	3/8	1/2	5/8	1	1 1/4	1 1/2	2
10	4.33					33	56	91	131
20	8.66	5	12	21	32	46	82	123	185
30	13.09					57	101	158	226
40	17.42	7.5	16	30	46	66	112	182	262
50	21.65					73	130	206	290
60	25.95	9.	20	36	58	80	143	223	329
70	30.28					88	154	239	348
80	34.63	10	23	41	64	92	164	258	370
90	38.98					97	173	271	391
100	43.31	11	26	46	72	104	184	288	415
110	47.64					109	192	300	432
120	51.98	13	28	50	79	114	202	316	454
130	56.31					118	209	325	471
140	60.61	13.5	31	55	81	122	217	336	491
150	64.97	14	32	57	87	126	226	353	509

The following tables will be of value to determine the proper size of pipe to use to properly supply fixtures:

Stores & Shops.....	.75	gallons per minute per fixture.
Office Buildings.....	.75	" " " " " "
Factories	1.00	" " " " " "
Apartment Buildings.....	.5	" " " " " "
Hotels8	" " " " " "
Hospitals	1.00	" " " " " "
Schools8	" " " " " "

THE BRUNSWICK-BALKE-COLLENDER CO.
WHALE-BONE-ITE
 REGISTERED TRADE MARK


The Quality Toilet Seat



No. 23-91
 24" 9" WITHOUT
 COVER



No. 16-91
 16" 9" WITHOUT COVER



No. 18-59 FOR EXTENDED
 LIP BOWLS
 18" 59" FOR REGULAR BOWL




No. 21-9 FOR EXTENDED
 LIP BOWLS



No. 16-9B SPRING HINGE
 FITS ANY TYPE SEAT

CONSTRUCTION OF WHALE-BONE-ITE SEAT



CUT SHOWS
 No. 23-9 SEAT

D NOTE CONCEALED HINGE
 C NOTE HEAVY COVERING
 B RUNS LENGTHWISE
 A NOTE THE DOUBLE LAYER OF LAMINATION
 THIS RUNS ACROSS SEAT

Whale-Bone-Ité Toilet Seats

- Instill confidence of sanitation
- One piece, no joints
- Impervious, no hidden germs
- Bacteria does not remain on WHALE-BONE-ITE
- Unqualifiedly guaranteed against cracking, checking, warping
- No exposed metal parts top or bottom, patented hinge construction, rigid, fool proof
- Acid has no effect on its surface thus no disintegration
- A quality product positively fulfilling the service intended.
- Sold by all plumbing houses

If you cannot secure locally, write
 Seat Department of the makers.

THE BRUNSWICK-BALKE-COLLENDER CO.
 1623 S. WABASH AVE., CHICAGO

From this point on the supply piping shall be of galvanized genuine wrought iron or galvanized steel pipe according to the class of work.

Where the water supply from City mains cannot be relied upon as sufficient in volume or pressure to supply all fixtures in the building it will be necessary to provide for reserve storage to insure a constant supply, and there are two kinds of systems to be considered—First the one most commonly known, a tank on the roof, and the other and more recent—a compression tank system with a closed pressure tank in the basement. The roof tank system is obsolete and not recommended—for the reason that in order to maintain a pressure of 20 lbs. on the top floor it would have to be elevated 50 feet above the floor to give this result. Furthermore such tanks require special provision to be made for their support, must be enclosed and generally considered from a standpoint of efficiency vs. expenditure, are out of question at the present time.

The best system is a compression tank pumping system—which we shall briefly describe. These systems may be divided in two kinds—one where the pressure of the water is so low that all must be pumped and the other where it is only necessary to increase the pressure for the upper floors—in which case the system is known as the “booster” type.

In the first type the water may be delivered from a well, cistern or city main and depending upon the source of supply a pump designed for that special work must be used. Wherever possible, when pump is within suction lift of the water (20 feet) a centrifugal or turbine type pump with direct connected motor is the best to use. These pumps are of greater efficiency, less noisy and are more economical in operation than piston pumps.

In order to determine the proper size of pump to install we refer to the following table—which should be checked up with the per capita allowance per day previously mentioned.

To apply the above—First ascertain the number of fixtures pump is to supply—be sure to include every kind of fixture. In case any fixtures are supplied direct from city main these should be deducted. Second—Multiply the number of fixtures by the proper decimal that may apply according to the class of building.

The table is based upon an equal number of males and females. If the major portion of occupants are females increase pump capacity 25 per cent.

Where more than 150 fixtures are to be supplied pump capacity may be reduced 15 to 25 per cent.

Where actual water requirements have been determined (by meter or otherwise) furnish a pumping unit capable of discharging three times the actual quantity used.

Example—The total number of fixtures to be supplied by pump in an office building is 120. $=120 \times .75 = 90$. Therefore 90 gallons per minute which pump must discharge. Now to determine the head—The water must be elevated 100 feet and develop a pressure of 20 lbs. The actual head therefore will be 150 feet and to this must be added the distance of suction lift, if any, and allowance for loss of head by friction in pipe. If suction lift is 20 feet—this added to 150 makes a total of 170 and allowance for friction, 10 per cent, makes a total head of 187 feet against which the pump would have to work. The problem worked out in this manner and reference to standard catalogues of pump manufacturers will enable anyone to select the proper equipment.

When the system is of the second type or “booster” system—the head against which pump will work is determined by the following method:

Pump location to highest fixture...	100 feet
Range from minimum to maximum pressure	100 “
	200 “
Deduct City pressure 25 lbs. in feet	
—60	60 “

Pump required for a total head of...140 feet

Compression tanks should be installed of such size that the cycles of pump operation do not exceed three to four per hour. To insure this condition the tank should have a storage capacity of 25 to 30 times the capacity of pump per minute. To illustrate for a pump of 90 gallons per minute:— $30 \times 90 = 30 \times 90 = 2700$ gallons per tank— $1/3$ to $1/2$ of the storage capacity of tank should be filled with air—at maximum working pressure.

The hot water supply for the building should be determined upon the actual requirements to suit the conditions of each case.

For instance—in the case of a hotel with 100 bath rooms—each containing lavatory and bath tub or shower—the demand for hot water is at a peak load—from 6:30 to 8:00 A. M. and 4:30 to 7:00 P. M. with lesser demands at noon and later at night.

To provide for such service a minimum of 30 to 40 gallons should be allowed for each bath room per hour—this with 100 rooms would mean a heater having a capacity of 3000 to 4000 gallons per hour to which must be added the quantity that will be required for kitchens, laundry, etc.

Generally speaking the following table may be used to determine size of hot water supply systems:

Schools (not boarding):

- 5—gallons per pupil per day for water used in lavatories,
- 6—gallons per minute for each shower or
- 25—gallons for each pupil using the shower.

Hospital:

- 50—gallons per day for each person and add 50% of total for kitchen—laundry and general service.

Hotels:

- 50—gallons per day for each bath room and add 50% of total for general service.

If there is a Turkish bath in connection with the hotel add 100 gallons for each bather—based upon the capacity per hour of the establishment.

Apartments: Allow 100 gallons per day for each apartment having not more than 2 baths, for each additional bath add 25 gallons and 25% of the total for general service.

Factories: Allow 10 gallons for each employee per day for each wash basin and 25 gallons for each employee using showers.

Boarding Schools—Asylums—Homes, etc.: Allow 40 gallons per day for each person. For showers 25 gallons for each user and add 50% of the total for general service.

For smaller installations a hot water storage tank with steam coils for winter service and hot water heater for summer service makes a satisfactory installation. The tank should always be provided with a thermostatic control to prevent overheating the water. Tanks with coils should always have a manhole at one end.

In cases where the heating system is a vapor system, the water should be heated by means of a hot water heater the year around, as the pressure of the steam is too low to effectively heat the water by means of steam coils in the tank.

Where showers are used it is desirable to place a thermostatic hot water line control valve in the hot water supply main in order to prevent scalding. It is good practice to separate the system in Hotels, Hospitals,

QUATURN

THE ULTIMATE FAUCET



No one would buy an automobile that had to be junked when the tires give out —

Yet some people still buy faucets that must be consigned to the scrap heap when the seats are cut.

Very few people will buy a car with clincher tires. It means work and inconvenience to change inner tubes on the road in case of puncture —

Yet some people will accept as mechanically correct faucets in which it is difficult and inconvenient to renew the seat.

Every one wants an automobile equipped with demountable rims so that a spare tire can be carried, ready for use at any time in case of trouble.

Everyone should have faucets with renewable seats embodied in a working UNIT which can be carried in reserve just as the spare tire is on the car. The architect can secure such faucets for his client by specifying

QUATURN

THE FAUCET WITH THE UNIT CONSTRUCTION

THE CHICAGO FAUCET CO.

2712 NORTH CRAWFORD AVENUE — CHICAGO

DOWNTOWN EXHIBIT:

Building Material Exhibit, 15 East Van Buren St., Chicago

etc., so that the water supplied to bath tubs, lavatories and showers is controlled in this manner. It not only prevents possible scalding but saves fuel and increases the life of valves, faucets, etc., which excessively hot water materially shortens.

In larger installations—especially where both exhaust and live steam (high or low pressure) are available; the hot water system should be arranged in two units; the first a storage tank of proper size, called the primary heater, in which the water is heated by exhaust steam—from this heater it passes to the secondary heater which is provided with coils supplied by live steam under thermostatic control. The latter heater brings the water up to the desired degree of temperature at which the control is set.

Another and most economical type of heater is the instantaneous type—heated by low or high pressure—controlled by an automatic thermostatic device and using only such quantity of steam as necessary to heat the water actually used—to the temperature for which the control is set. This type of heater is very efficient and economical and is especially adapted to large installations as Hotels, Hospitals, Factories and wherever there may be a large variation in the demand for hot water throughout the day or night.

In order to ensure proper results, hot water systems must be in perfect circulation—wherever possible the overhead type system should be used with a riser to the top floor—horizontal supply mains and drop supplies to the fixtures on floors below with circulating return in basement. Hot water riser should have an air vent trap at highest point.

Pressure of hot and cold water systems should always be the same.

In some cases circulating pumps are necessary. These should always be of the centrifugal type with low speed motors and if direct current is available, motors should be provided with a variable speed control.

In conclusion of the suggestions for water supply system—I would say that in my experience most mistakes have been made in having the piping system too small and this is especially true in the case of hot water tanks and heaters.

A heater too small for the service will waste more fuel than one too large.

ARRANGEMENT OF TOILET ROOMS AND PLUMBING FIXTURES.


Few Architects realize how much the cost of the plumbing and heating on a building is governed by the design and location of toilet rooms. Many buildings are up several stories before the location of pipe chases or shafts are decided upon and many botched up piping jobs are the result of this neglect.

This again brings up the great need of proper plumbing plans and diagrams—showing the proper size and location of the piping and permitting the general contractor to provide chases in walls—leave openings in floors and provide pipe shafts of proper size for the work.

In residences with wood studs the partition carrying soil pipe must have at least 6" studs and a still better arrangement is to have a hollow space and use 4 or 6" studs flat wise and framed once or twice in their height as this saves cutting of studs for horizontal vent pipes.

If partitions are hollow tile, 6" thick tile should be used. Thin partitions of Mackolite, Pyro Bar or similar gypsum materials make very unsatisfactory partitions for concealment of piping, as no secure anchorage can be had in same for bolts to fasten hangers or brackets for fixtures; furthermore, condensation on pipes dissolves sulphuric acid in gypsum and induces quick corrosion of metal.

With buildings of fireproof construction in which the floors are of reinforced concrete the location of bath and toilet rooms must receive careful study.



TOILET ROOMS WITH WORK-VENT SPACE BETWEEN SAME.

There are three schemes that may be used.

The first, a pipe shaft 2'-6" to 3' in width extending up through the building—in which all piping may be placed and fixtures all provided with wastes and supply connections to wall. (See illustration.) This arrangement is very desirable for Hospitals, Schools, Hotels, Office Buildings, etc.; it makes an ideal arrangement and is economical in cost of installation and maintenance. All pipe being exposed it is easily gotten at in case of repairs.

The second is to raise the floor of toilet rooms 7" to allow for piping being concealed in floor. This is sometimes objectionable and in the case of Hospitals, Homes and Institutions should not be done.

The third is to run the piping under the ceiling of room below—either exposed or concealing the same by furring down the ceiling.

In planning toilet rooms it is most important to ascertain the exact size of the various fixtures that are to be installed—so that these will be placed properly and to the best possible advantage.

This is especially necessary in the case of bath tubs and shower stalls. If recessed tubs are used, the exact length overall, distance the ends and back will extend into wall must be considered as there is always a difference between the nominal size of bath tub and their actual overall length; the end at which the waste and supply fixtures are to come should be shown and a paneled door of proper size provided so that the fittings can be properly installed and accessible in case of repairs. When recess tubs are used—it is always desirable to tile around the top of tub, as this makes a more permanent installation than a finish of hard plaster.

Shower stalls should never be less than 3'-0" x 3'-0" inside for a comfortable stall. 3'-2" x 3'-2" is the standard size adopted by plumbing manufacturers and should be used wherever possible. Stalls should be at least 6'-6" high. Solid porcelain receptors, grooved to receive marble partitions are the best and are absolutely leakproof. If marble floor

THE INCOMPARABLE NIEDECKEN MIXER

PATENTED

A Bath Tub or Shower Supply Control


Simplicity of Construction

Ease of Repair


Economy of Hot Water




CONCEALED MIXER
INSTALLED



CHINA HANDLE AND DIAL
REMOVED. THE ONLY
TOOL REQUIRED TO TAKE
THE MIXER APART IS A
SCREW-DRIVER



COVER REMOVED, GIVING
ACCESS TO VALVES AND
SEATS



VALVE SEATS ARE RENEW-
ABLE AND EASILY RE-
PLACED

NIEDECKEN SHOWERS

Niedecken showers are operated by the Niedecken Mixer Control. They have stood the test of time and are giving satisfaction under trying conditions in the largest shower installations in the world.

HOFFMANN & BILLINGS MFG. CO.
MANUFACTURERS SINCE 1855.
MILWAUKEE, U. S. A.

slabs are used they must not be less than 2" thick and should be grooved all around to receive marble partitions.

It is desirable to place the controlling valves to shower head on one side of the stall near the entrance (see adjoining illustration), so as to permit the water being turned on and tempered without wetting the bather. When a stop valve is placed in the supply to the shower head, it will be necessary to provide the hot and cold water supplies with check valves to prevent the by-pass of water from either side in event that the valves on inlet of shower are not entirely closed. When there is no valve between the inlet valves and the shower head, check valves are not absolutely necessary.

All shower heads should be placed 6 feet above floor; provided with an adjustable ball joint by means of which the angle of the shower head may be changed as desired. Shower heads arranged in this manner give better results and will not wet the bather's head unless he so desires.

When thermostatic or anti-scalding shower valves are used, it is always desirable to place on the hot and cold water supply line for each, a loose key compression shut off by means of which the supply can be controlled, which is necessary if the pressure is very high or the pressures of hot and cold water are not equal.

When plain compression type control valves for showers are used in place of thermostatic or anti-scalding valves—a thermostatic hot water control valve should be placed on the hot water supply line to the showers and set so as to prevent the hot water exceeding 110° F. in temperature.

The placing of plumbing fixtures against outside walls should be avoided. It is very unsatisfactory. Even if the supplies are carefully covered there is always danger of freezing. The custom of placing bath tubs under outside windows is most objectionable. This has been commonly done in apartment house work. A little study of grouping would have produced better results.


In public toilet rooms the arrangement of water closet stalls must be well considered. Where a number of these are to be installed the size of the stalls must be determined. The adopted standard width is 2'-6" centers for schools—they should not be less—but may be more. For adults the stalls should be 2'-10". Three (3) feet is the greatest width that should be used. To make them wider would be waste of space. The depth inside should not be less than 4'-6" with doors swinging in. This depth will allow the standard width—2 foot door to well clear the front of the closet bowl.

In factory, etc., and school work, especially primary grades, it is better to omit doors entirely and in this case the stalls need not be more than 3 feet, or at the most 3'-6" in depth.


If possible all flush tanks, piping, etc., should be concealed in a work space in rear of closet stalls. The wall of work space being formed by the backs of partitions or a built up wall as desired. Frequently this same work space is also utilized as a vent space, providing the back of each stall with a vent opening, protected by a ventilating hood or register face. This makes a most desirable arrangement for ventilating large toilet rooms—especially adapted for schools, asylums and all public toilet rooms.

The water closet stalls may be of marble, slate or steel according to the class of work. Steel partitions are very satisfactory and excellent for school and factory work.

The bottom of all partitions should be 12 inches above the floor. When marble is used the pilasters should be 1½ or 2 inches thick and grooved to receive the partitions. The backs should be cut out to receive the partitions and a top rail of marble corresponding in thickness to the pilasters and 3½ or 4"



PLAN



SECTION

high extend along the entire front. The bottom of rail should not be less than 6'-6" high for schools and 7 feet for public toilet rooms. This arrangement does away entirely with brass floor and top standards and all metal angles—very desirable for the reason that nickel plated brass work becomes tarnished very quickly and is rarely given the care it requires to keep the same in good condition.

If wood doors are used they should preferably be of the type known as "sanitary", perfectly flush without panels. The standard size is 2 feet wide, 5 feet high and 1½" thick. They should be provided with an adjustable N. P. box spring hinge and blank with check, door latches and stops and should always swing in, with spring set to hold the door open when not in use.

Most Service per Dollar

AUTOMATIC
SERVES
ONE
SHEET
AT
A
TIME—
NO
WASTE



HYGIENIC—
BECAUSE
AUTOMATIC—
NO
PROMISCUOUS
CONTACT
WITH
MECHANISM,
ETC.

WITHDRAWAL OF A SHEET
AUTOMATICALLY
PROJECTS THE NEXT SHEET

UNINTERRUPTED SERVICE

WITHOUT MAKE-SHIFTS AND WASTE

IS SPECIALLY PROVIDED FOR IN
THE AUTOMATIC TOILET CABINET

A FRESH PACKAGE OF PAPER CAN BE HUNG IN THE CABINET
WITHOUT REMOVING OR DISTURBING REMNANT OF OLD SUPPLY

THIS EXCLUSIVE FEATURE PLUS

ITS OTHER SALIENT POINTS:

**CONVENIENCE—ECONOMY—
HYGIENE—AUTOMATIC SERVICE—**

READILY ESTABLISHES IT


THE PREMIER SERVICE OF ITS KIND

UTILITY SERVICE ASSOCIATION
UTILITY DEVICES OF MERIT

3100-12 CARROLL AVENUE
PHONE, KEDZIE 2685-2686
CHICAGO, U.S.A.



600 WEST 181ST STREET
PHONE, WADSWORTH 6523
NEW YORK CITY, U.S.A.



WATER CLOSET. WALL OUTLET.

While on the subject of water closet stalls a word of caution regarding the floor is apropos. It frequently happens, especially in school and factory work, that the floors of toilet rooms are pitched toward a floor drain and whenever this is done the contractor doing the flooring work should be cautioned to keep that portion of the floor on which the water closets are to set perfectly level and establish his break line at least 3 inches forward of the front of the base of the water closet bowls. Unless this is done the plumber when setting the bowls will level them up with cement in order to obtain an even bearing and the cement under the base of the bowls either causes them to crack on account of unequal expansion and contraction or because of improper support throughout the entire base, the unequal strain on the ware will cause cracks.

For connecting water closets to soil pipe or fittings only cast iron bends of an approved type should be used—with a gasket of asbestos, graphited.

Now as to the type of water closets to be used. There are today practically only two styles—one known as a siphon jet bowl, the other a washdown with jet. There are of course a large number of various special type bowls in the market but they are modifications of the above types.

The siphon jet bowl is the best to use on account of its more quiet action in flushing and also for the reason that the interior of the bowl presents less fouling surface, owing to the larger water surface.

The greater the cross-sectional area of the siphon limb the better the operation of the bowl. The minimum diameter of the siphon limb should be $2\frac{1}{2}$ " and 3" is better. The more uniform the passage is the less danger of stoppage. All bowls should be tested out under water before shipment by the manufacturer—for two reasons: one to determine whether the ware is free from cracks—called "dunts" by the potteries, the other to be certain that the construction of the bowl is perfect.

In many localities the water contains incrusting ingredients that may cause clogging up of the jet tubes in time. Such conditions may be remedied by emptying the water contained in the bowl and pouring a pint or more of "Commercial" Muriatic acid into the bowl. The acid will dissolve the solids in the jet opening in about $\frac{1}{2}$ to $\frac{3}{4}$ of an hour.

However, where the water is extremely bad—it is advisable to use the washdown type of bowl with jet, which is not as apt to become stopped up as the jet openings are

larger than in the siphon jet type and the tube has no pocket in which deposits can accumulate.

Where it is necessary to practice economy in the selection of fixtures—it is advisable to use washdown water closets with jets. For Schools and Factories this style is generally used.

There is another type of closet used today which is a composite of the siphon jet and washdown bowls. This bowl is known as the "reversed trap type" and when correctly designed and properly made, makes a very satisfactory closet. It has less fouling surface than the washdown bowl and is siphonic in action.

The conditions that are to be met in each case must necessarily determine the particular kind of closet that should be used. Also whether the bowls should have extended lips, floor or wall outlets, have low down tank, or flush valves or flushed automatically by seat operating valves. No fixed rule may be prescribed for such selection, which can only be made according to requirements of the work itself.

In the selection of water closets consideration must be given as to the manner in which the closets are to be flushed. Water closets with high tanks or low down tanks require a $\frac{1}{2}$ " supply connection, whereas these fixtures if operated by means of flush valves—require 1 to $1\frac{1}{4}$ " supply connections to each flush valve. Water closets with automatic seat operating valves require $\frac{1}{2}$ " supply connections as a rule.

Where there is more than one water closet in a row or battery, the main supplies for such battery must be of a size that will adequately supply all fixtures. Reference to the following table will be of service:

Table of Branch Supplies for Water Closets.

The following table will be of service to determine the proper size of branch supplies for water closets from 1 to 12 fixtures in a battery. The size of pipe is based on a pressure of from 20 to 40 pounds.

For Automatic Seat Operating Water Closets or Water Closets with Low-Down or High Tanks

Number of Closets	Size of Branch, Inches
1	$\frac{3}{4}$
2	$\frac{3}{4}$
3	1
4	1
5	$1\frac{1}{4}$
6	$1\frac{1}{4}$
7	$1\frac{1}{2}$
8	$1\frac{1}{2}$
9	$1\frac{1}{2}$
10	$1\frac{1}{2}$
11	2
12	2

Each branch connection to closet valve or tank shall be $\frac{1}{2}$ inch.

For Water Closets with Flush Valves

Number of Closets	Size of Branch, Inches
1	$1\frac{1}{4}$
2	$1\frac{1}{2}$
3	2
4	$2\frac{1}{2}$
5	$2\frac{1}{2}$
6	$2\frac{1}{2}$
7	$2\frac{1}{2}$
8	$2\frac{1}{2}$
9	3
10	3
11	3
12	3

Each branch connection to flush valve shall be $1\frac{1}{4}$ or 1 inch, according to style of valve used.

Telephones Main 2002; Main 2003

M. J. CORBOY CO.

Plumbing, Drainage, Gas-Fitting

178 W. RANDOLPH STREET

CHICAGO

TELEPHONES, MAIN 1972-5354-5355

HULBERT & DORSEY

Plumbing Contractors

208 N. WELLS STREET

CHICAGO

P. M. MURPHY, President

R. E. MURPHY, Secretary

Telephone Harrison 4598

MURPHY PLUMBING CO.

CONTRACTORS FOR
PLUMBING

GAS FITTING and DRAINAGE

23 EAST CONGRESS STREET

CHICAGO

J. J. DALY

Plumbing Contractor

Our Facilities and Experience Assure Results

408-410 N. Wells Street

Telephone Main 4732

The water pressure must also be carefully considered for flush valves and automatic seat operating valve closets. For the former the minimum should be 10 lbs., and for the latter 20 lbs., at each bowl.

Consumption of water is another item to be considered. Tank closets will use 6 to 8 gallons per flush; those with flush valves from 8 to 10 gallons according to the pressure and automatic seat operating closets will only use $2\frac{1}{2}$ to 3 gallons per flush.

Now regarding urinals—At present there are four types. The solid porcelain urinal 18 and 24" wide which sets into floor and has a lipped extension base the top of which is usually set flush with floor. Then there is the old style wall hung urinals—either wash-down or siphon jet type. The enameled trough urinal and the slate or marble ventilated stall urinal with porcelain trough gutter set in the floor.

The first type mentioned is the one most generally used except for factory and school work. For the latter work the slate or ventilated stall urinal has several features in its favor. It is less expensive than the solid porcelain urinal and when equipped with a proper flushing device and a deep porcelain gutter carrying not less than 2" of water which is automatically flushed out periodically, makes a most sanitary fixture. The urinal is the most objectionable of all plumbing fixtures and unless it is properly ventilated and gutters contain a sufficient quantity of water for proper dilution of the urine, the fixture becomes a nuisance.

The Chicago ordinance does not permit of a urinal with gutters in the floor and I believe this a serious oversight. It permits of the use only of the solid porcelain, wall hung or lipped trough urinals. The two latter types are unquestionably inferior from a sanitary standpoint to a slate or marble ventilated urinal with a solid porcelain gutter and siphon trap.

When setting solid porcelain urinals into the floor a depth of 4" is required to bring the top of the drip receptor flush with the finished floor. Care should be taken to set

these in accordance with instructions of the manufacturers. They must never be solidly set in a cement grout; an inch or more of dry sand should be put under same and a strip of expansion joint composition placed on the front edge and exposed sides so the concrete sub-base of floor will not adhere. The finished tile, terrazzo or cement may be run up against the porcelain ware.

Regarding the other fixtures such as lavatories, sinks, slop sinks, etc., space will not permit going into details. The catalogues of manufacturers generally give all information necessary regarding same.

The only question of material interest to the Architect regarding these is the kind to be used. This in a measure may be determined by the class of the work itself.

For lavatories for first class work—only those of the best vitreous ware should be used. These are made in many styles and sizes. Enameled iron lavatories are not as desirable as those of vitreous ware.

For sinks—there are a large variety—solid porcelain, vitreous in certain sizes, enameled iron; slate, alberene stone and copper. "Liberty" silver and galvanized steel. Each has its especial field and the kind and size must be determined for each class of work.

Cost today, more than ever, is an important factor in considering the quality of plumbing fixtures that should be used. However, it would be very poor judgment to sacrifice quality of material in any line on account of cost. The work of the Architect is not for today, but for tomorrow, and he who builds well in all things will profit more than one who builds poorly, and hence, now more than ever skill in design and knowledge of materials and their proper use will be required of the Architect to secure results.

Nothing will cause as much annoyance and require as constant repairs as a poorly designed and cheap installation of plumbing. Repair bills are a constant reminder to the owner of mistakes made by the Architect, who failed to give in full the service for which he was paid.

PLUMBING DESIGN IN TALL BUILDINGS

By THOMAS J. CLAEFY

The tendency in the erection of modern hotels and office buildings is to increase the height. As the height of a building exceeds 8 to 10 stories, the effect upon water supply, plumbing and ventilation systems is immediately noticeable. In plumbing systems, the effect is noticed in the agitation of water in closet bowls and traps of other fixtures. When the height of buildings reach and even exceed 16 stories, the effect upon traps and plumbing fixtures becomes such that engineers and plumbers are forced to recognize the fact that something is wrong with the practice of installing plumbing systems. Little attention has been given the enormous striking force exerted by a column of water falling from the height of approximately 200 feet in a vertical pipe. The air compression in a plumbing system under such circumstances becomes so severe that the ordinary system of vents and revents as provided for in our present plumbing ordinance, seems inadequate.

There have been numerous examples of extreme air compression brought to the attention of the writer, brief reference to two of which will give some idea of what this means to the designing architect or engineer, as well as to the owner of a building.

One of the first of these was an 18-story office building in which the main toilet rooms were on the top floor. A 6" soil pipe carried off the waste and was extended through the roof, full size. A 3" vent pipe was connected into the bottom of this line, and extended through the roof where it was increased to 4". The revents for each individual fixture were connected to this vent pipe. In spite of all this, during periods of heavy operation of the main toilet room, the fixture seals were broken and water blown out of water closets and other fixtures onto the floors below the top floor.

TELEPHONE LINCOLN 8603-8604

NOBLE & THUMM

PLUMBING, SEWERAGE
HOT WATER, STEAM AND VAPOR HEATING

2313 LINCOLN AVENUE

Telephone Randolph 1614

G. ALBIN NILSON CO.

Plumbing Contractors

Warehouse and Material Yard
Roscoe St. and C. M. St. P. R. R.

Room 713-14 Ashland Blk.
155 N. CLARK ST., CHICAGO

Telephone Monroe 577

W. W. WATSON

CONTRACTOR FOR

**Plumbing, Gas Fitting, Drainage and Lead
Burning**

708 N. Carpenter St.

CHICAGO

At Milwaukee Avenue

INSTALLATION

REMODELING

TEL. LAKE VIEW 5668

TEL. GRACELAND 5774

WILLIAM H. GRIFFITH

Plumbing and Drainage

3656 Broadway, Chicago, Illinois

It became necessary to install an extra 4" relief vent pipe to take off the excess air pressure near the bottom of the line.


Another example was in a 10-story loft building in which the soil and vent pipes were installed according to the ordinance and similar in many respects to the installation just described. With the first heavy rain, and before the building was occupied, water was blown from the closet on the first floor almost half way to the ceiling. It became necessary immediately to provide relief, and the building being of concrete construction, the difficulty of cutting floors and extending a pipe through the roof seemed insurmountable. It was found possible, however, to obtain a connection near the outlet at the curb wall which discharged into a large receiving tank having an overflow to the street sewer. The necessary safety valve was provided, but it was a job that even the designing engineer was not proud of.

It is evident that the ordinary plumbing ordinance does not meet the requirements of the exaggerated conditions experienced in tall buildings. Plumbing ordinances specifying vent sizes, etc., were drawn in days when this type of building was in its infancy. We now see the necessity for revising some of the requirements specified in ordinances. It is not, however, a revision downward as many would think, but in the other direction. We know from experience and from tests,* that vent pipe sizes should be increased over those specified in our present plumbing ordinance. We are convinced that the main vent pipe should be at least as large as the soil or waste pipe which it serves and preferably a little larger, that it should be cross connected full size at intervals as shown in Figure (—), and should be connected in a specific manner at the bottom of the line. The latter is far more important than appears at first glance. From tests that were made at the University of Illinois, it was clearly demonstrated that the efficiency of a plumbing vent system depends largely on how this connection at the base is made. Unless provision is made to effectually separate the air and water at this point, there will be a seething mass of compressed air and water churned up in such a manner as to fill both soil and vent pipes and to prevent the passage of impounded air. By connecting in the manner shown in illustration, the falling water strikes the lower side of the fitting, and connecting nipple *a* to the horizontal extension, and follows the wall of the pipe. The air is released and escapes along the upper wall of the pipe *b* and up through the free opening of the vent *c*. This provides for the free escape of impounded air at the base of a vertical line of pipe and full sized cross connections at intervals above relieve pressure within the system by permitting a free circulation at much lower speed than is obtained otherwise.

The additional cost of these suggested improvements when compared with the total cost of the system are infinitesimal. We are sure that experience will demonstrate the justification for such expenditure.

There is no dependable data on proportioning pipe sizes of soil and vent pipes. Roughly speaking, a vertical pipe will carry off the discharge from any horizontal branch line, either singly or on separate floors. Therefore, the horizontal soil or waste pipe


carrying the largest number of fixtures determines size for the vertical to which it connects. Main vent pipes as previously mentioned, should be as large as the vertical soil or waste pipe which they serve and a size larger in buildings exceeding 16 stories high.



*Note—See report of tests at University of Illinois. Page 66, Proceedings 1916—A. S. S. E.

STANDARD VARNISH WORKS

HIGH-GRADE
ARCHITECTURAL
VARNISHES
ENAMELS
STAINS



STANDARD COOPER-BELL CO.
CHICAGO

Licensee and Western Manufacturer Standard Varnish Works' and
Cooper Bell Varnish Company's Products

VARNISHES, STAINS AND FILLERS,

By R. W. LINDSAY, CHEMIST

Only a few decades ago varnish making bordered on an occult art. The formulas and rule-of-thumb methods used by different manufacturers were so zealously guarded that the interest of others did not reach back of the finished product. Then the chemist entered the field. He made an exhaustive study of the properties given to varnish and its allied products by the different materials entering into their manufacture. Thus equipped, he was able to make products exactly adapted to all of the increasing number of purposes for which finishing materials are used. This means that to-day the architect can find excellent materials for any finish that he may wish to secure; but this bewildering variety of materials also means that he must give more thought than ever before to his selection. Should I specify an acid stain or an oil stain? Why should I use varnish instead of shellac on floors? These are samples of the hundreds of questions that can be answered intelligently only when the solution is based upon a comprehensive, organized knowledge of the materials available. And for the one who will delve deeply enough, it is a study as fascinating as it is profitable.

In considering the above subject it will be necessary to divide this treatise into four distinct classes in accordance with the title.

Stains.

The subject of stains may be divided into four parts, as follows:

- 1st.....Aniline Oil Stains
- 2nd.....Aniline Spirit Stains
- 3rd.....Pigment Oil Stains
- 4th.....Acid Stains

By the aniline oil stain is meant a stain made by the solution of an aniline color in some solvent such as benzol, solvent naphtha, turpentine, benzine, or in other words, an oil solvent. Often in combination with these aniline colors is used a considerable amount of asphaltum varnish in order to obtain certain desired results. There has always been, and still is, a great deal of doubt in the minds of most users as to just what is meant by an aniline color and when we consider the great number of organic compounds known as aniline colors, it is not strange that such is the case. By an aniline color we mean one derived from the chemical compound aniline which is found in coal tar. Aniline is then treated with various acids and other chemicals and we are able to form new compounds and from these compounds still other compounds, and it is these various new compounds which are formed that are the aniline colors of commerce. These colors vary in their solubility according to their composition and consequently we have aniline colors soluble in oil, aniline colors soluble in alcohol, aniline colors soluble in water and in addition we have also many aniline colors, which we may say are "forced" in their solubility, i. e., the aniline color may be only slightly soluble in a solvent such as benzol, but when combined with a fatty substance such as stearic or oleic acid, which is soluble in benzol, is carried into solution in this way. This latter fact accounts as you may readily understand for the non-drying nature of many of the oil anilines. The aniline color itself may be a material which would be perfectly dry, but of course, is not permitted to become so on account of the presence of these non-drying fatty acids.

The aniline oil stains have very strong penetrating powers and carry the dye far

into the wood. They may be used on both hard and soft woods, both open and closed grains, but naturally better penetration is secured in the softer woods. These stains, being perfectly clear and containing no pigment, produce a beautiful, clear, transparent stain, usually rich in color and beautiful to look upon. This beauty is of course brought out by the application of shellac and varnish.

In finishing a panel with a stain of this nature we find that the stain works very easily, giving a remarkably uniform effect and apparently is an excellent product. Shellac is then applied and later the varnish and the brilliancy of the stain is very much enhanced. Supposing that we have a panel finished up in this way and the same is allowed to be set aside for some time and then later examined, we are very much surprised to find that, first, instead of having a stain rich in color that a great deal of its depth has disappeared and left in many cases, a muddy effect. At any rate the stain has faded very considerably. Secondly we notice that the varnish itself has died down very materially and that upon scratching the varnish film, we have instead of a firm, tough finish, a finish which looks very much as though it were made entirely of rosin. This latter effect is due entirely to what is termed "Bleeding" of the stain due to the following conditions: The stain as applied, was, as stated above, composed of aniline colors soluble in benzol, turpentine and other solvents of a similar nature, and consequently upon application of the shellac over the stain, the alcohol penetrated into the pores and dissolved out a certain part of the stain and carried it into its own film. The varnish, then following, also having the power by means of its thinner, to dissolve this dye, picks up the color and carries it into its own film. These colors are extremely susceptible to this kind of an action and have been known to have carried sometimes through five or six coats of paint. There is one case, which has come to my attention, where there has been applied over a finish of this kind two coats of varnish and five coats of white enamel, yet after each successive coat of enamel has dried, the pinkish cast of the mahogany aniline stain has appeared and cannot be removed unless the entire finish down to the wood is taken off and the color itself removed. Naturally the layman in having his house finished and noticing the condition of his wood finish from time to time, detects the failing of the lustre of his varnish and immediately draws the conclusion that the varnish applied to his house is of an inferior quality and it is my presumption that the reputation of the varnish manufacturer has been harmed a great deal more than we realize by such conditions. Of course, many of the manufacturers of stains of this nature do produce what are called primers, which are supposed to take care of this "Bleeding" effect and no doubt these articles do retard the "Bleeding" very considerably, yet there are none which are absolutely free from this trouble.

In this same class of materials of a somewhat different construction, are the **spirit stains**. These, of course, are made by a solution of aniline colors in alcohol and only used to a very limited extent on account of the fact that they are extremely hard to work and apply evenly, it being almost impossible to apply a stain of this character on a large surface with any degree of evenness, and secondly, they are prone to work

Vitralite

THE LONG-LIFE ENAMEL

Vitralite is the long life enamel that lasts longer than paint outside or inside on wood, metal, concrete, plaster, brick or stone. In addition to the white, which may be had in gloss or eggshell, there are five tints in the gloss and three in the eggshell.

The tints are authoritative in color in that they harmonize perfectly with the prevailing modes in fabrics, wall coverings and upholstery. The white Vitralite will not turn yellow. Wherever the gloss is used it may be readily rubbed to a dull finish.

Be sure your files contain Vitralite specifications. Perhaps it would be a good plan to write for them today.

PRATT & LAMBERT, INC.

VARNISH MAKERS 72 YEARS

320 West 26th St., Chicago

	Factories	
New York	Buffalo	Chicago
	Bridgeburg, Ontario	

Save the surface and
you save all - *And a hundred*

PRATT & LAMBERT

VARNISH PRODUCTS

up into the shellac applied over them, so that it is almost an impossibility to get a good finish. They naturally "bleed" very considerably and have caused all kinds of trouble not only in this respect, but also in regard to their fading. Being used in such limited quantities as they are, it is not necessary to describe them further, but merely to state that they should be avoided.

The third type of stain mentioned above is what is termed **pigment stains**, and by such is meant one made by grinding of a pigment or pigments in oil, usually linseed oil, and its subsequent reduction with turpentine or some such vehicle sufficient to effect penetration. The pigments used in stains of this kind are:

Chrome Yellows
Chrome Greens
Carbon Black
Prussian Blue
Para Reds, etc.

and as you can readily see, their staining effects must be really due to the lodgment of the pigment within the pores of the wood. In reality they are nothing but a thin paint sufficiently reduced so as to penetrate the pores of the wood. These stains do not give as clear an effect as the penetrating stains nor do they penetrate the wood so readily, and consequently are limited almost entirely to soft woods where a sufficiently deep penetration may be effected. However, even though these stains are not quite as clear as the previously discussed class of stains, yet they are sufficiently clear to produce some very beautiful effects and when we consider the fact that they are practically non-fading, have absolutely no tendency to "bleed" and that the after results are consequently very much more satisfactory than otherwise, we must concede that they are far superior to any stain in which the after-results are very questionable. Furthermore, these stains being made upon a linseed oil base, have a tendency to preserve the wood and consequently are of material assistance in this way.

The third class of stains mentioned above are the **acid stains**. The term acid, applied to most of these stains is a misnomer on account of the fact that nearly all of these stains of this class are practically neutral in their reactions, i. e., they are not made by the solution of acids in water as the same suggests but are made by the solution of various dyes in water or a medium miscible with water. These stains are perfectly clear solutions and when applied to the work, they work very easily under the brush and may be spread out over large areas with a degree of evenness. Having been applied, and the work finished, they are very permanent as regards fading and have little tendency to "bleed".

The reason for the latter effect is due to the fact that the dye used is a water soluble product and consequently even though the vehicle of the varnish applied over the stain may penetrate into the wood, yet the dye is not picked up and consequently does not "bleed" into the successive coats of varnish. This point may be very readily illustrated by carrying out the following experiment: A panel, for example, is finished at one end with coat of mahogany aniline oil stain and at the other with a coat of mahogany acid stain and a coat of shellac is applied over the entire panel, followed by a coat of white enamel. Allow this panel to stand for a short time and the result is, that within a very short period of time, it will be noticed that the enamel over the aniline oil stain is covered with reddish spots, showing the way in which the "bleeding" has taken place. The enamel over the acid

stain has not been affected, thus indicating the "non-bleeding" nature of this stain. These acid stains produce beautiful, clear, transparent effects, are permanent and "non-bleeding" and are really the ideal kind of stain, but like many other materials which are so nearly perfect, they have one defect. This defect is due to the fact that when the water is applied to wood, the grain is caused to raise very materially and it is the sanding down of this grain, which restricts somewhat the use of the acid stain. The acid stain is confined almost entirely to the use of hard woods on account of the fact that the softer woods necessitate a large amount of sanding. The best practice is, of course, to sponge off the wood first, sand and then apply the stain and follow with another light sanding. In this way, the maximum amount of stain is retained in the wood and the effect is not spoiled. Notwithstanding this defect, however, these stains are really the most practical, most lasting and produce the most satisfactory results.

FILLERS.

This class of materials may be divided into two parts:

Liquid Fillers.

Paste Fillers.

When Liquid Fillers were first placed on the market, they were offered as substitutes for shellac and at that time the material sold as such was of far better quality than most of the so called Liquid Fillers of today. Today, most of these goods are composed of nothing more than Gloss Oil, a little Linseed Oil and the cheapest Pigment it is possible to get. All kinds of pigments have been used but the most satisfactory are either asbestos or China Clay on account of the property these pigments have of remaining in suspension. Notwithstanding the fact however, that the general run of Liquid Fillers has deteriorated so much, a few of the best manufacturers are producing goods for this purpose which really have quality. These goods are necessarily made so that they dry very hard and firm, carry sufficient pigment so as to fill the pores to a certain extent and give a surface which is very non-absorbent and over which the varnish may be applied in such a way as to have a good full body and lustre. This class of materials is not recommended for use upon floors or for exterior purposes on account of its extremely hard nature, yet for certain purposes, it serves in a very favorable way, and may be recommended.

The second type of filler is the **PASTE FILLER** and by this product we mean one sold in paste form and made by mixing or grinding together of certain pigments, linseed oil and a japan drier. The function of a paste wood filler is to close all the pores of the more or less open grained woods, so that, while the surface becomes non-absorbent, the natural beauty is not obscured, and if the wood is stained, the filler must not dull the transparency of the stain. Therefore, the more translucent the filling material, the more valuable the product. Consequently, while barytes, clay whiting and gypsum are still employed on account of their cheapness, the ideal material for a filler is silicic acid or silica. Silicic acid or silica is really powdered quartz, and is a pigment which is extremely transparent, has considerable "tooth," and consequently makes an ideal pigment for this purpose. A paste filler is generally made by merely mixing the silica and its vehicle, and is received by the consumer in paste form. This is reduced with turpentine, and is then ready for application. A good filler should be dry in twenty-four hours, and then sanded and dusted off, leaving a surface ready for the application of the material following.

Fillers are really materials to which suf-



*A LEAD Product
for
Every LEAD Purpose*

For Painting

Eagle Brand White Lead in Oil

(Old Dutch Process)

Red Lead in Oil

Dry Red Lead

Sublimed Blue Lead in Oil

For Construction

Eagle Brand All-Lead Roof Flange

Lead Pipe

Lead Traps and Bends

Plumbers' Lead Goods

Sheet Lead

Wedge Lead and Lead Wool

Descriptive literature sent on request.

The **EAGLE-PICHER**
LEAD Company

208 South La Salle Street, Chicago, Ill.

Manufacturers of White Lead, Lead Oxides, Sublimed White Lead, Sublimed Blue Lead, Babbitt Metal, Lead Pipe, Plumbers' Lead Goods, Pig Lead, Slab Zinc, Sulphuric Acid and Lithopone

ficient attention has not been given, and it behooves the architect to see that he gets the most translucent fillers possible even though the same costs him a little more, this extra expense being do doubt explained very largely by the fact that the pigment used is more expensive. Furthermore, the best grade of fillers always contain a good grade of linseed oil and a good gum Japan, the latter serving to harden up and to make the filler non-absorbent. Here, again, the use of a cheap filler necessarily means the use of a material containing a cheap japan which will have the effect of reducing the durability and stability of the filler. Colored fillers for various modern effects are, of course, made up by incorporating certain colors with the regular paste filler and some very beautiful results may be obtained.

VARNISHES.

This subject should be divided into two parts, as follows:

Spirit Varnishes.

Oil Varnishes.

After the wood has been properly filled, it is customary, both in architectural and industrial work, to apply a coat of spirit varnish. For many years practically no material was used for this purpose but shellac.

Gum shellac, as you are no doubt aware, comes to us very largely from India and is a resin produced by the vite or sting of certain insects on the small twigs of several species of East Indian trees. The resin appears to be formed from the plant sap by the female insect from whose body it exudes, ultimately burying the insect and her eggs and forming a thick excrescence on the twigs. This is collected, macerated with warm water to extract a dye and the residue (Seed Lac) is refined by melting and straining. It is then poured in thin films on wooden cylinders when it hardens and scales off in thin flakes and is then called "shellac."

Bleached shellac is made by passing a stream of chlorine gas into an alkaline solution of shellac. There are on the market a number of grades of shellac, due to the fact that during the melting process, rosin is added to facilitate the melting process. The result is that we have a great many products termed shellac which contain a very large proportion of rosin and many which contain absolutely no gum shellac.

Due to the extremely high cost of shellac there has come upon the market a large number of shellac substitutes and, as with all other varnishes, there are many which can be used with a high degree of satisfaction and many which are absolutely worthless. Most of the better grades of shellac are made by dissolving certain spirit copal gums in alcohol. On the other hand, there are a large number of shellac substitutes which are made on a rosin base or at least contain a large proportion of rosin so as to make a substitute which is satisfactory only from the standpoint of price.

To my mind, one of the most important points in an architect's specification is the question of the character of the spirit varnish which is applied over the filler; for the reason that, just as no house can be built with a foundation of sand, so no finish should be built up with a foundation coat which has no durability, is extremely brittle and has in fact no qualities to recommend it except that of cheapness. An architect in recommending a manufacturer's grade of substitute shellac has, of course, the assurance of the house manufacturing that goods that it will be satisfactory. On the other hand, as an architect specifies "shellac" and does not definitely specify as to the grade of shellac, he cannot be certain as to the results. It might be well to suggest that if an architect desires that shellac be used, he write a specification like that of the Government which compels the use of a shellac con-

taining no rosin nor other adulterants. With the extremely high cost of shellac at the present time, architects will find it well worth their time to consider shellac substitutes made by reputable manufacturers for work where it is not necessary to secure the very highest grade of finish.

We now come to the subject of Oil Varnishes, and in taking up this matter we will discuss the various materials used in varnish making and follow this with a brief description of the process itself.

Varnish has four main constituent parts.

First: The fossil resins, or gums, as they are termed, which give to the varnish its brilliancy and lustre and to a certain degree its durability.

Second: The drying oils which render the varnish elastic, durable and to a certain extent affect the lustre.

Third: The metallic driers which are incorporated with the oils to hasten the drying of the varnish film, acting as carriers of oxygen from the air to the drying oil.

Fourth: The volatile solvents which aid in the spreading of the varnish upon the work.

First we shall take up the various raw materials used in making varnish, and describe the source from which these various materials come, and then later, the way in which these materials are used in the actual varnish making process.

The first of the raw materials to be considered are the resins, which are divided into three classes. We first have the fossil resins, which are the exudation of trees which existed thousands of years ago, the sap having flowed from the trees to the ground where it was covered with decayed vegetation, etc., and fossilized. Second, we have the semi-fossil resins, which are the exudation of trees of more recent origin, and third, we have the crop resins, which are gathered directly from the tree, the tree being cut in such a way that the sap will flow and this sap is hardened by oxidation.

Zanzibar Animi is a fossil resin coming to us from Zanzibar on the eastern coast of Africa, and is characterized by the goose skin effect which we find upon the various pieces of gum. The gum is extremely hard, and was formerly used in the manufacture of our best grade of piano varnishes and interior varnishes. It was used in the piano varnishes on account of the fact that it makes an extremely hard varnish, and one which may be readily rubbed and polished. It was used in the spar varnishes on account of the fact that it made a varnish which was very durable. This resin is not used today on account of the fact that it is practically impossible for us to obtain sufficient quantities for use in a practical way.

The next resin is that of the Congo Copal, the term Copal being applied to the gum found upon the west coast of Africa, to differentiate between these and the ones found on the east coast of Africa, of which the Zanzibar is a type. The Congo Copal is very light in color, makes a varnish which dries with a good hard film, and is used in large quantities in high grade varnishes. For this reason it is used in high grade baking varnishes and interior varnishes where color is an essential feature.

The Benguela Copal is very similar to Congo, coming from the same general district on the west coast of Africa, but differs in that the varnishes made from this gum are darker. The Benguela is characterized by the greenish cast which is displayed throughout the various pieces of gum.

The Sierra Leone Copal is one of the most elastic resins known to the varnish maker. For this reason it has been used with wonderful success in the pale coach and car var-

A RICH, substantial, durable Enamel,
the choice of the homes of refinement and wealth—a perfected quality of 72 years of good paint making.



***Lucas* Seal Enamel**

Covers more surface than any other

MADE BY

John Lucas & Co., Inc.

1362 West 37th Street
CHICAGO

PHILADELPHIA

NEW YORK

BOSTON

PITTSBURGH

OAKLAND, CAL.



Hydrocarbon Paints & Compounds

Structural Iron and Steel Paints.
Insulating Paints
Acid Resistant Paints and Compounds
Dry Kiln Paints
Heat Resistant Paints
Plaster Bond
Roof Paint, Cement and Putty
Damp and Water Proofing

SEND US YOUR INQUIRIES

Ohmlac Paint & Refining Company

Refinery and Manufacturing Plant, Clearing, Illinois

GENERAL OFFICES: MARQUETTE BUILDING, CHICAGO

nishes and in spar varnishes, where elasticity is the most essential feature. At the same time it makes a varnish which has a very light color, and for this reason it is also very suitable for pale baking varnishes and also for varnishes where elasticity is a most important factor. This resin comes to us also from the west coast of Africa, coming from the district of Sierra Leone.

The next class of resins is the Kauri, coming to us from an entirely different region—from New Zealand. Kauri is one of the most popular resins in the varnish industry on account of the fact that by it may be made a most durable varnish, and also a varnish which is excellent for rubbing and polishing purposes, due to the fact that when this resin is handled properly varnish may be made which has less tendency to "sweat out" in the process of rubbing than a varnish made with other gums. Furthermore, Kauri has very good durability, and is consequently used in the high grade exterior varnishes. Kauri comes to us in various grades, ranging greatly in physical characteristics and price. The better quality Kauri, for instance, costs at the present time \$.90 per pound. The No. 1 Kauri costs \$.50 per pound, while the Brown Kauri costs \$.15 per pound. The varnishes made with these various grades of Kauri have, of course, the same general properties, yet differ so considerably that it is most important that the grade of gum be considered very carefully in the manufacture of a varnish.

The Manila Copal is a type of the resins which are termed soft resins, and comes to us mostly through the port of Manila, being found largely in the East Indies. White Manila is used a great deal in the cheaper interior and medium priced varnish, and when handled properly some very good results can be obtained. However, it carries quite a large amount of free acid and has the property of causing a varnish to have a softer film than one made with the Kauri or the other harder gums. Manila, like Kauri, comes to us in various grades, the best being the White Manila and a cheaper grade being the Manila Nubs, which is a form very popular with the varnish manufacturers on account of the fact that the Manila Nubs, being small pieces, are much easier to handle than the White Manila, which comes in extremely large pieces. The Manila gum is derived from one of the most prolific gum-bearing trees known, and some of the pieces of gum which have been found are very large in size, being sometimes two or three feet in diameter.

The Damar resin is a gum which is probably very familiar, having been used for years in the manufacture of Damar varnish. Its one important feature is its color, and that is about all which we can say for it. It has no durability, is very soft, and a resin with a very low melting point, so that it cannot be used in any of our high grade varnishes. Damar resin has been used for a great many years for the manufacture of white enamels and for a considerable length of time all the white enamels on the market were made upon this base. Today, however, the highest grade of white enamels contain no Damar on account of the fact that it is lacking in durability. We still, however, have a great many cheaper, quicker drying, and less durable enamels, which are made upon a Damar base.

The Asphaltum is not really a resin, being a cross between soft coal and petroleum, and comes to us largely at the present time from Utah. This bituminous material is used in the manufacture of our black air drying and baking japans, being used largely upon iron work.

While the above does not describe all of the resins which are used by the varnish-maker, yet it gives an idea of the various

properties which the varnishmaker obtains by using the different grades and kinds of resins, and we shall now proceed to give a brief description of the various ways in which these resins are gathered. As mentioned above, these resins are formed by a fossilization of the sap, which came from trees, which existed thousands of years ago, and it is of particular interest that many of these resins are found as deep in the earth as twenty or more feet.

The gum digging industry in the early days, particularly in New Zealand, was for many years carried on in a desultory manner, with the result that practically no gum was procured except that which lay on the surface. The gum diggers in the olden days would start out in the morning with what they termed their prodding stick and knapsack on their backs and by the use of this stick would determine places where the gum could be found. They would proceed to dig up the gum and carry it with them until evening, when they would sit around their camp fires and scrape the gum and prepare it for the market. Today, however, the gum digger is more like our modern miner. He starts off with his various prospecting sticks, his spade and coarse tooth saw, with which he saws around the roots and moss in order to unearth the gum. The surface of the earth, is then dug up and the gum and dirt thrown to one side. This digging goes on until at times we find diggers have proceeded to a depth of twenty feet below the surface of the earth in their search of gum. The gum is then thrown upon a screen, where it is washed and the earth and other decayed matter separated from it. The gum is then all scraped and sorted, and then carried down to a general warehouse, where it is further sorted and graded. The gum is then taken to the brokers' warehouse where it is further sorted by men who have wide experience in this line. These men start as mere boys, first working on the cheaper gums and then they are gradually promoted to work on the higher grades of gum. This is very important work when we realize the variations in its price. The gum is then put into bins, and from the bins is packed in cases, then shipped to foreign ports.

We now pass on from the subject of gums to that of oils, and the first oil we shall mention is, of course, Linseed Oil, which is made from the flaxseed grown in Canada, United States, Argentine, India, and around the Baltic Sea, and it is very curious to note that the oil from these various parts of the world should differ so much, due probably to climatic conditions and also to methods of harvesting.

The flax is cut in the field and the flaxseed is then separated from the flax stalk. This seed, in the case of that grown in our own country, is then carried to the various lake ports and comes down the lakes in large grain boats. The seed is then conveyed from the boats to the grain elevator, and is separated according to the various grades and the source from which it comes; it is then carried by means of large conveyors to the rolls. These consist of large steel corrugated rolls between which the seeds pass until they are entirely crushed into the form of a fine powder. This powder is then emptied into the tempering kettle on the floor below, where a certain amount of moisture and heat is applied by means of steam, the proper amount of moisture and the correct temperature being judged by the workman, who is very expert at this particular trade, gauging the temperature and moisture by the feel of the seed in his hand. When the powdered flaxseed is in proper condition the seed passes out under the "former" between two camelhair mats. It is then placed in the presses, the mats being one above the other and when the

W. P. NELSON COMPANY

Established 1856

N. J. NELSON, President

PHONE HARRISON

{ 5073
5074
5075
5076

INTERIOR DECORATORS

Painting and Finishing of Large Public
Buildings Our Specialty. Estimates, Schemes
and Designs Furnished Upon Request.

CHICAGO

614 S. Michigan Ave.

DETROIT

4403 St. Aubin Ave.

PITTSBURGH

712 Oliver Bldg.

NEW YORK

268 W. 40th St.

FRANKLIN MARLING Jr., Pres.-Treas.

JAMES C. JOHNSON, Secy.

Telephone Lake View 759

T. C. GLEICH CO.

INTERIOR DECORATING
FINE WOOD FINISHING AND PAINTING

2860 BROADWAY

CHICAGO

LACE CURTAINS, DRAPERIES AND SPECIAL FURNITURE

press is entirely set up a large hydraulic ram forces the mats together, pressing out the oil from the seed.

The material left in the press is the linseed oil cake, and all the surplus oil is found at the edge of the cake. The cake is consequently passed through a trimming machine, which takes off this edge and the cake is then baled up ready for shipment and the trimmings are sent back to go through the process once again. This cake is used largely for a cattle food, and the largest portion of it is shipped abroad to Belgium and Holland.

The oil is then filtered by filter presses, passing through filter cloths, and is now ready to be filled into the barrels. Thus we have our raw linseed oil. The oil at this point, however, is not in proper condition for use by the varnish maker on account of the fact that when heated to a temperature of about 450 degrees F., mucilaginous material, otherwise known as the "Break," separates from the oil. Consequently it is necessary that the linseed oil manufacturers further refine the oil, which is done by means of various chemicals and mechanical devices in order to produce an oil which will meet conditions imposed by their customers. At this point also the various driers are added to the oils in order to prepare the boiled oils found upon the market.

The next oil we shall consider is an oil which perhaps, is not quite so familiar as linseed oil, being our China Wood Oil, an oil made from the nuts of the Tung tree, a tree indigenous to China, growing largely in the interior of China, particularly along the banks of the Yangtze River. These trees bear fruit about the size of a small orange, each fruit containing five segments, each segment containing a kernel. The fruit is roasted over a fire, which breaks open the segments, the kernels separate and these kernels are then placed in the crushing machines.

The Chinese in the olden days used an extremely crude piece of apparatus for crushing these kernels, being nothing more or less than a large stone, which is rolled back and forth in a trough and crushes the kernels. A more modern crusher consists of a large stone weighing several tons; this is drawn around within the circular trough by means of mules, horses or other animals, and the kernels as they are crushed, gradually move toward the center. It is a very primitive means of carrying out these processes, but it must be remembered that individual Chinamen carry out the process on their own farms and therefore, the machinery cannot be very complex. The powdered China Wood Oil nuts are then tempered and placed between bamboo mats, and heated over a kettle of boiling water until the powdered nuts have picked up sufficient moisture and the mats are then placed edgewise in the large press. This press also is of primitive style, consisting of large mats, and a large wooden ram forces the logs between which the mats are set edgewise together, pressing out the oil. The oil is then filtered through bamboo cloths, and is then carried down to the China Wood Oil broker in large baskets, the baskets being lined with a peculiarly oiled paper. Each Chinaman carries four baskets, two being suspended from two sticks swung across the shoulders; each basket of oil which is purchased is tested and its richness determined. The oil is then emptied into the tanks, and from these tanks is drawn off into the barrels, in which it is shipped to varnish manufacturers. China Wood Oil being very different from linseed oil, and in fact, from any of the other oils, we will mention three of its chief characteristic properties. China Wood Oil when allowed to dry by itself on

glass, instead of drying with a clear, transparent film as does linseed oil, dries with a cloudy opaque film, very much resembling a piece of ground glass. Secondly, China Wood Oil when heated at a temperature of about 450 degrees F., instead of gradually thickening as does linseed oil, it almost instantly goes over to a solid jelly very much resembling soft rubber. Thirdly, China Wood oil when placed in a bottle and exposed to the light, even though the bottle is air-tight, will, by the actinic rays of the sun be converted to a hard like mass. This last property is very easily overcome by the heating of the oil. The gelatinizing of the oil is also very easily taken care of by proper treatment with various gums, etc. However, the most difficult feature to overcome is that of the "dry-flat," as the varnish maker terms it. This is due to a wrinkling of the varnish film, and I would add it has cost the varnish manufacturer a great deal of money, and they have spent a great deal of time in order to overcome this very serious drawback. However, after years of study the larger manufacturers understand this property thoroughly and have overcome it entirely.

You may ask with all these drawbacks, why it is that the varnish maker should care to use China Wood Oil at all. In the first place, China Wood oil has two important properties which are not found in linseed oil. A varnish made with China Wood Oil will be very much more waterproof than that made with Linseed Oil. In the second place, China Wood Oil has the property of causing the varnish to harden very much quicker than when Linseed Oil is used. These two properties make China Wood Oil a very important and essential feature in certain classes of varnishes. On the other hand Linseed Oil produces in a varnish greater elasticity fuller body and lustre, better flowing properties than can be obtained with China Wood Oil. In producing a varnish, it can readily be seen that it is necessary to utilize each of these oils according to the results desired in the varnish. If, for instance, we desire to produce a spar varnish which must needs have a maximum amount of elasticity in order to stand expansion and contraction due to weather conditions, it is necessary for us to use the most elastic materials which we can possibly obtain, consequently Linseed Oil gives us for this purpose the best results. China Wood Oil, on the other hand, when used in a spar varnish attains its waterproof qualities very much quicker upon exposure, will retain a perfect film only for a short period of time after which the film deadens, cracks and makes an extremely poor surface for refinishing. The Linseed Oil varnish on the other hand while it dries and hardens more slowly and possibly, if rained upon, before it has hardened, will turn white (this whiteness disappearing upon its drying out) yet, at the end of about six months, the film will have worn evenly, and the varnish will have retained a good portion of its lustre.

If we now desire to produce a floor varnish, we must bear in mind that the necessary requisites of a varnish of this kind are that it must be very tough, elastic, waterproof and hard drying. This last property meaning that it must not soften up in warm, humid weather. In designing a floor varnish, we must of course look to the China Wood Oil for our waterproofness and, to a considerable degree, our hard drying properties. At the same time, we must look to our Linseed Oil in order to obtain the maximum amount of elasticity in the varnish film. This latter property is one, which is extremely important and which really determines whether or not a varnish will wear down evenly or whether it will crack and chip. Most people do not realize the amount of stress caused by the impression of heels




DISTINCTIVENESS ⁱⁿ
 DECORATION
 AND
 HIGHEST STANDARD of
 WORKMANSHIP—
 HAS BUILT OUR
 ORGANIZATION

We operate any where in the
 United States

J. P. Sullivan
 INTERIOR DECORATING
 4515 INDIANA AVE CHICAGO
 OAKLAND 337

J. O. NELSON, Pres.

E. S. NELSON, Sec'y-Treas.



ESTABLISHED 1908

*Painting, Wood Finishing, Paperhanging
 Interior Decorating*

2568-2570 NORTH CLARK STREET

TELEPHONE LINCOLN 8761

CHICAGO

on a varnished floor, but upon considering this point, you can readily understand that it is necessary to have the maximum amount of elasticity in order to obtain the very best results. Thus, you can realize that in making a varnish for a definite purpose it is necessary to use those properties found in each of these oils in order to obtain a properly balanced product, and this only serves to emphasize the importance of specifying for definite kinds of work the varnish which has been especially designed for that purpose.

We will next take up the subject of Turpentine which is made from the sap, that comes from our southern pine trees. These trees were formerly cut according to the "Box Method;" that is, a box was dug at the base of the tree and the bark then cut from its side. The sap flowed down the side of the tree, ran into the box and was emptied from the box into a basket, then into barrels in which it was carried to the still. Today, however, on account of the fact that this method shortens the life of the tree, undermines its resistance to storms and thus permits great losses, we have perfected what is known as the "Cup and Gutter System." That is, the sap runs down the side of the tree into a gutter and then from the gutter into the cup, thus the tree is not wounded except on its side, and it is found that the production of sap is greatly increased as well as its quality improved. Furthermore, the trees last a great deal longer and there is not the danger of the entire destruction of forests by wind storm. The sap after being gathered from the tree is then taken to the still, where, a small amount of moisture having been added, it is heated in a large copper retort; the turpentine passes over as a vapor, through coils, is condensed and we have our gum spirits of turpentine. The residue left in the retort is rosin, which is subsequently strained, cooled and prepared for the market.

The material which I have just described is known to the trade as Gum Spirits of Turpentine and it may be well to mention the difference between this product and Wood Turpentine. Gum Spirits of Turpentine is, as I have described, made by the distillation of the sap of the pine tree, whereas, Wood Turpentine is made by the distillation of the wood itself usually utilizing for this purpose, the stumps of pine trees which have fallen. Both of these products are very similar in chemical constitution and in many cases can only be distinguished by their odor. It may be of interest to know that the American Society for Testing Materials in drawing up their specifications for turpentine have adopted a specification to which a high grade of Wood Turpentine can conform based upon the fact that the latter when conforming to this specification is equal in every way to the Gum Spirits. It is important, however, in permitting the use of

Wood Turpentine to insist that it conform to such specifications as these, as there are upon the market many grades which have entirely different properties and which should, under no circumstances, be used.

Having discussed the various raw materials used in varnish making, we will now describe briefly the varnish making process.

The gum or resins usually in approximately one hundred-pound lots are placed in a copper kettle, which stands about three feet high and about two and one-half feet in diameter. The kettle is then rolled upon the fire, the gum melted and held there until a certain proportion of the gum has been distilled off. At this endpoint, which is determined by the varnish maker, the melt is drawn from the fire and the oil, which has been heating at an adjacent chimney and which had been previously prepared, is emptied into the kettle. The gum and oil are then thoroughly stirred together, the kettle being run back on the fire and the gum and oil heated until thoroughly amalgamated. This endpoint is also determined by the varnish maker, who has his own particular way of judging as to when the melt is finished and when the batch is completed. The kettle is then withdrawn from the fire and allowed to cool, when it is taken to the thinning room, where the turpentine or other thinners are added. The varnish is then pumped into coolers, where it is allowed to cool to a certain extent before passing to the filter presses, which take out all the dirt. This is done very carefully, in order to take out the most minute particles of dirt and the varnish is then pumped to the ageing tanks, where it is allowed to age for a certain period of time, according to the quality of the varnish.

The question of ageing a varnish is one which has been given a great deal of study, and it has been proven that the ageing of varnish does improve it very considerably, both as regards its brilliancy and durability. This is apparently due to the fact that the various constituents of the varnish gradually become more and more closely knit together, which results in the improvement of the varnish.

While the matter of ageing is one, which has, in many cases, been very much overdrawn, yet, at the same time all manufacturers of the highest grade varnishes, even at the cost of tying up their capital, deem it sufficiently important to age their varnishes from one month to twelve months according to the character, grade and composition of the varnish. The completion of the ageing process is determined by tests made upon the varnish itself. After the varnish has been properly aged, it is then pumped to the filling tanks, from which it is drawn into the can or package, which is then labelled, and we have our finished product ready for the market.

Some Recent Operations Executed by

PLAMONDON-GABRIEL CO.

Painters—Decorators—Furnishers

308 N. Michigan Ave.

Chicago, Illinois

PHONES: RANDOLPH 6920-21-22

BUILDING	ARCHITECT	CONTRACTOR
Cleveland Hotel, Cleveland, Ohio.	Graham, Anderson, Probst & White	Thompson-Starrett Co.
Cooper-Carlton Hotel	Henry L. Newhouse	Sherman T. Cooper (Own- er)
Terrace Gardens, Kahl Bldg.	C. W. & Geo. L. Rapp	Walsh Const. Co.
Senate Theater	Walter W. Ahlschlager	Harry J. Kusel
Somerset Hotel	Samuel N. Crowen	Paschen Brothers
State-Lake Theater & O. Bldg.	C. W. & Geo. L. Rapp	Longacre Eng. & Const. Co.
Washington Hotel, Washington, D. C.	Carrere & Hastings	Frank C. Lewin
Webster Hotel	Fridstein & Co. (Eng.)	C. H. Lott (Owner)
Woods Apollo Theater	Holabird & Roche	Longacre Eng. & Const. Co.
Wrigley Building	Graham, Anderson, Probst & White	Lanquist & Iillsley Co.

PAINTING & DECORATING

EFFICIENCY-RELIABILITY

PHONE
LAKEVIEW 7626

Theo. Ebert & Co.
914-918 Diversey Parkway

PROTECTIVE, PRESERVATIVE AND DECORATIVE COVERINGS

File Brush Using Trade.

STANDARD PAINTERS' MATERIALS.

An attempt is made in the following to define those materials which may be readily prepared by any competent painter, that are generally accepted as standard for high grade work. Such materials very properly form the basis of comparison for all proprietary paints. No proprietary preparation should be accepted for use that does not equal in enduring, wearing quality, appearance, cost and ground for subsequent coats, the materials hereinafter described.

Classification of preservative and decorative coverings is commonly made according to the nature of the surfaces which these materials are designed to cover.

Materials for painters' work are divided according to their nature under the following headings: Pigments, Binders and Agents or Solvents.

Paint consists of a binder or binders and a pigment or pigments incorporated or mixed together. Mixing of paint ingredients is accomplished in a manner either by stirring or grinding together by hand or by machinery. Machinery mixing with proper apparatus is most certain to secure uniformity of result, and is therefore advised where practical. It is practically impossible to get a perfectly smooth paint by hand mixing.

Linseed Oil is the only known universally successful binder for paint and the holding power of the paint depends almost entirely on the strength of the linseed oil used. This oil is adulterated in many ways, but the most common is with mineral oil. The manufacturers of mineral oil substitute have perfected their product to such an extent that it is difficult to distinguish it from the real article except by chemical test or actual use, when its inferiority is quickly manifest.

STANDARD BINDERS.

Raw Linseed Oil is the oil obtained from seeds of the Flax-plant, *Linum Usitatissimum*, and what is known as commercially, pure grade, has a specific gravity of not less than .932 nor in excess of .936, when the temperature is 15° Centigrade, or at temperature 25° Centigrade, not less than .927 or more than .931. It has a minimum Acid number 6, Saponification number minimum 189, maximum 195. Unsaponifiable matter maximum 1.50%. Refractive index at 25° Centigrade minimum 1.4790 to maximum 1.4805. Iodine number (Hanus) 170. It is a straw yellow in color, weighs approximately 7½ lbs. to the gallon.

Boiled Linseed Oil, commercially pure, consists of raw linseed oil as above defined, kettle boiled at a temperature not to exceed 500 deg. Fah. nor less than 300 deg. Fah.; or the same sort of oil prepared with best pure Japan dryers, so as to increase drying qualities. If salts of lead or manganese are thoroughly incorporated into the raw oil, very similar results are produced to the boiling process. An old method of increasing the drying properties of linseed oil was to heat the oil to near the temperature at which it undergoes destructive distillation (550 deg. Fah. or thereabouts), and stir in at the same time, oxide of lead or oxide of manganese, or both. Such method, however, darkens the oil very much.

The U. S. Army Standard Specification for Boiled Linseed Oil Is as Follows:

Specification W. D. 2.

It shall be absolutely pure, well-settled linseed oil boiled with oxides of manganese

and lead. It shall conform to the following requirements:

	Max.	Min.
Specific grav. at 15.5°/15.5°C.....	0.945	0.937
Acid number	—8.000
Saponification number	195.000	189.000
Unsaponifiable matter, pct....	1.500
Refractive index at 25° C....	1.484	1.479
Iodine number (Hanus).....	168.000
Ash, per cent.....	0.700	0.200
Manganese, per cent.....	0.03
Lead, per cent.....	0.1

STANDARD SOLVENTS.

Spirits of Turpentine, chemically pure, is composed of a volatile oil obtained by the distillation of turpentine oil obtained by tapping or boxing yellow pine trees. It is a clear, colorless liquid, with a pleasant, pungent odor and shows a very slight residue when evaporated. Spread over any surface in a thin layer, it will dry in twenty-four hours, leaving practically no residue. Turpentine weighs about 7 lbs. to the gallon of bulk.

The U. S. Army Standard Specification for Turpentine Is as Follows:

Specification W. D. 3.

This specification applies both to the turpentine that is distilled from pine oleo-resins, and commonly known as gum turpentine or spirits turpentine, and to the turpentine commonly known as wood turpentine that is obtained from resinous wood, whether by extraction with volatile solvents, by steam, or by destructive distillation. The bidder should state whether gum spirits or wood turpentine is furnished.

The turpentine shall be clear and free from suspended matter and water. The color shall be water white. The specific gravity shall not be less than 0.860 or more than 0.875 at 15.5° C. The refractive index shall not be less than 1.468 or more than 1.478 at 15.5° C. The initial boiling point shall be not less than 150° C. nor more than 160° C. Ninety per cent of the turpentine shall distill below 170° C. The polymerization residue shall not exceed 2 per cent and its refractive index at 15.5° C. shall not be less than 1.500.

STANDARD PIGMENTS.

Red Lead, practically pure from a commercial standpoint, is equal to 98 per cent lead tetroxide; but to secure this degree of purity, without a trace of soda or nitrate salts, requires a special method of reduction not employed by all manufacturers. In fact it has only been within the last few years that even the best manufacturers have been able to produce a pure red lead without having present from .1 to .5 per cent of soda or nitrate salts, which salts have a strong tendency to promote rust. Paint is intended as a protection of metal against rust, and as such should not contain any elements of a rust inducing nature. Specification should therefore require that red lead must be wholly free from soda or nitrate salts. The process now used to get red lead which is 98 per cent true, is by burning the lower grade red lead, 85 per cent true, for about 20 to 24 hours longer. This brings the true red lead, Pb₃O₄ up to the high standard which has lately been accepted as most effective in preventing rust. The American Society of Testing materials after exhaustive tests conducted within the last nine years have concluded

Painting and Decorating

Every member of our organization is a Master-Craftsman whose efforts operate in the single direction of satisfactorily serving our customers to the last detail. From estimates to the finished work we use every means possible to produce a job that can be pronounced perfect. Ordinary Painting and Decorating when compared with the work of Rising, Craftsman, is flat and lifeless. Examples of our work can be seen from coast to coast and each individual job is an expression of "Work Well Done" by experienced workers who take pride in doing things better than they have ever been done before.

We cheerfully furnish estimates on work in any locality. Our prompt and complete service is at your disposal at any time.

THE RISING DECORATING COMPANY

Phone: Haymarket 6363-6364

527-31 South Peoria St.

CHICAGO, ILL.

PHONE, YARDS 768

J.M.BRENNAN & CO.

Painting and Decorating Contractors

RESIDENCES, OFFICES, HOTELS, CLUBS, SCHOOLS,
CHURCHES, STORES, APARTMENTS, THEATRES,
FACTORIES, WAREHOUSES, GARAGES

We are in a position to operate any place in the country

651 West 43rd Street

CHICAGO, ILL.

that the highest grade red lead, 98 per cent true, is even more lasting in character than the red lead which was formerly considered best for paint pigment which was about 83 per cent true red lead Pb_3O_4 (tetroxide of lead) plus 17% litharge PbO (mon oxide of lead). The Government specifications have been raised from 85 per cent to 90 per cent true, and lately have been increased to 95 per cent of true red lead. (This observation does not apply to the war department which still follows the old standard).

This, therefore, argues very strongly for the 98 per cent true red lead, but it still remains a fact that very enduring paint can be made in compliance with the following formula: Pb_3O_4 (tetroxide of lead), 85 per cent plus litharge PbO (mon-oxide of lead) 15 per cent. Owing to the tendency of this combination of red lead and litharge pigment to unite with linseed oil in chemical combination, paint composed of red lead and linseed oil should not be prepared to exceed twenty-four hours before using. For if this combination of red lead and litharge is mixed with linseed oil and sealed up in an air-tight can, it will be found after a time that the mixture has solidified showing that the oxygen of the air which is the hardening agent in ordinary paints is not necessary. The chemical combination that thus takes place between the litharge and the oil in this mixture probably gives an increased toughness and endurance to paint applied according to this formula, provided this chemical action takes place after the paint is applied. Practically, it is very difficult to secure intelligence in the application of paint to structural portions of a building and it is therefore doubtful practice to use so large a percentage of litharge, not because it will not make a strong enduring paint, but because it is extremely difficult to get same applied before chemical action takes place. It has been found also that the addition of say 10 per cent of a practically inert pigment such as Princess mineral or oxide of zinc, increases the wearing quality of red-lead paint without other injurious effect.

The U. S. Army Standard Specification for Reinforced Red Lead Paint Is as Follows:

Specification W. D. 40.

Pigment 64 per cent.
Liquid 36 per cent.

The pigment portion shall consist of Red Lead (not less than) 60 per cent, the balance to be Silicious Matter, such as Aluminum Silicate, Magnesium Silicate, Silica or a mixture thereof.

The Red Lead used shall contain not less than 85 per cent Pb_3O_4 , the balance to be PbO .

The liquid portion shall consist of—

Pure Raw Linseed Oil (not less than) 90 per cent, the balance to be combined Drier and Thinner. The thinner shall be Turpentine.

Special Requirements: The paint must weigh not less than 16 pounds per gallon. It is intended to be used for a Priming Coat on Steel and when applied to smooth iron surface, it shall dry in 12 hours without running, streaking or sagging.

Corroded Lead, Basic Lead Carbonate—chemically to $PbCO_3 \cdot Pb(OH)_2$ is the form of lead pigment which has been in most general use for many years past. A satisfactory formula for white lead pigment is 70 per cent to 75 per cent of lead carbonate to 25 to 30 per cent of lead hydrate; this is in substantial compliance with U. S. Government standard specifications. While Basic Lead Carbonate is more poisonous than sublimed lead it still is a perfectly safe pigment to use with proper precautions. In fact nearly all paint

pigments are more or less poisonous and so care should be taken by painter to avoid allowing paint to come in contact with the skin.

Sublimed Lead or Basic Lead Sulphate—chemically to $PbSO_4 \cdot PbO$ is coming into general use for paints and is practically non-poisonous and is just as valuable as a pigment for many purposes as the older form. It is particularly satisfactory as a base for tinting colors.

The U. S. Army Standard Specification for White Lead Basic Sulphate Is as Follows:

Specification W. D. 49.

The dry pigment shall be of the best quality, amorphous in structure, and of great opacity.

It shall contain:

Not more than 0.5 per cent Moisture,

Not more than 8.5 per cent Zinc Oxide (ZnO).

Not more than .075 per cent Sulphur Dioxide (SO_2), and

Not less than 12. per cent Lead Oxide (PbO).

Unless otherwise specified, this Basic Sulphate-White Lead shall be delivered in paste form, finely ground in pure, clear Raw or Refined Linseed Oil in the proportion of:

90 pounds Pigment.

10 pounds Oil.

White Lead Paste averages to contain by weight 92 per cent dry lead pigment and 8 per cent linseed oil and weighs about 38.1206 lbs. to the gallon of bulk.

Zinc White is oxide of zinc made by burning zinc in air. It is whiter than White lead but is not so opaque, and more coats of zinc paint are necessary to get a given effect over a dark background than of white lead. Paint consisting of commercially pure zinc white and linseed oil makes a strong and enduring wearing surface but does not produce as satisfactory ground for repainting after a period of service, as paint composed of a white lead pigment and linseed oil.

Combination Paint composed of an admixture of right proportions of White Lead and Zinc White with Linseed Oil will undoubtedly give better service than either White Lead and Oil or Zinc White and Oil alone, possibly for the same reason that two or more sizes of aggregate rightly proportioned make a better concrete with a lesser amount of cement than aggregate of only one size.

Graphite, or plumbago, may be said to be diamond plus heat; for if a diamond is heated to a very high temperature, without access to the air, it swells up and is converted into a black mass exactly resembling graphite in every particular. This theory being further verified by the fact that this change takes place without the loss or increase of weight. Graphite is found in nature in large quantities. It is sometimes found crystallized, but in a form different from diamond. Graphite can be prepared artificially by dissolving charcoal in molten iron; from such a solution graphite is deposited on cooling. Pure graphite is dark grayish-black in color and of a metallic luster. It is quite soft, leaving a leaden-gray mark on paper when drawn across same. It is used in the manufacture of the so-called lead pencil and is sometimes called black-lead. Such designation is wholly misleading, as it is in no sense metallic lead. Graphite is pure carbon, the element which is the principal constituent of all organic matter, both vegetable and animal. It is extensively used as a paint pigment, particularly for metal coating. Finely

Spierling & Linden

INTERIOR DECORATORS
and FURNISHERS

ESTABLISHED
1882

TELEPHONE
CAL. 511

Office and Studio: 1216 Michigan Ave., Chicago


We invite architects and owners of fine residences and public buildings to
avail themselves of our superior facilities and the high
ability of our artists and craftsmen

Sketches and drawings of work promptly furnished upon request

PAINTING

FINISHING

DECORATING



702 N. WELLS STREET

Superior 1964

CHICAGO

Phone, Evanston 4225

Hermann Olson Decorating Co.

*Painting : Wood-finishing
Interior Decorating*

911 Chicago Avenue

EVANSTON, ILL.

Phone, Irving 1046

C. E. Warnecke Co.

PAINTING and DECORATING

4043 Elston Avenue

CHICAGO, ILL.

ground amorphous or non-crystallized graphite, when mixed with linseed oil, forms a perfectly inert pigment when united in mechanical mixture with the oil and without the slightest evidence of chemical combination. For this reason prepared graphite-paint is not injured by age as is the case with oil-paints, which are composed of oil and a pigment which will form a more or less stable chemical union with same. It is contended, by advocates of Graphite paint, that the inert nature of graphite pigment contributes to the ease of its application and adds to its covering capacity and elasticity, making a better appearing mechanical job with less labor and also a covering which can accommodate itself to the contraction and expansion of the material covered without serious injury to its efficacy as a protective covering. The non-active nature of graphite pigment makes it possible to coat surfaces with a much thinner coating than with the paint containing a pigment which acts chemically with its oil.

Lamp Black is a very finely divided form of charcoal produced by the deposit on cold surfaces of the imperfectly combusted products from burning oil. Lamp black may be said to be the soot produced by burning oil without sufficient oxygen present to form perfect combustion. This soot is largely made up of fine particles of carbon. Lamp black is used in the manufacture of ink and as a pigment for paint to be applied to metal. Many of the best contracting painters insist that lamp black ground and mixed with linseed oil forms the most enduring and attractive appearing paint for ornamental iron.

Paint for metal, first coat, should not be applied until after the surface is thoroughly cleaned free from dirt or grease, as such material keeps the coating from coming in contact with the metal, so that it cannot adhere to same. It might be supposed that grease would be absorbed by paint or varnish but this does not prove true in practice. To mix such materials would require their thorough agitation together. This is prevented in the application over dirty surfaces due to the fact that the grease is always mixed with and covered by an adherent film of dirt, which interferes with the action of the paint or varnish upon it; consequently making a loose film which will not permanently support the paint coating.

Colors are produced by mixing the various color pigments with the standard base pigments of lead or zinc.

The addition of Tinting Colors to White paint generally greatly increases the durability of the paint. The volume of base pigment needs to be reduced in proportion to the amount of color pigment added, so as to maintain the same relative relation of pigment to oil in the various coats as hereinafter prescribed. The scope of this article does not permit a discussion of the composition and merits of the numerous commercial color-pigments offered to the trade.

Chemical action between the pigments and oil in paint ordinarily does not occur, but there are exceptions. Sabin states that such action takes place with White Lead and Linseed Oil, "probably between the oil and the lead hydrate, which constitutes at least a quarter of the pigment." "This change is said to be due to resinification of the oil converting it into a sort of varnish." "Zinc Oxide (White Zinc) also acts on oil, but in a much less degree." "Paint consisting of White Lead and White Zinc mixed together in the proportions of two of lead to one of zinc is reputed to be superior to either alone. Zinc brushes more readily and is said to have a spreading capacity of 50 per cent greater than a straight lead and oil paint.

Paint Proportions and Covering Capacity.

Primer of Lead and Oil for new work should be proportioned by bulk, so as to contain 27 per cent of White Lead Paste, 62 per cent of Linseed Oil and 11 per cent of Turpentine.

Priming Lead and Oil will require 10.3 lbs. White Lead, .62 gal. Linseed Oil and .11 gal. Turpentine to make one gal. of paint.

One Gallon Lead and Oil Primer will average to properly cover about 2½ squares of new wood work or 1¼ squares of common brick work.

One Square of New Wood Work requires to properly prime same with lead and oil 3½ lbs. White Lead, .23 gal. Linseed Oil and .04 gal. Turpentine, or if common brick requires 8.24 lbs. White Lead, .5 gal. Linseed Oil and .088 gal. Turpentine.

Succeeding Coats of Lead and Oil Paint after primer should be apportioned by bulk so as to contain 30 per cent White Lead, 64 per cent Linseed Oil and 6 per cent of Turpentine.

Succeeding Coats of Lead and Oil Paint after priming will require 11.44 lbs. White Lead Paste, .64 gal. Linseed Oil and .06 gal. of Turpentine to the gal.

One Gallon Lead and Oil Succeeding Coater will average to properly cover, any coat, about 4½ squares of wood work after same has been primed, or 3 squares of common brick work, second coat. Third coat on brick work, one gal. will cover as much surface as on wood.

One Square of Any Oil Succeeding Coat on wood work after same has been primed will average to require to properly cover same 2.54 lbs. White Lead, .14 gal. Linseed Oil and .0133 gal. of Turpentine; or for 2nd coat on common brick work, 3.48 lbs. White Lead, .21 gal. Linseed Oil and .02 gal. of Turpentine. Third coat on brick work will require the same amount of paint to unit of surface as "Succeeding Coats" on wood.

Primer for metal of red lead to give satisfactory results can be made by mixing 23 lbs. of dry "red lead for painting metal" to 1 lb. of "zinc white," adding sufficient commercially pure "raw linseed oil" to make a gallon of the mixture, and thoroughly incorporating together. The mixing of the oil and pigment should only be as required at the work, never to exceed 24 hours before applying. The paint resulting will be rather stiff and requires thorough and careful brush work to make the surface elastic, and the material cover proper area. This paint should not be thinned by addition of evaporant liquids as these have a tendency to produce destructive chemical action on the paint, effecting its permanency as a protective coating.

Succeeding coats on metal, after primer, can very satisfactorily be of white lead and oil or zinc paints as above described, or a combination of the two.

Primer for masonry surface which has a strong alkaline reaction, such as plastered walls, brick masonry and concrete, should consist of a solution of zinc sulphate crystals dissolved in water, in the proportion of 3 lbs. to the gallon, after which succeeding coats of paint as defined above for wood work may be applied with satisfactory results. Oil paint should never be applied direct to masonry. There are a number of proprietary mixtures that are prepared especially for this purpose and which give excellent results.

Cheap Practical Substitute Oil Paint for more or less temporary use is illustrated by

The
Hockaday-System
OF FINISHING WALLS

Printed detail specifications for finishing all classes of surfaces will be mailed on request.

Service Stations with stocks in all principal cities

The Hockaday Company, 1823-29 Carroll Ave., Chicago, Illinois



MURESCO

**MOST BEAUTIFUL, ECONOMICAL AND SANITARY
FINISH MADE FOR ALL**

INTERIOR DECORATING

Recommended by leading Architects and Contractors, and used on the finest residences, churches, schools, hospitals, office buildings, factories, etc.

Write for Sample Card and Descriptive Matter.

BENJAMIN MOORE & COMPANY

CHICAGO. NEW YORK. CLEVELAND. ST. LOUIS.

SOLVAY PROTECTIVE PAINTS

For the Preservation of Iron and Steel

Remarkably resistant to action of

Smoke—Water—Heat—Acids—Alkalies

Send for Sample and Price List

SEMET-SOLVAY COMPANY

Telephone: Harrison 3580

CHICAGO

332 So. Michigan Avenue

P. W. NELSON, Inc.

2834 SOUTH LOOMIS STREET, CHICAGO

**The Best CALCIMINES and WATER
PAINTS FOR EVERY PURPOSE.**

**WESTERN HEADQUARTERS
MUNNS WALL SIZE AND LEADOIL**

FOR INFORMATION CALL LAFAYETTE 7120-7121

the U. S. Government War Department "Exterior Cantonment Paint" Standard Specification, which is as follows:

"W. D. 19"

This Paint also to be furnished in white when required.

Pigment 64%.
Liquid 36%.

The pigment portion shall consist of—

White Lead (Basic Carbonate, Basic Sulphate, or a mixture thereof).....42%
Zinc Oxide33%
Aluminum Silicate, Magnesium Silicate, or a mixture thereof, combined with the necessary pure tinting colors to produce the desired shade (a total of)25%

The liquid portion shall consist of—

Pure Raw Linseed Oil.....20%
Menhaden Oil,* Soya Bean Oil,** or a mixture thereof.....40%

The balance to be combined Drier and Volatile Mineral Spirits.

Special Requirements: This paint shall weigh not less than 15 pounds per gallon, and shall dry within 12 hours, and leave a surface suitable to recoat in 36 hours.

The above name and standard specification applies wherever similar type of paint is to be used.

* The Menhaden Oil used in this paint shall be pure, refined, light in color, and not of objectionable odor. It shall have the following chemical constants:

Specific gravity.....92-93
Iodine number, not less than..... 166
Saponification number, not less than 186
Acid number, not more than..... 8

**The Soya Bean Oil used in this paint shall be pure, light in color, and shall have the following chemical constants:

Specific gravity.....92-93
Iodine number, not less than..... 130
Saponification number, not less than 180
Acid number, not more than..... 4

Flat Finish Interior Paint

The most satisfactory Flat Wall Paints are made with Lithopone as the principal ingredient in the pigment. Lithopone is a wonderful pigment for interior use. It has great hiding power and spreading capacity and when properly mixed with the right kind of liquids makes the ideal inside flat wall paint. There are many standard brands of flat wall paints on the market that are worthy of consideration and use.

**Fire Retardant Paint
U. S. Army Standard.**

W. D. 21.

In any Tint desired.

For Exterior Use on Lumber Construction Wherever Fire Resistance is Desired.

Specification.

White Paint and Tinted Paints made on a White Base.

Pigment 60%.
Liquid 40%.

The pigment portion shall consist of—
Basic Sulphate White Lead.....28%
Zinc Oxide.....22%
Magnesium Silicate, combined with the necessary pure tinting colors to produce the desired shade (a total of)....50%

The liquid portion shall consist of—

Pure Raw Linseed Oil (not less than)—55%
The balance to consist of equal parts of Drier, Turpentine and Volatile Mineral Spirits.

Special Requirements. This paint shall weigh not less than 13 pounds per gallon. When applied to new lumber construction it shall penetrate and dry rapidly to a durable film. It shall successfully withstand the standard firebrand test when applied to two-coat work.

The above named and standard specification applies wherever Fire Retardant Paint is to be used.

WOOD FINISHING MATERIAL.

**Orange Shellac Varnish
U. S. Army Standard**

W. D. 31.

Specification.

This material shall consist of 4½ pounds of Shellac cut in one gallon of Clear Neutral Denatured Alcohol.*

The Shellac used shall be a high grade Orange Shellac which, when treated with hot 95 per cent Alcohol, will not show a residue of insoluble matter exceeding 1.75 per cent.

The Shellac shall be free from Rosin and other adulterants.

The above standard specification applies wherever Orange Shellac Varnish is used.

* The alcohol used shall be No. 1 Internal Revenue Dept. Standard consisting of 100 gallons of grain alcohol and 5 gallons approved wood alcohol.

LIQUID WOOD FILLER.

U. S. Army Standard

W. D. 52.

Specification.

Pigment 17%.
Liquid 83%.

The pigment portion shall consist of—

Finely divided Silica that will pass through a 200 mesh screen.

The liquid portion shall consist of—

Varnish77%
The balance to be Turpentine or Volatile Mineral Spirits, or a mixture thereof.

Special Requirements. When applied to wood it shall dry in not more than 5 hours. It shall be of the proper consistency for either brushing or dipping.

The above standard specification applies wherever Wood Filler is to be used.

Generally speaking, there is no great demand for a liquid wood filler. A thin coat of

shellac or a varnish thinned with turpentine are recommended for use in place of liquid fillers.

Paste Filler for open grained hard-wood finish or floors requires for proper filling and wiping 1½ lbs. Silex paste and .14 gal. thinner to the square. Paste Filler is tinted or left transparent according to the color effect desired. One pound of prepared paste filler will fill 40 square feet of surface.

Wiping of paste filler is done with bur-lap, sea moss or excelsior and should always be done across the grain of the wood as if rubbed with the grain of the wood there is a tendency to lift the filler out of the pores of the wood and waste same, requiring more filler to give satisfactory results.

Thinner for paste filler may be either Turpentine or Benzine if the filler is of best quality of rock quartz, water floated, very finely bolted and mixed with special Japans and Linseed Oil, benzine seems to give the most satisfactory results for a thinner owing to its quicker evaporation. For the cheaper fillers Turpentine must be used.

Varnish is discussed in another article in this book so is omitted here.

Stains for wood work usually form one coat in addition to filler and coats of varnish or wax; these are of three kinds, oil-stain, spirit-stain and water-stain, and are used according to the effect desired.

Oil-Stain averages to require about .16 gal. to the square.

Spirit-Stain averages to require about .16 gal. to the square.

Water-Stain averages to require about .2 gal. to the square.

Prepared Wax averages to require about .33 lbs. to the square.

Gloss Oil is a term used to designate a preparation composed of resin and naphtha. This is a very cheap substitute for varnish often used as a size for plastered walls preparatory to tinting. It is a very inferior material and when used as a size softens and roughs with repeated washings. It is ruinous when used as a varnish or as a binder for paint.

Varnish, Best Light Interior, requires for properly coating one square, 1st coat over filler, 1½ to 1-7 gal.

Varnish, Cheap, Thick Rosin, requires for coating one square one gloss coat, 1½ to 1 gal.

Cresote Stain required to dip ¾ length one M. shingles equals about 2½ gal.

Cresote Stain required to brush coat one square shingles equals one gal.

Size for plastered walls preparatory to tinting should be varied according to the nature of the treatment to be applied over same and also with reference to the surface

on which it is applied. A very good size for this purpose on smooth plastered walls is a coat of medium grade varnish. Such a size would cost about \$2.25 per gallon. A standard medium cost size for smooth plastered walls is made up of China wood oil, resin and naphtha; such a size could be made up for about \$1.50 per gallon. The cheap size commonly used is made up of gloss-oil at a cost of not to exceed 75c per gallon; but taking into consideration lasting quality and labor expended, this is most expensive and unsatisfactory.

Fresco Size satisfactory for use on rough plastered walls may be made up as follows: Dissolve each separately in the proportions of one pound of glue to one gallon of water, one pound common yellow laundry soap to one gallon of water and one-fourth pound of alum to one gallon of water; the glue and soap solutions then being mixed together first, and after thoroughly mixed, the alum solution added and the whole well stirred together ready for application to the wall.

ESTIMATES ON PAINTING.

PAINTER'S ESTIMATE=(units of surface to be covered) × (amount of material required to cover a unit) + (cost of a unit of material) + [(number of hours of labor required by a mechanic to apply the material to a single unit of surface) × (hourly wage of mechanic) × (number of units of surface)] + (overhead charges, including scaffolding, brushes, drop-cloths, cartage, office expense and expense of supervision, etc.) + (Contractor's profit, which varies with the supply and demand).

UNITS OF SURFACE USED ARE (one sq. ft.), (sq. yd. 9 sq. ft.) or (square—100 sq. ft.).

AMOUNT OF SURFACE UNITS assumed for estimating purposes is increased at the judgment of the estimator. This is done to make proper allowance for increased labor and waste of material on account of broken and complicated surfaces, and so that prices per unit of labor and material can be maintained constant, the following enumerations being the assumptions most commonly used by estimators.

PLAIN D. & M. Wainscoting or partition stuff is measured once, actual surface, and is used as the standard of comparison. Other surfaces are increased in proportion as their difficulty of execution compares with D. & M. Wainscoting.

Sash for exterior are measured over the entire area instead of around each bar.

Shingle Gable, 1½ × actual surface area.

Dormer Windows 2 × actual surface area.

Shingles, Rough, 1½ to 2 × actual surface area.

Shingles, Dressed, Dimension, actual surface measure.

Spindle work, measure 4 times solid on one side.

Square Spindle work and pickets, 4 × one side measured solid.

Verandas with heavy columns and railings, etc., measure surface of ceiling and floors and all sides the same as though enclosed. Veranda, very simple in design, measure floor and ceiling and allow double area of brackets and columns.

Outside Blinds, measure 3 × actual surface of one side.

INTERIOR.

Base Boards, measure not less than 1 foot in width regardless of actual width.

Picture Mouldings, measure 1-3 foot in width.

Single Doors, including trim, count as 35 sq. ft. to a side or 70 sq. ft. for both sides.

Interior Side of Windows, including trim and tracing of sash, average at 35 sq. ft.

Wall Decorations, measure ceiling solid and sidewalls 8-10 of actual area to allow for openings, or measure actual area and deduct $\frac{1}{2}$ to $\frac{3}{4}$ of all openings.

Badly Weathered wood work or cracked and damaged plaster, add from 1-10 to 3-10 to measurements determined as above.

Prices of standard materials are quoted in market reports and fluctuate with supply and demand. The estimator should verify these preceding each estimate. At time of going to press the following prices obtain:

White Lead Paste, \$12.25 per cwt.

Linseed Oil, raw, 85c per gallon.

Turpentine, 82c per gallon.

Paste Filler, about 14c per lb. in 100-lb. packages or 12c in bbls.

Interior Varnishes, about \$1.75 to \$3.00 per gallon.

Stains vary so much in price that they can not be listed.

First Class Exterior Varnishes, about \$1.25 per gallon.

Proprietary Oil Paints of best quality are sold to the painters at about \$3.25 to \$3.75 per gal., depending on color. The materials in a gal. of White Lead and Linseed Oil "Succeeding Coat" of paint costs exclusive of labor and coloring matter about \$2.40 at present market prices and the labor of mixing by hand and the expense for colors brings this hand-mixed paint up in price to about the same as proprietary paints of equal quality. Unless the ingredients composing paint are thoroughly incorporated the paint is not satisfactory. This proper mixing, if done by hand, requires considerable expensive labor.

In figuring the cost per gallon of a lead and oil paint we should not overlook the fact that the only way to correctly figure the price of paint is to figure it by the cost per square yard and not the cost per gallon. One gallon of pure lead zinc and linseed oil paint, machine made, will cover from 350 to 400 square feet per gallon, two coats on the average job, while lead and oil, hand mixed, will cover approximately 225 square feet, two coats.

LABOR REQUIRED.

COST OF LABOR=(number of hours of labor required by a mechanic to apply the material to the single unit of surface) × (hourly wage of mechanics) × number of units of surface).

Wage per Hour=union scale obtaining in the locality where the work is to be executed. (In Chicago this is from 80c to 85c per hour prevailing wage at this time per hour under the award of Judge Landis).

Stopping knots with shellac requires in labor .2 of an hour's time to the square of surface.

Puttying defects in ordinary wood work requires in labor .3 of an hour's time to the square of surface.

Oil Painting, single coat, requires in labor .57 of an hour's time to the square of surface.

Paste Filler Coat, including cleaning of wood work, requires in labor 1.33 hours' time to the square of surface.

Varnish, single coat, including light sand-papering, requires in labor .66 of an hour's time to the square of surface.

Cresote staining of shingles by $\frac{3}{4}$ dipping, requires in labor 1 hour of a mechanic's time to dip 1,000 shingles, which average to cover when laid, one square of roof surface.

Cresote staining, one brush coat on roof, requires in labor .8 hour's time to cover one square of surface.

Sizing of plaster walls with either glue or hard oil size requires in labor .33 of an hour's time to the square of surface.

Tinting with water color, fresco tints or calcimine averages to require in labor .44 hour's time to the square of surface to the man employed, providing not less than two men are employed on the work. (Ordinarily, one man cannot work alone at tinting of walls, for if he does so work, the work cannot be satisfactorily done and more time is required in proportion to the surface covered).

Sponging and washing walls requires in labor a variable amount of time to the square according to the amount of size used in coat to be removed and must be approximated by the estimator after examination and test.



“WIRE GLASS”

When set in proper metal sash and frames furnishes one of the best forms of fire

Protection, Provided

The Standard Product, which bears this label, printed in red, is installed.

To obtain the Standard, and there is no equal, Specify
Polished “Wire Glass,” “Factrolite” “Wire Glass,” Syenite “Wire
Glass,” Maze “Wire Glass,” Rough “Wire Glass,” Ribbed
“Wire Glass” or Pentecor “Wire Glass.”

The Product of the

Mississippi Wire Glass Co.

7 W. Madison Street
Chicago

220 Fifth Avenue
New York

4070 N. Main Street
St. Louis

GLASS AND GLAZING

PLATE GLASS.

Sizes and Thickness.—Plate glass can be made under the present improved methods in extreme sizes up to 250 square feet and in such measurements as 10 feet by 21 feet (or 120"x252") containing 210 square feet—12 feet by 20 feet (or 144"x240") containing 240 square feet—13 feet by 19 feet (or 156"x228") containing 247 square feet. Such extraordinary glass is very difficult to make, quite expensive and dangerous to clean or handle and, being especially made to order, entails delay in replacement when broken, requires special flat car shipment and special facilities for unloading and hauling, and the most expert and skilled glaziers in setting. Sizes are usually given in inches.

It is advisable to confine sizes to the ordinary limitations in order to secure prompt and economical deliveries from distributors' stocks.

On account of the extraordinary demand for certain sizes of plate glass for stock sizes in mirrors, windshields for automobiles, and stock door glazing, the proportionate production is below the consumption and a higher value is therefore placed upon these sizes, and their multiples.

$\frac{1}{4}$ " to $\frac{3}{8}$ ".—Polished plate glass is manufactured in thicknesses ranging from $\frac{1}{8}$ " to $1\frac{1}{2}$ "; the standard product runs from $\frac{1}{4}$ " to $\frac{3}{8}$ " full. The other thicknesses (whether thicker or thinner) are made specially, and at an increased cost.

The sash or rabbet for regular plate glass glazing should be made to accommodate glass full $\frac{1}{8}$ of an inch thick.

Thick Plate.— $\frac{3}{4}$ ", $\frac{1}{2}$ ", $\frac{5}{8}$ ", $\frac{3}{4}$ ", $\frac{7}{8}$ ", 1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ ".

Glass thicker than the standard product is used for counter tops, deal plates, port and deck lights on ships, aquariums, etc.

Thin Plate, $\frac{1}{8}$ " to $\frac{3}{16}$ ".—One-eighth inch to three-sixteenth inch glass is used largely for residence windows and by car builders and for boat sash, automobile windshields, and for other special purposes where perfect surfaces, high polish and absolute clear vision is wanted, with minimum weight.

Weight.—Plate glass in regular glazing thickness ($\frac{1}{4}$ " to $\frac{3}{8}$ " thick) weighs $3\frac{1}{2}$ lbs. per square foot bare and may be computed at approximately five pounds per square foot boxed for shipment. A rule for figuring shipping weight of plate glass is found in the official price-list as follows:

Extend the glass at $3\frac{1}{2}$ pounds per square foot. Weight of box equals the contents of a plate of greatest width and length of those packed therein, multiplied by 10. Thus:

1 plate, 36"x96" } = 59'x3 $\frac{1}{2}$ ' = 206 $\frac{1}{2}$ pounds.

1 plate, 60"x84" }

Size of box 60"x96" = 40' x 10' = 400 pounds.

606 $\frac{1}{2}$ pounds.

The raw materials may be said to be virtually the same in plate glass as in window glass—the main difference in the finished products being due to the great care exercised in selecting and purifying the ingredients, and the elaborate method of casting, grinding and polishing plate glass as compared to the simple and rapid process of producing window glass from blown cylinders.

Plate glass was first made in France in 1688 and the term "French Plate Glass" or "French Mirrors" has its origin from the development of the plate glass industry in France. The first cast plate made in the United States was produced in 1860 and perfected a few years later so that it may be noted that this is a modern product compared to window glass which was made during the early settlement of this country, at

Jamestown, Va., about 1608. The making of ordinary glass has been included in the industries of almost every country in the world and dates back to ancient Egypt, centuries ago.

Ingredients.—The principal ingredients are silica (white-sand) soda (soda-ash) and lime (lime-stone). Also arsenic, charcoal and cullet (broken glass).

As stated before, the method of producing plate glass widely differs from window glass and it is little known that the melting, casting, rolling, annealing, grinding and polishing of plate involves the mining of silica and coal, the quarrying of limestone, the chemical manufacture of soda-ash on a large scale, the reduction and treatment of fire-clay and an elaborate system of pot-making for crucibles, all of which requires an enormous financial investment, a multitude of men, and extensive factory properties.

It should be stated that the product of the American factories is, by comparison, equal in every way to the European plate glass in clearness, freedom from flaws and defects, homogeneity and finish.

Special Quality and Thickness.—The making of irregular thicknesses, or superfine quality for mirrors or other uses where special glass is needed, requires special processes and entails additional expense in producing, and the making of beveled plates and mirrors necessitates two more elaborate lines of work and machinery and a corps of experts and skilled workmen.

Pot Making.—Pots of fire-clay are such a heavy expense in plate glass manufacture and take so important a part in the successful making of plate glass that the subject deserves special notice. The different clays after being mined are exposed to the weather for some time to bring about disintegration.

At the proper stage finely sifted raw clay is mixed with coarse, burned clay and water. This reduces liability of shrinkage and cracking. It is then "pugged," or kneaded in a mill; kept a long time (sometimes a year) in storage bins to ripen; and afterwards goes through the laborious process of "treading." No machinery has thus far been invented by which the plasticity can be developed as does this primitive treading by the bare feet of men. The clay must be treaded many times. The building of the pots is a slow, tedious and time-killing affair; but this is essential.

Without extreme care, some elements used in the making of the pots might be fused into glass while undergoing the intense heat of the furnace; or they might break in the handling, and much depends upon the strength of the pots.

The average pot must hold about a ton of molten glass, and the average furnace heat necessary is about 3,000 degrees Fahrenheit.

After completion comes the proper drying out of the pots; and this is another feature in which the greatest scientific care is required. No pot may be used until it has been left to season for at least three months, and even a year is desirable. And after all this, the pot has but twenty-five days of usefulness.

Melting and Casting.—The pot, having been first brought to the necessary high temperature, is filled heaping full with its mixed "batch" of ground silica, soda, lime, cullet, etc. Melting reduces the bulk so much that the pot is filled three times before it contains a sufficient charge of metal.

When the proper molten stage is reached the pot is lifted out of the furnace by a crane, is first carefully skimmed to remove surface impurities, and then carried overhead by an electric tramway to the casting table. This is a large, massive, flat table of iron, having as an attachment, a heavy iron

An Enormous Loss



Plate glass breakage causes the loss of millions of dollars every year. Insurance may cover the actual glass cost, but there is no way to recover the tremendous loss of time and inconvenience while waiting for a new glass to be set. Architects can save a great deal of money for their clients by recommending the installations of

ZOURI SAFETY METAL STORE FRONTS

Approved by Underwriters' Laboratories

Glass breakage due to faulty installation is next to impossible when Zouri construction is used. It meets with the approval of a greater number of architects every year. If you don't know about Zouri advantages,

Write for latest catalog

Zouri Drawn Metals Company

Factory and General Offices:
Chicago Heights, Illinois

Makers Also of the Famous International Store Front Construction

roller, which covers the full width, and arranged so as to roll the entire length of the table. The sides of the table are fitted with adjustable strips which gauge the production of plates of different thickness. The pasty, or half-fluid glass metal is now poured upon the table from the pot, and the roller quickly passes over it, leaving a layer of uniform thickness. The heavy roller is now moved out of the way, and then by means of a stowing tool the red hot plate is shoved into an annealing oven or lehr. The plates remain for some time in the lehrs, where the temperature is gradually reduced.

When the plate is taken from the annealing ovens it has a rough, opaque, almost undulating appearance on the surfaces. Only the surface, however, for within it is clear as crystal. First, it is submitted for careful inspection, and then goes to the cutter who takes off the rough edges and squares it into the right dimensions; and thence to the grinding room.

Grinding and Polishing.—The grinding table is a large flat revolving platform made of iron, twenty-five feet or more in diameter. This table is prepared by being flooded with plaster of paris and water; then the glass is carefully lowered, and men mount upon the plate and tramp it into place until it is set. After this, greater security is obtained by pegging with prepared wooden blocks; and the table is set in motion. The grinding is done by revolving runners. Sharp sand is fed upon the table, and a stream of water constantly flows over it. After the first cutting by the sand, emery is used in a similar manner. The plates are inspected after leaving the grinding room, and if scratches or defects are found they are marked.

There are also, not infrequently, nicks and fractures found at this stage; and in such cases the plate must again be cut and squared, or if the defects are too great, the plate is broken up for cullet. The polishing is done on another special table by means of special reciprocating machinery, using rouge, (iron peroxide), applied with water, and rubbing the glass with blocks of felt so arranged that every part of the plate is brought underneath the rubbing surface. The grinding and polishing has reduced the original plate half of its thickness, sometimes more. The material washed away is lost and fully half the original weight of lime and soda has vanished, and even at the completion, the inspectors very carefully scrutinize the glass for excessive defects and reject that which is not up to quality.

Grading and Quality.—New plate is sea-green, looking at the "metal" through the edge, which gradually fades when exposed for a period to sunlight and weather, to a yellow or light brown color due to the action of the elements upon the chemical constituents of the glass.

In the finished product (glazing quality) there may appear some defects which in no way impair the value, beauty, or durability of the glass for ordinary use—such as small seeds or bubbles, short-finish, reams or surface scratches, which are accepted as contingent with the regular run of plate, and even an open bubble or shot-hole (not clear through both surfaces) is passed in standard glazing quality, providing the plate is comparatively free from other defects and of good color and finish.

Special Quality.—When glass of particular quality is desired, a special selection is necessary. This requires an expert in the grading and selection of the material, sometimes necessitates cutting down larger sizes to minimize the amount of defects inherent with the regular production, and adds a proportionate extra cost to special quality plate.

Beveling.—The beveling of plate glass is of such interest and exemplifies such skill on

the part of the workmen that a description of the process should be added to the information already written in the preceding chapter on plate glass.

The glass to be beveled is subjected to treatment in different departments of the beveling plant, each division working out its particular process in taking off the bevel and restoring the surface of the glass to its original polish.

Five divisions of skilled workmen are necessary; namely, roughers, emeriers, smoothers, white-wheelers and buffers (polishers) using different abrasive or polishing materials, such as sand or carborundum, emery, sandstone, pumice and rouge.

The roughing-mill or wheel is a circular cast-iron disc having a fine cut corrugated surface about 30" in diameter, revolving rapidly upon its bearings as a horizontal plane. Sand or carborundum is conveyed to the mill from above through a hopper with a stream of water, so that the sand gives the desired roughness between the iron and the glass while the water minimizes the friction and heat.

Roughing.—(1) The edge of the plate is brought into contact with the swiftly moving roughing wheel, and the sand cuts the bevel to the desired depth. Curved and pattern plates with incurves, mitres, etc., require an expert practiced eye and great skill on the part of the operator.

Emerging.—(2) In the first roughing process the beveled surface has been cut so deep by the coarse sand that it is necessary to follow with a finer abrasive in another mill to bring the bevel to a smoother finish, and emery or finer carborundum is used.

Smoothering.—(3) Then the rough grinding is still further smoothed in the stone mill, or smoother, which is constructed upon the plan of the iron roughing wheel, using a circular revolving sandstone of fine texture with water flowing upon it to reduce friction.

Polishing.—(4) The first polishing process is upon a wood wheel in an upright position which brings the bevel to a dull, milky polish by the use of powdered pumice in solution automatically splashed upon the wheel by a paddle.

Finishing.—(5) The final high gloss polish is put upon the beveled surface by the application of rouge upon the upright polishing wheel which is covered with a layer of thick felt.

Regular Bevel 1½".—The standard width of bevel is 1½" and all beveled plate glass or beveled plate mirrors are furnished with 1½" bevel unless otherwise specified.

Slight scratches may be removed from the surface of plate glass by rubbing with pure thick felt mounted upon a hand-block, and using fine red or black rouge (moistened) as an abrasive. This must be skillfully done to avoid over-polishing or "burning" the delicate annealed surface of the plate.

Grinding and Polishing Edges.—The value of plate glass for furniture tops, desks and tables, show-cases, shelves and numerous other purposes has become generally recognized. The covering of glass with treated edges offers a clean, sanitary surface and an elegant appearance and also beautifies, protects and preserves the furniture.

The process of grinding and polishing the edges, or rounding of corners, curves or pattern lines, is similar to the beveling, except that the work is done on the edge of the plate instead of the surface.

The edge of the glass is rough ground, according to specifications, either rounded or squared or chamfered as desired, and finished through the polishing process—described in the previous chapter.

Wheel-Cut Mitred Work.—For decorative effects on door-plates, side-lights, transoms,

GLASS

for
BUILDING PURPOSES
GLAZING

Copper Store Front Construction

Tyler & Hippach

366-412 West Ohio St.

CHICAGO

TELEPHONE ALL DEPTS., SUPERIOR 4080



General Office and Factory: 410 WEST OHIO STREET, CHICAGO

Manufacturers of Morlite Sidewalk Lights

Roof and Floor Lights

Morlite Complete Store Fronts

Sidewalk
Doors
Sidewalk
Ventilators
Coal Hole
Covers

TELEPHONE SUPERIOR 4080
**Repair and remodel
work given special
attention**

Metal
Store Fronts
Corner
Bars
Division
Bars

partition-glass, etc., the rich effect of mitred design gives a tone of elegance, and emphasizes the beauty of the glass.

The lines are cut V shape into the surface of the glass by a vertical wheel with sharp edges, and the smoothing and polishing is accomplished by the same general process as on the beveled edge. This is identical in appearance and presents the richness and beauty of the finest cut tableware.

Mitred designs on plate glass mirrors or on rolled figured glass produce an elegant effect where special and elaborate decoration is wanted.

WINDOW GLASS.

The quality of window glass or sheet glass, also termed "blown" or "cylinder glass," has been improved by the modern methods of production, and much has been expended in the effort to make perfect blown cylinder material. Yet there are still some waves and general defects accepted in all window glass, due to the process of making, which differs entirely from cast and polished plate.

The glass is blown in cylinder form and flattened by reheating, which gives it a slight bend or bow, a possible variation in thickness in the larger sizes, and surface flaws.

The selection of the various grades is a matter of expert judgment. The large sheets produced, in single or double thickness and heavier, are cut to stock sizes according to the merits of the glass and graded in "AA," "A" or "B" quality. The defects being eliminated to the greatest possible extent. The ingredients, as we have said, are practically the same in window glass as in plate—it is wholly a matter of refinement and process which produces the different kinds of material.

Window glass is made by two methods—by "machine" or by "hand." The difference is in the blowing process—both producing the cylinder from which all window glass is evolved. The same general treatment of the cylinder, to produce flat sheet glass follows in both machine or human blown material, and both produce equally standard quality.

To make the cylinder the molten glass or "metal" is brought to proper consistency by extreme heat, and the glass in the human blown process is "gathered" upon the end of a tube (or blow pipe) from the furnace and blown into a huge cylinder by repeated heatings and blowings, until the material is all evenly distributed. From a globular mass about the size of a man's head, the blower swings the pipe into an alley or opening in the floor, blowing as he swings until the full sized cylinder is formed. This requires skill of the highest degree—the blower, by regulating the amount of material entering the cylinder, makes single strength or double strength or heavier glass as desired.

The blowing machine accomplishes the same result by purely mechanical process—the intricate working of the mechanism, the supply of molten glass, the air pressure, rapidity of action, making single or double thickness, being controlled by a single operator who appears to have supernatural powers, surely never dreamed of throughout the great stretch of years when the glass-blower was master of the art and accredited with inimitable skill.

The cylinder is decapitated at both ends by an ingenious method of spinning a string of hot glass at the proper place, or by the use of a wire wrapped around the glass and electrically heated which causes the cap and crown to break off clean. The cylinder is then split lengthwise—placed in the flattening oven on a large circular stone, and as the heat is increased and as the glass begins to wilt it is quickly smoothed out to the shape of the flat stone, upon which it rests.

Cylinder glass cannot be perfectly flattened, and the waviness and bow or slight curve will always occur in this product.

In glazing, the bend or bow should be glazed outward in the sash—the bulge towards the exterior.

Sizes.—Window glass in double strength, or heavier, is made as large as 30"x90" or 38"x86" or 48"x80" and such extreme sizes containing twenty-five square feet, but it is inadvisable to use such glass in these measurements on account of the liability of breakage and the distorted vision due to waves, etc.

The same may be said of the extreme sizes of single strength which can be made up to 24"x60" or 30"x54" or 36"x50" in sizes containing ten or twelve and one-half sq. ft.

Crystal Sheet Glass.—A heavy blown glass, made by the same process as ordinary window glass and subject to the same inherent defects. Graded in "AA," "A" or "B" quality and made in various thicknesses: 26-ounce, 29-ounce, 34-ounce and 39-ounce ($\frac{1}{8}$ " thick).

In examining samples of small size for inspection of quality, it should be remembered that the large light of glass will show the natural waves and defects, while the small piece may appear nearly perfect.

It is not altogether a matter of expert judgment to determine the various grades and certain rules may be accepted governing window glass specifications.

Thickness and Weight.—Single strength measures approximately twelve lights to the inch, but a small variation either way is permissible. Single strength weighs approximately 16 ounces to the square foot. Double strength measures approximately nine lights to the inch. The thickness should be fairly uniform and the weight approximately twenty-four ounces to the square foot.

Factory Packages.—Window glass is packed in regular sizes approximately 50 square feet to the box up to the 100 united inch bracket (adding width and length), and 100 square feet to the box in sizes over 100 united inches.

Shipping Weights.—Single strength in factory packages weighs from 65 to 75 pounds to the box (shipping weight). Double strength in factory packages weighs from 85 to 110 pounds to the box, 50 foot boxes, (shipping weight.)

Double strength in 100 foot cases weighs approximately 225 pounds (shipping weight).

"AA" or First Quality.—"AA" quality should be clear glass, free from any perceptible amount of air bubbles or blisters, burnt specks or burns, cords and strings. It should have a good gloss and an even surface and be well flattened. By air bubbles it is understood that tiny blisters, or imperfections not perceptible on the cutters' table, but detectable when placing the sheet directly towards the light, would not be objectionable. This should be a careful selection in both single and double and should represent the very best that can be produced in window glass by the present methods.

"A" or Second Quality.—"A" glass is the normal selection of glass when no special selection is desired or specified and it admits of such defects as small strings or lines, small blisters when not too close to one another or located in the center of the sheet. Well flattened, the surface even, and devoid of noticeable scratches, cropper marks, burns and other prominent defects.

"B" or Third Quality.—"B" glass covers a wider range than either "AA" quality or "A" quality. It permits many of the defects inherent to the process of making such as waves, strings, lines, blisters, scratches, burns and other similar or equivalent defects. This quality embraces everything below "A" quality, not stony or full of blisters or other

Daylight Your Buildings
with 3 Way-Luxfer
Prism Glass



American 3 Way-Luxfer Prism Co.
CICERO, ILLINOIS

Manufacturers of Sidewalk Lights, Skylights, Sidewalk Doors,
Prismatic Transom Lights, Sheet Prism and Wired Sheet Prism

GLASS

AND

PAINT

AND

ZOURI
Copper
Store Fronts

SERVICE

H.M.Hooker Glass & Paint Company
651-659 Washington Blvd.
Chicago

large defects objectionable for any common purpose, such as heavy scratches, heavy blisters, cords and sulphur stains.

26-oz. Crystal Sheet.—A cylinder or blown glass heavier than the ordinary Double strength, and graded by the same rules as window glass in first, second or third quality, measuring approximately $\frac{1}{8}$ " in thickness (technically 125/1000 of an inch).

29-oz. Crystal Sheet.—A heavier blown cylinder glass, graded as above (technically 135/1000 of an inch in thickness).

34-oz. Crystal Sheet.—A heavier blown cylinder glass, graded as above, (technically 159/1000 of an inch in thickness).

"4" or 39-oz. Crystal Sheet.—A heavier blown cylinder glass, graded as above, measuring $\frac{3}{8}$ " in thickness.

While there is no uniformity in specifications governing the method of glazing different styles of glass, it is nevertheless advisable to call attention to some features which have been developed through the experience of the glass houses in this business.

It is especially desirable that all glass to be specified for a building be placed under one heading in the architect's specifications under the heading, "Glass and Glazing."

Accuracy is a necessity. Use a standard rule, true to gauge; specify the size plainly. For instance, 56 inches might be confused if written 5' 6", and cut 66 inches—as 5 feet 6 inches. Always specify width first. In measuring, it is advisable to allow a little play and measure inside the rabbet. See that rabbet is made to accommodate glass of the thickness ordered; i. e., order glass of proper thickness to fit rabbet. Measure the opening and see if all sides are squared. Especially if metal work is to be glazed, it is essential to have perfect fit, and in large sizes it is not uncommon to find a warped frame, or not exactly square, slightly different at one side as compared with the other.

Be specific. It is better to give an abundance of information rather than leave anything indefinite, or to be taken for granted. Mistakes will follow carelessness, and corrections involve loss of time and expense.

Plate glass should rest on two pads of felt, leather, lead, oakum or soft wood blocks, one near each end, not against bare metal, or at a single bearing-point which might cause breakage through settling of building, vibration, etc. The soft wood blocks or lead strips are to be preferred.

Do not fasten or bind glazing-mouldings too tight, as it is necessary to allow for expansion and contraction, vibration and readjustment of construction.

Use pure putty. Have sash-rabbet well oiled or painted so that putty will adhere. Give fresh putty glazing time to set before handling or hanging sash. Don't try to back-putty glass with corrugated or figured surface, as the putty cannot be removed from the ridges in the glass.

Steel sash glazing requires special putty for metal rabbets.

Caution.—When glass of any kind has been delivered to a building packed in cases or with paper between the sheets, it is advisable to store the glass under cover in a dry place and unpack it to avoid stains which come from drying out of damp hay, straw, paper, or other packing materials.

Glaze prism-glass with ribs inside—flat surface outside. Regular glazing is done with uncolored putty. If colored putty is desired it should be specified accordingly. Glass is not bedded in putty or back-putted unless specially ordered or specified.

Window glass is regularly glazed with the natural bow or bend outside.

WIRE GLASS.

The use of metal frames, metal window sash and fire-proof construction has increased the demand for wire glass until the production of the material amounts to millions of square feet annually. Not only does this glass minimize the fire hazard, but its resisting and sustaining strength, its unyielding qualities even when cracked make it the logical glass for skylights, elevator shafts, stairwells, etc., where these features are a consideration.

Methods of Making.—Wire glass is made by three methods: 1. (Shuman process) by rolling a sheet of glass, laying the wire mesh upon it while the glass is still plastic, pressing the wire netting into the glass, and by a coincident process smoothing the surfaces. 2. (Appert or Schmertz process) by rolling a thin sheet of glass and laying the wire-mesh upon it and simultaneously pouring and rolling a second sheet of glass on top, imbedding the wire. 3. (Continuous or Solid process) by mechanically crimping the wire netting and placing same on the casting table and pouring and rolling the glass over it to produce a sheet of wire glass.

The introduction of the manufacture of wire glass is of so recent a date as to make the volume of consumption all the more surprising, especially when it is recalled that the product was comparatively unknown twenty years ago.

Standard Thickness $\frac{1}{4}$ ".—Wire glass is made in sheets as large as 60" wide and 130" long and in several thicknesses— $\frac{1}{4}$ " standard thickness for general use and approved by the National Board of Fire Underwriters.

Other Thicknesses.—Thinner wire glass is obtainable— $\frac{3}{8}$ " and $\frac{1}{2}$ " being made for special purposes, but the universal demand is for $\frac{1}{4}$ " or $\frac{3}{8}$ " or heavier, and no wire glass less than $\frac{1}{4}$ " thick is accepted under the rules of the Fire Prevention Bureaus or the National Board of Fire Underwriters.

Underwriters' Requirements.—It is necessary to follow certain rules and regulations in the making of fire-proof windows and construction, as provided by the National Fire Protection Association, and a copy of the requirements of the National Board of Fire Underwriters may be obtained from any member of The National Glass Distributors Association.

Extract from Rules and Requirements of the National Board of Fire Underwriters, Edition of 1906.


Thickness of Glass: Wire glass to have a thickness of at least $\frac{1}{4}$ of an inch at the thinnest point.

Size of Glass: The unsupported surface of the glass allowed, shall be governed by the severity of exposure and be determined in each case by the Underwriters having jurisdiction, but in no case shall it be more than 48 inches in either dimension or exceed 720 square inches.

Windows, doors and partitions should be specified for such sizes as 15"x48", 18"x40", 20"x36" and 24"x30" to conform to the above rule where dimensions are not to exceed 720 square inches. There are also restrictions and regulations governing the depth of rabbet ($\frac{3}{4}$ " deep) bearing of glass ($\frac{3}{8}$ " and style of metal frames and sash to meet the demands of fire-retardant construction and permit reglazing, etc.

Polished Wire Glass.—Wire glass is made in ordinary rolled "rough" or "ribbed" or "figured" patterns, and when ground and polished for clear or transparent vision, is specified under the term:—"Polished Wire Glass."

This is not the quality of clear polished plate, but a polished rough wire glass, with the ordinary run of defects inherent with rough glass which has polished surfaces.




Reduction from Sheet of Full Size Simplex Details.

THE SIMPLEX SYSTEM

of Partition and Ceiling Construction

Architects find that by specifying Simplex System non-bearing partitions and suspended ceilings they can greatly reduce costs of construction and at the same time give the building owner a thoroughly high-grade, fire-proof structure.

Simplex Steel Studs and gypsum plaster boards and plaster are the materials utilized to produce strong, thin, light-weight partitions and ceilings that are both fire and sound resistive.



This Handbook, profusely illustrated with photographs and blue prints, completely outlining The Simplex System, will be sent to architects upon request.

The patented design of the Simplex Stud and method of fastening the plaster board effect marked savings in labor, material and transportation costs. The System is adaptable to all types of buildings.

The subject is so broad and has so many phases that it is impossible to give you a thorough conception of Simplex advantages and methods except through our handbook or a personal demonstration. We shall be glad to give you this information and suggest that you call upon us.

Simplex Steel Products Co.

1146 Roscoe Street

Chicago

Adjoining the C. M. & St. P. switch track

STANDARD RULES OF THE MEASUREMENT OF PLASTERING.

Adopted by the Employing Plasterers' Association of Chicago.

LATH AND PLASTERING

to be measured by the superficial yard, from floor to ceiling for walls, and from wall to wall for ceiling.

In rooms containing one or more horizontal angles between the floor and ceiling line, the ceiling to be measured from wall to wall, as though all walls were vertical, for contents of ceiling, and from floor to highest point of ceiling for height of wall.

OPENINGS.

Openings in plastering to be measured between grounds. No deductions to be made for openings of two feet or less in width. One-half of contents to be deducted for openings two feet or more in width. The contents on all store front openings to be deducted, and the contractor to be allowed one foot six inches for each jamb by the height.

All beams or girders projecting below ceiling line to have one foot in width by total length added for each internal and external angle.

No openings to be deducted from "solid" or "hollow" metal lath and plaster partitions nor for openings in suspended ceilings containing less than 100 square feet, where furring is carried around such openings by plasterer. No openings to be deducted from cement wainscot or base.

CORNER BEADS, ARCHES, ETC.

All corner angles of more or less than 90 degrees, beads, "bullnoses," quirks, rule joints, and moldings, to be measured by the lineal foot on their longest extension, and one foot for each stop or miter.

CORNICES.

Length of cornices to be measured on walls. Plain cornices of one foot girth or less to be measured on walls by the lineal foot. Plain cornices exceeding one foot girth to be measured by the superficial foot. Add one lineal foot to girth for each stop or miter. Enriched cornices (cast work), by the lineal foot for each enrichment.

Arches, corbels, brackets, rings, center pieces, pilasters, columns, capitals, bases, rosettes, bosses, pendants and niches by the piece. Ceiling or frieze plates over eight inches wide by the square foot.

COLUMNS.

All columns to be measured by the lineal foot for plain plastered columns.

CEMENT WAINSCOTING AND BASE.

All cement wainscot to be measured by the square foot, and cement base by the lineal foot.

GROUND.

All grounds for various classes of work to be as follows, unless expressly specified to the contrary:

Grounds for 2-coat lath work.....	$\frac{3}{4}$ inch
Grounds for 3-coat lath work.....	1 inch
Grounds for 3-coat metal lath work.....	$\frac{5}{8}$ inch
Grounds for 3-coat metal lath work, on $\frac{1}{2}$ -inch iron furring.....	$1\frac{1}{8}$ inch
Grounds for 3-coat metal lath work, on 1-inch iron furring.....	$1\frac{5}{8}$ inch
Grounds for hard mortar metal lath work	$\frac{5}{8}$ inch
Grounds for hard mortar metal lath work, on $\frac{1}{2}$ -inch iron furring.....	$1\frac{1}{8}$ inch
Grounds for 2-coat work on brick or tile	$\frac{5}{8}$ inch
Grounds for hard mortar on brick or tile	$\frac{5}{8}$ inch
Grounds for hard mortar lath work.....	$\frac{3}{4}$ inch
Grounds for plaster board.....	$\frac{3}{4}$ inch

Where metal lath is spoken of it applies to all wire or metal lath.

The Employing Plasterers' Association of Chicago solicit the co-operation and support of Architects and others in the Association's efforts to set the highest standard possible for plastering.

In many of the branches of building construction, efforts are tending towards the use of better material and workmanship, no material or finish for a building combines so fully the essentials for fire protection and sanitation at so low a cost to the owner as does plastering, and no other material that enters so largely into the construction of a building presents so large an area of visible surface as does plastering. The cost of plastering represents only a small percentage of the total cost of a building.

It is a necessary base for the most expensive decorations and in itself provides the requisites necessary for a finish interior. The association believes that so important an element in the construction and finish of a building is worthy of being well done, and that the best workmanship and material if specified and called for will more than compensate owners and architects in their requirements for such grade of work. The Employing Plasterers' Association of Chicago respectfully submits the following outline specification for lath and plaster work; all trade names of material have been omitted. Architects will find a list of standard materials in the Hand Book and elsewhere.

TENTATIVE OUTLINE SPECIFICATION FOR LATH AND PLASTER WORK.

Sand. All sand to be clean, sharp lake sand.

Lime. All lime to be fresh burned lump lime.

Lath. All wood lath to be No. 1 white pine $1\frac{1}{2}$ " lath free from sap and bark and even edged.

Nails. To be 3 penny fine 16 gauge wire nail.

Wire Lath. To be No. 18 Washburn and Moen gauge .0475" mesh painted or No. 24 gauge metal lath painted with ribs not less than $\frac{1}{8}$ " wide, lath cut from sheet metal shall weigh not less than 4# per square yard.

Stucco. To be fresh.

Hair. To be well whipped cattle hair.

Fibre. To be long vegetable fibre.

Portland Cement. To be a brand that shall meet the requirements of the standard specifications for Portland Cement of the American Society for testing materials as revised to date by said Society.

Hard Plaster. To be an approved straight gypsum plaster.

Metal Corner Beads. To be a bead not less than 24 gauge galvanized.

Lathing. All wood lath to be nailed to each stud joist or bearing with joints broken not over seven lath to a break, no diagonal nor vertical lathing allowed, a full $\frac{3}{4}$ " key to be left for lime mortar and not less than a full $\frac{1}{4}$ " for hard plaster.

Lime Mortar. To be composed of clean coarse sand, fresh lump lime and hair and fibre in proper proportions and to be well slaked and protected.

Putty. Lime putty to be run off in a tight putty box, thoroughly tempered and screened through a fine putty screen.

Hard Finish. To be composed of cold run lime putty, fresh plaster of paris and sand to be well troweled to a smooth even surface, free from blisters, checks and other imperfections.

Sand Finish. All float sand finish to be composed of lime putty and sand to be

McNulty Bros. Company

Architectural Sculptors
and Plasterers

1028 W. Van Buren St.

Telephone Haymarket 7615

CHICAGO

Pittsburg and Cleveland

OSCAR A. REUM, President

ELMER W. ZANDER, Treasurer

H. E. REUM, Secretary

ZANDER-REUM CO.

Contracting Plasterers

ROOM 808, TRIBUNE BUILDING

7 South Dearborn Street

Telephone, Randolph 1588

CHICAGO

CHICAGO

Telephone Harrison 6981

CLEVELAND

R. S. HALDEMAN, President

F. S. SIMPSON, Secretary

LENNOX-HALDEMAN CO.

PLASTERING

Continental & Commercial Bank Bldg.

208 South La Salle Street

CHICAGO

WILLIAM BALHATCHET CO.

*Plastering
Contractors*

58 W. Washington Street
Chicago

Telephone Central 1373

water floated with a float to an even granular or sand surface.

Scratch Coat. All scratch coating to be well laid on and surface covered with a full coat which is to be scratched with wire scratcher to be well under cut for the brown coat, all lime mortar scratch coating to be dry before applying the brown coat.

Brown Coat. All brown coating to be well applied, allowing only sufficient space for the finish coat, brown coat to be rodged and screeded with all angles straight and true, all hard plaster to be mixed in accordance with the directions of the manufacturer and no hard mortar to be floated with water nor shall any "dead" material be retempered or used.

Wire or Metal Lath. Shall be lapped at each joint or seam and shall be stapled every six inches with blued or galvanized staples.

Band Iron Furring. The following shall be furred with $\frac{1}{4}$ ", $\frac{1}{2}$ ", $\frac{3}{4}$ " or 1" corrugated band iron furring, such furring to be stapled to bearings and the wire or metal lath to be stapled over such band iron furring.

Suspended Ceilings. To be constructed with $1\frac{1}{2}$ " or 2" flat bars, angles or channels as may be called for, such principals shall be spaced 4' 0" on centers, hung with flat bar or not less $\frac{1}{4}$ " rod hangers every 4' 0" securely fastened with approved clips to the structural framing or through the floor construction, in the event these hangers go through the floor construction they shall be provided with 6" channels or flat bar anchors, no hanger shall be supported from the bottom flange of the tile arch. The flat bar, angle or channel runners shall be cross furred 12" on centers with $\frac{3}{4}$ " steel channels, securely secured to the principals with rod clips, entire construction to be lathed with No. 18 W. M. gauge $\frac{3}{8}$ " mesh painted wire lath or No. 24 U. S. Gov. standard gauge metal lath, lath to have lapped edges at each joining and to be tied to the channel furring every 6" with 18 gauge galvanized tie wire.

Furring. All false beam or cornice furring to be constructed of $\frac{3}{4}$ " channel or 1" flat bar brackets not over 2' 0" apart lined out with intermediate furring supports and anchored or toggle bolted into the construction to be made to conform to the design so as to allow for a minimum of plaster, such brackets to be covered with 18 gauge wire or 24 U. S. Gov. gauge metal painted lath secured with 18 gauge galvanized tie wire, such furring to conform to the latest and best practice as to durability of construction.

Cornice Work. All moulded beams and cornices will be screeded and run in place with moulds, with true lines and accurate mitres.

Ornamental Work. All ornamental work to be modeled by artistic modelers who will be approved by the architects. Models to be submitted for approval and no casts to be made until such models have been approved, all patterns to be gotten out by skilled mechanics with true and accurate lines.

Casts. All casts to be well made, the contractor to supply a sufficient number to meet the requirements of the job, all casts to be made in line, well and truly undercut and free from warps and other irregularities supplying all necessary shrinkers and stretchers.

Rough Casting. Lath the exterior of the house with 18 gauge wire or 24 U. S. Gov. metal painted lath stapled over 1" band iron furring scratch coat with mortar composed of 2 vols. of coarse, sharp sand 1 vol. of Atlas or equal, Portland cement, to which mixture add 15% of rich lime mortar, thoroughly scratched and undercut when this coat was "set," brown with mortar composed of 3 vols. sharp sand to 1 vol. Portland cement rod and straighten all surfaces and when this coat has "set" rough cast with mortar composed of 3 vols. of sharp sand or

pebbles to 2 vols. Portland cement dashed on surface with a scoop or paddle to an even artistic finish.

Exterior Plastering on Wood Lath. Lath the exterior with No. 1 soft pine one-inch lath, nailed to each stud furring or bearing with not less than a 3 penny nail with full open $\frac{3}{4}$ " key space and not over seven lath to a break, plaster with 3 coats of cement plaster as called for under exterior plaster on metal lath, note the use of "hard plasters" so called are not recommended for exterior plastering.

Concrete Walls and Columns. All work on concrete walls and columns shall have such concrete well brushed with steel brushes and such concrete shall then be covered with a light coat of an approved bond cement as a bonding coat for the finish coat.

Concrete Ceilings. Shall first be washed with a solution of muriatic acid and such ceilings shall then be plastered as above.

Painted Walls. Walls that are to be coated with waterproofing shall first be scratch coated, then browned and finished.

Patching of Plaster. All patching of plaster damaged by other mechanics shall be paid for at the uniform scale of prices adopted by the Employing Plasterers' Association of Chicago, which scale of prices is set forth in the Hand Book.

Workmen's Compensation. This contractor shall insure his workmen under the provisions of the Workmen's Compensation Laws of the State of Illinois. This contractor shall also insure his liability for injury or death to "the public."

Scaffold. This contractor shall supply all necessary tools, scaffold and other appliances necessary to fulfill the requirements of the job, all scaffolding to be erected and maintained in accordance with the laws of the State relating to scaffolds.

Requirements. By Building Code in buildings of ordinary construction. At least two coats of plaster on all wood lath to $\frac{7}{8}$ " grounds.

By Union. All plain and ornamental plaster to the same contractor, the base coat of Portland cement under encaustic tile, cement base when installed independent of the floor or if 6" or more in height. All plastering regardless of the nature of the structure or of the material used.

RECOMMENDATIONS.

The use of soft pine lath, specify No. 1 white pine lath nailed to each stud, joist or bearing with 3 d. fine 16 gauge wire nails, with joints broken at least once in each seventh course or lath.

For better residence work specify one inch lath as above.

Wire or metal lath, specify No. 18 Washburn and Moen gauge wire lath $\frac{3}{8}$ " mesh, painted, or No. 24 U. S. Gov. standard metal lath painted, for better class work specify wire lath woven from galvanized strand or metal lath galvanized.

The use of wire or metal lath plastered insures slow burning construction, helps to prevent settlement cracks and bonds and ties all parts of the structure together, its use is called for in almost every building, particularly on basement ceilings to prevent or retard fire on ceilings with long span joist construction on store ceilings and under other space subject to heavy use or abuse. Its use should also be general in all better class building, in rated buildings its use throughout entitles it to better classification for insurance.

The Association recommends the use of three coat plastering. This will insure a far better class of work, a better bonding together of buildings of ordinary construction due to the use of a greater body of material. The application of the second base coat enabling one to straighten out rod and line work not possible in the use of two-coat work. Specify three-coat dry work, first coat to be a scratch coat well scratched and un-

SUTTON PLASTERING COMPANY
CONTRACTORS FOR
PLASTERING
PLAIN AND ORNAMENTAL

Suite 1720 Kimball Building, Chicago

Telephone Harrison 5791

Phone Franklin 2605

GOSS & GUISE
Plastering Contractors

1306 Security Building, CHICAGO
Madison and Wells Streets

Telephone Humboldt 3223

WM. WILLIAMS
PLASTERING CONTRACTOR

2841 EDGEWOOD AVENUE

CHICAGO

Telephone, State 4993

N. J. PARENT COMPANY
Plastering Contractors
Plain and Ornamental

5 South Wabash Avenue

CHICAGO

der cut. When dry, apply a brown coat, this brown coat to be screened and rodded and when dry apply a finish coat.

The following suggestions are offered for guidance:

Sand. The use of clean, coarse, sharp lake sand is essential for good plastering.

Metal Lath. Should be laid with lapped edges or joinings and should be stapled to bearings every 6". No suspended ceilings should be supported from the bottom or soffit of tile.

Portland cement base coat behind encaustic tile, Opalite or kindred material should be specified under "Plastering" with one rodded coat scratched on tile or brick or a scratch and rodded brown coat scratched on metal or wire lath. We do not recommend Portland cement direct to gypsum partition or gypsum furrings.

Damp proofed, waterproofed or painted walls and ceilings are required to be given 3 coats. If a finish coat is desired, it should be so specified. All lathing plain and ornamental plastering should be specified under one heading in order to avoid divided responsibility for final results.

JURISDICTION CLAIMS.

By Plasterers' Union, any and all plastering regardless of the nature of the material, or of the structure to which it is applied, including Scagliola made under the "New Process" so called.

By Lathers' Union, all lathing, metal corner beads and all light iron furring designed, specified or used primarily as a support for lath and plaster, including "Hi Rib."

By Hodcarriers and Building Laborers' Union, all scaffolding erected for the use of plasterers.

PATCHING OF PLASTERING AFTER OTHER TRADES.

Patching of plastering after other mechanics shall not be done as a part of the contract price, and shall be paid for at the following scale of prices which have been adopted by and are recommended by the Employing Plasterers' Association of Chicago.

In accordance with wage agreements effective under the "Landis Award," and present prices of materials, the following scale of prices for patching of plastering after other mechanics and for work done upon a time and material basis, is respectfully submitted.

The prices herein include cost of insurance of men under the provisions of the Workmen's Compensation Laws of the State of Illinois.

Foreman Plasterer	\$1.80 per hour
Plasterers	1.55 per hour
Foreman Lather	1.70 per hour
Lathers	1.45 per hour
Plasterer Laborer	1.15 per hour
Mortar	3.25 per bbl.
Putty	3.75 per bbl.
Neat Hard Plaster	1.30 per bag
Stucco	1.30 per bag
Metal or Wire Lath40 per yard
1½" Pine Lath75 per bunch

Owing to abnormal conditions material prices are subject to change without notice.
18 gauge ¾" mesh
painted wire lath
or 24 gauge expanded metal
painted

Where seven or more men are employed in one gang on same kind of work, foreman's time will be charged continuous while work is going on; where less than seven men are employed in one gang on same kind of work, foreman's time shall be counted one hour for each seven hours of men aggregate time employed on this work, unless foreman's time is required constantly, when he shall be so paid.

CITY ORDINANCE.

Be it ordained by the City Council of the City of Chicago:

Section 1. That Section 605 of the Chicago Code of 1911 be and the same is hereby amended so as to read as follows:

605. Wood Lathing and Plastering.) (a) In all buildings of ordinary construction, where the use of wood lath and plaster is permitted under the provisions of this chapter, such wood lath and plaster shall be done in accordance with these specifications:

Wood lath shall not be over one and one-half inches wide, and shall be nailed to each stud, joist or bearing with not less than a three-penny fine 16 gauge nail; lath to have joints broken with not over seven lath to a break; lath to be spaced not less than one-fourth of an inch apart. All wood lath must be covered with at least two coats of plaster; such lath and plaster to finish to a total thickness of at least seven-eighths of an inch; no dirty or loamy sand to be used in the mortar or plaster.

(b) In every building of ordinary construction which contains one or more rooms used for habitation or living purposes, the walls and ceilings of all rooms, including stores (except basement and attic rooms not used for habitation or living purposes), throughout the building shall be covered with not less than two coats of plaster of the thickness and quality hereinbefore in this section prescribed.

Provided, however, that where such building does not exceed one story and basement in height and contains a room or rooms used for the purposes of Class I as defined in this ordinance, a metal ceiling may be installed in the room used for the purpose of Class I; and provided further, that where such building of ordinary construction and containing one or more living rooms is more than one story and basement in height and contains a room or rooms used for the purposes of Class I as defined in this ordinance, a metal ceiling may be installed in such room used for the purpose of Class I according to the following provisions:

The ceiling of the room or rooms used for the purpose of Class I shall first be plastered with at least one coat of plaster on wood lath; wood lath to be not over one and one-half inches wide, and shall be nailed to each stud, joist or bearing with not less than a three-penny fine 16 gauge nail; lath to have joints broken with not over seven lath to a break; lath to be spaced not less than three-eighths of an inch apart. All wood lath to be covered with a heavy coat of mortar; such lath and plaster to finish to a total thickness of three-quarters of an inch in thickness. Before applying such metal ceilings, a wood strip not less than seven-eighths of an inch by one and one-quarter inch wide shall be used under every lap bead, or nailing flange at the intersection of all plates. Strips to be not more than two feet on centers in the direction of length of rooms with a cross strip every four feet on centers. A wire nail not less than three inches long shall be used in every strip at every joist in the surface to be covered. Metal plates to be not lighter than 29 gauge in thickness and nailed to every six inches on the lap.

(c) Where said metal plates are applied on walls of buildings of ordinary construction containing one or more rooms used for habitation or living purposes, plastering upon walls must conform with the requirements of this ordinance for plastered walls. A strip three-eighths of an inch in thickness may be used upon which to apply the metal, same to be nailed to every studding with a nail not less than two and three-quarter inches long; steel plates used on walls to be not lighter than 29 gauge and applied same manner as herein provided for ceilings.

Section 2. This ordinance shall be in force and effect from and after its passage and due publication.



JOSEPH DUX

Architectural Sculptor

STONE AND WOOD CARVING

ORNAMENTAL PLASTER AND CEMENT

ORNAMENTAL PATTERNS

DESIGNING, MODELING

2112-2118 WEST VAN BUREN ST.
NEAR BOYNE AVE.

TEL. WEST 1703

CHICAGO



R. O. SCHMIDT, Pres. C. BAUER, Vice-Pres.
CHR. DOD, Secy. & Treas.

Architectural Decorating Co.

Ornamental and Plain Plastering

1600-1608 S. JEFFERSON STREET

Telephone Canal 1463

Relief Decorations for exteriors and interiors in Cement, Plaster, Carton Piere, Composition and Wood. Porch Columns and Capitals in classic and modern designs, in all standard sizes, and weatherproof material. Sketches for ceiling and wall decorations on application. Ornamental patterns for Brass and Iron Castings. Models for Stone Carving.

ILLUSTRATED CATALOGUE ON APPLICATION

Branch Offices
444 S. Wabash Ave.
24 Van Buren St.

CROFOOT, NIELSEN & CO. BLUE PRINTERS

Blue Printing, Black Printing, Blue Line and Color Printing

Special Service Always—Speed and RESULTS
Big Floor Space and Equipment for Rush Orders

172 W. Washington Street

CHICAGO

Telephones Main 759-684, Harrison 8597



FOR BLUE PRINTS AND DRAWING MATERIAL

CALL UP

HARRISON 8600

American Blue Print Paper Co.

CHICAGO

Main Office
445 Plymouth Court

Branch Offices
104 S. Michigan Ave.
208 So. La Salle St.

STANDARD FORM OF CUT STONE SPECIFICATION

For Indiana Oolitic Limestone

CUT INDIANA LIMESTONE.

1. Work Included:

The work under this contract shall include all labor and material for the furnishing of cut stone work in accordance with the drawings and as hereinafter specified.

2. Description of Stone.

All Limestone specified or shown on drawings shall be standard No. 1 Gray, Standard Gray, No. 1 Buff, Standard Buff, No. 1 Variegated or Standard Variegated Indiana Oolitic Limestone building stock, free from all defects that would materially impair its strength, durability or appearance, and within the range of variation of color and texture represented by two samples approved by the Architect.

Specially graded stone acceptable as to hardness and color as per samples to be submitted shall be employed where indicated on drawings, for

and all other positions exposed to direct wear. Wherever the terms "Indiana Limestone" or "Limestone" occur in this specification, they specifically refer to and shall imply "Indiana Oolitic Limestone" quarried in Lawrence or Monroe County.

3. Samples.

The contractor shall submit to the Architect, two samples which shall be typical of the extremes which the contractor proposes to furnish. Samples to be about 3 $\frac{3}{4}$ " wide by 8 $\frac{1}{2}$ " long by about 1" thick, produced so that the large faces shall show across the grain of the stone, the finish specified to be indicated on the large face and at least two of the edges to be rock face. Similar samples shall be provided when Select stock or specially graded hard stone is specified for certain positions in the building.

These samples shall be labeled or otherwise clearly marked with the name of the contractor submitting same, and the name of the limestone, with the statement: "Samples of Indiana Limestone to be furnished for the () Building."

4. Standard Practice.

Insofar as these specifications pertain to the practice set out for the proper use of Indiana Oolitic Limestone, the standards established by the Indiana Limestone Quarrymen's Association of Bedford, Indiana, are to govern. Bidders not familiar with these standards are cautioned to inform themselves regarding them.

The Architect reserves the right to approve the sub-contractor for Cut Stone before this portion of the work is awarded.

5. Cutting & Setting Drawings.

The cut stone contractor shall prepare and submit to the Architect for his approval complete cutting and setting drawings in triplicate for all of the Indiana Limestone work under this contract. Such drawings shall show in detail sizes, sections and dimensions of stone, the arrangement of joints and bonding, anchoring and other necessary details.

Moulded or projecting courses, unless otherwise shown, shall have not less than four-sevenths (4/7) of their cubic contents inside the face of wall and all projecting stones, except where otherwise shown or specially anchored to the structure, and so provided for by details on setting drawings, shall have beds in the wall at least 1" greater in depth than their maximum projection. There shall be "through" or bond stones wherever indicated on approved stone details.

These drawings shall be based upon and follow the drawings and full size details prepared by the Architect, except where it is agreed in writing that changes be made. No departure from the Architect's drawings shall be indicated on setting drawings

submitted to the Architect for approval unless this departure is specifically called to the Architect's attention by a letter of explanation accompanying same. Each stone indicated on these drawings shall bear a corresponding number marked on the back or bed with a non-staining paint.

Provisions for the proper anchoring and dowelling or clamping of work in keeping with standard practices, also for the support of same by shelf angles and loose steel, etc., when required, shall be clearly indicated on the setting drawings.

6. Details for Lintels, Etc.

Lintels and Architraves or other members spanning openings, where supporting a superimposed load or only their own weight, shall be of the proportions and sectional area that will provide an ample factor of safety based on the average ultimate breaking strength of the stone.

7. Carving & Models.

All carving shall be done under this contract by skilled carvers, in a correct and artistic manner, in strict accord with the spirit and intent of the Architect's sketches, or from plaster models prepared or approved by the Architect.

8. Cutting.

All stone shall be cut accurately to shape and dimensions and full to the square and with jointing as shown on approved drawings. All exposed faces shall be cut true and out of the wind. Beds and all joints shall be dressed straight and at right angles to the face unless otherwise shown and except where otherwise shown or noted on drawings joints shall have a uniform thickness of $\frac{1}{4}$ ".

Patching or hiding of defects will not be permitted and Lewis Holes shall not be made on exposed surfaces.

Washes shall be as deep as practical and drips of sufficient width and depth to shed water shall be provided on all projecting stone and courses. In the absence of specific indication otherwise all coping, caps and sills shall overhang the work below not less than 1 $\frac{1}{2}$ " and shall have $\frac{3}{4}$ " drips.

Reglets for flashing, etc., shall be cut in the stone where so indicated on the drawings.

Moulded work shall be carefully executed from full size details, supplied by the Architect. All arrises to be sharp and true.

All columns shall be accurately cut with the entasis as shown on drawings. All pilasters unless indicated otherwise to be cut straight without entasis or taper.

9. Back Checking & Fitting to Structural Frame.

Stone coming in connection with structural work shall be back checked as indicated on the general drawings. Stones resting on structural work shall have beds shaped to fit the supports.

Where stone facing adjoins steel columns and spandrel girders, the depth of stone shall be such that it will allow not less than three inches between extreme edge of metal and the back of the stone.

10. Finish.

The finish on exposed surfaces generally shall be smooth, machine dressed, showing no tool marks.

11. Lewis Holes & Cutting for Dowels, Anchors, Clamps, Etc.

Lewis Holes shall be cut in all stones weighing more than 100 pounds. No Lewis or other holes shall come closer than 2 inches to the exposed face of the stone.

Holes and sinkages shall be cut in stones for all anchors, clamps, dowels, etc., called for under this specification and indicated on the cutting and setting drawings.

12. Loading & Shipment.

The Cut Indiana Limestone shall be carefully packed for rail or wagon transporta-



Durant Office Building,
Detroit, Michigan

Albert Kahn, Architect
Detroit, Michigan

*"And it can be truly said that such
buildings as these are sermons in Stone."*

IN the block bounded by Cass Ave., Grand Blvd., Milwaukee Ave. and Second Ave., in the City of Detroit, is a new building recently erected by the General Motors Company. It is fifteen stories high and built entirely of Stone. The artificial and the substitute had no part in the construction of this building. It was the desire of the owners and builders to erect a structure that would endure long after every man now living has turned to dust. One material only could be used—Stone.

After investigating the various stones for the exterior of the building, Bedford Indiana Limestone was adopted. For a project of this size, for which a large volume of stone had to be furnished in a short space of time, the Architect and Owners were left but one choice, and the product of the Indiana Quarries Company was decided upon. About 1,500 carloads were supplied in four months' time.

The completed building stands today as a monument to the achievements of the

INDIANA QUARRIES COMPANY

(Branch of the Cleveland Stone Co.)

General Offices:
112 W. ADAMS ST.
Chicago

Quarries and Mills:
BEDFORD, INDIANA

tion with exercise of all customary practical and reasonable precautions against damage in transit.

All cut stone under this contract shall be delivered promptly as ordered and in the sequence in which it is to be set.

13. Field Cutting.

(Specify in detail any field cutting that will be required.)

SETTING CUT STONE.

14. Work Included.

Contractor shall refer to the preceding specification for cut Indiana Limestone for more detailed information regarding the cut stone that is to be set under this contract; also refer to "General Masonry", "Sheet Metal Work", "Roofing" and "Carpentry" specifications for reference to work that must be executed in conjunction with this work.

15. Delivery & Storage.

All Indiana Limestone delivered f. o. b. cars at destination under another contract shall be carefully unloaded and delivered to the building site.

Wagon or truck haul shall be handled throughout by competent workmen and by such methods as will guard against soiling, mutilation or chipping in transit to and upon delivery at the building site.

The stone shall be stored at the building site, for whatever period, on planking set so that stone will rest entirely clear of the ground and be protected by proper means from damage to arrises and from contact with anything which would result in the accumulation of dirt, dust, soot, mud, grease or other staining or disfiguring elements. During extended periods of storage at building site, the stone to be covered with tarpaulin, stout non-staining paper or boards.

16. Setting Mortar.

All Indiana Limestone shall be set in carefully prepared lime mortar tempered with stainless cement of an approved brand. The mixture to consist of one part dry Hydrated Lime or lump lime paste, to not over three parts sharp, washed clean sand, with the addition of stainless cement in an amount equal to 15 per cent by volume of the lime used.

Lump Lime Paste shall be made of best quality freshly burned lump lime slaked with cold water and screened through a three-sixteenths inch mesh screen into a settling box following the practice employed in preparing lime for plastering, the Lime Putty so prepared to stand in the settling box not less than one week and then be mixed with the sand and be properly stacked to age. In each case proper precautions shall be taken by covering or otherwise to absolutely prevent either the lime or mortar from drying out; the cement to be added and thoroughly worked into the mixture in small batches just prior to its use for the setting of the stone.

The sharp sand must be washed clean, entirely free from silt, vegetable matter, salts and all other injurious substances and must be screened if containing pebbles or very coarse grains that would interfere with the proper bedding and jointing of the work. The water must be clear and devoid of salts and all injurious chemical elements.

17. Scaffolding.

All scaffolding required for the proper execution of this work will be furnished and erected by the Masonry Contractor for the use of all mortar using trades.

18. Centering.

All wood centering required for the proper setting of Cut Stone work will be furnished and erected by the Carpentry Contractor.

19. Anchors & Dowels.

All anchors, dowels, clamps, Lewis anchors, etc., required by setting drawings or necessary for the proper erection of the work shall be of thoroughly galvanized

iron. Anchors, etc., to be galvanized after they have been bent to shape.

20. Setting Cut Stone.

The Indiana Limestone shall be set in accordance with the requirements of the drawings. When ready for setting, all stone shall be washed on ALL sides and be scrubbed clean with soap and water applied with fibre brushes only and be thoroughly rinsed with clean water. Immediately prior to setting, all stone shall be sponged or drenched on all sides with clean water.

The stone shall be set accurately, true to line and level by competent stone setters, with full flushed joints. The face to be set on thoroughly soaked wooden wedges, which shall not be removed until the building is cleaned and pointed.

All beds and vertical joints shall be of a maximum width of $\frac{1}{4}$ inch except where otherwise indicated and mortar shall be raked out $\frac{3}{4}$ inch from the face of the stone to allow for pointing, and the stone be sponged off along all joints.

Splashing exposed faces of cut stone with mortar shall be avoided and any splashing shall be immediately removed with a sponge and clean water.

The entire backs of all stone, while wet, shall be plastered with not less than $\frac{1}{2}$ inch coat of setting mortar before backing up same and where the stone occurs as a facing applied direct to previously erected structural members, both back of stone and face of structural work shall be plastered with setting mortar to insure a thoroughly filled back joint.

The ends only of all sills shall be set in a full bed of mortar, balance of sills to be left free until pointed.

Steps shall be set with a slight pitch to the front.

All cornices, copings and projecting belt courses and all stones forming gutters, etc., shall be set with the vertical joints dry. These joints shall be caulked on exposed surfaces with picked oakum and shall then be filled solid from above with a mortar grout. Grout shall be composed of one part non-staining cement and one part fine white sand, mixed in small quantities and of as thick consistency as can be poured into joints, and be stirred vigorously until used.

Where the Limestone extends down to the grade line of the building the first course above grade shall be placed on a layer of approved non-staining impervious material.

21. Backing Up Cut Stone.

The first course of brick next to stone facing, shall be laid in the same kind of mortar as used by Masons for setting of stone.

22. Protection of Finished Work.

The Contractor setting Cut Stone shall co-operate with the Carpentry Contractor who will furnish and erect the necessary protection for sills and projecting stone work.

23. Cleaning.

The face of all stone work under this contract shall be thoroughly cleaned upon completion, this cleaning to be done with soap or soap powder boiled in clean water and applied vigorously with stiff fibre brushes, if necessary, clean, sharp, fine, white sand to be added to the soap and water mixture.

After cleaning, the exposed surfaces are to be drenched with clear water.

The use of wire brushes or acids of any kind will not be permitted under any circumstances for cleaning the stone work.

24. Pointing.

All face joints shall be brushed out clean $\frac{1}{4}$ inch in depth, carefully removing all wedges so that pointing will be continuous and after a thorough wetting of the stone be pointed flush with mortar, consisting of one part stainless cement, two parts clean white sand and sufficient cold lime putty to make as stiff a mixture as can be worked.

CEMENT GUN WORK

Use GUNITE for Walls and Roofs on Industrial Plant Buildings

Mr. Architect—We have successfully completed hundreds of Cement Gun Contracts, including Walls, Roofs, Tanks, Etc.; we have waterproofed Reservoirs, Reconstructed Chimneys, and Repaired Concrete of every kind.

Confer with us before you complete your plans and specifications. Our advice is free and involves no obligations.

WE DO THE WORK

CEMENT GUN CONSTRUCTION CO.

537 S. Dearborn St., Chicago

1112 Keystone Bank Bldg., Pittsburgh



Grain Elevator—GUNITE Walls




Acid Condenser House—GUNITE Walls and Roof

SEPTIC TANKS and SEPTIC CLOSETS


FOR

HOSPITALS, SCHOOLS, HOMES and SUMMER COTTAGES

Require No Chemicals



Septic Tank with Country Residence



Septic Closet

Let us help you solve your Sewage Disposal problems.

We will advise you without charge. We have been in this business for many years and if you will give us full information regarding requirements, lay of land, nature of soil, we will furnish you data for your plans and specifications.

CEMENT PRODUCTS CO., 537 S. Dearborn St., CHICAGO, ILL.

MISCELLANEOUS AND USEFUL INFORMATION CONCERNING BUILDING ENGINEERING, TRADES AND MATERIALS.

The following pages contain tables, formulae, and miscellaneous information intended to be of assistance to architects in the preparation of plans, specifications, estimates, and the general supervision of the construction work. In order to make the classification simple and to follow a uniform system this matter is classified according to the Dewey System, see page 550, and the file or classification numbers are printed in small type at the head of each piece of matter falling under a different classification. As far as possible the names of authorities quoted are given but in some cases this has been impossible.

FILE 690.12

RULES AND FORMULAS FOR THE DESIGN OF SIMPLE WOOD BEAMS OR JOISTS.

When a beam is to be designed its length and the loads to which it is to be subjected are known, thus the maximum bending moment may be found.

The allowable-working-strength is assumed in accordance with engineering practice and must not be more than allowed by building laws, locally applicable. This allowable-working-strength is usually stated in municipal codes as a fixed number of pounds per square inch of cross sectional area, for each kind of material. This might just as well be stated in tons or any other unit of weight per square foot or any other unit of area, it being only important that whatever unit of dimension is used that the same unit shall be used both for areas, lengths and breadths.

Breadth-of-the-beam times the-square-of-the-depth divided by six equals Bending-Moment divided by allowable-working-strength per unit of area corresponding with unit of length used for stating the length and breadth of beam.

Bending-Moment (for beams uniformly loaded) equals weight-to-be-supported-per-unit-of-length times the-square-of-the-total-number-of-units-of-length divided by eight.

For a simple beam loaded with a single weight, the maximum-Bending-Moment (which is to be used in formula) equals the-entire-load times [(the-length-of-the-beam) minus (the-distance-of-the-load-from-the-left-hand-end)] times the-distance-of-the-load-from-the-left-hand-end-of-the-beam divided by the-length-of-the-beam.

If the load be movable the-distance-of-load-from-left-hand-end will be variable and the maximum-moment will be developed when the load is at the middle where the maximum-Bending-Moment is equal to one-fourth-the-load times the-length-of-the-beam. Placing the entire load on a beam at its center therefore produces the maximum strain that it is possible to produce on such beam by any position of such load.

APPLICATION OF ABOVE PRINCIPLES.

M=maximum bending moment.

S=the tensile or compressive unit stress per square inch allowable by building code or engineering practice for the material selected (See Section 539, Chicago Municipal Code, using the smallest value where there is a difference between compression and tension strength.)

l=length in inches of beam between supports.

b=breadth in inches of the beam.

d=depth in inches of the beam.

w=weight in pounds on beam including the weight of the beam itself per each inch of length.

W=total weight in pounds on beam = l w.

FOR UNIFORM LOADING.

$$b = \frac{3 w l^2}{4 d^2 S} = \frac{3 W l}{4 d^2 S} = \text{breadth of beam.}$$

$$d = \sqrt{\frac{3 w l^2}{4 b S}} = \sqrt{\frac{3 W l}{4 b S}} = \text{depth of beam}$$

To find b it is necessary to assume a value for d. Also to find d it is necessary to assume a value for b. In case it is found that the value by formula is too large or too small for practical use, then assumed value must be changed so as to bring the computed value to a practical size.

LOADS IN POUNDS (UNIFORMLY DISTRIBUTED)
TABLE OF STRENGTH OF YELLOW PINE BEAMS
WEIGHT OF BEAM INCLUDED
1910 CHICAGO BUILDING ORDINANCE

Fibre Stress 1300 lb. in². Shear 130 lb. in².
Each beam $\frac{3}{8}$ in. less than nominal width and depth

STRENGTH
Unplastered Construction
Width in Inches

DEFLECTION LIMITED
Plastered Construction
Width in Inches

2 in.	3 in.	4 in.	6 in.	8 in.	10 in.	Span in feet.	2 in.	3 in.	4 in.	6 in.	8 in.	10 in.
6 in. Beam=5% in. Load in pounds.							6 in. Beam=5% in. Load in pounds.					
1491	2409	3327	5163	5	1491	2409	3327	5163
1243	2008	2773	4303	6	1243	2008	2773	4303
1066	1722	2378	3690	7	913	1475	2037	3161
932	1506	2080	3228	8	699	1129	1559	2419
828	1338	1848	2868	9	553	893	1233	1913
746	1205	1664	2582	10	450	727	1004	1558
678	1095	1512	2346	11	371	599	827	1283
621	1003	1385	2149	12	310	501	692	1074
8 in. Beam=7% in.							8 in. Beam=7% in.					
1955	3158	4361	6767	9173	7	1955	3158	4361	6767	9173
1711	2764	3817	5923	8029	8	1711	2764	3817	5923	8029
1523	2460	3397	5271	7145	9	1351	2182	3013	4675	6337
1370	2213	3056	4742	6428	10	1094	1767	2440	3786	5132
1245	2011	2777	4309	5841	11	905	1462	2019	3133	4247
1141	1843	2545	3949	5353	12	761	1229	1697	2633	3569
1053	1701	2349	3645	4941	13	647	1045	1443	2239	3035
978	1580	2182	3386	4590	14	559	903	1247	1935	2623
914	1476	2038	3162	4286	15	488	788	1088	1688	2288
856	1383	1910	2964	4018	16	428	691	954	1480	2006
10 in. Beam=9% in.							10 in. Beam=9% in.					
2709	4376	6043	9377	12711	16045	8	2709	4376	6043	9377	12711	16045
2426	3919	5412	8398	11384	14370	9	2426	3919	5412	8398	11384	14370
2183	3526	4869	7555	10241	12927	10	2183	3526	4869	7555	10241	12927
1986	3208	4430	6874	9318	11762	11	1803	2913	4023	6243	8463	10683
1820	2940	4060	6300	8540	10780	12	1518	2452	3386	5254	7122	8990
1677	2709	3741	5805	7869	9933	13	1292	2087	2882	4472	6062	7652
1560	2520	3480	5400	7320	9240	14	1117	1804	2491	3865	5239	6613
1454	2349	3244	5034	6824	8614	15	972	1570	2168	3364	4560	5766
1365	2205	3045	4725	6405	8085	16	855	1381	1907	2959	4011	5063
1284	2074	2864	4444	6024	7604	17	757	1223	1689	2621	3553	4485
1212	1958	2704	4196	5688	7180	18	676	1092	1508	2340	3172	4004
1149	1856	2563	3977	5391	6805	19	606	979	1352	2096	2840	3584
1092	1764	2436	3780	5124	6468	20	546	882	1218	1890	2562	3234

Continued on next page.

2 in.	3 in.	4 in.	5 in.	6 in.	8 in.	10 in.	12 in.	Span in feet	2 in.	3 in.	4 in.	5 in.	6 in.	8 in.	10 in.	12 in.
12 in. Beam = 11½ in.									2 in. Beam = 11½ in.							
3550	5750	7930	10100	12350	16600	21100	25500	9	3550	5750	7930	10100	12350	16600	21100	25500
3200	5160	7150	9100	11100	15000	19000	23000	10	3200	5160	7130	9100	11100	15000	19000	23000
2910	4700	6500	8300	10100	13700	17400	20900	11	2910	4700	6500	8300	10100	13700	17400	20900
2650	4300	5910	7560	9200	12450	15750	19000	12	2500	4050	5590	7110	8670	11720	14800	17900
2460	3960	5470	7000	8500	11500	14550	17590	13	2125	3440	4750	6080	7380	9990	12600	15200
2290	3670	5070	6500	7890	10650	13450	16300	14	1840	2960	4100	5235	6360	8600	10850	13150
2140	3440	4740	6080	7350	9930	12650	15200	15	1600	2590	3670	4550	5540	7500	9450	11450
1990	3210	4440	5660	6900	9340	11800	14250	16	1405	2270	3140	4000	4860	6590	8500	10080
1870	3025	4160	5330	6490	8760	11050	13380	17	1250	2020	2790	3550	4325	5860	7400	8980
1770	2860	3950	5050	6120	8300	10500	12700	18	1115	1795	2490	3160	3850	5210	6580	8000
1670	2700	3740	4760	5800	7850	9900	12000	19	1000	1615	2230	2840	3455	4695	5910	7150
1590	2575	3550	4530	5500	7480	9430	11400	20	900	1450	2000	2555	3110	4220	5325	6450
1530	2450	3400	4335	5280	7200	9000	10900	21	810	1320	1820	2320	2820	3840	4840	5840
1450	2350	3250	4150	5050	6850	8650	10300	22	745	1200	1660	2120	2580	3500	4410	5340
1390	2250	3100	3950	4800	6550	8300	10000	23	680	1100	1520	1940	2350	3200	4040	4870
1340	2150	2970	3800	4600	6250	7900	9550	24	630	1010	1400	1780	2160	2940	3710	4500
14 in. Beam = 13½ in.									14 in. Beam = 13½ in.							
4000	6450	8900	11400	13850	18700	23700	28700	11	4000	6450	8900	11400	13850	18700	23700	28700
3660	5900	8150	10400	12650	17150	21600	26200	12	3660	5900	8150	10400	12650	17150	21600	26200
3360	5450	7520	9600	11650	15800	20000	24200	13	3360	5450	7520	9600	11650	15800	20000	24200
3140	5060	7000	8910	10850	14700	18580	22500	14	3140	5060	7000	8910	10850	14700	18580	22500
2925	4725	6520	8310	10100	13700	17300	20950	15	2750	4450	6130	7810	9500	12850	16250	19700
2745	4345	6130	7810	9500	12850	16250	19620	16	2400	3875	5350	6830	8300	11240	14200	17200
2590	4170	5760	7350	8940	12150	15300	18500	17	2125	3440	4750	6050	7360	9950	12600	15210
2440	3940	5450	6940	8430	11410	14410	17450	18	1900	3070	4250	5410	6580	8930	11250	13600
2310	3740	5160	6590	8000	10810	13650	16550	19	1700	2740	3790	4840	5880	7960	10100	12150
2195	3550	4900	6240	7600	10260	13000	15700	20	1535	2480	3425	4370	5320	7200	9090	11000
2090	3360	4660	5940	7240	9800	12390	14950	21	1395	2255	3120	3980	4840	6550	8270	10000
2000	3250	4450	5700	6900	9400	11900	14300	22	1270	2050	2830	3600	4400	5950	7500	9100
1900	3090	4250	5430	6600	9000	11350	13700	23	1160	1870	2590	3300	4000	5450	6850	8300
1830	2950	4090	5200	6320	8600	10900	13100	24	1070	1720	2370	3070	3690	5000	6300	7600
16 in. Beam = 15½ in.									16 in. Beam = 15½ in.							
4410	7150	9860	12600	15400	20800	26400	31600	13	4410	7150	9860	12600	15400	20800	26400	31600
4100	6625	9150	11660	14200	19240	24280	29380	14	4100	6625	9150	11660	14200	19240	24280	29380
3830	6190	8540	10890	13240	17950	22650	27400	15	3830	6190	8540	10890	13240	17950	22650	27400
3580	5790	8000	10200	12400	16800	21205	25650	16	3565	5770	7970	10160	12350	16750	21190	25640
3380	5455	7545	9620	11700	15850	20000	24200	17	3180	5140	7095	9050	11000	14900	18830	22790
3185	5160	7120	9095	11050	14960	18900	22850	18	2840	4580	6325	8060	9810	13300	16800	20250
3020	4880	6745	8600	10450	14180	17900	21600	19	2540	4100	5655	7225	8790	11900	15050	18180
2865	4640	6400	8160	9925	13450	16980	20500	20	2290	3700	5105	6520	7930	10750	13550	16400
2740	4425	6110	7800	9480	12850	16200	19600	21	2080	3360	4640	5925	7200	9755	12310	14900
2610	4220	5825	7445	9050	12250	15490	18700	22	1895	3065	4240	5400	6560	8900	11230	13580
2500	4045	5590	7125	8660	11740	14810	17900	23	1740	2805	3880	4950	6025	8150	10300	12430
2400	3890	5370	6850	8150	11300	14300	17200	24	1600	2570	3580	4580	5580	7500	9500	11400
2300	3720	5150	6550	8000	10900	13700	16500	25	1470	2370	3300	4200	5100	6950	8750	10500
2220	3580	4930	6300	7650	10400	13100	15800	26	1360	2200	3030	3880	4700	6400	8100	9700
18 in. Beam = 17½ in.									18 in. Beam = 17½ in.							
4875	7860	10860	13860	16880	22850	28850	34950	15	4875	7860	10860	13860	16880	22850	28850	34950
4560	7370	10180	13000	15800	21400	27000	32650	16	4560	7370	10180	13000	15800	21400	27000	32650
4300	6950	9580	12210	14895	20180	25300	30750	17	4300	6950	9580	12210	14895	20180	25300	30750
4050	6550	9040	11520	14000	19000	24000	29000	18	4050	6550	9040	11520	14000	19000	24000	29000
3840	6210	8560	10930	13300	18030	22800	27500	19	3640	5880	8110	10350	12550	17080	21500	26100
3645	5895	8140	10350	12610	17100	21600	26050	20	3295	5320	7350	9350	11410	15400	19450	23500
3470	5610	7750	9890	12030	16300	20600	24850	21	3040	4900	6760	8630	10500	14200	17950	21700
3310	5350	7400	9450	11460	15550	19630	23750	22	2730	4400	6090	7750	9410	12750	16100	19500
3170	5120	7060	9000	10950	14850	18750	22650	23	2545	4110	5660	7230	8800	11900	15000	18200
3040	4920	6800	8625	10520	14260	18000	21800	24	2290	3700	5100	6510	7900	10700	13550	16400
2910	4700	6500	8300	10100	13700	17300	20800	25	2120	3400	4700	6000	7350	9900	12500	15100
2800	4510	6250	7980	9700	13200	16600	20000	26	1950	3150	4370	5600	6800	9200	11600	14000

TABLES OF WORKING STRESSES IN ORDINARY STRUCTURAL DESIGN

By BENJAMIN E. WINSLOW, M. W. S. E.

The tables and data given on pages 358, 359 and 360 are extracts from articles published by Mr. Winslow in "The Technograph" (Editor)

ULTIMATE AND SAFE STRENGTH OF WOOD IN POUNDS PER SQUARE INCH

MATERIAL	Extreme Fiber Stresses				Compression with the Grain				Compression Across the Grain				Modulus of Elasticity				Weight per Cubic Foot	
	Ultimate		Safe		Ultimate		Safe		Ultimate		Safe		Ultimate		From	To		
	From	To	To	Av.	From	To	To	Av.	From	To	To	Av.						
Long Leaf Pine.....	7000	14000		1500	6000	9000		1500	1000	2000		350	1,500,000	2,250,000	40	50		
Oregon Pine.....	7000	13000		1400	6000	9000		1400	900	1800		300	1,400,000	2,100,000	35	45		
White Oak.....	6000	12000		1300	5000	8000		1300	1500	3000		500	1,300,000	1,950,000	45	55		
Short Leaf Pine.....	6000	11000		1200	5000	8000		1200	900	1800		300	1,200,000	1,800,000	35	45		
Spruce.....	5000	10000		1100	4000	7000		1100	800	1600		250	1,100,000	1,650,000	30	40		
Norway Pine.....	5000	9000		1000	4000	6000		1000	700	1400		200	1,000,000	1,500,000	30	40		
White Pine.....	4000	8000		900	4000	6000		900	600	1200		200	900,000	1,350,000	25	30		
Fir.....	4000	7000		800	3000	5000		800	600	1200		200	800,000	1,200,000	25	30		
Hemlock.....	3000	6000		700	3000	4000		700	600	1200		200	700,000	1,050,000	25	30		
Cedar.....	3000	5000		600	3000	4000		600	500	1000		200	600,000	900,000	20	25		
MATERIAL	Shear with the Grain				Shear Across the Grain				Tension with the Grain				Elastic Limit		Modulus of Resilience			
	Ultimate		Safe		Ultimate		Safe		Ultimate		Safe		Ultimate		From	To		
	From	To	To	Av.	From	To	To	Av.	From	To	To	Av.						
Long Leaf Pine.....	400	800		150	4000	6000		1030	8000	15000		1700	6000	12000	3.0			
Oregon Pine.....	400	700		140	4000	5000		900	8000	14000		1600	6000	11000	3.0			
White Oak.....	400	1000		200	4000	6000		900	7000	14000		1500	5000	11000	3.0			
Short Leaf Pine.....	350	700		120	3000	5000		800	7000	13000		1400	5000	10000	2.5			
Spruce.....	300	600		110	3000	4000		800	6000	12000		1300	4000	9000	2.5			
Norway Pine.....	300	600		100	3000	4000		700	6000	11000		1200	4000	8000	2.5			
White Pine.....	300	600		90	2000	3500		600	5000	10000		1100	3500	7000	2.0			
Fir.....	250	500		80	2000	3000		500	5000	10000		1000	3000	6000	2.0			
Hemlock.....	200	400		70	2000	3000		500	4000	9000		900	2500	5000	2.0			
Cedar.....	200	400		60	2000	2500		400	4000	8000		800	2500	4500	1.5			

ULTIMATE AND SAFE STRENGTH OF CONCRETE IN POUNDS PER SQUARE INCH.

Modulus of Elasticity of P. C. Stone Concrete 1:2:4—60 Days Old for Various Stresses	Initial Mod. of Elasticity....	Modulus of Elasticity	Strength of 1:2:4 P. C. Stone Concrete for Various Ages				Compression on Top Fibers of Beams		Modulus of Elasticity	
			Ultimate	Ultimate		Safe	Ultimate	From	To	
				From	To					
										From
		2,000,000	1 Day Old	200	300	0				
	E. for Stress of 400 lbs pr. □	1,700,000	2 “ “	400	700	100				
	“ “ 600 “ “	1,600,000	4 “ “	600	1000	200	800,000	1,300,000		
	“ “ 800 “ “	1,500,000	7 “ “	900	1500	375	1,200,000	2,000,000		
	“ “ 1000 “ “	1,400,000	1 Month Old.....	1200	2000	500	1,600,000	2,600,000		
	“ “ 1200 “ “	1,300,000	2 “ “	1400	2300	575	1,800,000	3,000,000		
	“ “ 1400 “ “	1,100,000	3 “ “	1500	2500	625	2,000,000	3,300,000		
	“ “ 1600 “ “	900,000	6 “ “	1600	2700	675	2,200,000	3,600,000		
	“ “ 1800 “ “	600,000	1 Year Old.....	1700	2900	725	2,300,000	3,800,000		
	P. for Ultimate Strength....	0	2 “ “	1800	3000	750	2,400,000	4,000,000		

These tables will cover variations of the material and give the range of strength that could be expected of good ordinary materials and workmanship. Inferior materials will come below the lowest limits given in these tables, and superior materials will come above the highest limits. The safe compressive unit stress to be used for long columns should be obtained from the use of some approved column formulae, which also should take care of possible eccentric applications of the load.

The safe extreme fiber stress for long, narrow beams and girders, including plate girders, not braced sideways, should also be obtained from some approved column formulae. In this manner the lateral strength of beams is

provided for.

The following method is believed to conform with good practice for computing loads in buildings:

Figure all parts of the building for the full dead load.
Figure joists and beams for the full live load.

Figure girders for 85 to 90 per cent of the live load.

reducing the live load for a building for the full live load. For each succeeding story below, make a reduction of 5 per cent in the full live load coming on the columns. This reduction must however, not exceed 50 per cent of the full live load for a many stored building.

Figure the foundations for one-third of the full live load.

ULTIMATE AND SAFE STRENGTH OF MASONRY IN POUNDS PER SQUARE INCH.

MATERIAL	Compression			Safe Bearing	Modulus of Elasticity			Shear			Tension			Weight per Cubic Foot		
	Ultimate		Safe		Ultimate		Ultimate		Ultimate		Safe					
	From	To			Av.	From	To	From	To	From		To	From	To		
						From	To		From	To	Av.		From	To	From	To
Hard Brick Work in P. C.	2000	3000	200	275	1,500,000	2,500,000						100	200	20	130	150
Common " P. C.	1500	2500	175	250	1,500,000	2,500,000	150	300	20			100	200	20	110	130
" " N. C.	1000	2000	150	200	1,000,000	1,500,000						50	100	10	110	130
" " L. M.	800	1600	100	150	500,000	1,000,000						20	40	5	110	130
" " P. C. & L. M.	1000	2000	150	200	1,000,000	1,500,000						50	100	10	110	130
Old Brick Work in P. C.	2000	3000	200	275	2,000,000	3,000,000						120	250	25	110	130
" " N. C.	1500	2500	175	250	1,500,000	2,000,000						70	120	15	110	130
" " L. M.	1000	2000	150	200	1,000,000	1,500,000						25	50	7	110	130
Brick Piers in P. C.	1500	2500	175	250	1,500,000	2,500,000						100	200	20	110	130
" " L. M.	800	1600	100	150	500,000	1,000,000						20	40	5	110	130
" " P. C.	1000	2000	150	200	1,500,000	2,500,000						70	150	20	130	150
Rubble Work in P. C.	1500	2500	175	250	2,000,000	3,000,000						100	200	20	140	160
Coursed Rubble in P. C.	1500	2500	175	250	2,000,000	3,000,000						100	200	20	140	160
Neat P. C.	2000	4000	200	300	1,500,000	3,000,000	1200	2400	300			400	800	70	80	90
Neat N. C.	1000	3000	175	250	1,000,000	2,000,000	700	1500	125			200	400	30	60	70
P. C. Mortar 1 : 3	1500	2500	175	250	1,000,000	2,000,000						200	400	30	120	130
N. C. Mortar 1 : 2	800	1500	150	200	800,000	1,500,000						150	200	20	120	130
Lime Mortar	200	400	100	150	500,000	800,000						50	100	10	90	110
P. C. Stone Concrete 1:2:4	1500	3500	400	500	1,500,000	3,500,000	800	1200	125			200	400	40	140	150
" " N. C.	1000	2000	200	300	1,000,000	2,000,000	500	1000	80			150	300	25	140	150
P. C. Cinder 1:2:5	800	1600	150	200	500,000	1,000,000	70	120	10			100	150	20	100	110
Granite	12000	20000	400	600	3,000,000	6,000,000	1200	2400	300			1200	2400	200	160	180
Limestone	6000	12000	350	500	2,000,000	5,000,000	1000	2000	175			1000	2000	175	150	170
Sandstone	5000	10000	300	400	1,000,000	3,000,000	800	1600	125			800	1600	125	140	160
Brick and Tile	2000	5000	200	300	1,000,000	3,000,000	500	1000	80			500	1000	80	120	140

ULTIMATE AND SAFE STRENGTH OF IRON AND STEEL IN POUNDS PER SQUARE INCH

Material	Compression			Safe Bearing	Shear			Modulus of Elasticity		Weight per Cu. Ft.
	Ultimate		Safe Average		Ultimate		Safe Average	Ultimate		
	From	To			From	To		From	To	
Hard Steel	36,000	40,000	18,000	26,000	45,000	55,000	12,000	28,000,000	31,000,000	490
Medium Steel	33,000	38,000	16,000	24,000	50,000	60,000	12,000	"	"	"
Steel Pins	33,000	38,000	16,000	24,000	50,000	60,000	12,000	"	"	"
Shop Rivets	24,000	29,000	16,000	24,000	50,000	60,000	12,000	"	"	"
Field Rivets	24,000	29,000	12,000	20,000	50,000	60,000	10,000	"	"	"
Cast Steel	60,000	90,000	12,000	26,000	50,000	60,000	12,000	29,000,000	32,000,000	"
Cast Iron	60,000	90,000	10,000	15,000	15,000	25,000	2,000	12,000,000	18,000,000	450

Material	Extreme Fiber Stress			Tension			Elastic Limit		Modulus of Resilience
	Ultimate		Safe Average	Ultimate		Safe Average	Ultimate		
	From	To		From	To		From	To	
Hard Steel	50,000	70,000	18,000	65,000	75,000	18,000	35,000	45,000	35
Medium Steel	40,000	60,000	16,000	60,000	70,000	16,000	30,000	40,000	35
Steel Pins	40,000	60,000	24,000	60,000	70,000	16,000	30,000	40,000	
Shop Rivets	40,000	60,000	24,000	48,000	58,000		24,000	30,000	
Field Rivets	40,000	60,000	18,000	46,000	54,000		24,000	30,000	
Cast Steel	60,000	90,000	16,000			18,000	35,000	50,000	
Cast Iron	30,000	40,000	3,500			3,000	10,000	20,000	1.2

PERCENTAGE OF HOOPING FOR VARIOUS CORE DIAMETERS AND HOOPING FOR HOOPED REINFORCED CONCRETE COLUMNS.

BY BENJ. E. WINSLOW, Mem. A. I. A. and Mem. Am. Soc. C. E.

MAXIMUM PITCH OF SPIRALS TO BE NOT GREATER THAN 1/10 THE DIAM. OF COL. NOR GREATER THAN 3"																		
Minimum No. of Rods																		
Pitch	3/16" Hooping			1/4" Hooping			5/16" Hooping			3/4" Hooping			1" Hooping			1 1/8" Hooping		
	1 3/8"	1 1/2"	1 1/4"	1 3/4"	1 3/8"	1 1/2"	1 5/8"	1 3/4"	1 3/8"	2"	2 1/4"	2 1/2"	2 3/4"	2 1/2"	2 1/4"	2 3/8"	2 3/4"	3"
9	0.89	0.82	1.46															
10	0.80	0.74	1.31															
11	0.73	0.67	1.19															
12	0.67	0.61	1.09	1.01	0.94	0.87	0.82	1.71	1.57	1.46	1.36	1.27	1.14	1.03		1.46	1.34	1.24
13	0.62	0.57	1.01	0.93	0.87	0.81	0.75	1.58	1.45	1.35	1.25	1.17	1.06	0.95	1.50	1.36	1.24	1.14
14	0.57	0.53	0.94	0.87	0.81	0.75	0.70	1.46	1.35	1.25	1.17	1.09	0.98	0.88	1.58	1.40	1.26	1.15
15	0.54	0.49	0.87	0.81	0.75	0.70	0.65	1.36	1.26	1.17	1.09	1.02	0.91	0.82	1.57	1.47	1.31	1.17
16	0.50		0.82	0.76	0.70	0.66	0.61	1.28	1.18	1.10	1.02	0.96	0.85	0.77	1.58	1.47	1.38	1.23
17	0.47		0.77	0.71	0.66	0.62	0.58	1.21	1.11	1.03	0.96	0.90	0.81	0.72	1.49	1.39	1.30	1.16
18			0.73	0.67	0.63	0.58	0.54	1.14	1.05	0.97	0.91	0.85	0.76	0.68	1.51	1.40	1.31	1.22
19			0.69	0.64	0.59	0.55	0.52	1.08	1.00	0.93	0.86	0.81	0.72	0.65	1.43	1.33	1.24	1.16
20			0.66	0.61	0.56	0.52	0.49	1.02	0.95	0.88	0.82	0.76	0.68	0.61	1.36	1.26	1.18	1.12
21			0.62	0.58	0.54	0.50		0.98	0.90	0.84	0.78	0.73	0.65	0.58	1.30	1.20	1.12	1.05
22			0.60	0.55	0.51	0.48		0.93	0.86	0.80	0.75	0.70	0.62	0.56	1.24	1.15	1.07	1.00
23			0.57	0.53	0.49			0.89	0.82	0.76	0.71	0.67	0.59	0.53	1.18	1.10	1.02	0.96
24			0.55	0.50				0.85	0.79	0.73	0.68	0.64	0.57	0.51	1.13	1.05	0.98	0.92
25			0.52	0.49				0.82	0.76	0.70	0.66	0.61	0.55	0.49	1.09	1.01	0.94	0.87
26			0.50					0.79	0.73	0.67	0.63	0.59	0.53		1.05	0.97	0.91	0.85
27			0.49					0.76	0.70	0.65	0.61	0.57	0.51		1.01	0.94	0.87	0.82
28								0.73	0.68	0.63	0.59	0.55	0.49		0.97	0.90	0.84	0.79
29								0.71	0.65	0.60	0.57	0.53			0.94	0.87	0.81	0.76
30								0.68	0.63	0.58	0.55	0.51			0.91	0.84	0.79	0.73
31															0.85	0.79	0.74	0.69
32								0.64	0.59	0.55	0.51	0.48			0.80	0.74	0.69	0.65
33								0.60	0.56	0.52	0.48				0.76	0.70	0.66	0.61
34								0.57	0.53	0.49					0.72	0.67	0.62	0.58
35								0.54	0.50						0.68	0.63	0.59	0.55
36								0.51	0.47						0.65	0.60	0.56	0.53
37								0.50							0.62	0.57	0.54	0.50
38								0.47							0.59	0.55	0.51	0.48
39															0.57	0.53	0.49	
40															0.54	0.51		
41															0.52	0.49		
42															0.50			
43																		
44																		
45																		
46																		
47																		
48																		
49																		
50																		
51																		
52																		
53																		
54																		

NOTE: Values inside of heavy lines are within the limits set by the Chicago Building Ordinance. See Sec. 546-567.

7/16" Hooping										1/2" Hooping										3/16" Hooping																										
Pitch										Core Diameter, for Column										Core Diameter, for Column																										
1 3/4"	1 1/2"	2"	2 1/8"	2 1/4"	2 1/2"	2 3/4"	3"	3 1/4"	3 1/2"	1 3/4"	1 1/2"	2"	2 1/8"	2 1/4"	2 1/2"	2 3/4"	3"	3 1/4"	3 1/2"	1 3/4"	1 1/2"	2"	2 1/8"	2 1/4"	2 1/2"	2 3/4"	3"	3 1/4"	3 1/2"	1 3/4"	1 1/2"	2"	2 1/8"	2 1/4"	2 1/2"	2 3/4"	3"									
16					1.50	1.37	1.25										1.53																				6									
17					1.57	1.41	1.29	1.18									1.59	1.45																				6								
18				1.57	1.48	1.33	1.22	1.11									1.50	1.37																				8								
19				1.49	1.40	1.26	1.16	1.05									1.57	1.43	1.30																			8								
20		1.60	1.51	1.41	1.33	1.29	1.10	1.00									1.50	1.36	1.24																			8								
21		1.53	1.43	1.35	1.27	1.14	1.04	0.95									1.59	1.43	1.30	1.18																		1.58	8							
22	1.56	1.46	1.37	1.29	1.22	1.09	1.00	0.91									1.52	1.37	1.24	1.13																		1.51	8							
23	1.49	1.39	1.31	1.23	1.16	1.07	0.95	0.87									1.54	1.45	1.31	1.19	1.09																	1.44	8							
24	1.43	1.34	1.25	1.18	1.11	1.00	0.91	0.83									1.57	1.48	1.40	1.26	1.14	1.04																1.45	1.33	9						
25	1.37	1.28	1.20	1.13	1.07	0.96	0.88	0.80									1.51	1.42	1.34	1.21	1.10	1.01																1.53	1.39	1.28	9					
26	1.32	1.23	1.16	1.09	1.03	0.93	0.84	0.77									1.45	1.37	1.29	1.16	1.06	0.97																1.47	1.34	1.23	9					
27	1.27	1.19	1.11	1.05	0.99	0.89	0.81	0.74									1.55	1.40	1.32	1.25	1.12	1.02	0.93																1.58	1.42	1.29	1.18	10			
28	1.23	1.15	1.07	1.01	0.96	0.86	0.77	0.72									1.60	1.50	1.40	1.32	1.25	1.12	1.02	0.93															1.52	1.37	1.25	1.14	10			
29	1.18	1.10	1.04	0.98	0.92	0.83	0.75	0.69									1.55	1.44	1.35	1.27	1.20	1.08	0.99	0.90																1.51	1.38	1.24	1.13	1.04	11	
30	1.14	1.07	1.00	0.94	0.89	0.80	0.73	0.67									1.50	1.40	1.31	1.23	1.16	1.05	0.95	0.87																1.61	1.47	1.32	1.20	1.10	10	
32	1.07	1.00	0.95	0.88	0.84	0.75	0.68	0.63									1.40	1.31	1.23	1.15	1.09	0.98	0.89	0.82																1.51	1.38	1.24	1.13	1.04	11	
34	1.01	0.94	0.88	0.83	0.79	0.71	0.64	0.59									1.32	1.23	1.15	1.09	1.03	0.92	0.84	0.77																1.56	1.46	1.30	1.17	1.06	0.98	12
36	0.95	0.89	0.83	0.79	0.74	0.67	0.61	0.56									1.25	1.16	1.09	1.02	0.97	0.87	0.79	0.73																1.47	1.38	1.23	1.10	1.00	0.92	13
38	0.90	0.84	0.79	0.75	0.70	0.63	0.58	0.53									1.18	1.10	1.03	0.97	0.92	0.83	0.75	0.69																1.40	1.31	1.16	1.05	0.95	0.87	13
40	0.86	0.80	0.75	0.71	0.67	0.60	0.55	0.50									1.12	1.05	0.98	0.92	0.87	0.79	0.71	0.65															1.32	1.24	1.10	0.99	0.90	0.83	14	
42	0.82	0.76	0.72	0.67	0.64	0.57	0.52	0.48									1.07	1.00	0.94	0.88	0.83	0.75	0.68	0.62															1.26	1.18	1.05	0.95	0.86	0.79	15	
44	0.78	0.73	0.68	0.64	0.61	0.55	0.50										1.02	0.95	0.89	0.84	0.79	0.71	0.65	0.60														1.20	1.13	1.00	0.90	0.82	0.75	15		
46	0.75	0.70	0.65	0.62	0.59	0.52	0.49										0.98	0.91	0.85	0.80	0.76	0.68	0.62	0.57														1.15	1.08	0.96	0.87	0.79	0.72	16		
48	0.72	0.67	0.63	0.59	0.56	0.50											0.94	0.87	0.82	0.77	0.73	0.65	0.60	0.55														1.10	1.03	0.92	0.83	0.75	0.69	17		
50	0.69	0.64	0.60	0.57	0.54	0.48											0.90	0.84	0.79	0.74	0.70	0.63	0.57	0.52														1.06	0.99	0.88	0.80	0.72	0.66	18		
52	0.66	0.62	0.58	0.54	0.51												0.86	0.80	0.75	0.71	0.67	0.60	0.55	0.50													1.02	0.96	0.85	0.77	0.70	0.64	18			
54	0.64	0.59	0.56	0.52	0.49												0.83	0.78	0.73	0.68	0.65	0.58	0.53	0.49													0.98	0.92	0.82	0.74	0.67	0.61	19			
56	0.61	0.57	0.54	0.50													0.80	0.75	0.70	0.66	0.62	0.56	0.51														0.95	0.89	0.79	0.71	0.65	0.59	20			
60	0.57	0.53	0.50	0.47													0.75	0.70	0.65	0.62	0.58	0.52														0.88	0.83	0.74	0.65	0.60	0.55	21				

FORMULAS FOR CONCRETE COLUMNS ACCORDING TO THE CHICAGO BUILDING ORDINANCES.

- I. For All Concrete Columns:
 $W = Af$ Total safe load in lbs.
 $A =$ Total cross section area of columns in sq. ins. for II.
 $f =$ Average allowable unit stress in lbs. per sq. in. (in II and III).
 $p =$ Percentage of vertical steel (expressed in whole numbers).
 $p =$ Percentage of hooping steel (expressed in whole numbers).
Maximum height of columns must not exceed $12 \times$ diameter, and no column shall have a cross section area of less than 64 sq. in.
- II. Reinforced Concrete Columns III. Hooped Reinforced Concrete Columns:
1:1:2 Concrete $f = 580$ (1+0.09p) 1:1:2 Concrete $f = 725$ (1+0.25p) (1+0.09p)
1:1 1/2:3 Concrete $f = 480$ (1+0.11p) 1:1 1/2:3 Concrete $f = 600$ (1+0.30p) (1+0.11p)
1:2:4 Concrete $f = 400$ (1+0.14p) 1:2:4 Concrete $f = 500$ (1+0.375p) (1+0.14p)
1:2:4 Concrete $f = 400$ (1+0.14p) 1:2:4 Concrete $f = 500$ (1+0.375p) (1+0.14p)
1:2:4 Concrete $f = 400$ (1+0.14p) 1:2:4 Concrete $f = 500$ (1+0.375p) (1+0.14p)

(See Sec. 552 Building Ordinances of Chicago, Ill.)

TABLE I.

Copyrighted 1916, by Benj. E. Winslow.

Safe Extreme Fiber Stresses for Reinforced Concrete Beams in Accordance with the Chicago Building Ordinance Requirements for Concrete of Various Mixtures and Various Safe Stresses in the Steel Reinforcement. Straight Line Theory.

BY BENJ. E. WINSLOW, Mem. A. I. A. and Mem. Am. Soc. C. E.

Percentage of tensile reinforcing.	Mixture of concrete. Stone.					Stress in steel.	
	1:1.2.	1:1½:3.	1:2:4.	1:2½:5.	1:3:7.	16000.	18000.
0.00	58	48	40	35	30	0	0
0.01	11	11	11	11	11	9	11
0.02	21	21	21	21	21	19	21
0.03	31	31	31	31	31	28	31
0.04	41	41	41	41	41	37	42
0.05	50	50	50	50	50	45	50
0.06	60	60	60	60	60	55	60
0.07	70	70	70	70	70	65	70
0.08	80	80	80	80	80	70	80
0.09	90	90	90	90	90	80	90
0.10	100	100	100	100	100	90	100
0.11	115	115	115	110	110	100	115
0.12	125	125	125	120	120	110	125
0.13	135	135	135	130	130	120	135
0.14	145	145	145	140	140	125	145
0.15	150	150	150	145	145	135	150
0.16	160	160	160	155	155	145	160
0.17	170	170	170	165	165	150	170
0.18	180	180	180	175	175	160	180
0.19	190	190	190	185	185	170	190
0.20	205	205	205	200	200	180	205
0.22	220	220	220	215	215	195	220
0.24	240	240	240	235	235	210	240
0.26	260	260	260	250	250	230	260
0.28	280	280	275	270	270	245	275
0.30	300	300	295	295	290	265	295
0.32	320	320	315	315	310	280	315
0.34	335	335	330	330	325	295	330
0.36	355	355	350	350	345	310	350
0.38	375	375	370	370	365	330	375
0.40	395	395	390	390	385	345	390
0.42	415	415	410	400	400	365	410
0.44	430	430	425	420	420	380	425
0.46	450	450	445	440	440	395	445
0.48	470	470	465	460	455	410	465
0.50	490	485	480	475	470	430	480
0.52	510	505	500	495	490	445	515
0.54	525	520	515	510	505	460	515
0.56	545	540	535	530	515	480	535
0.58	565	560	555	550	520	495	555
0.60	585	580	575	570	530	510	575
0.62	600	595	590	585	535	525	595
0.64	620	615	610	595	540	540	610
0.66	640	635	630	600	540	560	630
0.68	660	655	650	605	545	575	650
0.70	675	670	665	610	550	590	665
0.72	695	690	680	620	555	605	670
0.74	715	710	685	625	560	620	700
0.76	730	725	690	630	565	635	720
0.78	750	745	695	635	570	655	735
0.80	770	760	700	635	575	670	755
0.82	790	780	710	640	580	685	770
0.84	805	795	715	650	585	700	790
0.86	820	805	720	655	590	715	805
0.88	840	810	725	660	595	730	825
0.90	860	815	730	660	600	750	840
0.92	875	820	735	665	600	765	860

See note on following page.

Percentage of tensile reinforcing.	Mixture of concrete. Stone.					Stress in steel.	
	1:1.2.	1:1½:3.	1:2:4.	1:2½:5.	1:3:7.	16000.	18000.
0.94	895	825	740	670	605	780	875
0.96	920	835	745	675	610	795	895
0.98	930	840	750	680	615	810	910
1.00	950	845	755	685	620	825	930
1.1	980	870	780	700	635	905	1015
1.2	1010	895	800	720	650	980	1105
1.3	1030	920	815	740	660	1055	1190
1.4	1055	940	835	750	680	1135	1275
1.5	1080	960	850	760	690	1205	1360
1.6	1100	980	865	780	695	1285	1445
1.7	1120	995	880	790	710	1355	1530
1.8	1140	1010	895	800	720	1435	1610
1.9	1160	1025	905	810	725	1505	1695
2.0	1175	1040	920	830	740	1580	1780
2.5	1250	1090	965	865	775	1945	2190
3.0	1310	1150	1010	895	800	2305	2590
3.5	1360	1190	1040	925	820	2660	2990
4.0	1405	1220	1070	950	840	3010	3385
4.5	1440	1250	1090	965	860	3355	3770
5.0	1470	1280	1110	980	870	3700	4165

TABLE II.

Ultimate Extreme Fiber Stresses for Concrete Beams Reinforced with High Carbon Steel—Straight Line Theory.

By L. J. MENSCH, Mem. Am. Soc. C. E.

Ultimate Compressive Strength Obtained from Cylinder Tests.

% tensile steel.	2900		2400		2000		1750		1500		700	
	1:1.2	1:1½:3	1:2:4	1:2½:5	1:3:7							
0.25	1040	1030	1020	1010	1010	960						
0.30	1240	1230	1220	1200	1190	1080						
0.35	1430	1420	1400	1380	1370	1200						
0.40	1630	1610	1580	1560	1550	1330						
0.45	1820	1800	1760	1740	1710	1440						
0.50	2010	1970	1940	1900	1870	1540						
0.55	2190	2150	2110	2060	2030	1620						
0.60	2370	2330	2280	2230	2170	1700						
0.65	2540	2500	2440	2370	2310	1800						
0.70	2720	2650	2600	2520	2450	1800						
0.75	2900	2820	2740	2660	2590	1800						
0.80	3070	2990	2900	2800	2720	1800						
0.85	3240	3150	3040	2930	2830	1800						
0.90	3400	3300	3180	3060	2950	1800						
0.95	3560	3440	3320	3200	3050	1800						
1.00	3700	3570	3450	3310	3160	1800						
1.10	4020	3860	3700	3520	3350	1800						
1.20	4300	4120	3930	3730	3510	1800						
1.30	4600	4380	4140	4000	3600	1800						
1.40	4860	4610	4330	4000	3600	1800						
1.50	5120	4820	4520	4000	3600	1800						
1.60	5370	5050	4600	4000	3600	1800						
1.70	5600	5250	4600	4000	3600	1800						
1.80	5820	5450	4600	4000	3600	1800						
1.90	6040	5600	4600	4000	3600	1800						
2.00	6260	5750	4600	4000	3600	1800						
2.25	6700	5800	4600	4000	3600	1800						

TABLE III.

Copyright 1916 by Benj. E. Winslow.

Safe Extreme Fiber Stresses in Pounds per Square Inch for Double Reinforced Concrete Beams for Various Percentages of Top and Bottom Steel. Straight Line Theory.

BY BENJ. E. WINSLOW, Mem. A. I. A. and Mem. Am. Soc. C. E.

Maximum Compression on Extreme Fiber of Concrete=700 Lbs. per Sq. In. Maximum Tension in Steel Reinforcement=18000 Lbs. per Sq. In. Mixture of Concrete 1:2:4. Ratio of Modulus of Elasticity of Steel to That of Concrete=15. Ratio of Depth of Top Steel to Depth of Bottom Steel Below Top of Beam=0.10. Values for Other Steel and Concrete Stresses Are Directly Proportionate to Those Given in This Table.

		Percentage of Compressive Steel														
		0.00	0.10	0.25	0.50	0.75	1.00	1.25	1.50	1.75	2.00	2.25	2.50	2.75	3.00	
Percentage of Tensile Steel	0.60	575	578	579	580	581	582	583	584	584	585	586	587	588	589	0.60
	0.62	595	596	597	599	600	601	602	603	604	605	606	607	608	609	0.62
	0.64	610	612	613	615	616	618	619	621	622	624	625	627	628	629	0.64
	0.66	630	632	633	635	636	638	639	641	642	644	645	647	648	649	0.66
	0.68	650	652	653	655	656	658	659	661	662	663	665	666	667	668	0.68
	0.70	665	667	668	670	671	673	674	676	677	678	680	682	684	686	0.70
	0.72	680	688	689	691	693	694	696	697	699	700	702	703	705	706	0.72
	0.74	685	704	706	707	709	710	712	713	715	716	718	719	721	723	0.74
	0.76	690	720	726	728	729	731	732	734	735	737	738	740	741	743	0.76
	0.78	695	726	744	746	747	749	750	752	753	755	757	759	761	763	0.78
	0.80	700	731	762	764	766	768	770	772	774	776	778	780	781	783	0.80
	0.82	710	739	779	782	784	786	788	790	792	794	796	798	800	802	0.82
	0.84	715	743	790	800	802	804	806	808	810	812	814	816	818	821	0.84
	0.86	720	750	795	820	822	824	826	828	830	832	834	836	838	840	0.86
	0.88	725	755	800	839	842	844	846	848	850	852	854	856	858	860	0.88
	0.90	730	760	807	858	861	863	866	868	870	872	874	876	878	880	0.90
	0.92	735	765	812	873	880	883	885	887	890	892	894	896	898	900	0.92
	0.94	740	770	818	888	900	902	904	906	908	910	912	914	916	918	0.94
	0.96	745	775	823	892	920	922	924	926	928	930	932	934	935	937	0.96
	0.98	750	780	828	900	938	940	942	944	946	948	950	952	954	956	0.98
1.00	755	786	832	905	956	958	960	962	964	967	969	972	974	976	1.00	
1.10	780	811	853	930	1010	1060	1061	1063	1065	1066	1068	1069	1071	1072	1.10	
1.20	800	828	874	954	1031	1105	1155	1157	1159	1161	1163	1165	1167	1170	1.20	
1.30	815	850	895	978	1058	1130	1210	1252	1254	1256	1258	1260	1262	1265	1.30	
1.40	835	869	916	1006	1076	1156	1232	1310	1345	1348	1351	1354	1358	1362	1.40	
1.50	850	882	935	1020	1100	1178	1255	1331	1410	1450	1452	1455	1457	1460	1.50	
1.60	865	899	950	1034	1115	1196	1276	1352	1435	1511	1547	1550	1553	1555	1.60	
1.70	880	913	967	1054	1130	1215	1296	1374	1455	1538	1630	1650	1652	1655	1.70	
1.80	895	928	983	1064	1149	1232	1316	1394	1480	1560	1645	1710	1747	1750	1.80	
1.90	905	940	995	1082	1162	1250	1332	1414	1500	1580	1665	1725	1830	1848	1.90	
2.00	920	952	1008	1100	1178	1266	1350	1432	1513	1600	1680	1760	1840	1918	2.00	
2.50	965	1004	1055	1152	1241	1331	1420	1510	1595	1686	1715	1855	1945	2026	2.50	
3.00	1010	1048	1105	1196	1291	1385	1480	1570	1660	1750	1840	1930	2020	2108	3.00	
3.50	1040	1080	1140	1234	1334	1427	1515	1615	1705	1806	1890	1990	2080	2174	3.50	
4.00	1070	1115	1170	1266	1366	1464	1560	1665	1755	1852	1940	2040	2130	2230	4.00	
4.50	1090	1145	1205	1295	1395	1500	1595	1700	1795	1888	1980	2080	2180	2278	4.50	
5.00	1110	1160	1235	1315	1415	1525	1620	1730	1825	1924	2020	2120	2220	2318	5.00	
																Percentage of Tensile Steel

For values above heavy line, tension in steel is equal to 18000 lbs. per square inch.

For values below heavy lines compression in concrete is equal to 700 lbs. per square inch.

Values for other steel and concrete stresses are directly proportional to those given in

Tables I and III.

Table I gives the Extreme Fiber Stress for rectangular reinforced concrete beams for various mixtures of concrete and stresses in the steel for percentages of steel varying from plain concrete beams, to beams reinforced with as high as 5% of steel; all in accordance with the Building Ordinance Requirements for the City of Chicago.

In Table II are given in the headings the ultimate compressive strength of concrete as assumed by the Chicago Building Ordinance for various concrete mixtures. According to the theory of Mr. L. J. Mensch as published in the Journal of the American Concrete Institute for December, 1914, these compressive strengths, if introduced in the straight line formula do not agree with scientific tests on reinforced concrete beams to rupture. In order to make the straight line theory agree with the tests at rupture the ultimate extreme fiber stresses as given in Table II must be assumed instead of the values given in the headings.

The value 700 in the heading is for 1:2:4 cinder-concrete. It is also valid for stone concrete a few days old. The depth of the reinforced-concrete beams is of course assumed to be the depth to the center of the steel. Tables I, II and III assume only pure tension or compression failures. Special calculations should therefore be made for bond, shear and diagonal tension.

Table III gives the Extreme Fiber Stress for rectangular Double Reinforced concrete beams, for various percentages of tensile and compressive steel; all in accordance with the Building Ordinance Requirements for the City of Chicago. See Sec. 546-567.

RECOMMENDATIONS FOR THE DESIGN OF HOPPED COLUMNS.

Concrete 1:2:4.
 Rods round— $\frac{1}{2}$ "^o to $1\frac{1}{4}$ "^o.
 Core diameter 4" less than column diameter.
 As few different sizes of columns as possible.
 Column diameter never less than 1/12th the story height.
 Percentage of vertical steel from 1% to 7%.
 Percentage of hooping steel from 0.5% to 1.5%.
 Maximum pitch of spiral 1/10th of core diameter, or 3".
 Minimum pitch of spiral $1\frac{1}{2}$ ".
 Maximum size of spiral steel $\frac{1}{2}$ "^o.
 Minimum size of spiral steel $3/16$ "^o.
 Maximum spacing of vertical steel 9" or $\frac{1}{4}$ circumference of column.
 Minimum spacing of vertical steel $3\frac{1}{2}$ ".
 Minimum lap of vertical steel 18".
 Lap of vertical steel for average core stresses less than 1000#—"—25 diameters.

Lap of vertical steel for average core stresses greater than 1000#—"—30 diameters.
 Length of plain round stub bars in footings, 60 diameters.
 Length of square twisted stub bars in footings, 40 diameters.
 Stub bars embedded one-half their length in footing and one-half in column.
 Length of spirals to be clear story height with one extra turn at top and bottom.
 3 vertical lines of spacers for all spirals under 18" diameter.
 4 vertical lines of spacers for all spirals over 18" diameter.
 When columns require a large percentage of vertical steel it is often more economical to use a structural steel column and encase it in concrete. It must be remembered that the working stress of reinforcing steel is only (nxfc) while that of a structural column encased in concrete is $18000-70\frac{1}{r}$.

Metric Tables.

	Approximate Equivalent.		Accurate Equivalent.
1 inch	[length].. $2\frac{1}{2}$	cubic centimeters	2.539
1 centimeter	0.4	inch	0.393
1 yard	1	meter	0.914
1 meter (39.37 inches)	1	yard	1.093
1 foot	30	centimeters	30.479
1 kilometer (1,000 meters).....	$\frac{5}{8}$	mile	0.621
1 mile	$1\frac{1}{2}$	kilometers	1.600
1 gramme	[weight].. $15\frac{1}{2}$	grains	15.432
1 grain	0.064	gramme	0.064
1 kilogramme (1,000 grammes)	2.2	pounds avoirdupois	2.204
1 pound avoirdupois	$\frac{1}{2}$	kilogramme	0.453
1 ounce avoirdupois (437½ grains).....	28.1/3	grammes	28.349
1 ounce troy, or apothecary (480 grains).....	31	grammes	31.103
1 cubic centimeter	[bulk].. 1.06	cubic inch	1.060
1 cubic inch	16.1/3	cubic centimeters	16.386
1 liter (1,000 cubic centimeters).....	1	U. S. standard quart.....	0.946
1 United States quart.....	1	liter	1.057
1 fluid ounce	29.1/2	cubic centimeters	29.570
1 hectare (10,000 square meters)....[surface]..	$2\frac{1}{2}$	acres	2.471
1 acre	0.4	hectare	0.40

In the nickel five-cent piece of our coinage is a key to the tables of linear measures and weights. The diameter of this coin is two centimeters, and its weight is five grammes. Five of them placed in a row will give the length of the decimeter, and two of them will weigh a decagram. As the kiloliter is a cubic meter, the key to the measure of length is also the key to the measure of capacity.

Handy Table.

Diameter of a circle $\times 3.1416$ = circumference.	Circumference of a sphere \times its diameter = surface.
Radius of a circle $\times 6.283185$ = circumference.	Square of the diameter of a sphere $\times 3.1416$ = surface.
Square of the diameter of a circle $\times 0.7854$ = area.	Square of the circumference of a sphere $\times 0.3183$ = surface.
Square of the circumference of a circle $\times 0.07958$ = area.	Cube of the diameter of a sphere $\times 0.5236$ = solidity.
Half the circumference of a circle \times half its diameter = area.	Cube of the radius of a sphere $\times 4.1888$ = solidity.
Circumference of a circle $\times 0.159155$ = radius.	Cube of the circumference of a sphere $\times 0.016887$ = solidity.
Square root of the area of a circle $\times 0.56419$ = radius.	Square root of the surface of a sphere $\times 0.56419$ = diameter.
Circumference of a circle $\times 0.31831$ = diameter.	Square root of the surface of a sphere $\times 1.772454$ = circumference.
Square root of the area of a circle $\times 1.12838$ = diameter.	Cube root of the solidity of a sphere $\times 1.2407$ = diameter.
Diameter of a circle $\times 0.86$ = side of inscribed equilateral triangle.	Cube root of the solidity of a sphere $\times 3.8978$ = circumference.
Diameter of a circle $\times 0.7071$ = side of an inscribed square.	Radius of a sphere $\times 1.1547$ = side of inscribed cube.
Circumference of a circle $\times 0.225$ = side of an inscribed square.	Square root of ($\frac{1}{2}$ of the square of) the diameter of a sphere = side of inscribed cube.
Circumference of a circle $\times 0.282$ = side of an equal square.	Area of its base $\times \frac{1}{3}$ of its altitude = solidity of a cone or pyramid, whether round, square, or triangular.
Diameter of a circle $\times 0.8662$ = side of an equal square.	Area of one of its sides $\times 6$ = surface of a cube.
Base of a triangle $\times \frac{1}{2}$ the altitude = area.	Altitude of trapezoid $\times \frac{1}{2}$ the sum of its parallel sides = area.
Multiplying both diameters and .7854 together = area of an ellipse.	
Surface of a sphere $\times 1/6$ of its diameter = solidity.	

Square root of ($\frac{1}{6}$ of the square of) the diameter of a sphere = side of inscribed cube.
 Area of its base $\times \frac{1}{3}$ of its altitude = solidity of a cone or pyramid, whether round, square, or triangular.

Area of one of its sides $\times 6$ = surface of a cube.

Altitude of trapezoid $\times \frac{1}{2}$ the sum of its parallel sides = area.

TABLE OF SQUARE ROOTS.

No.	Sq. Root.	No.	Sq. Root.	No.	Sq. Root.	No.	Sq. Root.
25	5.	650	25.46	1400	37.42	2600	50.99
50	7.071	700	26.46	1450	38.08	2700	51.96
75	8.66	750	27.39	1500	38.73	2800	52.91
100	10.00	800	28.28	1550	39.37	2900	53.85
125	11.18	850	29.15	1600	40.00	3000	54.77
150	12.25	900	30.00	1650	40.62	3200	56.57
175	13.23	950	30.82	1700	41.23	3400	58.30
200	14.14	1000	31.62	1800	42.43	3600	60.00
250	15.81	1050	32.40	1900	43.59	3800	61.64
300	17.32	1100	33.16	2000	44.72	4000	63.24
350	18.70	1150	33.91	2100	45.82	4200	64.80
400	20.00	1200	34.64	2200	46.90	4400	66.32
450	21.21	1250	35.36	2300	47.95	4600	67.82
500	22.36	1300	36.06	2400	48.99	4800	69.28
550	23.45	1350	36.74	2500	50.00	5000	70.72
600	24.49						

Dimensions of a Barrel.—Diameter of head, 17 inches; bung, 19 inches; length, 28 inches; volume, 7,680 cubic inches.

Expansion of Water (Dalton).

Temperature.	Expansion.	Temperature.	Expansion.	Temperature.	Expansion.
22°	1.0009	72°	1.0018	152°	1.01934
32	1	92	1.00477	172	1.02575
*46	1	112	1.0088	192	1.03265
52	1.00021	132	1.01367	212	1.0466

*Greatest density at 39.1° Fahr.

A box 24 inches long by 16 inches wide and 28 inches deep will contain a barrel, or three bushels; 24 by 16 inches and 14 inches deep contains half a barrel; 16 inches square and 8 $\frac{1}{2}$ inches deep will contain one bushel; 16 by 8 $\frac{1}{2}$ inches and 8 inches deep will contain half a bushel; 8 by 8 $\frac{1}{2}$ inches and 8 inches deep will contain one peck; 8 inches square and 4 $\frac{1}{2}$ inches deep will contain one gallon; 7 by 4 inches and 4 $\frac{1}{2}$ inches deep will contain half a gallon; 4 inches square and 4 $\frac{1}{2}$ inches deep will contain one quart; 4 feet long, 3 feet 5 inches wide and 2 feet 8 inches deep will contain one ton of coal, or 36 cubic feet.

Table Showing the Pressure of Water at Different Elevations.

Feet Head	Equals Pressure per Square Inch.	Feet Head	Equals Pressure per Square Inch.	Feet Head	Equals Pressure per Square Inch.	Feet Head	Equals Pressure per Square Inch.	Feet Head	Equals Pressure per Square Inch.	Feet Head	Equals Pressure per Square Inch.
1	43	65	28.15	130	56.31	195	84.47	260	112.62	350	151.61
5	2.16	70	30.32	135	58.48	200	86.63	265	114.79	360	155.94
10	4.33	75	32.48	140	60.64	205	88.80	270	116.96	370	160.27
15	6.49	80	34.65	145	62.81	210	90.96	275	119.12	380	164.61
20	8.66	85	36.82	150	64.97	215	93.14	280	121.29	390	168.94
25	10.82	90	38.98	155	67.14	220	95.30	285	123.45	400	173.27
30	12.99	95	41.15	160	69.31	225	97.49	290	125.62	500	216.58
35	15.16	100	43.31	165	71.47	230	99.63	295	127.78	600	259.90
40	17.32	105	45.48	170	73.64	235	101.79	300	129.95	700	303.22
45	19.49	110	47.64	175	75.80	240	103.96	310	134.28	800	346.54
50	21.65	115	49.81	180	77.97	245	106.13	320	138.62	900	389.86
55	23.82	120	51.98	185	80.14	250	108.29	330	142.95	1,000	433.18
60	25.99	125	54.15	190	82.30	255	110.46	340	147.28		

Weights of Materials. **Dry Woods.**

	Lbs. Board ft.	Lbs. Cubic ft.		Lbs. Board ft.	Lbs. Cubic ft.
Apple	4.1	49.	Iron Wood	6.	71.
Ash, American white	3.9	47.	Larch	3.	35.
Birch	3.9	45.	Lignum Vitæ	6.9	83.
Beech	3.7	43.	Mahogany, Honduras	2.9	35.
Boxwood	5.	60.	Mahogany, Spanish	4.4	53.
Cedar, American	2.9	35.	Maple	4.1	49.
Cedar, W. Indian	3.9	47.	Maple, soft	3.5	42.
Cedar, Lebanon	2.5	30.	Oak, live	4.9	59.3
Cherry	3.5	42.	Oak, red	3.9	45.
Chestnut	3.4	41.	Oak, white	4.3	52.
Cork	1.3	15.	Pine, Southern	3.7	45.
Elm	2.9	35.	Pine, white	2.1	25.
Ebony	6.3	76.1	Pine, yellow	2.8	34.3
Hemlock	2.1	25.	Spruce	2.1	25.
Hickory	4.4	53.	Sycamore	3.1	37.
Hornbeam	2.9	47.	Walnut	3.2	38.

Building Materials—Stacked.

	Lbs. per cubic ft.		Lbs. per cubic ft.
Brick—pressed	150	Glass—window	157
" common	125	Granite	170
" soft	100	Lime—quick	53
Cement—Portland	100	Plaster of Paris	70
Cement—Rosedale	56	Sand	90-106
Cinders—dry	72	Sandstone	151
Cinders—packed	90	Shale	162
Earth—dry, shaken	82- 92	Slate	175
Earth—rammed	92-100	Trap rock	187

Masonry.

	Lbs. per cubic ft.		Lbs. per cubic ft.
Brick—pressed or paving	140	Granite	160
Brick—hard, common	120	Mortar and plaster	120
Brick—soft	100	Rubble—limestone, common	140
Brick—hollow	90	Rubble—limestone, cut face	150
Concrete—stone	150	Rubble—sandstone, common	140
Concrete—cinder	96	Rubble—sandstone, cut face	150

Building Materials—In Construction.

Roofing.

	Lbs. per square ft.		Lbs. per square ft.
Copper sheet	0.75 to 1.25	Shingles—wood 16"	2
Felt and gravel8 to 10	Singles—wood 16"	2
Iron—corrugated1 to 3.75	Slate—average	10
Iron—galvanized1 to 3	Tile—fancy, laid in mortar	25 to 30
Iron—sheet, black, painted	1.5	Tile—plain, average	12
Ready composition roofing1 to 1.5	Tin and paint	1
Sheet lead4 to 8	Zinc	1 to 2

Floors.

	Lbs. per sq. ft.		Lbs. per sq. ft.
Flat arches (tile) 3" thick	17	Flat arches (tile) 12" thick	39
" " " 4" "	18	" " " 14" "	43
" " " 6" "	25	" " " 16" "	49
" " " 8" "	31	Book tile 2" thick	15
" " " 10" "	35	" " 3" "	17
Brick arches 4" thick and concrete	70	Beam tile	15

Table for Weights of Yellow Pine Joists, Studs and Rafters on the Assumption That One Board Foot of Y. P. Weighs 2.8 Pounds.

Spacing	Size	Weight per Sq. Foot	Size	Weight Per Sq. Foot	Size	Weight
12"	2"x4"	1.87	2"x6"	2.8	2"x8"	3.74
14"	"	1.60	"	2.4	"	3.20
16"	"	1.40	"	2.1	"	2.80
18"	"	1.25	"	1.87	"	2.50
20"	"	1.12	"	1.68	"	2.24
22"	"	1.02	"	1.52	"	2.04
12"	2"x10"	4.68	2"x12"	5.61	2"x14"	6.55
14"	"	4.00	"	4.80	"	5.60
16"	"	3.50	"	4.20	"	4.90
18"	"	3.13	"	3.75	"	4.38
20"	"	2.80	"	3.36	"	3.92
22"	"	2.55	"	3.06	"	3.57

Partitions.

	Lbs. per sq. ft.		Lbs. per sq. ft.
Gypsum partition blocks 3" thick....	10	Partition tile 3" thick.....	17
" " " 4" "	12	" " " 4" "	18
" " " 5" "	14	" " " 6" "	25
" " " 6" "	16	" " " 8" "	31
Plaster on brick, tile or concrete....	5	" " " 10" "	35

Ceiling.

	Lbs. per sq. ft.
Lath and plaster 2 coats.....	9
Lath and plaster 3 coats.....	10
Suspended ceiling	10

Sheathing, Flooring, etc.

	Lbs. per sq. ft.
Pine, Hemlock, Spruce, Poplar, Redwood, per inch thick.....	3
Chestnut, Maple	4

Weight per Square Foot of Sheet Lead.

1/62 inch thick.....	2 lbs.	1/10 inch thick.....	7 lbs.
3/64 " "	2 1/2 "	1/8 " "	8 "
1/25 " "	3 "	5/32 " "	10 "
1/16 " "	4 "	3/16 " "	12 "
1/14 " "	5 "	7/32 " "	14 "
1/12 " "	6 "	1/2 " "	16 "

Miscellaneous Items.

	Lbs. per sq. ft.		Lbs. per sq. ft.
While the following items vary considerably in weight, the values given below are fair averages and may be used for preliminary computations.		Wood stair construction	20
Iron stair construction	50	Sidewalk lights in concrete.....	30
Concrete stair construction	150	Reinforcement of concrete	6
		Steel joists per sq. ft. of floor....	6
		Steel girders per sq. ft. of floor....	4

Contents of Storage Warehouses.

Material.	Weight per Cu. ft.	Allowable Height of Pile in ft.	Weight per Cu. ft.	Allowable Height of Pile in ft.
Groceries Etc.				
Beans—in bags	40	8	Wool—worsted, in cases..	27 8
Canned goods—cases	58	6	Hardware, Etc.	
Coffee—roasted, in bags... 33	8		Sheet tin—in boxes.....	278 2
Coffee—green, in bags..... 39	8		Wire—insulated copper, in coils	63 5
Flour—in barrels	40	5	Wire—galvanized iron, in coils	74 4.5
Molasses—in barrels..... 48	5		Wire—magnet, on spools..	75 6
Rice—in bags	58	6	Drugs, Paints, Oils, Etc.	
Salt Soda—in barrels..... 46	5		Glycerine—in cases.....	52 6
Salt—in bags	70	5	Linseed oil—in bbls.....	36 6
Soap powder—in cases..... 38	8		Logwood extract—in boxes	70 5
Starch—in barrels	25	6	Rosin—in bbls.....	48 6
Sugar—in barrels	43	5	Shellac—gum	38 6
Sugar—in cases	51	6	Soda — Caustic, in iron drums	88 3.33
Tea—in chests	25	8	Soda—Silicate, in bbls....	53 6
Wines and Liquors, in bbls. 38	6		Sulphuric Acid	60 1.66
Dry Goods, Cotton, Wool, Etc.			White Lead Paste—in cans	174 3.5
Burlap—in bales	43	6	White Lead—dry	86 4.75
Coir Yarn, in bales..... 33	8		Red Lead and Litharge	
Cotton — in bales, compressed	18	8	Putty—dry	132 3.75
Cotton Bleached Goods — in cases	28	8	Miscellaneous.	
Cotton Flannel—in cases... 12	8		Glass and Chinaware — in cases	40 8
Cotton Sheeting—in cases. 23	8		Hides and Leather — in bales	20 8
Cotton Yarn—in cases.... 25	8		Paper — newspaper and strawboard	35 6
Excelsior—compressed ... 19	8		Paper—writing and calendared	60 6
Hemp—Manila, compressed	30	8	Rope—in coils	32 6
Linen Goods—in cases..... 30	8			
Wool—in bales, not compressed	13	8		

NOMENCLATURE OF DRAWINGS

We present in the following pages a collation of symbols for plan nomenclature, which we hope will be the means of bringing about a more uniform practice. In addition to the convenience, which will result from uniform practice to those compelled to examine, estimate from or execute plans from different offices; it will be found that the proficiency of draftsmen will not be so seriously affected on changing from office to office if practice becomes uniform.

General symbols presented have been collated from various sources. To assist memory those symbols have been selected which are suggestive in their make up.

GENERAL SYMBOLS

	In color system	use
	Earth	Black
	Cinders	Green
	Concrete	Brown
	Stone	Blue
	Brick	Red
	Structural tile	Brown
	Composition wall blocks	Blue
	Architectural terra cotta	Brown
	Plaster	Blue
	Structural iron	Green
	Sheet metal	Green
	Floor tile, tile and mosaics	Brown
	Marble (in elevation)	Blue
	Marble (in section)	Blue
	Terrazo	Black
	Wood in section (soft wood)	Yellow
	Wood in section (hard wood)	Brown
	Wood in section (soft wood)	Yellow
	Wood in section (hard wood)	Brown
	Cork	Brown
	Glass	Blue
	Robble	Dressed ashlar
	Robblestone	Rock faced ashlar
	Dimensioned stone	Any stone dressed
	Ashlar stone	No. described, small numeral refers to details and specifications.

For illustration all lines indicating water pipes have a periodic double indentation suggestive of a "w"; gas lines a periodic embryo "G", etc.

Lighting symbols are those adopted by the American Institute of Architects and the National Electrical Contractors' Association, except that 50 watts is taken as the standard for one light unit instead of 16 c. p.

Structural iron standard symbols; the Osborn systems are so generally understood and used that it hardly seems necessary to publish same. (See Cambria pocket book, 1906 edition, p. 309.)

	Column	Small numeral indicates No. of particular column
	Door	Small numeral indicates No. of particular door
	Window	Small numeral indicates No. of particular window
	Indicates designating No. of a room or space.	
	Elevation of point	Small numerals indicate elevation above zero point.

PIPING SYMBOLS

	In color system
	Cold water
	Hot water
	Hot water return
	Filtered or drinking water
	Gas piping
	Air piping
	Compressed air piping
	Vacuum cleaning

SEWERAGE AND DRAINAGE

	Iron sewer pipe	Green
	Sanitary iron sewer pipe	Green
	Tile sewer	Red
	Sanitary Tile Sewer	Red
	Drainage tile	Brown
	Soil pipe	Green
	Waste pipe	Green
	Down spout	Green
	Vent riser	Green
	Floor drain	Brown
	Bracket: Prefix with "F" if for fuel.	Blue
	Ceiling: Prefix with "F" if for fuel.	Blue
	Floor outlet: Prefix with "F" if for fuel.	Blue
	Combined gas and electric; lower figure indicates No. of gas tips; upper figure indicates No. of 50 watt electric lamps.	Blue

	Ceiling outlet; electric only. Num. in center indicates No. of standard 50 watt electric lamps		Main or feeder run under floor concealed
	Ceiling outlet; combination 4/2 indicates 200 watt electric light capacity and 2 gas burners		Main or feeder run concealed under floor above
	Bracket outlet; electric only. Numeral in center indicates No. 50 watt electric lamps		Main or feeder run exposed
	Bracket outlet; combination 4/2 indicates 200 watt electric light capacity and 2 gas burners		Branch circuit run concealed under floor
	Show as many symbols as there are switches, or in case of a very large group of switches indicate the number of switches by a Roman numeral, thus: S' XII means 12 single pole switches. Describe type of switch in specifications, that is flush or surface, push button or snap.		Branch circuit run concealed under floor above
			Branch circuit run exposed
	Wall or baseboard receptacle outlet: Numeral in center indicates No. of stand. 50 watt electric lamps		Pole line
	Floor outlet: Numeral in center indicates number of 50 watt electric lamps		Riser
	Outlet for outdoor standard or pedestal, electric only. Numeral indicates No. of 50 watt electric lamps		Telephone outlet; Private service
	Outlet for outdoor standard or pedestal: Combination 6/6 indicates 300 watt electric light capacity lamps, 6 gas burners		Telephone outlet; Public service
	Special outlet for lighting, heating or power current as described in specifications		Bell outlet
	Drop cord outlet		Buzzer outlet
	One light outlet for lamp receptacle		Push button outlet; Numeral indicates No. of pushes
	Arc lamp outlet		Annunciator; Numeral indicates No. of points
	Ceiling fan outlet		Speaking tube
	S. P. Switch outlet.....		Watchman clock outlet
	D. P. Switch outlet.....		Watchman station outlet
	3-way switch outlet.....		Master time clock outlet
	Automatic door switch outlet.....		Secondary time clock outlet
	Electroliner switch outlet.....		Door opener
	Meter outlet		Special outlet; signal system as described in specifications
	Distribution panel		Battery outlet
	Junction or pull box		
	Motor outlet: Numeral in center indicates horse power		
	Motor control outlet		
	Transformer		
	Circuit for clock, telephone, bell or other service run under floor concealed. Kind of service wanted ascertained by symbol to which line connects		
	Circuit for clock, telephone, bell or other service run under floor above, concealed. Kind of service wanted ascertained by symbol to which line connects		

NOTE: If other than standard 50 watt electric lamps capacity is desired specifications should describe capacity of lamp desired

SUGGESTIONS IN CONNECTION WITH STANDARD SYMBOLS FOR WIRING PLANS

It is important that ample space be allowed for the installation of mains, feeders, branches and distribution panels.


It is desirable that a key to the symbols used accompany all plans.

If mains, feeders, branches and distribution panels are shown on the plans it is desirable that they be designated by letters or numbers.

Heights of center of wall outlets; (unless otherwise specified)


Living rooms.....	5'-6"
Chambers	5'-0"
Offices	6'-0"
Corridors	6'-3"

Heights of Switches (unless otherwise specified) 4'-0"



● S. F. 7 Steam feed vertical—No. designates particular pipe

● S. R. 5 Steam return vertical—No. designates particular pipe



17 Radiator, wall supported numeral for identification


12 Radiator, floor supported numeral for identification

Pipe coil radiator


6 Small numeral in inches gives size and arrow locates feed

3 Small numeral in inches gives size and arrow locates return


VENTILATING SYMBOLS




MECHANICAL EQUIPMENT




CENTRIFUGAL FAN




DISC FAN




PROPELLER FAN




DIFFUSER




ENLARGER




AIR DUCT EXHAUST DROP




AIR DUCT EXHAUST RISER




AIR DUCT SUPPLY DROP




AIR DUCT SUPPLY RISER



INLET REGISTER FROM DUCTS



OUTLET REGISTER TO DUCTS



MECHANICAL EQUIPMENT











TABLE OF TREADS AND RISES

No. of Treads.	6	6 ¹ / ₂	7	7 ¹ / ₂	7 ³ / ₈	7 ¹ / ₂	7 ³ / ₈	8	8 ¹ / ₂	9	9 ¹ / ₂	10	10 ¹ / ₂	11	13	14
Inch Rise.	6	6 ¹ / ₂	7	7 ¹ / ₂	7 ³ / ₈	7 ¹ / ₂	7 ³ / ₈	8	8 ¹ / ₂	9	9 ¹ / ₂	10	10 ¹ / ₂	11	13	14
In. ft.	6	6 ¹ / ₂	7	7 ¹ / ₂	7 ³ / ₈	7 ¹ / ₂	7 ³ / ₈	8	8 ¹ / ₂	9	9 ¹ / ₂	10	10 ¹ / ₂	11	13	14
1	6	6 ¹ / ₂	7	7 ¹ / ₂	7 ³ / ₈	7 ¹ / ₂	7 ³ / ₈	8	8 ¹ / ₂	9	9 ¹ / ₂	10	10 ¹ / ₂	11	13	14
2	1 0	1 0 ¹ / ₂	1 1	1 1 ¹ / ₂	1 1 ¹ / ₂	1 3	1 3 ¹ / ₂	1 3 ¹ / ₂	1 4 ¹ / ₂	1 5	1 5 ¹ / ₂	1 8	1 9	1 10	2 2	2 4
3	1 6	1 6 ¹ / ₂	1 9	1 9 ¹ / ₂	1 10 ¹ / ₂	1 10 ¹ / ₂	1 11 ¹ / ₂	2 0	2 0 ¹ / ₂	2 3	2 3 ¹ / ₂	2 6	2 7 ¹ / ₂	2 9	3 3	3 6
4	2 0	2 1	2 2	2 2 ¹ / ₂	2 2 ¹ / ₂	2 6	2 6 ¹ / ₂	2 7	2 7 ¹ / ₂	3 0	3 0 ¹ / ₂	3 4	3 4 ¹ / ₂	3 8	4 4	4 8
5	2 6	2 7 ¹ / ₂	2 11	2 9 ¹ / ₂	3 0 ¹ / ₂	3 1 ¹ / ₂	3 2 ¹ / ₂	3 3 ¹ / ₂	3 5 ¹ / ₂	3 9	3 11 ¹ / ₂	4 2	4 4 ¹ / ₂	4 7	5 5	5 10
6	3 0	3 1 ¹ / ₂	3 6	3 4 ¹ / ₂	3 9 ¹ / ₂	3 9	3 9 ¹ / ₂	4 0	4 1 ¹ / ₂	4 6	4 9	5 0	5 3	5 6	6 6	7 0
7	3 6	3 7 ¹ / ₂	4 1	4 1 ¹ / ₂	4 5 ¹ / ₂	4 4 ¹ / ₂	4 5 ¹ / ₂	4 8	4 9 ¹ / ₂	5 3	5 6 ¹ / ₂	5 10	6 1 ¹ / ₂	6 5	7 7	8 2
8	4 0	4 2	4 8	4 9	5 1	5 0	5 1	5 4	5 6	6 0	6 4	6 8	7 0	7 4	8 8	9 4
9	4 6	4 8 ¹ / ₂	5 3	5 4 ¹ / ₂	5 8 ¹ / ₂	5 7 ¹ / ₂	5 8 ¹ / ₂	6 0	6 2 ¹ / ₂	6 9	7 1 ¹ / ₂	7 6	7 10 ¹ / ₂	8 3	9 9	10 6
10	5 0	5 2 ¹ / ₂	5 10	5 11 ¹ / ₂	6 0 ¹ / ₂	6 3	6 4 ¹ / ₂	6 8	6 10 ¹ / ₂	7 1	7 11	8 4	8 9	9 2	10 10	11 8
11	5 6	5 8 ¹ / ₂	6 5	6 7 ¹ / ₂	6 11 ¹ / ₂	6 10 ¹ / ₂	7 1 ¹ / ₂	7 4	7 6 ¹ / ₂	8 3	8 8 ¹ / ₂	9 2	9 7 ¹ / ₂	10 1	11 11	12 10
12	6 0	6 3	7 0	7 1 ¹ / ₂	7 7 ¹ / ₂	7 6	7 7 ¹ / ₂	8 0	8 3	9 0	9 6	10 0	10 6	11 0	13 0	14 0
13	6 6	6 9 ¹ / ₂	7 7	7 8 ¹ / ₂	8 3 ¹ / ₂	8 1 ¹ / ₂	8 3 ¹ / ₂	8 8	8 11 ¹ / ₂	9 9	10 3 ¹ / ₂	10 10	11 4 ¹ / ₂	11 11	14 1	15 2
14	7 0	7 3 ¹ / ₂	8 2	8 3 ¹ / ₂	8 7 ¹ / ₂	8 9	8 10 ¹ / ₂	9 4	9 7 ¹ / ₂	10 6	11 1	11 8	12 3	12 10	15 2	16 4
15	7 6	7 9 ¹ / ₂	8 9	8 10 ¹ / ₂	9 0 ¹ / ₂	9 4 ¹ / ₂	9 6 ¹ / ₂	10 0	10 3 ¹ / ₂	11 3	11 10 ¹ / ₂	12 6	13 1 ¹ / ₂	13 9	16 3	17 6
16	8 0	8 4	9 4	9 6	9 8	10 0	10 2	10 4	10 6	11 4	12 0	13 4	14 0	14 8	17 4	18 8
17	8 6	8 10 ¹ / ₂	9 11	10 1 ¹ / ₂	10 3 ¹ / ₂	10 7 ¹ / ₂	10 9 ¹ / ₂	11 1 ¹ / ₂	11 4	11 8 ¹ / ₂	12 0 ¹ / ₂	14 2	14 10 ¹ / ₂	15 7	18 5	19 10
18	9 0	9 4 ¹ / ₂	10 6	10 8 ¹ / ₂	10 10 ¹ / ₂	11 3	11 5 ¹ / ₂	12 0	12 4 ¹ / ₂	12 9	13 6	15 0	15 9	16 6	19 6	21 0
19	9 6	9 10 ¹ / ₂	11 1	11 3 ¹ / ₂	11 6 ¹ / ₂	11 10 ¹ / ₂	12 0 ¹ / ₂	12 8	13 0 ¹ / ₂	14 3	15 0 ¹ / ₂	15 10	16 7 ¹ / ₂	17 5	20 7	22 2
20	10 0	10 5	11 8	11 10 ¹ / ₂	12 1	12 3 ¹ / ₂	12 6 ¹ / ₂	13 1 ¹ / ₂	13 4	15 0	15 10	16 8	17 6	18 4	21 8	23 4
21	10 6	10 11 ¹ / ₂	12 3	12 5 ¹ / ₂	12 8 ¹ / ₂	13 1 ¹ / ₂	13 4 ¹ / ₂	14 0	14 5 ¹ / ₂	15 9	16 7 ¹ / ₂	17 6	18 4 ¹ / ₂	19 3	22 9	24 6
22	11 0	11 5 ¹ / ₂	12 10	13 0 ¹ / ₂	13 3 ¹ / ₂	13 9	13 11 ¹ / ₂	14 8	15 1 ¹ / ₂	16 6	17 5	18 4	19 3	20 2	23 10	25 8
23	11 6	11 11 ¹ / ₂	13 5	13 7 ¹ / ₂	14 1 ¹ / ₂	14 4 ¹ / ₂	14 7 ¹ / ₂	15 4	15 9 ¹ / ₂	17 3	18 2 ¹ / ₂	19 2	20 1 ¹ / ₂	21 1	24 11	26 10
24	12 0	12 6	14 0	14 3	14 6	15 0	15 3	15 6	16 0	18 0	19 0	20 0	21 0	22 0	25 0	28 0
25	12 6	13 0 ¹ / ₂	14 7	14 10 ¹ / ₂	15 1 ¹ / ₂	15 7 ¹ / ₂	15 10 ¹ / ₂	16 8	17 2 ¹ / ₂	18 9	19 3 ¹ / ₂	20 10	21 10 ¹ / ₂	22 11	27 1	29 2
26	13 0	13 6 ¹ / ₂	15 2	15 5 ¹ / ₂	15 8 ¹ / ₂	16 3	16 6 ¹ / ₂	17 4	17 10 ¹ / ₂	18 5	19 6	20 7	21 8	22 9	28 2	30 4
27	13 6	14 0 ¹ / ₂	15 9	16 0 ¹ / ₂	16 3 ¹ / ₂	16 10 ¹ / ₂	17 1 ¹ / ₂	17 8 ¹ / ₂	18 6 ¹ / ₂	19 1 ¹ / ₂	20 3	21 4 ¹ / ₂	22 6	23 7 ¹ / ₂	29 3	31 6
28	14 0	14 7	16 4	16 7 ¹ / ₂	16 11	17 2 ¹ / ₂	17 6	18 4 ¹ / ₂	19 3	19 10	21 0	22 2	23 4	24 6	30 4	32 8
29	14 6	15 1 ¹ / ₂	16 11	17 2 ¹ / ₂	17 6 ¹ / ₂	18 1 ¹ / ₂	18 5 ¹ / ₂	18 8 ¹ / ₂	19 11 ¹ / ₂	20 6 ¹ / ₂	21 9	22 11 ¹ / ₂	24 2	25 4 ¹ / ₂	31 5	33 10
30	15 0	15 7 ¹ / ₂	16 10 ¹ / ₂	17 9 ¹ / ₂	18 1 ¹ / ₂	18 9	19 0 ¹ / ₂	20 0	20 7 ¹ / ₂	21 3	22 6	23 9	25 0	26 3	32 6	35 0

RULE FOR CALCULATING PROPORTIONED WIDTH AND HEIGHT OF STAIRS.

Subtract the width of tread from 25 in. and the result will be twice the height of the riser. Thus: if the tread is 10 in. wide, then $25 - 10 = 15 \div 2 = 7\frac{1}{2}$ in., the height or riser proportionate to a 10-inch tread. This is exclusive of nosings.



SPACE OCCUPIED BY AUTOMOBILES.

Touring Cars.

Length, 13 ft. 6 in. to 20 ft.

Height, 7 ft. 3 in.

Width, 6 ft. 0 in.

Smallest practical door, 8 ft. 0 in. high by 8 ft. 0 in. wide. Alley door should be not less than 11 ft. 4 in. and should be set not less than 22 ft. from opposite side.

Heavy Trucks.

Length, 15 ft. to 26 ft.

Width, 6 ft. 0 in.

Height, 10 ft. 0 in.

Width on floor between wheel pockets, 48 in. Length of wheel pocket, 34 in.

Smallest practical door, 9 ft. 0 in. wide by 11 ft. 0 in. high; for largest trucks, 13 ft. 6 in. high.

Doors to alley should not be less than 12 ft. wide and should be set not less than 28 ft. from opposite side of alley.

Moving Vans.

Length, 13 ft. to 16 ft. 6 in.

Width, 7 ft. to 8 ft. 2 in.

Height, 10 ft. to 12 ft.

Smallest practical door 10 ft. 0 in. wide by 13 ft. 6 in. high.

CLEARANCE UNDER OLD ELEVATED RAILWAY STRUCTURES AND TROLLEY WIRES, 12 FT. 0 IN.

Clearance required by the city for steam roads, 13 ft. 6 in.

Architects will be perfectly safe in making the maximum limit of door heights for any sort of vehicle 13 ft. 6 in., standard subway height, as no vehicle can be used commercially on the streets of Chicago that will not clear steam road viaducts. They might go around elevated viaducts, but they can not go around steam road viaducts and there is a probability that any future elevated viaducts would be raised to the city standard height of 13 ft. 6 in.

FURNITURE DIMENSIONS.

FILE 72894.

Chairs—Height of seat, 18"; depth of seat, 19"; top of back, 38"; arms, 9" above seat.

Lounge—6' long, 30" wide.

Tables—Writing, height, 2'-5"; sideboards, height, 3'-0"; general height, 2'-6".

Note—The smallest size practical for knee holes, 2' high by 1'-8" wide.

Beds—Single, width, 3' to 4'; $\frac{3}{4}$ bed, width, 4'; double bed, width, 4'-6" to 5'-0", length 6'-6" to 6'-8"; standard double bed, 4'-6" x 6'-6"; footboards, 2'-6" to 3'-6" high; headboards, 5' to 6'-6".

Bureaus—Common, width, 3'-5" or 4'; depth, 1'-6" or 1'-8"; height, 2'-6" or 3'.

Commodores—Top, 1'-6" square and 2'-6" high.

Chiffoniers—3' wide, 1'-8" deep, 4'-4" high.

Cheval Glasses—Height, 6'-4" or 5'-0" or 5'-2"; width, 3'-2" or 2'-6" or 1'-8".

Washstands—Length, 3'-0"; width, 1'-6"; height, 2'-7".

Wardrobes—Length, 4'-6"—3'-0"; depth, 2'-0"—1'-5"; height, 8'-0".

Sideboards—Length, 5' to 6'; depth, 2'-2".

Pianos—Upright, length, 4'-10" to 5'-6"; height, 4'-4" to 4'-9"; depth, 2'-4". Square, length, 6'-8"; depth, 3'-4".

Billiard Tables—4'-8", $4\frac{1}{2}$ " x 9, 5' x 10. Must have 16' x 20' space.

Wardrobe Shelves—5'-10" high.

Coat Hooks—5'-6" high.

Flour Barrel—28" to 30" high and 20" to 21" dia.

DATA ON BUILDINGS WITH SIDINGS.

Clearance from face of building to center of track, 7'-0".

Height of loading decks:

For shipping, 4'-0".

For receiving, 3'-0".

Clearance from center of track to edges of loading decks:

Upper edge, 7'-0".


Lower edge, 5'-0".

Spec. No.	No. of Stops.	From Back to Front Line of Case.	Width of Space Required.	Height Required for Swell-Box and Large Pipes.
5	10	7' 4"	11' 6"	12' 6"
7	11	8'	11' 6"	12' 6"
8	12	8'	12' 6"	12' 6"
10	13	8' 7"	12' 6"	12' 6"
11	14	9' 3"	12' 6"	12' 6"
13	16	10' 5"	12' 6"	12' 6"
14	17	11'	14' 8"	17'
16	18	11' 7"	14' 8"	17'
17	19	12' 2"	14' 8"	17'
19	20	12' 9"	14' 8"	17'

Spec. No.	No. of Stops.	From Back to Front Line of Case.	Width of Space Required.	Height Required for Swell-Box and Large Pipes.
20	21	12' 9"	15' 6"	17'
22	22	13' 4"	15' 6"	17'
23	23	13' 6"	15' 6"	17'
25	24	14'	15' 6"	17'
26	25	14' 6"	15' 6"	17'
28	26	14' 6"	15' 6"	17'
29	27	14' 6"	16' 4"	17' 6"
31	28	15'	16' 4"	17' 6"
32	29	15' 6"	16' 4"	17' 6"
34	30	15' 6"	17'	17' 6"

Add 40" more from Front Line of Case for Keydesk Pedals and Seat.

TABLE SHOWING THE LENGTH OF SIDES OF BAYS
ANGLE BEING 45, 30-60 AND 22½-67½ DEGREES.



Examples.

Angle of 45 Degrees.

1 ft.	6 in.	by	1 ft.	6 in.	2 ft.	1 7/8 in.	2 ft.	10 in.	by	2 ft.	10 in.	4 ft.	0 1/8 in.
1	7	"	1	7	"	2 7/8	2	11	"	2	11	4	1 1/8
1	8	"	1	8	"	4 1/4	3	0	"	3	0	4	2 1/8
1	9	"	1	9	"	5 1/2	3	1	"	3	1	4	3 1/8
1	10	"	1	10	"	7 1/4	3	2	"	3	2	4	4 1/8
1	11	"	1	11	"	8 1/2	3	3	"	3	3	4	5 1/8
2	0	"	2	0	"	9 1/8	3	4	"	3	4	4	6 1/8
2	1	"	2	1	"	11 3/8	3	5	"	3	5	4	7 1/8
2	2	"	2	2	"	0 3/4	3	6	"	3	6	4	8 1/8
2	3	"	2	3	"	2 1/8	3	7	"	3	7	5	9 1/8
2	4	"	2	4	"	3 3/8	3	8	"	3	8	5	10 1/8
2	5	"	2	5	"	4 1/8	3	9	"	3	9	5	11 1/8
2	6	"	2	6	"	5 1/8	3	10	"	3	10	5	12 1/8
2	7	"	2	7	"	6 1/8	3	11	"	3	11	5	13 1/8
2	8	"	2	8	"	7 1/8	4	0	"	4	0	5	14 1/8
2	9	"	2	9	"	8 1/8							


Angle of 30-60 Degrees.

1 ft.	6 in.	by	2 ft.	7 3/8 in.	3 ft.	0 in.	2 ft.	10 in.	by	4 ft.	10 3/8 in.	5 ft.	8 in.
1	7	"	2	7 3/8	3	2	2	11	"	4	10 3/8	5	10
1	8	"	2	8 3/8	3	4	3	0	"	5	2 3/8	6	2
1	9	"	2	9 3/8	3	6	3	1	"	5	4 1/8	6	4
1	10	"	2	10 3/8	3	8	3	2	"	5	6 1/8	6	6
1	11	"	2	11 3/8	3	10	3	3	"	5	8 1/8	6	8
2	0	"	2	0 3/8	3	12	3	4	"	5	10 1/8	6	10
2	1	"	2	1 3/8	3	14	3	5	"	5	12 1/8	6	12
2	2	"	2	2 3/8	3	16	3	6	"	5	14 1/8	6	14
2	3	"	2	3 3/8	3	18	3	7	"	5	16 1/8	6	16
2	4	"	2	4 3/8	3	20	3	8	"	5	18 1/8	6	18
2	5	"	2	5 3/8	3	22	3	9	"	5	20 1/8	6	20
2	6	"	2	6 3/8	3	24	3	10	"	5	22 1/8	6	22
2	7	"	2	7 3/8	3	26	3	11	"	5	24 1/8	6	24
2	8	"	2	8 3/8	3	28	4	0	"	5	26 1/8	6	26
2	9	"	2	9 3/8	3	30				5	28 1/8	6	28

Angle of 22½-67½ Degrees.

1 ft.	6 in.	by	3 ft.	7 7/8 in.	3 ft.	11 in.	2 ft.	10 in.	by	9 ft.	10 1/2 in.	7 ft.	4 1/2 in.
1	7	"	3	7 7/8	4	1 1/2	2	11	"	7	0 1/2	7	7 1/2
1	8	"	3	8 7/8	4	4 1/2	3	0	"	7	2 1/2	7	10 1/2
1	9	"	3	9 7/8	4	6 7/8	3	1	"	7	4 1/2	8	0 1/2
1	10	"	3	10 7/8	4	9 1/2	3	2	"	7	6 1/2	8	3 1/2
1	11	"	3	11 7/8	4	11 1/2	3	3	"	7	8 1/2	8	5 1/2
2	0	"	3	0 7/8	4	14 1/2	3	4	"	8	10 1/2	8	8 1/2
2	1	"	3	1 7/8	4	16 1/2	3	5	"	8	12 1/2	8	11 1/2
2	2	"	3	2 7/8	4	18 1/2	3	6	"	8	14 1/2	8	13 1/2
2	3	"	3	3 7/8	4	20 1/2	3	7	"	8	16 1/2	8	15 1/2
2	4	"	3	4 7/8	4	22 1/2	3	8	"	8	18 1/2	8	17 1/2
2	5	"	3	5 7/8	4	24 1/2	3	9	"	8	20 1/2	8	19 1/2
2	6	"	3	6 7/8	4	26 1/2	3	10	"	9	22 1/2	10	0 1/2
2	7	"	3	7 7/8	4	28 1/2	3	11	"	9	24 1/2	10	2 1/2
2	8	"	3	8 7/8	4	30 1/2	4	0	"	9	26 1/2	10	4 1/2
2	9	"	3	9 7/8	4	32 1/2				9	28 1/2	10	6 1/2

SIZES OF FREIGHT CARS AND LEGAL RAILWAY CLEARANCES



Car.	A	B	C	D	E	F	G	H	I	J
North-Western	59"	9'-0"	9'-4"	10'-4"	10'-10"	38"	34'-0"	60"	49"	7'-6"
Chicago & Alton	"	9'-3"	9'-0"	10'-6"	11'-0"	36"	40'-6"	72"	48"	7'-8"
New York Central	"	9'-3"	9'-2"	10'-2"	10'-10"	42"	36'-6"	72"	48"	8'-0"
Baltimore & Ohio	"	9'-4"	8'-10"	9'-10"	10'-6"	37"	36'-6"	72"	42"	7'-7"
Pacific Fruit Express ..	"	9'-3"	9'-0"	9'-10"	10'-3"	40"	33'-9"	48"	50"	6'-2"
North-Western Furniture ..	"	9'-6"	10'-6"	11'-6"	12'-0"	30"	50'-6"	144"	40"	9'-8"
Cotton Belt	"	9'-3"	9'-6"	10'-6"	11'-6"	38"	36'-6"	62"	48"	7'-8"
Chicago & Alton	"	9'-2"	8'-8"	9'-8"	10'-11"	37"	34'-8"	66"	47"	6'-8"
North-Western	"	9'-4"	9'-2"	10'-2"	11'-2"	39"	36'-6"	60"	49"	7'-6"
North-Western	"	9'-2"	8'-5"	9'-6"	10'-7"	36"	34'-6"	60"	46"	6'-10"
Erie	"	9'-6"	8'-8"	9'-8"	10'-10"	40"	34'-10"	62"	50"	6'-10"



FIG. 1



FIG. 2




FIG. 3



FIG. 4

Fig. 1. Buildings and Miscellaneous Structures adjacent to Main Tracks, L=21' 6", K=8' 0"; Adjacent to Subsidiary Passenger Tracks L=21' 6", K=7' 6"; Tracks entering buildings L=car clearance (see diagram above for estimate), K=7' 0".

Structures adjacent to Subsidiary Freight Tracks except as otherwise specified. Tracks outside buildings L=21' 6", K=8' 0"; Tracks entering buildings L=practical car clearance, K=7' 0".

Fig. 2. Bridges supporting Main Tracks or Subsidiary Freight Tracks clearance shall be

as follows: L=21' 3", M=4' 2", 0", P=4' 0", Q=5' 0". Bridges spanning Main Tracks or Subsidiary Freight Tracks Fig. 1. L=21' 6", K=8' 0".

Fig. 3. High Freight Platforms R=not to exceed 5' 8", S=not less than 5' 8" except when such platforms have S=not less than 8' 0".

Fig. 4. High Passenger Platforms on exclusive passenger tracks may have R=height of car floor above rail. Low passenger platforms R=0' 8", S= not less than 5' 0".

Size of Swimming Tank.

FILE 725.74

Swimming tanks that can be used for swimming contests must be exactly 20 yards in interior length, no less. (A tank 1/2 inch short would be ruled out of contest.) Eight yards wide is best, although 7 yards will pass; 4 feet deep at shallowest point and 8 feet deep at deepest point, which deepest point should be about 12 feet from end where springboard is placed. Depth at springboard

end should be six feet. Interior of tank, both sides and bottom, should be white, and there should be three black lines on the bottom extending parallel with sides, and dividing the tank into four equal alleys; there should be a line across tank on bottom and up sides at exactly 2 yards from each end, measured horizontally, making lines exactly 16 yards apart horizontally.

Size of the Billiard Room, Gas Light, Etc.

The space required for the different sized tables is as follows:
For table 6 x 12, Room should be 16 x 22
For table 5 1/2 x 11, Room should be 15 1/2 x 21
For table 5 x 10, Room should be 15 x 20
For table 4 1/2 x 9, Room should be 14 x 18 1/2
For table 4 x 8, Room should be 13 x 17
For table 3 1/2 x 7, Room should be 12 1/2 x 16
The following directions for arranging the lights over billiard tables will be found use-

ful. The distance of the light from the floor should be about 6 feet 2 inches. For a 5 1/2 by 11 table, cross-arms 31 inches and long arms 62 inches. For a 5 by 10 table, the cross-arms of the pendant should measure, from light to light, 23 inches and the long arm 56 inches. For a 4 1/2 by 9 table, cross-arms 25 inches and long arms 50 inches. For a 4 by 8 table, cross-arms 22 inches and long arms 44 inches.

MASONRY, PLASTERING AND FIREPROOFING.

Weight of Brickwork

Placing the weight of brickwork at 112 lb. per cubic foot, the weights per superficial foot for different walls are:

9 inch wall.....	84 lb.
13 inch wall.....	121 lb.
18 inch wall.....	168 lb.
22 inch wall.....	205 lb.
26 inch wall.....	243 lb.

Measurement of Old Brick

Uncleaned rough from building dumped from 8 to 10 bricks per cubic foot, or average of 111 cubic feet to the M.

Uncleaned stacked on outside and interior of stack filled promiscuously 10-12 per cubic foot, or average of 91 cubic feet to the M.

Cleaned and closely stacked, 16 to 18 bricks per cubic foot, or actual average of 59 cubic feet to M. (Usually sold at 60 cubic feet to M to allow for waste and poor piling.)

Cleaned stacked on outside and interior filled promiscuously, 12 to 14 per cubic foot, or actual average of 77 cubic feet to M. (When sold from pile measure customary to count 80 cubic feet to M, to allow for waste and bats.)

Measurement of New Brickwork.

The Chicago Masons and Builders' Association have arbitrarily assumed that a cubic foot of wall contains $22\frac{1}{2}$ common brick, or $7\frac{1}{2}$ brick to the superficial foot of 4-inch wall and 15 brick to the superficial foot of 8-inch wall. These figures of the Masons' and Builders' Association are frequently used for the appraisal of party walls, etc., but if so used, the price per M for work in wall should be reduced accordingly.

The actual number of Chicago common brick required for a cubic foot of solid wall varies from $17\frac{1}{2}$ to $19\frac{1}{2}$, and masons in purchasing brick usually reserve 18 brick per cubic foot of solid wall; and when so doing, rarely find an excess or shortage at the end of construction. When the walls are divided into many small piers, requiring much cutting, and consequently much waste, it is best to figure 20 brick to the cubic foot.

On account of the wide variance of practice on the part of masons in estimating, architects, when calling for estimates on brick work by the thousand, will avoid useless controversy by stipulating that quantity of brick will be determined by superficial wall measurement according to the following rule, which is very nearly correct, as Chicago brick now run. Divide the total number of superficial feet of wall surface of a given thickness by 160, and multiply the result by the number of brick widths the wall is thick, and the result will equal the number of thousands of brick contained. A four-inch wall will contain $6\frac{1}{4}$ brick to the superficial foot, or 1,000 brick to 160 square feet.

Miscellaneous Masonry Data.

One hundred yards of plastering will require fourteen hundred laths, four and a half bushels of lime, four-fifths of a load of sand, nine pounds of hair and five pounds of nails, for two-coat work.

A load of mortar measures a cubic yard, requires a cubic yard of sand and nine bushels of lime, and will fill thirty hods.

A bricklayer's hod measuring one foot four inches by nine inches, equals 1.296 cubic inches in capacity, and contains twenty bricks.

A single load of sand or other materials equals a cubic yard.

Cement Mortars.

FILE 603.2

S. W. Curtiss, an authority on mortars, states that the only way lime mortar will set is by chemical combination with carbonic acid gas. In common practice this always comes from the atmosphere. Anything excluding air from lime mortar will prevent its setting; for this reason it is detrimental to lay imporous brick in lime mortar as such brick do not conduct air through same to the mortar joint and the only air that can come in contact with the mortar must pass through the mortar itself.

Cement mortar sets by crystallization, which means that in order to set cement must be supplied with water. In consequence cement mortar sometimes fails to set, or harden when used for laying porous brick because of the fact that capillarity draws all of the moisture out of the mortar into the brick and it does not have sufficient water for crystallization. Porous brick if laid in cement mortar should be thoroughly soaked so as to fill the pores and destroy the tendency to absorb moisture from the mortar. Nearly all stone products if ground fine enough will crystallize when mixed with water forming a cement of greater or less strength according to the character of the material and the fineness of the grinding. Calcareous matters or Portland cement which will not pass a 100 mesh sieve are incapable of crystallization and therefore valueless as a cementing material. The introduction of sand or stone products in cement not ground so as to pass 100 mesh reduces the amount of cementing material to the volume and at the same time increases its efficiency. A one hundred volume of neat cement that has a tensile strength of 700 pounds to the square inch will, when used with a four hundred volume of properly assorted gravel give a tensile strength of three hundred fifty pounds to the square inch. As there are five square inches the cement holds five times 350 or 1,750. Thus increasing the efficiency of the cement two and one-half times, and at the same time the proper proportion of graded gravels eliminate shrinking or swelling of the mass. While neat cement is stronger per cubic inch than the concrete, it is necessary in practical use to combine it with proper quantity of proper aggregates to avoid craze cracking from shrinkage. The smaller proportion of water in Portland cement making it workable gives the greatest strength. Neat Portland will take 22% of water to make it workable. This is an excess of water needed in the crystallization. In compressing it is impossible to compress the water, causing a shrinkage when crystallization takes place. When Portland cement is used with four volumes of aggregates 8% of the five volumes of water will make a workable material. This can be compressed without the danger of shrinkage. The cement attacks the silica of the aggregates, crystallizing into one mass. The introduction of quick lime into cement mortar means weakening the strength of the mortar way out of proportion to the amount of lime introduced. The effect is much worse than the introduction of an increased amount of sand except that the lime has a slightly retardative effect on the setting of the cement.

Hydrated lime in small quantities is probably less injurious than slacked lime. Cement has a tendency to prevent the setting of lime, by excluding the atmosphere, while lime has a tendency to prevent the setting of cement by absorbing moisture required for crystallization of the cement.

OVERLAYING CONSTRUCTION SHEET, SHINGLE AND COMPOSITION COVERING.

FILE 685.1

The average width of a shingle is four inches. Hence, when shingles are laid four inches to the weather each shingle averages 16 square inches, and 900 are required for a square of roofing (100 square feet). If $4\frac{1}{2}$ inches to the weather, 800; 5 inches, 720; $5\frac{1}{2}$ inches, 655; 6 inches, 600.

Slating.

FILE 695.2

Slating is estimated by the "square," which is the quantity required to cover 100 square feet. The slates are usually laid so that the third laps the first three inches.

Number of Slates per Square.

Size in Inchs.	Pieces per Square.	Size in inches.	Pieces per Square.	Size in Inchs.	Pieces per Square.
6 × 12	533	8 × 16	277	12 × 20	141
7 × 12	457	9 × 16	246	14 × 20	121
8 × 12	400	10 × 16	221	11 × 20	137
9 × 12	355	9 × 18	213	12 × 22	126
7 × 14	374	10 × 18	192	14 × 22	108
8 × 14	327	12 × 18	160	12 × 24	114
9 × 14	291	10 × 20	169	14 × 24	98
10 × 14	261	11 × 20	151	16 × 24	86

The weight of slate per cubic foot is about 174 pounds, or per square foot of various thicknesses as follows:

Thickness in inches.....	$\frac{1}{8}$	$\frac{3}{16}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$
Weight in pounds.....	1.81	2.71	3.62	5.43	7.25

The weight per square foot of roof tiling, set in iron or between wood rafters ready for slating, is about 12 pounds.

Tin Roofs.

FILE 695.4

Tin roofs should be laid with cleats.

There are two kinds of tin—"bright tin," the coating of which is all tin, that is, the tin proper; and "tern," "leaded," or "roofing" tin, the coating of which is a composition, part tin and part lead. This last will not rust any quicker, but the sulphur in soft coal smoke eats through the "leaded" coating sooner than through the "tinned."

Sizes of tin, 10 by 14 and 14 by 20, and two grades of thickness—IC light, and IX, heavy. For a steep roof (one-sixth pitch or over) the IC 14 by 20 tin ("leaded" if high up where little smoke will get to it; "bright" if low down), put on with a standing groove, and with the cross seams put together with a double lock, makes as good a roof as can be made. For flat roofs IX 10 x 14 "light" is best, laid with cleats, but the others make good roofs and any of them will last twenty-five years at least, if painted periodically.

Number of Square Feet a Box of Roofing Tin Will Cover.—For flat seam roofing, using $\frac{1}{2}$ -inch locks, a box of "14 by 20" size will cover about 192 square feet, and for standing seam, using $\frac{3}{4}$ -inch locks and turning $1\frac{1}{4}$ and $1\frac{1}{2}$ inch edges, making 1-inch standing seams, it will lay about 168 square feet.

For flat seam roofing, using $\frac{1}{2}$ -inch locks, a box of "28 by 20" size will cover about 399 square feet, and for standing seam, using $\frac{3}{4}$ -inch locks and turning $1\frac{1}{4}$ and $1\frac{1}{2}$ inch edges, making 1-inch standing seams, it will lay about 365 square feet.

Every box of roofing plates (IC or IX "14 by 20" or "28 by 20" sizes) contains 112 sheets.

For roofs and gutters use seven-pound lead; for hips and ridges, six-pound; for flashings, four-pound.

Gutters should have a fall of at least one inch in ten feet.

No sheet lead should be laid in greater length than ten or twelve feet without a dip to allow for expansion.

Joints to lead pipes require a pound of solder for every inch in diameter.

SANITARY AND ELECTRIC POWER EQUIPMENT

INCLUDING PLUMBING, ILLUMINATION AND ELECTRIC POWER

Capacity of Cisterns.

FILE 698

For a circular cistern, square the diameter and multiply by .7854, for the area; multiply this by 1,728 and divide by 231, for number of gallons of one foot in depth; for a square cistern, multiply length by breadth, and proceed as above.

CIRCULAR CISTERN.

5 feet in diameter holds 4.66 bbls.
6 feet in diameter holds 6.71 bbls.
7 feet in diameter holds 9.13 bbls.
8 feet in diameter holds 11.93 bbls.
9 feet in diameter holds 15.10 bbls.
10 feet in diameter holds 18.65 bbls.

SQUARE CISTERN.

5 feet by 5 feet holds 5.92 bbls.
6 feet by 6 feet holds 8.54 bbls.
7 feet by 7 feet holds 11.63 bbls.
8 feet by 8 feet holds 15.19 bbls.
9 feet by 9 feet holds 19.39 bbls.
10 feet by 10 feet holds 23.74 bbls.

Wrought-iron Welded Pipe.

DIMENSIONS, WEIGHTS, ETC., OF STANDARD SIZES FOR STEAM, GAS, WATER, OIL, ETC.

Inside Diameter	Outside Diameter	External Circumference, A	Length of Pipe per Sq Foot of Outside Surface.	Internal Area	External Area.	Length of Pipe containing one Cubic Foot.	Weight per Foot of Length	No. of Threads per Inch of Screw.	Contents in *Gallons per Foot.	Weight of Water per Foot of Length.
In.	In.	In.	Ft.	In.	In	Ft	Lbs.			Lbs.
1/8	40	1 272	9.44	012	129	2,500	.24	27	.0006	.003
1/4	54	1 636	7.075	049	229	1,385.	.42	18	.0026	.021
3/8	67	2 121	5.657	110	358	751.5	.56	14	.0057	.047
1/2	84	2 652	4.502	196	554	472.4	.84	14	.0102	.085
3/4	1 05	3 299	3 637	441	866	270.	1.12	11 1/2	.0230	.190
1	1 31	4 134	2 903	785	1 357	166.9	1 67	11 1/2	.0408	.349
1 1/4	1 66	5 215	2 301	1 227	2 164	96.25	2.25	11 1/2	.0638	.527
1 1/2	1 9	5 969	2 01	1 767	2 835	70.65	2.69	11 1/2	.0918	.760
2	2 37	7 461	1 611	3 141	4 330	42.36	3.66	8	.1632	1.356
2 1/2	2 87	9 032	1 358	4 908	6 491	30.11	5.77	8	.2550	2.116
3	3 5	10 996	1 091	7 068	9 621	19.49	7.54	8	.3673	3 049
3 1/2	4	12 566	.955	9 621	12 566	14.56	9 05	8	.4998	4 155
4	4 5	14 137	.849	12 566	15 904	11.31	10.72	8	.6528	5 405
4 1/2	5	15 708	.765	15 904	19 635	9 03	12.49	8	.8263	6 851
5	5 56	17 475	.629	19 635	24 299	7 20	14.56	8	1.020	8 500
6	6 62	20 813	.577	28 274	34 471	4 98	18 76	8	1 469	12 312
7	7 62	23 954	.505	38 484	45 663	3 72	23 41	8	1 999	16 662
8	8 62	27 096	.444	50 265	58 426	2 88	28 34	8	2 611	21 750
9	9 68	30 433	.394	63 617	73 715	2 26	34 67	8	3 300	27 500
10	10 75	33 772	.355	78 540	90 792	1 80	40 64	8	4 081	34 000

* The Standard U S. gallon of 231 inches.

Divide the external circumference column, A, by 12 and the result will be the square feet of surface per lineal foot

Grade Per Mile.

The following table will show the grade per mile:

An inclination of

1 foot in 15 is 352 feet per mile.
1 foot in 20 is 264 feet per mile.
1 foot in 25 is 211 feet per mile.
1 foot in 30 is 176 feet per mile.
1 foot in 35 is 151 feet per mile.

1 foot in 40 is 132 feet per mile.
1 foot in 50 is 106 feet per mile.
1 foot in 100 is 53 feet per mile.
1 foot in 125 is 42 feet per mile.

To find quantity of water elevated in one minute running at 100 feet of piston speed per minute: Square the diameter of the water cylinder in inches and multiply by 4. Example: Capacity of a 5-inch cylinder is desired. The square of the diameter (5 inches) in 25, which, multiplied by 4, gives 100, the number of gallons per minute (approximately).

Quantity of Brickwork in Barrel Drains and Wells.

Diameter in Clear	Thickness of Brickwork	Superficial Feet of Brickwork in One Linear Yard.	Number of Bricks Required for One Linear Yard
1 foot, 0 inches	0 feet, 4½ inches	16 feet, 6 inches	115
1 " 6 "	0 " 4½ "	21 " 2 "	148
2 " 0 "	0 " 4½ "	25 " 10 "	181
2 " 0 "	0 " 9 "	33 " 0 "	462
2 " 6 "	0 " 9 "	37 " 8 "	528
2 " 6 "	1 " 1 "	43 " 2 "	906
3 " 0 "	0 " 9 "	42 " 6 "	594
3 " 0 "	1 " 1 "	47 " 10 "	1004
3 " 6 "	0 " 9 "	47 " 1 "	659
3 " 6 "	1 " 1 "	52 " 7 "	1104
4 " 0 "	0 " 9 "	51 " 10 "	725
4 " 0 "	1 " 1 "	57 " 3 "	1203
5 " 0 "	0 " 9 "	61 " 3 "	857
5 " 0 "	1 " 1 "	66 " 9 "	1402
6 " 0 "	1 " 1 "	76 " 1 "	1597
7 " 0 "	1 " 1 "	85 " 6 "	1795

Tests for Pure Water.

Color: Fill a clean long bottle of colorless glass with the water; look through it at some black object. It should look colorless and free from suspended matter. A muddy or turbid appearance indicates soluble organic matter or solid matter in suspension. **Odor:** Fill the bottle half full, cork it, and leave it in a warm place for a few hours. If when uncorked it has a smell the least repulsive, it should be rejected for domestic use. **Taste:** If water at any time, even after heating, has a disagreeable taste, it should be rejected.

A simple semi-chemical test is known as the "Heisch test." Fill a clean pint bottle three-fourths full of the water; add a half-teaspoonful of clean granulated or crushed loaf sugar; stop the bottle with glass or a clean cork and let it stand in a light and moderately warm room for forty-eight hours. If the water becomes cloudy, or milky, it is unfit for domestic use.

Capacity of Drain Pipe.

SIZE OF PIPE.	GALLONS PER MINUTE.							
	½-in. Fall per 100 ft.	3-in. Fall per 100 ft.	6-in. Fall per 100 ft.	9-in. Fall per 100 ft.	12-in. Fall per 100 ft.	18-in. Fall per 100 ft.	24-in. Fall per 100 ft.	36-in. Fall per 100 ft.
3-inch	21	30	42	52	60	74	85	104
4 "	36	52	76	92	108	132	148	184
6 "	84	120	169	206	240	294	338	414
9 "	232	330	470	570	660	810	930	1140
12 "	470	680	960	1160	1360	1670	1920	2350
15 "	830	1180	1680	2040	2370	2920	3340	4100
18 "	1300	1850	2630	3200	3740	4600	5270	6470
20 "	1760	2450	3450	4180	4860	5980	6850	8410

Table showing the velocity of discharge of different sized sewers.

Diam. of pipe.	180 feet per minute, 3 feet per second.		270 feet per minute, 4½ feet per second.		360 feet per minute, 6 feet per second.		540 feet per minute, 9 feet per second.	
	Fall.	Gallons per minute.	Fall.	Gallons per minute.	Fall.	Gallons per minute.	Fall.	Gallons per minute.
3.....	1 in 69	54	1 in 30.4	81	1 in 17.2	108	1 in 7.6	162
4.....	1 in 92	96	1 in 40.8	144	1 in 23.	192	1 in 10.2	288
6.....	1 in 138	216	1 in 61.2	324	1 in 34.5	432	1 in 15.3	648
9.....	1 in 207	495	1 in 92.	742.5	1 in 51.7	990	1 in 23	1,485

Transmission of Heat by Various Substances.

FILE 697.0

Window glass being.....	1,000	Brick (rough)	200 to 250
Oak or Walnut.....	66	Brick Whitewashed	200
White Pine	80	Granite or Slate.....	250
Pitch Pine	100	Sheet Iron	1,030 to 1,110
Lath and Plaster.....	75 to 100		

Table Showing Amount of Glass Surface which may be Heated by 1 Square Foot of Radiating Surface in Good Buildings.

Temperature of radiating surface (radiators) Fahr.....	Hot Water.			Steam.	
	160°	180°	200°	227° 5 Lbs.	240° 10 Lbs.

Square Feet of Glass to 1 Square Foot Radiator Surface.

Temperature above surrounding air 90°.....	1.9	2.3	2.8	3.3	3.8
" " " " 80°.....	2.3	2.9	3.5	4.0	4.6
" " " " 70°.....	3.0	3.6	4.2	5.0	5.7
" " " " 60°.....	4.0	4.6	5.25	6.0	7.0
" " " " 50°.....	5.0	6.0	6.8	8.0	9.0
" " " " 40°.....	6.9	8.0	8.2	10.0	11.5

Formulae for Figuring Radiation for Factories.

A formula for figuring radiation which is used by some of the best heating engineers in determining the amount of radiation for factory buildings is as follows: $\frac{G}{3.3} + \frac{W}{10.9} + \frac{V}{171} =$

sq. ft. of radiation in which, G = Glass Area.

W = Net Wall Area.

V = Volume of air in the Room.

SIZE OF STANDARD FLUE LINING ON SALE ON THIS MARKET.

Outside size.	Inside size.	Inside area.
4¼ x 8½ in.	3½ x 7¼ in.	22.6 sq. in.
8½ x 8½ in.	7 x 7 in.	49 sq. in.
13 x 13 in.	11½ x 11½ in.	135 sq. in.
4½ x 13 in.	3½ x 11½ in.	36.5 sq. in.
8½ x 13 in.	6½ x 11½ in.	77 sq. in.
13 x 18 in.	11½ x 16¼ in.	193 sq. in.
8½ x 18 in.	6½ x 16¼ in.	114 sq. in.
18 x 18 in.	15¼ x 15¼ in.	247 sq. in.

GENERAL RULE FOR BRICK STACKS.

Diameter of base should not be less than 1/10 of height if square, or round, 1/12 of height. Batter of stacks 3/100 of an inch to the foot in height. Thickness of brick work should be not less than one brick from top to 25 feet below same, changing to 1½ brick from 25 feet to 50 feet below top, increasing

½ brick in thickness for each succeeding 25 feet, measuring from the top downward.

Fireplace Flue Areas.

For three-story building, area at top of smoke chamber should be 1/12 of area of fireplace opening.

Two-story building area at top of smoke chamber should be 1/10 of area of fireplace opening.

One-story building area at top of smoke chamber should be ¼ area of fireplace opening.

Throat of fireplace should never be less than 3 in. or more than 4½ in. by the width of fireplace opening.

Front edge of arch should never be thicker than one-half brick, approximately 4 in.

Splay of sides of flue from throat opening up to flue lining should be 2 in. to the foot. The raise from soffit or lintel, or from highest point or soffit to arch should be 6 in.

Proportion of Parts of Steam Heating Boilers.

FROM PROF. R. C. CARPENTER.

FILE 697.43

Radiating surface—square feet.....	250	500	750	1000	1500	2000	3000	4000	5000	7500	10000
Nominal horse-power.....	2.5	5.0	7.5	10.0	15.0	20.0	30.0	40.0	50.0	75.0	100.0
Ratio radiating to heating surface.....	4.5	5.1	5.4	5.6	6.0	6.2	6.7	6.9	7.0	7.0	7.0
Probable evaporation per lb. coal.....	5.5	5.7	6.0	6.5	7.0	7.5	8.0	8.5	9.0	9.5	10.0
Pounds of steam per sq. ft. grate (A).....	55.0	57.0	60.0	65.0	70.0	75.0	80.0	85.0	90.0	95.0	100.0
Pounds of steam per sq. ft. grate (B).....	44.0	46.0	48.0	52.0	56.0	60.0	64.0	68.0	72.0	76.0	80.0
Ratio radiating to grate surface (A).....	165.0	171.0	180.0	195.0	210.0	225.0	240.0	255.0	270.0	285.0	300.0
Ratio radiating to grate surface (B).....	132.0	138.0	144.0	156.0	168.0	180.0	192.0	204.0	216.0	228.0	240.0
Ratio heating to grate surface (A).....	36.5	33.2	33.2	34.8	35.0	36.2	36.5	37.0	38.5	40.5	42.5
Ratio heating to grate surface (B).....	28.5	27.0	26.7	27.7	28.0	29.0	29.3	29.6	30.8	31.5*	32.3*
Heating surface, square feet.....	55.0	98.0	138.0	178.0	250.0	322.0	447.0	580.0	710.0	833*	1071*
Grate surface, square feet (A).....	1.52	2.92	4.15	5.68	7.15	8.9	12.4	15.7	18.5	26.5	33.3
Grate surface, square feet (B).....	1.88	3.88	5.4	6.37	8.92	11.2	15.5	19.5	23.2	32.5	41.5
Diameter of safety valve, inches.....	1.5	2.25	2.50	2.75	3.0	3.25	3.5	4.2	4.0	2 of 3	2 of 4
Diameter of smoke flues, inches.....	7.0	10.0	11.2	12.0	15.0	17.0	19.0	23.0	25.0	24	3A
Square inches in above flues.....	38.5	78.5	95.0	113.0	176.7	227.0	283.5	415.5	490.9	615.7	907.9

* Water tube boilers.

A When rate of coal consumption is 10 pounds per hour each square foot grate surface.

B When rate of coal consumption is 8 pounds per hour each square foot grate surface.

THE ORDERS AND THEIR APPLICATION

By ALFRED W. S. CROSS, M. A., F. R. I. B. A., and ALAN E. MUNBY, M. A.

Introduction.

So many scholarly works upon the Orders are in existence, that some explanation seems to be called for in introducing another series of articles upon a subject that is, to all appearances, already well worn.

Notwithstanding the consensus of opinion as to the general proportions that ought to be followed in their delineation, an opinion based upon the rules laid down by the architects of an early period of the Renaissance, a surprising divergence from the precepts and practices of these old masters of their art is to be found in many buildings of our own time.

The writers are only aware of the existence of one book which seems to meet the usual office requirements, and that is a work entitled: "Rules for Drawing the Several Parts of Architecture," by James Gibbs, published in 1732; a book that has never been reprinted and copies of which are not now readily obtainable. The object aimed at, and successfully attained, is an illustration and description of an example of each Order, not "after Gibbs," but representing one of a good average type of design so proportioned that the dimensions of the various parts bear simple and easily discernible ratios one to another.

An attempt has been made to co-ordinate the leading features of the book by re-drawing some of the illustrations, retaining the useful dimensions shown thereon and entirely re-writing the description of the plates, with the introduction of some general principles likely to be of value to the draughtsman and student, for which purpose the opinions of standard writers, particularly those of Sir William Chambers, have been freely incorporated.

Before attempting such a condensation of the material in the book it was thought desirable to ascertain how far the generalizations adopted by Gibbs really represent the proportions used by acknowledged authorities. For this purpose the average ratio of the diameter of the column to the height of the entablature, as being a relation which essentially affects the whole proportion of the Order, was obtained by measuring a number of recognized examples, and it may be of interest to give the results, as an indication of the actual value of the dimensions used.

The result renders it evident that the general proportions of the Orders as recommended for adoption by this architect are fully worthy of confidence.

Hence, it would obviously seem preferable to master a few main dimensions, and, having thus inculcated a general sense of proportion, to rely upon gaining familiarity with the plates by constant use, when the proportions of the smaller members of the compositions will become naturally assimilated. The Composite Order is given in Gibbs' book, but, owing to its similarity to the Corinthian and to the absence of a consensus of opinion as to its dimensions, it has not been included in the present work.

No encroachments have been shown on any of the Orders to avoid distracting attention from the dimensions. With the exception of the whole of the Tuscan Order and of the frieze of the Ionic Order there are few members, apart from mere fillets, which have not been enriched, by some form of ornament, in one or another example, the Doric naturally the least and the Corinthian the most. In the latter Order, in fact, even the cyma and corona of the cornice, in addition to the frieze, ogees and beads, are often ornamented, but, apart from the question of expense, it is undesirable to carry such elaboration too far, as when placed in close contact with each other, especially when a distant view is alone possible, one moulding will often rob another of its effect, and, indeed, the value of richness of detail is more often than not lost in this manner.

The enrichment of columns beyond ordinary flutings is generally to be deprecated, while the application of ornament to bases and pedestals is seldom either requisite or desirable.

However great may be the utility of drawings dealing with the Orders, it should never be forgotten that they are merely a means to an end, that end being an executed building. Those whose work is confined to a drawing board develop a strong tendency to consider their compositions solely from an elevational and artistic draughtsman's point of view, and every opportunity should be taken of checking this habit and of cultivating the art of thinking "in the round." The study of per-

TABLE SHOWING THE APPROXIMATE RATIO BETWEEN THE LOWER DIAMETER OF THE COLUMN AND THE HEIGHT OF THE ENTABLATURE.

Tuscan.	Doric.	Ionic.	Corinthian.
Alberti1:1.5	Alberti1:2.0	Alberti1:1.4	Alberti1:1.8
Palladio1:1.8	Palladio1:1.9	Palladio1:1.7	Palladio1:2.0
Scamozzi1:1.9	Scamozzi1:2.1	Scamozzi1:2.0	Scamozzi2:2.0
Vignola1:1.8	Vignola1:2.0	Scamozzi1:1.8	Vignola1:2.5
—	Parthenon1:2.0	Vignola1:2.3	Pantheon1:2.3
—	Baths, Diocletian 1:2.0	Fortuna (Rome) 1:2.3	Jupiter Stator ..1:2.5
—	Temple Paestum..1:1.7	Baths, Diocletian 1:1.9	Jupiter Tonans..1:2.2
—	Apollo, Delos ...1:1.8	Minerva, Athens. 1:2.3	Temple Antonius 1:2.3
St. Paul's Convent	Bow Church,	Illiis, Athens...1:2.3	
Garden ...1:1.8	Portico1:1.9	Banqueting Hall.1:2.0	Hamden Court..1:2.2
Average1:1.76	Average1:1.93	Average1:2.00	Average1:2.00
Gibbs1:1.75	Gibbs1:2.00	Gibbs1:1.82	Gibbs1:2.00

The above examples have not been selected with any intention of justifying the proportions adopted by Gibbs, but are merely cited as those which readily occurred to the mind, or of which the dimensions could be easily obtained.

spective of buildings, and, best of all, the preparation of models of portions of a proposed building, an occupation which often results in the discovery of latent defects of design, are alike of the greatest educational value to the student of architecture

THE SETTING UP OF AN ORDER.

(To be studied in connection with Plates I., II., III., IV. and V.)

The sequence followed in setting up an Order will be found to influence, to some extent, the rapidity and facility with which it can be accomplished. An outline of the method of procedure may, therefore, prove useful.

Usually the height of the Order is fixed by circumstances, as, for example, when it is to be applied to a given story of a building.

The total height having been settled, draw the limiting horizontal lines and then set out the vertical centre lines of the columns, thus dividing the frontage to be treated into bays appropriate to the exigencies of the design and having due regard to the correct intercolumniation of the Order adopted. If a pedestal is to be placed under the column, cut off one-fifth of the total height for it, and cut off one-fifth or one-sixth of the remainder (measured from the top limiting horizontal line) for the vertical height of the entablature; the intervening space gives the height of the column, including its cap and base. If no pedestal is to be used, divide the whole of the given height into five or six parts, cut off one of these parts, from the top, for the entablature, and the remainder gives the height of the column.

The Column. Since some of the dimensions of the entablature are in terms of the diameter of the column, the latter should be next developed. The term "diameter of the column" refers always to its greatest diameter—namely, that of the shaft just above the lower cincture. This dimension is one-seventh to one-tenth of the height between the soffit of the entablature and the top of the pedestal, or lower limit of the Order in the absence of a pedestal. If the centre lines of the piers do not represent the centres of the columns, as, for instance, when coupled columns are used, the centre line of one of the columns must now be decided upon and the diameter of the Order symmetrically disposed horizontally across it. A semi-diameter is then cut off, from the bottom of the column, for the height of the base, and it should be noticed that this—except in the Tuscan and alternative Doric Orders—does not include the fillet at the base of the shaft, the members above the upper torus being reckoned as part of the shaft, as are also the astragal and fillet below the necking of the capital of the column. The plinth and lower torus of the base project one-third and the upper torus one-fifth of a semi-diameter beyond the lower circumference of the shaft. The leading lines for the base having thus been obtained, cut off by a horizontal line the height of the capital from the top of the column, and (except in the Ionic Order) again below it, a height equal to one-sixth of a semi-diameter for the astragal and fillet below the necking.

The semi-diameter of the shaft at one-third of its height from the bottom is then divided into five or six parts, and four or five of these parts are taken as a semi-diameter at the top, below the astragal. The shaft may now be completed, the entasis being usually made to start from the greater diameter, one-third up the shaft, below which point it is a true cylinder until the cincture at the base is reached. This is the best method to adopt in the case of small scale drawings. Where large detailed drawings are in question the diameter may be alternatively divided at the base of the shaft instead of at one-third of

its height, and the entasis extended throughout the whole length. The completion of the shaft enables the projection of the capital to be marked off, and also that of the astragal and fillet, which is equal to their combined height.

The Entablature. The development of the entablature can now be proceeded with, the architrave, frieze and cornice being ruled off horizontally and the members of each inserted (see dimensions). The projections for a returned end or section are obtained from the upper diameter of the shaft. The lowest member of the architrave, and also the frieze, lie vertically over the circumference of this upper end of the shaft. The projection of the cornice beyond the frieze line is equal to its height, except in the Doric Order, in which the projection is one-third more than its height of one diameter. Further rules dealing with minor projections and the position of the modillions, dentils, etc., will be supplied by a study of the plates and tabulated dimensions.

Pedestal. Finally, the pedestal, if any, should be divided vertically into four parts; the lower part is ruled off for the height of the plinth, one-third of the second part for the height of the base, and one-half of the top part for that of the cap. The projection of the die is equal to that of the base of the column, and the plinth and the cap of the pedestal extends beyond this for a distance equal to the height of the base of the pedestal previously obtained.

The above dimensions will all be found in the subjoined table, which represents an endeavour to bring together, in a form suitable for reference, sufficient information to make any glaring disproportion impossible.

A few of the minor divisions are only approximations; they will, however, be found to be sufficiently accurate for any but large detail drawings, in which it is not desirable to destroy all individuality by rigorous mechanical rules.

On the left hand will be found the dimension required and, in the intermediate column the fraction for each Order of the previously ascertained unit given in the right-hand column.

Plate I.

Plate I. represents the four Orders drawn to a common vertical height.

The pedestal may or may not be required and, if used, it is to be regarded as an addition to the Order, the relative dimensions of the parts of which are not altered by its removal or introduction.


The diameter of the column (by which is meant the diameter of the shaft following its lower cincture) is the ruling dimension from which most of the others are obtained, and the smaller circumference of the top of the shaft always coincides with the frieze line from which all the projections of the entablature are set out.

In judging the value of such projections it should be borne in mind that in execution the higher vertical faces of the composition will usually be much foreshortened to the observer and that there will be a consequent increase in the comparative value of neighboring projections.

A perusal of the table will indicate those dimensions which all the Orders have in common, but for convenience of reference they are further summarized thus:

Height of Pedestal, $\frac{1}{2}$ total height of Order.

PLATE 1.



TUSCAN

DORIC

IONIC

CORINTHIAN

Height of Plinth, $\frac{1}{4}$ height of Pedestal.
Height of Pedestal Base, $\frac{1}{3}$ height of Pedestal Plinth.
Height of Pedestal Cap, $\frac{1}{2}$ height of Pedestal Plinth.

Projection of Cap and Plinth, $\frac{1}{3}$ height of Pedestal Plinth.

Projection of Corona over Die, $\frac{3}{4}$ projection of Pedestal Cap.

Height of Column Base, $\frac{1}{2}$ diameter of Column.

Projection of Base over Shaft, $\frac{1}{3}$ semi-diameter of Column.

Pilasters. The general proportions allotted to the columns of the Orders apply also to pilasters, which may be regarded as columns square on plan, but almost universally deeply engaged. The projection of pilasters must be regulated by circumstances. If impost mouldings or other projections stop upon them, as on the inner wall of an arcade, these projections must be sufficient to take the mouldings, and if they line with engaged columns crowned by an entablature, they must have a projection similar to the columns, and therefore in such cases never less than a semi-diameter. Apart from these

considerations, the projection should be about one-fourth of the diameter. Pilasters may be fluted or plain; if the former, the flutes should be, as far as possible, the same size as those of the adjoining columns, and always an odd number.

* * *

On plain faces 7 flutes (occasionally 9) are used, and therefore in the above case 4 flutes (or 5) would be employed on each side of the re-entering angle. The returned sides of pilasters should never be fluted unless the projection is as much as half of a diameter. The diameter assigned to a pilaster will be that of a column (if any) used in conjunction with it. The shaft may or may not be diminished.

If the pilaster stand alone it is best formed with the same top and bottom diameter, but if a column stand in front of it then it should be diminished to the same extent as the column. Entasis is not usually given to pilasters.

Unless columns and pilasters are monoliths the shafts should be built up of three drums and not two, as a central joint, unless exceptionally well executed, has a very disagreeable appearance.

PLATE 2.





Plate II.

The Tuscan Order, though seldom used, is suitable for situations in which an appearance of strength and simplicity is required, and in which the cost of the work is an important factor. It should always be devoid of any enrichment and the unbroken character of the frieze and cornice makes it particularly useful in designs presenting awkward problems of intercolumniation.

The ratio of the dimensions of its parts is exceedingly simple. It should be noticed that the fillet below the cincture of the shaft is included in the height of the base of this Order. The projection of the cornice over the upper circumference of the column is, in this and in all Orders, except the Doric, equal to its height.

TUSCAN

PLATE 3. MUTULE CORNICE



DORIC

DENTICULAR CORNICE





Plate III.

The Doric Order is always effective when used in lower storeys, arcades, and door and window openings, but owing to the triglyphs upon the frieze, which must fall centrally over the columns, it is the most difficult to deal with when spacing is in question.

The dimensions of the cornice do not lend themselves to any simple ratio and its projection is always greater than that adopted for the other Orders. The 45° line from the top of the frieze at once gives the bed mould of the mutule course, and one-third of the height of the cornice added to the top projection of this guiding line gives the total projection, while the mutules are one-half a diameter in side elevation. Some considerable modifications of the Order, as here represented, will be found to exist in many recognised examples. Occasionally the mutules are dispensed with, and their bed mould is cut to form a dentil course, as in the Theatre of Marcellus. The cyma crowning the cornice is often replaced by a cavetto, while the Doric base (shown alternatively on the plate) sometimes replaces the more graceful attic base. When this base is used, the upper fillet should be included in the height of the base, as in the Tuscan Order.



IONIC CAPITAL

Plate IV.

The Ionic Order shows smaller variations from the pure Classic examples than any other, and its proportions are fairly simple.

Two styles of cornices are, however, used, the modillion and the dentil cornice, and although the method adopted by Gibbs of giving prominence to the former has been followed, it should be stated that the latter is more generally found in old examples, whilst the former is preferred by Palladio.

Represented side by side upon the plate the extent of the variation is easily discernible. A modillion or dentil should always be bisected by the centre line of the column and the spacing determined by the distance of this line from the frieze, as set out upon the drawing. The frieze is always plain and in larger works it is, preferably, kept flat. In smaller compositions, however, when narrow or when used over doors and windows a pulvinated frieze may be adopted with good effect.

The earlier alternative form of the Ionic capital in which the faces of the volutes are parallel to the plane of the elevation (not shown upon the drawings) may, of course, be substituted for the capital with angle volutes at 45°, though the latter has usually a much more graceful effect, particularly in small compositions. Of course, the geometrical method for setting out the volutes cannot be used in drawing such capitals in ordinary elevation. It should be noticed that the height of the capital in this Order is measured from the soffit of the volutes.


The centre of the eye is one-third of the height of the capital from its bottom and is in elevation placed just outside the top circumference of the shaft, while the horizontal fillet at the top of the shaft is immediately below the eye.

When the column is fluted the width of the fillets should be one-fourth to one-third that of the flutes. The flutes generally number twenty or twenty-four; in the latter case the simple method of setting them out on plan, as shown on the drawing, will be found of service.

The attic base is always used with the Ionic Order.

IONIC

PLATE 5.



CORINTHIAN

Plate V.

The Corinthian Order has been represented with considerable variations from the original type.

The Ionic entablature was often used by the ancients, supported by Corinthian columns, and the Corinthian cornice itself, though here represented with a dentil band, is often found without one. No general rule appears to exist for spacing the modillions or for their dimensions, the ratio of the width of the modillion to the space between two of them varying from $1:1\frac{1}{2}$ to $1:2\frac{1}{2}$, and again the number of the dentils between the modillions varies from 2 to 5 in different examples.


Both features should be symmetrically placed with reference to one another and to the centre line of the column, a point often neglected. To secure this result the following method is recommended:— Draw a modillion one-sixth of the diameter of the column in width, arranged symmetrically over the centre line of the column. Place another with its outside edge three and a half times its width within the total projection of the cornice, and thus obtain the spacing between the blocks. Divide the distance between two modillion centres into 15 parts, give two to a dentil, to be placed symmetrically under a modillion, and one to each space between the dentils, which will be found to bring the inside edge of the last dentil before the return, on the frieze line.

The form and projection of the leaves of the capital are largely matters of individual taste, but the general method of their arrangement will be evident after examining the drawing. It may, however, be noted that the eye of the volute is just outside the lower circumference of the shaft, and that the tiers of leaves divide the capital below the abacus into three approximate equal horizontal sections.


The column may or may not be fluted as in the Ionic Order.

The attic base, as used in the Ionic Order, is very generally employed—in fact, it is often preferable to adopt it, omitting the additional mouldings shown, for the sake of variety, on the drawing.

PLATE 6.



IONIC



DORIC

Plate VI.

The relations and dimensions given in this and similar subsequent plates must, therefore, be looked upon as necessarily somewhat elastic. At the same time, such dimensions as are given should not be disregarded, but considered in the light of proportions to be attained as far as the exigencies of the plan will admit.

The spacing of arcading dealt with in this plate should be governed by the height of the space to be treated, and it will be found that the best effects are obtained when the widths of the

seen that a relation exists between the diameter of the column, the width of the pilaster, and the width of the opening. Again, the diameter of the column relatively to the opening will be influenced by the presence, or absence, of a pedestal to the Order. The summary shown, collected from Gibbs's work, giving the dimensions to be aimed at in order to comply with the above relations, will be found useful.

The height of the impost should always be about two-thirds of the height from the ground to the soffit of the architrave of the Order, whether a pedestal is in use or not.

Diameter of Column = 1.


	Tuscan.		Doric.		Ionic.		Corinthian.	
	No Ped.	With Ped.	No Ped.	With Ped.	No Ped.	With Ped.	No Ped.	With Ped.
Width of bay centre to center	6	7	6 $\frac{1}{4}$	7 $\frac{1}{2}$	6	7 $\frac{1}{2}$	6 $\frac{5}{12}$	8 $\frac{1}{6}$
Width of one pilaster	$\frac{1}{2}$	$\frac{2}{3}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{1}{2}$	$\frac{7}{10}$
Width of opening	4	4 $\frac{2}{3}$	4 $\frac{1}{4}$	5 $\frac{1}{4}$	4	5 $\frac{1}{4}$	4 $\frac{1}{3}$	5 $\frac{1}{2}$

openings approximate to half of their height, and when the total width of the piers lies between one-half and two-thirds of that of the opening.

The spacing must also be considered in reference to the Order employed, so that when triglyphs, or modillions, are placed centrally over the columns their proper spacing may be interfered with as little as possible. It will thus be

The archivolt or moulding running round the arch should be the same width as the pilaster (less any necessary clearance for the mouldings)—that is, about one-eighth of the width of the opening, which should also be the height of the impost cap to the bottom of the necking. Further details as to the members will be found on Plate VII.

PLATE 7.



IMPOSTS AND ARCH MOVLDS




Plate VII.

Impost Mouldings.

Details are here given of impost mouldings, with their archivolts, suitable for the different Orders. The divisions of the impost are all simple and similar in each example, the height of the corona and of its mouldings above, if any, being equal to the height of the mouldings below, which, again, are equal to the necking. The bead and fillet below the necking are one-sixth of the height of the impost, the bead being double the height of the fillet. The projection of the impost beyond the line of the pilaster is equal to the height of the corona and member over in the

first two Orders, while the projection of the corona itself is equal to this height in the last two.

The pilaster is square on plan, and, therefore, the plan of the archivolt is represented by this square upon which the mouldings are placed. An examination of these mouldings will show that they resemble the architraves given for their respective Orders, and their forms admit of similar variations. It will be noticed that the innermost face is always in the plane of the face of the pilaster, while the projection of the moulding at the extrados increases from about one-quarter the width of the whole archivolt in the Tuscan to one-third in the Corinthian Order.

SUBJECT INDEX.

System of Classification for Filing Data, Drawings, Plates, Catalogues, Etc.,
in Architects' and Contractors' Offices.

INTRODUCTION.

The decimal system of classification was devised and elaborated by Mr. Melvil Dewey, formerly director of the New York State Library. This system was intended primarily for the use of librarians in the classification and arrangement of books and pamphlets, but it was soon found that the system furnished also a simple and effective means of classifying, indexing and filing literary matter of all kinds. Engineers have found it useful for indexing technical data and information, catalogs, reports, card systems, drawings, etc., and it has been found equally useful by manufacturing and business concerns.

Much of the following subject matter has been obtained from the original publication of Mr. Dewey and extension bulletins published by the University of Illinois, but this data has all been rearranged and classified by the editor for the 1921 edition of the "Illinois Society of Architects HAND BOOK FOR ARCHITECTS AND BUILDERS." The purpose of the rearrangement being to bring the Index more nearly in accord with the trade divisions of modern practice.

EXPLANATION OF THE DECIMAL SYSTEM.

The essential characteristic of the Dewey System is its method of division and sub-division. The entire field of knowledge is divided into nine chief classes numbered by the digits from 1 to 9. Matter of too general a nature to be included in any of these classes is put into a tenth class and indicated by 0. The following are the primary classes of the Dewey System:

- 0 GENERAL WORKS
- 1 PHILOSOPHY
- 2 RELIGION
- 3 SOCIOLOGY
- 4 PHILOLOGY
- 5 NATURAL SCIENCE
- 6 USEFUL ARTS
- 7 FINE ARTS
- 8 LITERATURE
- 9 HISTORY

Each of these classes is again divided into nine divisions, with a tenth division for general matter, and each division is separated into nine sections. The sections are again sub-divided and the process may be carried as far as desired.

It is thought that this system will be especially valuable to architects for classifying drawings, catalogs, reports and technical data. Our space is too limited to publish the complete work, nor is it desirable. Should any one be sufficiently interested to go into the matter thoroughly, they should have Mr. Dewey's complete text on the subject. In order to make the application of the system clear in the briefest possible way, the miscellaneous information contained in this book has been assumed to comprise a small architect's library and has been classified according to the Dewey System. It is hoped that this will make clear the practical application to architects' libraries, both large and small. In succeeding years, we hope to be able to publish a more extensive relative index in which the items of the classification are arranged alphabetically, the one at present published only covering the items of miscellaneous information contained in this book, with some of the more important general topics. We are particularly concerned as practitioners of the profession of architecture with divisions 6 and 7, "Useful Arts"

and "Fine Arts," comprising the following subject numbers:

- 600 USEFUL ARTS
- 610 MEDICINE
- 620 ENGINEERING
- 630 AGRICULTURE
- 640 DOMESTIC ECONOMY
- 650 COMMUNICATION AND COMMERCE.
- 660 CHEMICAL TECHNOLOGY
- 670 MANUFACTURES
- 680 MECHANIC TRADES
- 690 BUILDING

Omitting all sub-divisions of this topic, with the exception of 690 "Building," we publish the sub-divisions of same. As distinguished from "Architectural Construction," "Building" has to do more particularly with the processes of construction and matters pertaining to trades and materials involved in the construction of buildings should be more properly classified under "Building," while matters as to types and component architectural parts are more properly classified under Architectural Construction.

690 BUILDING — Materials and Trades.

- 690.0 GENERAL.
- .01 History.
- .011 History of Materials.
- .012 History of the Art of Building.
- .013 Biography of Architects.
- .014 Biography of Builders.
- .015 Biography of Craftsmen.
- .02 Organization of Construction.
- .03 Finance of Building.
- .04 Operation of Buildings.
- .05 General Works on the Occupation and Art of Building.
- .051 Manuals.
- .052 Handbooks.
- .053 Receipts.
- .054 Periodicals.
- .055 Society Proceedings.
- .056 Trade Unions, Guilds, Etc.
- .057 Contractor's Associations.
- .058 Material Dealer's Associations.
- .059

690.1 EDUCATION OF PERSONNEL CONCERNED IN BUILDING.

- .11 Education of Designers.
- .12 Education of Supervisors.
- .13 Education of Managers.
- .14 Education of Craftsmen.

690.2 BUILDING MATERIAL IN THE ABSTRACT.

(All special material should be classified under the appropriate trade.)

690.3 PLANS FOR BUILDINGS.

- .30 Incidents to the Preparation of Drawings.
- .301 Drafting Room Supplies.
- .302 Drafting Methods.
- .31 Preliminary Studies.
- .32 General Drawings.
- .33 Scale Details.
- .34 Full Size Details.

690.4 SPECIFICATIONS FOR BUILDINGS.

- .40 Matter Pertaining to All Trades.
- .40-A General Conditions of the Contract.
- .41 Earth Working and Transportation Trades. (See File 691.)
- .41-A Preparation of Site.
- .41-B Excavations.
- .41-C Construction Planting.
- .41-D Grading and Filling.
- .41-E Preparation of Soil, Sodding and Seeding.
- .41-F Planting.

- .42 Mortar Using Trades.** (See File 692.)
- .42-A Masonry Materials.
- .42-B Foundation Work.
- .42-C Concrete Work.
- .42-D Stone Work.
- .42-E Brick Work.
- .42-F Fireproofing, Furring and Partitions.
- .42-G Architectural Terra Cotta.
- .42-H Paving.
- .42-I Plastic Floors.
- .42-J Plastic Reinforcement, Lathing and Furring.
- .42-K Plastering.
- .42-L Plastic Insulation, Pipe Covering, Etc.
- .42-M Models, Clay and Plaster.
- .42-N Marble and Substitutes (Including Slate, Structural Glass Terrazzo Slabs, Etc.)
- .42-O Tile and Substitutes.
- 690.43 Wood-Working Trades and Hardware.** (See File 693.)
- .43-A Wood-Working Materials and Methods.
- .43-B Carpentry.
- .43-C Rough Carpentry Hardware.
- .43-D Finish Hardware.
- .43-E Special Door, Window and Screen Hardware.
- .43-F Wood Furniture.
- 690.44 Heavy Metal Trades** (employing metal heavier than No. 10 gauge). (See File 694.)
- .44-A Metal Materials and Methods.
- .44-B Structural Metal (over No. 10 gauge).
- .44-C Miscellaneous Metal, Fire-escapes.
- .44-D Ornamental Metal (over No. 10 gauge).
- .44-E Vaults, Safes, Vault Doors, Etc.
- .44-F Solid Metal Sash.
- .44-G Heavy Metal Doors and Shutters.
- 690.45 Sheet Metal Trades** (employing metal of No. 10 gauge or less. See File 695.)
- .45-A Sheet-Metal Materials and Methods.
- .45-B Ordinary Sheet-Metal.
- .45-C Sheet-Metal or Sheet-Metal Covered Fire-Resisting Doors and Windows.
- .45-D Art Sheet-Metal Trim and Doors.
- .45-E Metal Ceilings.
- .45-F Sheet-Metal Furniture.
- .45-G Miscellaneous Sheet-Metal, Store-Fronts, Etc.
- .45-H Utensils.
- .45-I Ventilating Ducts and Stacks, Furnace Work, Etc.
- 690.46 Brush, Broom and Swab-Using Trades** (See File 696.)
- .46-A Brush Trade Materials and Methods.
- .46-B Water-proofing Membrane and Mastic or other Viscous Compositions mopped, broomed or swabbed in place.
- .46-C Composition Roofing.
- .46-D Plain Painting and Varnishing.
- .46-E Decorations (Plain, Painted or Water Color).
- .46-F Hangings, Fabrics.
- .46-G Upholstery.
- .46-H Window Shades.
- .46-I Plain Glass and Glazing.
- .46-J Art Glass and Glazing.
- 690.47 Pipe Trades.** (See File 697.)
- .47-A Pipe Trade Materials and Methods.
- .47-B Plumbing.
- .47-C Gas-fitting.
- .47-D Sprinkler Fitting.
- .47-E Heating (including Steam and Hot Water Heating).
- .47-F Steam Power Work.
- .47-G Mechanical Ventilation. (See 698.)
- 690.48 Wire and Conduit Trades** (See File 698.)
- .48-A Wire Trade Materials and Methods.
- .48-B Electrical Conduit and Wiring.
- .48-C Lighting Fixtures.
- .48-D Electrical Power Work.
- 690.49 Machinery and Miscellaneous Trades** (See File 699.)

- .49-A Machinery and Miscellaneous Materials and Methods.
- .49-B Elevators.
- .49-C Conveying Machines.
- .49-D Mechanical Cleaners.
- .49-E General Machinery.
- .49-F Mechanical Refrigeration.
- .49-G Insulation, Pipe Covering, Etc. (See File 690, 42-L.)
- .49-H Refrigerators, Coolers and Freezers.
- .49-I Miscellaneous Equipment not Classified.
- 690.5 ESTIMATES FOR BUILDINGS.**
- 690.6 CONTRACTS.**
- 690.7 SUPERVISION OF CONSTRUCTION AND ACCOUNTS.**
- 690.8 PROFESSIONAL SERVICES.**
- .80-A Remuneration Fees, Commissions.
- .80-B Duties, Relationships, Etc.
- .80-C Responsibility, Etc.
- .80-D License or Registration.
- .81 Architect.
- .82 Structural Engineer.
- .83 Mechanical Engineer.
- .84 Sanitary Engineer.
- .85 Electrical Engineer.
- .86 Illuminating Engineer.
- .87 Clerk of the Works.
- .88 Building Construction Manager.
- .89 Specialists not otherwise Classified.
- 690.9 LAWS AND RULES CONTROLLING BUILDING.**
- .91 State or General Laws.
- .92 Municipal Ordinances, Rules, Etc.
- .93 Trade Rules.
- .94 Findings, National Joint Board of Jurisdictional Awards.
- .95 Lien Laws.
- .96 Underwriters' Rules.
- .97 Public Service Company's Rules.
- .98 Liabilities of:
- .981 Architects.
- .982 Contractor.
- .983 Workman.
- .984 Owner.
- .985 Bondsman.
- .986 Liability Insurance Co.
- .987 Adjoining Property Owner.
- .988 Public.
- .989 Any Other Responsibilities.
- 691 EARTH—WORKING, TRANSPORTATION AND TEAMING TRADES.**
- 691.0 TOOLS, UTENSILS, APPARATUS, ETC.**
- .01 Shovels, Picks, Drills, Bars, Wheelbarrows, Etc.
- .02 Plows, Scrapers, Trucks, Carts, Wagons, Teams, Tractors.
- .03 Excavating, Trench and Mining Machinery.
- .04 Hoists, Cranes, Pile Drivers, Conveyors, Etc.
- .05 Dummy Railroad Equipment, Tracks, Cars, Etc.
- .06 Soil Testing Apparatus.
- .07 Shoring, Sheet Piling, Piling, Caissons, Etc.
- .071 Wood.
- .072 Metal.
- .073 Concrete.
- .08 Blasting Powder and Apparatus.
- .09 Rock Crushers.
- 691.1 MATERIALS TO BE REMOVED.**
- .11 Common Earth, Clay, Sand, Gravel.
- .12 Hard-pan, Conglomerate Rock, Etc.
- .13 Trees, Shrubs, Etc.
- .14 Rubbish, Etc.
- .15 Buildings, Vaults, Pipes, Cisterns, Etc.
- 691.2 DISPOSAL OF MATERIALS.**
- .21 Stacking.
- .22 Cartage.
- .23 Dumps.
- 691.3 UTILIZATION OF MATERIALS.**
- .31 Sand and Gravel Stored for Mortar.
- .32 Black Earth for Top Fill.
- .33 Crushed Rock for Aggregate.

- 691
 .34 **Cleaning and Stacking Building Material for Use in New Building.**
 .35 **Re-Plant and Protection of Trees and Shrubs.**
- 691.4 **FILLING MATERIAL.**
 .5 **FERTILIZER.**
 .6 **NURSERY STOCK.**
 .7 **DRAINAGE MATERIAL.**
 .8 **FROST PROTECTION.**
 .9
- 692 **MORTAR-USING TRADES — (Inc. Masonry, Plastering, Tile and Marble Setting and the preparation for same).**
- 692.0 **MASONRY APPARATUS.**
 .01 **Mixing Boxes, Platforms, Etc.**
 .02 **Tools, Hose, Heaters, Etc.**
 .03 **Mixers for Mortar and Concrete.**
 .04 **Scaffolding, Horses, Planks, Etc.**
 .05 **Forms.**
 .06 **Erection Apparatus, Hoists, Cranes, Chutes.**
 692.1 **MATERIALS FOR MASONRY.**
 .11 **Liquids, Water, Anti-freezing, Etc.**
 .12 **Aggregate (a) Sand, (b) Stone Screenings, (c) Gravel, Crushed Stone, (d) Crushed Slag, (e) Cinders.**
 .13 **Cementing Materials for Masonry.**
 .131 **Limes.**
 .132 **Hydraulic Cements, (a) Natural, (b) Portland, (c) Miscellaneous.**
 .133 **Gypsums, (a) Plaster of Paris, (b) Keene's Cement, (c) Miscellaneous.**
 .134 **Magnesites.**
 .135 **Asphaltic Cements.**
 .136 **Composite Cements.**
 .137 **Other Cements.**
 .14 **Solids for Masonry.**
 .141 **Stone.**
 .142 **Brick, (a) Adobe, (b) Burned Clay.**
 .143 **Structural Partition and Load-bearing Tile.**
 .144 **Terra Cotta.**
 .145 **Cement Blocks.**
 .146 **Composite Blocks.**
 .147 **Marble, Soapstone, Structural Slate and Glass.**
 .148 **Tile, Paving and Wall.**
 .149 **Terrazzo Blocks and Slabs.**
 .15 **Mason's Hardware.**
 .151 **Anchors, Ties, Wall Boxes, Plates, Inserts, Scoopers, Sleeves, Etc.**
 .152 **Thimbles, Ash and Coal Chutes, Clean-out Doors, Dampers, Grate Bars, Chimney Cap, Vent Gratings, Etc.**
 .153 **Vault Lights, Sidewalk Doors, Etc.**
 .154
- 692.2 **STONE CONSTRUCTION.**
 .21 **Preservatives, Treatment.**
 .22 **Bond, Anchorage, Ties, Lewises, Etc.**
 .23 **Cutting and Dressing of Stone, Stereotomy, Drips, Weathering, Etc.**
 .24 **Setting, Joints, Mortar, Bedding, Etc.**
 .25 **Cleaning and Pointing.**
- 692.3 **BRICK CONSTRUCTION.**
 .31 **Preservative Treatment.**
 .32 **Common Brick Work.**
 .33 **Fire Brick Work.**
 .34 **Face Brick Work.**
 .35 **Laying Joints, Mortar, Etc.**
 .36 **Chases, Fire-Stops, Corbels, Etc.**
 .37 **Bonds, Anchors, Etc.**
 .38 **Cleaning and Pointing, Etc.**
- 692.4 **TERRA COTTA CONSTRUCTION.**
 .41 **Preservative Construction.**
 .42 **Bonding, Anchorage, Ties, Etc.**
 .43 **Structural Tile Walls.**
 .44 **Structural Tile Floors.**
 .45 **Ornamental or Decorative Terra Cotta.**
 .46 **Laying Joints, Mortar, Etc.**
 .47 **Fitting Around Structural Parts.**
 .48 **Centers, Supports, Protection.**
 .49 **Cleaning, Pointing and Repairing.**
- 692
 .5 **FIREPROOF CONSTRUCTION.**
 .51 **Hollow Clay Tile, Hard, Porous.**
 .52 **Gypsum Tile.**
 .53 **Concrete.**
 .54 **Tying, Fitting, Securing.**
 .55 **Combination Construction.**
 .56 **Centers, Forms, Etc. (See 693, .41 for Wood and 695 for Sheet-Metal.)**
 .59 **Patching, Repairing.**
- 692.6 **CONCRETE CONSTRUCTION.**
 .61 **Massive, Caissons, Footings, Retaining Walls, Etc.**
 .62 **High Duty Concrete.**
 .63 **Hollow Concrete Building Blocks.**
 .64 **Ornamental Concrete.**
 .65 **Concrete Supported on the Ground, Paving of Walks, Floors, Drives, Etc.**
 .66 **Waterproof Concrete.**
 .67 **Reinforced Concrete.**
 .671 **Reinforcing Systems, Arranged Alphabetically.**
 .672 **Forms and Centers. (See 693, .41 for Wood; also 695 for Sheet-Metal.)**
 .673 **Tests and Inspection.**
 .674 **Data for Experiments.**
 .675 **Formulae.**
 .676 **Special Applications.**
- 692.7 **DECORATIVE AND SANITARY WALL AND FLOOR SURFACING.**
 .71 **Marble, Soapstone and Slate.**
 .72 **Structural Glass.**
 .73 **Terrazzo.**
 .74 **Tile Mosaic, (a) Ceramic, (b) Marble, (c) Glass.**
 .75 **Tile, (a) Quarry, (b) Encaustic, (c) Marble, (e) Ornamental.**
- 692.8 **WATER-PROOFING AND HARDENERS.**
 .81 **Integral (for brush applied mastic and painting, water-proofing, see File 696).**
 .82 **Hardeners (a) Surface, (b) Admixed.**
- 692.9 **PLASTER TRADES.**
 .91 **Interior Plaster.**
 .91(a) **Common Lime Plaster.**
 .91(b) **Gypsum Plaster.**
 .91(c) **Magnesite.**
 .91(d) **Portland Cement Plaster.**
- 693 **WOOD WORKING TRADES.**
 .0 **APPARATUS, INCIDENTAL TOOLS, ETC.**
 .01 **Mechanic's Tool.**
 .02 **Wood-working Power Machinery, (a) Saws, (b) Planers, (c) Stickers, (d) Sand-papering Machines, (e) Scraping Machines.**
 .03 **Kilns, Dryers.**
 .04 **Scaffolding, Ladders, Horses and Benches.**
- 693.1 **MATERIALS.**
 .11 **Lumber.**
 .111 **Timber, larger than 6"x6".**
 .112 **Common Lumber.**
 .112 (a) **Boards, Furring and Grounds.**
 .112 (b) **Piece Stuff, Joists and Scantling.**
 .112 (c) **Shingles.**
 .113 **Finish Lumber.**
 .113 (a) **Hardwood.**
 .113 (b) **Soft Wood.**
 .113 (c) **Flooring.**
 .114 **Mill Stock.**
 .115 **Veneers.**
 .12 **Glues.**
 .13 **Rough Hardware.**
 .131 (a) **Nails, (b) Spikes, (c) Brads, (d) Tacks, Etc.**
 .132 (a) **Bolts, (b) Rods, (c) Anchors and Ties, Etc.**
 .133 **Rivets.**
 .134 (a) **Washers, (b) Flitch Plates, (c) Splice Plates.**
 .135 **Mill Construction Hardware, (a) Stirrups, (b) Hanger, (c) Column Anchors, (d) Ties, (e) Box and Wall Anchors, (f) Bearing Plates, Etc.**

693		694	
.136	Double Hung Sash Hardware, (a) Pulleys, (b) Cords, (c) Chain, (d) Weights, (e) Spring Balances.	.1	MATERIALS USED IN THE METAL TRADES.
.137		.11	Iron Products.
.138		.111	Cast-Iron.
.14	Finish Hardware.	.112	Wrought Iron.
.141	Hanging Hardware, (a) Butts, (b) Hinges, (c) Pivots, Etc.	.113	Steel.
.142	Controlling Hardware, (a) Bumpers, (b) Strikes, (c) Holders, (d) Hooks, (e) Stays, (f) Adjusters, Etc.	.114	Alloys, (a) Copper Bearing Steel, (b) Nickel Steel, (c) Sheradized Steel.
.143	Fastening Hardware, (a) Old Fashion Latches, (b) Spring Latches, (c) Catches, (d) Fasts, (e) Thumb Bolts, (f) Locks, Etc.	.12	Copper.
.144	Trimming Hardware, (a) Pulls, (b) Knobs, (c) Spindles, (d) Roses, (e) Escutcheons.	.13	Brass.
.145	Protection Hardware, (a) Kick Plates, (b) Push Plates, (c) Direction Plates or Signs, (d) Push Bars, Etc.	.14	Bronze.
.146	Operating Hardware, (a) Closers and Checks, (b) Springs, (c) Weights and Pulleys, (d) Window Poles, Etc.	.15	Aluminum.
.147	Weathering Hardware, (a) Weather Strips, (b) Thresholds, (c) Special Drips, (d) Metal Astrigals, Etc.	.16	Miscellaneous Structural Metals.
.148	Automatic and Panic Hardware.	694.2	STRUCTURAL METAL CONSTRUCTION.
.149	Miscellaneous Hardware not otherwise classified, (a) Wardrobe Hardware, (b) Showcase Hardware.	.21	Fabrication.
693.2	ORDINARY CONSTRUCTION.	.211	Shop Drawings.
.21	Balloon Construction for Frame Buildings.	.22	Framing.
.22	Joist Construction for Masonry Buildings.	.221	Bases, Bearing Plates, Etc.
693.3	HEAVY TIMBER CONSTRUCTION.	.222	Columns and Struts.
.31	Heavy Post and Timber Construction for Frame Buildings.	.223	Caps, Connections, Gussets, Etc.
.32	Mill Construction for Masonry Buildings.	.224	Girders, Beams, Etc.
693.4	AUXILIARY WOOD CONSTRUCTION FOR FIREPROOF BUILDINGS.	.225	Suspenders, Tie-Rods, Chains, Etc.
.41	Centers, Forms, Protective Covering, Scaffolding, Etc.	.23	Preservatives.
.42	Grounds, Attachment Strips, Etc.	.231	Paint. (See 696.)
693.5	JOINERY AND MILL WORK.	.232	Galvanizing.
.51	Frames and Sash.	.233	Other Methods.
.511	Box Frames, Double Hung Sash.	694.3	MISCELLANEOUS METAL.
.512	Casement Frames, Sash Opening In.	.31	Fire Escapes.
.513	Casement Frames, Sash Opening Out.	.32	
.514	Frames for Sash Hinged at Bottom, Swinging In at Top.	.33	
.515	Frames for Sash Hinged at Top, Swinging In at Bottom.	694.4	HEAVY METAL DOORS, SHUTTERS, ETC.
.516	Frames for Sash Hinged at Top, Swinging Out at Bottom.	.41	Underwriters' Doors.
.517	Frames for Horizontal Pivoted Sash.	.42	Sidewalk Doors.
.518	Frames for Vertical Pivoted Sash.	.43	Shutters.
.52	Wood Interior Trim.	694.5	ORNAMENTAL METAL.
.53	Wood Floors.	.51	Fences.
.54	Blinds.	.52	Enclosures, Guards, Grills, Gates, Etc.
.55	Doors.	.53	Elevator Enclosures and Cages.
.551	Ordinary Panel Doors.	.54	Fireplace Trimming.
.552	Special Revolving Doors.	.541	Andirons.
.553	Folding, Accordion Doors.	.542	Grate Frames, Dampers, Grates, Etc.
.554	Rolling Doors.	694.6	SOLID METAL SASH.
.56	Screens.	694.7	VAULT DOORS, SAFES, VAULTS, ETC.
693.6	STAIR BUILDING.	.71	Vault Doors.
693.7	ORNAMENTAL JOINERY, CABINET WORK.	.72	Safes.
693.8	WOOD CARVING.	.73	Vaults and Bank Equipment.
.8	WOOD FURNITURE.	694.8	
.9	MISCELLANEOUS.	695	SHEET-METAL TRADES — (Employing Metal of No. 10 gauge or less).
694	HEAVY METAL TRADES — (Employing Metal heavier than No. 10 gauge).	695.0	TOOLS, UTENSILS AND APPARATUS (used by the Sheet-Metal Trades).
.0	TOOLS, UTENSILS, APPARATUS, ETC.	.01	Brakes, Shears, Mallets, Hammers, Etc.
.01	Job Machinery.	.02	Welding Machines.
.02	Job Tools, Hammers, Sledges, Punches, Tongs, Reamers, Riveters, Forges, Etc.	.03	Soldering Apparatus.
.03	Derricks, Cable, Hoisting Masonry.	.04	Plating Apparatus.
		695.1	SHEET-METAL MATERIALS.
		.11	Sheet Iron.
		.111	Tin or Tin Coated Sheet Iron.
		.112	Galvanized Iron.
		.12	Sheet Copper.
		.121	Planished Copper.
		.13	Zinc Sheet.
		.14	Brass Sheet.
		.15	Bronze Sheets.
		.16	Other Sheet Metals.
		.17	Solders, Fluxes, Etc.
		.18	Hardware.
		.181	Rivets and Bolts.
		.182	Nails, Tacks and Screws.
		.183	Incidental Hardware. (See 694.1.)
		.19	Miscellaneous.
		695.2	ORDINARY SHEET-METAL CONSTRUCTION.
		.21	Roofs.
		.211	Tin.
		.212	Galvanized Iron.
		.213	Copper.
		.22	Cornices, Etc.

695		696	
.23	Flashing, Gutters, Valleys, Down-Spouts and Conductor Heads.	.7	UPHOLSTERY.
.24	Sky-lights, Ventilator Heads, Etc.	.8	HANGINGS.
.25	Furnace Work, Casings, Ducts and Stacks, Etc.	.81	Ordinary Window Shades.
695.3	FIRE RESISTING DOORS AND WINDOWS.	696.82	Lace Curtains.
.31	Underwriters' Tin-Clad Doors.	.83	Draperies, Etc.
.32	Underwriters Sheet-Metal Sash.	.84	
.33	Rolling Steel Shutters and Doors.	696.9	GLAZING.
695.4	CEILING, STAMPED SHEET-METAL.	.91	Common Glazing.
695.5	DRAWN SHEET-METAL.	.92	Art Glass Glazing.
.51	Store Front Bars.	697	PIPE TRADES.
.52	Showcase Bars, Etc.	.0	TOOLS, UTENSILS AND APPARATUS.
695.6	TRIM AND DOORS OF SHEET METAL.	.01	Mechanic's Chest Tools, Furnaces, Etc.
695.7	FURNITURE OF SHEET METAL.	.02	Power Pipe Cutter, Benders, Dies, Etc.
695.8	UTENSILS OF SHEET METAL.	.03	Scaffolding Ladders, Etc.
696	BRUSH, BROOM AND SWAB- USING TRADES.	697.1	MATERIALS.
.0	BRUSH TRADE, TOOLS AND APPARATUS.	.11	Metals, (a) Wrought Iron, (b) Steel, (c) Lead, (d) Brass, (e) White Metal.
.01	Kettles, Buckets, Ladles, Swabs and Other Roofers' and Waterproofers' Tools.	.12	Pipe.
.02	Brushes, Cans, Knives, Etc.	.121	Wrought Iron, (a) Black, (b) Galvanized.
.03	Ladders, Scaffolding, Hoists, Etc.	.122	Steel, (a) Black, (b) Galvanized.
.04	Drop Cloths.	.123	Cast Iron.
.05	Grinders.	.124	Brass, Bronze and Copper.
696.1	BRUSH TRADE MATERIALS AND METHODS.	.125	White Metal.
.11	Roofing and Waterproofing Materials.	.126	Block Tin.
.111	Felt.	.127	Lead Lined Iron.
.112	Paper.	.128	Tin Lined Iron.
.113	Gravel, Slag, Crushed Stone, Paving Tile, Etc.	.129	Tile Pipe.
.12	Painters' Materials.	.13	Pipe Fittings.
.121	Binders, (a) Oil, (b) Casein.	.131	Screw Connections.
.122	Pigments, (a) White Lead, (b) Red Lead, (c) Zinc, (d) Graphite, (e) Whiting, (f) Lime, (g) Other Pigments.	.132	Flange Connections.
.123	Colors, (a) Vegetable, (b) Mineral.	.133	Union Connections.
.124	Solvents, (a) Turpentine, (b) Benzine, (c) Alcohol, (d) Other Solvents.	.134	Caulked Connections.
.125	Wood Finishing Materials, (a) Stains, (b) Fillers, (c) Shellacs, (d) Varnishes, (e) Enamels, (f) Waxes, (g) Other Materials.	.135	Valves, (a) Shut-off, (b) Gate, (c) Disk, (d) Other Valves.
.13	Water Paints.	.136	Pipe Hangers and Supports, Etc.
.131	Binder, (a) Casein, (b) Glue, (c) Other Binders.	.137	
.132	Pigments, (a) Lime, (b) China Clay, (c) Whiting.	.14	Tanks.
.133	Colors.	.141	Hot Water.
.14	Wall Papers.	.142	Cold Water.
.15	Textile Hanging.	.142	Cold Water, (a) Wood, (b) Metal.
.151	Fabrics.	.143	Oil Tanks.
.152	Hanging, Hardware Poles, Etc.	.144	Gas Tanks.
.16	Leather, (a) Genuine, (b) Imitation.	.15	Boiler.
.17	Upholstery, (a) Tacks, (b) Feathers, (c) Hair, (d) Moss, (e) Ticking, (f) Cord, (g) Other Materials.	.151	Steel Water Tube.
.18	Glazing Material.	.152	Steel Flue Tube.
.181	Glass, (a) Common Glass, (b) Plate Glass, (c) Ornamental Glass, (d) Prismatic Glass, (e) Colored Glass.	.153	Cast Iron Sectional.
.182	Putties.	.16	Stoves.
.183	Tacks.	.161	Coal.
.184	Leading Bars, (a) Lead, (b) Zinc, (c) Copper, (d) Ventilators.	.162	Gas.
.19	Other Materials.	.163	Oil.
696.2	WATER-PROOFING.	.17	Furnaces, Grates and Stokers.
.21	Brushed on Construction.	.18	Brass Goods.
.22	Membrane.	.19	Pottery.
696.3	COMPOSITION ROOFING.	697.2	SEWERAGE. (See 692 for Masonry Sewers.)
.31	Tar and Gravel Roofing.	.3	PLUMBING TRADE.
.32	Asphaltum Composition Roofing.	697.1	Plumbing Fixtures.
.33	Promenade Deck Roofing.	.311	Roughing-in, (a) Durham System, (b) Cast-Iron Caulked Joint System.
696.4	PAINTING WORK.	.312	Water Supply, (a) Pumps, (b) Tanks, (c) Hose and Fire Apparatus, (d) Fitters, (e) Sterilizers, (f) Ice Machinery, (g) Stills, Etc. (h) Domestic Heater.
.5	WOOD FINISHING WORK.	.313	Garbage Disposal.
.6	GENERAL DECORATIONS.	.314	Fixtures for Plumbing, (a) Floor Drains, (b) Cesspools, (c) Sinks, (d) Slop Sinks, (e) Laundry Wash Trays, (f) Lavatories, (g) Bathtubs, (h) Showers, (i) Water Closets, (j) Urinals, (k) Bath and Toilet Room Trimmings, Paper-Holders, Towel Racks, Tumbler Holders, Soap Dishes, Etc.
.61	Ordinary Water Color Tinting.	697.4	GAS FITTING.
.62	Fresco Painting, Stenciling, Etc.	.41	Meters.
.63	Mural Decorations.	.42	Fixtures.
		697.5	MECHANICAL CLEANING.
		.6	SPRINKLER FITTING.
		.60	Erecting Apparatus.
		.61	Sprinkler-fitting Devices.
		.7	HEATING, STEAM AND HOT WATER AND VENTILATION.
		.71	One-Pipe Gravity.
		.72	Two-Pipe Gravity.

697				705	PERIODICALS. MAGAZINES. RE-
.73	Vapor Two-Pipe. (Systems ar-			706	VIEWS.
.74	Vacuum. (Systems arranged alpa-			707	SOCIETIES. TRANSACTIONS. RE-
.75	betically.)			708	PORTS, ETC.
.76	Radiation, (a) Direct, (b) Direct-In-			709	EDUCATION. STUDY AND TEACH-
.77	direct, (d) Indirect.				ING OF ART.
.78	Boiler Trimmings.				ART GALLERIES AND MUSEUMS.
697.8	Automatic Regulators.				HISTORY OF ART IN GENERAL
.9	Mechanical Ventilation.				Divided like 930-999.
698	STEAM-POWER WORK.			710	LANDSCAPE GARDENING.
	OTHER PIPE TRADES.			711	PUBLIC PARKS.
				712	PRIVATE GROUNDS. LAWNS.
				713	WALKS. DRIVES. BRIDGES.
				714	WATER. FOUNTAINS. LAKES.
				715	TREES. HEDGES. SHRUBS.
					See also 634.9, Forestry; 582, Bot-
					any.
				716	PLANTS. FLOWERS.
					.1, Plants; .2, Flowers; .3, Conserva-
					tories; .4, Window gardens; .5, Fern-
					eries.
				717	ARBORS. SEATS. OUTLOOKS.
				718	MONUMENTS. MAUSOLEUMS.
				719	CEMETERIES. See also 393.1, Earth
					burial; 614.61, Public health.
				720	ARCHITECTURE.
				.1	Theories, Esthetics, Architectonics;
					.2, Compends, Manuals; .3, Diction-
					aries, Cyclopedias; .4, Essays, Lec-
					tures; .5, Periodicals; .6, Societies;
					.7, Education, Study, Training,
					Schools of Architecture; .8, Poly-
					graphy, Collections; .9, General His-
					tory of Architecture, divided geogra-
					ically like 940-999.
				721	ARCHITECTURAL CONSTRU-
					CTION.
				.1	Foundations. See Bridge Engineer-
					ing, 624.1, Foundations.
				.2	Walls, Partitions, etc.
				.3	Piers. Columns.
				.4	Arched Constructions.
				721.5	Roofs. See 695, Roof Coverings;
				.6	Floors and Flooring. See 620.8,
				.7	Ceilings.
				.8	Doors. Windows.
				.9	Iron and Composite Structures.
				722	ANCIENT ARCHITECTURE.
					Include under this general classifica-
					tion all architecture from the be-
					ginning up to about A. D. 200 to
					300.
				.00	Prehistoric Architecture.
				.1	Egyptian or Nile Valley. (Period
					4000 B. C. to about 527 B. C.
				.11	Old and Middle Empire. (4000-
					2000.)
				.12	Shepherd Kings (2000-1600 ?)
				.13	Theban New Empire (1600-1250).
				.14	
				.2	Mesopotamian Architecture. Period
					3800 ? to about 536 B. C.
				.21	Chaldaeian (3800 ? to 1500 ? B. C.).
				.22	Assyrian (1500 ? to 1020 ? B. C.).
				.23	Babylonian (1020 ? to 536 B. C.).
				.24	Persian-Median (536 B. C. to 293
					A. D.).
				.241	First Empire founded by Cyrus
					(536-334).
				.242	Sassanian Period (334 B. C. to A. D.
					293).
				.3	East Asian Architecture. Little is
					known of Chinese, Korean, Japan-
					ese, Indian and Philippine Archi-
					tecture of the ancient period and
					dates can hardly be approximated.
				.4	Pelagic Architecture. North and
					east Mediterranean, including the
				.41	islands of that sea.
					.42, Pre-Mycenaean, .43 My-
					cenaean, .44, Post-Mycenaean, .45
					Homeric and .46 Early Hittite.
				.5	Grecian or Hellenic Period (1500 ?
					to 100 B. C.).
				.51	Heroic Period (1500 ? to 776).
				.52	Hellenic proper (776 ? to 100), .521
					Doric, no other to 430 B. C.;
					.522, Ionic (430 to 330 ? B. C.); .523,
					Corinthian; only a few examples.
700	FINE ARTS.				
701	PHILOSOPHY. THEORIES.				
702	UTILITY. AESTHETICS.				
703	COMPENDS. OUTLINES.				
704	DICTIONARIES. CYCLOPEDIAS.				
	ESSAYS. LECTURES. ADDRESSES.				

- .6 **Roman**, Period 753 ? B. C. to 323 A. D.
- .61 Regal (753 ? B. C. to 510 ? B. C.).
- .62 Republic (510 ? B. C. to 27 B. C.).
- .63 **Imperial** (27 B. C. to 323 A. D.).
- .631, Tuscan; .632, Doric; .633, Ionic; .634, Corinthian; .635, Composite.
- 723 **MEDIAEVAL ARCHITECTURE.**
The Architecture of the Middle Ages is generally understood to extend over a period from 300 A. D. to about 1450 A. D.
- .1 **Byzantine or Early-Christian.**
Developed under the Roman Emperor Constantine, at Constantinople, and to a more or less extent in all countries bordering the Mediterranean.
- .11 Basilican Type, derived from the Roman business exchange, adopted more generally as the early Christian church in Western and Northern Europe.
- .12 Baptistry Type, derived from the Roman Bath, adopted more generally in Eastern Europe and Western Asia and North Africa for early Christian Church, motif for Mohammedan Mosque.
- .121, Early Christian subdivided according to political divisions of the time.
- .122, Mohammedan-Moorish effected with Persian influence later becomes a distinct style.
- .2 **PERSIAN MEDIAEVAL** (293 A. D. to 1499). Developed under more or less Roman influence up to Mohammedan conquest; after that gradually developed the Mohammedan Style.
- .21 Sassanian (293 A. D. to 652 A. D.).
- .22 Mohammedan (652 to 1499 A. D.).
- .3 **Indian.**
- .31 Buddhist.
- .32 Jain.
- .33 Brahman.
- .34 Indo-Moslem.
- .4 **Chinese, Korean and Japanese.**
- .5 Mohammedan Style.
- .51 Moorish, Turkish, Persian, Indian.
- .6 **Romanesque.** The Architecture of Europe between the Roman-Byzantine period and the Gothic (Period about 900 A. D. to about 1100 A. D.).
- .61, Austrian; .62, British Isles; .63, French and Belgian; .64, German; .65, Holland and Switzerland; .66, Italian; .67, Scandinavian; .68, Spanish; .69, Unclassified.
- .7 **Gothic.** The Architecture of Europe between the Romanesque period and the Neo-Classic (Period about 1150 A. D. to 1450 A. D., traces in Spain and Italy as far back as 475 A. D.). The name means Architecture of the Goths.
- .71 Austrian; .72, British Isles; .63, French and Belgian; .64, German; .65, Holland and Switzerland; .66, Italian; .67, Scandinavian; .68, Spanish and Portuguese; .69, Unclassified.
724. **MODERN.**
- .1 Renaissance;
- .2 Classical Revival. Grecian.
- .3 Gothic Revival.
- .4 Tudor Gothic Revival.
- .5 Queen Anne Revival.
- 724.6 **Neo Grec.**
- .7 Half-Timber Swiss.
- .8 Romanesque Revival.
- .9 Other Recent Styles.
- 725 **PUBLIC BUILDINGS.**
- .1 Administrative. Governmental.
- .11 Capitols. Houses of Parliament.
- .12 Ministries of War, State, etc.
- .13 City and Town Halls. Bureaus.
- .14 Public Offices. City Plans.
- .14 Custom Houses. Bonded Warehouses. Excise Offices.

- .15 Court Houses. Record Offices.
- .16 Post Offices, General and Special.
- .17 Official Residences. Palaces of Rulers.
- .18 Barracks. Armories. Police Stations.
- .19 Engine Houses. Fire Alarm Stations.
- .2 **Business and Commercial.**
- .21 Stores, Wholesale and Retail.
- .22 Mixed Store, Office, and Apartment Buildings.
- .23 Office Buildings. Telegraph. Insurance. Loft.
- .24 Banks. Safe Deposit. Savings.
- .25 Exchanges. Boards of Trade.
- .26 Markets.
- .27 Cattle Markets. Stock Yards.
- .28 Abattoirs.
- .29 Other Business Buildings.
- .3 **Transportation and Storage.**
- .31 Railway Passenger Stations.
- .32 Railway Freight Houses.
- .33 Railway Shops, Round Houses, Car Houses, Tanks, Stores.
- .34 Dock Buildings. Wharf Boats and Houses.
- .35 1, Warehouses; 2, Cold Storage; 3, Safe Deposit Storage.
- .36 Elevators, Grain.
- .37
- .38
- .39 Other.
- .4 **Manufactories.**
- .41 Textile Factories or Mills. Wool, Cotton, Silk.
- .42 Breweries. Malteries. Distilleries.
- .43 Foundries. Machine Shops. Iron and Steel Works.
- .44 Wood-working Mills. Furniture Factories.
- .45 Carriage and Car Factories.
- .46 Paper Mills.
- .47 Mills for Flour, Meal, Feed, etc.
- .48 Pottery, Glass, Terra Cotta, Brick Works.
- .49 Other Manufactories.
- 725.5 **Hospitals and Asylums.** See also 725.6. Reformatories.
- .51 Sick and Wounded. Eye and Ear. Incurables. Lying-in.
- .52 Insane.
- .53 Idiotic. Feeble-minded.
- .54 Blind. Deaf and Dumb.
- .55 Paupers. Almshouses.
- .56 Aged.
- .57 Children. Orphans.
- .58 Foundling.
- .59 Soldiers' Homes.
- 725.6 **Prisons and Reformatories.**
- .61 State Prisons. Penitentiaries.
- .62 Jails. Cell Houses.
- .63 Reformatories for Adults. Houses of Correction.
- .64 Reform Schools.
- .65 Inebriate Asylums.
- 725.7 **Refreshment. Baths. Parks.**
- .71 Cafés. Restaurants.
- .72 Saloons.
- .73 Baths: Warm, Medicated, Turkish, Russian.
- .74 Swimming Baths.
- .75 Buildings for Watering Places, Spas, etc.
- .76 Buildings for Parks and Streets, Public Comfort Stations.
- 725.8 **Recreation.**
- .81 Music Halls Auditoriums.
- .82 Theatres. Opera Houses.
- .83 Halls for Lectures, Readings, etc.
- .84 Bowling Alleys. Billiard Saloons.
- .85 Gymnasiums. Turn Halls.
- .86 Skating Rinks. Bicycle Rinks.
- .87 Boat Houses. Bath Houses.
- .88 Riding Halls and Schools.
- .89 Shooting Galleries.
- 725.9 **Other Public Buildings.**
- .91 Exhibition Halls.

- 725 .92 Temporary Halls. Tabernacles. Wigwams.
 .93 Workingmen's Clubs and Institutes.
 .94 Town Squares.
 .95 Summer Recuperating Camps.
- 726 **ECCLESIASTICAL AND RELIGIOUS.**
 .1 Temples.
 .2 Mosques.
 .3 Synagogues.
 .4 Chapels. Sunday-school Buildings.
 .5 Churches.
 .51 Frame.
 .52 Brick or Stone.
 .521 Small Aud., seating less than 600.
 .522 Large Aud., seating more than 600.
 .6 Cathedrals.
 .7 Monasteries. Convents. Abbeys.
 .8 Mortuary. Cemetery Chapels. Receiving Vaults. Tombs.
 .9 Other. Y. M. C. A., etc.
- 727 **EDUCATIONAL AND SCIENTIFIC.**
 .1 Schools.
 .11 Ward and Grammar.
 .12 High Schools.
 Study and Recitation Rooms. Not including dormitory or boarding.
 .2 Academies. Seminaries. Boarding Schools.
 .3 Colleges. Universities.
 .4 Professional and Technical Schools. Law, Theology, etc.
 .5 Laboratories: Physical, Chemical. See 542.1, Biological, etc. Zoological and Botanic Gardens. See also 590.7 and 580.7.
 .6 .1, Museums. .2, Herbariums. See 580.7.
 .7 .1, Art Galleries. .2, Studios.
 .8 Libraries. See 022, Library Buildings.
 .9 Other. Learned Societies, etc.
- 728 **RESIDENCES.**
 .1 Tenement Houses.
 .11 City Homes of Poor.
 .12 Country Homes of Poor.
 .13 Cités Ouvrières.
- 728.2 **Collective Dwellings.**
 .21 Flats; one family to the floor.
 .211 Small Flats less than 8 rooms.
 .212 Large Flats, 8 rooms or more.
 .22 Apartment Houses; more than one family to floor.
 .221 Five Suites or Less.
 .222 Six Suites or More.
 .2221 Elevator Service.
 .2222 No Elevator Service.
- 728.3 **City Houses. Mansions. Palaces.**
 .31 Between party-walls. Stone.
 .32 Between party-walls. Brick.
 .33 Between party-walls. Partly wood.
 .34 Semi-detached, including end houses in city blocks. Stone.
 .35 Semi-detached, including end houses in city blocks. Brick.
 .36 Semi-detached, including end houses in city blocks. Partly wood.
 .37 Detached. Stone.
 .38 Detached. Brick.
 .39 Detached. Partly wood.
- 728.4 **Club Houses. Buildings for Secret Societies.**
 .5 Hotels.
 .51 City Hotels.
 .52 Summer Resorts.
 .53 Country Inns.
- 728.6 **Village and Country Homes.**
 .61 Village Dwellings. On small lots.
 .62 Stone.
 .63 Brick.
 .64 Concrete or stucco.
 .65 Part masonry, part wood.
 .66 All wood, 1, less than 7 rooms, 2, 7-12 rm; 3, 13 rm or over.
 .67 Farm Houses.
- 728 .68 Laborers' Cottages. 1. Frame; 2, Masonry.
- 728.7 **Seaside and Mountain Cottages. Chalets.**
- 728.8 **Country Seats.**
 .81 Castles.
 .82 Chateaux.
 .83 Manor Houses.
 .84 Villas
 .85 Log Houses.
 .86 Bungalows.
- 728.9 **Out-Buildings.**
 .91 Porters' Lodges.
 .92 Servants' Quarters.
 .93 Kitchens and Laundries.
 .94 .1, Stables. .2, Carriage Houses. .3, Garages.
 .95 Barns, Granaries.
 .96 Dairies.
 .97 Ice Houses.
 .98 Conservatories. Green Houses. Graperies.
 .99 Other.
- 729 **ARCHITECTURAL DESIGN AND DECORATION.**
 .1 The Elevation.
 .11 Composition; .12, Distribution; .13, Proportion; .14, Light and Shade; .15, Perspective effect; .16, .17, .18, .19.
 For projection of shadows and graphics of light and shadow see 515.63 and 515.7.
 .2 The Plan.
 .21 Elements required; .22, Distribution; .23, Proportion; .24, .25, .26, .27, .28, .29.
 .3 Elementary Forms. For construction of these forms see 721.
 .31 Walls. Mouldings. Cornices. .32, Piers, Columns Pilasters, Pedestals and the Orders. Colonnades. .33, Arches and Arcades. .34, Vaults and Domes. .35, Roof. Spires. Dormers. .36, Towers. .37, Gables and Pediments. .38, Doors and Windows. Bays. Orrels. .39, Stairs and Balustrades. See also 515.83, Stereotomy; 604.8, Building.
 .4 Painted Decoration.
 729.5 **Decoration in Relief.**
 .6 Incrustation and Veneering.
 .7 Mosaic and Marble.
 .71 Mosaic Ceilings; .72, Mosaic Walls; .73, Mosaic Floors; .74, Other Mosaic designs; .75, .76, .77, .78, .79.
 .8 Stained Glass Design. For technical processes see 666.1; for history see 748.
 .9 Architectural Accessories and Fixed Furniture.
 .91 Altars, Pulpits, Tribunes, Dais Thrones (Ecclesiastical).
 729.92 **Seating for Public Buildings.**
 .921 Benches; 2, Settees; 3, Portable Chairs and Opera Chairs.
 .93 Domestic Chairs, Tables, Couches, Stools, Beds, etc.
 .94 Buffets.
 .95 Mantels. Overmantels. Andirons.
 .96 Steel Furniture.
 .97 Window Shades.
 .98 .1, Organs. .2, Pianos.
 .99 Lighting Fixtures.
- 730 **SCULPTURE.**
- 731 **MATERIALS AND METHODS.**
- 732 **ANCIENT.**
- 733 **GREEK AND ROMAN.**
- 734 **MEDIEVAL.**
- 735 **MODERN.**
- 736 **CARVING. SEALS. DIES. GEMS. CAMEOS.**
- 737 **NUMISMATICS. COINS. MEDALS.**
- 738 **POTTERY. PORCELAIN.**
- 739 **BRONZES. BRASSES. BRIC-A-BRAC.**

CLASSIFIED LIST OF ADVERTISERS

Advertisers are classified with a view to furnish Architects and others a ready reference list of houses engaged in the Building Business. Besides the Index to Advertisements on page 572, the number of the pages on which the Advertisements appear follows directly after each name Classified in this list. It is requested that those using it will kindly mention this book in their correspondence.

AIR COMPRESSORS.

Am. Steam Pump Co., 53 W. Jackson 448
Gallagher & Speck, 215 W. Congress St. 436

AIR WASHERS AND PURIFIERS.

Gustafson, K. A., 2114 N. Springfield 444
Haines Co., 1933 W. Lake St. 444
Mellish, Hayward Co., 213 W. Austin Av. 446
Monarch Vent. Co., 1338 S. Sedgwick St. 446
Narowetz Heat. & Vent. Co., 1711 Park Av 444
Webster, Warren & Co., 53 W. Jackson 442
Wittenmeier Mch'y. Co., 850 N. Spaulding 120

ANGLES AND CHANNELS.

(See Architectural Iron Work)

ARCHITECTURAL IRON WORK.

American Bridge Co., 208 S. La Salle 354
Badger Wire & Iron Co., Milwaukee, Wis. 390
Bolter's, A., Sons, 2361 Ward St. 376
Butler St. Fdry. & Iron Co., 3424 Normal 384
Duffin Iron Co., 4837 S. Kedzie Av. 372
Federal Iron Wks., 30 N. La Salle St. 380
Guaranty Iron & Steel Co., 2847 W. Lake 382
Halsted, Joseph, Co., 1233 W. Randolph 380
Hanke Iron & Wire Wks., 840 N. Albany 380
Holmes, Pyott, & Co., 159 N. Jefferson 376
Johnson-Meier Co., 155 Wendell St. 360
Kenwood Bridge Co., 1st Nat. Bk. Bldg. 376
Manton & Smith Co., 1709 W. Austin Av. 382
Reder Fdry. Co., 3336 S. Oakley Av. 380
Reuter Brothers, 5814 Wood St. 384
Smith, F. P., W. & I. Wks., 2346 Clybourn 384
Sullivan-Korber Co., 2437 W. 21st Pl. 382
Union Fdry. Wks., 38 S. Dearborn St. 372
Vierling Steel Wks., 313 W. 23rd St. 384
Western Iron Constr. Co., 4906 N. Clark 390
Woodbridge Orntl. Iron Co., 1519 Altgeld 358

ARCHITECTURAL SCULPTORS.

Architectural Dec. Co., 1600 S. Jefferson 508
Dux, Joseph, 2112 W. Van Buren St. 508

ARCHITECTS' SUPPLIES.

Am. Blue Print Paper Co., 445 Plymouth 508
Crofoot, Nielsen & Co., 172 W. Wash. 508

ASBESTOS PRODUCTS.

Cent. Asbestos & Mag. Co., 214 W. Grand 342
Johns-Manville Co., 18th & Mich. 342
Krez, Paul J., Co., 444 N. La Salle St. 342
Standard Asbestos Mfg. Co., 816 W. Lake 342
Watson, H. F., Co., 5331 S. Western Av. 342

ASPHALT SHINGLES.

(See Shingles, Fireproof)

AUDITORIUM CHAIRS.

Rowles, E. W. A., Co., 2345 S. La Salle 576

AWNINGS—BRONZE, WOOD AND IRON.

Dodge, H. B., & Co., 332 S. Michigan Av. 262

AWNINGS—CANVAS.

Walger Awning Co., 561 W. Monroe St. 4

BANK AND OFFICE FIXTURES.

Anderson & Lind Mfg. Co., 2127 Iowa St. 98
Baumann, F. O., Mfg. Co., 1501 Smith 262
Brunswick-Balke-Collender Co., 623 S. Wabash Av. 460

BANKERS.

Corn Exc. Nat'l Bank, 134 S. La Salle 52
Greenebaum Sons Bank & Trust Co., 9 S. La Salle St. 302

BAR SPACERS AND BENDERS

Calumet Steel Co., 208 S. La Salle St. 378
Dean, Olney, J., & Co., 179 W. Wash. 388
Kalman, Paul J., Co., 22 W. Monroe St. 356
Scully Steel & Iron Co., 2364 S. Ashland 370
Universal Form Clamp Co., 14 N. May St. 368

BARS—IRON AND STEEL.

American Bridge Co., 208 S. La Salle 354
Calumet Steel Co., 208 S. La Salle St. 378
Castle, A. M. & Co., 715 N. Morgan St. 370
Dean, Olney, J., & Co., 179 W. Wash. 388
Kalman, Paul J. Co., 22 W. Monroe St. 356
Scully Steel & Iron Co., 2364 S. Ashland 370

BATH ROOM FIXTURES.

(See Plumbing Supplies)

BATH TUBS.

(See Plumbing Supplies)

BEAMS AND COLUMNS—IRON AND STEEL.

(See Architectural Iron Work)

BEDS—DISAPPEARING AND WALL.

Pick, Albert & Co., 212 W. Randolph 80-82

BELT AND HAND POWER ELEVATORS.

(See Elevators—Passenger and Freight)

BILLIARD ROOM SUPPLIES.

Brunswick-Balke-Collender Co., 623 S. Wabash Av. 460
Pick, Albert & Co., 212 W. Randolph 80-82

BLACKBOARDS.

Rowles, E. W. A., Co., 2345 S. La Salle 576

BLOWER REGULATORS.

Davis, G. M. Reg. Co., 428 Milwaukee 442

BLUE AND BLACK PRINTING.

Am. Blue Print Paper Co., 445 Plymouth 508
Crofoot, Nielsen & Co., 172 W. Wash. 508

BOILERS—STEAM AND HOT WATER.

Ill. Malleable Iron Co., 1801 Diversey 426
Kellogg Mackay Co., 419 W. 18th St. 404
Kewanee Boiler Co., 228 W. Washington 406
Mueller, L. J. Furnace Co., 60 E. Lake 424
Utica Heater Co., 218 W. Kinzie St. 410
Weir & Craig Co., 6316 Wentworth Av. 420

BONDS.

Builders & Mfrs. Mutual Casualty Co., 133 W. Washington St. 54
Sherman & Ellis, Inc., 11 S. La Salle St. 264

BOWLING ALLEYS.

(See Billiard Room Supplies)

BRASS AND IRON—ARCHITECTURAL.

Badger Wire & Iron Co., Mil. Wis. 390
Federal Iron Wks., 30 N. La Salle St. 380
Guaranty Iron & Steel Co., 2847 W. Lake 382
Halsted, Joseph, Co., 1233 W. Randolph 380
Hanke Iron & Wire Wks., 840 N. Albany 380
Johnson-Meier Co., 155 Wendell St. 360
Manton & Smith Co., 1709 W. Austin Av. 382
Newman Mfg. Co., Cincinnati, O. 390
Reuter Brothers, 5814 Wood St. 384
Smith, F. P., W. & I. Wks., 2346 Clybourn 384
Sullivan-Korber Co., 2437 W. 21st Pl. 382
Western Iron Constr. Co., 4906 N. Clark 390
Woodbridge Ornl. Iron Co., 1519 Altgeld 358

BRICK—COMMON—SEWER

Ill. Brick Co., 111 W. Washington St. 402
Carey Brick Co., 133 W. Washington 402
Western Brick Co., Danville, Ill. 392

BRICK—FACED.

Consumers Co., 111 W. Washington 114
Garden City Sand Co., 133 W. Wash. 394
Western Brick Co., Danville, Ill. 392

BRICK—FIRE.

Consumers Co., 111 W. Washington 114
Dee, Wm. E. Co., 30 N. La Salle St. 394
Garden City Sand Co., 133 W. Wash. 394
Ill. Fire-Proof Constr. Co., 209 S. La Salle St. 400
McCarthy, W. H., 133 W. Washington 394

Nat. Fire Proofing Co., 2610 Shields Av. 400
 Rosing, Astrid S., 111 W. Monroe St. 116
 Western Brick Co., Danville, Ill. 392

BRICK-PAVING.

Garden City-Sand Co., 133 W. Wash. 394
 Western Brick Co., Danville, Ill. 392

BRONZE WORK.

(See Brass and Iron—Architectural)

BRIDGES AND ROOFS.

American Bridge Co., 208 S. La Salle 354
 Kenwood Bridge Co., 1st Nat. Bk. Bldg. 376
 Morava Constr. Co., 122 S. Michigan 376

BUILDERS HARDWARE.

Lawson Mfg. Co., 228 W. Superior St. 64
 Midwest Hardware Co., 56 W. Randolph 81
 Wolff, Geo. & Co., 190 N. State St. 258

BUILDING LOANS.

(See Real Estate Loans)

BUILDING MATERIALS.

Brownell Improv. Co., 133 W. Wash. 394
 Consumers Co., 111 W. Washington 114
 Dee, Wm. E. Co., 30 N. La Salle St. 394
 Garden City Sand Co., 133 W. Wash. 394
 Mears-Slayton Bldg. Mat. Co., Clark & Howard Av. 112
 Rosing, Astrid S., 111 W. Monroe St. 116

BUILDING PAPERS.

Barrett Co., 10 S. La Salle St. 22
 Bird & Son, 1472 W. 76th St. 26
 Cabot, Samuel, 24 W. Kinzie St. 340
 Cent. Asbestos & Mag. Co., 214 W. Grand 342
 Johns-Manville Co., 18th & Mich. 8
 Krez, Paul J., Co., 444 N. La Salle St. 342
 Lehon Co., 44th & Oakley Ave. 66
 Standard Asbestos Mfg. Co., 816 W. Lake 342
 Union Insul. & Constr. Co., 20 W. Jackson 40
 Watson, H. F., Co., 5331 S. Western Av. 342

BUILDING RAISERS AND MOVERS.

Friedstedt, L. P. Co., Tribune Bldg. 294

BUMPING POSTS.

Mechanical Mfg. Co., Loomis & Pershing Rd. 60

CABINET WORK.

(See Interior Finish)

CAFETERIA FIXTURES—METAL.

Newman Mfg. Co., Cincinnati, O. 390
 Pick Albert & Co., 212 W. Randolph St. 80-82

CALCIMINE.

Moore, Benj. & Co., 415 N. Green St. 490
 Nelson, P. W., Inc., 2834 S. Loomis St. 490

CANOPIES—IRON & BRONZE.

Badger Wire & Iron Co., Mil. Wis. 390
 Bolter's A., Sons, 2301 Ward St. 376
 Duffin Iron Co., 4837 S. Kedzie Av. 372
 Federal Iron Wks., 30 N. La Salle St. 380
 Guaranty Iron & Steel Co., 2847 W. Lake 382
 Halsted, Joseph, Co., 1233 W. Randolph 380
 Hanke Iron & Wire Wks., 840 N. Albany 380
 Holmes, Pyott & Co., 159 N. Jefferson 376
 Johnson-Meier Co., 155 Wendell St. 360
 Kenwood Bridge Co., 1st Nat. Bk. Bldg. 376
 Mantion & Smith Co., 1709 W. Austin Av. 382
 Reuter Brothers, 5814 Wood St. 384
 Smith, F. P. W. & I. Wks., 2346 Clybourn 384
 Sullivan-Korber Co., 2437 W. 21st Pl. 382
 Union Fdry. Wks., 38 S. Dearborn St. 372
 Vierling Steel Wks., 23d & Stewart 384
 Western Iron Constr. Co., 4906 N. Clark 390
 Woodbridge Orntl. Iron Co., 1519 Altgeld 358

CARPENTER CONTRACTORS.

Anderson, A. & E. Co., 19 S. La Salle 278
 Anderson, Edward A. Co., 8 E. Huron St. 298
 Appel, Henry L. Co., 931 W. North Av. 290
 Archibald, E. L. Co., 111 W. Washington 280
 Ardmore Const. Co., 186 N. La Salle 284
 Barnard, H. B., 140 S. Dearborn St. 276
 Barrett Constr. Co., 77 E. Washington 300
 Brundage, Avery, 110 S. Dearborn St. 138
 B. W. Constr. Co., 10 S. La Salle St. 274
 Cadenhead Co., 8 E. Huron St. 298
 Dahl-Stedman Co., 11 S. La Salle St. 112
 Ericsson, Henry Co., 139 N. Clark St. 286
 Griffiths, John & Son Co., 112 W. Adams 124
 Hanson Bros. Co., 127 N. Dearborn St. 282

Jones Constr. Co., 1748 W. Madison St. 298
 Lanquist & Hilsley Co., 1100 N. Clark St. 132
 Lund A., Co., 19 S. La Salle St. 136
 Lynch, Austin, J. Co., 111 W. Monroe St. 296
 Mavor, Wm. Co., 7 S. Dearborn St. 296
 McKeown Bros. Co., 112 W. Adams St. 280
 McLennan Constr. Co., 3105 Calumet Av. 272
 Menke, Henry Co., 2128 W. Lake St. 284
 Meyne, Gerhardt F., 127 N. Dearborn St. 300
 Morrice, Wm. Co., 17 N. La Salle St. 300
 Moses, C. A. Constr. Co., 133 W. Wash. 278
 Mueller Constr. Co., 179 W. Wash. 134
 Mutual Constr. Co., 2532 Warren Ave. 300
 Nielsen, S. N. & Co., 3059 Augusta St. 282
 Olson, Peter, Co., 19 S. La Salle St. 276
 Rasmussen, C., 154 W. Randolph St. 292
 Regnell, B. J. Co., 19 S. La Salle St. 296
 Rosenthal-Cornell, O. W. Co., 80 E. Jack. 274
 Solomon-Waterton Co., 35 S. Dearborn 292
 Samuelson, A. J., 189 W. Madison St. 286
 Scharmer Constr. Co., 139 N. Clark St. 270
 Shelden, James & Co., 106 N. La Salle 272
 Snyder, J. W. Co., 122 S. Michigan Av. 126
 Sollitt, Ralph & Sons Constr. Co., 30 N. La Salle St. 270
 Sollitt, Sumner Co., 225 N. Michigan 298
 Strandberg, E. P. Co., 111 W. Washington 288
 Thielberg, A. C., 154 W. Randolph St. 296
 Thompson-Starrett Co., 175 W. Jackson 120
 Thomson, Geo. & Son Co., 30 N. La Salle 290
 Wells Bros. Const. Co., 53 W. Jackson Bl. 128
 Wilson, R. F. & Co., 1851 Elston Av. 122

CARPETS AND RUGS.

Pick, Albert & Co., 212 W. Randolph 80-82

CARVING.

Dux, Joseph, 2112 W. Van Buren St. 508

CASTINGS—GENERAL.

(See Foundries)

CEMENT.

Consumers Co., 111 W. Washington 114
 Garden City Sand Co., 133 W. Wash. 394
 Rosing, Astrid S., 111 W. Monroe St. 116
 Sandusky Cement Co., Cleveland, O. 46
 Universal Portland Cement Co., 208 S. La Salle St. 386

CEMENT COATING.

Advance Waterproof Cement Co., 15 E. Van Buren St. 402
 Cement Gun Constr. Co., 537 S. Dearborn 512
 Garden City Sand Co., 133 W. Wash. 394
 Semet Solvay Co., 332 S. Michigan Av. 490
 Vitri-fyx Co., 2526 W. Congress St. 350

CEMENT—MANUFACTURERS.

Sandusky Cement Co., Cleveland, O. 46
 Universal Portland Cement Co., 208 S. La Salle St. 386

CEMENT TESTING.

Hunt, Robt. W. & Co., Ins. Exc. Bldg. 402

CEMENT—REGROUND PORTLAND.

Advance Waterproof Cement Co., 15 E. Van Buren St. 402

CHAIRS—SCHOOL-AUDITORIUM-OPERA.

Rowles, E. W. A. Co., 2345 S. La Salle 576

CHANDELIERS.

(See Lighting Fixtures)

CHEMISTS.

Hunt, Robt. W. & Co., Ins. Exc. Bldg. 402

CHIMNEY CONSTRUCTION.

Am. Chimney Constr. Co., 118 N. La Salle 392
 Heine Chimney Co., 123 W. Madison 392

CLOSET SEATS.

Brunswick-Balke-Collender Co., 623 S. Wabash Av. 460

CLOTHES DRYERS.

Am. Laundry Mch. Co., 208 W. Monroe 344
 Troy Laundry Mch. Co., 23d & La Salle 344

COAL AND ASH HANDLING MACHINERY.

Olson, Samuel & Co., 2418 Bloomingdale 14
 Weller Mfg. Co., 1856 N. Kostner Av. 86

COAL TAR PRODUCTS.

Barrett Co., 10 S. La Salle St. 22
 Am. Tar Products Co., 208 S. La Salle 268

COLD STORAGE DOORS.

Matot, D. A., 1538 Montana St. 266

COLD STORAGE INSULATION.

Matot, D. A., 1538 Montana St. 266

Mechanical Mfg. Co., Loomis & Pershing 66

Rd. 66

Union Insul. & Constr. Co., 20 W. Jackson 68

United Cork Companies, 110 S. Dearborn 68

COLUMN CLAMPS.

Dean, Olney, J. & Co., 179 W. Wash. 388

Universal Form Clamp Co., 14 N. May St. 368

COLUMNS—WOOD.

Hartmann-Sanders Co., 2155 Elston Av. 344

COMPOSITION FOR EXTERIOR AND INTERIOR—ORNAMENTAL.

Architectural Dec. Co., 1600 S. Jefferson 508

Lux, Joseph, 2112 W. Van Buren St. 508

CONCRETE CONSTRUCTION—FLAT SLAB.

Barton Spider-Web Sys., 3426 S. Kedzie 366

CONCRETE—ENAMELS.

Advance Waterproof Cement Co., 15 E. 402

Van Buren St. 402

Vitrifyx Co., 2526 W. Congress St. 350

CONCRETE FORM CLAMPS.

Universal Form Clamp Co., 14 N. May St. 368

CONCRETE HARDENER.

Advance Waterproof Cement Co., 15 E. 402

Van Buren St. 402

Schofield, Evans & Co., 508 S. Dearborn 346

Vitrifyx Co., 2526 W. Congress St. 350

CONCRETE PILES.

Raymond Con. Pile Co., 111 W. Monroe 12

CONCRETE MIXERS.

Babcock Bros. Co., 140 S. Dearborn 96-362

CONCRETE REINFORCING BARS—STEEL.

(See Reinforcing Bars—Concrete)

CONCRETE REINFORCING STEEL FABRIC.

(See Steel Fabric for Reinforcing Concrete)

CONCRETE SPACERS AND SUPPORTS.

Universal Form Clamp Co., 14 N. May St. 368

CONDUITS—UNDERGROUND—STEAM PIPES.

Stannard Power Equipment Co., 53 W. 448

Jackson 448

CONTRACTORS' BONDS.

Builders & Mfrs. Mutual Casualty Co., 133 W. Washington St. 54

Sherman & Ellis, Inc., 11 S. La Salle St. 264

CONTRACTORS—ELEVATORS.

Sasgen Derrick Co., 3103 W. Grand Av. 118

CONVEYORS—BELT & GRAVITY.

Olson, Samuel & Co., 2418 Bloomingdale 14

Weller Mfg. Co., 1856 N. Kostner Av. 86

COOLING SYSTEMS FOR BUILDINGS.

Gustafson, K. A., 2114 N. Springfield 444

Herlihy, J. J., 751 W. Van Buren St. 432

Haines Co., 1933 W. Lake St. 444

Mehring & Hanson Co., 118 N. Franklin 428

Monarch Vent. Co., 1338 Sedgwick St. 146

Narowetz Heat. & Vent. Co., 1711 Park 444

Webster, Warren & Co., 53 W. Jackson 442

Wittenmeier Mch. Co., 850 N. Spaulding Av. 120

CORK INSULATION.

Union Insul. & Const. Co., 20 W. Jackson 40

United Cork Companies, 110 S. Dearborn 68

CORNICES—COPPER, GALVANIZED.

Gustafson, K. A., 2114 N. Springfield 444

CORRUGATED IRON.

Scully Steel & Iron Co., 2364 S. Ashland 370

CREOSOTED WOOD BLOCKS.

Indiana Zinc Creosoting Co., 111 W. Wash. 58

CREOSOTED LUMBER—TIES—TIMBER AND PILING.

Indiana Zinc Creosoting Co., 111 W. Wash. 58

CRUSHED STONE.

Brownell Improve. Co., 133 W. Wash. 394

CURE GUARDS—CONCRETE.

Calumet Steel Co., 208 S. La Salle St. 378

CUT STONE.

Cent. Oolitic Stone Co., 2126 S. Kedzie 72

Indiana Quarries Co., 112 W. Adams St. 510

DAMP RESISTING COMPOUNDS.

Advance Waterproof Cement Co., 15 E. 402

Van Buren St. 402

Am. Tar Products Co., 208 S. La Salle 268

Barrett Co., 10 S. La Salle St. 22

Crescent Sales & Mfg. Co., 110 S. Dear. 24

Johns-Manville Co., 18th & Mich. 8

Ohmlac Paint & Rfg. Co., 140 S. Dearborn 478

Schofield, Evans & Co., 508 S. Dearborn 346

Semet Solvay Co., 332 S. Michigan Av. 490

Vitrifyx Co., 2526 W. Congress St. 350

DAMP-PROOFING—CONCRETE.

Schofield, Evans & Co., 508 S. Dearborn 346

Semet Solvay Co., 332 S. Michigan Av. 490

DEADENING MATERIAL.

Am. Tar Products Co., 208 S. La Salle 268

Barrett Co., 10 S. La Salle St. 22

Bird & Son, 1472 W. 76th St. 26

Cabot, Samuel, 24 W. Kinzie St. 340

Johns-Manville Co., 18th & Mich. 8

Stevens Partition & Floor Deadener Co., 175 W. Washington 346

Union Insul. & Constr. Co., 20 W. Jackson 40

United Cork Companies, 110 S. Dearborn 68

DECORATORS—INTERIOR.

Brennen, J. M. & Co., 651 W. 43rd St. 486

Ebert, Theo. Co., 914 Diversey Pkwy. 484

Gleich, T. C. Co., 2850 Broadway 480

Nelson, W. P. Co., 614 S. Michigan Av. 480

Noelle, J. B. Co., 702 N. Wells St. 488

Olson, Herman Dec. Co., 911 Chgo. Av., Evanston, Ill. 488

Olson, Hermann & Co., 2568 N. Clark St. 482

Plamondon & Gabriel Co., 308 N. Mich. 484

Rising Dec. Co., 527 S. Peoria St. 486

Spierling & Linden, 1216 Michigan Av. 488

Sullivan, J. P., 4515 Indiana Av. 482

Warnecke, C. E. Co., 4043 Elston Av. 488

DERRICKS.

Sasgen Derrick Co., 3103 W. Grand Av. 118

DOORS.

Curtis Door & Sash Co., 1414 S. Western 144

Morgan Sash & Door Co., 2287 Blue Island Av. 144

Nollau & Wolff Mfg. Co., 1705 Fullerton 344

DOORS—CROSS HORIZONTAL FOLDING.

Babcock Bros. Co., 140 S. Dearborn 96-362

Hill, O. H. Co., 2253 St. Paul Av. 374

Kinnear Mfg. Co., 208 S. La Salle St. 388

Variety Fire Door Co., 2958 Carroll Ave. 388

DOORS—FLUSH VENEERED

Curtis Door & Sash Co., 1414 S. Western 144

Morgan Sash & Door Co., 2287 Blue Island Av. 144

DOORS—HOLLOW METAL.

Babcock Bros. Co., 140 S. Dearborn 96-362

Hill, O. H. Co., 2253 St. Paul Av. 374

Smith, F. P. W. & I. Wks., 2346 Clybourn 384

Variety Fire Door Co., 2958 Carroll Av. 388

DOORS—SLIDING SWING.

Babcock Bros. Co., 140 S. Dearborn 96-362

Dodge, H. B. & Co., 332 S. Michigan Av. 262

Smith, F. P. W. & I. Wks., 2346 Clybourn 384

DRAINAGE.

Am. Heat. & Plumb. Corp., 189 N. Clark 428

Corboy, M. J. Co., 178 W. Randolph St. 468

Daly, J. J., 408 N. Wells St. 468

Dwyer & Co., 31 W. Illinois St. 432

Griffith, Wm. H., 3656 Broadway 470

Hanley & Co., 3444 Forest Ave. 440

Hulbert & Dorsey, 208 N. Wells St. 468

Murphy Plumbing Co., 23 E. Congress 468

Nacey, P. Co., 927 S. State St. 436

Nilson Bros., 3222 N. Halsted St. 430

Nilson, G. Albin & Co., 155 N. Clark St. 470

Noble & Thumm, 2313 Lincoln Av. 470

Watson, W. W., 708 Carpenter St. 470

DRAIN BASE.

Stannard Power Equipment Co., 53 W. Jackson 448

DRAPERIES.

Spierling & Linden, 1216 Michigan Av. 488

DRAWING MATERIALS.

Am. Blue Print Paper Co., 445 Plymouth 508
Crofoot, Nielsen & Co., 172 W. Wash. 508

DRINKING FOUNTAINS.

Imperial Brass Mfg. Co., 1200 W. Harr. 458
Smith, F. P. W. & I. Wks., 2346 Clybourn 384

DRUG FIXTURES.

Brunswick-Balke-Collender Co., 623 S. Wabash Av. 460

DRY ROOMS.

Am. Laundry Mchy. Co., 208 W. Monroe 344
Troy Laundry Mchy. Co., 23d & La Salle 344

DUMB WAITERS.

Babcock Bros. Co., 140 S. Dearborn 96-362
Matot, D. A., 1538 Montana St. 266

DYNAMOS.

Commonwealth Edison Co., 72 W. Adams 322
Comstock, L. K. & Co., 79 W. Monroe 336
Newgard, Henry & Co., 947 Washington 324

ELECTRIC ELEVATORS.

(See Elevators—Passenger and Freight)

ELECTRIC FIXTURES.

Beardslee Chandelier Mfg. Co., 216 S. Jefferson 316
Benjamin Elec. Mfg. Co., 847 W. Wash. 308
Central Electric Co., 320 S. Wells St. 334
Everson, C. G. & Co., 70 W. Lake St. 336
Johnson-Meier Co., 155 Wendell St. 360
Manhattan Elec. Supply Co., 114 S. Wells 334
Luminous Unit Co., 108 S. La Salle 318
Pearlman, Victor A. & Co., 533 S. Wabash Av. 306
Reflectolyte Co., 914 Pine St., St. Louis, Mo. 320

ELECTRIC FUSES.

Benjamin Elec. Mfg. Co., 847 W. Wash. 308
Central Electric Co., 320 S. Wells St. 334
Chgo. Fuse Mfg. Co., 1501 W. 15th St. 312
Economy Fuse & Mfg. Co., 2711 Greenview Av. 310
Johns-Manville Co., 18th & Mich. 8
Manhattan Elec. Supply Co., 114 S. Wells 334

ELECTRIC SUPPLIES—MANUFACTURERS

Benjamin Elec. Mfg. Co., 847 W. Wash. 308
Central Electric Co., 320 S. Wells St. 334
Manhattan Elec. Supply Co., 114 S. Wells 334

ELECTRIC MOTORS.

Central Electric Co., 320 S. Wells St. 334
Commonwealth Edison Co., 72 W. Adams 322
Manhattan Elec. Supply Co., 114 S. Wells 334

ELECTRICAL CONTRACTORS.

Commonwealth Edison Co., 72 W. Adams 322
Comstock, L. K. & Co., 79 W. Monroe 336
Dearb'n Elec'l Constr. Co., 27 W. Kinzie 336
Fuchs, E. D. Elec. Co., 129 S. La Salle 330
Hanley & Co., 3444 Forest Av. 440
Hewitt, J. B. & Co., 10 S. La Salle St. 332
Lamont, L. H. & Co., 9 S. Clinton St. 336
Newgard, Henry & Co., 947 Washington 324
Pierce Electric Co., 215 W. Randolph St. 328
White City Elect. Co., 14 N. Franklin St. 326

ELEVATING AND CONVEYING MCHY.

(See Conveyors—Belt and Gravity)

ELEVATOR APPLIANCES.

Shur-Loc Co. of Ill., 208 S. La Salle St. 258

ELEVATOR CABLES.

Gallaher & Speck, 215 W. Congress St. 436

ELEVATOR DOORS AND ENCLOSURES.

Babcock Bros. Co., 140 S. Dearborn 96-362
Badger Wire & Iron Co., Mil., Wis. 390
Duffin Iron Co., 4837 S. Kedzie Av. 372
Federal Iron Wks., 30 N. La Salle St. 380
Gallaher & Speck, 215 W. Congress St. 436
Guaranty Iron & Steel Co., 2847 W. Lake 382
Halsted, Joseph, Co., 1233 W. Randolph 380
Hanke Iron & Wire Wks., 840 N. Albany 380
Hill, O. H. Co., 2253 St. Paul Av. 374
Johnson-Meier Co., 155 Wendell St. 360
Reuter Brothers, 5814 Wood St. 384

Smith, F. P. W. & I. Wks., 2346 Clybourn 384
Sullivan-Korber Co., 2437 W. 21st Pl. 382
Union Fdry. Wks., 38 S. Dearborn St. 372
Vierling Steel Wks., 313 W. 23rd St. 384
Western Iron Const. Co., 4906 N. Clark 390
Woodbridge Orn'tl. Iron Co., 1519 Altgeld 358

ELEVATOR FIRE DOORS.

Hill, O. H. Co., 2253 St. Paul Av. 374
Kinnear Mfg. Co., 208 S. La Salle St. 388

ELEVATORS—PASSENGER AND FREIGHT.

Elevator Co. of Am., 190 N. State St. 30
Kaestner & Hecht Co., 500 S. Throop St. Inside Back Cover
Montgomery Elevator Co., 122 S. Mich. 314
Otis Elevator Co., 600 W. Jackson Bl. 28
Pitt Engineering Co., 120 W. Kinzie 34
Wheeler Elevator Co., 1100 Washington 32

ELEVATOR REPAIRS.

Elevator Co. of Am., 190 N. State St. 30
Gallaher & Speck, 215 W. Congress St. 436
Kaestner & Hecht Co., 500 S. Throop St. Inside Back Cover
Montgomery Elevator Co., 122 S. Mich. 314
Otis Elevator Co., 600 W. Jackson Bl. 28
Pitt Engineering Co., 120 W. Kinzie 34
Wheeler Elevator Co., 1100 Washington 32

EMERGENCY EXITS.

Standard Fire Escape Co., 23 S. Western Av. 374

ELEVATOR SAFETY LOCK.

Shur-Loc Co. of Ill., 208 S. La Salle St. 258

ELEVATORS—BUILDING MATERIAL.

Sasgen Derrick Co., 3103 W. Grand Av. 118

ENAMELS.

Ohmlac Paint & Rfg. Co., 140 S. Dearborn 478
Pratt & Lambert, Inc., 320 W. 26th St. 474
Standard Cooper-Bell Co., 2606 Federal 472

ENGINES.

Kaestner & Hecht Co., 500 S. Throop St. Inside Back Cover

ENGINEERS—CIVIL.

Greeley-Howard-Norlin Co., 127 N. Dearborn St. 304
Jones, W. D., 8 S. Dearborn St. 304
Kramer, Wm., 8 S. Dearborn St. 304
Silander, A. I., 30 N. La Salle St. 304

ENGINEERS—CONSULTING.

Hunt, Robt. W. & Co., Ins. Exc. Bldg. 402

ENGINEERS—STRUCTURAL.

Barton Spider-Web Sys., 3426 S. Kedzie 366
Morava Constr. Co., 122 S. Michigan 376

EXCAVATING.

Chicago Foundation Co., 76 W. Monroe 302
Newman, W. J. Co., 21 N. Curtis St. 302

EXHAUST FANS.

Am. Blower Co., 140 S. Dearborn St. 420
Hayward, R. B. Co., 849 W. Ohio St. 444
Ilg Electric Ventilating Co., 2834 N. Crawford Av. 424
Mellich-Hayward Co., 213 W. Austin Av. 446
N. Y. Blower Co., 608 S. Dearborn St. 418

FAUCETS.

Chgo. Faucet Co., 2712 N. Crawford Av. 462
Jenkins Bros., 646 W. Washington Bl. 422

FENCE POSTS—CAST IRON.

Castle, A. M. & Co., 715 N. Morgan St. 370
Cyclone Fence Co., 39 S. La Salle St. 62
Reder Fdry. Co., 3536 S. Oakley Av. 380
Smith, F. P. W. & I. Wks., 2346 Clybourn 384

FENCES FOR FACTORIES.

Cyclone Fence Co., 39 S. La Salle St. 62

FILTERS.

Everson, C. G. & Co., 70 W. Lake 336
Greer Chemical Co., 20 W. Jackson Bl. 94

FIRE DOORS.

Babcock Bros. Co., 140 S. Dearborn 96-362
Hill, O. H. Co., 2253 St. Paul Av. 374
Kinnear Mfg. Co., 208 S. La Salle St. 388
Mechanical Mfg Co., Loomis and Pershing Rd. 60
Smith, F. P. W. & I. Wks., 2346 Clybourn 384
Variety Fire Door Co., 2958 Carroll Av. 388

FIRE ESCAPES.

Balsted, Joseph, Co., 1233 W. Randolph	380
Hanke Iron & Wire Wks., 840 N. Albany	380
Smith, F. P. W. & I. Wks., 2346 Clybourn	384
Standard Fire Escape Co., 23 S. Western	374
Union Edry. Wks., 38 S. Dearborn St.	372
Vierling Steel Wks., 413 W. 23rd St.	384

FIRE EXTINGUISHERS.

(See Sprinkler Systems)

FIRE WINDOWS.

Babcock Bros. Co., 140 S. Dearborn	96-362
Detroit Steel Prod. Co., 111 W. Wash.	38
Lupton, David, Sons Co., 28 E. Jackson	50

FIREPLACES.

Colonial Fireplace Co., 4626 W. Roosevelt	78
Interior Tiling Co., 21 E. Van Buren St.	396

FIREPLACE FURNISHINGS, ETC.

Colonial Fireplace Co., 4626 W. Roosevelt	78
Interior Tiling Co., 21 E. Van Buren St.	396

FIREPROOFING.

Am. Cement Plaster Co., 111 W. Wash.	20
Barron Brick Co., 7 S. Dearborn	398
Consolidated Expanded Metal Co., 562 W. Monroe St.	368
Ill. Fire-Proof Constr. Co., 209 S. La Salle St.	400
Johnson, E. V. Co., 20 W. Jackson Bl.	288
McCarthy, W. H., 133 W. Washington	394
North Western Expanded Metal Co., 407 S. Dearborn St.	352
Rosing, Astrid S., 111 W. Monroe St.	116
U. S. Gypsum Co., 205 W. Monroe St.	36

FIREPROOF PARTITIONS.

Am. Cement Plaster Co., 111 W. Wash.	20
Barron Brick Co., 7 S. Dearborn	398
Dee, Wm. E. Co., 30 N. La Salle St.	394
Ill. Fire Proof Constr. Co., 209 S. La Salle	400
McCarthy, W. H., 133 W. Washington	394
Nat. Fire-Proofing Co., 2610 Shields Av.	400
Rosing, Astrid S., 111 W. Monroe St.	116
Simplex Steel Prod. Co., 1146 Roscoe St.	502
U. S. Gypsum Co., 205 W. Monroe St.	36

FIREPROOF SHUTTERS AND DOORS.

(See Iron Doors & Shutters)

FIXTURES—STEEL.

Durand Steel Locker Co., 76 W. Monroe	18
Federal Steel Fixture Co., 4545 Homer	74

FLOOR COVERINGS.

Barrett Co., 10 S. La Salle St.	22
Bird & Son, 1472 W. 76th St.	26

FLOOR DEADENING.

Stevens Partition & Floor Deadener Co., 175 W. Washington	346
---	-----

FLOOR PLATES—WROUGHT IRON.

Castle, A. M. & Co., 715 N. Morgan St.	370
Scully Steel & Iron Co., 2364 S. Ashland	370

FLOOR PRESERVATIVE.

Seofield, Evans & Co., 508 S. Dearborn	346
Vitrifyx Co., 2526 W. Congress St.	350

FLOORS—ACID PROOF.

Fulton Asphalt Co., 53 W. Jackson	88
-----------------------------------	----

FLOORS—ASPHALT.

Fulton Asphalt Co., 53 W. Jackson	88
-----------------------------------	----

FLOORS—HARDWOOD.

Burns, John E. Lbr. Co., 700 W. Chicago	104
Hettler, Herman H. Lbr. Co., 2601 Elston	106
Hines, Edw. Lumber Co., 2431 S. Lincoln	100
Mears-Slayton Bldg. Mat. Co., Clark and Howard Av.	112
Pilsen Lumber Co., 2201 Laflin St.	110
Rittenhouse & Embree Co., 3500 S. Racine	108
Thornton Clancy Lbr. Co., 2315 Elston	102

FLOORS—COMPOSITION.

Am. Magnesia Pro. Co., 5746 Roosevelt Road	6
Craig Co., 30 N. Michigan Av.	396
Muller, Franklyn R. & Co., Waukegan, Ill.	1

Weary & Beck, 1732 S. Michigan	396
Williams-Wendt Co., 118 N. La Salle St.	396

FLOORS—WOOD BLOCK.

Dodge, H. B. & Co., 332 S. Michigan Av.	262
Indiana Zinc Creosoting Co., 111 W. Washington	58

FLUE LININGS.

Dee, Wm. E. Co., 30 N. La Salle St.	394
Garden City Sand Co., 133 W. Wash.	394
Ill. Fire-Proof Constr. Co., 209 S. La Salle St.	400
McCarthy, W. H., 133 W. Washington	394
Northwestern Terra Cotta Co., 2525 Clybourn Av.	10
Nat. Fire-Proofing Co., 2610 Shields Av.	400
Rosing, Astrid S., 111 W. Monroe St.	116

FORGINGS.

American Bridge Co., 208 S. La Salle	354
Kenwood Bridge Co., 1st Natl. Bk. Bldg.	376

FOUNDATIONS.

Chicago Foundation Co., 76 W. Monroe	302
Raymond Con. Pile Co., 111 W. Monroe	12

FOUNDRIES.

Butler St. Fdry. & Iron Co., 3424 Normal	384
Holmes, Pyott & Co., 159 N. Jefferson	376
Ill. Malleable Iron Co., 1801 Diversey	426
Reder Fdry. Co., 3536 S. Oakley Av.	380
Smith, F. P. W. & I. Wks., 2346 Clybourn	384

FRICTION CLUTCHES.

Elevator Co. of Am., 190 N. State St.	30
Kaestner & Hecht Co., 500 S. Throop St.	
Inside Back Cover	
Olson, Samuel & Co., 2418 Bloomingdale	14
Otis Elevator Co., 600 W. Jackson Bl.	28
Pitt Engineering Co., 120 W. Kinzie	34
Weller Mfg. Co., 1856 N. Kostner Av.	86
Wheeler Elevator Co., 1100 Washington	32

FURNACES—INDUSTRIAL.

Gordon, Robt. Inc., 622 W. Monroe	412-428
-----------------------------------	---------

FURNACES—SMOKELESS.

Hayward, R. B. Co., 849 W. Ohio St.	444
Mellish-Hayward Co., 213 W. Austin Av.	446
Mueller, L. J. Furnace Co., 60 E. Lake	424
Robinson Furnace Co., 205 W. Lake St.	442

FURNITURE—SCHOOL.

Rowles, E. W. A. Co., 2345 S. La Salle	576
--	-----

FURNITURE, SPECIAL DESIGN.

Plamondon & Gabriel Co., 308 S. Michigan Av.	484
Spierling & Linden, 1216 Michigan Av.	488

FUSE RENEWABLE.

Benjamin Elec. Mfg. Co., 847 W. Wash.	308
Chgo. Fuse Mfg. Co., 1501 W. 15th St.	312
Economy Fuse & Mfg Co., 2711 Greenview Av.	310

GALVANIZING—ELECTRO PLATE.

Brasco Mfg. Co., 5035 S. Wabash Av.	260
Kawneer Co., 175 W. Jackson Bl.	48
Mechanical Mfg. Co., Loomis & Pershing Road	60
Scully Steel & Iron Co., 2364 S. Ashland	370

GARBAGE CREMATORIES.

Kerner Incinerator Co., 28 E. Jackson	408
Kewanee Boiler Co., 328 W. Washington	406

GAS APPLIANCES.

Peoples Gas Light & Coke Co., 122 S. Michigan	338
---	-----

GAS AND ELECTRIC FIXTURES.

Everson, C. G. & Co., 70 W. Lake St.	336
Peoples Gas Light & Coke Co., 122 S. Michigan	338

GAS FITTING.

Am. Heat & Plumb. Corp., 189 N. Clark	428
Corboy, M. J. Co., 178 W. Randolph St.	468
Daly, J. J., 408 N. Wells St.	470
Dwyer & Co., 31 W. Illinois St.	432
Griffith, Wm. H., 3656 Broadway	470
Hanley & Co., 3444 Forest Av.	440
Hulbert & Dorsey, 208 N. Wells St.	468
Murphy Plumbing Co., 23 E. Congress	468
Nacey, P. Co., 927 S. State St.	436

Nilson Bros., 3222 N. Halsted St.	430
Nilson, G. Albin & Co., 155 N. Clark St.	470
Noble & Thumm, 2313 Lincoln Av.	470
Watson, W. W., 708 Carpenter St.	470

GAS—ILLUMINATING.

Peoples Gas Light & Coke Co., 122 S. Michigan	338
---	-----

GAS LOGS AND GAS GRATES.

Colonial Fireplace Co., 4626 W. Roosevelt	78
Interior Tiling Co., 21 E. Van Buren St.	396
Pearlman, Victor A. & Co., 533 S. Wash. Av.	306
Peoples Gas Light & Coke Co., 122 S. Michigan	338

GAS RANGES AND STOVES.

Peoples Gas Light & Coke Co., 122 S. Michigan	338
Pick, Albert & Co., 212 W. Randolph St.	80-82

GENERAL CONTRACTORS.

Anderson, A. & E. Co., 19 S. La Salle	276
Anderson, Edward A. Co., 8 E. Huron St.	298
Appel, Henry L. Co., 931 W. North Av.	290
Archibald, E. L. Co., 111 W. Wash.	280
Ardmore Constr. Co., 186 N. La Salle St.	284
Barnard, H. B., 140 S. Dearborn St.	276
Barrett Constr. Co., 77 E. Washington	300
Blome-Sinek Co., 139 N. Clark St.	140
Brundage, Avery, 110 S. Dearborn St.	138
B. W. Constr. Co., 10 S. La Salle St.	274
Cadenhead Co., 8 E. Huron St.	298
Cement Gun Constr. Co., 537 S. Dearborn	512
Dahl-Stedman Co., 11 S. La Salle St.	142
Eriesson, Henry Co., 139 N. Clark St.	286
Griffiths, John & Son Co., 112 W. Adams	124
Hanson Bros. Co., 127 N. Dearborn St.	282
Johnson, E. V. Co., 20 W. Jackson Bl.	288
Jones Constr. Co., 1748 W. Madison St.	298
Lanquist & Illsley Co., 1100 N. Clark St.	132
Lund, A. Co., 19 S. La Salle St.	136
Lynch, Austin J. Co., 111 W. Monroe St.	296
Mavor, Wm. Co., 7 S. Dearborn St.	296
McKeown Bros. Co., 112 W. Adams St.	280
McLennan Constr. Co., 3105 Calumet Av.	272
Menke, Henry Co., 2128 Lake St.	284
Meyne, Gerhardt F., 127 N. Dearborn St.	300
Morrice, Wm. Co., 17 N. La Salle St.	300
Moses, C. A. Constr. Co., 133 W. Wash.	278
Mueller Constr. Co., 179 W. Wash.	134
Mutual Constr. Co., 2532 Warren Av.	300
Nielson, S. N. & Co., 3059 Augusta St.	282
Olson, Peter Co., 19 S. La Salle St.	276
Rasmussen, C., 154 W. Randolph St.	292
Regnell, B. J. Co., 19 S. La Salle St.	296
Rosenthal-Cornell, O. W. Co., 80 E. Jack.	274
Salomon-Waterton Co., 35 S. Dearborn	292
Samuelson, A. J., 189 W. Madison St.	286
Scharmer Constr. Co., 139 N. Clark St.	270
Shedden, James & Co., 106 N. La Salle St.	272
Snyder, J. W. Co., 122 S. Michigan Av.	126
Sollitt, Ralph & Sons Constr. Co., 30 N. La Salle St.	270
Sollitt, Sumner Co., 225 N. Michigan Av.	298
Strandberg, E. P. Co., 111 W. Washington	288
Thielberg, A. C., 154 W. Randolph St.	296
Thompson-Starrett Co., 175 W. Jackson	130
Thomson, Geo. & Son Co., 30 N. La Salle	290
Wells Bros. Const. Co., 53 W. Jackson	128
Wilson, R. F. & Co., 1851 Elston Av.	122

GLASS—ART, ORNAMENTAL AND STAINED.

Spierling & Linden, 1216 Michigan Av.	488
---------------------------------------	-----

GLASS AND GLAZING.

Hooker, H. M. Glass & Paint Co., 651 W. Washington	500
Morlite Co., 366 W. Ohio St.	498
Tyler & Hippach, 366 W. Ohio St.	498

GLASS—PRISMATIC.

Am. 3 Way-Luxfer Prism Co., Cicero, Ill.	500
Hooker, H. M. Glass & Paint Co., 651 W. Washington	500
Morlite Co., The, 366 W. Ohio St.	498
Tyler & Hippach, 366 W. Ohio St.	498

GLASS—WIRE.

Mississippi Wire Glass Co., 7 W. Madison St.	494
--	-----

GRAIN ELEVATOR MACHINERY.

Kaestner & Hecht Co., 500 S. Throop St.	14
Inside Back Cover	
Olson, Samuel & Co., 2418 Bloomingdale	14
Weller Mfg. Co., 1856 N. Kostner Av.	86

GRATES AND FIREPLACES.

Colonial Fireplace Co., 4626 W. Roosevelt Road	78
Interior Tiling Co., 21 E. Van Buren St.	396

GRAVEL.

Am. Sand & Gravel Co., 133 W. Wash.	294
Brownell Improv. Co., 133 W. Wash.	394
Consumers Co., 111 W. Washington	114
Dee, Wm. E. Co., 30 N. La Salle St.	394
Garden City Sand Co., 133 W. Wash.	394
Rosing, Astrid S., 111 W. Monroe St.	116

GRILLE WORK.

Architectural Dec. Co., 1600 S. Jefferson	508
Dux, Joseph, 2112 W. Van Buren St.	508

GRILLE WORK—METAL.

(See Iron Work—Ornamental)

GYPSUM PRODUCTS.

Am. Cement Plaster Co., 111 W. Wash.	20
U. S. Gypsum Co., 205 W. Monroe St.	36

HANGERS AND SHAFING.

Scully Steel & Iron Co., 2364 S. Ashland	370
--	-----

HARDWARE—BUILDERS.

Lawson Mfg. Co., 228 W. Superior St.	64
Midwest Hardware Co., 56 W. Randolph	84
Wolff, Geo. & Co., 190 N. State St.	258

HARDWOOD FLOORING.

(See Flooring—Hardwood)

HEATING APPARATUS.

Clow, Jas. B. & Sons, 544 S. Franklin	452
Gordon, Robert, Inc., 622 W. Monroe	412-428
Ill. Malleable Iron Co., 1801 Diversey	426
Kellogg Mackay Co., 419 W. 18th St.	404
Kewanee Boiler Co., 328 W. Washington	406
Monarch Vent. Co., 1338 Sedgwick St.	446
Mueller, L. J. Furnace Co., 60 E. Lake	424
Nacey, P. Co., 927 S. State St.	436
Robinson Furnace Co., 205 W. Lake	442
Steam Corporation, 215 N. Michigan	414
Utica Heater Co., 218 W. Kinzie St.	410
Wear & Craig Co., 6316 Wentworth Av.	420

HEATING CONTRACTORS—HOT WATER—STEAM—VACUUM—VAPOR HEATING.

Am. Heat. & Plumbing Co., 189 N. Clark	428
Arcade Steam Heat. Co., 126 W. Kinzie	90
Baker & Smith Co., 408 N. Wells St.	436
Claffey, E. J. Co., 10 W. Illinois St.	432
Douglass, Thos. J. & Co., 441 N. Dearborn	440
Dwyer & Co., 31 W. Illinois St.	432
Gallaher & Speck, 215 W. Congress St.	436
Glennon-Bielke Co., 546 W. Lake St.	432
Gordon, Robert, Inc., 622 W. Monroe	412-428
Graves Heating Co., 162 N. Desplaines	434
Haines Co., 1933 W. Lake St.	444
Hanley & Co., 3444 Forest Av.	440
Hayward, R. B. Co., 849 W. Ohio St.	444
Henrich, Geo. A. Co., 5650 Broadway	438
Herlihy, J. J., 751 W. Van Buren St.	432
Hoier, Wm. V. & Co., 701 N. Wells St.	440
Johnson, C. W., Inc., 644 Washington Bl.	438
Kehm Bros. Co., 15 W. Kinzie St.	430
Kilander, A. & Co., 126 S. Clinton St.	438
Kirk, Geo. H., 6711 Wentworth Av.	438
Lees, Wm., 548 Washington Bl.	436
Mehring & Hanson Co., 118 N. Franklin	428
Monarch Vent. Co., 1338 Sedgwick St.	446
Nacey, P. Co., 927 S. State St.	436
Narowitz Heat. & Vent. Co., 1711 Park Av.	444
Nilson Bros., 3222 N. Halsted St.	430
Noble & Thumm, 2313 Lincoln Av.	470
Peckham, Harry, Jr., 2345 W. Roosevelt	428
Phillips, Getschow Co., 128 W. Kinzie	430
Pope, Wm. A., 26 N. Jefferson St.	434
Prentice, L. H. Co., 328 Sherman St.	428
Rigby, Ben, 545 W. Lake St.	434
Schampel & Dougherty, 173 W. Wash.	440
Watson, W. W., 708 Carpenter St.	470
Webster, Warren & Co., 53 W. Jackson	442

HEATING—INDUSTRIAL.

Gordon, Robert, Inc., 622 W. Monroe 412-428
 Nacey, P. Co., 927 S. State St. 436

HEAT REGULATION.

Johnson Service Co., 177 N. Dearborn 442

HECTOGRAPH PRINTS.

Am. Blue Print Paper Co., 445 Plymouth 508
 Crofoot, Nielsen & Co., 172 W. Wash. 508

HOISTING MACHINERY.

Sasgen Derrick Co., 3103 W. Grand Av. 118

HOLLOW TILE.

Barron Brick Co., 7 S. Dearborn 398
 Dee, Wm. E. Co., 30 N. La Salle St. 394
 Illinois Fire-proof Constr. Co., 209 S. La Salle St. 400
 McCarthy, W. H., 133 W. Washington 394
 Natl. Fire Proofing Co., 2610 Shields Av. 400
 Rosing, Astrid S., 111 W. Monroe St. 116
 Western Brick Co., Danville, Ill. 392

HOSPITALS—SURFACING WALLS IN OPERATING AND UTILITY ROOMS.

Vitrolite Co., 133 W. Washington St. 44

HOT BLAST HEATING APPARATUS.

Am. Heat & Plumb. Corp., 189 N. Clark 428
 Arcade Steam Heat Co., 126 W. Kinzie 50
 Baker & Smith Co., 408 N. Wells St. 426
 Davis, G. M. Reg. Co., 428 Milwaukee 442
 Douglass, Thos. J. & Co., 441 N. Dearborn 440
 Dwyer & Co., 31 W. Illinois St. 432
 Gallaher & Speck, 215 W. Congress St. 436
 Glennon-Bielke Co., 546 W. Lake St. 432
 Gustafson, K. A., 2114 N. Springfield 444
 Haines Co., 1933 W. Lake St. 444
 Hanley & Co., 3444 Forest Ave. 440
 Hayward, R. B. Co., 849 W. Ohio St. 444
 Henrich, George A. Co., 5650 Broadway 438
 Herlihy, J. J., 751 W. Van Buren St. 432
 Hoier, Wm. V. & Co., 701 N. Wells St. 440
 Johnson, C. W. Inc., 644 Washington Bl. 438
 Kehm Bros. Co., 15 W. Kinzie St. 420
 Kilander, A. & Co., 126 S. Clinton St. 438
 Lees, Wm., 548 Washington Bl. 436
 Mehring & Hanson Co., 118 N. Franklin 428
 Mellish-Hayward Co., 213 W. Austin Av. 446
 Monarch Vent. Co., 1338 Sedgwick St. 446
 Mueller, L. J. Furnace Co., 60 E. Lake 424
 Nacey, P. Co., 927 S. State St. 436
 Narowetz Heat. & Vent. Co., 1711 Park Av. 444
 Peckham, Harry Jr., 2345 W. Roosevelt 428
 Phillips, Getschow Co., 128 W. Kinzie 420
 Pope, Wm. A., 26 N. Jefferson St. 434
 Prentice, L. H. Co., 328 Sherman St. 420
 Robinson Furnace Co., 205 W. Lake St. 442
 Schampel & Dougherty, 173 W. Wash. 440

HOT WATER HEATERS.

Humphrey Co., Kalamazoo, Mich. 422
 Ill. Malleable Iron Co., 1801 Diversey 426
 Kewanee Boiler Co., 328 W. Washington 406
 Mueller, L. J. Furnace Co., 60 E. Lake 424
 Weir & Craig Co., 6316 Wentworth Av. 420

HOTEL SUPPLIES.

Pick, Albert & Co., 212 W. Randolph 80-82

HOUSE MOVERS AND RAISERS.

Friestedt, L. P. Co., Tribune Bldg. 294

HYDRANTS.

Chgo. Faucet Co., 2712 N. Crawford Av. 462
 Jenkins Bros., 646 W. Washington Bl. 122

HYDRAULIC ELEVATORS.

Elevator Co. of Am., 190 N. State St. 30
 Kaestner & Hecht Co., 500 S. Throop St. Inside Back Cover
 Otis Elevator Co., 600 W. Jackson Bl. 28
 Pitt Engineering Co., 120 W. Kinzie 34
 Wheeler Elevator Co., 1100 Washington 32

ICE CONVEYING MACHINERY.

Olson, Samuel & Co., 2418 Bloomingdale 14
 Weller Mfg. Co., 1856 N. Kostner Av. 86

ICE MACHINERY.

Wittenmeier Mch. Co., 850 N. Spaulding Av. 120

INDUCED DRAFT REGULATORS.

Davis, G. M. Reg. Co., 428 Milwaukee 442

INCINERATORS—GARBAGE.

Kerner Incinerator Co., 28 E. Jackson Bl. 408

INDIANA LIMESTONE.

Cent. Oolitic Stone Co., 2126 S. Kedzie 72
 Indiana Quarries Co., 112 W. Adams St. 510

INDUSTRIAL LIGHTING.

Beardslee Chandelier Mfg. Co., 216 S. Jefferson 316
 Benjamin Electric Mfg. Co., 847 W. Washington Blvd. 308
 Pearlman Victor A. & Co., 533 S. Wash-bash Av. 306
 Luminous Unit Co., 108 S. La Salle 318
 Reflectolyte Co., 914 Pine St. St. Louis 320

INSERTS—CONCRETE.

Dean, Olney, J. & Co., 179 W. Wash. 388

INSPECTORS.

Hunt, Robt. W. & Co., Ins. Exc. Bldg. 402

INSULATION.

Cent. Asbestos & Mag. Co., 214 W. Grand 342
 Johns-Manville Co., 18th & Mich. 8
 Krez, Paul J., Co., 444 N. La Salle St. 342
 Standard Asbestos Mfg. Co., 816 W. Lake 342
 Union Insul. & Constr. Co., 20 W. Jackson 40
 United Cork Companies, 110 S. Dearborn 68
 Watson, H. F. Co., 5331 S. Western Av. 342

INSULATION, COLD STORAGE.

Union Insul. & Constr. Co., 20 W. Jackson 40
 United Cork Companies, 110 S. Dearborn 68

INSULATING MATERIALS.

Bird & Son, 1472 W. 76th St. 26
 Johns-Manville Co., 18th & Mich. 8
 Ohmlac Paint & Rfg. Co., 140 S. Dear. 478

INTERIOR FINISH.

Anderson & Lind Mfg. Co., 2127 Iowa St. 98
 Baumann, F. O. Mfg. Co., 1501 Smith 262
 Nollau & Wolff Mfg. Co., 1705 Fullerton 344

IRON DOORS AND SHUTTERS.

Babcock Bros. Co., 140 S. Dearborn 96-362
 Badger Wire & Iron Co., Mil., Wis. 390
 Butler St. Fdry. & Iron Co., 3424 Normal 384
 Halsted, Joseph, Co., 1233 W. Randolph 380
 Hanke Iron & Wire Wks., 840 N. Albany 380
 Hill, O. H. Co., 2253 St. Paul Av. 374
 Holmes, Pyott & Co., 159 N. Jefferson 376
 Ill. Malleable Iron Co., 1801 Diversey 426
 Johnson-Meier Co., 155 Wendell St. 360
 Kinnear Mfg. Co., 208 S. La Salle St. 388
 Smith, F. P. W. & I. Wks., 2346 Clybourn 384
 Variety Fire Door Co., 2958 Carroll Av. 388
 Vierling Steel Wks., 313 W. 23rd St. 384
 Western Iron Constr. Co., 4906 N. Clark 390

IRON STAIRS—RAILINGS AND FENCES.

Badger Wire & Iron Co., Milwaukee, Wis. 390
 Bolter's, A., Sons, 2301 Ward St. 376
 Butler St. Fdry. & Iron Co., 3424 Normal 384
 Castle, A. M., & Co., 715 N. Morgan St. 370
 Cyclone Fence Co., 39 S. La Salle St. 62
 Duffin Iron Co., 4837 S. Kedzie Av. 372
 Federal Iron Wks., 30 N. La Salle St. 380
 Guaranty Iron & Steel Co., 2847 W. Lake 382
 Halsted, Joseph, Co., 1233 W. Randolph 380
 Hanke Iron & Wire Wks., 840 N. Albany 380
 Holmes, Pyott & Co., 159 N. Jefferson 376
 Johnson-Meier Co., 155 Wendell St. 360
 Manton & Smith Co., 1709 W. Austin Av. 382
 Newman Mfg. Co., Cincinnati, O. 390
 Reder Fdry. Co., 3536 S. Oakley Av. 380
 Reuter Brothers, 5814 Wood St. 384
 Scully Steel & Iron Co., 2364 S. Ashland 370
 Smith, F. P. W. & I. Wks., 2346 Clybourn 384
 Sullivan-Korber Co., 2437 W. 21st Pl. 382
 Union Fdry. Wks., 38 S. Dearborn St. 372
 Vierling Steel Wks., 313 W. 23rd St. 384
 Western Iron Const. Co., 4906 N. Clark 390
 Woodbridge Orntl. Iron Co., 1519 Altgeld 358

IRON STORE FRONTS.

Badger Wire & Iron Co., Milwaukee, Wis. 390
 Butler St. Fdry. & Iron Co., 3424 Normal 384
 Duffin Iron Co., 4837 S. Kedzie Av. 372
 Federal Iron Wks., 30 N. La Salle St. 380
 Halsted, Joseph, Co., 1233 W. Randolph 380
 Hanke Iron & Wire Wks., 840 N. Albany 380
 Holmes, Pyott & Co., 159 N. Jefferson 376
 Manton & Smith Co., 1709 W. Austin Av. 382

Reder Fdry. Co., 3536 S. Oakley Av.	380	Am. Laundry Mchy. Co., 208 W. Monroe	344
Reuter Brothers, 5814 Wood St.	384	Clow, Jas. B., & Sons, 544 S. Franklin	452
Scully Steel & Iron Co., 2364 S. Ashland	370	Kellogg Mackay Co., 419 W. 18th St.	404
Smith, F. P. W. & I. Wks., 2346 Clybourn	380	Mott, J. L., Iron Wks., 104 S. Michigan	456
Sullivan-Korber Co., 2437 W. 21st Pl.	382	Standard Sanitary Mfg. Co., 14 N. Peoria	454
Union Fdry. Wks., 38 S. Dearborn St.	372	Wolff Mfg. Co., 225 N. Hoyne Ave.	450
Vierling Steel Wks., 313 W. 23rd St.	384		
Western Iron Const. Co., 4906 N. Clark	390	LEAD BURNING.	
Woodbridge Orntl. Iron Co., 1519 Altgeld	358	Gustafson, K. A., 2114 N. Springfield	444
		Hayward, R. B., Co., 849 W. Ohio St.	444
IRON WORK—ORNAMENTAL.		Mellish-Hayward Co., 213 W. Austin Av.	446
Badger Wire & Iron Co., Milwaukee, Wis.	390	Nacey, P., Co., 927 S. State St.	436
Bolter's, A. Sons, 2301 Ward St.	376	LIABILITY INSURANCE.	
Butler St. Fdry. & Iron Co., 3424 Normal	384	Builders & Mfgs. Mutual Casualty Co.,	
Duffin Iron Co., 4837 S. Kedzie Av.	372	133 W. Washington St.	54
Federal Iron Works, 30 N. La Salle St.	380	Sherman & Ellis, Inc., 11 S. La Salle St.	264
Halsted, Joseph Co., 1233 W. Randolph	380	LIGHTING FIXTURES.	
Hanke Iron & Wire Wks., 840 N. Albany	380	Beardslee Chandelier Mfg. Co., 216 S. Jef-	
Holmes, Pyott & Co., 159 N. Jefferson St.	376	erson	316
Johnson-Meier Co., 155 Wendell St.	360	Central Electric Co., 320 S. Wells St.	334
Manton & Smith Co., 1709 W. Austin Av.	382	Commonwealth Edison Co., 72 W. Adams	322
Reuter Bros., 5814 Wood St.	384	Everson, C. G., & Co., 70 W. Lake St.	336
Smith, F. P. W. & I. Wks., 2346 Clybourn	384	Johnson Meier Co., 155 Wendell St.	360
Sullivan-Korber Co., 2437 W. 21st Pl.	382	Luminous Unit Co., 108 S. La Salle	318
Union Fdry. Wks., 38 S. Dearborn St.	372	Pearlman, Victor A., & Co., 533 S. Wa-	
Vierling Steel Wks., 313 W. 23rd St.	384	bash Ave.	306
Western Iron Const. Co., 4906 N. Clark	390	Reflectolite Co., 914 Pine St., St. Louis,	
Woodbridge Orntl. Iron Co., 1519 Altgeld	358	Mo.	320
IRON WORK—STRUCTURAL.		LIGHTNING RODS	
(See Structural Iron and Steel)		Arrow Conductor Co., 1536 W. Adams	382
IRONERS—WASHERS—WEINGERS.		LIME.	
Am. Ironing Machine Co., 168 N. Mich.	266	Consumers Co., 111 W. Washington	114
IRONING MACHINES (ELECTRIC)		Rosing, Astrid S., 111 W. Monroe St.	116
Am. Ironing Machine Co., 168 N. Mich.	266	LIQUID SOAP FIXTURES.	
Commonwealth Edison Co., 72 W. Adams	322	Imperial Brass Mfg. Co., 1200 W. Harr.	458
Troy Laundry Mchy. Co., 23rd & La Salle	344	LOANS—BUILDING.	
JAIL AND PRISON BUILDERS.		Baird & Warner, 29 S. La Salle St.	56
Bolter's, A. Sons, 2301 Ward St.	376	Corn Exc. Nat'l Bank, 134 S. La Salle	52
Butler St. Fdry. & Iron Co., 3424 Normal	384	Greenebaum Sons Bank & Trust Co., 9	
Halsted, Joseph Co., 1233 W. Randolph	380	S. La Salle St.	302
Holmes, Pyott & Co., 159 N. Jefferson	376	LOCKERS—METAL.	
Morava Constr. Co., 122 S. Michigan Av.	376	Dodge, H. B., & Co., 332 S. Michigan Av.	262
Smith, F. P. W. & I. Wks., 2346 Clybourn	384	Durand Steel Locker Co., 76 W. Monroe	18
Union Fdry. Wks., 38 S. Dearborn St.	372	Federal Steel Fixture Co., 4545 Homer	74
Vierling Steel Wks., 313 W. 23rd St.	384	Smith, F. P., W. & I. Wks., 2346 Clybourn	384
LABORATORY—TESTING.		LUMBER.	
Hunt, Robt. W. & Co., Ins. Ex. Bldg.	402	Burns, John E., Lbr. Co., 700 W. Chicago	104
LAMPS, EXTERIOR—IRON AND BRONZE.		Hettler, Herman H., Lbr. Co., 2601 Elston	106
Halsted, Joseph Co., 1233 W. Randolph	380	Hines, Ed., Lumber Co., 2431 S. Lincoln	100
Johnson-Meier Co., 155 Wendell St.	360	Mears-Slayton Bldg. Mat. Co., Clark and	
Manton & Smith Co., 1709 W. Austin Av.	382	Howard Ave.	112
Reuter Bros., 5814 Wood St.	384	Pilsen Lbr. Co., 2201 Laflin St.	110
Smith, F. P. W. & I. Wks., 2346 Clybourn	384	Rittenhouse & Embree Co., 3500 S. Ra-	
Sullivan-Korber Co., 2437 W. 21st Pl.	382	cine	108
Woodbridge Orntl. Iron Co., 1519 Altgeld	358	Thornton Claney Lbr. Co., 2315 Elston	102
LANDSCAPE ENGINEERS.		LUMBER—STEEL.	
Peterson Nursery, 30 N. La Salle St.	340	Natl. Pressed Steel Co., Massillon, O.	364
LATH.		MACHINISTS.	
Burns, John E. Lbr. Co., 700 W. Chicago	104	Gallaher & Speck, 215 W. Congress St.	436
Hettler, Herman H., Lbr. Co., 2601 Elston	106	Gordon, Robert, Inc., 622 W. Monroe	412-428
Hines, Ed., Lumber Co., 2431 S. Lincoln	100	Nacey, P., Co., 927 S. State St.	436
Mears-Slayton Bldg. Mat. Co., Clark and		MAGNESIA PRODUCTS.	
Howard Ave.	112	Cent. Asbestos & Mag. Co., 214 W. Grand	342
Pilsen Lbr. Co., 2201 Laflin St.	110	Johns-Manville Co., 18th & Mich.	8
Rittenhouse & Embree Co., 3500 S. Racine	108	Krez, Paul J., Co., 444 N. La Salle St.	342
Thornton Claney Lbr. Co., 2315 Elston	102	Standard Asbestos Mfg. Co., 816 W. Lake	342
LATH—METAL AND WIRE.		Watson, H. F. Co., 5331 S. Western Av.	342
Consolidated Expanded Metal Co., 562 W.		MANHOLE COVERS.	
Monroe St.	368	Dee, Wm. E., Co., 30 N. La Salle St.	394
MacAdams & Call, 111 W. Washington	350	MANTELS.	
McCarthy, W. H., 133 W. Washington	394	Colonial Fireplace Co., 4626 W. Roosevelt	78
North Western Expanded Metal Co., 407		Interior Tiling Co., 21 E. Van Buren St.	396
S. Dearborn St.	352	MARBLE CONTRACTORS.	
Smith, F. P. W. & I. Wks., 2346 Clybourn	384	Marthens, Chester N., Marble Co., 53rd	
Voss, Frederick, 552 W. Monroe St.	388	and Wallace Sts.	392
LAUNDRY DRYERS.		MASON CONTRACTORS.	
Am. Laundry Mchy. Co., 208 W. Monroe	344	Anderson, A. & E., Co., 19 S. La Salle	278
Troy Laundry Mchy. Co., 23rd & La Salle	344	Anderson, Edward A., Co., 8 E. Huron St.	298
LAUNDRY MACHINERY.		Appel, Henry L., Co., 931 W. North Av.	290
Am. Ironing Machine Co., 168 N. Mich.	266	Archibald, E. L., Co., 111 W. Washington	280
Am. Laundry Mchy. Co., 208 W. Monroe	344	Ardmore Constr. Co., 186 N. La Salle	284
Troy Laundry Mchy. Co., 23rd & La Salle	344	Barnard, H. B., Co., 140 S. Dearborn St.	276
LAUNDRY TRAYS AND KITCHEN		Barrett Constr. Co., 77 E. Washington	300
SINKS			
Alberene Stone Co., 214 N. Clinton St.	446		

Blome-Sinek Co., 139 N. Clark St.	140
Brundage, Avery, 110 S. Dearborn St.	138
B. W. Constr. Co., 10 S. La Salle St.	274
Cadenhead Co., 8 E. Huron St.	298
Dahl-Stedman Co., 11 S. La Salle St.	142
Ericsson, Henry Co., 139 N. Clark St.	286
Hanson Bros. Co., 127 N. Dearborn St.	282
Griffiths, John, & Son Co., 112 W. Adams	124
Johnson, E. V., Co., 20 W. Jackson Blvd.	288
Jones Constr. Co., 1748 W. Madison St.	293
Lanquist & Hilsley Co., 1100 N. Clark St.	132
Lund, A., Co., 19 S. La Salle St.	136
Lynch, Austin J., Co., 111 W. Monroe St.	296
Mavor, Wm., Co., 7 S. Dearborn St.	296
McLennan Constr. Co., 3105 Calumet Av.	272
Menke, Henry, Co., 2128 Lake St.	284
Meyne, Gerhardt F., 127 N. Dearborn St.	300
Morrice, Wm., Co., 17 N. La Salle St.	300
Moses, C. A., Constr. Co., 133 W. Wash.	273
Mueller Constr. Co., 179 W. Wash.	134
Mutual Constr. Co., 2532 Warren Av.	300
Nielsen, S. N., & Co., 3059 Augusta St.	282
Olson, Peter, Co., 19 S. La Salle St.	276
Rasmussen, C., 154 W. Randolph St.	292
Regnell, B. J., Co., 19 S. La Salle St.	296
Rosenthal-Cornell, O. W. Co., 80 E. Jack.	274
Salomon-Waterton Co., 35 S. Dearborn	292
Samuelson, A. J., 189 W. Madison St.	286
Scharmer Constr. Co., 139 N. Clark St.	270
Shedden, James & Co., 106 N. La Salle	272
Snyder, J. W., Co., 122 S. Michigan Av.	126
Sollitt, Ralph, & Sons Constr. Co., 30 N. La Salle St.	270
Sollitt, Sumner, Co., 225 N. Michigan	298
Strandberg, E. P., Co., 111 W. Washington	288
Thielberg, A. C., 154 W. Randolph St.	296
Thompson-Starrett Co., 175 W. Jackson	130
Thomson, Geo., & Son Co., 30 N. La Salle	290
Wells Bros. Const. Co., 53 W. Jackson Bl.	128
Wilson, R. F., & Co., 1851 Elston Av.	122

MATERIAL HOISTS.

Sasgen Derrick Co., 3103 W. Grand Av.	118
---------------------------------------	-----

METAL LATH.

Consolidated Expanded Metal Co., 562 W. Monroe St.	368
McCarthy, W. H., 133 W. Washington	394
North Western Expanded Metal Co., 407 S. Dearborn St.	352
Smith, F. P. W. & I. Wks., 2346 Clybourn	384
Voss, Frederick, 552 W. Monroe St.	388

METAL SASH & FRAMES.

Babcock, Bros. Co., 140 S. Dearborn	96-362
Detroit Steel Prod. Co., 111 W. Wash.	38
Lupton, David, Sons Co., 28 E. Jackson	50

MILL WORK.

Anderson & Lind Mfg. Co., 2127 Iowa St.	98
Baummann, F. O., Mfg. Co., 1501 Smith	262
Curtis Door & Sash Co., 1414 S. Western	144
Morgan Sash & Door Co., 2287 Blue Island Av.	Inside Front Cover
Nollau & Wolff Mfg. Co., 1705 Fullerton	344

MORTGAGE LOANS.

Baird & Warner, 29 S. La Salle St.	56
Corn Exp. Nat'l Bank, 131 S. La Salle	52
Greenebaum Sons Bank & Trust Co., 9 S. La Salle St.	302

MOSAICS.

Interior Tiling Co., 21 E. Van Buren St.	396
Marthens, Chester N., Marble Co., 53rd and Wallace Sts.	392

MOULDINGS—METAL.

Brasco Mfg. Co., 5035 S. Wabash Av.	260
Kawneer Co., 175 W. Jackson Bl.	48
Newman Mfg. Co., Cincinnati, O.	390

MURAL DECORATIONS.

Spierling & Linden, 1216 Michigan Av.	488
---------------------------------------	-----

NEEDLE PATH WATER MIXERS.

Hoffmann & Billings Mfg. Co., Milwaukee, Wis.	464
---	-----

NURSERY MEN.

Peterson Nursery, 30 N. La Salle St.	340
--------------------------------------	-----

OFFICE FIXTURES.

Anderson & Lind Mfg. Co., 2127 Iowa St.	98
Baummann, F. O., Mfg. Co., 1501 Smith	262

Brunswick-Balke-Collender Co., 623 S. Wabash Av.	460
--	-----

OFFICE FIXTURES—STEEL.

Federal Steel Fixture Co., 4545 Homer	74
---------------------------------------	----

OIL BURNERS.

Steam Corporation, 215 N. Michigan	414
------------------------------------	-----

OPERA CHAIRS.

Rowles, E. W. A., Co., 2345 S. La Salle	576
---	-----

ORNAMENTAL PATTERNS FOR METAL CASTINGS.

Architectural Dec. Co., 1600 S. Jefferson	508
Dux, Joseph, 2112 W. Van Buren St.	508

PACKAGE CONVEYORS.

Olson, Samuel, & Co., 2418 Bloomingdale	14
Weller Mfg. Co., 1856 N. Kostner Av.	86

PACKING HOUSE EQUIPMENT.

Mechanical Mfg. Co., Loomis and Pershing Rd.	60
--	----

PAINT—ACID PROOF.

Semet Solvay Co., 332 S. Michigan Av.	490
---------------------------------------	-----

PAINT—CEMENT.

Garden City Sand Co., 133 W. Wash.	394
Moore, Benj., & Co., 415 N. Green St.	490
Semet Solvay Co., 332 S. Michigan Av.	490
Vitrifyx Co., 2526 W. Congress St.	350

PAINT—COLD WATER.

Johns-Manville Co., 18th & Mich.	8
Lucas, John, & Co., 1362 W. 37th St.	478
Moore, Benj., & Co., 415 N. Green St.	490
Nelson, P. W., Inc., 2834 S. Loomis St.	490

PAINT—DAMP RESISTING.

Am. Tar Products Co., 208 S. La Salle	268
Barrett Co., 10 S. La Salle St.	22
Crescent Sales & Mfg. Co., 110 S. Dear.	24
Garden City Sand Co., 133 W. Wash.	394
Scofield, Evans & Co., 508 S. Dearborn	346
Vitrifyx Co., 2526 W. Congress St.	350

PAINT—FIREPROOF.

Am. Tar Products Co., 208 S. La Salle	268
Barrett Co., 10 S. La Salle St.	22
Johns-Manville Co., 18th & Mich.	8
Moore, Benj., & Co., 415 N. Green St.	490
Scofield, Evans & Co., 508 S. Dearborn	346
Semet Solvay Co., 332 S. Michigan Av.	490

PAINT—GRAPHITE.

Lucas, John, & Co., 1362 W. 37th St.	478
Moore, Benj., & Co., 415 N. Green St.	490

PAINT—IRON.

Am. Tar Products Co., 208 S. La Salle	268
Barrett Co., 10 S. La Salle St.	22
Crescent Sales & Mfg. Co., 110 S. Dear.	24
Garden City Sand Co., 133 W. Wash.	394
Lucas, John, & Co., 1362 W. 37th St.	478
Moore, Benj., & Co., 415 N. Green St.	490
Ohmlac Paint & Rfg. Co., 140 S. Dearborn	478
Scofield, Evans & Co., 508 S. Dearborn	346
Semet Solvay Co., 332 S. Michigan Av.	490

PAINT FOR ARCHITECTURAL AND SUBMERGED STEEL.

Semet Solvay Co., 332 S. Michigan Av.	490
---------------------------------------	-----

PAINTS—MIXED

Hockaday Co., 1823 Carroll Av.	490
Hooker, H. M., Glass & Paint Co., 651 W. Washington Bl.	500
Lucas, John, & Co., 1362 W. 37th St.	478
Moore, Benj., & Co., 415 N. Green St.	490

PAINTS—ROOFING.

Am. Tar Products Co., 208 S. La Salle	268
Barrett Co., 10 S. La Salle St.	22
Bird & Son, 1472 W. 76th St.	26
Cent. Asbestos & Mag. Co., 214 W. Grand	342
Garden City Sand Co., 133 W. Wash.	394
Johns-Manville Co., 18th & Mich.	8
Krez, Paul J., Co., 444 N. La Salle St.	342
Lehon Co., 44th & Oakley Av.	66
Lucas, John, & Co., 1362 W. 37th St.	478
Moore, Benj., & Co., 415 N. Green St.	490
Ohmlac Paint & Rfg. Co., 140 S. Dearborn	478
Standard Asbestos Mfg. Co., 816 W. Lake	342
Watson, H. F. Co., 5331 S. Western Av.	342

PAINTING CONTRACTORS.

Brennan, J. M., & Co., 651 W. 43rd St.	486
--	-----

Ebert, Theo., Co., 914 Diversey Pkwy	484	Hoffmann & Billings Mfg. Co., Milwaukee, Wis.	464
Gleich, T. C., Co., 2850 Broadway	480	Imperial Brass Mfg. Co., 1200 W. Harr.	458
Nelson, W. P., Co., 614 S. Michigan Av.	480	Kellogg Mackay Co., 419 W. 18th St.	404
Noelle, J. B., Co., 702 N. Wells St.	488	Mott, J. L., Iron Wks., 104 S. Michigan	456
Olson, Herman, Dec. Co., 911 Chgo. Av., Evanston, Ill.	488	Standard Sanitary Mfg. Co., 14 N. Peoria	454
Olson, Hermann Co., 2568 N. Clark St.	482	Wolff Mfg. Co., 225 N. Hoyne Av.	450
Plamondon & Gabriel Co., 308 N. Mich.	484	PLUMBING, GASFITTING AND SEWER-AGE.	
Rising Dec. Co., 527 S. Peoria St.	486	Am. Heat. & Plumb. Corp., 189 N. Clark	428
Spiertling & Linden, 1216 Michigan Av.	488	Corboy, M. J., Co., 178 W. Randolph St.	468
Sullivan, J. P., 4515 Indiana Av.	482	Daly, J. J., 408 N. Wells St.	468
Warnecke, C. E., Co., 4043 Elston Av.	488	Dwyer & Co., 31 W. Illinois St.	432
PAINT MILLS & MACHINERY.		Hanley & Co., 3444 Forest Av.	440
Kaestner & Hecht Co., 500 S. Throop St.		Hulbert & Dorsey, 208 N. Wells St.	468
Inside Back Cover		Murphy Plumbing Co., 23 E. Congress	468
PARTITION & CEILING CONSTRUCTION.		Nacey, P., Co., 927 S. State St.	436
Simplex Steel Prod. Co., 1146 Roscoe St.	502	Nilson Bros., 3222 N. Halsted St.	430
PARTITION AND FLOOR DEADENING.		Nilson, G. Albin, & Co., 155 N. Clark St.	470
Stevens Partition & Floor Deadener Co., 175 W. Washington	346	Noble & Thumm, 2313 Lincoln Av.	470
PARTITIONS AND CEILINGS—SOUND PROOF.		Watson, W. W., 708 Carpenter St.	470
Simplex Steel Prod. Co., 1146 Roscoe St.	502	POST CAPS.	
Stevens Partition & Floor Deadener Co., 175 W. Washington	346	Castle, A. M., & Co., 715 N. Morgan St.	370
PARTITION TILE. (See Hollow Tile)		Cyclone Fence Co., 39 S. La Salle St.	62
PARTITIONS—TOILET.		Reder Fdry. Co., 3535 S. Oakley Av.	380
Vitrolite Co., 133 W. Washington St.	44	Smith, F. P., W. & I. Wks., 2346 Clybourn	384
PILING—CONCRETE.		POWER EQUIPMENT.	
Raymond Con. Pile Co., 111 W. Monroe	12	Stannard Power Equipment Co., 53 W. Jackson	448
PILING—WOOD.		POWER PLANTS.	
Lake Superior Piling Co., 961 W. 22nd	302	Am. Heat. & Plumb. Corp., 189 N. Clark	428
PIPE AND BOILER COVERING.		Arcade Steam Heater, 126 W. Kinzie	90
Cent. Asbestos & Mag. Co., 214 W. Grand	342	Baker & Smith Co., 408 N. Wells St.	436
Garden City Sand Co., 133 W. Wash.	394	Claffey, E. J., Co., 350 N. Clark St.	432
Johns-Manville Co., 18th & Mich.	8	Douglass, Thos. J., & Co., 441 N. Dearborn	440
Krez, Paul J., Co., 444 N. La Salle St.	342	Dwyer & Co., 31 W. Illinois St.	432
Standard Asbestos Mfg. Co., 816 W. Lake	342	Gallaher & Speck, 215 W. Congress St.	436
Watson, H. F. Co., 5331 S. Western Av.	342	Glennon-Bielke Co., 546 W. Lake St.	432
PLATE GLASS—SETTING.		Gordon, Robert, Inc., 622 W. Monroe	412-428
Brasco Mfg. Co., 5035 S. Wabash Av.	260	Graves Heating Co., 162 N. Desplaines	434
Kawneer Co., 111 W. Washington	48	Hanley & Co., 3444 Forest Av.	440
Zouri Drawn Metals Co., Chgo Hghts., Ill.	496	Henrich, George A., Co., 5650 Broadway	438
PLASTER.		Herlihy, J. J., 751 W. Van Buren St.	432
Am. Cement Plaster Co., 111 W. Wash.	20	Johnson, C. W., Inc., 644 Washington Bl.	438
U. S. Gypsum Co., 205 W. Monroe St.	36	Kaestner & Hecht Co., 500 S. Throop St.	
PLASTER BASE.		Inside Back Cover	
MacAdams & Call, 111 W. Washington	350	Kehm Bros. Co., 15 W. Kinzie St.	430
PLASTER BOARD.		Kirk, Geo. H., 6711 Wentworth Av.	438
Am. Cement Plaster Co., 111 W. Wash.	20	Mehring & Hanson Co., 118 N. Franklin	428
Bird & Son, 1472 W. 76th St.	26	Nacey, P. Co., 927 S. State St.	436
U. S. Gypsum Co., 205 W. Monroe St.	36	Phillips, Getschow, Co., 128 W. Kinzie St.	420
PLASTER BOND.		Pope, Wm. A., 26 N. Jefferson St.	434
Advance Waterproof Cement Co., 15 E. Van Buren St.	402	Prentice, L. H., Co., 328 Sherman St.	430
Ohmlac Paint & Rfg. Co., 140 S. Dearborn	478	Rigby, Ben, 545 W. Lake St.	434
PLASTER—ORNAMENTAL.		Schampel & Dougherty, 173 W. Wash.	440
Architectural Dec. Co., 1600 S. Jefferson	508	PRESSURE AND GRAVITY FILTERS.	
Dux, Joseph, 2112 W. Van Buren St.	508	Greer Chemical Co., 20 W. Jackson Bl.	94
PLASTERING CONTRACTORS.		PUMPS.	
Balhatchet, Wm., Co., 58 W. Wash.	504	Am. Steam Pump Co., 53 W. Jackson	448
Goss & Guise, 189 W. Madison St.	506	Chicago Pump Co., 2336 Wolfram St.	426
Lennox-Haldeman Co., 208 S. La Salle	504	Nash Engr. Co., 53 W. Jackson Bl.	448
McNulty Bros. Co., 1028 W. Van Buren	504	Yeomans Bros., 1432 Dayton St.	448
Parent, N. J., Co., 5 S. Wabash Av.	506	PUMPS—AUTOMATIC AND HYDRAULIC.	
Sutton Plastering Co., 25 E. Jackson Bl.	506	Am. Steam Pump Co., 53 W. Jackson	448
Williams, Wm., 2841 Edgewood Av.	506	Chicago Pump Co., 2336 Wolfram St.	426
Zander-Reum Co., 7 S. Dearborn	504	Nash Engr. Co., 53 W. Jackson Bl.	448
PLASTERING MATERIAL.		PUMPS—STEAM.	
Am. Cement Plaster Co., 111 W. Wash.	20	Am. Steam Pump Co., 53 W. Jackson	448
Consumers Co., 111 W. Washington	114	Chicago Pump Co., 2336 Wolfram St.	426
Garden City Sand Co., 133 W. Wash.	394	PUMPS—VACUUM.	
Rosing, Astrid S., 111 W. Monroe St.	116	Nash Engr. Co., 53 W. Jackson Bl.	448
U. S. Gypsum Co., 205 W. Monroe St.	36	PUMPS—ELECTRIC.	
PLASTIC RELIEF.		Chicago Pump Co., 2336 Wolfram St.	426
Architectural Dec. Co., 1600 S. Jefferson	508	Yeomans Bros., 1432 Dayton St.	448
Dux, Joseph, 2112 W. Van Buren St.	508	PUMPING MACHINERY.	
PLUMBING SUPPLIES.		Am. Steam Pump Co., 53 W. Jackson	448
Clow, Jas. B., & Sons, 544 S. Franklin	452	Chicago Pump Co., 2336 Wolfram St.	426
		Nacey, P., Co., 927 S. State St.	436
		Yeomans Bros., 1432 Dayton St.	448
		RADIATORS.	
		Kewanee Boiler Co., 328 W. Washington	406

RADIATOR SHIELDS.

Hayward R. B. Co., 849 W. Ohio St.	444
Mellish-Hayward Co., 213 W. Austin Av.	446
Prentice, L. H. Co., 328 Sherman St.	430

RADIATOR VALVES—PACKLESS.

Dole Valve Co., 1923 Carroll Av.	434
Dunham, C. A. Co., 230 E. Ohio St.	416

REAL ESTATE LOANS.

Baird & Warner, 29 S. La Salle St.	56
Corn Exc. Nat'l Bank, 134 S. La Salle St.	52
Greenebaum Sons Bank & Trust Co., 9 S. La Salle St.	302

REFLECTORS—DIRECT & INDIRECT.

Beardslee Chandelier Mfg. Co., 216 S. Jefferson St.	316
Luminous Unit Co., 108 S. La Salle	318
Pearlman, Victor A., & Co., 533 S. Wabash Av.	306
Reflectolyte Co., 914 Pine St., St. Louis, Mo.	320

REFRIGERATORS.

Brunswick-Balke-Collender Co., 623 S. Wabash Av.	460
Matot, D. A., 1538 Montana St.	266
McCray Refrigerator Co., 1000 S. Michigan Av. and Kendallville, Ind.	2
Pick, Albert, & Co., 212 W. Randolph	80-82

REFRIGERATED ROOMS INSULATION.

Mechanical Mfg. Co., Loomis & Pershing Rd.	60
Union Insul. & Constr. Co., 20 W. Jackson	40
United Cork Companies, 110 S. Dearborn	68

REFRIGERATING MACHINERY.

Wittenmeier Mch Co., 850 N. Spaulding Av.	120
---	-----

REGULATORS—DAMPER.

Davis, G. M., Reg. Co., 428 Milwaukee	442
Dunham, C. A. Co., 230 E. Ohio St.	416

REGULATORS—HEAT—STEAM—AIR—WATER.

Davis, G. M., Reg. Co., 428 Milwaukee	442
Dunham, C. A. Co., 230 E. Ohio St.	416
Hoffmann & Billings Mfg. Co., Milwaukee, Wis.	464
Johnson Service Co., 177 N. Dearborn	442

REINFORCED CONCRETE CONSTRUCTION.

Barton Spider-Web Sys., 3426 S. Kedzie	366
--	-----

REINFORCING BARS—CONCRETE.

Am. Steel & Wire Co., 208 S. La Salle	366
Calumet Steel Co., 208 S. La Salle St.	378
Castle, A. M., & Co., 715 N. Morgan St.	370
Dean, Olney J., & Co., 179 W. Wash.	388
Kalman, Paul J., Co., 22 W. Monroe St.	356
North Western Expanded Metal Co., 407 S. Dearborn St.	352
Scully Steel & Iron Co., 2364 S. Oakley	370
Smith, F. P., W. & I. Wks., 2346 Clybourn	384

REINFORCING STEEL FABRIC.

(See Steel Fabric for Reinforcing Concrete)

REMODELING AND REPAIR WORK.

Meyne, Gerhardt F., 127 N. Dearborn St.	300
Mutual Constr. Co., 2532 Warren Av.	300

ROLLING PARTITIONS—WOOD AND STEEL.

Dodge, H. B., & Co., 332 S. Michigan Av.	262
--	-----

ROOF TRUSSES.

McKeown Bros. Co., 112 W. Adams	280
---------------------------------	-----

ROOFING CONTRACTORS.

Moore, Edw., Rfg. Co., 133 W. Wash.	92
Powell, M. W., Co., 140 S. Dearborn St.	340

ROOFING—CORRUGATED IRON.

American Bridge Co., 208 S. La Salle	354
Kenwood Bridge Co., 1st Nat. Bk. Bldg.	376
Morava Constr. Co., 122 S. Michigan	376
Scully Steel & Iron Co., 2364 S. Ashland	370

ROOFING—MATERIALS.

Amalgamated Rfg. Co., 431 S. Dearborn	260
Barrett Co., 10 S. La Salle St.	22
Beckman-Dawson Rfg. Co., 19 S. La Salle	340
Bird & Son, 1472 W. 76th St.	26

Johns-Manville Co., 18th & Michigan	8
Lehon Co., 44th & Oakley Ave.	66
Moore, Edw., Rfg. Co., 133 W. Wash.	92
Watson, H. F. Co., 5331 S. Western Av.	342

ROOFING PAPER.

Amalgamated Rfg. Co., 431 S. Dearborn	260
Barrett Co., 10 S. La Salle St.	22
Bird & Son, 1472 W. 76th St.	26
Beckman-Dawson Rfg. Co., 19 S. La Salle	340
Cent. Asbestos & Mag. Co., 214 W. Grand	342
Johns-Manville Co., 18th and Michigan	8
Krez, Paul J., Co., 444 N. La Salle St.	342
Lehon Co., 44th & Oakley Ave.	66
Moore, Edw., Rfg. Co., 133 W. Wash.	92
Standard Asbestos Mfg. Co., 816 W. Lake	342
Watson, H. F. Co., 5331 S. Western Av.	342

ROOFING TILE.

Federal Cement Tile Co., 110 S. Dearborn	16
Ludowici-Celadon Co., 104 S. Michigan	70

ROPE TRANSMISSION MACHINERY.

Elevator Co. of Am., 190 N. State St.	30
Kaestner & Hecht Co., 500 S. Throop St.	
Inside Back Cover	
Olson, Samuel, & Co., 2418 Bloomingdale	14
Otis Elevator Co., 600 W. Jackson Bl.	28
Pitt Engineering Co., 120 W. Kinzie	34
Wheeler Elevator Co., 1100 Washington	32
Weller Mfg. Co., 1856 N. Kostner Av.	86

RUGS AND CARPETS—ORIENTAL AND DOMESTIC.

Pick, Albert & Co., 212 W. Randolph	80-82
-------------------------------------	-------

SAND AND GRAVEL.

Am. Sand & Gravel Co., 133 W. Wash.	294
Brownell Improve. Co., 133 W. Wash.	394
Consumers Co., 111 W. Washington	114
Dee, Wm. E., Co., 30 N. La Salle St.	394
Garden City Sand Co., 133 W. Wash.	394
Rosing, Astrid S., 111 W. Monroe St.	116

SASH, DOORS AND BLINDS.

Curtis Door & Sash Co., 1414 S. Western	144
Morgan Sash & Door Co., 2287 Blue Island Av.	
Inside Front Cover	
Nollau & Wolff Mfg. Co., 1705 Fullerton	344

SASH OPERATORS.

Babcock Bros. Co., 140 S. Dearborn	96-362
Dean, Olney J., & Co., 179 W. Wash.	388
Detroit Steel Prod. Co., 111 W. Wash.	38
Lupton, David, Sons Co., 28 E. Jackson	50
Metallic Sash Operator Co., St. Louis, Mo.	76

SASH—STEEL.

Babcock Bros. Co., 140 S. Dearborn	96-362
Dean, Olney J., & Co., 179 W. Wash.	388
Detroit Steel Prod. Co., 111 W. Wash.	38
Lupton, David, Sons Co., 28 E. Jackson	50

SCALE MODELS OF BUILDINGS.

Architectural Dec. Co., 1600 S. Jefferson	508
Dux, Joseph, 2112 W. Van Buren St.	508

SCHOOL FURNITURE.

Rowles, E. W. A., Co., 2345 S. La Salle	576
---	-----

SCREENS—WINDOW AND DOOR.

Chamberlin Metal Weather Strip Co., 626 S. Dearborn	264
Wolff, Geo. & Co., 190 N. State St.	258

SECURITY BONDS FOR CONTRACTORS.

Builders & Mfrs. Mutual Casualty Co., 133 W. Washington St.	54
Sherman & Ellis, Inc., 11 S. La Salle St.	264

SEATING—PUBLIC BUILDINGS.

Rowles, E. W. A., Co., 2345 S. La Salle	576
---	-----

SEPARATORS STEAM AND OIL.

Webster, Warren & Co., 53 W. Jackson	442
--------------------------------------	-----

SHELVES—STEEL FOR FACTORIES.

Durand Steel Locker Co., 76 W. Monroe	18
Federal Steel Fixture Co., 4545 Homer	74

SCUPPERS & FLOOR DRAINS.

Dean, Olney, J., & Co., 179 W. Wash.	388
--------------------------------------	-----

SEATS—CLOSET.

Brunswick-Balke-Collender Co., 623 S. Wabash Av.	460
--	-----

SELF CLOSING COCKS.

Imperial Brass Mfg. Co., 1200 W. Harr. 458

SEWER PIPE.Dee, Wm. E., Co., 30 N. La Salle St. 394
Rosing, Astrid S., 111 W. Monroe St. 116**SEWER WORK.**

Nacey, P., Co., 927 S. State St. 436

SEWAGE EJECTORS AND BILGE PUMPS.Chicago Pump Co., 2336 Wolfram St. 426
Yeomans Bros., 1432 Dayton St. 448**SHADE EQUIPMENT FOR INDUSTRIAL BUILDINGS.**

Walger Awning Co., 561 W. Monroe St. 4

SHEET METAL WORKS.Gordon, Robert, Inc., 622 W. Monroe 412-428
Gustafson, K. A., 2114 N. Springfield 444
Haines Co., 1933 W. Lake St. 444
Hayward, R. B. Co., 849 W. Ohio St. 444
Mechanical Mfg. Co., Loomis & Pershing Rd. 60
Mellish-Hayward Co., 213 W. Austin Av. 446
Monarch Vent. Co., 1338 Sedgwick 446
Narowetz Heat. & Vent. Co., 223 W. Lake 444**SHINGLES.**Burns, John E., Lbr. Co., 700 W. Chicago 104
Hettler, Herman H. Lbr. Co., 2601 Elston 106
Hines, Ed. Lumber Co., 2431 S. Lincoln 100
Mears-Slayton Bldg. Mat. Co., Clark and Howard Av. 112
Pilsen Lbr. Co., 2201 Lafin St. 110
Rittenhouse & Embree Co., 3500 S. Racine 108
Thornton Clancy Lbr. Co., 2315 Elston 102**SHINGLES—FIREPROOF.**Amalgamated R'fg. Co., 431 S. Dearborn 260
Am. Tar Products Co., 208 S. La Salle 268
Barrett Co., 10 S. La Salle St. 22
Beckman Dawson R'fg. Co., 19 S. La Salle 340
Bird & Son, 1472 W. 76th St. 26
Johns-Manville Co., 18th & Mich. 8
Lehon Co., 44th & Oakley Av. 66
Watson, H. F. Co., 5331 S. Western Av. 342**SHINGLE STAINS.**Am. Tar Products Co., 208 S. La Salle 268
Barrett Co., 10 S. La Salle St. 22
Cabot, Samuel, 24 W. Kinzie St. 340
Lehon Co., 44th & Oakley Av. 66
Lucas, John & Co., 1362 W. 37th St. 478
Ohmlac Paint & R'fg. Co., 140 S. Dearborn 478
Moore, Benj. & Co., 415 N. Green St. 490**SHORING CONTRACTORS.**

Friestedt, L. P. Co., Tribune Bldg. 294

SHOWER MIXERS.

Hoffmann & Billings Mfg. Co., Mil., Wis. 464

SHOWERS.

Hoffmann & Billings Mfg. Co., Mil., Wis. 464

SIDEWALK DOORS.Am. 3 Way-Luxfer Prism Co., Cicero, Ill. 500
Badger Wire & Iron Co., Mil., Wis. 390
Hill, O. H. Co., 2253 St. Paul Av. 374
Morlite Co., The, 366 W. Ohio St. 498
Smith, F. P. W. & I. Wks., 2346 Clybourn 384
Western Iron Const. Co., 4906 N. Clark 390**SIDEWALK AND VAULT LIGHTS.**Am. 3 Way-Luxfer Prism Co., Cicero, Ill. 500
Morlite Co., The, 366 W. Ohio St. 498**SKYLIGHTS.**Am. 3 Way-Luxfer Prism Co., Cicero, Ill. 500
Babcock Bros. Co., 140 S. Dearborn 96-362
Detroit Steel Prod. Co., 111 W. Wash. 38
Federal Cement Tile Co., 110 S. Dear. 16
Gustafson, K. A., 2114 N. Springfield 444
Lupton, David, Sons Co., 28 E. Jackson 50**SLUICE GATES.**

Jenkins Bros., 646 W. Washington Bl. 422

SMOKE STACK LININGSCent. Asbestos & Mag. Co., 214 W. Grand 342
Krez, Paul J., Co., 444 N. La Salle St. 342
Standard Asbestos Mfg. Co., 816 W. Lake 342**SOIL AND SOD.**

Peterson Nursery, 30 N. La Salle St. 340

SPIRAL CHUTES.Olson, Samuel & Co., 2418 Bloomingdale 14
Weller Mfg. Co., 1856 N. Kostner Av. 86**SPRINKLER SYSTEMS.**Haggarty Fire Protection Co., 327 S. La Salle 268
Ill. Malleable Iron Co., 1801 Diversey 426
Nacey, P. Co., 927 S. State St. 436
New Era Fire Protection Engrs., 716 W. Madison St. 446**STAINS.**Pratt & Lambert, Inc., 320 W. 26th St. 474
Standard Cooper-Bell Co., 2606 Federal 472**STAIRS AND RAILINGS.**Anderson & Lind Mfg. Co., 2127 Iowa St. 98
Baumann, F. O. Mfg. Co., 1501 Smith 262**STAIRS—IRON AND BRONZE.**Castle, A. M. & Co., 715 N. Morgan St. 370
Duffin Iron Co., 4837 S. Kedzie Av. 372
Federal Iron Wks., 30 N. La Salle St. 380
Guaranty Iron & Steel Co., 2847 W. Lake 382
Halsted, Joseph, Co., 1233 W. Randolph 380
Johnson-Meier Co., 155 Wendell St. 360
Manton & Smith Co., 1709 W. Austin 382
Reuter Brothers, 5814 Wood St. 384
Smith, F. P. W. & I. Wks., 2346 Clybourn 384
Standard Fire Escape Co., 23 S. Western 374
Sullivan-Korber Co., 2437 W. 21st Pl. 382
Woodbridge Orntl. Iron Co., 1519 Altgeld 358**STAND PIPES.**Guaranty Iron & Steel Co., 2847 W. Lake 382
Hanke Iron & Wire Wks., 840 N. Albany 380
Nacey, P., Co., 927 S. State St. 436**STEAM HEATING.**

(See Heating—Hot Water and Steam)

STEAM GENERATORS.

Kewanee Boiler Co., 328 W. Washington 406

STEAM SPECIALTIESDavis, G. M. Reg. Co., 428 Milwaukee 442
Jenkins Bros., 646 W. Washington Bl. 422
Johnson Service Co., 177 N. Dearborn 442**STEEL BARS FOR REINFORCING CONCRETE.**

(See Reinforcing Bars—Concrete)

STEEL FABRIC FOR REINFORCING CONCRETE.Am. Steel & Wire Co., 208 S. La Salle 366
Dean, Olney J. & Co., 179 W. Washington 388
Consolidated Expanded Metal Co., 562 W. Monroe St. 368
North Western Expanded Metal Co., 407 S. Dearborn St. 352**STEEL LUMBER.**

Natl. Pressed Steel Co., Massillon, O. 364

STONE COATING.Cement Gun Constr. Co., 537 S. Dearborn 512
Garden City Sand Co., 133 W. Wash. 394
Ohmlac Paint & R'fg. Co., 140 S. Dear. 478**STONE-CUT BUILDING.**Cent. Oolitic Stone Co., 2126 S. Kedzie 72
Indiana Quarries Co., 112 W. Adams St. 510**STONE FRONTS—METAL CONSTRUCTION.**Brasco Mfg. Co., 5035 S. Wabash Av. 260
Hooker, H. M. Glass & Paint Co., 651 W. Washington 500
Kawneer Co., 111 W. Washington 48
Tyler & Hippach, 366 W. Ohio St. 498
Zouri Drawn Metals Co., Chgo. Heights, Ill. 496**STORE AND OFFICE FIXTURES.**Anderson & Lind Mfg. Co., 2127 Iowa St. 98
Baumann, F. O. Mfg. Co., 1501 Smith 262
Brunswick-Balke-Collender Co., 623 S. Wabash Av. 460
Pick, Albert & Co., 212 W. Randolph 80-82**STOVES—GAS.**Peoples Gas Light & Coke Co., 122 S. Michigan 338
Pick, Albert & Co., 212 W. Randolph 80-82**STRAINERS—SUCTION.**

Dunham, C. A. Co., 230 E. Ohio St. 416

STRUCTURAL IRON AND STEEL.

American Bridge Co., 208 S. La Salle	354
Badger Wire & Iron Co., Mil., Wis.	390
Belter's A. Sons, 2301 Ward St.	376
Butler St. Fdry. & Iron Co., 3424 Normal	384
Duffin Iron Co., 4837 S. Kedzie Av.	372
Federal Iron Wks., 30 N. La Salle St.	380
Halsted, Joseph, Co., 1233 W. Randolph	380
Holmes, Pyott & Co., 159 N. Jefferson	376
Kenwood Bridge Co., 1st Nat. Bk. Bldg.	376
Morava Constr. Co., 122 S. Michigan	376
Natl. Pressed Steel Co., Massillon, O.	364
Reder Fdry. Co., 3536 S. Oakley Av.	380
Scully Steel & Iron Co., 2364 S. Ashland	370
Smith, F. P. W. & I. Wks., 2346 Clybourn	384
Union Fdry. Wks., 38 S. Dearborn St.	384
Vierling Steel Wks., 313 W. 23rd St.	384
Western Iron Constr. Co., 4906 N. Clark	390

STUCCO BASE.

MacAdams & Call, 111 W. Washington	350
------------------------------------	-----

STUCCO.

Am. Magnesia Pro. Co., 5746 Roosevelt Rd. 6	
Cement Gun Constr. Co., 537 S. Dearborn	512
Garden City Sand Co., 133 W. Wash.	394
McCarthy, W. H., 133 W. Washington	394

SURETY BONDS.

Builders & Mfrs. Mutual Casualty Co., 133 W. Washington St.	54
Sherman & Ellis, Inc., 11 S. La.Salle St.	264

SURVEYORS—CITY AND COUNTY.

Greeley-Howard-Norlin Co., 127 N. Dearborn St.	304
Jones, W. D., 8 S. Dearborn St.	304
Kramer, Wm., 8 S. Dearborn St.	304
Silander, A. I., 30 N. La Salle St.	304

SURVEYORS' SUPPLIES.

Am. Blue Print Paper Co., 445 Plymouth	508
Crofoot, Nielsen & Co., 172 W. Wash.	508

TABLETS AND NAMEPLATES—IRON AND BRONZE.

Halsted, Joseph, Co., 1233 W. Randolph	380
Johnson-Meier Co., 155 Wendell St.	360
Manton & Smith Co., 1709 W. Austin Av.	382
Newman Mfg. Co., Cincinnati, O.	390
Reuter Brothers, 5814 Wood St.	384
Smith, F. P. W. & I. Wks., 2346 Clybourn	384
Sullivan-Korber Co., 2437 W. 21st Pl.	382
Woodbridge Orntl. Iron Co., 1519 Altgeld	358

TANKS—IRON AND STEEL.

Alberene Stone Co., 214 N. Clinton St.	446
Kaestner & Hecht Co., 500 S. Throop St.	
Inside Back Cover	
Kewanee Boiler Co., 328 W. Washington	406
Mechanical Mfg. Co., Loomis & Pershing Rd.	60

TANKS—WOOD.

Ajax Tank & Tower Co., 1407 W. 37th St.	390
---	-----

TELEPHONE INSTALLATION.

Ill. Bell Telephone Co., 212 W. Wash.	348
---------------------------------------	-----

TELEPHONES FOR PUBLIC AND PRIVATE USE.

Ill. Bell Telephone Co., 212 W. Wash.	348
---------------------------------------	-----

TEMPERATURE REGULATORS.

Ill. Malleable Iron Co., 1801 Diversey	426
Johnson Service Co., 177 N. Dearborn	442
Webster, Warren & Co., 53 W. Jackson	442

TERRA COTTA.

Midland Terra Cotta Co., 133 W. Wash.	42
Northwestern Terra Cotta Co., 2525 Clybourn Av.	10

THERMOSTATS.

Johnson Service Co., 177 N. Dearborn	442
--------------------------------------	-----

TILE—CERAMIC, ETC.

Interior Tiling Co., 21 E. Van Buren St.	396
Marthens, Chester N., Marble Co., 53rd and Wallace Sts.	392
Weary & Beck, 1732 S. Michigan	396

TILE—CORK.

United Cork Companies, 110 S. Dearborn	68
--	----

TILE—FLOORS.

Interior Tiling Co., 21 E. Van Buren St.	396
Marthens, Chester N., Marble Co., 53rd and Wallace Sts.	392
Weary & Beck, 1732 S. Michigan	396

TILE—GYPSUM.

Am. Cement Plaster Co., 111 W. Wash.	20
L. S. Gypsum Co., 205 W. Monroe St.	36

TILE—HOLLOW

Barron Brick Co., 7 S. Dearborn	398
Dee, Wm. E. Co., 30 N. La Salle St.	394
Ill. Fire-Proof Constr. Co., 209 S. La Salle St.	400
Nat. Fire Proofing Co., 2610 Shields Av.	400
Rosing, Astrid S., 111 W. Monroe St.	116

TILE—ROOF.

Federal Cement Tile Co., 110 S. Dear.	16
Ludowici-Celadon Co., 104 S. Michigan	70

TILE WAJNSCOTING.

Interior Tiling Co., 21 E. Van Buren St.	396
Marthens, Chester N., Marble Co., 53rd and Wallace Sts.	392
Weary & Beck, 1732 S. Michigan	396

TOILET CABINETS AUTOMATIC FOR PAPER.

Utility Service Assn., 3100 Carroll Av.	466
---	-----

TOILET PARTITIONS.

Vitrolite Co., 133 W. Washington St.	44
--------------------------------------	----

TRAPS—STEAM.

Davis, G. M. Reg. Co., 428 Milwaukee	442
Dunham, C. A. Co., 230 E. Ohio St.	416
Johns-Manville Co., 18th & Michigan	8

TREADS—SAFETY.

Castle, A. M. & Co., 715 N. Morgan St.	370
Scully Steel & Iron Co., 2364 S. Ashland	370

TRUSSES—WOOD.

McKeown Bros. Co., 112 W. Adams St.	280
-------------------------------------	-----

TUBES—BOILER.

Scully Steel & Iron Co., 2364 S. Ashland	370
--	-----

TUBING—METAL.

Brasco Mfg. Co., 5035 S. Wabash Av.	260
Kawneer Co., 111 W. Washington	48

TURN TABLES.

American Bridge Co., 208 S. La Salle	354
Kenwood Bridge Co., 1st Nat. Bk. Bldg.	376

UBINAL STALLS.

Alberene Stone Co., 214 N. Clinton St.	446
Clow, Jas. B. & Sons, 544 S. Franklin	452
Imperial Brass Mfg. Co., 1200 W. Harr.	458
Mott, J. L. Iron Wks., 104 S. Michigan	456
Standard Sanitary Mfg. Co., 14 N. Peoria	454
Wolff Mfg. Co., 225 N. Hoyne Av.	450

VALVES.

Dole Valve Co., 1923 Carroll Av.	434
Jenkins Bros., 646 W. Washington Bl.	422

VALVES—AIR.

Davis, D. M., Reg. Co., 428 Milwaukee	442
Dole Valve Co., 1923 Carroll Av.	434
Jenkins Bros., 646 W. Washington Bl.	422

VALVES—BACK PRESSURE.

Davis, G. M. Reg. Co., 428 Milwaukee	442
Dole Valve Co., 1923 Carroll Av.	434
Jenkins Bros., 646 W. Washington Bl.	422

VALVE MANUFACTURERS.

Davis, G. M. Reg. Co., 428 Milwaukee	442
Dole Valve Co., 1923 Carroll Av.	434
Jenkins Bros., 646 W. Washington Bl.	422

VALVES—PACKLESS.

Dole Valve Co., 1923 Carroll Av.	434
Dunham, C. A. Co., 230 E. Ohio St.	416

VALVES—PRESSURE REDUCING.

Dole Valve Co., 1923 Carroll Av.	434
Dunham, C. A. Co., 230 E. Ohio St.	416
Jenkins Bros., 646 W. Washington Bl.	422

VALVES—REGULATING.

Davis, G. M. Reg. Co., 428 Milwaukee	442
Dole Valve Co., 1923 Carroll Av.	434
Dunham, C. A. Co., 230 E. Ohio St.	416

VALVES—VACUUM.

Davis, G. M. Reg. Co., 428 Milwaukee	442
Dunham, C. A. Co., 230 E. Ohio St.	416
Webster, Warren & Co., 53 W. Jackson	442

VALVE—VENT—AIR.

Dunham, C. A. Co., 230 E. Ohio St.	416
------------------------------------	-----

VALVES—WATER MIXERS.

Hoffmann & Billings Mfg. Co., Mil., Wis.	464
--	-----

VARNISH MANUFACTURERS.

Moore, Benj. & Co., 415 N. Green St.	490
Pratt & Lambert, Inc., 320 W. 26th St.	474
Standard Cooper-Bell Co., 2606 Federal	472

VENETIAN BLINDS.

Dodge, H. B. & Co., 332 S. Michigan Av.	262
---	-----

VENTILATORS.

Am. Blower Co., 140 S. Dearborn St.	420
Babcock Bros. Co., 140 S. Dearborn	96-362
Ilg Electric Ventilating Co., 2834 N. Crawford Av.	424
Imperial Brass Mfg. Co., 1200 W. Harr.	458
N. Y. Blower Co., 608 S. Dearborn St.	418

VENTILATING SYSTEMS.

Am. Heat. & Plumb. Corp., 189 N. Clark	428
Arcade Steam Heat. Co., 126 W. Kinzie	90
Baker & Smith Co., 408 N. Wells St.	436
Claffey, E. J. Co., 350 N. Clark St.	432
Douglass, Thos. J. & Co., 441 N. Dear.	440
Dwyer & Co., 31 W. Illinois St.	432
Gallaher & Speck, 215 W. Congress St.	436
Glennon-Bielke Co., 546 W. Lake St.	432
Gordon, Robert, Inc., 622 W. Monroe	412-428
Graves Heating Co., 162 N. Desplaines	434
Gustafson, K. A., 2114 N. Springfield	444
Haines Co., 1933 W. Lake St.	444
Hanley & Co., 3444 Forest Av.	440
Hayward, R. B. Co., 849 W. Ohio St.	444
Henrich, George A. Co., 5650 Broadway	438
Herlihy, J. J., 751 W. Van Buren St.	432
Holer, Wm. V. & Co., 701 N. Wells St.	440
Johnson, C. W., Inc., 644 Washington Bl.	438
Kehm Bros. Co., 15 W. Kinzie St.	430
Kilander, A. & Co., 126 S. Clinton St.	438
Kirk, Geo. H., 6711 Wentworth Av.	438
Lees, Wm., 548 Washington Bl.	436
Mehring & Hanson Co., 113 N. Franklin	428
Mellish-Hayward Co., 213 W. Austin Av.	446
Monarch Vent. Co., 1338 Sedgwick St.	446
Nacey, P. Co., 927 S. State St.	436
Narowetz Heat. & Vent. Co., 223 W. Lake	444
Peckham, Harry, Jr., 2345 W. Roosevelt	428
Phillips, Getschow Co., 128 W. Kinzie	430
Pope, Wm. A., 26 N. Jefferson St.	434
Prentice, L. H. Co., 328 Sherman St.	430
Rigby, Ben, 545 W. Lake St.	434
Robinson Furnace Co., 205 W. Lake St.	442
Schampel & Dougherty, 173 W. Wash.	440
Webster, Warren & Co., 53 W. Jackson	442

WAINSCOTING FOR OFFICE AND PUBLIC BUILDINGS.

Craig Co., 30 N. Michigan Av.	396
Vitrolite Co., 133 W. Washington St.	44

WALL BEDS—OSCILLATING AND PORTABLE.

Pick, Albert & Co., 212 Randolph	80-82
----------------------------------	-------

WALL BOARD.

Bird & Son, 1472 W. 76th St.	26
U. S. Gypsum Co., 205 W. Monroe St.	36

WALL COPING.

Dee, Wm. E. Co., 30 N. La Salle St.	394
Garden City Sand Co., 133 W. Wash.	394
Ill. Fire-Proof Constr. Co., 209 S. La Salle St.	400
McCarthy, W. H., 133 W. Washington	394
Nat. Fire Proofing Co., 2610 Shields Av.	400
Northwestern Terra Cotta Co., 2525 Clybourn Av.	10
Rosing, Astrid S., 111 W. Monroe St.	116

WALL PAPER.

Brennan, J. M., & Co., 651 W. 43rd St.	486
Ebert, Theo., Co., 914 Diversey Pkwy.	484
Gleich, T. C. Co., 2850 Broadway	480
Nelson, W. P. Co., 614 S. Michigan Av.	480
Olson, Herman Dec. Co., 911 Chgo. Av., Evanston, Ill.	488
Olson, Hermann & Co., 2568 N. Clark	482
Plamondon & Gabriel Co., 308 N. Mich.	484
Rising Dec. Co., 527 S. Peoria St.	486
Spielring & Linden, 1216 Michigan Av.	488
Sullivan, J. P., 4515 Indiana Av.	482
Warnecke, C. E. Co., 4043 Elston Av.	488

WARDROBES—VENTILATED.

Dodge, H. B. & Co., 332 S. Michigan Av.	262
Durand Steel Locker Co., 76 W. Monroe	18
Federal Steel Fixture Co., 4545 Homer	74
Smith, F. P. W. & I. Wks., 2346 Clybourn	384

WASHING MACHINES.

Am. Ironing Machine Co., 168 N. Mich.	266
Am. Laundry Mch. Co., 208 W. Monroe	344
Commonwealth Edison Co., 72 W. Adams	322
Peoples Gas Light & Coke Co., 122 S. Michigan Av.	338
Pick, Albert & Co., 212 W. Randolph	80-82
Troy Laundry Mch. Co., 23rd & La Salle	344

WATER FILTERS.

Everson, C. G. & Co., 70 W. Lake St.	336
Greer Chemical Co., 20 W. Jackson Bl.	94

WATER HEATERS—AUTOMATIC.

Humphrey Co., Kalamazoo, Mich.	422
Kewanee Boiler Co., 328 W. Washington	406
Webster, Warren & Co., 53 W. Jackson	442

WATERPROOFING.

Advance Waterproof Cement Co., 15 E. Van Buren St.	402
Barrett Co., 10 S. La Salle St.	22
Bird & Son, 1472 W. 76th St.	26
Crescent Sales & Mfg. Co., 110 S. Dear.	24
Fulton Asphalt Co., 53 W. Jackson	88
Garden City Sand Co., 133 W. Wash.	394
Johns-Manville Co., 18th & Michigan	8
Ohmlac Paint & Rfg. Co., 140 S. Dear.	478
Scofield, Evans & Co., 508 S. Dearborn	346
Semet Solvay Co., 332 S. Michigan Av.	490
Smith, F. P. W. & I. Wks., 2346 Clybourn	384
Vitri-fyx Co., 2526 W. Congress St.	350

WEATHER STRIPS—METAL.

Chamberlin Metal Weather Strip Co., 626 S. Dearborn	264
Wolff, Geo. & Co., 190 N. State St.	258

WHITE LEAD MANUFACTURERS.

Eagle Picher Lead Co., 208 S. La Salle	476
--	-----

WINDOW ADJUSTERS.

Babcock Bros. Co., 140 S. Dearborn	96-362
Lupton, David, Sons Co., 28 E. Jackson	50
Metallic Sash Operator Co., St. Louis Mo.	76

WINDOW GUARDS.

Cyclone Fence Co., 39 S. La Salle St.	62
---------------------------------------	----

WINDOW AND DOOR SCREENS.

Chamberlin Metal Weather Strip Co., 626 S. Dearborn	264
Wolff, Geo. & Co., 190 N. State St.	258

WINDOW SHADES FOR INDUSTRIAL BUILDINGS.

Walger Awning Co., 561 W. Monroe St.	4
--------------------------------------	---

WINDOWS—STEEL CASEMENT.

(See Sash Steel)

WIRE FABRIC FOR CONCRETE FIRE-PROOFING.

Am. Steel & Wire Co., 208 S. La Salle	366
---------------------------------------	-----

WIRE GLASS.

Mississippi Wire Glass Co., 7 W. Mad.	494
---------------------------------------	-----

WIRE PARTITIONS.

Cyclone Fence Co., 39 S. La Salle St.	62
---------------------------------------	----

WIRE WORK.

Badger Wire & Iron Co., Mil., Wis.	390
Duffin Iron Co., 4837 S. Kedzie Av.	372
Federal Iron Wks., 30 N. La Salle St.	380
Guaranty Iron & Steel Co., 2847 W. Lake	382
Halsted, Joseph Co., 1233 W. Randolph	380
Hanke Iron & Wire Wks., 840 N. Albany	380
Manton & Smith Co., 1709 W. Austin Av.	382
Reuter Brothers, 5814 Wood St.	384
Smith, F. P. W. & I. Wks., 2346 Clybourn	384
Sullivan-Korber Co., 2437 W. 21st Pl.	382
Union Fdry. Wks., 38 S. Dearborn St.	372
Western Iron Constr. Co., 4906 N. Clark	390
Woodbridge Orntl. Iron Co., 1519 Altgeld	358

WOOD BLOCKS FOR FLOORS.

Indiana Zinc Creosoting Co., 111 W. Washington St.	58
--	----

WOOD CARVING.

Architectural Dec. Co., 1600 S. Jefferson	508
Dux, Joseph, 2112 W. Van Buren St.	508

WOOD COLUMNS.

Hartmann-Sanders Co., 2155 Elston Av.	344
---------------------------------------	-----

WOOD MANTELS AND CONSOLES.

Colonial Fireplace Co., 4626 W. Roosevelt	78
---	----

WOOD PILES.

Lake Superior Piling Co., 961 W. 22nd	302
---------------------------------------	-----

WOOD PRESERVATIVE.

Scofield, Evans & Co., 508 S. Dearborn	346
--	-----

WOOD TANKS.

Ajax Tank & Tower Co., 1407 W. 37th St.	390
---	-----

WOOD TURNING.

Hartmann-Sanders Co., 2155 Elston Av.	344
---------------------------------------	-----

WOODWORKING.

Anderson & Lind Mfg. Co., 2127 Iowa St.	98
Baumann, F. O. Mfg. Co., 1501 Smith	262
Nollau & Wolff Mfg. Co., 1705 Fullerton	344

WRECKING CONTRACTORS.

Newman, W. J. Co., 21 N. Curtis St.	302
-------------------------------------	-----

INDEX TO ADVERTISERS.

A

	PAGE
Advance Waterproof Cement Co.....	402
Ajax Tank & Tower Co.....	390
Alberene Stone Co.....	446
Amalgamated Roofing Co.....	260
American Blower Co.....	420
American Blue Print Paper Co.....	508
American Bridge Co.....	354
American Cement Plaster Co.....	20
American Chimney Construction Co.....	392
American Heating & Plumbing Corp....	428
American Ironing Machine Co.....	266
American Laundry Machinery Co.....	344
American Magnesia Products Co.....	6
American Sand & Gravel Co.....	294
American Steam Pump Co.....	448
American Steel & Wire Co.....	366
American Tar Products Co.....	268
American 3 Way-Luxfer Prism Co.....	500
Anderson, A. & E., Co.....	278
Anderson, Edward A., Co.....	298
Anderson & Lind Mfg. Co.....	98
Appel, Henry L., Co.....	290
Arcade Steam Heating Co.....	90
Archibald, E. L., Co.....	280
Architectural Decorating Co.....	508
Ardmore Construction Co.....	284
Arrow Conductor Co.....	382

B

Babcock Bros. Co.....	96-362
Badger Wire & Iron Co.....	390
Baird & Warner.....	56
Baker & Smith Co.....	436
Balhatcher, William Co.....	504
Barnard, H. B.....	276
Barrett Co., The.....	22
Barrett Construction Co.....	300
Barron Brick Co.....	398
Barton Spider-Web System.....	366
Baumann, F. O., Manufacturing Co.....	262
Beardslee Chandelier Mfg. Co.....	316
Beckman-Dawson Roofing Co.....	340
Benjamin Electric Manufacturing Co.....	308
Bird & Son.....	26
Blome-Sinek Co.....	140
Bolter's A., Sons.....	376
Brasco Manufacturing Co.....	260
Brennan, J. M., & Co.....	486
Brownell Improvement Co.....	394
Brundage, Avery.....	138
Brunswick-Balke-Collender Co., The....	460
Builders' & Manufacturers' Mutual Casualty Co.....	54
Burns, John E., Lumber Co.....	104
Butler St. Foundry & Iron Co.....	384
B-W Construction Co.....	274

C

Cabot, Samuel, Inc.....	340
Cadenhead Co.....	298
Calumet Steel Co.....	378
Carey Brick Co.....	402

PAGE

Castle, A. M., & Co.....	370
Cement Gun Construction Co.....	512
Central Asbestos & Magnesia Co.....	342
Central Electric Co.....	334
Central Oolitic Stone Co.....	72
Chamberlain Metal Weather Strip Co...	264
Chicago Faucet Co.....	462
Chicago Foundation Co.....	302
Chicago Fuse Manufacturing Co.....	312
Chicago Pump Co.....	426
Claffey, E. J., Co.....	432
Clow, James B., & Sons.....	452
Colonial Fireplace Co.....	78
Commonwealth Edison Co.....	322
Comstock, L. K., & Co.....	336
Consolidated Expanded Metal Co.....	368
Consumers Co.....	114
Corboy, M. J., Co.....	468
Corn Exchange National Bank, The....	52
Craig Co., The.....	396
Crescent Sales & Manufacturing Co....	24
Crofoot, Nielsen & Co.....	508
Curtis Door & Sash Co.....	144
Cyclone Fence Co.....	62

D

Dahl-Stedman Co.....	142
Daly, J. J.....	468
Davis, G. M., Regulator Co.....	442
Dean, Olney J., & Co.....	388
Dearborn Electrical Construction Co....	336
Dee, Wm. E., Co.....	394
Detroit Steel Products Co.....	38
Dodge, H. B., & Co.....	262
Dole Valve Co.....	434
Douglass, Thomas J., & Co.....	440
Duffin Iron Co.....	372
Dunham, C. A., Co.....	416
Durand Steel Locker Co.....	18
Dux, Joseph.....	508
Dwyer & Co.....	432

E

Eagle-Picher Lead Co.....	476
Ebert, Theo., Co.....	484
Economy Fuse & Manufacturing Co.....	310
Elevator Company of America.....	30
Ericsson, Henry, Co.....	286
Everson, C. G., & Co.....	336

F

Federal Cement Tile Co.....	16
Federal Iron Works.....	380
Federal Steel Fixture Co.....	74
Friedstedt, L. P., Co.....	294
Fuchs, E. D., Electric Co.....	330
Fulton Asphalt Co.....	88

G

Gallaher & Speck.....	436
Garden City Sand Co.....	394
Gleich, T. C., Co.....	480
Glennon-Bielke Co.....	432
Gordon, Robert, Inc.....	412-428

	PAGE
Goss & Guise.....	506
Graves, W. B., Heating Co.....	434
Greeley-Howard-Norlin Co.....	304
Greenebaum Sons Bank & Trust Co.....	302
Greer Chemical Co., The.....	94
Griffith, William H.....	470
Griffiths, John, & Son Co.....	124
Guaranty Iron & Steel Co.....	382
Gustafson, K. A.....	444

H

Haggarty Fire Protection Co.....	268
Haines Co., The.....	444
Halsted, Joseph, Co.....	380
Hanke Iron & Wire Works.....	380
Hanley & Co.....	440
Hanson Bros. Co.....	282
Hartmann-Sanders Co.....	344
Haywood, R. B., Co.....	444
Heine Chimney Co.....	392
Henrich, George A., Co.....	438
Herlihy, J. J.....	432
Hettler, Herman H., Lumber Co.....	106
Hewitt, J. B., & Co.....	332
Hill, O. H., Co.....	374
Hines, Edward, Lumber Co.....	100
Hockaday Co., The.....	490
Hoffmann & Billings Manufacturing Co.....	464
Hoier, William V., Co.....	440
Holmes, Pyott & Co.....	376
Hooker, H. M., Glass & Paint Co.....	500
Hulbert & Dorsey.....	468
Humphrey Co.....	422
Hunt, Robert W. & Co.....	402

I

Ilg Electric Ventilating Co.....	424
Illinois Bell Telephone Co.....	348
Illinois Brick Co.....	402
Illinois Fire Proof Construction Co.....	400
Illinois Malleable Iron Co.....	426
Imperial Brass Manufacturing Co.....	458
Indiana Quarries Co.....	510
Indiana Zinc Creosoting Co.....	58
Interior Tiling Co.....	396

J

Jenkins Brothers.....	422
Johns-Manville Co.....	8
Johnson, C. W., Inc.....	438
Johnson, E. V., Co.....	288
Johnson-Meier Co.....	360
Johnson Service Co.....	442
Jones Construction Co.....	298
Jones, W. D.....	304

K

Kaestner & Hecht Co.....	Inside Back Cover
Kalman, Paul J., Co.....	356
Kawneer Co., The.....	48
Kehm Bros. Co.....	430
Kellogg-Mackay Co., The.....	404
Kenwood Bridge Co.....	376
Kerner Incinerator Co.....	408
Kewanee Boiler Co.....	406
Kilander, A., & Co.....	438
Kinnear Manufacturing Co.....	388

PAGE

Kirk, George H.....	438
Kramer, William.....	304
Krez, Paul J., & Co.....	342

L

Lake Superior Piling Co.....	302
Lamont, L. H., & Co.....	336
Lanquist & Illsley Co.....	132
Lawson Manufacturing Co.....	64
Lees, William.....	436
Lehon Co., The.....	66
Lennox-Haldeman Co.....	504
Lucas, John, & Co.....	478
Ludowici-Celadon Co.....	70
Luminous Unit Co.....	318
Lund, A., Co.....	136
Lupton's David, Sons Co.....	50
Lynch, Austin J., Co.....	296

M

MacAdams & Call.....	350
Manhattan Electrical Supply Co.....	334
Manton & Smith Co.....	382
Marthens, Chester N., Marble Co.....	392
Matot, D. A.....	266
Mavor, William, Co.....	296
McCarthy, W. H.....	394
McCray Refrigerator Co.....	2
McKeown Brothers Co.....	280
McLennan Construction Co.....	272
McNulty Brothers Co.....	504
Mears-Slayton Building Material Co.....	112
Mechanical Manufacturing Co.....	60
Mehring & Hanson Co.....	428
Mellish-Hayward Co.....	446
Menke, Henry, Co.....	284
Metallic Sash Operator Co.....	76
Meyne, Gerhardt F.....	300
Midland Terra Cotta Co.....	42
Midwest Hardware Co.....	84
Mississippi Wire Glass Co.....	494
Monarch Ventilating Co.....	446
Montgomery Elevator Co.....	314
Moore, Benjamin & Co.....	490
Moore, Edward Roofing Co.....	92
Morava Construction Co.....	376
Morgan Sash & Door Co..	Inside Front Cover
Morlite Co., The.....	498
Morrice, William, Co.....	300
Moses, C. A., Construction Co.....	278
Mott, J. L., Iron Works.....	456
Mueller Construction Co.....	134
Mueller, L. J., Furnace Co.....	424
Muller, Franklyn R., & Co.....	1
Murphy Plumbing Co.....	468
Mutual Construction Co.....	300

N

Nacey, P., Co.....	436
Narowetz Heating & Ventilating Co.....	444
Nash Engineering Co.....	448
National Fire Proofing Co.....	400
National Pressed Steel Co.....	364
Nelson, P. W., Inc.....	490
Nelson, W. P., Co.....	480
New Era Fire Protection Engineers.....	446
Newgard, Henry, & Co.....	324
Newman Manufacturing Co.....	390
Newman, W. J., Co.....	302

	PAGE		PAGE
New York Blower Co.....	418	Sollitt, Sumner Co.....	298
Nielsen, S. N. & Co.....	282	Spierling & Linden.....	488
Nilson Brothers	430	Standard Asbestos Manufacturing Co... 342	
Nilson, G. Albin, Co.....	470	Standard Cooper Bell Co.....	472
Noble & Thumm.....	470	Standard Fire Escape Co.....	374
Noelle, J. B., Co.....	488	Standard Sanitary Manufacturing Co... 454	
Nollau & Wolff Manufacturing Co..... 344		Stannard Power Equipment Co.....	448
North Western Expanded Metal Co..... 352		Steam Corporation, The.....	414
Northwestern Terra Cotta Co., The..... 10		Stevens Partition & Floor Deadener Co.. 346	
O		Strandberg, E. P., Co.....	288
Ohmlac Paint & Refining Co.....	478	Sullivan, J. P.....	482
Olson, Herman, Decorating Co.....	488	Sullivan-Korber Co.	382
Olson, Hermann, & Co.....	482	Sutton Plastering Co.....	506
Olson, Peter, Co.....	276	T	
Olson, Samuel, & Co.....	14	Thielberg, A. C.....	296
Otis Elevator Co.....	28	Thompson-Starrett Co.	130
P		Thomson, George, & Son Co.....	290
Parent, N. J., Co.....	506	Thornton Clancy Lumber Co.....	102
Pearlman, Victor A., & Co.....	306	Troy Laundry Machinery Co.....	344
Peckham, Harry, Jr.....	428	Tyler & Hippach	498
Peoples Gas Light & Coke Co.....	338	U	
Peterson Nursery	340	Union Foundry Works	372
Phillips, Getschow Co.....	430	Union Insulating & Construction Co.... 40	
Pick, Albert, & Co.....	80-82	United Cork Companies	68
Pierce Electric Co.....	328	United States Gypsum Co.....	36
Pilsen Lumber Co.....	110	Universal Form Clamp Co.....	368
Pitt Engineering Co.....	34	Universal Portland Cement Co.....	386
Plamondon & Gabriel Co.....	484	Utica Heater Co.....	410
Pope, William A.....	434	Utility Service Assn.....	466
Powell, M. W., Co.....	340	V	
Pratt & Lambert, Inc.....	474	Variety Fire Door Co.....	388
Prentice, L. H., Co.....	430	Vierling Steel Works.....	384
R		Vitriflyx Co.	350
Rasmussen, C.	292	Vitrolite Co., The.....	44
Raymond Concrete Pile Co.....	12	Voss, Frederick	388
Reder Foundry Works.....	380	W	
Reflectolyte Co.	320	Walger Awning Co.....	4
Regnell, B. J., Co.....	296	Warnecke, C. E., Co.....	488
Reuter Brothers	384	Watson, H. F. Co.....	342
Rigby, Ben, Inc.....	434	Watson, W. W.....	470
Rising Decorating Co.....	486	Weary & Beck.....	396
Rittenhouse & Embree Co.....	108	Webster, Warren & Co.....	442
Robinson Furnace Co.....	442	Weir & Craig Co.....	420
Rosenthal-Cornell, O. W., Co.....	274	Weller Manufacturing Co.....	86
Rosing, Astrid S., Inc.....	116	Wells Brothers Construction Co..... 128	
Rowles, E. W. A., Co.....	576	Western Brick Co.....	392
S		Western Iron Construction Co.....	390
Salomon-Waterton Co.	292	Wheeler Elevator Co.....	32
Samuelson, A. J.....	286	White City Electric Co.....	326
Sandusky Cement Co.....	46	Williams-Wendt Co.....	396
Sasgen Derrick Co.....	118	Williams, William	506
Schampel & Dougherty.....	440	Wilson, R. F., & Co.....	122
Scharmer Construction Co.....	270	Wittenmeier Machinery Co.....	120
Scofield, Evans & Co.....	346	Wolff, George F., & Co.....	258
Scully Steel & Iron Co.....	370	Wolff Manufacturing Co.....	450
Semet-Solvay Co.	490	Woodbridge Ornamental Iron Co..... 358	
Shedden, James & Co.....	272	Y	
Sherman & Ellis, Inc.....	264	Yeomans Brothers Co.....	448
Shur-Loc Company of Illinois.....	258	Z	
Silander, A. I.....	304	Zander-Reum Co.	504
Simplex Steel Products Co., The..... 502		Zouri Drawn Metals Co.....	496
Smith, F. P., Wire & Iron Works..... 384			
Snyder, J. W., Co.....	126		
Sollitt, Ralph, & Sons Construction Co.. 270			

TABLE OF CONTENTS.


	Page
Advertisers, Alphabetical List of.....	572
Advertisers, Classified List of	558
American Institute of Architects, Chapter Presidents and Secretaries.....	75
Announcement	9
Architects, Alphabetical List of Registered.....	37
Architects, License Law	91
Architects, Registration of, in the State of Illinois.....	111
Architects, Registration, States Requiring	75
Associated Builders of Chicago, Officers and Committees.....	89
Building Construction Employers Assn., Executive Board and Committee.....	87
Building Ordinance, City of Chicago (See Index, 145), (Special Ruling 291).....	161
Catalogues and Printed Matter, Suggestions for Firms Issuing Same.....	105
Charges, Proper Minimum, Schedule of and Professional Practice of Architects....	33
Chicago Architectural Club Officers and Members, List of.....	81
Chicago Master Steam Fitters Assn., Standards.....	423
City Council—Members and Committees.....	127
City Hall and County Building Directory.....	119
City Officials of Chicago.....	125
Civil Administrative Code of the State of Illinois, Extracts from.....	95
Commonwealth Edison Co.'s System, Rules and Information Pertaining to Electric Service Meters and Wiring.....	323
Concrete Floors, Plain, Revised Specifications for.....	387
Concrete and Excavation Work, Rules of Measurement for.....	381
Contract Forms, List and Price of, Issued by the Illinois Society of Architects....	103
Editorial, Illinois Society of Architects.....	21
Electricity, Department of, City of Chicago.....	307
Electrical Inspection, Sections of the City Code Governing Same.....	309
Engravings—	
Board of Arbitration of the Illinois Society of Architects.....	15
Committee on Public Action of the Illinois Society of Architects.....	17
Directors of the Illinois Society of Architects.....	13
Examining Committee of Architects, State of Illinois.....	19
Officers of the Illinois Society of Architects.....	11
Excavation and Concrete Work, Rules of Measurement for.....	381
Floors, Plain Concrete, Revised Specifications for.....	387
Furnace Design, with Special Reference to Hand Fired Boilers and Limitations of Each Design	445
Gas Fitters' Rules for Piping Buildings, Peoples Gas, Light & Coke Co.'s System.	339
Glass and Glazing.....	495
Heating and Ventilating.....	405
Hollow Tile Fireproofing, Standard Specifications for.....	399
Hot Water Heating, Two-Pipe Non-Short Circuit System.....	421
Illinois Chapter, American Institute of Architects, Officers and Members, List of...	77
Illinois Society of Architects, Officers and Committees	5
Illinois Society of Architects, Officers and Members, List of.....	59
Labor Prices Per Hour of Building Trades.....	117
License Law, Architects.....	91
Lighting Fixtures and Their Relation to the Home Beautiful.....	335
Mechanics Lien Law, State of Illinois.....	131
Metal Lath, Specifications for Erecting.....	353
Miscellaneous and Useful Information Concerning Building, Engineering Trades and Materials	513
National Council of Architectural Boards.....	107
Office Practice	101
Plastering, Standard Rules of Measurement of.....	503
Plumbing Design in Tall Buildings.....	469
Preface	7
Professional Ethics, Canons of, Illinois Society of Architects.....	27
Protective, Preservative and Decorative Coverings.....	485
Reinforcement Bars, Concrete, Billet and Rail Steel, Standard Specifications for..	377-379
Sanitary Code, Sections of Interest to Architects, with Index.....	427
Sanitation, Modern, of Buildings.....	451
Steel Lumber Construction.....	367
Stone, Cut, Standard Specifications for.....	509
Structural Building Steel.....	335
Title Page	3
Varnishes, Stains and Fillers.....	473
Ventilation, Measuring	443
Yellow Pine, Southern, Timbers, Standard Specifications for.....	393
Zoning Bill, State of Illinois.....	303

Include These in the Specifications




Wood pulp composition blackboards are a proved success. Among the many on the market DUROPLATE is one of the leading brands. It is used successfully by leading educational institutions and is admirably adapted for the varying requirements of a wood pulp composition blackboard. Each year thousands of square feet are placed in new buildings for permanent use as well as in portable buildings, temporary teaching quarters, Sunday Schools, Nursery Rooms and Kindergartens. It is also used for special framed blackboards in conference rooms, lecture halls, bulletin boards, and has many other uses too numerous to mention.

SEND FOR SAMPLES AND FURTHER INFORMATION




Our complete furniture catalog illustrating all kinds of school equipment should be in your files for instant reference. It will be of assistance in drawing up specifications.



Write for Catalog 121 Today

E.W.A. ROWLES CO.
M'F'RS. SCHOOL FURNITURE & SUPPLIES
2345-51 SO. LA SALLE ST. . . CHICAGO, ILL.



*The Wrigley Building, Chicago
Graham, Anderson,
Probst & White,
Architects*

Kaestner & Hecht Elevators

WILLIAM WRIGLEY, Jr., has used K & H elevators, as well as other makes, in his factory for eight years. He had ample opportunity to make comparisons. When he selected the elevators for his new office building, a monument to his business achievement, he chose K & H. **Q** Mr. Wrigley realizes that good elevator service attracts both tenants and visitors.

Kaestner & Hecht Co.
Founded 1863 • Chicago

DETROIT • BIRMINGHAM • MINNEAPOLIS • MILWAUKEE • INDIANAPOLIS • OMAHA

UNIVERSITY OF ILLINOIS-URBANA



3 0112 055054669